



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL ENGINEERING DEPARTMENT

SCHEDULE- A

Tender Notice No:

HY/FCD/OT-02/2012-13, Dt: 18.05.2012

PRICE BID

Item no.: 4

Name of work: Maintenance of External sewage system / Open drains clearing of sewage lines and sanitation of roads in factory area & Admn. Building area.

S. No.	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
1	Earth work in excavation by mechanical means (Hydraulic Excavators) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m etc. complete all as directed by engineer-in-charge.	100.00	Cu.M	103.40	10,340.00
2	Cleaning the open drains by removing mud, leaves and stones and conveying the same within a lead of 2 Kms., etc., complete as directed by Engineer-in-charge.	10,000.00	R.M	5.32	53,200.00
3	Laying and jointing of RCC hume pipes of 150 and 225 mm (6" and 9") dia, in CM 1:1 including excavation, testing and refilling etc., complete. RCC hume pipes will be supplied free of cost by BHEL at their stores etc. complete all as directed by engineer-in-charge.	10.00	R.M	54.25	542.50
4	Roding of under ground sewer lines such as S.W.G pipes / R.C.C. pipes, / G.I. pipes and clearing and removing the deposits from the manholes, / chambers upto depth of 10.00 M and disposing the same to a lead of 2.00 KMS., for the following dia. Of pipes at all depths. The rate quoted shall include cost of labour and tools required for cleaning the sewer lines, cleaning rods and safety equipment etc. complete all as directed by engineer-in-charge.				
a	100 mm dia..	1,100.00	R.M	7.00	7,700.00
b	150 mm dia.	2,500.00	R.M	9.00	22,500.00
c	225 mm dia.	6,000.00	R.M	10.75	64,500.00
d	300 mm dia.	6,000.00	R.M	13.42	80,520.00
e	375 mm dia.	2,500.00	R.M	13.20	33,000.00
f	for inspection chambers	25.00	Each	87.05	2,176.25
g	for man holes	25.00	Each	87.05	2,176.25
5	Cleaning of canteen waste collection tanks and waste collection chambers located at 02, 03, 04 and 51 staff and works canteens including removal of waste from the chambers and septic tanks, loading into vehicle, conveying and unloading the same at outside the factory area etc., complete as directed by the Engineer-in-charge. The vehicle shall be weighed before and after lading the waste materials, at BHEL weigh bridge for each trip. The rate quoted shall include cost or labour, hire charges of vehicle, cost or tools required for cleaning. The payment will be made against the weight for the waste materials disposed etc. complete all as directed by engineer-in-charge.	40.00	M.T	409.00	16,360.00

S. No.	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
6	Cleaning and Clearing the choke ages of nahany traps 'P' or 'S' traps and gully traps in the toilets at factory and Administrative building areas including removal and disposal of waste materials etc., complete as directed by the Engineer-in-charge. The rate quoted shall include cost of labour and tools.	250.00	Each	42.62	10,655.00
7	Sweeping of the roads, open yards, road side berms etc. including entrances of blocks, Annexes etc. including making heaps of collected garbage, dry leaves, waster etc. and loading into tractor on daily basis. The rate quoted shall include cost of tools, tackles and safety equipment. (It is assessed that one semiskilled and nine unskilled services per day are required for carrying out the above job of one operation). (1SSW & 9 USW) etc. complete all as directed by engineer-in-charge.	287.00	One Oper	5,471.26	15,70,251.62
8	Engaging tractor trailer with six unskilled services per day , for removal of waste, materials from out side the blocks, storage yards etc. like surplus earth, canteen waste, papers, wood, steel, plastic, drainage silt, any other waste materials are to be conveyed to garbage yard or scrap yard without weighment. The rate quoted shall include cost of labour and hire charges of tractor trailer with driver per day etc. complete all as directed by engineer-in-charge.	150.00	Tractor Day	4,454.64	6,68,196.00
9	Cleaning of road gully chambers by removing leaves, mud, stones etc., and disposing the garbage to places as directed upto a lead of 2 KMs etc. complete all as directed by engineer-in-charge.	1,000.00	Each	9.15	9,150.00
Total				₹	25,51,267.62
Total : ₹ Twenty five lakhs fifty one thousand two hundred sixty seven and sixty two paise only					

Note:

1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.
2	Service tax is extra as applicable, which will be reimbursable to the agency on production of paid proof documents and VAT not applicable.
3	The rates are inclusive of all taxes and duties.

Note : The bidders are required to quote the tender value on percentage (%) basis at excess or less or on par with estimate value in figures and words.

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor