



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL ENGINEERING DEPARTMENT

SCHEDULE- A

Tender Notice No:

PRICE BID

HY/FCD/OT-04/2012-13, Dt: 31.05.2012

Item no.: 3

Name of work: Providing new wooden flooring (job tilting floor) in 01 & 06 blocks.

S. No.	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
1	Dismantling the existing reinforced cement concrete / plain cement concrete and disposing of debris upto a lead of 2 KM including loading, unloading and spreading as directed by Engineer-in-charge etc., complete.	90.00	Cu.m	582.68	52,441.20
2	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement, including consolidation by vibrations for all works up to plinth level with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) etc. complete as directed by Engineer-in-charge.	67.00	Cu.M	1,687.00	1,13,029.00
3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding grills with binding wire all complete by cold twisted bars etc. complete as directed by Engineer-in-charge.	5.00	M.T	4,003.00	20,015.00
4	Centering and shuttering including strutting, propping etc.; and removal of form work, for columns, pillars, piers, abutments, machine foundations, posts and struts etc. complete as directed by Engineer-in-charge.	47.00	Sq.m	180.40	8,478.80
5	Conveyance of excavated spoil upto a lead of 2 Kms, including loading, unloading and spreading etc. complete as directed by Engineer- in- charge.	197.00	Cu.M	56.41	11,112.77
6	Fabrication and fixing MS angles/Channels in concrete wall with lugs of required dia welded to the MS angles/channels. (Structural Steel, electrodes and gas required for work will be issued on free of cost by BHEL at their stores) etc. complete as directed by Engineer-in-charge.	2.10	MT	3,500.00	7,350.00
7	Supply of Hard Wood Blocks of size 300X300X230mm for tilting floor including cutting to required size conveying to site, loading, unloading and stacking in stores, cost of wood etc.; complete as directed. (The hard wood blocks of above size shall conform to the standard specification - hard to very hard - not indented by finger nail and cut with considerable difficulty with knife. it shall have the weight of more than 750Kg/Cu.m. The moisture content should not be more than 12%. The wood pieces shall have uniform colour and shall be free from knots and cracks) etc. complete as directed by Engineer-in-charge.	2,287.00	Each	1,272.00	29,09,064.00

S. No.	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
8	Fixing of hard wood logs of size 300X300X230mm including making grooves, tightening every fourth line by a 20mm dia MS tie rod with threaded bolts,nuts washers etc. at ends, including the cost of saw dust for leveling the blocks etc. complete. (MS rounds, MS strips, only will be issued on free of cost at BHEL stores). The rate quoted shall include cost of all labours etc. complete as directed by Engineer-in-charge.	196.00	Sq.m	1,993.00	3,90,628.00
	Total			₹	35,12,118.77
	Add 1% on 70% cost of the work for VAT			₹	24,584.83
	Total value of work			₹	35,36,703.60
Total : ₹ Thirty five lakhs thirty six thousand seven hundred three and sixty paise only					

Note:- For Cement consuming items other than RMC, BHEL will issue cement and steel on free of cost at their stores.

1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.
2	Service tax is extra as applicable, which will be reimbursable to the agency on production of paid proof documents.
3	The rates are inclusive of all taxes and duties.

Note : The bidders are required to quote the tender value on percentage (%) basis at excess or less or on par with estimate value in figures and words.

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor