~~	FRICE DID- FAIX	•				
SL. NO	ITEM DESCRIPTION	UNIT	QTY.	RATE IN FIG (INR)	RATE IN WORDS	AMOUNT (INR)
	SECTION A - TOPOGRAPHICAL SURVEY					
1	Carrying out bench mark from the nearest GTS bench mark or any other available source as approved by the engineer-in-charge to different locations in the project area including clearing of jungles and/or cutting trees and any other works required for completion of the said item etc all complete as per specification and instructions of the engineer-in-charge. (Construction of bench mark pillar to be paid separately)	km	3			
2	Carrying out topographical survey of plant and allied areas showing all permanent & general features and detailed contour survey by taking spot levels at 25m interval, carrying out cross section of canal/nallah by taking spot levels at 5m interval or less including clearance of jungles and cutting of trees etc which are interfering with the survey works and any other field works necessary for the completion of the said item, preparation and submission of all plans (maps), reports, floppy and originals etc all complete as per specification and instructions of the engineer-in- charge.		9			
3	Construction of bench mark pillar/reference pillar/grid pillar at different locations including clearing of jungles, excavation, supply of materials, pillar marking, backfilling, white washing, painting on MS plate etc all complete as per specification, drawings and instructions of the engineer-in- charge.					
	a) Bench mark pillar	Each	2			
	b) Grid/reference pillar	Each	20			
	TOTAL OF SECTION-A					
	SECTION B - SOIL INVESTIGATION					

	TRISE BIB-TART-II (VOE-III)							
SL.	ITEM DESCRIPTION	UNIT	QTY.	RATE	RATE	AMOUNT		
NO				IN FIG (IN WORDS	(INR)		
				INR)				
1	Mobilisation of necessary equipments, men and materials to the project site for carrying out the geotechnical investigation and demobilisation of the same after completion of all the field works etc all complete as per specification, drawings and as directed by the engineer-in-charge. 1 (One Set) comprising of minimum indicative list of equipment to be deployed as per Appendix - I of Tender Specification. Any additional equipments if required shall be mobilized as per the directions of the BHEL Engineer to match the work schedule without extra cost	LS	1					
2(a)	Making 150mm nominal diameter bore hole at various locations upto a maximum depth of 10m below ground level in all types of soil including laterite using suitable approved method of boring including chiselling, cleaning, providing casing pipes as required or as directed; performing standard penetration test at every 2m interval down to 10m depth below ground level and at every 3m interval beyond 10m depth, at change of strata and at depths wherever undisturbed soil samples could not be collected; collection of undisturbed soil samples at every 2m interval down to 10m depth below ground level and at every 3m interval beyond 10m depth and at change of strata; collection of disturbed soil samples and water samples, sealing and packing of samples, observation such as ground water table etc; transportation of all the collected samples to the laboratory and back filling of boreholes with sand on completion of the same etc all complete as per specification and as directed by the engineer-in-charge.	RM	300					

CT	THEM DESCRIPTION	TINITE	OTN	DATE	DATE	AMOUNT
SL.	ITEM DESCRIPTION	UNIT	QTY.	RATE	RATE	AMOUNT
NO				IN FIG (IN WORDS	(INR)
- 4 >				INR)		
2(b)	Core drilling (Nx size) in rock up to a maximum of 25m depth below ground					
	level using hydraulic feed rotary drill and double tube core barrel with diamond					
	bit including collection of core samples, performing SPT at locations where core					
	recovery is less than 20%, maintaining continuous record of core recovery and	RM	450			
	RQD, keeping the cores in wooden core boxes, transporting the cores to		730			
	laboratory, back filling the holes with 1 part of cement: 3 part of sand grout on					
	completion of the same etc all complete as per specification, drawings and as					
	directed by the engineer-in-charge.					
3	Excavating trial pit (TP)of size 3m x 3m at various locations upto 4m depth					
	below ground level in all types of soil and weathered rock which can be excavated					
	with pick axe/crow bar etc including sheeting or shoring the sides for the purpose					
	of stability, dewatering and maintaining the pit dry at all times, collecting	α_{M}	1 4 4			
	disturbed/undisturbed samples at 1m interval and at final depth and transporting	CuM	144			
	all the collected samples to the laboratory; backfilling of the pit with excavated					
	material etc all complete as per specification and as directed by the engineer-in-					
	charge.					
4	Conducting plate load test (PLT) in various locations at specified depth					
	complete as per specification, drawings and as directed by the engineer-in-charge.	- 1				
	Payment for making the pit of suitable size, maintaining it dry and backfilling etc	Each	3			
	shall be paid separately as per item no.3					
5	Conducting cyclic plate load test (CPLT) in various locations at specified depth					
	complete as per specification, drawings and as directed by the engineer-in-charge.					
	Payment for making the pit of suitable size, maintaining it dry and backfilling etc	Each	4			
	shall be paid separately as per item no.3					
	sharr be para separately as per item no.s					

SL.	ITEM DESCRIPTION	UNIT	QTY.	RATE	RATE	AMOUNT
NO			(IN FIG (IN WORDS	(INR)
				INR)		
6	Conducting cross hole shear wave test (CHSWT) in bore hole in all types of					
	strata at all depths such as 2m, 4m, 6m, 8m, 10m, 13m, 16m, 19m, 22m, 25m,					
	28m, 31m, 34m, 37m & 40m below ground level including preparation of					
	borehole, providing PVC liner, grouting and backfilling with sand after	Each	6			
	completion of the test etc all complete as per specification, drawings and as					
	directed by the engineer-in-charge. Cost of the borehole and backfilling etc					
	shall be paid separately as per item no.2a & 2b above.					
7	Performing dynamic cone penetration test (DCPT) at various locations using					
	65mm cone with circulation of bentonite slurry etc all complete as per	Each	10			
	specification, drawings and as directed by the engineer-in-charge.					
8	Performing static cone penetration test (SPT) at various locations complete as	Each	10			
	per specification, drawings and as directed by the engineer-in-charge.	Lacii	10			
9	Conducting field vane shear test (FVST) in various locations at specified depth					
	including collection of disturbed soil sample etc all complete as per specification,	Each	5			
	drawings and as directed by the engineer-in-charge.					
10	Conducting electrical resistivity test (ERT) at various locations complete as per	Each	35			
	specification, drawings and as directed by the engineer-in-charge.	Lacii	33			
11(a)	Conducting pump in type field permeability test (FPT) by constant head or					
	falling head method (suitability of type of test shall be as per site conditions) in					
	various boreholes at specified depth including providing packers as required etc	Each	2			
	all complete as per specification, drawings and as directed by the engineer-in-	Lacii	2			
	charge. Cost of the borehole and backfilling etc shall be paid separately as per					
	item no.2a & 2b above.					
11(b)	Conducting field permeability test in boreholes for rocky stratum at specified					
	depth by double packer method complete as per specification, drawings and as					
	directed by the engineer-in-charge. Cost of the borehole and backfilling etc shall					
	be paid separately as per item no.2a & 2b above.					
	a)Double packer method	Each	2			

SL.	ITEM DESCRIPTION	UNIT	QTY.	RATE	RATE	AMOUNT
NO				IN FIG (IN WORDS	(INR)
				INR)		, ,
12	Conducting pressuremeter test (PMT) in various bore holes in all types of strata			Í		
	at all depths such as 2m, 5m, 8m, 11m, 14m, 17m, 20m, 23m, 26m, 29m, 32m,	Fach				
	35m, 38m & 40m below ground level including preparation of bore hole of		5			
	required size etc all complete as per specification, drawings and as directed by the		3			
	engineer-in-charge. Cost of the borehole and backfilling etc shall be paid					
	separately as per item no.2a & 2b above.					
13	Conducting seismic refraction test (SRT) at various locations complete as per	RM	1000			
	pecification, drawings and as directed by the engineer-in-charge.	1000				
14(a)	Conducting Laboratory Test on soil samples at an approved laboratory					
	including preparation of soil samples to determine the following properties etc all					
	complete as per specification.					
	a)Bulk density and moisture content	Each				
	1) 0:		50			
	b)Sieve analysis	Each	100			
	c)Hydrometer analysis	Each				
		<u> </u>	30			
	d)Liquid limit and plastic limit	Each	100			
	e)Shrinkage limit	Each	100			
	c)Sirinkage mint	Lacii	30			
	f)Specific gravity	Each				
	<i>,</i> 1		30			
	g) Swell pressure	Each	30			
	h) Free swell index	Each				
			30			
	i) Relative density	Each	30			
	j) Unconfined compressive strength	Each	30			
	J) Oncommed compressive suchgui	Eacii	50			

SL.	ITEM DESCRIPTION	UNIT	QTY.	RATE	RATE	AMOUNT
NO				IN FIG (INR)	IN WORDS	(INR)
	k) Direct shear test	Each	100			
	I) Box shear test	Each	50			
	m) Triaxial shear test					
	i)unconsolidated undrained test	Each	50			
	(ii) Consolidated undrained test with the measurement of pore water pressure	Each	50			
	(iii) Consolidated drained	Each	50			
	n) One dimensional consolidation test	Each	50			
	o) Standard Proctor compaction test	Each	10			
	p) CBR test at					
	(i) soaked condition	Each	10			
	(ii) un-soaked conditions	Each	10			
	q) Chemical analysis	Each	10			
14(b)	Conducting Laboratory Test on rock samples including preparation of the samples to determine the following properties etc all complete as per specification.					

SL.	ITEM DESCRIPTION	UNIT	QTY.	RATE	RATE	AMOUNT
NO	TEM BESCRIPTION	CIVII	Q11.	IN FIG (INR)	IN WORDS	(INR)
	a)Moisture content, porosity & density	Each	50			
	b)Specific gravity, Hardness	Each	30			
	c)Slake durability index	Each	30			
	d)Unconfined compressive strength (both at saturated and in–situ water content)	Each	75			
	e)Point load strength	Each	30			
	f) Deformability test (Saturated & Dry sample)	Each	30			
15	Conducting chemical test on water samples to determine the carbonate, sulphate, chloride and nitrate contents, pH value, turbidity, organic matter and any other chemicals harmful to foundation material etc all complete as per specification.	Each	10			
16	Conducting chemical test on 2:1 water: soil extract to determine the carbonate, sulphate, chloride and nitrate contents, pH value, turbidity, organic matter and any other chemicals harmful to foundation material etc all complete as per specification.	Each	10			
17	Preparation and submission of draft report in 3 copies and final report in 5 hard copies and 2 soft copies on 3½" floppies after the approval of draft report including all field records, laboratory test results, graphs, analysis of test results and recommendation etc all complete as per specification.		1			
	TOTAL OF SECTION-B					
	TOTAL OF SECTION A & SECTION-B IN RS					
	TOTAL OF SECTION-A & SECTION-B IN WORDS (RS		•	<u>'</u>		•