

BHEL, PSWR: NAGPUR
TS :BHE/PW/PUR/BORLI-SSH/569
PART-II: PRICE BID

RATE SCHEDULE

| | SUB : CONSTRUCTION OF STORAGE SHED AT BINA | | | | |
|-----------------|---|------------|------------|----------------------------|---------------|
| Item No. | Description | UOM | Qty | Unit Rate In Rs | Amount |
| 1 | Earth work in excavation from 0 to 2 m depth in all kind of soil for foundation column saptic tank ,ramps etc | Cum | 175 | | |
| 2 | Back filling in foundation and plinth with excavated soil in layers not exceeding 15 cm thick including watering and consolidating. | Cum | 12 | | |
| 3 | Back filling in foundation and plinth with murrum in layers not exceeding 15 cm thick including watering and consolidating etc complete. | Cum | 210 | | |
| 4 | Providing the laying of plain cement concrete of mix 1:4:8 using 40mm and down size hard broken granote stone jelly for foundation flooring etc | Cum | 105 | | |
| 5 | Providing and laying concrete mix 1:2:4 using 20mm hard stone aggregates including centring etc | Cum | 20 | | |
| 6 | Providing DPC with CC 1:2:4-50 mm thick including coating as per standard practice and specification | Sqm | 55 | | |
| 7 | Providing fixing Reinforcement | MT | 3 | | |
| 8 | Providing random rubble masonry with hard stone in foundation and up to plinth with hard cement mortor 1:6 including cost of material cement and pointing works | Cum | 80 | | |

BHEL, PSWR: NAGPUR
TS :BHE/PW/PUR/BORLI-SSH/569
PART-II: PRICE BID

RATE SCHEDULE

| SUB : CONSTRUCTION OF STORAGE SHED AT BINA | | | | | |
|--|--|-----|------|--------------------|--------|
| Item No. | Description | UOM | Qty | Unit Rate In Rs | Amount |
| 9 | Providing brick work in cement mortar 1:6 using best quality bricks as per IS standard and drawing for foundation wall etc. | Cum | 180 | | |
| 10 | Providing and laying soling 230mm thick with 150-200mm thick bolder size and filling the voids | Cum | 135 | | |
| 11 | Design manufacture supply and erection of tubular truss purlins spaced generally @ 1.4m centre to centre to support roofing with AC sheet and wind ties to be provided and fixing base plate with splices etc. | MT | 18 | | |
| 12 | Providing and fixing 6 mm thick AC corrugated sheets with ridge caps | Sqm | 1025 | | |
| 13 | Providing and fixing translucent RMP/FRP sheets 1.5 mm thick of approved make | Sqm | 60 | | |
| 14 | Providing steel window, Ventilator | | | | |
| | i) Steel Windows | Sqm | 2 | | |
| | ii) Ventilators | Sqm | 10 | | |
| 15 | Manufacturing supply and fixing of best quality country wooden doors comprising of frame 95X70mm and 38/40mm thick flush shutter door including painting with Handle hinges etc | Sqm | 2 | | |

BHEL, PSWR: NAGPUR
TS :BHE/PW/PUR/BORLI-SSH/569
PART-II: PRICE BID

RATE SCHEDULE

| | SUB : CONSTRUCTION OF STORAGE SHED AT BINA | | | | |
|-----------------|---|------------|------------|-----------------------|------------------------|
| Item No. | Description | UOM | Qty | Unit In Rs | Rate Amount |
| 16 | i) External plaster 18mm thick | Sqm | 960 | | |

BHEL, PSWR: NAGPUR
TS :BHE/PW/PUR/BORLI-SSH/569
PART-II: PRICE BID

RATE SCHEDULE

| SUB : CONSTRUCTION OF STORAGE SHED AT BINA | | | | | |
|--|--|-------|------|--------------------|--------|
| Item No. | Description | UOM | Qty | Unit Rate In Rs | Amount |
| 17 | ii)Internal 12mm thick | Sqm | 600 | | |
| 18 | Providing and fixing IPS flooring 40mm/25mm thick with cement concrete 1:2:4 as per standard practice | | | | |
| | B)IPS Flooring 40mm thick | Sqm | 900 | | |
| 19 | Providing white or colour wash 3 coats on newly plastered surface using best lime including cleaning brushing of wall etc. | Sqm | 1600 | | |
| 20 | Manufacture ,supply and fixing of MS rolling shutter as per IS Specification | Sqm | 40 | | |
| 21 | Providing MCB 63 amps | No | 1 | | |
| 22 | Single pole MCB 6 amps | No | 10 | | |
| 23 | Providing and installing wiring for lighting and fans with junction box using 2.5 sqmm copper conductor | point | 50 | | |
| 24 | Supplying and installing tube lights Standard Make | No | 250 | | |
| | TOTAL OF ALL ITEMS IN RS | | | | |

BHEL, PSWR: NAGPUR
TS :BHE/PW/PUR/BORLI-SSH/569
PART-II: PRICE BID

RATE SCHEDULE

| | | | | | |
|-----------------|---|------------|------------|-----------------------|------------------------|
| | SUB : CONSTRUCTION OF STORAGE SHED AT BINA | | | | |
| Item No. | Description | UOM | Qty | Unit In Rs | Rate Amount |
| | TOTAL OF ALL ITEMS IN WORDS (RS | | | | |