

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	1(A)	EARTH WORK <b>EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH</b> IN ALL KINDS OF SOIL ( <b>EXCEPT SOFT ROCK AND HARD ROCK</b> ) FOR <b>FOUNDATIONS, SEPTIC TANK, SOAK PIT, RAMPS</b> ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	<b>350.00</b>			
Sec. A	1(B)	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH FOR SOFT ROCK AND HARD ROCK (BY MANUAL CHISELING OR BY MECHANICAL MEANS BUT WITHOUT BLASTING) FOR FOUNDATIONS, SEPTIC TANK, SOAK PIT, RAMP ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	<b>110.00</b>			
Sec. A	1(C)	EARTH WORK <b>EXCAVATION FROM 2.0M TO 4.0 M DEPTH</b> IN ALL KINDS OF SOIL ( <b>EXCEPT HARD ROCK AND SOFT ROCK</b> ) FOR <b>FOUNDATIONS, SEPTIC TANK, SOAK PIT, RAMPS</b> ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	<b>20.00</b>			
Sec. A	1(D)	EXCAVATION IN ALL KINDS OF SOIL <b>INCLUDING SOFT &amp; HARD ROCK</b> ((BY MANUAL CHISELING OR BY MECHANICAL MEANS BUT WITHOUT BLASTING) <b>FROM 2 TO 4M DEPTH</b> FOR <b>SEPTIC TANK AND SOAK PIT</b> , WHEREVER REQUIRED INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	<b>45.00</b>			
Sec. A	1(E)	SUB GRADE PREPARATION: CUTTING LEVELLING, FILLING WITH EXCAVATED EARTH, WATERING AND CONSOLIDATION FOR <b>PLINTH PROTECTION AREA</b> BEFORE LAYING THE PCC WITH ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.	M2	<b>123.00</b>			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	2	DISPOSAL OF EXCAVATED EARTH/ROCK ( <b>NOT SUITABLE FOR BACK FILLING</b> ) BEYOND INITIAL LEAD OF 50M AND UPTO A MAXIMUM LEAD OF 2 KM OR PART THEREOF INCLUDING LOADING, UNLOADING , TRANSPORTING AND SPREADING AS PER DIRECTION OF BHEL ENGINEER .	M3	170.00			
Sec. A	3	BACKFILLING OF FOUNDATION ,FLOORS AND PLINTH IN LAYERS NOT EXCEEDING 150MM THICK. INCLUDING WATERING AND CONSOLIDATING ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.					
Sec.A	A	WITH <b>GOOD EXCAVATED SOIL</b> AVAILABLE FROM THE EARTH WORK.	M3	200.00			
Sec. A	B	WITH GRANULAR MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 150MM ) BELOW FOUNDATIONS, AND RAMP AS PER STANDARD SPECIFICATION, RELEVANT DRAWINGS AND INSTRUCTED BY BHEL ENGINEER INCLUDING ROYALTY. CONTRACTOR HAS TO SUBMIT ROYALTY CERTIFICATE FROM CONCERNED STATE GOVT. MINING DEPARTMENT	M3	41.00			
	C	WITH <b>GOOD</b> EARTH BROUGHT FROM OUTSIDE FROM CONTRACTOR'S OWN SOURCE INCLUDING ROYALTY ETC.	M3	35.00			
Sec. A	D	PROVIDING & FILLING IN <b>SOAK PIT WITH BRICK BATS 40-80MM</b> INCLUDING SAND PACKING ETC. COMPLETE, AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.	M3	8.50			
Sec. A	E	PROVIDING STONE SOLING OF REUIRED THICKNESS AS PER DRAWING BELOW FLOORING, RAMP, COLUMN FOUNDATIONS OF STORAGE SHED ETC. BY USING 80 MM SIZE HARD BROKEN BLACK GRANITE/ QUARTIZITE/ GNEISS/ TRAP STONE METAL INCLUDING GRANULAR MURRUM PACKING, WATERING & COMPACTION ETC COMPLETE.AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER	M3	301.00			
Sec. A	4(A)	PROVIDING AND LAYING OF <b>PLAIN CEMENT CONCRETE OF MIX 1:4:8</b> USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY FOR FOUNDATION, FLOORING, COLUMN ETC. INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	130.00			
Sec. A	4(B)	PROVIDING AND LAYING OF <b>100 MM THICK PLAIN CEMENT CONCRETE OF MIX 1:3:6</b> USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY WITH TROWEL FINISH FOR <b>PLINTH PROTECTION</b> WITH TROWEL FINISH INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	12.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	5	PROVIDING AND LAYING OF <b>RCC MIX 1:2:4</b> USING OPC GRADE 43/53, 20MM DOWN SIZE HARD BROKEN GRANITE STONE AGGREGATE INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK & CENTERING AS PER DRAWING AND SPECIFICATION AND DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS.	<b>M3</b>	<b>105.00</b>			
Sec. A	6	PROVIDING AND LAYING <b>DPC</b> (DAMP PROOF COURSE) 50MM THICK IN 1:2:4 CEMENT CONCRET LAYER USING OPC GRADE 43/53AND WITH 6MM DOWN AGGREGATE, INCLUDING FORMWRK, BITUMEN FELT USING CEMENT WITH WATER PROOFING COMPOUND ETC. COMPLETE	<b>M2</b>	<b>75.00</b>			
Sec. A	7	PROVIDING , CUTTING, BENDING AND FIXING IN POSITION <b>REINFORCEMENT OF VARIOUS DIA.</b> USING <b>HIGH TENSILE TOR STEEL (Fe - 415/500 )</b> FOR FOUNDATIONS, COLUMNS, BEAMS, FLOORS, SUNSHED, SLAB ETC. AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL MATERIALS, LEADS, LIFT, LABOURS, MS BINDING WIRE 18/20 GAUGE, TACK WELDING AND SUPPORTING IF REQUIRED COMPLETE.	<b>MT</b>	<b>8.50</b>			
Sec. A	8 (A)	PROVIDING <b>BRICK WORK IN CM 1:6</b> (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND <b>LOCALLY AVAILABLE BURNT CLAY BRICKS</b> (MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, SUPER STRUCTURE, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	<b>M3</b>	<b>162.00</b>			
Sec. A	8 (B)	PROVIDING <b>BRICK WORK IN CM 1:6</b> (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND <b>FLY ASH LIME BRICKS</b> (FAL - MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	<b>M3</b>	<b>87.00</b>			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	9 (A)	PROVIDING <b>HALF BRICK WORK PARTITION WALL IN CM 1:4</b> (1 CEMENT & 4 COARSE SAND) USING OPC GRADE 43/53 AND <b>LOCALLY AVAILABLE BURNT CLAY BRICKS</b> (MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL ETC INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, RAKING OUT JOINTS,CURING AS PER DRAWING AND DIRECTED BY BHEL ENGINEER.	M2	5.00			
Sec. A	9 (B)	PROVIDING <b>HALF BRICK WORK FOR PARTITION WALL IN CM 1:4</b> (1 CEMENT & 4 COARSE SAND) USING OPC GRADE 43/53 AND <b>FLY ASH LIME BRICKS</b> (FAL - MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL ETC INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, RAKING OUT JOINTS,CURING AS PER DRAWING AND DIRECTED BY BHEL ENGINEER.	M2	5.00			
Sec. A	10(A)	SUPPLY,FABRICATING, AND ERECTION OF <b>TUBULAR TRUSSES (BY USING CLASS B ,MEDIUM QUALITY PIPE)</b> AS PER BHEL DRAWING WITH <b>AC SHEETS</b> AND <b>WIND TIES (USING FLAT OF SIZE 40X5MM)</b> TO BE PROVIDED ABOVE SHEETS AND PROVIDING AND FIXING BASE PLATES WITH HOLDING DOWN BOLTS ON RCC COLUMNS, GUSSETS, RIBS, PINS, SPLICES ETC. AS REQUIRED INCLUDING TRANSPORT, LOADING, UNLOADING CHARGES FROM FABRICATION SHOP TO SITE ETC. COMPLETE. RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE. <b>HALLOW TRUSS (OUTER MAIN FRAME WITH CENTER POST EXCEPT OTHER VERTICAL &amp; CROSS BRACING/TUBES/CROSS STUD) SHALL BE PROVIDED ON BOTH SIDE OF GABLE END TO FIX THE PURLINS AND ROFFING MATERIAL.</b>	MT	16.00			
Sec. A	10(B)	SUPPLY, FABRICATING, AND ERECTION OF <b>STRUCTURAL STEEL STAGING</b> (APPROX. Ht. 4.0M) FOR <b>INSTALLATION OF PVC OVER HEAD WATER TANK (OHT)</b> OF CAPACITY- 1000 LITRES. AS PER BHEL DRAWING . RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE.	MT	1.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	11	PROVIDING AND FIXING <b>6/7MM THICK AC CORRUGATED SHEETS</b> WITH RIDGE CAPS FOR ROOFING INCLUDING GALVANISED IRON J OR L HOOK , BOLTS, BITUMINOUS WASHERS, GI CRAMP BOLTS, NUTS,SCAFOLDING ETC. COMPLETE, ALL AS PER LATEST IS 459, 3307 AND 730.	M2	1020.00			
Sec. A	12	PROVIDING AND FIXING OF <b>TRANSLUCENT RMP/FRP (FIBRE GLASS REINFORCED PLASTIC) SHEETS - 2.00</b> MM THICK OF APPROVED MAKE INCLUDING COST OF GI J OR L HOOKS , BOLTS, NUTS, WASHERS, BITUMEN WASHERS,SCAFOLDING ETC. COMPLETE SO AS TO MATCH WITH AC CORRUGATED SHEETS FOR NATURAL LIGHTING.	M2	67.00			
Sec. A	13	PROVIDING AND FIXING OF <b>FALSE CEILING OF AC PLAIN SHEETS WITH 4MM THICK</b> OF APPROVED QUALITY AND DESIGN OF SIZE 600x600 MM PANELS WITH SQUARE EDGES SUPPORTED BY ANODISED ALUMINIUM FRAMES OF TEES 35x23.5x1.5 MM THICK AS MAIN MEMBER AND 19x23.5x1.5 MM TEES AS CROSS SUPPORTING MEMBERS AND WALL ANGLES OF 23.5x23.5x1.5MM. THE MAIN RUNNERS SHALL BE SUSPENDED FROM ROOF AT 1200 MM CENTRE TO CENTRE BY MEANS OF MS RODS WITH GI 'J' THREADED HOOK FOR ADJUSTMENTS. THE CROSS RUNNERS SHALL BE FIXED TO MAIN RUNNER TO FORM ' <b>A' GRID PATTERN</b> OF 600x600MM AND PROVIDING 25 MM WIDE ALUMINIUM STRIP TEES OR MOULDED SECTIONS AT ALL JOINTS. THE RATE SHALL BE INCLUSIVE OF TWO COATS OF APPROVED OBD ON AC PLAIN SHEETS, SUPPLY & FIXING OF ALUMINIUM FRAME AND SCAFDOLDING ETC. COMPLETE.	M2	195.00			
Sec. A	14(A)	PROVIDING AND FIXING OF <b>BEST QUALITY COUNTRY WOOD DOORS</b> COMPRISING OF <b>FRAME 95 X 70MM AND 38/40MM THICK FLUSH SHUTTERS OF SOLID CORE TYPE</b> USING COMMERCIAL PLY INCLUDING HOLD FASTS, WIND APPLIANCES, HANDLES, TOWER BOLTS AND ALDROPS, MORTISE OR SUITABLE LOCKS ETC. AS PER THE STANDARD PRACTICE AND APPLYING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED SHADE &COLOR OVER A COAT OF PRIMER AS DIRECTED BY BHEL ENGINEER.	M2	16.50			
Sec. A	14(B)	PROVIDING AND FIXING OF <b>BEST QUALITY PVC PANELLED DOORS OF THICKNSS 29MM, SINTEX/BAJAJ MAKE OR APPROVED EQUIVALENT</b> FOR TOILETS INCLUDING ALL FITTINGS AND FIXTURES, MS ANGLE FRAME OF SIZE 40x40x6MM ETC. ALL COMPLETE AS PER DRAWINGS AND SPECIFICATIONS.	M2	2.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	14(C)	PROVIDING AND FIXING OF <b>18 GAUGE M.S. SHEET DOOR</b> WITH FRAME WORK <b>40 X 40 X 6 MM M.S. ANGLE</b> INCLUDING LOCKING ARRANGEMENTS, HOLD FAST , APPLYING ANTICORROSSIVE PRIMER COAT OF RED LEAD PAINT AND 2 COATS OF SYNTHETIC ENAMLE PAINT OF APPROVED COLOUR COMPLETE AS DIRECTED BY BHEL ENGINEER.	M2	2.25			
Sec. A	15	SUPPLING, MANUFACTURING AND FIXING IN POSITION OF <b>STEEL WINDOWS AND VENTILATORS</b> INCLUDING FRAMES & IRON BARRED (GUARD BAR OF SQUARE SECTION @ 100 MM C/C) AND GLAZED WITH 4MM PLAIN GLASS AS PER STANDARD SPECIFICATIONS & RELEVANT <b>IS CODE</b> AND INSTRUCTIONS OF BHEL ENGINEER. THE COST SHALL BE INCLUSIVE OF ALL ACCESSORIES FITTINGS, HOLD FASTS, PAINTING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER ETC. COMPLETE.					
Sec. A	A	<b>STEEL WINDOWS</b>	M2	10.00			
Sec. A	B	<b>STEEL LAUVERED VENTILATORS :-</b>	M2	9.00			
Sec. A	16	PROVIDING AND FIXING OF <b>IPS FLOORING 40MM THICK USING OPC GRADE 43/53</b> WITH CEMENT CONCRETE 1:2:4 (USING 12 MM DOWN AGGREGATES) AS PER STANDARD PRACTICE IN PANELS OF SIZE NOT EXCEEDING 2.0 x 2.0 SQ.M BY PROVIDING, FIXING GLASS STRIPS.INCLUDING CURING & CLEANING.	M2	820.00			
Sec. A	17	PROVIDING <b>2MM THICK NEAT CEMENT FINISH USING OPC GRADE 43/53</b> OVER CONCRETE BASE FOR FLOORING, PAVING, PLASTERED SURFACE ETC. INCLUDING CURING & CLEANING AND SCAFFOLDING COMPLEATE.	M2	895.00			
Sec. A	18	PROVIDING AND LAYING OF <b>5.5 MM THICK CERAMIC TILES</b> OF REQUIRED SIZE LAID OVER THE BED OF CM - 1:4 (1 CEMENT & 4 COARSE SAND) USING OPC GRADE 43/53.TILES FROM REPUTED MANUFACTURER LIKE <b>JONSON OR EQUIVALENT</b> INCLUDING ALL MATERIALS COMPLETE AS PER STANDARD PRACTICE AND SPECIFICATION.					
Sec. A		(I) FLOORING - 300MM X 300MM	M2	82.00			
Sec. A		(II) SKIRTING - 300MM X 150MM	M2	7.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	19	SUPPLYING AND FIXING OF <b>WHITE GLAZED TILES OF REQUIRED SIZES LAID OVER THE BED OF CM - 1:4 (1 CEMENT &amp; 4 COARSE SAND) USING OPC GRADE 43/53 . DADO IN TOILET &amp; PANTRY ROOM UP TO 1.5 M</b> ELEVATIONS INCLUDING PEREPARATION OF BASE LAYING UNDERBED, FINISHING AND ROUNDING CORNERS AND JUNCTIONS, CURING ETC. COMPLETE AS PER DRAWINGS AND SPECIFICATIONS.					
Sec. A		(I) FLOORING (5.0MM TO 6.0MM THICK OF SIZE 300MM X 300MM)	M2	28.00			
Sec. A		(II) DADO (5MM TO 6MM THICK OF SIZE 150MM X 150MM) - 1.5M HEIGHT FROM FINISHED FLOOR LEVEL	M2	32.00			
Sec. A	20	PROVIDING <b>PLASTERING WITH CEMENT MORTAR -1:6 (1 CEMENT &amp; 6 COARSE SAND) USING OPC GRADE 43/53</b> OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES, PARTITION WALLS ETC. AT ALL LEVELS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.					
Sec. A		(i) EXTERNAL PLASTERING - <b>18MM THICK</b>	M2	865.00			
Sec. A		(ii) INTERNAL PLASTERING - <b>12MM THICK</b>	M2	1250.00			
Sec. A	21(A)	PROVIDING & APPLYING <b>COLOUR WASH -THREE COATS</b> ON NEWLY PLASTERED EXTERNAL SURFACE OF SHED BY USING BEST <b>SHALE LIME</b> TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, BASE COAT OF WHITE WASH,APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	M2	865.00			
Sec. A	21(B)	PROVIDING & APPLYING <b>WHITE WASH - THREE COATS</b> ON NEWLY PLASTERED INTERNAL SURFACE OF SHED (EXCLUDING INNER WALL OF OFFICE/C&I ROOM) BY USING BEST <b>SHALE LIME</b> TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	M2	815.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	21(C)	PROVIDING & APPLYING TO INTERIOR SURFACES OF STORE OFFICE AND C&I ROOM BY <b>TWO COATS OF OIL BOUND DISTEMPER (OBD)</b> OF APPROVED SHADE ,COLOR AND MAKE CONFIRMING TO IS : 428 TO OBTAIN A EVEN FINISH AND UNIFORM COLOR OVER A COAT OF PRIMER AS PER MANUFACTURE RECOMMENDATION INCLUDING COST OF PAINT, SURFACE PREPARATION LIKE CLEANING AND BRUSHING & BROOMING OF WALLS , SCAFFOLDING AT ALL LEVEL ETC, COMPLETE. <b>SURFACE PREPARATION SHALL BE DONE BY APPLYING PUTTY/PLASTER OF PARISH (POP)</b> INCLUDING COST OF MATERIAL, LABOUR ETC. COMPLETE.	M2	450.00			
Sec. A	22	PROVIDING AND FIXING <b>OVER HEAD HYDRAULIC DOOR CLOSER</b> (HEAVY DUTY) OF APPROVED BRAND AND SIZE ON NECESSARY DOORS AS DIRECTED BY BHEL ENGINEER.	NO.	7.00			
Sec. A	23	PROVIDING AND FIXING <b>WHITE GLAZED VITREOUS CHINA WASH HAND BASIN</b> OF 55 CM X 40 CM SIZE INCLUDING COLD WATER FILLER TAP, BRACKETS, STOP TAP, CHROMIUM PLATED BOTTLE TRAP AND NECESSARY PIPE CONNECTIONS INCLUDING UPVC WASTE PIPE AND TRAP UPTO THE OUT SIDE FACE OF THE WALL, MAKING GOOD THE DAMAGED SURFACE, TESTING ETC. COMPLETE. PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.	NO	1.00			
Sec. A	24	PROVIDING AND FIXING <b>EUROPEAN TYPE WHITE GLAZED VITREOUS CHINA</b> W.C.PAN WITH UPVC SEAT AND LID WITH CHROMIUM PLATED BRASS HINGES AND RUBBER BUFFERS INCLUDING UPVC VENT PIPE (APPROX. 2M. HT. WITH COWL)) ON THE OUTSIDE FACE OF WALL, 10 LITRE PVC LOW LEVEL FLUSHING CISTERN WITH ALL FITTINGS, PIPE AND STOP COCK, BRACKETS FOR FIXING CISTERN, 32 MM DIA. UPVC FLUSH PIPE WITH FITTINGS AND CLAMPS, 20 MM DIA. UPVC OVERFLOW PIPE, FLOAT VALVES, CUTTING AND MAKING GOOD TO THE WALLS AND FLOORS, TESTING ETC. COMPLETE. PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.	NO	1.00			



SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	25	PROVIDING AND FIXING IN POSITION OF <b>WHITE GLAZED EARTHENWARE</b> FLAT BACK/CORNER TYPE LIPPED FRONT <b>URINALS OF 430MM X 260MM X 350MM / 340X460X265 MM</b> OF APPROVED MAKE AND QUALITY WITHOUT FLUSHING CISTERN, GI FLUSH PIPE AND SPREADERS WITH BRASS UNIONS, GI CLAMPS, CUTTING OF WALLS AND MAKING GOOD OF ALL DAMAGES AND FINISHING TO MATCH THE EXISTING WORK ETC. COMPLETE. RATE QUOTED SHALL INCLUDE COST OF ALL MATERIALS AND LABOUR FOR CARRYING, LAYING & FIXING AND ALL OTHER INCIDENTAL CHARGES ETC. COMPLETE.	NO	2.00			
Sec. A	26	PROVIDING AND FIXING IN POSITION OF <b>HIGH CLASS BELGIUM OR SUPERIOR MAKE BEVELLED EDGE MIRROR OF SIZE 450MM X 550MM X 6MM</b> WITH <b>16 MM DIA &amp; 550MM LENGTH NICKEL PLATED TOWEL ROD MOUNTED</b> ON 6 MM THICK PLYWOOD OR PLASTIC FOLDER SHEET. RATE TO INCLUDE COST OF ALL MATERIALS, LABOUR FOR FIXING THE WOODEN PLUGS WITH CP BRASS SCREWS AND WASHERS ETC. COMPLETE.	NO	1.00			
Sec. A	27	PROVIDING AND FIXING IN POSITION OF 15 MM DIA <b>CONCUSSION PUSH BUTTON</b> TYPE BRASS/ <b>GUN MATEL SELF CLOSING TAP</b> INCLUDING NACESSARY SOCKET,TESTING ETC COMPLETE FOR URINALS AS DIRECTION OF BHEL ENGINEER.	NO	2.00			
Sec. A	28 (A)	PROVIDING AND FIXING IN POSITION OF <b>15 MM DIA NOMINAL SIZE SCREW DOWN TYPE CHROMIUM PLATES BRASS BIB COCKS</b> OF STANDARD TYPE OF APPROVED MAKE AND QUALITY (LEADER MAKE OR EQUIVALENT) AS PER STANDARD SPECIFICATION.RATE INCLUDES JOINTING MATERIALS,SOCKETS,UNION NUT,TESTING, LABOURS FOR CARRYING AND FIXING ETC. COMPLETE	NO	3.00			
Sec. A	28 (B)	PROVIDING AND FIXING IN POSITION OF <b>25 MM DIA GATE VALVE.INCLUDING ALL NACESSARY FITTING &amp; FIXTURE ETC. COMPLETE</b> AS PER STANDARD SPECIFICATION.	NO	1.00			
Sec. A	28 (C)	PROVIDING AND FIXING IN POSITION OF <b>40 MM DIA GATE VALVE.INCLUDING ALL NACESSARY FITTING &amp; FIXTURE ETC. COMPLETE</b> AS PER STANDARD SPECIFICATION.	NO	1.00			
Sec. A	29	PROVIDING AND FIXING IN POSITION OF <b>15 MM DIA NOMINAL SIZE SCREW DOWN TYPE CHROMIUM PLATES BRASS STOP COCKS</b> OF APPROVED MAKE AND QUALITY (LEADER MAKE OR EQUIVALENT) AS PER STANDARD SPECIFICATION.RATE INCLUDES COST OF JOINTING MATERIALS, SOCKETS,UNION NUT,TESTING, LABOURS FOR CARRYING AND FIXING ETC. COMPLETE	NO	4.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	30	PROVIDING AND FIXING IN POSITION OF <b>100MM X 50MM HCI "NAHANI" TRAP</b> WITH HCI GRATINGS, BENDS, CONNECTING PIECES OF CI PIPE UPTO OUTSIDE FACE OF THE WALL. MAKING GOOD THE DAMAGED SURFACE, TESTING ETC <b>COMPLETE</b> AS PER STANDARD SPECIFICATIONS. RATE TO BE ALL INCLUSIVES.	NO	<b>4.00</b>			
Sec. A	31	PROVIDING AND FIXING IN POSITION OF <b>150MM SALT GLAZED STONE WARE GULLY TRAP WITH HCI GRATINGS</b> AND CI COVER OF SIZE 300X300 MM OF APPROVED MAKE (WEIGHT NOT LESS THAN 2 KG) AND QUALITY AS PER STANDARD SPECIFICATIONS. RATE TO BE ALL INCLUSIVE.	NO	<b>2.00</b>			
Sec. A	32	PROVIDING AND LAYING WITH REQUIRED GRADING & LEVELING IN TRENCHES <b>MEDIUM GRADE (TYPE) GALVANISED IRON (G I) PIPE</b> HAVING EMBOSSED ISI MARK ON IT, OF REQUIRED DIAMETER WITH SCREWED, SOCKETS, JOINTS, NECESSARY GALVANISED IRON FITTINGS SUCH AS SOCKETS, BACK NUTS, ELBOWS, BENDS, TEES, REDUCERS, ENLARGERS, PLUGS, CLAMPS ETC. INCLUDING ALL NECESSARY EXCAVATION, BACK FILLING, FIXING WITH CLAMPS, TESTING ETC. COMPLETE. (PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.)					
Sec. A	A	40MM DIA	RM	<b>100.00</b>			
Sec. A	B	25MM DIA	RM	<b>50.00</b>			
Sec. A	C	20MM DIA	RM	<b>25.00</b>			
Sec. A	D	15MM DIA	RM	<b>20.00</b>			
Sec. A	33	PROVIDING AT WORKING SITE, CARRYING AND LOWERING INTO TRENCHES, LAYING TO PROPER ALIGNMENT, LEVEL AND GRADE, JOINTING WITH CM (1:1) AND TESTING OF JOINTS ETC. OF THE FOLLOWING SIZE OF SALT <b>GLAZED STONEWARE PIPE</b> INCLUSIVE OF ALL NECESSARY SPECIALS TARRED HEMP YARN AND ALL JOINTING MATERIALS COMPLETE AS PER STANDARD SPECIFICATIONS INCLUDING ALL NECESSARY EXCAVATION ,BACKFILLING, DISPOSAL OF SURPLUS EARTH ,LEAD AND LIFT AS PER SITE CONDITIONS. RATE SHALL INCLUDE COST OF ALL MATERIALS, LABOUR CHARGES AND INCIDENTAL CHARGES ETC. COMPLETE.					
Sec. A	A	100MM DIA STONEWARE PIPELINE INCLUDING ALL SPECIALS COMPLETE.	RM	<b>50.00</b>			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	34	PROVIDING AND FIXING IN POSITION OF <b>PVC OVERHEAD WATER TANK OF SYNTEX OR ANY APPROVED MAKE OF 1000 LITRE CAPACITY</b> WITH PROVISION FOR OVERFLOW ARRANGEMENT VALVES, INLET AND OUTLET ETC. COMPLETE. SUPPORTING STEEL STRUCTURE FOR FIXING THE TANK SHELL BE PAID IN THE RELEVANT ITEM.	NO	1.00			
Sec. A	35	CONSTRUCTION OF 230MM THICK BURNT CLAY / FLY ASH LIME <b>BRICK CHAMBER</b> (USING OPC GRADE 43/53) OF THE FOLLOWING DIMENSIONS (INNER DIMENSION) WITH 20MM THICK INTERNAL & EXTERNAL CEMENT PLASTER OF MIX CM 1:5 (1 CEMENT & 5 COARSE SAND) , NEAT CEMENT FINISH , TOP <b>CI – COVER</b> AND CONNECTORS FOR SEWER LINES. RATE SHALL BE INCLUSIVE OF ALL NECESSARY EXCAVATION & FILLING, PCC-100 MM THICK OF 1:3:6 FOR BEDDING ON 100MM THICK OVERSIZER SOLING WITH 80 MM METALETC. COMPLETE.					
Sec. A	A	600X450X450 WITH C.I COVER	NO	2.00			
Sec. A	B	900X600X450 WITH C.I. COVER	NO	3.00			
Sec. A	36	PROVIDING AND FIXING OF <b>PRECAST 80 MM THICK RCC COVER</b> OF MIX 1:1.5:3 FOR MAN HOLES OF VARIOUS SIZES WITH REINFORCEMENT OF 10 MM DIA BOTH WAY TIED WITH TACK WELDING @ 150 MM C/C WITH 2 HOOKS OF 12 MM DIA BARS ETC.COMPLETE.					
Sec. A	A	750MM x 600MM	Nos.	2.00			
	B	1050MM x 750MM	Nos.	3.00			
Sec. A	37	PROVIDING AND FIXING <b>CHROMIUM PLATED TOWEL ROD 16 MM DIA.</b> AND 75CM. IN LENGTH INCLUDING ALL ACCESSORIES COMPLETE. (PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE).	NO.	1.00			
Sec. A	38	PROVIDING & FIXING OF <b>LIQUID SOAP DISPENSER</b> AT ALL WASH BASIN LOCATION.	NO.	1.00			
Sec. A	39	PROVIDING & FIXING OF <b>WOODEN FRAME OF BEST QUALITY COUNTRY WOOD (2.5"x3.0")</b> FOR INSTALLING PORTABLE <b>1.5T AIR CONDITIONER</b> ON THE WALL OPENING (31"x22"), SO AS TO MAKE A FRAME OF INSIDE CLEAR DIMENSION 26"x17" WITH COMPLETE FINISHING, PAINTING, HOLD FAST ETC. RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR, MAKING GOOD THE DAMAGED SURFACE ETC. COMPLETE. AS APPROVED BY BHEL ENGINEER.	NOS.	6.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. A	40	PROVIDING & FIXING IN POSITION OF <b>CI VENT PIPE OF DIA. 100MM (APPROX. HT. 3M ) IN SEPTIC TANK.</b> RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC.	RM	4.00			
Sec. A	41	PROVIDING AND FIXING OF METALLIC DECORATIVE TYPE <b>HEAVY DUTY PELMET ROD FOR DOORS AND WINDOWS.</b> RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC. AS APPROVED BY BHEL ENGINEER.	EACH	5.00			
Sec. A	42	PROVIDING AND FIXING OF <b>AQUA-GUARD OR EQUIVALENT WATER PURIFIER,</b> ALONG WITH ALL FITTINGS. RATE TO INCLUDE ALL NECESSARY FITTINGS & FIXTURES, LABOUR ETC.AS APPROVED & DIRECTED BY BHEL ENGINEER.	NOS.	1.00			
Sec. A	43	PROVIDING AND FIXING OF 1 No. <b>18"X24" SIZE STAINLESS STEEL SINK</b> WITH ALL FITTINGS LIKE DRAIN PIPE, STOP VALVE ETC.RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC.AS APPROVED & DIRECTED BY BHEL ENGINEER.	NOS.	1.00			
Sec. A	44	PROVIDING , SUPPLYING AND FIXING OF <b>20 GAUGE MS ROLLING SHUTTERS</b> OF SIZE <b>4.6 M X 4.7 M (APPROX.)</b> AS PER I.S. SPECIFICATIONS, COMPLETE, MECHANICALLY OPERATED FROM IN AND OUTSIDE BOTH AS INSTRUCTED BY BHEL ENGINEER INCLUDING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER LOCKING ARRANGEMENT. RATE SHALL BE INCLUSIVE OF ALL THE ABOVE COMPLETE.	M2	23.00			
Sec. A		<b>TOTAL VALUE OF SECTION-A IN Rs.</b>					

BHEL : PS WR  
TS NO : BHE/PW/PUR/BRIT-ENB/640  
PRICE BID-PART-II ( RATE SCHEDULE )

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
<b>BHEL:PSWR:NAGPUR</b>							
<b>RATE SCHEDULE, SECTION B</b>							
Sec. B	<b><u>NAME OF THE WORK : INTERNAL ELECTRIFICATION WORK OF 1 NO. CLOSED SHED WITH STORE OFFICE AND C&amp;I ROOM AT UNIT 1 OF 2x 600 MW JHABUA MADHYA PRADESH</u></b>						
	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.		RATE	AMOUNT
Sec. B	1	SUPPLYING & INSTALLING <b>POWER DISTRIBUTION BOARD</b> COMPLETE WITH: COMMON BOARD FOR ALL SHEDS. 1) INCOMING MCB TPH 100 AMPS. - 1 NO. 2) OUTGOING MCB TPH 32 AMPS. -2NOS. 3) RCCB DP 25/20 AMPS. - 2NOS. 4) OUTGOING MCB SP 6 AMPS - 6NOS. All RCCBs, MCBs SHALL BE MDS/INDO KOPP MAKE. DISTRIBUTION BOARDS SHALL BE SIEMENS / MDS / INDO KOPP MAKE WITH INTERNAL BUSBARS, INTERNAL WIRING, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS.	Set	1			
Sec. B	2	PROVIDING AND INSTALLING <b>WIRING USING 2.5 SQ.MM</b> COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR COMPUTER ROOM, OFFICE SHED & FOR REST OF SHEDS OPEN AND WHRERVER REQUIRED IN PVC CONDUIT OF REQUIRED SIZE.	PER POINT	30.00			
Sec. B	3	PROVIDING AND INSTALLING <b>WIRING FOR USING 4.0 SQ.MM</b> COPPER CONDUCTOR THROUGH PVC CONDUIT OF REQUIRED SIZE WITH ACCESSORIES AND FIXTURES .WIRING SHALL BE CONCEALED TYPE FOR COMPUTER ROMM, OFFICE SHED & FOR REST OF SHEDS OPEN AND WHRERVER REQUIRED IN PVC CONDUIT OF REQUIRED SIZE.	PER POINT	10.00			
Sec. B	4	PROVIDING AND INSTALLING <b>WIRING FOR MAINS USING 6.00 SQ.MM</b> COPPER CONDUCTOR OF ISI MAKE. USING CONCEALED TYPE WIRING/PVC CONDUIT OF REQUIRED SIZE.	PER POINT	8.00			
Sec. B	5	PROVIDING AND INSTALLING <b>WIRING FOR MAINS USING 16.00 SQ.MM</b> COPPER CONDUCTOR OR ISI MAKE USING CONCEALED TYPE WIRING/PVC CONDUIT OF REQUIRED SIZE.	PER POINT	5.00			
Sec. B	6	PROVING AND INSTALLATION OF <b>WIRING FOR FANS/COOLERS USING 2.5SQ.MM</b> COPPER CONDUCTOR OF ISI MARK THROUGH PVC CONDUITS WITH ACCESSORIES AND FIXTURES. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	PER POINT	6.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. B	7	POVIDING AND INSTALLATION OF <b>PLUG POINT OF 5A SOCKET</b> (ANCHOR OR EQUIV.) OUTLET INCLUDING WIRING TERMINATION. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NO	15.00			
Sec. B	8	POVIDING AND INSTALLATION OF <b>PLUG POINT OF 15A SOCKET</b> (ANCHOR OR EQUIV.) OUTLET INCLUDING WIRING TERMINATION. THIS INCLUDES TUBE LIGHT FITTINGS V	NO	7.00			
Sec. B	9	PROVIDING AND FIXING <b>ORDINARY TUBELIGHT WITH FRAME</b> OF STANDARD MANUFACTURER LIKE PHILIPS/BAJAJ OR EQUIVALENT AS APPROVED BY BHEL. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NO.	20.00			
Sec. B	10	PROVIDING AND FIXING <b>EXHAUST FANS 12" DIAMETER</b> WITH FRAME OF STANDARD MANUFACTURER LIKE CROMPTAN GREEVES OR EQUIVALENT AS APPROVED BY BHEL.	NO.	3.00			
Sec. B	11	PROVIDING AND FIXING <b>HEAVY DUTY PLUG POINT 15 AMPS</b> ( ANCHOR MAKE OR EQUIV.) WITH ONE SWITCH FOR COMPUTER ,ONE FOR AC CONNECTION WITH BORD ETC COMPLETE.	NO.	6.00			
Sec. B	12	PROVIDING AND FIXING METAL CLAD PLUG AND <b>MCB</b> OF 30AMPS. (CROMPTON/MDS MAKE) FOR AIR CONDITIONER WITH BOARD ETC COMPLETE.	NO.	4.00			
Sec. B	13	PROVIDING AND FIXING <b>CEILING FAN 48" DIAMETER</b> OF APPROVED COMPANY SUCH AS CROMTAN GREEVES OR ANY OTHER STANDARD MANUFACTURER AS DIRECTED BY BHEL. THIS INCLUDES TUBE LIGHT FITTINGS ETC. COMPLETE.	NO	6.00			
Sec. B	14	PROVIDING AND FIXING <b>CALLING BELLS</b> (WITH INDICATOR LIGHT)	NO	2.00			
Sec. B	15	PROVIDING <b>EARTHING PITS WITH 2 " DIA</b> , 2 M LONG GI PIPES WITH FLANGE & GI WIRES WITH CHARCOAL, SALT AND AS PER THE STANDARD PRACTICE FOR ELECTRICAL CONNECTION.RATE SHALL BE INCLUSIVE OF ALL MATERIALS, LABOURS, ETC COMPLETE.	NO	3.00			
Sec. B	16	PROVIDING & FIXING <b>ALUMINIUM DISPERSIVE LUMINAIRE</b> ENAMELED GREEN AND WHITE WITH CAST ALUMINIUM FLANGE AND NIPPLE SUITABLE FOR USE WITH GLS LAMP, DOME 12" DIAMETER, WITH HANGING BRACKET AND <b>200W GLS LAMP</b> OF CROMPTON OR EQUIVALENT <b>BAJAJ/PHILIPS</b> MAKE, COMPLETE.	Nos.	35.00			
Sec. B	17	<b>WIRING WITH 2.5 SQ MM</b> ISI MARK COPPER WIRE FOR ABOVE IN PVC CONDUIT ALONG WITH GI EARTH WIRE INCLUSIVE OF ALL MATERIAL, LABOUR ETC. COMPLETE	Per Point	35.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. B	18	SUPPLYING & FIXING <b>WALL MOUNTING TYPE LIGHTING PANELS</b> , EACH WITH. (1) INCOMING MCB TPN -32 AMPS - 1NO. (2) RCCB DP 32 AMPS - 3NOS (3) MCB SP 6AMPS - 30 NOS. ALL MCBS AND RCCBS SHALL BE OF MDS / INDO KOPP MAKE. LIGHTING PANEL SHALL BE SIEMENS/MDS/INDO KOPP MAKE WITH INTERNAL BUSBARS, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS & WIRING FROM MAIN DB.	Sets.	1.00			
Sec. B		<b>TOTAL VALUE OF SECTION-B IN Rs.</b>					
<b>BHEL:PSWR:NAGPUR</b>							
<b>RATE SCHEDULE, SECTION - C</b>							
<b><u>CONSTRUCTION OF 2No. - CLOSED STORAGE SHED (60 M X 15 M) AT UNIT 1 OF 2x 600 MW JHABUA MADHYA PRADESH</u></b>							
Sec.	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.		RATE	AMOUNT
Sec. C	1(A)	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH IN <b>ALL KINDS OF SOIL (EXCEPT SOFT ROCK AND HARD ROCK) FOR FOUNDATIONS, RAMPS</b> ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	460.00			
Sec. C	1(B)	EARTH WORK EXCAVATION FROM <b>0 (ZERO) TO 2 M DEPTH FOR SOFT ROCK AND HARD ROCK</b> (BY MANUALLY OR MECHANICALLY BUT WITHOUT BLASTING) FOR <b>FOUNDATIONS, RAMPS</b> ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	120.00			
Sec. C	1(C)	EARTH WORK <b>EXCAVATION FROM 2.0M TO 4.0 M DEPTH</b> IN ALL KINDS OF SOIL ( <b>EXCEPT HARD ROCK AND SOFT ROCK</b> ) FOR <b>FOUNDATIONS, RAMPS</b> ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	20.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. C	1(D)	EXCAVATION IN ALL KINDS OF SOIL <b>INCLUDING SOFT &amp; HARD ROCK</b> ((BY MANUAL CHISELING OR BY MECHANICAL MEANS BUT WITHOUT BLASTING) <b>FROM 2 TO 4M DEPTH FOR FOUNDATIONS, RAMPS ETC</b> WHEREVER REQUIRED INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	50.00			
Sec. C	1(E)	SUB GRADE PREPARATION: CUTTING LEVELLING, FILLING USING EXCAVATED EART, WATERING AND CONSOLIDATION FOR <b>PLINTH PROTECTION AREA</b> BEFORE LAYING THE PCC WITH ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.	M2	246.00			
Sec. C	2	DISPOSAL OF EXCAVATED EARTH/ROCK <b>(NOT SUITABLE FOR BACK FILLING)</b> BEYOND INITIAL LEAD OF 50M AND UPTO A MAXIMUM LEAD OF 2 KM OR PART THEREOF INCLUDING LOADING, UNLOADING , TRANSPORTING AND SPREADING AS PER DIRECTION OF BHEL ENGINEER .	M3	260.00			
Sec. C	3	BACKFILLING OF FOUNDATION ,FLOORS AND PLINTH IN LAYERS NOT EXCEEDING 150MM THICK. INCLUDING WATERING AND CONSOLIDATING ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.					
Sec. C	A	WITH GOOD <b>EXCAVATED SOIL</b> AVAILABLE FROM THE EARTH WORK.	M3	320.00			
Sec. C	B	WITH GRANULAR MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 150MM ) BELOW FOUNDATIONS AND RAMP AS PER STANDARD SPECIFICATION, RELEVANT DRAWINGS AND INSTRUCTED BY BHEL ENGINEER INCLUDING ROYALTY. CONTRACTOR HAS TO SUBMIT ROYALTY CERTIFICATE FROM CONCERNED STATE GOVT. MINING DEPARTMENT	M3	80.00			
Sec. C	C	WITH <b>GOOD</b> EARTH BROUGHT FROM OUTSIDE FROM CONTRACTOR'S OWN SOURCE INCLUDING ROYALTY ETC.	M3	80.00			
Sec. C	D	PROVIDING <b>STONE SOLING</b> OF REUIRED THICKNESS AS PER DRAWING BELOW FLOORING, RAMP, COLUMN FOUNDATIONS OF STORAGE SHED ETC. BY USING 80 MM SIZE HARD BROKEN BLACK GRANITE/QUARTIZITE/GNEISS/TRAP STONE METAL INCLUDING GRANULAR MURRUM PACKING, WATERING & COMPACTION ETC COMPLETE.AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER	M3	560.00			



SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. C	4	PROVIDING AND LAYING OF <b>PLAIN CEMENT CONCRETE OF MIX 1:4:8</b> USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY FOR FOUNDATION, FLOORING, COLUMN ETC. INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	230.00			
Sec. C	5	PROVIDING AND LAYING OF <b>100 MM THICK PLAIN CEMENT CONCRETE OF MIX 1:3:6</b> USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY WITH TROWEL FINISH FOR <b>PLINTH PROTECTION</b> WITH TROWEL FINISH INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	26.00			
Sec. C	6	PROVIDING AND LAYING OF <b>RCC MIX 1:2:4</b> USING OPC GRADE 43/53, 20MM DOWN SIZE HARD BROKEN GRANITE STONE AGGREGATE INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK & CENTERING AS PER DRAWING AND SPECIFICATION AND DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS.	M3	200.00			
Sec. C	7	PROVIDING AND LAYING <b>DPC</b> (DAMP PROOF COURSE) 50MM THICK IN 1:2:4 CEMENT CONCRET LAYER USING OPC GRADE 43/53AND WITH 6MM DOWN AGGREGATE, INCLUDING FORMWRK, BITUMEN FELT USING CEMENT WITH WATER PROOFING COMPOUND ETC. COMPLETE	M2	110.00			
Sec. C	8	PROVIDING , CUTTING, BENDING AND FIXING IN POSITION <b>REINFORCEMENT OF VARIOUS DIA.</b> USING <b>HIGH TENSILE TOR STEEL (Fe -415/500 )</b> FOR FOUNDATIONS, COLUMNS, BEAMS, FLOORS, SUNSHED, SLAB ETC. AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL MATERIALS, LEADS, LIFT, LABOURS, MS BINDING WIRE 18/20 GAUGE, TACK WELDING AND SUPPORTING AS REQUIRED COMPLETE.	MT	15.00			
Sec. C	9 (A)	PROVIDING <b>BRICK WORK IN CM 1:6</b> (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND LOCALLY AVAILABLE BURNT CLAY BRICKS (MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, SUPER STRUCTURE, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	M3	220.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. C	9(B)	PROVIDING <b>BRICK WORK IN CM 1:6</b> (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND FLY ASH LIME BRICKS (MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	M3	120.00			
Sec. C	10	SUPPLY,FABRICATING, AND ERECTION OF <b>TUBULAR TRUSSES (BY USING CLASS B ,MEDIUM QUALITY PIPE)</b> AS PER BHEL DRAWING WITH <b>AC SHEETS</b> AND <b>WIND TIES (USING FLAT OF SIZE 40X5MM)</b> TO BE PROVIDED ABOVE SHEETS AND PROVIDING AND FIXING BASE PLATES WITH HOLDING DOWN BOLTS ON RCC COLUMNS, GUSSETS, RIBS, PINS, SPLICES ETC. AS REQUIRED INCLUDING TRANSPORT, LOADING, UNLOADING CHARGES FROM FABRICATION SHOP TO SITE ETC. COMPLETE. RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE. <b>HALLOW TRUSS (OUTER MAIN FRAME EXCEPT VERTICAL &amp; CROSS BRACING/TUBES/CROSS STUD) SHALL BE PROVIDED ON BOTH SIDE OF GABLE END TO FIX THE PURLINS AND ROOFING MATERIAL.</b>	MT	32.00			
Sec. C	11	PROVIDING AND FIXING <b>6/7MM THICK AC CORRUGATED SHEETS</b> WITH RIDGE CAPS FOR ROOFING INCLUDING GALVANISED IRON J OR L HOOK , BOLTS, BITUMINOUS WASHERS, GI CRAMP BOLTS, NUTS,SCAFFOLDING ETC. COMPLETE, ALL AS PER LATEST IS 459, 3307 AND 730.	M2	1980.00			
Sec. C	12	PROVIDING AND FIXING OF <b>TRANSLUCENT RMP/FRP(FIBRE GLASS REINFORCED PLASTIC) SHEETS - 2.00 MM THICK</b> OF APPROVED MAKE INCLUDING COST OF GI J ,OR L HOOKS , BOLTS, NUTS, WASHERS, BITUMEN WASHERS,SCAFFOLDING ETC. COMPLETE SO AS TO MATCH WITH AC CORRUGATED SHEETS.	M2	132.00			

SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. C	13	SUPPLING, MANUFACTURING AND FIXING IN POSITION OF <b>STEEL VENTILATORS</b> INCLUDING FRAMES & IRON BARRED (GUARD BAR OF SQUARE SECTION @ 100 MM C/C) AND GLAZED WITH 4MM PLAIN GLASS AS PER STANDARD SPECIFICATIONS & RELEVANT <b>IS CODE</b> AND INSTRUCTIONS OF BHEL ENGINEER. THE COST SHALL BE INCLUSIVE OF ALL ACCESSORIES FITTINGS, HOLD FASTS, PAINTING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER ETC. COMPLETE.					
Sec. C	A	<b>STEEL LAUVERED VENTILATORS :-</b>	<b>M2</b>	<b>18.00</b>			
Sec. C	14	PROVIDING AND FIXING OF <b>IPS FLOORING 40MM THICK USING OPC GRADE 43/53</b> WITH CEMENT CONCRETE 1:2:4 (USING 12 MM DOWN AGGREGATES) AS PER STANDARD PRACTICE IN PANELS OF SIZE NOT EXCEEDING 2.0 x 2.0 SQ.M BY PROVIDING, FIXING GLASS STRIPS.INCLUDING CURING & CLEANING.	<b>M2</b>	<b>1840.00</b>			
Sec. C	15	PROVIDING <b>2MM THICK NEAT CEMENT FINISH USING OPC GRADE 43/53</b> OVER CONCRETE BASE FOR FLOORING, PAVING ,PLASTERED SURFACE ETC.INCLUDING CURING & CLEANING AND SCAFFOLDING COMPLETE.	<b>M2</b>	<b>1840.00</b>			
Sec. C	16	PROVIDING <b>PLASTERING WITH CEMENT MORTAR -1:6 (1 CEMENT &amp; 6 COARSE SAND) USING OPC GRADE 43/53</b> OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES, PARTITION WALLS ETC. AT ALL LEVELS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.		<b>0.00</b>			
Sec. C		(i) EXTERNAL PLASTERING - 18MM THICK	<b>M2</b>	<b>1790.00</b>			
Sec. C		(ii) INTERNAL PLASTERING -12MM THICK	<b>M2</b>	<b>1620.00</b>			
Sec. C	17(A)	PROVIDING & APPLYING <b>COLOUR WASH -THREE COATS</b> ON NEWLY PLASTERED EXTERNAL SURFACE OF SHED BY USING BEST <b>SHALL LIME</b> TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, BASE COAT OF WHITE WASH,APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	<b>M2</b>	<b>1790.00</b>			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. C	17(B)	PROVIDING & APPLYING <b>WHITE WASH - THREE COATS</b> ON NEWLY PLASTERED INTERNAL SURFACE OF SHED BY USING BEST <b>SHALL LIME</b> TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	M2	1620.00			
Sec. C	18	MANUFACTURING, SUPPLYING AND FIXING OF <b>20 GAUGE MS ROLLING SHUTTERS</b> OF SIZE <b>4.6 M X 4.7 M</b> AS PER I.S. SPECIFICATIONS, COMPLETE, MECHANICALLY OPERATED FROM IN AND OUTSIDE BOTH AS INSTRUCTED BY BHEL ENGINEER INCLUDING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER LOCKING ARRANGEMENT. RATE SHALL BE INCLUSIVE OF ALL THE ABOVE COMPLETE.	M2	46.00			
Sec. C		<b>TOTAL VALUE OF SECTION-C IN Rs.</b>					
<b>BHEL:PSWR:NAGPUR</b>							
<b>RATE SCHEDULE, SECTION D</b>							
<b><u>NAME OF THE WORK : INTERNAL ELECTRIFICATION WORK OF 2NOS. CLOSED SHED (60M X 15M ) AT UNIT 1 OF 2x 600 MW JHABUA MADHYA</u></b>							
Sec. D	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.		RATE	AMOUNT
Sec. D	1	Supplying & Installing Power Distribution Board complete as below: 1) Incoming MCB TPH 100 Amps. - 1 No. 2) Outgoing MCB TPH 32 Amps. -2Nos.. 3) RCCB DP 25/20 Amps. - 4Nos. 4) Outgoing MCB SP 6 Amps - 8Nos. All RCCBs, MCBs shall be MDS/INDO KOPP make. Distribution Boards shall be SIEMENS / MDS / INDO KOPP make with internal busbars, internal wiring, 2 nos. earthing terminals, earth connections, including Glands, Lugs etc.	Set	1			
Sec. D	2	PROVIDING & FIXING ALUMINIUM DISPERSIVE LUMINAIRE ENAMELED GREEN AND WHITE WITH CAST ALUMINIUM FLANGE AND NIPPLE SUITABLE FOR USE WITH GLS LAMP, DOME 12" DIAMETER, WITH HANGING BRACKET AND 200W GLS LAMP OF CROMPTON OR EQUIVALENT BAJAJ / PHILIPS MAKE, COMPLETE.	Nos.	70.00			
Sec. D	3	<b>WIRING WITH 2.5 SQ MM</b> ISI MARK COPPER WIRE FOR ABOVE IN PVC CONDUIT ALONG WITH GI EARTH WIRE INCLUSIVE OF ALL MATERIAL, LABOUR ETC. COMPLETE	Per Point	70.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. D	4	SUPPLYING & FIXING <b>WALL MOUNTING TYPE LIGHTING PANELS</b> , EACH WITH : (1) INCOMING MCB TPN -32 AMPS - 1NO. (2) RCCB DP 32 AMPS - 3NOS (3) MCB SP 6AMPS - 30 NOS. ALL MCBS AND RCCBS SHALL BE OF MDS / INDO KOPP MAKE. LIGHTING PANEL SHALL BE SIEMENS/MDS/INDO KOPP MAKE WITH INTERNAL BUSBARS, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS & WIRING FROM MAIN DB.	Sets.	2.00			
Sec. D	5	PROVIDING EARTH PITS WITH 2" DIA., 2.5 MTR. LONG GI PIPES WITH FLANGE AND 8 SWG GI WIRE WITH CHARCOAL, SALT AND AS PER IS 3043. RATE SHALL BE INCLUSIVE OF ALL MATERIAL, LABOUR ETC. COMPLETE. A BRICK WALL CHAMBER WITH CI COVER FOR ALL EARTH PITS SHALL BE PROVIDED.	NOS.	2.00			
Sec. D		<b>TOTAL VALUE OF SECTION-D IN Rs.</b>					
<b><u>BHEL:PSWR:NAGPUR</u></b>							
<b><u>RATE SCHEDULE, SECTION - E</u></b>							
<b><u>CONSTRUCTION OF 2 No. - STRUCTURAL SHED (60 M X 15 M) AT UNIT 1OF 2x 600 MW JHABUA MADHYA PRADESH</u></b>							
Sec	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.		RATE	AMOUNT
Sec.E	1(A)	EARTH WORK EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH IN <b>ALL KINDS OF SOIL (EXCEPT HARD ROCK AND SOFT ROCK) FOR FOUNDATIONS, RAMPS</b> ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	460.00			
Sec.E	1(B)	EARTH WORK EXCAVATION FROM <b>0 (ZERO) TO 2 M DEPTH FOR SOFT ROCK AND HARD ROCK</b> (BY MANUALLY OR MECHANICALLY BUT WITHOUT BLASTING) FOR <b>FOUNDATIONS, RAMPS</b> ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	120.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec.E	1(C)	EARTH WORK <b>EXCAVATION FROM 2.0M TO 4.0 M DEPTH</b> IN ALL KINDS OF SOIL ( <b>EXCEPT HARD ROCK AND SOFT ROCK</b> ) FOR <b>FOUNDATIONS</b> ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	20.00			
Sec.E	1(D)	EXCAVATION IN ALL KINDS OF SOIL <b>INCLUDING SOFT &amp; HARD ROCK</b> ((BY MANUAL CHISELING OR BY MECHANICAL MEANS BUT WITHOUT BLASTING) <b>FROM 2 TO 4M DEPTH</b> FOR <b>FOUNDATIONS</b> ETC WHEREVER REQUIRED INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	50.00			
Sec.E	1(E)	SUB GRADE PREPARATION: CUTTING LEVELLING,FILLING WITH EXCAVATED EARTH, WATERING AND CONSOLIDATION FOR <b>PLINTH PROTECTION AREA</b> BEFORE LAYING THE PCC WITH ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.	M2	246.00			
Sec. E	2	DISPOSAL OF EXCAVATED EARTH/ROCK ( <b>NOT SUITABLE FOR BACK FILLING</b> ) BEYOND INITIAL LEAD OF 50M AND UPTO A MAXIMUM LEAD OF 2 KM OR PART THEREOF INCLUDING LOADING, UNLOADING , TRANSPORTING AND SPREADING AS PER DIRECTION OF BHEL ENGINEER .	M3	260.00			
Sec.E	3	BACKFILLING OF FOUNDATION ,FLOORS AND PLINTH IN LAYERS NOT EXCEEDING 150MM THICK. INCLUDING WATERING AND CONSOLIDATING ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.					
Sec.E	A	WITH GOOD <b>EXCAVATED SOIL</b> AVAILABLE FROM THE EARTH WORK.	M3	320.00			
Sec. E	B	WITH GRANULAR MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 150MM ) BELOW FOUNDATIONS AND RAMP AS PER STANDARD SPECIFICATION, RELEVANT DRAWINGS AND INSTRUCTED BY BHEL ENGINEER INCLUDING ROYALTY. CONTRACTOR HAS TO SUBMIT ROYALTY CERTIFICATE FROM CONCERNED STATE GOVT. MINING DEPARTMENT	M3	80.00			
Sec. E	C	WITH <b>GOOD</b> EARTH BROUGHT FROM OUTSIDE FROM CONTRACTOR'S OWN SOURCE INCLUDING ROYALTY ETC.	M3	80.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec.E	D	PROVIDING <b>STONE SOLING</b> OF REUIRED THICKNESS AS PER DRAWING BELOW FLOORING, RAMP, COLUMN FOUNDATIONS OF STORAGE SHED ETC. BY USING 80 MM SIZE HARD BROKEN BLACK GRANITE/QUARTIZITE/GNEISS/TRAP STONE METAL INCLUDING GRANULAR MURRUM PACKING, WATERING & COMPACTION ETC COMPLETE.AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER	M3	560.00			
Sec.E	4	PROVIDING AND LAYING OF <b>100 MM THICK PLAIN CEMENT CONCRETE OF MIX 1:3:6</b> USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY WITH TROWEL FINISH FOR <b>PLINTH PROTECTION AND FLOORING</b> WITH TROWEL FINISH INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	210.00			
Sec. E	5	PROVIDING AND LAYING OF <b>PLAIN CEMENT CONCRETE OF MIX 1:4:8</b> USING OPC GRADE 43/53, 20 MM DOWN SIZE HARD BROKEN GRANITE STONE JELLY FOR FOUNDATION, COLUMN ETC. INCLUDING SHUTTERING, FINISHING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	46.00			
Sec.E	6	PROVIDING AND LAYING OF <b>RCC MIX 1:2:4</b> USING OPC GRADE 43/53, 20MM DOWN SIZE HARD BROKEN GRANITE STONE AGGREGATE INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK & CENTERING AS PER DRAWING AND SPECIFICATION AND DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS.	M3	128.00			
Sec.E	7	PROVIDING AND LAYING <b>DPC</b> (DAMP PROOF COURSE) 50MM THICK IN 1:2:4 CEMENT CONCRET LAYER USING OPC GRADE 43/53AND WITH 6MM DOWN AGGREGATE, INCLUDING FORMWRK, BITUMEN FELT USING CEMENT WITH WATER PROOFING COMPOUND ETC. COMPLETE	M2	110.00			
Sec.E	8	PROVIDING , CUTTING, BENDING AND FIXING IN POSITION <b>REINFORCEMENT OF VARIOUS DIA.</b> USING <b>HIGH TENSILE TOR STEEL (Fe -415/500 )</b> FOR FOUNDATIONS, COLUMNS, BEAMS, FLOORS, SUNSHED, SLAB ETC. AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL MATERIALS, LEADS, LIFT, LABOURS, MS BINDING WIRE 18/20 GAUGE, TACK WELDING AND SUPPORTING AS REQUIRED COMPLETE.	MT	10.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec.E	9 (A)	PROVIDING <b>BRICK WORK IN CM 1:6</b> (1 CEMENT & 6 COARSE SAND) OF ANY THICK ( 115 / 230 / 345 MM ) USING OPC GRADE 43/53 AND LOCALLY AVAILABLE BURNT CLAY BRICKS (MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, SUPER STRUCTURE, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	M3	40.00			
Sec.E	9(B)	PROVIDING <b>BRICK WORK IN CM 1:6</b> (1 CEMENT & 6 COARSE SAND) OF ANY THICK ( 115 / 230 / 345 MM ) USING OPC GRADE 43/53 AND FLY ASH LIME BRICKS (MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	M3	32.00			
Sec.E	10(A)	SUPPLY,FABRICATING, AND ERECTION OF <b>TUBULAR TRUSSES (BY USING CLASS B ,MEDIUM QUALITY PIPE)</b> AS PER BHEL DRAWING WITH <b>AC SHEETS</b> AND <b>WIND TIES (USING FLAT OF SIZE 40X5MM)</b> TO BE PROVIDED ABOVE SHEETS AND PROVIDING AND FIXING BASE PLATES WITH HOLDING DOWN BOLTS ON RCC COLUMNS, GUSSETS, RIBS, PINS, SPLICES ETC. AS REQUIRED INCLUDING TRANSPORT, LOADING, UNLOADING CHARGES FROM FABRICATION SHOP TO SITE ETC. COMPLETE. RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE.	MT	34.00			
Sec.E	10(B)	<b>MANUFACTURE, SUPPLY AND ERECTION OF STR COLUMNS (OF 4.5M HEIGHT FIXING OVER RCC PEDESTAL ) AS PER BHEL DRAWING</b> . PROVIDING AND FIXING BASE PLATES WITH HOLDING DOWN BOLTS ON RCC PEDESTALS, GUSSETS, RIBS, PINS, SPLICES ETC. AS REQUIRED. RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, TRANSPORTATION, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE. ,	MT	23.00			



SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec.E	10(C)	STRUCTURAL WORK FOR <b>AC SHEET SIDE SIDE CLADDNG</b> BY USING 65MM DIA TUBULAR SECTION OF CLASS B-MEDIUM QUALITY <b>AS PER BHEL DRAWING</b> .RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE.	MT	4.00			
Sec.E	11(A)	PROVIDING AND FIXING <b>6/7MM THICK AC CORRUGATED SHEETS</b> WITH RIDGE CAPS FOR ROOFING INCLUDING GALVANISED IRON J OR L HOOK , BOLTS, BITUMINOUS WASHERS, GI CRAMP BOLTS, NUTS,SCAFOLDING ETC. COMPLETE, ALL AS PER LATEST IS 459, 3307 AND 730.	M2	1980.00			
Sec.E	11(B)	FOR SIDE CLADDING (APPROX-1.50 M FROM TRUSS BOTTOM LEVEL)	M2	690.00			
Sec.E	12	PROVIDING AND FIXING OF <b>TRANSLUCENT RMP/FRP(FIBRE GLASS REINFORCED PLASTIC) SHEETS - 2.00</b> MM THICK OF APPROVED MAKE INCLUDING COST OF GI J ,OR L HOOKS , BOLTS, NUTS, WASHERS, BITUMEN WASHERS,SCAFOLDING ETC. COMPLETE SO AS TO MATCH WITH AC CORRUGATED SHEETS.	M2	132.00			
Sec.E	13	PROVIDING <b>PLASTERING WITH CEMENT MORTAR -1:6 (1 CEMENT &amp; 6 COARSE SAND) USING OPC GRADE 43/53</b> OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES, PARTITION WALLS ETC. AT ALL LEVELS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.					
Sec.E		(i) EXTERNAL PLASTERING - 18MM THICK	M2	1790.00			
Sec.E		(ii) INTERNAL PLASTERING -12MM THICK	M2	1620.00			
Sec.E	14(A)	PROVIDING & APPLYING <b>COLOUR WASH -THREE COATS</b> ON NEWLY PLASTERED EXTERNAL SURFACE BY USING BEST <b>SHALL LIME</b> TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, BASE COAT OF WHITE WASH,APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	M2	1790.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec.E	14(B)	PROVIDING & APPLYING <b>WHITE WASH - THREE COATS</b> ON NEWLY PLASTERED INTERNAL SURFACE BY USING BEST <b>SHALL LIME</b> TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	M2	1620.00			
Sec.E		<b>TOTAL VALUE OF SECTION-E IN Rs.</b>					
<b>BHEL:PSWR:NAGPUR</b>							
<b>RATE SCHEDULE, SECTION - F</b>							
<b>INTERNAL ELECTRIFICATION OF 2 No. - STRUCTURAL SHED (60M X 15M) AT UNIT 1OF 2x 600 MW JHABUA MADHYA PRADESH</b>							
Sec.F	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.		RATE	AMOUNT
Sec.F	1	SUPPLYING & INSTALLING POWER DISTRIBUTION BOARD COMPLETE WITH: 1) INCOMING MCB TPH 100 AMPS. - 1 NO. 2) OUTGOING MCB TPH 32 AMPS. -2NOS. 3) RCCB DP 25/20 AMPS. - 2NOS. 4) OUTGOING MCB SP 6 AMPS - 4NOS. All RCCBs, MCBs SHALL BE MDS/INDO KOPP MAKE. DISTRIBUTION BOARDS SHALL BE SIEMENS / MDS / INDO KOPP MAKE WITH INTERNAL BUSBARS, INTERNAL WIRING, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS AND LUGS.ETC.	Set	1.00			
Sec.F	2	PROVIDING & FIXING ALUMINIUM DISPERSIVE LUMINAIRE ENAMELED GREEN AND WHITE WITH CAST ALUMINIUM FLANGE AND NIPPLE SUITABLE FOR USE WITH GLS LAMP, DOME 12" DIAMETER, WITH HANGING BRACKET AND 200W GLS LAMP OF CROMPTON OR EQUIVALENT BAJAJ / PHILIPS MAKE, COMPLETE.	Nos.	70.00			
Sec.F	3	<b>WIRING WITH 2.5 SQ MM</b> ISI MARK COPPER WIRE FOR ABOVE IN PVC CONDUIT ALONG WITH GI EARTH WIRE INCLUSIVE OF ALL MATERIAL, LABOUR ETC. COMPLETE	Per Point	70.00			
Sec.F	4	SUPPLYING & FIXING <b>WALL MOUNTING TYPE LIGHTING PANELS</b> , EACH WITH : (1) INCOMING MCB TPN -32 AMPS - 1NO. (2) RCCB DP 32 AMPS - 2NOS (3) MCB SP 6AMPS - 20 NOS. ALL MCBS AND RCCBS SHALL BE OF MDS / INDO KOPP MAKE LIGHTING PANEL SHALL BE SIEMENS/MDS/INDO KOPP MAKE WITH INTERNAL BUSBARS, 2 NOS. EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS & WIRING FROM MAIN DB.	Sets.	2.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec.F	5	PROVIDING EARTH PITS WITH 2" DIA., 2.5 MTR. LONG GI PIPES WITH FLANGE AND 8 SWG GI WIRE WITH CHARCOAL, SALT AND AS PER IS 3043. RATE SHALL BE INCLUSIVE OF ALL MATERIAL, LABOUR ETC. COMPLETE. A BRICK WALL CHAMBER WITH CI COVER FOR ALL EARTH PITS SHALL BE PROVIDED.	NOS.	2.00			
Sec.F		TOTAL VALUE OF SECTION- F IN Rs.					
BHEL:PSWR:NAGPUR							
RATE SCHEDULE, SECTION - G							
NAME OF WORK: DEVELOPMENT OF OPEN STORAGE YARD OF AREA 2,00,000sqm. WITH INTERNAL ROADS, DRAINAGE, FENCING WORKS AT UNIT 1 OF 2x 600 MW JHABUA, MADHYA PRADESH							
SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.		RATE	AMOUNT
Sec. G	1	EXCAVATION FOR ROADWAY IN ALL TYPES OF SOILS, SAND AND GRAVEL OR SOFT MURAM INCLUDING DRESSING OF SECTION TO THE REQUIRED GRADE, CAMBER & SIDE SLOPES AND SPREADING OF SURPLUS EXCAVATED EARTH UNIFORMLY OVER THE SPECIFIED AREA FOR SITE LEVELING & DEVELOPMENT OF REQUIRED DEPTH TO MAINTAIN UNIFORM GROUND LEVEL AS DIRECTED BY THE BHEL & CONSOLIDATION OF THE SURFACE INCLUDING SUB- BASE BY ROLLING THE SURFACE WITH 8 - 10 MT CAPACITY POWER ROLLER,DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.AS PER DRAWINGS & SPECIFICATIONS.	M3	25150.00			
Sec. G	2	EXCAVATION FOR SIDE DRAIN/DRAINS AND CULVERTS IN ALL KINDS OF SOILS, TO THE SPECIFIED SECTION AS PER DRAWINGS & SPECIFICATIONS. INCLUDING SPREADING OF SURPLUS EXCAVATED EARTH UNIFORMLY OVER THE SPECIFIED AREA FOR SITE LEVELING & DEVELOPMENT OF REQUIRED DEPTH TO MAINTAIN UNIFORM GROUND LEVEL, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE. DIRECTED BY THE BHEL ENGINEER.					
Sec. G	a	IN ORDINARY SOIL	M3	4000.00			
Sec. G	b	IN SOFT/HARD ROCK	M3	600.00			
Sec. G	3	BACK FILLING THE SIDES OF DRAINS,CULVERTS WITH GOOD EXCAVATED SOIL AVAILABLE FROM WORK IN LAYERS NOT EXCEEDING 15 CM THICKNESS INCLUDING WATERING AND CONSOLIDATING ETC. COMPLETE AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.	M3	745.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. G	4	DISPOSAL OF EXCAVATED EARTH/ROCK ( <b>NOT SUITABLE FOR BACK FILLING</b> ) UPTO A MAXIMUM LEAD OF 2 KM OR PART THEREOF INCLUDING LOADING,UNLOADING ,CONVEYING AND SPREADING AS PER DIRECTION OF ENGINEER INCHARGE.AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.	M3	4670.00			
Sec. G	5	PROVIDING & FILLING OF <b>300MM COMPACTED THICK GRANULAR MURUM IN LAYERS (THICKNESS OF EACH LAYER SHOULD NOT EXCEED 150MM )</b> IN SUB-BASE OF ROAD BELOW SOLING, WATERING AND COMPACTION WITH 8-10 T POWER ROLLER COMPLETE. RATE SHALL INCLUDE TRANSPORTATION, ROYALTY, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE ETC.	M3	11430.00			
Sec. G	6	PROVIDING AND LAYING SOLING 230 MM COMPACTED THIK WITH 150 -200 MM THICK BOULDER SIZE AND FILLING OF VOIDS WITH HAND BROKEN METAL OF SIZE 40-60 MM , SPREADING & PACKING MURRUM , ROLLING AND COMPACTION INCLUDING WATERING, WITH 8 - 10 MT CAPACITY ROAD ROLLER.	M3	8765.00			
Sec. G	7	PROVIDING <b>150 MM COMPACTED THICK WATER BOUND MACADAM (WBM) IN TWO LAYERS OF EACH 75 MM,</b> WITH 40MM TO 60MM METAL (STONE AGGREGATE) INCLUDING SUPPLYING AND SPREADING GRAVEL/MURRUM OVER THE SOLING/CONSOLIDATED BASE, COMPACTION THE SAME WITH POWER ROLLER INCLUDING NECESSARY LABOUR, WATERING, MATERINGS ETC. COMPLETE, ALL AS PER RELEVANT SPECIFICATIONS AND DIRECTIONS OF BHEL ENGINEER (RATE SHALL BE INCLUSIVE OF ALL LABOUR, MATERIALS ETC., COMPLETE).	M3	5715.00			
Sec. G	8	PROVIDING AND LAYING OF <b>PLAIN CEMENT CONCRETE OF MIX 1:4:8</b> USING 40MM & DOWN SIZE HARD BROKEN GRANITE STONE JELLY FOR DRAINS,CULVERTS ETC. INCLUDING SHUTTERING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	525.00			
Sec. G	9	PROVIDING AND LAYING OF <b>RCC OF MIX 1:2:4 USING 20MM DOWN SIZE</b> HARD BROKEN GRANITE STONE AGGREGATE FOR RCC SLAB OF CULVERT, RCC COPING OVER BRICK WALL OF DRAIN INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK AND CENTERING AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER	M3	130.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. G	10	PROVIDING AND FIXING OF <b>REINFORCEMENT</b> INCLUDING CUTTING, BENDING AND FABRICATION OF REINFORCEMENT USING HIGH TENSILE TOR STEEL ( <b>Fe-415</b> ) AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL LEADS, LIFT AND MATERIALS, LABOUR AND MS BINDING WIRE 18/20 GAUGE ETC. COMPLETE.	MT	13.00			
Sec. G	11	PROVIDING <b>BRICK WORK IN CM 1:6</b> (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND LOCALLY AVAILABLE BURNT CLAY BRICKS (MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, SUPER STRUCTURE, SEPTIC TANK ETC. INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING , AT ALL ELEVATIONS AND LEVELS , RAKING OUT JOINTS ETC. COMPLETE AND AS DIRECTED BY ENGINEER . EXCLUDING PLASTERING & PAINTING.	M3	1310.00			
Sec. G	12	PROVIDING AND <b>PLASTERING WITH CEMENT MORTAR 1:6 (12MM THICK)</b> OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES ETC. OF ALL HEIGHTS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.	M2	7785.00			
Sec. G	13	40MM THICK <b>COPING</b> OVER THE DRAIN WALL TOP USING <b>MIX - 1:2:4</b>	M3	80.00			
Sec. G	14	PROVIDING <b>3 MM THICK NEAT CEMENT FINISH</b> OVER CONCRETE BASE FOR FLOORING PAVING AND INTERNAL SURFACE OF BRICK DRAINS ETC.	M2	7785.00			
Sec. G	15	PROVIDING & FIXING OF <b>WEEP HOLES</b> WITH 75MM DIA. AC PIPES AT 3M C/C ON BOTH SIDES OF DRAIN WALL WITH FILTER MEDIA USING 40MM SIZE STONE GRIT OF SIZE (300X300X300MM).	RM	1000.00			
Sec. G	16	SUPPLYING & FIXING IN POSITION OF <b>RCC HUME PIPE OF NP2</b> WHEREVER DRAIN CROSSES THE ROADS INCLUDING ALIGNING,LEVELLING ETC. COMPLETE AS PER THE DIRECTION OF ENGINEER. INCLUDING P.C. & INCLUDING COLLAR JOINTS, ENCASEMENT WITH CONCRETE 1:3:6 OF 300 MM DIA , ENCASING SHALL BE PAID EXTRA UNDER RESPECTIVE ITEMS OF CONCRETE..					
Sec. G	A	400mm dia	RM	230.00			
Sec. G	B	600mm dia	RM	55.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. G	17	SUB GRADE PREPARATION: CUTTING & DISPOSAL OF GRASS, LEVELLING, WATERING AND ROLLING WITH 10-12 MT CAPACITY ROLLER FOR SUB BASE PREPARATION BY AVERAGE OF $\pm$ 250MM THICK CUTTING & FILLING OF FOLLOWING THICK AVAILABLE EARTH WITH ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.FOR OPEN STORAGE YARD.	M2	200000.00			
Sec. G	18	PROVIDING AND FIXING <b>BARBED WIRE FENCING</b> AROUND OPEN STORAGE YARD <b>AS PER BHEL DRAWING</b> . POSTS SHALL BE SPACED AT <b>3M CENTRES AND STRUTS AT 30M CENTRES</b> AND AT ALL TURNINGS WITH FOUNDATIONS,SUPPLYING AND FIXING GI BARBED WIRES, 10 HORIZONTAL LINES, TWO DIAGONALS BETWEEN POSTS BY MEANS OF GI STAPLES AS PER STANDARD PRACTICE. THE BARBED WIRE SHALL CONFORM TO IS 278 AND BE MADE OF TWO STRANDS OF GALVANISED TWISTED 2.5MM DIA (12.5 GAUGE) STEEL WIRE WITH FOUR POINT BARS. RATE QUOTED SHALL BE INCLUSIVE OF EXCAVATION, DISPOSAL OF SURPLUS EARTH, CONCRETE (1:3:6), FORM WORK AND ALL MATERIALS, COST OF POSTS, BARBED WIRES, TRANSPORTING, FIXING IN POSITION ETC. INCLUDING COST OF ALL LABOUR AND TWO COATS OF ENAMEL PAINT OF APPROVED SHADE WITH A SHOP COAT OF PRIMER IN ALL STRUCTURAL MEMBERS ETC COMPLETE.	RM	2615.00			
Sec. G	19	<b>REMOVAL OF WILD GROWTH</b> , BUSHES VEGITATIONS AND DISPOSAL AS PER INSTRUCTION WITHIN THE PLANT BOUNDARY <b>(SIZE OF STEM FROM 150MM TO 600MM DIA. )</b>	NOS	250.00			
Sec. G	20	SUPPLY FABRICATION, AND FIXING IN POSITION OF <b>MS GATES</b> WITH STRUCTURAL/TUBULAR STEEL FRAMES AS PER BHEL DRAWING INCLUDING COST OF FOUNDATION & POSTS, PAINTING TWO COATS BY SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER, COST OF ALL MATERIALS, LABOUR, TRANSPORT ETC. COMPLETE.	MT	3.00			
Sec. G		<b>TOTAL OF SECTION-G IN RS</b>					

BHEL : PS WR  
**TS NO : BHE/PW/PUR/BRLT-ENB/640**  
**PRICE BID-PART-II ( RATE SCHEDULE )**

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
<b>BHEL:PSWR:NAGPUR</b>							
<b>RATE SCHEDULE, SECTION - H</b>							
<b>NAME OF WORK- EXTERNAL ILLUMINATION OF OPEN STORAGE YARD AT UNIT 1OF 2x 600 MW JHABUA MADHYA PRADESH</b>							
Sec	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.		RATE	AMOUNT
Sec. H	1	SUPPLYING, INSTALLATION & COMMISSIONING OF <b>SODIUM VAPOUR LAMP STREET LIGHT FITTING 150 WATT</b> SSG-2315 IH OF CROMPTON OR SIMILAR PHILIPS MAKE, COMPLETE WITH ONE PIECE CANOPY, INTEGRAL CONTROLGEAR COMPRISING OF COPPER WOUND CHOKE , IGNITOR , HPF CAPACITOR, HPSV LAMP AND SUITABLE FOR DIRECTLY SLIPPING OVER LIGHT MOUNTING BRACKET MADE OUT OF 40 MM OD PIPE AND SUITABLE FOR LAMPS, CONTROL GEAR BOX CABLING & TERMINATION OF ITEMS SUPPLIED (TO BE MOUNTED ON 9 MTR POLE - ITEM NO. 2).	NOS.	100.00			
Sec. H	2	SUPPLY AND ERECTING <b>STEEL TUBULAR SWAGED POLES, 9 MTR</b> LONG MADE OF SHEET STEEL HAVING ULTIMATE TENSILE STRENGTH 42 KG F/SQ.MM CONFIRMING TO BIS :2713 (RPART-II) COMPLETE WITH 300X300X6 MM THICK M. S. BASE PLATE FOR WELDING AT SITE AND SIZE AS PER CONFIGURATION GIVEN IN BIS FOR 410 SP-28 (113 KG- POLE WEIGHT ) WITH 1.5 MTR. DEEP EXACAVATION, CONCRETING IN 1:4:8 RATIO SIZE 45 CMS X 45 CMS X 150 CMS AND POLE PLINTH IN 1:3:6 CEMENT CONCRETING HAVING 300 MM HEIGHT AND 300 MM DIA .INCLUDING DOUBLE EARTHING OF POLE WITH SUITABLE ARRANGEMENT, DULY PAINTED WITH TWO COATS OF RED OXIDE PAINT AND ONE COAT OF ALUMINIUM PAINT TO BE APPLIED AFTER ERECTION; THE LENGTH OF POLE BELOW GROUND TO BE PAINTED WITH TWO COATS OF BLACK BITUMINUS PAINT. THE POLE SHALL BE COMPLETE WITH JB, FUSE AND MINOR FABRICATION AS BELOW : <b>I) DRILING 20 MM DIA HOLE AT ABOUT 2.5 MTR FROM GROUND LEVEL FOR WIRE LEADS FROM JUNCTION BOX TO LIGHT FIXTURE .</b> <b>II) DRILING 15MM DIA HOLES AT ABOUT 0.7 AND AT 2.5 MTR FROOM GROUND LEVEL AND WELDING 12 MM NUTS FOR USING A 12 MM G.I BOLT FOR FASTENING EARTH CONDUCTERS.</b> <b>III) WELDING REQUIORED HOLES FOR FIXING POLE CAP OF STREET LIGHT BRACKET.</b> <b>AND WELDING DIAMETRICALLY 40 MM M.C. BOUND 20 MM BELOW POLE TOP EDGE FOR CLIPPING WIRE LEADS .</b>	NOS.	100			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. H	3	SUPPLY OF <b>WEATHER PROOF FLOOD LIGHT LUMINIARIES</b> OF CROMPTON MAKE (FBD 1425/40-WITH HIGH PRESSURE SODIUM VAPOUR LAMP 1X 400 WATT ALONG WITH NON- INTEGRAL TYPE CONTROL GEAR BOX HAVING ADEQUATE NUMBER OF TERMINAL CONNECTORS FOR TERMINATING TWO CABLE OF 3X 10 SQMM AL AND SUITABLE FOR OUT DOOR APPLICATION ) OR EQUIVALENT IN BAJAJ, PHILLIPS ONLY , INCLUDING SUPPLY & FIXING CABLES BETWEEN THE CONTROL GEAR BOX AND LIGHT LUMINIARIES AND MOUNTING FIXTURE WITH HARDWARE FOR MOUNTING OF LIGHT LUMINIARIES AND CONTROL GEAR BOX ON POLE TYPE 410 SP-28.	NOS.	25.00			
Sec. H	4	INSTALLATION & COMMISSIONING OF <b>FLOOD LIGHT LUMINIARIES</b> , CONTROL GEAR BOX , CABLING & TERMINATION FOR SR.NO.01 (ITEMS SUPPLIED ABOVE)	NOS.	25.00			
Sec. H	5	ENGINEERING , SUPPLY AND INSTALLATION OF <b>LATTICE TYPE STRUCTURAL TOWER OF HEIGHT 15M</b> .TOWER SHALL BE FABRICATED IN THREE SECTION OF EQUAL LENGHT OF 5 METER EACH.PREPARATION OF FABRICATION DRAWING & ITS APPROVAL FROM BHEL. BRIEF DETAILS ARE AS GIVEN BELOW. TOWER SHALL BE ADEQUATELY STRONG TO WITHSTAND HEAVY WIND . NO STAY/GUY ROPES SHALL BE TIED WITH IT. AT TOP OF THE TOWER ADEQUATE SIZE OF PLATEFORM SHALL BE PROVIDED WITH RAILING AROUND THE PLATFORM FOR MOUNTING OF LIGHTING LUMINIARIES( TENTATIVELY TWEVEL FITTING ON EACH TOWER) AND MAITENANCE PURPOSE , FLOOR OF PLATFORM SHALL BE COVERED WITH CHEQURED PLATE. A LADDER ALONG WITH PROTECTIVE CAGE SHALL BE PROVIDED ALONG THE HEIGHT OF TOWER. IT SHOULD BE PAINTED WITH ONE COAT RED OXIDE PRIMER AND TWO COATS OF ALUMINIUM PAINT AFTER INSTALLATION. EACH TOWER SHALL BE PROVIDED WITH POWER DISTRIBUTION BOX OUT DOOR TYPE AND SHOULD HAVE PROVISION OF TERMINATING ONE NUMBER INCOMING AND EIGHT OUT GOING CABLE .ERECTING AT SITE INCLUDING ALL CIVIL WORKS LIKE EXCAVATION, CASTING OF FOUNDATION OF REQUIRED SIZE AND DEPTH WITH CONCRETE OF GRADE 1:2:4  WITH BASE PLATES, GROUTING OF LATTICE STRUCTURE, ONE EARTH PIT AS PER BIS STANDARD IS TO BE MADE NEAR THE TOWER AND EARTHING OF THE TOWER INCLUDING SUPPLY OF MATERIAL ETC. COMPLETE.	NOS.	8.00			



SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. H	6	SUPPLY, OF <b>FLOOD LIGHT LUMINIARIES</b> OF BAJAJ MAKE TYPE BGENF 22 OR EQUIVALENT IN CROMPTON , PHILLIPS ONLY, EACH LUMINIARIES SHALL BE WITH TWO NUMBER 400 WATT HPSV LAMPS AND CONTROL GEAR BOX INTEGRAL/ NON ITEGRAL TYPE INCLUDING CABLES FOR INTERCONNECTION . (THESE FITTING SHALL BE MOUNTED ON LIGHTING MAST /TOWER , ON EACH TOWER 8 SUCH FITTING SHALL BE MOUNTED).	NOS.	64.00			
Sec. H	7	SUPPLY OF <b>CABLES 3-1/2 CORE X 95 SQMM ALUMINIUM</b> ARMOURED PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 ( PART -I) (TO BE USED FORM SHEDS AS WELL AS OPEN STORAGE YARD WHEREVER REQUIRED)	M	2000.00			
Sec. H	8	INSTALLATION OF <b>CABLES 3 -1/2 CORE X 95 SQMM ALUMINIUM ARMOURED</b> PVC INSULATED CABLE CONFIRMING TO IS 1554 ( PART - I) INCLUDING LAYING OF CABLE BELOW GROUND, EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC COMPLETE. CABLES ARE TO BE LAID FROM 415 VOLT AC DISTRIBUTION BOARD TO FEEDER PILLAR BOARD , FEEDER PILLAR BOARD TO LIGHTING MAST / TOWER & FOR SHEDS .	M	2000.00			
Sec. H	9	SUPPLY OF <b>CABLES 2 CORE X 10 SQMM ALUMINIUM ARMOURED</b> PVC INSULATED CABLE CONFIRMING TO IS 1554 ( PART -I)	M	5000.00			
Sec. H	10	INSTALLATION OF <b>CABLES 2 CORE X 10 SQMM ALUMINIUM ARMOURED</b> PVC INSULATED CABLE CONFIRMING TO IS 1554 ( PART - I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC COMPLETE. CABLES ARE TO BE LAID FROM 415 VOLT AC POWER FEEDER PILLAR BOARD BOARD TO LIGHTING POLES & POLE TO POLE	M	5000.00			
Sec. H	11	SUPPLY OF <b>CABLES 3 -1/2 COREX 185 SQMM ALUMINIUM ARMOURED</b> PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 ( PART -I)	M	1000.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. H	12	INSTALLATION OF <b>CABLES 3 -1/2 COREX 185 SQMM ALUMINIUM ARMoured</b> PVC INSULATED CABLE CONFIRMING TO IS 1554 ( PART - I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC. CABLES ARE TO BE LAID FROM TRANSFORMER SUB STATION TO 415 VOLT AC DISTRIBUTION BOARD.	M	1000.00			
Sec. H	13	SUPPLY OF <b>CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured</b> PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 ( PART -I)	M	2500.00			
Sec. H	14	INSTALLATION OF <b>CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured</b> PVC INSULATED CABLE CONFIRMING TO IS 1554 ( PART - I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC. CABLES ARE TO BE LAID FROM TRANSFORMER SUB STATION TO 415 VOLT AC DISTRIBUTION BOARD TO STORE YARD & SHEDS	M	2500.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. H	15	<p>SUPPLY &amp; INSTALLING <b>3 PHASE METERING AND POWER DISTRIBUTION BOARD</b> COMPLETE WITH.</p> <p>(1) INCOMING SFU TPN 400 AMPS- 1NO, (2) OUTGOING SFU TPN 200 AMPS -2NOS. (3) OUTGOING SFU TPN 100 AMPS -2NOS. (4) OUTGOING SFU TPN 32 AMPS -2NOS. 3 PHASE ELECTRONIC ENERGY METER - BHEL / L&amp;T / GEC MAKE.</p> <p>AMMETER, VOLTMETER AND SELECTOR SWITCHES FOR BOTH - AE AND KAYCEE MAKE.</p> <p>PHASE INDICATION LAMPS, HRC FUSES FOR IC AND OG FEEDERS, CABLE GLANDS, POWER TERMINALS FOR CABLES TERMINATION, CABLE LUGS AND PROVISION FOR DOUBLY EARTHING THE PANEL ENCLOSURE.</p> <p>PANEL ENCLOSURE SHALL BE MADE OF SHEET METAL THICHNNES NOT LESS THAN 1.6 MM AND SUITABLE FOR OUT DOOR INSTALLATION, MODULAR CONSTRUCTION, HINGED DOOR WITH LOCKING ARRANGEMENT, BASE FRAME, SHOULD HAVE SLOPPED CANOPY, DULY PAINTED WITH FIRST COAT OF PRIMER AND TWO COATS OF SYNTHETIC ENAMEL PAINT (INTERIOR WITH WHITE PAINT AND EXTERIOR WITH LIGHT GREY AS PER SHADE 5, IS 630) INTERNAL POWER DISTRIBUTION TO DEVICES SHALL BE WITH AL BUSBARS OR COPPER FLEXIBLE SINGLE CORE PVC CABLES OF 1.1 KV GRADE, CONTROL WIRING WITH 1.5 SQMM, SUITABLE STOOL MADE OUT OF MS STRUCTURE OF 1.2 METER HIGH FOR MOUNTING OF PANEL WITH ANCHORING ARRAGEMENT. AT FOUNDATION, SUITABLE FOR BOTTOM ENTRY OF CABLES.</p>	NO	2.00			
Sec. H	16	<p>PROVIDING <b>SUITABLE FOUNDATION FOR MOUNTING AC DISTRIBUTION BOARD</b> AS SPECIFIED IN SL. NO.15 , INSTALLATION &amp; COMMISSIONING OF PANEL</p>	NO	2.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. H	17	SUPPLY OF <b>415 VOLT AC , 3 PHASE /FOUR WIRE POWER FEEDER PILLAR BOARD</b> , BOARD SHALL BE COMPRISES OF THREE NUMBER AND ONE NUMBER ALUMINIUM BUS BAR FOR PHASE & NEUTRAL RESPECTIVELY. BUS BAR RATING SHALL BE 200 AMPS AND SHALL BE MOUNTED ON EPOXY INSULATOR OF 1.1 KV GRADE, EACH BUS BAR SHALL HAVE DRILLED HOLE FOR CONNECTING INCOMING / OUT GOING CABLES, PROVISION FOR EARTHING THE PANEL ENCLOSURE. PANEL ENCLOSURE SHALL BE MADE OF SHEET METAL THICHNNNESS NOT LESS THAN 1.6 MM AND SUITABLE FOR OUT DOOR INSTALLATION, HINGED DOOR WITH LOCKING ARRAGEMENT , BASE FRAME , SHOULD HAVE SLOPPED CANOPY, DULY PAINTED WITH FIRST COAT WITH PRIMER AND TWO COATS OF SYNTHETIC ENAMEL PAINT ( INTERIOR WITH WHITE PAINT AND EXTERIOR WITH SMOKE GREY AS PER IS), SUITABLE STOOL MADE OUT OF MS STRUCTURE OF 1.2 METER HIGH FOR MOUNTING OF PANEL WITH ANCHORING ARRAGEMENT AT FOUNDATION .	NO	3.00			
Sec. H	18	PROVIDING <b>SUITABLE FOUNDATION FOR MOUNTING 415 VOLT AC POWER FEEDER PILLAR BOARD</b> AS SPECIFIED IN SL. NO.12 , INSTALLATION & COMMISSIONING OF OF PANEL	NO	3.00			
		<b>TOTAL VALUE OF SECTION-H IN Rs.</b>					
		<b>BHEL : PSWR : NAGPUR</b>					
		<b>RATE SCHEDULE, SECTION - I</b>					
		<b>NAME OF WORK- CIVIL WORKS FOR PORTABLE OFFICE &amp; TOILET BLOCK AT UNIT 1OF 2x 600 MW JHABUA MADHYA PRADESH</b>					
Sec	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.		RATE	AMOUNT
Sec. I	1(A)	EARTH WORK <b>EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH</b> IN ALL KINDS OF SOIL (EXCEPT HARD ROCK AND SOFT ROCK) FOR <b>SEPTIC TANK, SOAK PIT, PLACING BRICK PEDESTAL( OF SIZE 460 MM X 460 MM)</b> ETC., SPREADING THE EARTH UNIFORMLY AROUND THE <b>PORTA CABIN OFFICE ,SEPTIC TANK</b> ETC. AS DIRECTED BY BHEL ENGINEER AND INCLUDING DISPOSAL OF SURPLUS EARTH (IF ANY) , DEWATERING WITH ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.	M3	150.00			
Sec. I	1(B)	EARTH WORK <b>EXCAVATION FROM 0 (ZERO) TO 2 M DEPTH</b> IN ALL KINDS OF SOIL INCLUDING SOFT ROCK AND HARD ROCK ( MANUALLY OR MECHANICALLY WITHOUT BLASTING) FOR <b>SEPTIC TANK, SOAK PIT</b> ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING , ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.	M3	30.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. I	1(C)	EARTH WORK <b>EXCAVATION FROM 2.0M TO 4.0 M DEPTH</b> IN ALL KINDS OF SOIL ( <b>EXCEPT HARD ROCK AND SOFT ROCK</b> ) FOR <b>SEPTIC TANK, SOAK PIT</b> ETC., AS DIRECTED BY BHEL ENGINEER INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	20.00			
Sec. I	1(D)	EXCAVATION IN ALL KINDS OF SOIL <b>INCLUDING SOFT &amp; HARD ROCK</b> ((BY MANUAL CHISELING OR BY MECHANICAL MEANS BUT WITHOUT BLASTING) <b>FROM 2 TO 4M DEPTH</b> FOR <b>SEPTIC TANK AND SOAK PIT</b> , WHEREVER REQUIRED INCLUDING REMOVING THE EXCAVATED MATERIALS UP TO A DISTANCE OF 50M, DEWATERING (BOTH GROUND WATER AS WELL AS RAIN WATER) AND KEEP THE AREA DRY TILL COMPLETION OF ALL THE WORKS, LABOURS, MATERIALS AND REQUIRED T&Ps ETC. COMPLETE.	M3	20.00			
Sec. I	1(E)	<b>SUB GRADE PREPARATION:</b> CUTTING & DISPOSAL OF GRASS, BUSHES , LEVELLING, WATERING AND COMPACTION BY ROLLING WITH 10-12 MT CAPACITY ROLLER FOR SUB BASE PREPARATION BY AVERAGE CUTTING & FILLING OF 200MM THICK AVAILABLE EARTH WITH ALL T&P, LABOURS, MATERIALS ETC. COMPLETE.FOR	M2	2200.00			
Sec. I	2	<b>BACK FILLING INSIDE THE RAISED PLATFROM FOR PLACING PORTA CABINS</b>					
Sec. I	2(A)	WITH <b>EXCAVATED SOIL</b> AVAILABLE AT SITE	M3	140.00			
	2(B)	WITH <b>GOOD EARTH</b> BROUGHT FROM OUTSIDE FROM CONTRACTOR'S OWN SOURCE INCLUDING ROYALTY ETC.	M3	60.00			
Sec. I	2(C)	PROVIDING & FILLING IN <b>SOAK PIT WITH BRICK BATS 40-80MM</b> INCLUDING SAND PACKING ETC. COMPLETE, AS PER STANDARD SPECIFICATION AND INSTRUCTED BY BHEL ENGINEER.	M3	14.00			
Sec. I	3	PROVIDING AND LAYING OF <b>PLAIN CEMENT CONCRETE OF MIX 1:4:8</b> USING 40MM & DOWN SIZE HARD BROKEN GRANITE STONE JELLY FOR <b>BASE OF BRICK PEDESTAL( OF SIZE 460 MM X 460 MM) , FOOT PATH</b> (REF. DRAWING) ETC. INCLUDING SHUTTERING, CURING, CONSOLIDATION ETC. COMPLETE AS PER STANDARD SPECIFICATIONS AND AS DIRECTED BY BHEL ENGINEER.	M3	66.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. I	4	PROVIDING AND LAYING CONCRETE OF <b>MIX 1:3:6 USING 20MM DOWN SIZE</b> HARD BROKEN GRANITE STONE AGGREGATE FOR <b>BACK SIDE AND BETWEEN THE PORTA CABINS ETC AND WHEREVER REQUIRED.</b> INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK AND CENTERING AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS FOR FLOORING.	M3	12.00			
Sec. I	5	PROVIDING AND LAYING CONCRETE OF <b>MIX 1:2:4 USING 20MM DOWN SIZE</b> HARD BROKEN GRANITE STONE AGGREGATE FOR <b>RAISED PLATFORM / FOOTPATH,COPING OVER BRICK PEDESTAL ETC.</b> INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK AND CENTERING AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS FOR FLOORING.	M3	19.00			
Sec. I	6	PROVIDING AND LAYING CONCRETE OF <b>MIX 1:2:4 USING 20MM DOWN SIZE</b> HARD BROKEN GRANITE STONE AGGREGATE FOR <b>SEPTIC TANK ETC</b> INCLUDING MECHANICAL MIXING, VIBRATION, CURING, FORM WORK AND CENTERING AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER BUT EXCLUDING COST OF REINFORCEMENTS FOR FLOORING.	M3	8.00			
Sec. I	7	PROVIDING AND FIXING OF <b>REINFORCEMENT</b> INCLUDING CUTTING, BENDING AND FABRICATION OF REINFORCEMENT USING HIGH TENSILE TOR STEEL (Fe-415) AS PER DRAWING AND SPECIFICATION AND AS DIRECTED BY BHEL ENGINEER INCLUDING COST OF ALL LEADS, LIFT AND MATERIALS, LABOUR AND MS BINDING WIRE 18/20 GAUGE ETC. COMPLETE.	MT	0.75			
Sec. I	8	PROVIDING <b>BRICK WORK IN CM 1:6</b> (1 CEMENT & 6 COARSE SAND) USING OPC GRADE 43/53 AND <b>FLY ASH LIME BRICKS / BURNT CLAY BRICK</b> ( MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING FOR <b>KERB OF RAISED PLATEFORM/FOOTPATH, BRICK PEDESTAL, ETC.</b> INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, CURING ETC. COMPLETE AND AS DIRECTED BY ENGINEER AT ALL ELEVATIONS AND LEVELS INCLUDING RAKING OUT JOINTS, CURING ETC. COMPLETE EXCLUDING PLASTERING .	M3	145.00			
Sec. I	9	PROVIDING <b>HALF BRICK WORK IN CM 1:4</b> (1 CEMENT & 4 COARSE SAND) USING OPC GRADE 43/53 AND <b>FLY ASH LIME BRICKS/BURNT CLAY BRICK</b> ( MIN STRENGTH 35 KG/CM <sup>2</sup> ) AS PER DRAWING AND SPECIFICATION FOR FOUNDATION, WALL ETC INCLUDING COST OF ALL MATERIALS, LABOUR, SCAFFOLDING, RAKING OUT JOINTS,CURING <b>AS PER DRAWING</b> AND DIRECTED BY BHEL ENGINEER.	M2	50.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. I	10	PROVIDING <b>PLASTERING WITH CEMENT MORTAR -1:6 (1 CEMENT &amp; 6 COARSE SAND) USING OPC GRADE 43/53</b> OVER BOTH INTERNAL AND EXTERNAL FACES OF BRICKWORK AND CONCRETE SURFACES, PARTITION WALLS ETC. AT ALL LEVELS INCLUDING PREPARING THE SURFACE, RAKING JOINTS, SCAFFOLDING, CURING, COST OF ALL MATERIALS, LABOUR ETC. COMPLETE.					
		(i) 18MM THICK	<b>M2</b>	<b>120.00</b>			
		(ii) 12MM THICK (includes plastering on top of raised palteform)	<b>M2</b>	<b>710.00</b>			
Sec. I	11	PROVIDING <b>2MM THICK NEAT CEMENT FINISH</b> OVER CONCRETE BASE AND BRICK WALL FOR SEPTIC TANK ETC.	<b>M2</b>	<b>150.00</b>			
Sec. I	12	SUPPLYING AT SITE OF WORK, TRENCHING, CARRYING TO TRENCHES AND LOWERING INTO TRENCHES AND ON WALLS, FLOORS ETC., LAYING TO PROPER ALIGNMENT, GRADE, LEVEL AND JOINTING WITH ALL NECESSARY SPECIALS, TEES, ELBOWS, UNIONS AND APPURTENANCES AND INCLUDING PRESSURE TESTING OF THE FOLLOWING SIZES OF <b>GI PIPE LINES</b> INCLUDING REFILLING OF TRENCHES WITH EXCAVATED EARTH IN LAYERS, WATERING AND RAMMING AND RESTORATION OF GROUND, ALL COMPLETE AS PER SPECIFICATIONS. RATE TO INCLUDE EARTH WORK EXCAVATION IN ALL SOILS, EXCEPT HARD ROCK REQUIRING BLASTING , SHORING, BALLING OR PUMPING OUT OF WATER WHEREVER REQUIRED, REMOVAL OF SLUSH ETC. REMOVING AND DEPOSITING SURPLUS EARTH AS DIRECTED BY THE BHEL ENGINEER INCLUDING ALL LEADS AND LIFTS AS PER SITE CONDITIONS.					
Sec. I	A	40MM DIA GI PIPE LINE WITH ALL SPECIALS (from customer point to BHEL premises as per site condition)	<b>RM</b>	<b>300.00</b>			
Sec. I	B	25MM DIA GI PIPE LINE WITH ALL SPECIALS	<b>RM</b>	<b>35.00</b>			
Sec. I	C	20MM DIA GI PIPE LINE WITH ALL SPECIALS	<b>RM</b>	<b>25.00</b>			
Sec. I	D	15MM DIA GI PIPE LINE WITH ALL SPECIALS	<b>RM</b>	<b>25.00</b>			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. I	13	SUPPLYING AT SITE OF WORK, CARRYING AND LOWERING INTO TRENCHES, LAYING TO PROPER ALIGNMENT, LEVEL AND GRADE, JOINTING WITH CM (1:1) AND TESTING OF JOINTS ETC. OF THE FOLLOWING SIZE OF SALT <b>GLAZED STONEWARE PIPE</b> INCLUSIVE OF ALL NECESSARY SPECIALS TARRED HEMP YARN AND ALL JOINTING MATERIALS COMPLETE AS PER STANDARD SPECIFICATIONS INCLUDING ALL LEAD AND LIFT AS PER SITE CONDITIONS. (RATE QUOTED SHALL INCLUDE COST OF ALL MATERIALS, LABOUR CHARGES AND INCIDENTAL CHARGES ETC. COMPLETE).					
Sec. I	A	100MM DIA STONEWARE PIPELINE INCLUDING ALL SPECIALS COMPLETE.	RM	100.00			
Sec. I	14	SUPPLY AND FIXING IN POSITION <b>PVC WATER OVERHEAD TANK OF SYNTEX OR ANY APPROVED MAKE OF REQUIRED CAPACITY</b> WITH PROVISION FOR OVERFLOW ARRANGEMENT VALVES, INLET AND OUTLET ETC. COMPLETE. SUPPORTING STRUCTURE FOR FIXING THE TANK WILL BE AS PER ITEM RATE GIVEN SEPARATELY.					
	A	1000 LIT	NO	1.00			
	B	500 LIT	NO	1.00			
Sec. I	15	CONSTRUCTION OF <b>BRICK CHAMBER</b> OF THE FOLLOWING DIMENSIONS (INNER DIMENSION) WITH CEMENT PLASTER INSIDE WITH NEAT CEMENT FINISH & TOP WITH <b>CI – COVER</b> FOR CONNECTING THE SEWER LINES. RATE SHALL BE INCLUSIVE OF ALL EXCAVATION, FILLING, PCC, B/K WORK , PLASTER, COVERS ETC. COMPLETE.					
Sec. I	A	450X450X450 WITH C.I COVER	NO	3.00			
Sec. I	B	600X600X600 WITH C.I. COVER	NO	5.00			
Sec. I	16	PROVIDING & FIXING IN POSITION <b>CI VENT PIPE OF DIA. 100MM (HT. 3M ) IN SEPTIC TANK</b>	RM	8.00			
Sec. I	17	PROVIDING AND FIXING OF <b>PRECAST 80 MM THICK RCC COVER IN M-20</b> FOR MAN HOLES OF VARIOUS SIZES WITH REINFORCEMENT OF 10 MM DIA BOTH WAY TIED WITH TACK WELDING @ 150 MM C/C WITH 2 HOOKS OF 12 MM DIA BARS ETC.COMPLETE.					
Sec. I		1) 750 x600 MM	Nos.	3.00			



SECTION	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. I	18	SUPPLY,FABRICATING, AND ERECTION OF <b>TUBULAR POST &amp; PURLINES (BY USING CLASS B ,MEDIUM QUALITY PIPE)</b> AS PER BHEL DRAWING FOR FIXING FRP SHEET/AC SHEET <b>SHEETS</b> AND <b>WIND TIES</b> TO BE PROVIDED ABOVE SHEETS AND PROVIDING AND FIXING BASE PLATES WITH HOLDING DOWN BOLTS ON RCC COLUMNS, GUSSETS, RIBS, PINS, SPLICES ETC. AS REQUIRED INCLUDING TRANSPORT, LOADING, UNLOADING CHARGES FROM FABRICATION SHOP TO SITE ETC. COMPLETE. RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE.	MT	1.75			
Sec. I	19	SUPPLY, FABRICATING, AND ERECTION OF <b>STRUCTURAL STEEL STAGING</b> (APPROX. Ht. 4.0M) FOR <b>INSTALLATION OF PVC OVER HEAD WATER TANK (OHT)</b> OF CAPACITY- 1000/500 LITRES. AS PER BHEL DRAWING . RATE IS INCLUSIVE OF ALL MATERIALS, LOADING & UNLOADING, FABRICATION, FIXING IN POSITION, LABOUR CHARGES , T&Ps AND COST OF RED OXIDE PRIMER AT FACTORY AND TWO COATS OF SYNTHETIC ENAMEL PAINTS (OVER PRIMER COAT OF RED OXIDE) OF APPROVED COLOUR AND QUALITY AT SITE.	MT	1.25			
Sec. I	20	PROVIDING AND FIXING <b>6/7MM THICK AC CORRUGATED SHEETS OVER THE LEAN TO ROOF OF TOILET/PANTRY BLOCK</b> AS PER BHEL DRAWING INCLUDING GALVANISED IRON J OR L HOOK , BOLTS, BITUMINOUS WASHERS, GI CRAMP BOLTS, NUTS,SCAFOLDING ETC. COMPLETE, ALL AS PER LATEST IS 459, 3307 AND 730.	M2	30.00			
Sec. I	21	PROVIDING AND FIXING OF <b>TRANSLUCENT RMP/FRP (FIBRE GLASS REINFORCED PLASTIC) SHEETS - 2.00 MM THICK</b> OF APPROVED MAKE OVER THE VARANDAH AS PER BHEL DRAWING INCLUDING COST OF GI J OR L HOOKS , BOLTS, NUTS, WASHERS, BITUMEN WASHERS,SCAFOLDING ETC. COMPLETE SO AS TO MATCH WITH AC CORRUGATED SHEETS FOR NATURAL LIGHTING.	M2	60.00			
Sec. I	22	PROVIDING AND FIXING OF <b>BEST QUALITY COUNTRY WOOD DOORS</b> COMPRISING OF <b>FRAME 95 X 70MM AND 38/40MM THICK FLUSH SHUTTERS OF SOLID CORE TYPE</b> USING COMMERCIAL PLY INCLUDING HOLD FASTS, WIND APPLIANCES, HANDLES, TOWER BOLTS AND ALDROPS, MORTISE OR SUITABLE LOCKS ETC. AS PER THE STANDARD PRACTICE AND APPLYING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED SHADE &COLOR OVER A COAT OF PRIMER AS DIRECTED BY BHEL ENGINEER.	M2	6.50			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. I	23	SUPPLING, MANUFACTURING AND FIXING IN POSITION OF <b>STEEL WINDOWS AND VENTILATORS</b> INCLUDING FRAMES & IRON BARRED (GUARD BAR OF SQUARE SECTION @ 100 MM C/C) AND GLAZED WITH 4MM PLAIN GLASS AS PER STANDARD SPECIFICATIONS & RELEVANT <b>IS CODE</b> AND INSTRUCTIONS OF BHEL ENGINEER. THE COST SHALL BE INCLUSIVE OF ALL ACCESSORIES FITTINGS, HOLD FASTS, PAINTING TWO COATS OF SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER ETC. COMPLETE.					
Sec. I	A	STEEL WINDOWS	<b>M2</b>	<b>2.00</b>			
Sec. I	B	STEEL LAUVERED VENTILATORS :-	<b>M2</b>	<b>1.00</b>			
Sec. I	24	PROVIDING & APPLYING <b>COLOUR WASH -THREE COATS</b> ON NEWLY PLASTERED SURFACE BY USING BEST <b>SHALE LIME</b> TO GIVE AN EVEN SHADE INCLUDING PREPARING THE SURFACE LIKE CLEANING AND BRUSHING & BROOMING OF WALLS AND IN ACCORDANCE WITH STANDARD SPECIFICATION. RATE INCLUDE COST OF ALL MATERIALS , COLOURING AGENT, BASE COAT OF WHITE WASH,APPROVED ADDESSIVE, SCAFFOLDING AT ALL LEVEL, BRUSH ETC. COMPLETE.	<b>M2</b>	<b>285.00</b>			
Sec. I	25	PROVIDING AND FIXING <b>EUROPEAN TYPE WHITE GLAZED VITREOUS CHINA</b> W.C.PAN WITH UPVC SEAT AND LID WITH CHROMIUM PLATED BRASS HINGES AND RUBBER BUFFERS INCLUDING UPVC VENT PIPE (APPROX. 2M. HT. WITH COWL)) ON THE OUTSIDE FACE OF WALL, 10 LITRE PVC LOW LEVEL FLUSHING CISTERN WITH ALL FITTINGS, PIPE AND STOP COCK, BRACKETS FOR FIXING CISTERN, 32 MM DIA. UPVC FLUSH PIPE WITH FITTINGS AND CLAMPS, 20 MM DIA. UPVC OVERFLOW PIPE, FLOAT VALVES, CUTTING AND MAKING GOOD TO THE WALLS AND FLOORS, TESTING ETC. COMPLETE. PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.	<b>NO</b>	<b>1.00</b>			
Sec. I	26	PROVIDING AND FIXING <b>WHITE GLAZED VITREOUS CHINA WASH HAND BASIN</b> OF 55 CM X 40 CM SIZE INCLUDING COLD WATER FILLER TAP, BRACKETS, STOP TAP, CHROMIUM PLATED BOTTLE TRAP AND NECESSARY PIPE CONNECTIONS INCLUDING UPVC WASTE PIPE AND TRAP UPTO THE OUT SIDE FACE OF THE WALL, MAKING GOOD THE DAMAGED SURFACE, TESTING ETC. COMPLETE. PRIOR APPROVAL OF SAMPLE AND BRAND BY BHEL ENGINEER IS NECESSARY BEFORE USE.	<b>NO</b>	<b>1.00</b>			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. I	27	PROVIDING AND FIXING OF 1 No. <b>18"X24" SIZE STAINLESS STEEL SINK</b> WITH ALL FITTINGS LIKE DRAIN PIPE, STOP VALVE ETC.RATE TO INCLUDE ALL NECESSARY FITTING & FIXTURE, LABOUR ETC.AS APPROVED & DIRECTED BY BHEL ENGINEER.	NOS.	<b>1.00</b>			
Sec. I	28	PROVIDING AND FIXING IN POSITION OF <b>WHITE GLAZED EARTHENWARE</b> FLAT BACK/CORNER TYPE LIPPED FRONT <b>URINALS OF 430MM X 260MM X 350MM / 340X460X265 MM</b> OF APPROVED MAKE AND QUALITY WITHOUT FLUSHING CISTERN, GI FLUSH PIPE AND SPREADERS WITH BRASS UNIONS, GI CLAMPS, CUTTING OF WALLS AND MAKING GOOD OF ALL DAMAGES AND FINISHING TO MATCH THE EXISTING WORK ETC. COMPLETE. RATE QUOTED SHALL INCLUDE COST OF ALL MATERIALS AND LABOUR FOR CARRYING, LAYING & FIXING AND ALL OTHER INCIDENTAL CHARGES ETC. COMPLETE.	NO	<b>2.00</b>			
Sec. I	29	SUPPLY FABRICATION, AND FIXING IN POSITION OF <b>MS GATES</b> WITH STRUCTURAL/TUBULAR STEEL FRAMES WITH GALVANIZED CHAIN LINK MESH OF APPROVED DESIGN INCLUDING COST OF FOUNDATION & POSTS, PAINTING TWO COATS BY SYNTHETIC ENAMEL PAINT OF APPROVED COLOUR AND QUALITY OVER ONE COAT OF RED OXIDE PRIMER, COST OF ALL MATERIALS, LABOUR, TRANSPORT ETC. COMPLETE.	MT	<b>1.00</b>			
Sec. I	30	PROVIDING AND FIXING <b>BARBED WIRE FENCING</b> AROUND OPEN STORAGE YARD AS PER BHEL DRAWING. POSTS SHALL BE SPACED AT <b>3M CENTRES AND STRUTS AT 30M CENTRES</b> AND AT ALL TURNINGS WITH FOUNDATIONS,SUPPLYING AND FIXING GI BARBED WIRES, 10 HORIZONTAL LINES, TWO DIAGONALS BETWEEN POSTS BY MEANS OF GI STAPLES AS PER STANDARD PRACTICE. THE BARBED WIRE SHALL CONFORM TO IS 278 AND BE MADE OF TWO STRANDS OF GALVANISED TWISTED 2.5MM DIA (12.5 GAUGE) STEEL WIRE WITH FOUR POINT BARS. RATE QUOTED SHALL BE INCLUSIVE OF EXCAVATION, DISPOSAL OF SURPLUS EARTH, CONCRETE (1:3:6), FORM WORK AND ALL MATERIALS, COST OF POSTS, BARBED WIRES, TRANSPORTING, FIXING IN POSITION ETC. INCLUDING COST OF ALL LABOUR AND TWO COATS OF ENAMEL PAINT OF APPROVED SHADE WITH A SHOP COAT OF PRIMER IN ALL STRUCTURAL MEMBERS ETC COMPLETE.	RM	<b>200.00</b>			
Sec. I		<b>TOTAL VALUE OF SECTION-I IN Rs.</b>					

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
		<b>BHEL:PSWR:NAGPUR</b>					
		<b>RATE SCHEDULE, SECTION - J</b>					
		<b>NAME OF WORK- EXTERNAL ELECTRIFICATION OF PORTA CABIN AT UNIT 1OF 2x 600 MW JHABUA MADHYA PRADESH</b>					
	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.		RATE	AMOUNT
Sec. J	1	SUPPLYING & INSTALLING <b>POWER DISTRIBUTION BOARD</b> COMPLETE WITH: 1) INCOMING MCB TPH 100 AMPS. - 1 NO. 2) OUTGOING MCB TPH 32 AMPS. - 1 NO. 3) RCCB DP 25/20 AMPS. - 1NO. 4) OUTGOING MCB SP 6 AMPS - 2NOS. ALL RCCBS, MCBS SHALL BE MDS/INDO KOPP MAKE. DISTRIBUTION BOARDS SHALL BE SIEMENS / MDS / INDO KOPP MAKE WITH INTERNAL BUSBARS, INTERNAL WIRING, 2 NOS - EARTHING TERMINALS, EARTH CONNECTIONS, INCLUDING GLANDS, LUGS.	Set	1.00			
Sec. J	2	PROVIDING <b>EARTH PITS WITH 2" DIA., 2.5 MTR. LONG GI PIPES</b> WITH FLANGE AND 8 SWG GI WIRE WITH CHARCOAL, SALT AND AS PER IS 3043. RATE SHALL BE INCLUSIVE OF ALL MATERIAL, LABOUR ETC. COMPLETE. A BRICK WALL CHAMBER WITH CI COVER FOR ALL EARTH PITS SHALL BE PROVIDED.	NOS.	1.00			
Sec. J	3	SUPPLY OF <b>CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured</b> PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 ( PART -I)	M	100.00			
Sec. J	4	INSTALLATION OF <b>CABLES 3 -1/2 COREX 35 SQMM ALUMINIUM ARMoured</b> PVC INSULATED CABLE CONFIRMING TO IS 1554 ( PART - I) INCLUDING LAYING OF CABLE BELOW GROUND , EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC. CABLES ARE TO BE LAID FROM TRANSFORMER SUB STATION TO 415 VOLT AC DISTRIBUTION BOARD	M	100.00			
Sec. J	5	SUPPLY OF <b>CABLES 3 -1/2 CORE X 95 SQMM ALUMINIUM ARMoured</b> PVC INSULATED CABLE (THREE AND HALF CORE) CONFIRMING TO IS 1554 ( PART -I)	M	100.00			

SECTION N	SL.NO	DESCRIPTION OF WORK	UNIT	QTY.	RATE IN FIG ( IN RS )	RATE IN WORDS	AMOUNT
Sec. J	6	INSTALLATION OF <b>CABLES 3 -1/2 CORE X 95 SQMM ALUMINIUM ARMoured</b> PVC INSULATED CABLE CONFIRMING TO IS 1554 ( PART - I) INCLUDING LAYING OF CABLE BELOW GROUND, EXCAVATION OF TRENCH OF 600 MM DEPTH IN ALL KIND OF SOIL, TERMINATION OF CABLES CORES WITH CRIMP TYPE LUGGS, PROVIDING SAND LAYER BELOW/ ABOVE THE CABLE, BRICK LAYING BOTH SIDE /ABOVE THE ABOVE THE CABLE AND BACK FILLING ETC COMPLETE. CABLES ARE TO BE LAID FROM 415 VOLT AC DISTRIBUTION BOARD TO FEEDER PILLAR BOARD , FEEDER PILLAR BOARD TO LIGHTING MAST / TOWER.	M	100.00			
Sec. J		TOTAL VALUE OF SECTION--J IN Rs.					
	<b>TOTAL SUMMARY OF PRICE BID ( TS : BHE/PW/PUR/BRLT-ENB/640 )</b>						
	PARTICULARS						AMOUNT IN RS
	<i>Total of Section A - CONSTRUCTION OF CLOSED SHED WITH OFFICE &amp; C &amp; I ROOM (60MX15M),--- 1 No.</i>						
	<i>Total of Section B - INTERNAL ELECTRICAL FOR THE ABOVE</i>						
	<i>Total of Section C - CONSTRUCTION OF CLOSED SHED (60MX15M), ---- 2No.</i>						
	<i>Total of Section D - INTERNAL ELECTRICAL FOR THE ABOVE</i>						
	<i>Total of Section E - CONSTRUCTION OF STRUCTURAL SHED (60MX15M), ---- 2 No.</i>						
	<i>Total of Section F - INTERNAL ELECTRICAL FOR THE ABOVE</i>						
	<i>Total of Section G- DEVELOPMENT OF OPEN STORAGE YARD, ROADS, DRAINS (2,00,000 sqm.)</i>						
	<i>Total of Section H - ELECTRICAL &amp; ILLUMINATION FOR THE ABOVE</i>						
	<i>Total of Section I - (CIVIL WORKS FOR PORTABLE OFFICE &amp; TOILET BLOCK)</i>						
	<i>Total of Section J- EXTERNAL ELECTRICAL FOR THE ABOVE</i>						
	<i>Grand Total of All Sections in Rs.</i>						
	<i>Grand Total of All Sections in Words ( Rs..... )</i>						