



**BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL ENGINEERING DEPARTMENT**

SCHEDULE- A

Tender Notice No:

HY/FCD/OT-03/2011-12, Dt:- 05.05.2011

PRICE BID

Item no 2

Name of work: Maintenance of Railway lines, Fencing in Factory area.

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
1	<p>Removing the existing railway lines / gantry lines carefully and re laying the new track with all points / crossings etc as per revised layout, using materials issued by Dept. to proper level & gauge and Maintenance of Railway track and gantry tracks including correcting of alignment defects, keeping rails in required level, maintaining gauge within permissible limits, lubricating the turnouts through packing of sleepers, cleaning the grooves at level crossing and providing clear visibility using at all required tools and plants etc. complete as directed by Engineer-in-charge. The total length of the track to be maintained is 17.40KM and 51 turnouts. (Daily 4.60KM track is to be maintained on an average and minimum of one labour are required per 0.92 KM track maintenance of the track) The rate quoted shall include cost of maintenance of track and with all turnouts, tools, tackles and safety equipments etc. The agency should supply tools like beats, shovels, railway crowbars, gauge, jack, spirit level etc. to the railway gangman. (Total 1150 KM).</p> <p>It is assessed that Four Skilled, Two Semi Skilled and Five unskilled services per day are required to execute the above job for one operation, as detailed below.</p>				
a	4 Skilled services are required for carrying out one operation - to carry out critical activities viz.erection of new track, alignment, levelling work among the above scheduled operations of work.	287.00	One Oper.	2,390.40	6,86,044.80
b	2 Semi skilled workers required for carrying out one operation- For assisting the above jobs listed in (A).	287.00	One Oper.	1,114.80	3,19,947.60
c	5 Unskilled required for carrying out one operations - For assisting the above jobs listed in (A) & (B).	287.00	One Oper.	2,574.50	7,38,881.50

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
2	Providing assistance for attending the Misc and emergency works such as sanitation of Annexes, Open areas, shifting of materials from yards, rearranging of materials, cleaning around annexes, collection and disposal of bulk waste papers to bins, from bins to dump yard, making arrangements during VIP visits such as tying banners, rearrangement of furniture, removal of posters, banners and removal of pamphlets from the entrances of blocks and buildings etc. complete as directed by Engineer-in-charge. The rate quoted shall include cost of tools, tackles and safety equipment etc. (It is assessed that a minimum of six unskilled services per day are required to execute the above job of one operation).	287.00	One Oper	3,089.40	8,86,657.80
3	Supply and stacking of graded stone aggregate at site of size range of 63 mm to 45 mm in two layers of 100 mm thick.	100.00	One Cu.m	768.45	76,845.00
	Total Value of work			Total Rs:	27,08,376.70
Total : Rs. Twenty seven lakhs eight thousand three hundred seventy seven only.					

Service Tax:- Service tax is extra as applicable, which will be reimbursable to the agency on production of Valid documents and VAT not applicable.

Note : The bidders are required to quote the tender value on percentage (%) basis at excess or less on par with estimate value

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer