



**BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL ENGINEERING DEPARTMENT**

SCHEDULE- A

Tender Notice No:

HY/FCD/OT-10/2011-12, Dt:- 10.08.2011

PRICE BID

Item no : 2

Name of work: Modification of Parking area – Laying of Parking pavers near J-gate.

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Earth work in excavation in all soils by mechanical means (Hydraulic Excavators) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50M.	165.00	Cu.m	103.40	17,061.00
2	Dismantling reinforced cement concrete / plain cement concrete and disposing of debries upto a lead of 2 KM including loading, unloading and spreading as directed by Engineer-in-charge etc., complete.	10.00	Cu.m	582.68	5,826.80
3	Filling with available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidation each deposited layer by ramming and watering, lead upto 50.00 m and lift upto 1.50 m.	15.00	Cu.M	45.70	685.50
4	Providing and laying in position cement concrete of specified garde excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size).	2.00	Cu.m	2,449.00	4,898.00
5	Plastering in CM 1:6, 20 mm thick to internal and external surfaces of walls including the cost of all materials, labour, curing etc, complete -Upto 10.00 M level.	80.00	Sq.M	95.10	7,608.00
6	Brick work with FPS bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6.	6.00	Cu.M	2,463.60	14,781.60
7	Preparation and consolidation of Sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc; and re-rolling the sub grade and disposal of surplus earth lead upto 2.00 KM	3,608.00	Sq.m	33.90	1,22,311.20
8	Supply & Stacking of stone dust including transportation and spreading as directed by Engineer-in-charge.	360.00	Cu.m	753.20	2,71,152.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
9	Supplying & laying of heavy duty Factory made hydraulically pressed and mechanically compacted pre-cast concrete designed pavers with 60 mm thickness, in required design and colour , including spreading of stone dust properly fixing the pavers into one level in required design and compacting the paved area with machine compactor etc. complete. Rate shall include material, transportation, labour, tools, tackles etc. complete. Rate for stone dust will be paid seperately.	3,762.00	Sq.m	461.60	17,36,539.20
Total Value of work				Total Rs:	21,80,863.30
Total : Rs. Twenty one lakhs eighty thousand eight hundred and sixty three only					

Note: Service tax is extra as applicable, which will be reimbursable to the agency on production of Valid documents.

Note : The bidders are required to quote the tender value on percentage (%) basis at excess or less or on par with estimate value

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer