



**BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL ENGINEERING DEPARTMENT**

SCHEDULE- A

Tender Notice No:

HY/FCD/OT-13/2011-12, Dt: 11.10.2011

PRICE BID

Item no :1

Name of work: Renovation of Toilets in GF +FF of 90 building – (Civil and Electrical works).

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
PART - I - Civil works					
1	Supply and fixing of new urinary pans, "Parry ware" make, ceramic, Model (Cat 0575)- "New Magnum Urinal" (590 mm x 400 mm) along with all accessories, C.P spreader brackets etc., along with partition for Magnum Urinal ceramic, 'Z' type brackets to be screwed to the wall at the bottom. Colour - Silky Off - White	8.00	Each	3,933.00	31,464.00
2	Supply and fixing with "Parry ware" make Cascade pedestal ceramic wash hand basin of size 550 mm x 440 mm and pedestal size 705 mm height, with centre tap hole with all accessories like brackets, screws, PVC connections etc. complete. Colour: Silky Off - White.	4.00	Each	3,000.00	12,000.00
3	Supply and fixing of new "Parry ware" make Elite - European water closet of size 530 mm x 400 mm, with "P/S" trap including PVC Slimline Dual flush tank (Cistern) of size 475 mm x 318 mm (Code No. C8109), EWC standard seat cover (Cat C8071) with all accessories like Parryware flush kit suitable to the above flush tank, brackets, screws, connecting pipe from flush tank to EWC, PVC Connections etc. complete. Colour: Silky Off - White.	1.00	Each	2,000.00	2,000.00
4	Supply and fixing of new "Parry ware" make Indian Water Closet, Orissa pan of size 580 mm x 410 mm - Open rim (Code No. C0109) including PVC Slimline Dual Flush tank (Cistern) of size 475 mm x 318 mm (Code No. C8109) with all accessories like Parryware flush kit suitable for the above flush tank with all required accessories etc., complete. Colour: Silky Off - White.	2.00	Each	3,000.00	6,000.00
5	Supply & fixing of 6 mm thick mirror of approved quality "Modi float/Saintgobin glass", with 6 mm thick hard board back and with best quality teak wood frame (design beading) all round the mirror including necessary clamps, polishing to the beading, cost of all materials etc. complete.	3.20	Sq.m	1,445.00	4,624.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
6	Providing and fixing shutters along with frames for toilets that are 30 mm thick factory made PVC rigid foam paneled, door and shutters manufactured by M/s. Rajashri made from M.S. tube, 19 gauge thick, size 19x19mm for styles and 15x15mm for top and bottom rails, covered with heat moulded PVC "C" channel of 5mm thick sheet and 30x50mm wide for styles and 5mm thick and 75mm wide PVC sheets for top rail and bottom rail either side and 5 mm thick, 20mm wide cross PVC sheet as gap insert for top rail and bottom rail, paneling of 5mm thick PVC sheet fitted with M.S. frame welded / sealed to the styles and rails with 5x30mm PVC sheet beading on either side and joined together with solvent cement adhesive etc. complete in all respects as per direction of engineer in-charge fixed to frames. This includes providing brass hinges, brass aldrops, brass tower bolts, brass handles and brass door stoppers (For W.C. and bathroom doors). Make:- RAJASHRI	4.80	Sq.m	1,830.00	8,784.00
7	Supply and fixing of toilet doors along with teak wood door frame of required size consist teak scantlings of 100 mm x 75 mm and flush door shutter and laminating both door frame and shutter with premium quality teak vineer in required colour and design and malamine polish. Flush door shutter shall be chemically treated and water/insect/borer proof and 30 mm thick. This includes providing brass hinges, brass aldrops, brass tower bolts, brass handles and brass door stoppers.	2.20	Sq.m	3,180.00	6,996.00
8	Supply & fixing "Jaquar" make Pressmatic urinal flush valve for urinal pots (Cat. No. 51027) with all accessories.	8.00	Each	1,320.00	10,560.00
9	Supply & fixing "Marc" make Oreintal series brass bib cocks, with all accessories / Cat: MOR 1030.	5.00	Each	506.00	2,530.00
10	Supply & fixing "Jaquar" make Pressmatic pillar cock for wash basins, with all accessories. (Cat: 031)	4.00	Each	519.00	2,076.00
11	Supply & fixing "Marc" make Oriental series brass stop cock with all accessories.	7.00	Each	698.00	4,886.00
12a	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacture) of approved make in all colours, shades except burgundy, bottle green , black of any size as approved by engineer-in-charge in skirting , risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 Kg per Sq.m including poniting in white cement mixed with pigment of matching shade complete.	85.00	Sq.m	556.80	47,328.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
b	Supply & fixing of 18 mm thick best quality approved colour and design machine cut mirror polished granite slabs in required sizes for counter wash basins, floorings, vanity counter, claddings, facias etc. including cutting, champering, rounding and mirror polishing etc. complete as directed. Cost of granite slabs shall be Rs. 1600/- per Sq. m and granite slabs of required design and colour will be selected by department.	45.00	Sq.m	3,070.92	1,38,191.40
13	Supply & fixing in position PVC Pipes of 3" dia(as per IS 6kg/sq.m) of best quality for drainage lines / urinal / hand wash areas including chasing the brick wall, concrete etc and making good the same after fixing the same etc. complete.	25.00	RM	108.70	2,717.50
14	Supplying and fixing CI Nahany traps 1st quality ISI marked conforming to IS: 1729 - 1979 with C.P Grating fixing with white cement as per site requirements with standard practice - 100mm inlet - 75 mm dia (3") outlet pipe - 4 Kgs.	3.00	Each	200.00	600.00
15a	Supply & fixing 15 mm dia Nominal Bore GI pipe medium Grade properties and weight as per IS 1239 ISI mark with GI fittings including the cost of GI pipe & its fittings, chasing brick work/concrete and making good the same, cost of labour, all materials etc. complete. Make: TATA/JINDAL/ZENITH	22.00	RM	131.00	2,882.00
b	.. Do... 20mm dia (3/4") Make: TATA/JINDAL/ZENITH	30.00	RM	146.00	4,380.00
c	.. Do... 25mm dia (1") Make: TATA/JINDAL/ZENITH	40.00	RM	191.00	7,640.00
16(a)	Supply & fixing of GM peet valves, heavy quality, ISI marked Leader/Zoloto make of nominal bore for 15 mm (1/2") dia	2.00	Each	242.00	484.00
b	.. Do .. 20mm dia (3/4")	2.00	Each	327.00	654.00
c	.. .do ...25mm dia (1")	2.00	Each	482.00	964.00
17	Construction of brick masonry chamber of size 23 x 30 Cm (9" x 12") in brick work in CM 1:6 and plastering in CM 1:4, 20 mm for gully trap 150 mmx100mm including cost of excavation, PCC 1:4:8, 75 mm thick, all materials, labour etc., complete.	1.00	Each	321.00	321.00
18	Providing and placing on terrace (at all floor levels) of polyethylene water storage tank of 1000 ltrs capacity with double layer approved brand and manufacture as per ISI with cover and suitable locking arrangement and making necessary holes for inlet and outlet and overflow pipes with fittings (ballcock, inlet and outlet nipples) without base support for tank. (Brick work will be paid seperately)-Sintex tank with lid - (ISI 12701/96).	1.00	Each	6,000.00	6,000.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
19	Thorough cleaning of existing oil bound distemper paint/white washing with water by scrapers or any other suitable tools and applying one coat of oil based cement primer and applying 3 coats altek lappam one coat after drying the previous coat and sand papering and applying one coat of oil bound cement primer etc., complete as directed by the Engineer-in-charge. (Only OBD Paint will be supplied by BHEL).	140.00	Sq.m	84.10	11,774.00
20	Brick work with FPS bricks of class designation 75 in superstructure above plinth level up to floor five level in all shapes and sizes in cement mortar 1:6.	1.00	Cu.M	2,463.60	2,463.60
21	Plastering in CM 1:6, 20 mm thick to internal and external surfaces of walls including the cost of all materials, labour, curing etc. complete upto 10.00 M level.	10.00	Sq.m	95.10	951.00
22	Supplying and fixing plain PVC pipe of 90 mm dia of approved quality with specials, accessories and approved sealing / jointing compound on the exterior of the inserted portion of the fitting and fixing in position and jointing to MS gutters, including cost of all materials, sealing compound, labour etc., for all heights complete.	30.00	R M	103.86	3,115.80
23	Supply & fixing PVC Ventilating cowl of 110 mm dia.	1.00	Each	14.00	14.00
24	Supply & fixing 12.7 mm PVC connection with brass union nut CP coated.	7.00	Each	67.00	469.00
25	Supply & fixing P Trap 1st quality ISI marked conforming to IS:1729 - 1979 with CP grating fixing with white cement as per site requirements with standard practice - 100 mm dia (4") .	5.00	Each	512.00	2,560.00
26	Dismantling brick masonry walls for all heights, removing and clearing the debries and carrying away upto a lead of 2 Km including loading, unloading and spreading segregating useful materials as directed by Engineer-in-charge including the cost of all labour scaffolding etc. complete.	1.00	Cu.M	355.88	355.88
27	Dismantling reinforced cement concrete / plain cement concrete and disposing of debries upto a lead of 2 Km including loading, unloading and spreading as directed by Engineer-in-charge etc. complete.	1.00	Cu.M	582.68	582.68
28	Dismantling teak wood door with frame and shutters including chowkats, holdfasts etc. complete and stacking within 50 meters etc. complete.	4.20	Each	75.35	316.47
29	Removing of wall plastering along with Glazed tiles from walls and flooring and skirting, raking out joints and cleaning the surface for plastering including disposal of rubbish to the dumping ground within a lead of 50.00 M.	130.00	Sq.m	19.10	2,483.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
30	Applying two coats of Synthetic enamel paint of given shade over a coat of primer to new wood work including scraping the surfaces, cost of all labour, tools and other incidentals etc. complete.	16.00	Sq.m	20.00	320.00
31	Providing and Fixing PTMT waste coupling for wash basin and sink, of approved quality and colour - waste Coupling 31 mm of 79 mm length and 62 mm breadth weighing not less than 45 gms.	4.00	Each	75.80	303.20
32	Supply and fixing of "Jaquar (Allied)" Make Health Fauset with 8 mm dia. 1 M long Flexible tube and wall hook Cat no. 573.	2.00	Each	1,325.00	2,650.00
Total of Part - I		Rs.	3,32,440.53		
PART - II - Electrical Works					
S.No	Description	Appro. Qty	Unit	Rate in Rs	Amount (Rs)
1(a)	Supply & Installation of lighting/fans wiring with 1.5 sq. mm copper conductor single core multi-strand PVC insulated cable run through rigid PVC pipe of suitable size (Sudhakar make) from switch board/FBD to individual points laid on wall/roof including earth continuity for all points with copper wire of 14 SWG with 5 A ceiling rose on teakwood round block.	8.00	Point	372.00	2,976.00
(b)	---do--- for 10 Amps Power Switch cum sockets for chargers, pedestal fans and emergency lamps with 1.5 Sq. mm cable.	2.00	Point	372.00	744.00
2(a)	Supply and fixing of 10 Amps, 250 V SPT switches for control of light fittings with ROMA, Code: 21 011 of Anchor make or equivalent type of North-West make fixed on a suitable Modular type concealed box with suitable top cover for item 1(a).	8.00	Set	250.00	2,000.00
(b)	Supply and fixing of 230 V, 10 Amps switch cum sockets of ROMA code: 21 003 & 30 373 of Anchor make North-West make fixed on a suitable Modular type concealed box with suitable top cover for item 1 (b).	2.00	Set	400.00	800.00
3	Supply and installation of Energy efficient light fitting, T5 type 2 x 28 W industrial luminaire with 28W T5 Fluorescent lamps. This includes supply & fixing of downrods, round blocks, connecting the copper twin twisted wire from ceiling rose to fitting and other accessories. Make: Philips/Asian Electronics	4.00	Set	1,800.00	7,200.00
4	Supply and installation of 300 mm (12") sweep exhaust fans, which includes assembling and testing of all fans. The fans are to be rigidly fixed to wall with suitable arrangement. Black colour, double ball bearing, low noise, white epoxy powder coated paint finish with bird guard. Make: Orient/Usha/Crompton.	1.00	Set	1,600.00	1,600.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
5	Disconnection of power supply and dismantling of existing light fittings, fans, power boards, cables and other accessories. The removed items are to be handed over to concerned section.	2.00	LS - 2 No. of toilets	500.00	1,000.00
Total of part - II		Rs.		16,320.00	
Total value of work (Part - I + Part II)				Rs.	3,48,760.53
Total : Rs. Three lakhs forty eight thousand seven hundred sixty one only					

Note: Service tax is extra as applicable, which will be reimbursable to the agency on production of Valid documents.

Note : The bidders are required to quote the tender value on percentage (%) basis at excess or less or on par with estimate value

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer