



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL DEPARTMENT

SCHEDULE- A

Tender Notice No:

HY/FCD/OT- 19 /2010-11 , Dt: - 28.10.2010

PRICE BID

Item no : 2

**Name of the Work :- Providing Rain water harvesting pits in GT complex and
New Balde shop.**

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
1a	Earth work in excavation in all soils by mechanical means (Hydraulic Excavtors) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m , including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50M.	300.00	Cu.m	103.40	31020.00
b	----do---- up to First additional depth of 1.50 M to 3.00 M.	228.00	Cu.m	122.30	27884.40
2	Collection , Supply and filling the pits with 40 mm hard graded granite stone metal aggregate at site.(1/3 will be deducted for voids) etc; complete all as directed by engineer-in-charge.	180.00	Cu.m	810.55	145899.00
3	Collection , Supply and filling the pits with 20 mm hard graded granite stone metal aggregate at site.(1/3 will be deducted for voids) etc; complete all as directed by engineer-in-charge.	72.00	Cu.m	810.55	58359.60
4	Collection , supply and filling in pits with good quality coarse river sand etc; complete all as directed by Engineer-in-charge.	54.00	Cu.m	301.50	16281.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size).	4.20	Cu.M	2449.00	10285.80
5	Brick work with FPS bricks of class designation 75 in superstructure above plinth level up to ground floor in all shapes and sizes in cement mortar 1:6.	12.00	Cu.M	2463.60	29563.20
6	Plastering in CM 1:6 , 20 mm thick to internal and external surfaces of walls including the cost of all materials , labour , curing etc, complete -Upto 10.00 M level.	120.00	Sq.m	95.10	11412.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
7	Filling with available excavated earth (excluding rock) in trenches , plinth , sides of foundations etc. in layers not exceeding 20 cm in depth , consolidation each deposited layer by ramming and watering , lead upto 50.00 m and lift upto 1.50 m.	120.00	Cu.M	45.70	5484.00
8	Conveyance of excavated spoil up to a lead of 2 Kms, including loading , unloading and spreading etc. complete as directed by Engineer- in- charge.	528.00	Cu.M	56.41	29784.48
Under Contractor's Scope				Total Rs:	3,65,973.48
Total : Rs.Three Lakhs Sixty Six thousand only.					

Service Tax:- The Service tax as applicable is extra which will be paid by BHEL to the agency after submission of necessary valid documents by the agency.

Note : The Tenderers are required to quote the tender value on percentage (%) basis at excess or less or on as per estimate value

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer