



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL DEPARTMENT

SCHEDULE- A

Tender Notice No:

PRICE BID

HY/FCD/OT- 20 /2010-11 , Dt: -09.11.2010

Item no : 3

Name of the work :- Modification - Providing berms and boulder soling to approach road from outside K-gate to Main Road.

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Earth work in excavation in all soils by mechanical means (Hydraulic Excavtors) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50M.	180.00	Cu.m	103.40	18612.00
2	Preparation and consolidation of Sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc; and re-rolling the sub grade and disposal of surplus earth lead upto 2.00 KM	2850.00	Cu.M	33.90	96615.00
3	Rolling with power road roller 8T to 10T capacity to required compacting .(Hire charges)	7.00	Days	1000.00	7000.00
4	Providing Boulder to required thickness of minimum 230mm using hard granite stone boulders and 25% granite metal of 38.1 to 76 mm (1-1/2" to 3") gauge for opacking and 20% gravel for filling interstices etc; complete all as directed by Engineer-in-charge. The rate includes the cost of carting of murrum from the designated places of BHEL shown by the Engineer - incharge.	780.00	Cu.M	729.00	568620.00
5	Supply and stacking at site 63 mm to 45 mm size stone aggregate.	80.00	Cu.M	768.45	61476.00
6	Supply and stacking at site Murum(gravel). (Excluding the cost of muram which has to be supplied from the designated places of surplus excavated soil from BHEL Factory /Township area).Bhel will pay the conveyance charges.	183.00	Cu.m	56.41	10323.03

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
7	Laying , Spreading and compacting stone aggregate of specified sizes to WBM specifications including spreading in uniform thickness, hand picking , rolling with 3 wheeled road / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fillup intertices of coarse aggregate watering and compacting to the required density.	80.00	Cu.m	192.55	15404.00
Under Contractor's Scope				Total Rs:	7,78,050.03
Total : Rs.Fourteen Lakhs thirty Six thousand five hundred ninty only.					

Service Tax:- The Service tax as applicable is extra which will be paid by BHEL to the agency after submission of necessary valid documents by the agency.

Note : The Tenders are required to quote the tender value on percentage (%) basis at excess or less or on as per estimate value

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer