



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL ENGINEERING DEPARTMENT

SCHEDULE- A

Tender Notice No:

HY/FCD/OT-16/2011-12, Dt: 28.11.2011

PRICE BID

Item no :1

Name of work: Providing false ceiling and fixing safety grills to buildings at K-gate area.

S No	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
	Part - I (False ceiling to buildings near K-gate)				
1	Providing and fixing in true horizontal level 600 mmx600mm false ceiling system manufactured by M/s. Armstrong World Industries using DUNE SUPREME RH 99 MICROLOOK EDGE WITH SILHOUETTE GRID, using hot dipped galvanized steel section, rotary stitched main tee of size 15mm x 42 mm web height, having 0.36 mm gauge at every 600 mm centre to centre maximum and rotary stitched cross tee of size 15 mm x 42 mm, having 0.33 mm gauge at every 600 mm. c/c. and wall angle of size 19x19 mm., having 0.35 mm gauge fixed to the periphery of the wall. The above grid is suspended at every 600mm c/c. in both directions using 2.0 mm. thick pre-straightened GI wire, and laying Dune Supreme Microlook Edge ceiling tiles manufactured by M/s. Armstrong World Industries, of size 600mmx600mmx15mm having NRC 0.50, Light reflectance of > 85% (WT), thermal conductivity k = 0.052-0.057 W/m0K, Humidity Resistance of 99% (having LIFETIME GUARANTEE against SAG), having Fire Performance CLASS O / CLASS 1 (BS 476), surface having 3 coats of white paint - crisp finely granulated with microperforations, back of the tile duly sanded and finished with a coat of protective paint over the formed grid and complete in all respects. Boards, where light fixtures to be fixed shall be handed over to Department. Make: Armstrong	200.00	Sq.m	1,130.00	226,000.00

S No	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
	Part - II (Safety grills to windows for bldgs near K-gate)				
1	Supply and fixing of aluminum window grills of size 1.50Mx1.80M approx and 1.20Mx1.80M approx. along with aluminium frame consisting aluminium 'F' (solid) 0.80kg/12' supply and fixing of design of 4" aperture aluminium grill to the above frame work with necessary fixtures. It includes fixing of total frame to the existing brick work, finishing etc complete. (The material shall be aluminium alloy :6063, thick 7 mm, ultimate tensile strength more than 19 kgs/sq.mm)	62.00	Sq.m	1,540.00	95,480.00
	Total Value of work (Part- I + Part -II)			Total ₹:	321,480.00
Total : ₹ Three lakhs twenty one thousand four hundred eighty only					

Service tax: Service tax is extra as applicable, which will be reimbursable to the agency on production of Valid documents.

Note : The bidders are required to quote the tender value on percentage (%) basis at excess or less or on par with estimate value.

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer