



BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL ENGINEERING DEPARTMENT

SCHEDULE- A

Tender Notice No:

PRICE BID

HY/FCD/OT-22/2011-12, Dt: 15.02.2012

Item no.: 1

Name of work: Site levelling and dry stone pitching works in GT complex area.

S. No.	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
1a	Earth work in excavation in all soils by mechanical means (Hydraulic Excavators) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50M.	2,261.00	Cu.m	103.40	2,33,787.40
1b	----do---- up to First additional depth of 1.50 M to 3.00 M.	1,927.00	Cu.m	122.30	2,35,672.10
1c	----do---- up to First additional depth of 3.00 M to 4.50 M.	604.00	Cu.m	141.20	85,284.80
1d	----do---- up to First additional depth of 4.50 M to 6.00 M.	297.00	Cu.m	160.10	47,549.70
2	Earth work in excavation by mechanical means (Hydraulic Excavators) / manual means over areas (exceeding 30 cm in depth , 1.5 m in width as well as 10 Sq.m on plan) including disposal of excavated earth , lead upto 50 m and lift upto 1.5 m, disposing earth to be levelled and neatly dressed for Hard Rock (Blasting prohibited).	3,375.00	Cu.M	325.25	10,97,718.75
3	Transportation including handling, leading, loading and disposal of rock boulders within a lead of 2kms. The quantity is measured in stacks and 33% is deducted for voids.	4,312.00	Cu.M	90.25	3,89,158.00
4	Conveyance of excavated soil up to a lead of 2 Kms, including loading, unloading and spreading etc. complete as directed by Engineer- in- charge.	3,725.00	Cu.M	56.41	2,10,127.25
5	Dismantling brick masonry walls for all heights, removing and clearing the debries and carting away upto a lead of 2 KM including loading, unloading and spreading segregating useful materials as directed by Engineer-in-charge including the cost of all labour, scaffolding etc., complete.	5.00	Cu.m	355.88	1,779.40

S. No.	Description of the item	Qty	Unit	Rate (₹)	Amount (₹)
6	Dismantling reinforced cement concrete / plain cement concrete and disposing of debries upto a lead of 2 KM including loading, unloading and spreading as directed by Engineer-in-charge etc., complete.	5.00	Cu.m	582.68	2,913.40
7	Dry stone pitching 22.5cm thick including supply of stones and preparing bedding surfacce.etc. Complete as directed by Engineer in charge.	1,770.00	Sq.m	211.10	3,73,647.00
8	Pointing on stone work with cement mortar 1:3 (1cement :3fine sand) - Flush/Ruled pointing. (Cement only will be issued by BHEL on free of cost at their stores).	1,770.00	Sq.m	56.40	99,828.00
Total value of work				₹	27,77,465.80
Add increase in Vat 1% over the material cost (70% of contractor scope)					19,442.26
Total				₹	27,96,908.06
Total : ₹ Twenty seven lakhs ninty six thousand nine hundred and eight only					

Service tax: Service tax is extra as applicable, which will be reimbursable to the agency on production of Valid documents.

Note : The bidders are required to quote the tender value on percentage (%) basis at excess or less or on par with estimate value.

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer