



**BHARAT HEAVY ELECTRICALS LIMITED**  
**RAMACHANDRAPURAM::HYDERABAD::32**  
**FACTORY CIVIL DEPARTMENT**

SCHEDULE- A

Tender Notice No:

HY/FCD/OT- 27 /2010-11, Dt:- 03.02.2011 Item No. 4

**PRICE BID**

**Name of the Work :- Construction of foundation for CNC Horizontal boring machine  
 200mm in 01 Block.**

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Dismantling reinforced cement concrete / plain cement concrete and disposing of debris upto to a lead of 2 KM including loading, unloading and spreading as directed by Engineer-in-charge etc., complete.	80.00	Cu.m	582.68	46614.40
2	Dismantling brick masonry walls for all heights , removing and clearing debris and carting away upto a lead of 2 km including loading, unloading and spreading segregating useful material as directed by engineer in charge including the cost of all labour, scaffolding etc., complete	3.00	Cu.m	355.88	1067.64
3	Dismantling steel work in built up sections in angles tees, flats and channels including all gusset plates, bolts, cutting rivets, welding etc., including dismembering and stacking within 50 metres lead. (Clamping Bars, May Pole etc).	1.00	MT	890.11	890.11
4	Removal of wood/M S Scrap including MS packing strips loading into the vehicle and unloading the same at specified yards as directed by Engineer in charge. The vehicle shall be weighed before and after loading for each trip at BHEL weigh Bridge. The quoted rate shall include cost of hire charges of vehicle, labour, tools, safety eqpt etc., complete. Payment will be made against the weight of material disposed.	5.00	MT	381.00	1905.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
5a	<b>Earth work in excavation in all soils</b> by mechanical means (Hydraulic Excavators) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50M.	250.00	Cu.m	103.40	25850.00
5b	----do---- up to First additional depth of 1.50 M to 3.00 M.	250.00	Cu.m	122.30	30575.00
5c	----do---- up to second additional depth of 3.01 M to 4.50 M.	100.00	Cu.m	141.20	14120.00
6	Earth work in excavation by mechanical means (Hydraulic Excavators) / manual means over areas (exceeding 30 cm in depth , 1.5 m in width as well as 10 Sq.m on plan) including disposal of excavated earth , lead upto 50 m and lift upto 1.5 m, disposing earth to be levelled and neatly dressed for <b>Hard Rock</b> (Blasting prohibited).	630.00	Cu.M	325.25	204907.50
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with <b>1:4:8</b> (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size).	30.00	Cu.M	2449.00	73470.00
8	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement, including consolidation by vibrations for all works <b>up to plinth level</b> with <b>1:1½,3</b> (1 cement : 1½ coarse sand : 3 graded stone aggregate of 20 mm nominal size ).	90.00	Cu.M	3732.00	335880.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
9	Providing and laying in position ready mix concrete manufactured in fully automatic batching plant and transported to site of work in transit mixer for a lead up to 25 KM having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work including pumping of <b>R.M.C</b> from transit mixer to site of laying, excluding the cost of centering, shuttering finishing and reinforcement including cost of admixtures in recommended proportions as per ID: 9103 to accelerate/retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer-in-charge. <b>M 25 grade</b> Reinforced cement concrete by using 380 kgs of cement per cu.m of concrete. All works upto floor V level. as per IS 456: 2000 for all concrete works upto all levels.(cement cost considered in the estimate is Rs 225 per bag.If there is increase or decrease proportionate reimbursement/recovery cost will be done by BHEL)	600.00	Cu.m	4162.80	2497680.00
10	<b>Reinforcement for R.C.C. work</b> including straightening , cutting , bending , placing in position and binding grills with binding wire all complete by cold twisted bars.	55.20	M.T	42700.00	2357040.00
11	<b>Centering</b> and shuttering including strutting, propping etc; and removal of form work, for columns, pillars, piers, abutments, machine foundations, posts and struts.	990.00	Sq.M	180.40	178596.00
12	<b>Grouting</b> with cement mortar 1:1 including cost of all materials, labour, curing for all leads & lifts etc: complete. For pockets	10.00	one cum	6016.56	60165.60

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
13	Supplying and fixing position 40 mm thick fibre glass covered by cotton cloth (netted) fixed in position and covered with aluminium perforated sheet above the insulation for the foundation including fixtures and accessories and cost of all materials, labour etc., complete. Rock wool shall be of standard quality.	114.00	Sq.M	580.00	66120.00
14	Supply and fixing in position 60 mm thick / 30 mm thick in two layers <b>thermocoal</b> including cost of materials, labour etc., complete.	114.00	Sq.M	426.00	48564.00
15	Finishing with <b>Epoxy paint (two or more coats) of ASIAN or BERGER make</b> at all locations prepared and applied as per manufactures specifications including appropriate priming coat, preparation of surface, cost of all materials etc; complete on concrete work.	500.00	Sq.M	77.75	38875.00
16	Fabrication and fixing <b>inserts</b> in concrete wall with lugs of required dia welded to the insert plates.(St. Steel,electrodes and gas required for work will be issued on free of cost by BHEL at their stores)	2.00	MT	3500.00	7000.00
17a	Supplying and fixing plain PVC pipe of 200mm dia of approved quality with specials, accessories and approved sealing/jointing compound on the exterior of the inserted portion of fitting and fixing in position and joining MS gutters, including cost of all materilas, sealing compound, labour etc, for all heights complete	14.00	One RM	437.32	6122.48
17b	----do----- 100 mm dia	47.00	one RM	140.15	6587.05
18	<b>Conveyance</b> of excavated spoil up to a lead of 2 Kms, including loading , unloading and spreading etc. complete as directed by Engineer- in- charge.	830.00	Cu.M	56.41	46820.30

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
19	<b>Filling</b> with available excavated earth (excluding rock) in trenches , plinth , sides of foundations etc. in layers not exceeding 20 cm in depth , consolidation each deposited layer by ramming and watering , lead upto 50 m .	200.00	Cu.M	45.70	9140.00
20	Granolithic topping of 25 mm thick using 1 cement 1 granite chips of 10mm down graded laid over base concrete when it is green conditions and <b>ironite finishing</b> 12mm thick using a mix of 50Kg of ironite , 200 Kg of cement and 0.30 Cu.m of granite metal 6mm down graded including cost of form work , curing etc. complete.	50.00	Sq.m	485.00	24250.00
	<b>Total Value of work</b>			<b>Total Rs:</b>	<b>60,82,240.08</b>
<b>Total : Rs. Sixty lakhs eighty two thousand two hundred forty only.</b>					

**Service Tax:-** All taxes inclusive except Service tax as applicable is extra which will be paid by BHEL to the agency after submission of necessary valid documents by the agency.

**Note :** The Tenderers are required to quote the tender value on percentage (%) basis at excess or less or on as per estimate value

Tender %	In figure	In words
Excess		
Less		
Estimated value		

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer