



**BHARAT HEAVY ELECTRICALS LIMITED  
RAMACHANDRAPURAM::HYDERABAD::32  
FACTORY CIVIL DEPARTMENT**

SCHEDULE- A

Tender Notice No:

**PRICE BID**

HY/FCD/OT- 13 /2010-11 , Dt:- 14.08.2010

Item no : 05

**Name of work : Structural stability of Factory blocks 04, 05 and 08-  
Replacement of roof truss in 08 block and painting of  
structural steel work.**

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Painting with acid proof paint of approved brand and manufacture of required colour to give an even shade two or more coats on new / old structural work including necessary scraping etc., complete.	180576.00	Sq.m	32.40	5850662.40
2a	Fabrication of structural steel work including all materials going into the process of fabrication and forming an integral part of steel work together with all shop and site rivets and electrodes for site welding as necessary and all site connections comprising sag rods, floor beams, girders, bracings, trusses and frame work for fixed false ceiling and for movable false ceiling, purlins with channel / angles, MS flat supports including all connections as per detailed drawings connected steel works etc., cleats, gusset plates, all bolts, nuts, washers, base plates, anchor bolts as per detailed drawings, cutting, welding and painting 2 coats of red-oxide primer before erection etc., complete. The rate shall include painting 2 coat of Red-oxide as per IS specifications and all charges for handling, leading and loading at the fabrication yard. The raw structural steel sections, electrodes, gasses will be issued by BHEL on FREE of cost at their stores	13.00	MT	7563.80	98329.40
b	Erection of Steel work out lined in item No.2(a) above including the charges for handling, leading and stacking at site at approved locations prior to erection including all site rivetting, bolting, jointing and site welding where ever required.	13.00	MT	3241.60	42140.80

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
3	Dismantling Steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc; including dismembering and stacking within 2.00 Km lead.	13.00	MT	890.11	11571.43
4	Removing of old A.C. sheets, translucent sheets from roof, side walling of factory blocks and sheds and refixing with new/old sheets at all height including transportation of A.C. sheets and disposing off old sheets to a lead of 2 K.Ms. etc., complete as directed. (Required consumable materials will be supplied by BHEL free of cost at their stores).	450.00	Sq.M	72.82	32769.00
5	Dismantling the existing steel work by gas cutting/loosening nuts or nay other suitable means and reerecting the same at new location by suitably modifying by gas cutting, welding drilling new holes, pointing to new members by welding or bolting etc. complete.	14.00	MT	5505.90	77082.60
				<b>Total</b>	<b>61,12,555.63</b>
<b>Total : Rs. Sixty one lakhs twelve thousand five hundred fifty six only.</b>					

**Service Tax:-** The Service tax as applicable is extra which will be paid by BHEL to the agency after submission of necessary valid documents by the agency.

**Note :** The Tenders are required to quote the tender value on percentage (%) basis at excess or less or on as per estimate value

Tender %	In figure	In words
Excess		
Less		
Estimated value		

**Name of the Contractor :**

**Signature of the Contractor**

**Accounts Representative**

**Opening officer**