



**BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM::HYDERABAD::32
FACTORY CIVIL DEPARTMENT**

SCHEDULE- A

Tender Notice No:

HY/FCD/OT- 13 /2010-11 , Dt:- 14.08.2010

PRICE BID

Item no : 06

Name of work : Development of Visitors Parking lot opp. to Admn. Bldg.

| S No | Description of the item | Qty | Unit | Rate (Rs) | Amount (Rs) |
|------|---|--------|------|-----------|-------------|
| 1 | Earth work in excavation in all soils by mechanical means (Hydraulic Excavtors) / manual means in foundations trenches or drains (not exceeding 1.5m in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50M. | 165.00 | Cu.M | 103.40 | 17061.00 |
| 2 | Dismantling reinforced cement concrete / plain cement concrete and disposing of debries upto a lead of 2 Km including loading, unloading and spreading as directed by Engineer-in-charge etc. complete. | 10.00 | Cu.M | 582.68 | 5826.80 |
| 3 | Filling with available excavated earth (excluding rock) in trenches , plinth , sides of foundations etc. in layers not exceeding 20 cm in depth , consolidation each deposited layer by ramming and watering , lead upto 50.00 m and lift upto 1.50 m. | 15.00 | Cu.M | 45.70 | 685.50 |
| 4 | Providing and laying in position cement concrete of specified garde excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size). | 2.00 | Cu.M | 2449.00 | 4898.00 |
| 5 | Plastering in CM 1:6 , 20 mm thick to internal and external surfaces of walls including the cost of all materials , labour , curing etc, complete -Upto 10.00 M level. | 50.00 | Sq.m | 95.10 | 4755.00 |

| S No | Description of the item | Qty | Unit | Rate (Rs) | Amount (Rs) |
|------|--|---------|------|-----------|-------------|
| 6 | Brick work with FPS bricks of class designation 75 in superstructure above plinth level up to ground floor in all shapes and sizes in cement mortar 1:6. | 2.00 | Cu.M | 2463.60 | 4927.20 |
| 7 | Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 30 cm depth, dressing of camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth lead upto 50 meters. | 3608.00 | Sq.m | 33.90 | 122311.20 |
| 8 | Supply & Stacking of stone dust including transportation and spreading as directed by Engineer-in-charge etc. complete. | 360.00 | Cu.m | 753.20 | 271152.00 |
| 9 | Supplying & laying of heavy duty Factory made hydraulically pressed and mechanically compacted pre-cast concrete designed pavers of 200 x 100 with 60 mm thickness, zig-zag paver 80 mm / Hexagon 60 mm, including spreading of stone dust properly fixing the pavers into one level in required design etc. complete. Rate shall include material, transportation, labour, tools, tackles etc. complete. Rate for stone dust will be paid seperately. | 3286.00 | Sq.m | 556.30 | 1828001.80 |

| S No | Description of the item | Qty | Unit | Rate (Rs) | Amount (Rs) |
|--|---|--------|------|--------------|---------------------|
| 10 | Supplying & laying of heavy duty Factory made hydraulically pressed and mechanically compacted pre-cast concrete designed pavers, with 60 mm thickness, including spreading of stone dust properly fixing the pavers into one level in required design etc. complete. Rate shall include material, transportation, labour, tools, tackles etc. complete. Rate for stone dust will be paid seperately. | 322.00 | Sq.m | 461.60 | 148635.20 |
| | | | | Total | 24,08,253.70 |
| Total : Rs. Twenty four lakhs eight thousand two hundred fifty four only. | | | | | |

Service Tax:- The Service tax as applicable is extra which will be paid by BHEL to the agency after submission of necessary valid documents by the agency.

Note : The Tenders are required to quote the tender value on percentage (%) basis at excess or less or on as per estimate value

| Tender % | In figure | In words |
|-----------------|-----------|----------|
| Excess | | |
| Less | | |
| Estimated value | | |

Name of the Contractor :

Signature of the Contractor

Accounts Representative

Opening officer