

ENQUIRY No.: PE/PG/YAD/E-6901/2021 dtd 07.03.2022

NAME OF PROJECT: SX800 MW TSGENCO YADADRI TPS

NAME OF PACKAGE: Aux PRDS

S. N.	DESCRIPTION	UNIT	STAGE-I QUANTITY (Unit-1 & 2)	STAGE-II QUANTITY (Unit-3,4 & 5)	TOTAL QTY (stage-I & stage-II)	UNIT EX- WORKS PRICE (INR)	TOTAL EX-WORKS PRICE(DULY PACKED) (INR)	Freight rate in %	Freight Amount,as applicable in Rs.	TOTAL PRICES (Total Ex works + Freight(as applicable)) (INR)	GST type	GST rate in %	GST amount in Rs.	TOTAL PRICE F.O.R SITE PRICE (INR)	Total FOR site Price In Words
CONTROL VALVES & ACCESSORIES															
MAIN SUPPLY															
A	Total price for Design, Engineering, Manufacture, Assembly, Inspection, Testing, Proper Packing for Transportation and Dispatch to site of auxiliary steam pressure reducing and desuperheating stations complete with controls valves and all accessories incl					₹ -	₹ -		₹ -	₹ -			₹ -	₹ -	
A.1	Combined Type 1x100 % High Capacity Pressure Reducing & De-superheating Valve (On MS line) (ASV-22)	Nos.	2	3	5		₹ -		0	0			0 ₹	-	
A.2	Combined Type 1x30 % Intermediate Capacity Pressure Reducing & De-superheating Valve (On MS line)(ASV-20)	Nos.	2	3	5		₹ -		0	0			0 ₹	-	
A.3	Low Capacity Pressure Reducing Valve (from CRH line) (ASV-26)	Nos.	2	3	5		₹ -		0	0			0 ₹	-	
A.4	Spray Control Valve for 1x100 % HC-PRDS (CDV-138)	Nos.	2	3	5		₹ -		0	0			0 ₹	-	
A.5	Spray Control Valve for 1x30 % IC-PRDS (CDV-11)	Sets	2	3	5		₹ -		0	0			0 ₹	-	
A.6	ORDERING VALUE (A.1 to A.5)						₹ -		₹ -	₹ -			₹ -	₹ -	
B	Site visit for valve installation check to ensure proper valve functionality check after the erection of the valve during the commissioning (cold condition) and during the hot charging of the valve considering 5 nos. of site visit for 2 days each.														
B.1	Charges per visit	1 visit	6	9	15		₹ -			₹ -			0 ₹	-	
B.2	Charges per mandays	1 day	12	18	30		₹ -			₹ -			0 ₹	-	
	ORDERING VALUE (B.1 to B.2)						₹ -		₹ -	₹ -			0 ₹	-	

Note:

1. PLEASE REFER TECHNICAL SPECIFICATION PE-TS-417-142-N101.


2. EACH CONTROL VALVE SHALL BE SUPPLIED WITH THE ACCESSORIES SPECIFIED IN THE RELEVANT DATA SHEETS IN TECHNICAL SPECIFICATION (i.e. commissioning Spares (Gasket+ Gland (stem) packing) & SS Tubing).

3. Bidder shall depute engineer for supervision and site inspection after intimation by BHEL for 2 days time. Addition /deduction in no. of days in site visit shall be considered on prorata basis as per Sl. no. B.2.

4. Additional site visit, if required, shall be considered on prorata basis as per Sl. no. B. above and shall be calculated as per formulae: B.1 x No. of visits + B.2 x No. of days. The prices shall be inclusive of charges of airfare, transport within India, boarding/lodging, meals, visa, insurance etc.

PROJECT: 5x800 MW Yadadri
PACAKGE: - AUX PRDS
ENQUIRY NO. PE/PG/YAD/E-6901/2021, Dated 07.03.22
CIF CONTENT (UNPRICED)

Sl No.	Description	CURRENCY	RATE OF CUSTOM DUTY	SOURCE OF SUPPLY	TOTAL CIF CONTENT
1.0	List of CIF content (if any)				

	TECHNICAL SPECIFICATION FOR AUXILIARY STEAM PRESSURE REDUCING & DESUPERHEATING STATION	SPEC. NO.: PE-TS-417-142-N101		
		SECTION	II	
		REV. NO.	00	DATE 28.02.2022

12.0 SCHEDULE OF TECHNICAL DEVIATION/ CLARIFICATION

S. No.	Document Ref/ Title / Section	Page No.	Clause No.	Description	Deviation/ Clarification

Note:

Bidder may take pre-bid clarifications also in this format (i.e. before submitting the bid), if required.