

BHARAT HEAVY ELECTRICALS LIMITED
HPEP, RAMACHANDRAPURAM, HYDERABAD-32
(Township Administration Department)
Schedule - A - Price bid

Tender Notice No. HY/TA/OT-05/2020-21

Date: 16.01.2021

Name of Work :- Supply & Laying of HDPE pipe line from STP to Nehru Udyan and STP to Sundaravanam Park inside BHEL Township.

Sl. no	Description	Qty	Unit	Rate (in Rs.)	Amount (in Rs)
1	Cutting road and making good the same including supply of extra quantities of materials i.e. aggregate, moorum screening, red bajri and labour required for Bitumen portion. (All the materials are in agency scope).	15.00	Cum	1756.59	26348.85
2	Earth work in excavation in all soils by mechanical means (hydraulic excavators) / drains (not exceeding 1.5m in width or 10 sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 3.00 metre, including getting out the excavated soil and disposal of surplus excavated soil etc all shall be as per the directions of Engineer-in-charge.	1132.00	Cum	130.80	148065.60
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means for hard rock (blasting prohibited) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed etc all as directed by the Engineer-in-charge.	23.00	Cum	490.10	11272.30
4	Filling with available excavated earth (excluding rock) in trenches,plinth,sides of foundation etc. in layers not exceeding 20cm in depth, consolidation each deposited layer by ramming and watering, lead up to 50.00m and lift upto 3.00m.	470.00	Cum	83.80	39386.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering including consolidation by vibrations for all work upto plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20mm nominal size). (All the materials are in the contractor scope only and only river sand shall be used).	7.00	Cum	3202.00	22414.00
6	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3(1cement 1.5 coarse sand 3 grade stone aggregate 20mm nominal size) excluding the cost of centring shuttering finishing and reinforcement All work up to plinth level. (All the materials are in the contractor scope only and only river sand shall be used).	17.00	Cum	4507.98	76635.66
7	Reinforcement for RCC work including straightening, cutting bending placing in position and binding all complete, Cold twisted bars, Reinforcement Fe415 make of SAIL or JINDAL or TATA (All the materials are in the contractor scope only)	2550.00	Kg	53.79	137164.50
8	Brick work FPS brick of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6(1cement :6 coarse sand) (All the materials are in the contractor scope only and only river sand shall be used)	2.00	Cum	3479.70	6959.40
9	Cement Plastering of 12 mm cement plaster of mix:1:6(1 cement : 6 fine sand) (All the materials are in the contractor scope only and only river sand shall be used).	500.00	Sqm	104.30	52150.00
10	Supply & Delivery of 90 mm dia HDPE Pipes with 4.0kg/sq.cm of confirming to IS 4984-1995 including transportation of 90mm diameter as per the direction of Engineer-in-charge. All the necessary fittings and related materials are in contractor scope.	3960.00	Rmt	138.00	546480.00
11	Laying and Jointing of 90 mm dia. HDPE pipes by butt fusion welding as per IS: 7634-partII/1975 as amended from time to time to the alignment and gradient and testing the pipe line to the required pressure, as per the direction of engineer-in-charge. (All the necessary fittings and related materials are in contractor scope).	3960.00	Rmt	36.00	142560.00
12	Supply & Fixing of HDPE pipe of 90mm diameter Fittings confirming to IS 4984-1995 including transportation, as per the direction of engineer-in-charge. . (all the materials including necessary fittings are in the contractor scope only)				
	a) Pipe Ends Long Neck of required size	20.00	Each	121.00	2420.00
	b) MS flanges of required size	20.00	Each	189.00	3780.00
	c) Cap Ends of required size	20.00	Each	83.00	1660.00
	d) Reducer of required size	20.00	Each	188.00	3760.00
	e)TEES of required size	20.00	Each	269.00	5380.00
	f) Bends size of required size	30.00	Each	248.00	7440.00
13	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	8400.00	Sqm	4.82	40488.00

Signature of Tenderer

Accepting Authority

BHARAT HEAVY ELECTRICALS LIMITED
HPEP, RAMACHANDRAPURAM, HYDERABAD-32
(Township Administration Department)
Schedule - A - Price bid

Tender Notice No. HY/TA/OT-05/2020-21

Date: 16.01.2021

Name of Work :- Supply & Laying of HDPE pipe line from STP to Nehru Udyan and STP to Sundaravanam Park inside BHEL Township.

Sl. no	Description	Qty	Unit	Rate (in Rs.)	Amount (in Rs)
14	Dry stone pitching of 15cm x 22.5 cm thick including supply of stones and preparing surface complete etc (All the materials are in the contractor scope only and only river sand shall be used)	300.00	Sqm	313.2	93960.00
15	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc. lead upto 50 m and lift upto 1.5 m :All kinds of soil	40.00	Cum	181.25	7250.00
16	Supplying and Erection of 3-phase, 5 HP submersible Monoblock horizontal Pump set with ISI marked, 5-star rated and capable of total working head of min. 25 mtr to 30 mtrs complete with starter, pannel box , including all necessary fittings etc. Basic material of construction: Impeller : Bronze / SS/CSteel Pump shaft : Stainless Steel Motor shaft : stainless steel// SS/Csteel Motor casing : stainless steel make : Kirloskar/ Crompton Greaves/ CRI Pumps/ KSB Pumps/ Tormac Pumps/ Falcon. all complete as directed by Engineer-in-charge.(all the materials with	4.00	Each	20000	80000.00
17	Supplying, lowering, aligning and fixing of (Non-return) reflex valve (heavy type) including a pair of steel flanges, cost of all jointing materials such as rubber packing, bolts and nuts etc, complete all as directed for (Sample must be approved by Engineer - in- charge) 90 mm dia (All the materials with necessary fittings are in contractor scope only)	2.00	Each	3,763.94	7527.89
18	Supplying and fixing of CI sluice valve(Gate valve), (with cap) complete with bolts, nuts rubber insertions etc complete all as directed by Engineer-in-charge. (Sample must be approved by the Engineer-in-charge). 90 mm dia (All the materials with necessary fittings are in contractor scope only)	4	Each	5,136.73	20546.92
19	Supply and fixing pressure gauge 6kg/sqcm and jointing in Main line with all necessary fittings etc complete all as directed by Engineer-in-charge. (Sample must be approved by the Engineer-in-charge).(All the materials with necessary fittings are in contractor scope only).	4	Each	675.00	2700.00
20	Supplying, installing, testing and commissioning approved make CI body Foot Valve with brass strainer with necessary flanges, nuts and bolts etc., complete on to the suction line.Rate as per the lowest quotation of Bharat Fire Safety Engineers. Makes:Norm 100 mm nominal dia (All the materials with necessary fittings are in contractor scope only)	4	Each	5,100.00	20400.00
21	Supply and laying of 300mm dia NP2 RCC Hume pipe with Collars for Road crossings with all necessary fittings as directed by Engineer in Charge. (All the materials with necessary fittings are in contractor scope only)	50	RMT	630.00	31500.00
22	Supply & laying of one number PVC insulated PVC sheathed steel wire/strip armoured multi stranded Aluminium conductor cable, 4-core 16 sq.mm. 1100V grade confirming to IS, direct in ground including excavation, sand cushioning, protective covering (with shahabad stones) and refilling thr trench etc. as required; complete all as directed by Engineer-in-charge. (All the materials with necessary fittings are in contractor scope only)	765	Metre	248.6	190179.00
23	Supply and making cable end termination with brass compression gland and aluminium lugs for 4 core - 16 sq. mm. PVC insulated and PVC sheathed/ XLPE aluminium conductor cable of 1.1 kV grade; complete all as directed by Engineer-in-charge. (All the materials with necessary fittings are in contractor scope only)	16	Each	119	1904.00

Signature of Tenderer

Accepting Authority

BHARAT HEAVY ELECTRICALS LIMITED
HPEP, RAMACHANDRAPURAM, HYDERABAD-32
(Township Administration Department)
Schedule - A - Price bid

Tender Notice No. HY/TA/OT-05/2020-21

Date: 16.01.2021

Name of Work :- Supply & Laying of HDPE pipe line from STP to Nehru Udyan and STP to Sundaravanam Park inside BHEL Township.

Sl. no	Description	Qty	Unit	Rate (in Rs.)	Amount (in Rs)
24	Supply, fabrication and erection of 1.6mm MS sheet enclosure for power control cubicle panel / boxes with hinges & mechanical locking arrangements etc., including cutting, bending, drilling, welding & reveting etc., complete and painting with 2 coats of red-oxide paint and finished with general purpose oil paint of suitable shade including cost and conveyance of all materials and labour charges; complete all as directed by Engineer-in-charge. (All the materials with necessary fittings are in contractor scope only)	140	Kg.	184	25760.00
25	Supply & fixing of 40A, four pole, 415V isolator, complete with connections, testing & commissioning etc. as required. (All the materials with necessary fittings are in contractor scope only)	4	Each	554	2216.00
26	Supply & connecting of 1.1 kV grade 3 core, 4.0 sq.mm. PVC insulated PVC outer sheathed flat flexible copper conductor cable conforming to IS 694/1990 (make : AVOCAB / FINOLEX / as supplied by pump manufacturer) for submersible pump motors including all incidental charges; complete all as directed by Engineer-in-charge. (All the materials with necessary fittings are in contractor scope only)	450	Metre	131	58950.00
27	Supply & installation of earthing arrangement comprising of 40 mm dia, 3 mm thick GI pipe buried upto a minimum depth of 4.5 mtrs including excavation of pit and filling the pit with homogenous layers of coke/charcoal, salt & sand etc. as required conforming to IS Standards (IS:3043). The earth pit to be provided with brick masonry chamber with hinged cover and watering arrangement; complete in all respects, as directed by Engineer-in-charge. (All the materials with necessary fittings are in contractor scope only)	2	Each	3385	6770.00
28	Providing and fixing 4.00 mm dia annealed copper wire on surface or in recess for connection of earth pits as required; complete all as directed by Engineer-in-charge (All the materials with necessary fittings are in contractor scope only)	110	Metre	87.5	9625.00
29	Providing, installation, testing and commissioning of dual plate non - return valve of following sizes conforming to IS: 5312 complete with rubber gasket, GI bolts, nuts, washers etc as required Makes: Audco / Kirloskar / BDK / H-Shankar / Leader/ Zolotto / Intervolve. 90 mm dia (All the materials with necessary fittings are in contractor scope only)	2	Each	2030	4060.00
Total amount Rs.					1,837,713
Tender %	In words	Figures			
Excess					
Less					
Estimate					
Notes:					
1	Agency has to quote his prices by considering consolidated wages /Bonus payable to workers/ BHEL wages (which consists of state Govt. minimum wages and additional payments), allowances and other statutory dues payable to workers				
2	Agency supervisor shall control the deployed work force, shall not cause any traffic restriction in Township during the movement of agency vehicles in Township. Agency authorised vehicles are only allowed in the BHEL Premises, agency other vehicles are not permitted inside the BHEL Campus.				
3	Agency supervisor shall look after the working areas where the work has been carried out.				
4	The Agency supervisor shall do frequent checking.				
5	Controlling of Tractors, JCB, Traffic, Drivers and deployed work force shall be monitored.				
6	Agency supervisor is the overall in-charge of the work. Single Point of Contact (SPOC) during the work.				
7	Agency supervisor is to ensure workers are posted in their respective posts as per the directions of BHEL officer in-charge and record to be submitted daily.				
8	To ensure all the communication given by BHEL officer is to be passed to the workers promptly.				
9	To ensure required guidance, training etc. is provided to the workers at their respective works beside the regular briefing etc.				
10	Custodian of the daily attendance				
11	Supervisor shall stav at the site until he total work is done and ensures the same for the workers too				

Signature of Tenderer

Accepting Authority

BHARAT HEAVY ELECTRICALS LIMITED
HPEP, RAMACHANDRAPURAM, HYDERABAD-32
(Township Administration Department)
Schedule - A - Price bid

Tender Notice No. HY/TA/OT-05/2020-21

Date: 16.01.2021

Name of Work :- Supply & Laying of HDPE pipe line from STP to Nehru Udyan and STP to Sundaravanam Park inside BHEL Township.

Sl. no	Description	Qty	Unit	Rate (in Rs.)	Amount (in Rs)
12	Any incidents occurred during the work has to bring it to the notice of the BHEL officer in-charge and if necessary depends on the situation report has to submitted to the police station.				
13	Monitor the performance of the workers and their quality of service.				
14	Report of the daily work done shall be submitted daily with duly signed with stamp.				
15	Workers to alert and inform his superiors about any suspicious materials found within the Township Premises.				
16	Supervisor along with supporting workers, Drivers, Tractors, JCB etc., has to report to BHEL Officer in-charge and they have to follow the instructions given by the BHEL Officer in-charge				
17	During any public functions / festivals / sports events / school events / BHEL Management events / any VIP visits / any elections etc., Supervisor has to follow the guidelines given by the BHEL Officer In-charge for Sweeping and Garbage Lifting works				
18	All group gathering by engaged work force / drunk & drive / accidents / group fighting / rash driving etc., has to be taken monitor by the Supervisor				
19	Monitoring of Vehicles control in all required places and report to be submitted to officer				
20	As per the time-to-time instructions given by the BHEL management, supervisor along with their staff has to work with the given instructions.				
21	During the execution of contract, if required, agency shall work on Sundays and holidays also as per the direction of Engineer-in-charge.				
22	Penalty as per the clause 2.1.36 shall be applicable.				

Signature of Tenderer

Accepting Authority