

**BHARAT HEAVY ELECTRICALS LIMITED**

BOILER AUXILIARIES PLANT

RANIPET - 632406

**ESTIMATE****NAME OF WORK : Name of Work: Fan Testing Station Roof covering in Factory****ESTIMATE REF NO : CF/CA/01**

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RS RATE P	RS AMOUNT P
10.2	01		70000	KGS	10.70	749000.00
12.1	02	Providing CORRUGATED G.S SHEET ROOFING fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia. with bitumen & G.I. limpet washers or with G.I.limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto a pitch of 60 degrees) excluding the cost of prulins, rafters and trusses:				
12.1.1	02A	1.00 mm/0.8mm thick with zinc coating not less than 275 gm/m2	2750	SQ.M	108.38	298034.94
13.62.1	03	Providing and Painting with SYNTHETIC ENAMEL PAINT of approved brand and manufacture to give an even shade two or more coats on new work.	70	M.T.	1343.03	94012.10

TOTAL ESTIMATED VALUE 11,41,047.04

CONTRACTOR TENDER PERCENTAGE @ ABOVE / BELOW / AT PAR \_\_\_\_\_%

(Percentage in words )

TOTAL VALUE OF WORK

=====

=====

CONTRACTOR/ TENDERER

ACCEPTING OFFICER