



भारत हेवी इलेक्ट्रिकल्स लिमिटेड  
BHARAT HEAVY ELECTRICALS LIMITED

(A Government of India Undertaking)

**Power Sector Eastern Region**

WBDCL, Sagardighi Thermal Power Project STAGE III (1X660 MW, Unit. 5)  
P.O.: Monigram, Dist.; Murshidabad, W.B.PIN: 742237

Ref: PSER:SOX( SGD): CIVIL :Precast Cover

Date:28.03.2026

To,

-----  
-----  
-----

**Sub:** Casting of RCC precast drain covers and their placement over drains, including cleaning of drains prior to placement wherever required at 1×660 MW SgTPP U#5 Extension Project, BHEL-Sagardighi.

Dear Sir,

With reference to above, please find enclosed herewith above tender document for further need this attention at your end.

Thanking You,

Yours faithfully,

**PALASH MUKHERJEE**  
Engineer/Civil  
Bharat Heavy Electricals Ltd.  
PSER Sagardighi Site, 1X660 MW  
Murshidabad (WB)



(A Government of India Undertaking)

**Power Sector Eastern Region**

WBDCL, Sagardighi Thermal Power Project STAGE III (1X660 MW, Unit. 5)

P.O.: Monigram, Dist.: Murshidabad, W.B.PIN: 742237

Ref: PSER:SOX( SGD): CIVIL :Precast Cover

Date:28.03.2026

**NOTICE INVITING TENDER**

**Sub:** Casting of RCC precast drain covers and their placement over drains, including cleaning of drains prior to placement wherever required at 1x660 MW SgTPP U#5 Extension Project, BHEL-Sagardighi.

Offers are invited for the subject job by the undersigned on behalf of Bharat Heavy Electricals Limited as per the terms and conditions detailed herein.

Following points relevant to the tender may please be noted and complied with:

- Details of tender documents:
  1. Annexure A – Special Terms & conditions of the job
  2. Annexure B – Preamble
  3. Annexure C – No Deviation Certificate
  4. Annexure D – BOQ Cum Rate Schedule
- Date & time of issue of tender document: From 09.00 hrs of 28.03.2026.
- Last date of submission of offer: 30.03.2026 by 15.00 Hrs.
- Cost of tender document: Nil
- Earnest money deposit and Security deposit: Not applicable
- The offers shall be submitted through E-mail (Email ID: adaschowdhury@bhel.in & palash.m@bhel.in ) or by hand to BHEL Site Office, Sagardighi TPP.

COVER NO	SHALL CONTAIN FOLLOWING
<b>COVER-I (TECHNO-COMMERCIAL BID)</b>	Un-priced rate schedule duly signed by the bidder One original copy of each of following should be submitted by the bidder: <ol style="list-style-type: none"><li>a) Covering letter of offer (in bidder's letterhead)</li><li>b) Techno-Commercial Bid (signed copy of NIT/ Enquiry)</li><li>c) Price schedule / Rate schedule – <b>Unpriced</b> but mentioning only <b>quoted / unquoted</b> against each item of price bid/Schedule format (<b>Volume-III</b>)</li><li>d) No deviation certificate in <b>bidder's letterhead</b> as per format given at <b>Annexure - C</b></li><li>e) PAN No. A photocopy of PAN card (Self attested) is to be submitted</li><li>f) GST registration number. A photocopy of GST certificate (Self attested) is to be submitted</li><li>g) PF registration details</li></ol>
<b>Cover -II (PRICE BID/SCHEDULE)</b>	<ol style="list-style-type: none"><li>a) Copy of covering letter as given in Cover-I</li><li>b) Complete price offer in line with prescribed price schedule [<b>Volume-III</b>] duly filled in all respect.</li></ol>

- Since the work shall be executed at BHEL 1X660 MW Sagardighi TPP, Sagardighi, Murshidabad, bidders must get acquainted with the prevailing site conditions before quoting.

*P. Anugm*  
P. ANUGM  
Engineer Civil  
Bharat Heavy Electricals Ltd.  
Sagardighi Site, 1X660 MW  
Murshidabad (WB)



भारत हवी इलेक्ट्रिकल्स लिमिटेड  
BHARAT HEAVY ELECTRICALS LIMITED

(A Government of India Undertaking)

**Power Sector Eastern Region**

WBDCL, Sagardighi Thermal Power Project STAGE III (1X660 MW, Unit. 5)  
P.O.: Monigram, Dist., Murshidabad, W.B.PIN: 742237

**Ref: PSER:SOX( SGD): CIVIL :Precast Cover**

**Date:28.03.2026**

- For any clarification on the tender document, bidder may seek the same in writing through mail within 30.03.2026 by 09.00 Hrs. failing which no further clarification shall be entertained.
- BHEL reserves the right to accept or reject any or all offers without assigning any reasons thereof. BHEL also reserves the right to cancel the Tender wholly or partly without assigning any reason thereof. Also, BHEL shall not entertain any correspondence from bidders in this matter.
- Date and time of opening of tender: 30.03.2026 by 16.00 Hrs.
- In case BHEL decides opening of tender to be 'Public Opening' and in such a case, one authorized representative of the bidder shall be allowed to attend.

For and on behalf of  
BHEL/Sagardighi

Palash Mukherjee  
Engineer-Civil/1x660 MW SgTPP U#5



भारत हेवी इलेक्ट्रिकल्स लिमिटेड  
BHARAT HEAVY ELECTRICALS LIMITED

(A Government of India Undertaking)

**Power Sector Eastern Region**

WBDCL, Sagardighi Thermal Power Project STAGE III (1X660 MW, Unit. 5)  
P.O.: Monigram, Dist.; Murshidabad, W.B.PIN: 742237

Ref: PSER:SOX( SGD): CIVIL :Precast Cover

Date:28.03.2026

ANNEXURE A

### PREAMBLE

- 1.0 This preamble forms part of the tender document and schedule of items. The tenderer should read this preamble carefully before filling up the rates for various items. Clauses of this preamble shall be read in conjunction with GCC and other terms of the tender document and shall have precedence over any contrary statement mentioned any where in the above documents.
- 2.0 The work shall be carried out as per specifications, descriptions of the items in the schedule and or as per engineer's instructions.
- 3.0 Unless specifically mentioned otherwise in the tender document, the tenderer shall quote for the finished items and shall provide for the complete cost towards supply of materials including consumables, labour & other misc. elements that may be required for carrying out the job including transport, layout, rectification, maintenance till handing over, supervision, overheads, profits etc. including all incidental items complete.
- 4.0 The quantities in this schedule are approximate and may vary to any extent or may be deleted altogether. The rate quoted against each item of the schedule shall remain firm till the contract value remains within "+" or "-"15%.
- 5.0 The rates shall be quoted both in figures & words in clear legible writing. No overwriting is allowed. All scoring and cancellations should be countersigned and in case of illegibility, the interpretation of engineer shall be final. All entries shall be in English. The rates quoted are inclusive of all taxes and duties, etc.
- 6.0 The tenderer shall be deemed to have studied detailed specifications and terms & conditions of the tender.
- 7.0 Engineer's decision shall be final & binding on the contractor regarding clarification of items in the schedule with respect to other terms & conditions of the contract.

For and on behalf of  
BHEL/Sagardighi

Palash Mukherjee  
Engineer-Civil/SgTTP Site



भारत हेवी इलेक्ट्रिकल्स लिमिटेड  
BHARAT HEAVY ELECTRICALS LIMITED

(A Government of India Undertaking)

**Power Sector Eastern Region**

WBPDC, Sagardighi Thermal Power Project STAGE III (1X660 MW, Unit. 5)  
P.O.: Monigram, Dist.; Murshidabad, W.B.PIN: 742237

Ref: PSER:SOX( SGD): CIVIL :Precast Cover

Date:28.03.2026

### Special Terms & conditions of the job

These Special Conditions shall be read and construed along with General Conditions of Contract and in case of any conflict or inconsistency between the General & Special Conditions of Contract; the content in this specification shall prevail.

#### 1. SCOPE OF WORK:

Casting of RCC precast drain covers and their placement over drains, including cleaning of drains prior to placement wherever required at 1x660 MW SgTTP U#5 Extension Project, BHEL- Sagardighi.

The work is to be carried out as per relevant IS standards/specifications, and as directed by BHEL Engineer. All materials required for the job will be in the scope of successful bidder.

Required manpower, material, T&Ps, consumables and resources along with one skilled and experience supervisor for execution & completion of job as per BHEL requirement to be provided by the successful bidder

The successful bidder will be responsible for preparing the protocols & other relevant quality documents in line with field quality plan or as per direction of BHEL Engineer.

In addition to above, following are also in the scope of work of contractor:

- Labour license and group insurance of the workmen employed by the contractor and other statutory requirements shall be complied, as applicable, by the contractor.
- All labour rules, factories act, statutory requirements to be strictly adhered by the contractor.
- Arranging gate passes is in the contractor's scope, however BHEL shall provide necessary supports if required.
- All Statutory procedure (wage payment, Gate pass, medical certificate, insurance, PF, UAN, accommodation, transportation etc.) for payment compliance as per govt procedure in the scope of contractor.
- Any unrest / strike / IR to be handled by the contractor.
- All PPE kit in the scope of contractor.
- Contractor must comply with BHEL standard safety policy.
- The Contractor shall be responsible for safety of his workmen, materials and equipment deployed at site
- Prevailing BHEL HSE norms shall be strictly adhered by the contractor.
- Job must be executed by contractor as per BHEL FQP and BHEL standard quality policy in consultation with BHEL Engineer.
- Quantities mentioned in the BOQ cum rate schedule/price schedule may vary upto any extent. However, contractor's quoted rate shall remain firm for the entire contract period.

#### 2. TAXES, DUTIES ETC: As per BHEL General Conditions of Contract

#### 3. REVISION OF ACCEPTED RATES/PRICE/OVER RUN CHARGES:

*P. Anurag*  
**PALASH MUKHERJEE**  
Engineer/Civil  
Bharat Heavy Electricals Ltd.  
Sagardighi Site, 1X660 MW  
Murshidabad (WB)



**Ref: PSER:SOX( SGD): CIVIL :Precast Cover**

**Date:28.03.2026**

No revision of rates/over run charges shall be paid to the contractor in the event of the completion period getting extended for any reason whatsoever.

**4. CONSTRUCTION WATER & ELECTRICITY:**

Construction water and electric power supply, if required for the job, will be provided free of cost.

**5. COMPLETION PERIOD:**

Total work in all respect is to be completed within 10 (Ten) days from the date of issue of LOI/WO.

**6. TERMS OF PAYMENT:**

95% of the payment shall be released after completion of the work in all respects, duly certified by the BHEL Engineer. All admissible recoveries/adjustments, if any shall be made from the bill. Payment shall be made within 30 days from the date of receipt of a correct and complete invoice at the BHEL site office, along with the BHEL Engineer's certification / jointly signed measurement sheet, PF compliance documents, and other statutory documents, subject to their completeness and correctness in all respects.

The balance 5% of the payment shall be released after expiry of the guarantee period, which shall be a minimum of 1 (one) month from the date of completion of the entire work, duly certified by BHEL

Measurements shall be recorded as per the relevant clauses of the BHEL General Conditions of Contract (GCC) and shall be certified by the BHEL Engineer for the actual work executed. Payment shall be made after deduction of statutory taxes, duties, and other applicable deductions as per prevailing rules from time to time.

Payment shall be made through RTGS / Bank Cheque.

Amount on account of GST will be reimbursed on submission of required documents/challan.

**7. SECURITY DEPOSIT:** Not applicable.

**8. HEALTH, SAFETY & ENVIRONMENT:**

Contractor has to comply with minimum HSE requirements as applicable for IOCL, Paradip Refinery Project.

**9. TERMINATION OF CONTRACT:**

In case at any point of time, if it is observed that the contractor is not fulfilling the requirement/ requirements stipulated in the contract or is not complying BHEL requirement in terms of quality and progress for timely completion of works under this contract, BHEL reserves the right to terminate this contract for which 3 days advance notice will be served to the contractor. However, prior to issuance of this advance termination notice, contractor will be given enough opportunities for course correction. At least, 3 successive letters of warnings within a gap of 1 day will be issued for this purpose

**10. GUARANTEE/WARRANTEE:**

In this type of precast slab casting work, proper surface finishing shall be ensured. The finished surface shall be free from any undulations and shall allow proper seating in position. Any deviation in level or



भारत हेवी इलेक्ट्रिकल्स लिमिटेड  
BHARAT HEAVY ELECTRICALS LIMITED

(A Government of India Undertaking)

**Power Sector Eastern Region**

WBPDC, Sagardighi Thermal Power Project STAGE III (1X660 MW, Unit. 5)  
P.O.: Monigram, Dist.: Murshidabad, W.B.PIN: 742237

**Ref: PSER:SOX( SGD): CIVIL :Precast Cover**

**Date:28.03.2026**


presence of undulation shall not be accepted. It shall also be ensured that all works are completed prior to the onset of the monsoon.

In the event of any damage or breakage, the responsibility shall rest with the contractor/vendor, who shall repair or replace the same at their own cost. No financial implication shall be borne by BHEL in this regard.

Although the work shall be carried out under the overall supervision of BHEL, the contractor/agency shall remain fully responsible for the quality of workmanship and execution of the work. The contractor shall guarantee the completed work for a minimum period of one (01) month from the date of completion, as certified by BHEL. Any settlement, unevenness, or defects observed during the guarantee period shall be rectified by the contractor at their own cost, without any additional financial implication to BHEL.

Any other terms and conditions not specifically covered herein shall be governed by the BHEL General Conditions of Contract."

For and on behalf of BHEL.

  
**PALASH MUKHERJEE**  
Engineer/Civil  
Bharat Heavy Electricals Ltd.  
PSER Sagardighi Site, 1X660 MW  
Murshidabad (WB)

**NO DEVIATION CERTIFICATE****(To be submitted in the Bidder's letter head)**

To,  
 The Project Director,  
 POWER SECTOR- EASTERN REGION  
 WBPDC, Sagardighi Thermal Power Project  
 STAGE III (1x660 MW, Unit. 5)  
 P.O.: Monigram, Dist; Murshidabad, W.B.PIN: 742237

Sub	No Deviation Certificate.	
Job	<b>Casting of RCC precast drain covers and their placement over drains, including cleaning of drains prior to placement wherever required at 1x660 MW SgTPP U#5 Extension Project, BHEL-Sagardighi.</b>	
	1.0	BHEL's NIT Ref: PSER:SOX( SGD): CIVIL :Precast Cover dated- 28.03.2026
	2.0	All other pertinent issues till date.

Dear Sirs,

With reference to above, this is to confirm that as per tender conditions, we have visited site before submission of our offer and noted the job content & site conditions etc. We also confirm that we have not changed/ modified the tender documents as appeared in the website/ issued by you and in case of such observance at any stage, it shall be treated as null and void.

We hereby confirm that we have not taken any deviation from tender clauses together with other references as enumerated in the above referred NIT. We hereby confirm our unqualified acceptance to all terms & conditions, unqualified compliance to technical specification, integrity pact (if applicable) and acceptance to reverse auctioning process.

In the event of observance of any deviation in any part of our offer at a later date whether implicit or explicit, the deviations shall stand null & void.

We confirm to have submitted/uploaded offer/documents in accordance with tender instructions with acceptance of the terms & conditions of the tender by us and as per aforesaid references.

Thanking you,

Yours faithfully,

*P. Munim*  
**PALASH MUKHERJEE**  
 Engineer/Civil  
 Bharat Heavy Electricals Ltd.  
 PSER Sagardighi Site, 1X660 MW  
 Murshidabad (WB)

(Signature, Date & Seal of the authorized  
 Representative of the bidder)

**BOQ cum Rate Schedule (Annexure-D)**


Ref Tender Notice No. PSER:SOX(SGD): CIVIL :P. Last Cover, Date:28.03.2026

Sub: Casting of RCC precast drain covers and their placement over drains, including cleaning of drains prior to placement wherever required at 1x660 MW SgTPP U#5 Extension Project, BHEL-Sagardighi.

ST No.	Description of Item	Unit	Qty.	Rate ( in INR)	Amount ( In INR)
1	CONCRETE WORK: Transportation from Batching Plant and placing concrete work including cost of labour, materials (unless otherwise specified in BOQ/contract specification) and equipment for handling, transportation, placing, vibrating and curing (excluding cost of centering, shuttering and reinforcement) with mechanised equipments like transit mixer, concrete pump etc. complete as per drawing, specifications and as per direction of engineer in charge for the following: (RMC WITH REQUIRED ADDITIVES/PLASTICIZER/SUPERPLASTICIZER SHALL BE PROVIDED BY BHEL AT BATCHING PLANT IN PROJECT PREMISES . TRANSPORTATION FROM THE BATCHING PLANT UP TO THE POURING POINT SHALL BE UNDER THE SCOPE OF CONTRACTOR)				
1a	Providing and laying Design Mix cement concrete conforming to IS:456 & IS 10262-2009 for reinforced concrete works with coarse sand and graded hard stone aggregate of 20mm nominal size in foundations/substructure, grade slab, paving, drains, under floors etc at all level below finished floor level, any shape, position or thickness etc complete including use of plasticizer/ superplasticizer conforming to IS:9103 (latest) to achieve required slump in concrete all complete, setting in position with cement sand mortar (1:3), filling the gaps between adjacent precast units as per specification & drawing for the following.				
i	M 25 Grade	Cum	20		
2	FORMWORK: Providing, fixing and removing formwork at all elevations for all structures, as per specifications and including all labour, material, scaffoldings and centering etc. complete as per drawing, specifications and as per direction of engineer in charge for the following:				
2a	Fairface form work with good quality water proof ply wood of minimum 12mm thickness and smooth surface above finished ground floor level for columns, beams, suspended floors, roofs, lintels, cantilevers, staircases, landings, balconies, etc. including chamfering of edges as per drawing for all heights as per specification, drawing and instruction of engineer in charge.	Sqm	220		
3	REINFORCEMENT WORK : Reinforcement work including all labour, material (unless otherwise specified in BOQ/contract specification), equipment, transportation, handling etc at all level as per specification, drawings and as directed by engineer - in - charge for the following:.				
3a	Straightening, cutting, bending, placing in position at all level, binding in position of steel reinforcements of TMT steel of grade Fe-500D or 500EQR conforming to IS:1786 including cost of reinforcement steel, binding wire, labour, scaffolding, transportation to & from stores, unloading of materials etc. complete all as per specifications, drawings and as directed by Engineer. (BHEL WILL BE PROVIDED REINFORCEMENT STEEL AS FREE OF COST AS PER TCC)	MT	2		
4	Providing manpower services for surface dressing, levelling and drain cleaning as required prior to placement of precast slabs over drains, as per instructions of BHEL Engineer-in-Charge.	Man-days	100		

**Total in Rs.**

Total (Excluding GST) is Rupees ..... Or y.

  
**ANIL KUMAR**  
 Engineer/Civil  
 1x660 MW SgTPP  
 U#5 Extension Project  
 BHEL-Sagardighi  
 BHEL