

**TENDER SPECIFICATION  
BHEL PSSR SCT 1989**

**for**

**Levelling and Grading works in CHP area  
at**

**5x800MW Yadadri Thermal Power Plant,  
Veerlapalem Village, Dameracherla Mandal,  
Nalgonda District, Telangana State**

**VOLUME –II  
PRICE BID**



**BHARAT HEAVY ELECTRICALS LIMITED**


(A Government of India Undertaking)

Power Sector – Southern Region

Tek Towers, No.11, Old Mahabalipuram Road,  
Okkiyam Thoraipakkam, Chennai - 600097

**TENDER SPECIFICATION CONSISTS OF**

**Tender Specification**



## PRICE BID

---

<b>CONTENTS</b>	
<b>Description</b>	<b>No. of pages</b>
Part A of Price Bid: Instructions to the Bidders	01
Part B : Format for total amount (Enclosed as a separate Excel File in BHEL NIC e-Procurement portal for the subject tender)	(Separate Excel File)
Part C: Bill of quantities with weightage for amount of each items with respect to the total quoted price	03

**PART A**

**Instruction to Bidders:**

1. The quantity indicated in the BOQ in Part C of Price Bid is approximate only and is liable for variation. Payment will be as per actual quantity executed and as certified by BHEL Engineer.
2. Tenderers are requested to affix their company seal and authorized signature in all pages.
3. Bidders shall quote 'Total Amount' in the format enclosed as a separate Excel File in BHEL NIC e-Procurement portal for the subject tender and upload the same under 'Packet details - > Tender covers -> Finance '(Cover Type Description – Price Bid)' and same shall be taken into account for evaluation and awarding and hence, shall be complete in all respect for the full scope of work defined in specification and in accordance with terms & conditions of the tender. Any other entry elsewhere in the price bid shall be treated as Null and Void. Quoting of rates in any other form/formats will not be entertained.
4. The above mentioned 'Total amount' is for the entire Bill of Quantity (BOQ) given in Part -C of the Price Bid.
5. BHEL has pre-fixed the weightages for the amount of individual items of Bill of Quantity with respect to the 'Total Amount' in Part C of Price Bid.
6. Based on the pre-fixed weightages, the amount for the individual items of the Bill of Quantity shall be arrived at. This amount shall be rounded off to the nearest rupee.
7. Based on the quantities of individual item and the amount arrived in Sl. No: 6 above, unit rate of individual items shall be derived. This unit rate shall be rounded off to four decimal places.
8. Bidders to note that this is an item rate contract. Payment shall be made for the actual quantities of work executed as certified by BHEL Engineer at the unit rate arrived at as per Sl No.7 above
9. The quantities given in the contract are tentative and may change to any extent (both in plus side and minus side). The derived item rates (as mentioned above) for individual items shall remain firm irrespective of any variations in the individual quantities. No compensation becomes payable in case the variation of the final executed contract value is within the limit of Minus (-) 30% of awarded contract value

**Part C : Bill of Quantities**

**Tender Specification BHEL:PSSR:SCT:1989 for Levelling and Grading works in CHP area  
at 5 X 800 MW Yadadri TPS**

Ref.No.	Description	Unit of Measurement	Qty.	Weightage for amount of each item (Nearest to the 7 decimal points) w.r.t the total amount
2600.0	LEVELING & GRADING: Levelling & grading works including all labour, material (unless otherwise specified in BOQ/contract specification), equipment etc. as per specification, drawings and as directed by engineer - in - charge for the following:	--		
2601.0	Cutting of trees having girth more than 300 mm measured at a height of 1m above ground level including removal of roots, stacking the serviceable material like trunks, branches etc at specified area within the plant boundary and disposal of unserviceable parts/materials within a lead upto 1km etc all complete.	--		
a	300 mm upto 600 mm girth.	EACH	25	.0000594
b	601 mm upto 1200 mm girth.	EACH	25	.0002661
c	1200mm and above.	EACH	5	.0002477
A2601	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 300mm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 500m outside the periphery of the area cleared.	SQM	80,000	.0038763
2603.0	Earth work in excavation upto any depth below ground level in all types of soil including moorum, ash which can be excavated by any means for grading including setting out, levelling, dewatering (wherever required), dressing the sides & bottom, levelling to grade, all lifts, ramming/compacting the excavated bottom/graded surface, stacking/disposal of surplus excavated materials within a lead upto 1km, spreading/levelling of disposed materials etc all complete as per specification, drawing and as directed by the engineer-in-charge. (Exclusive of Royalty/ Seigniorage charges etc.)	CUM	75,000	.0524338

## Part C : Bill of Quantities

### Tender Specification BHEL:PSSR:SCT:1989 for Levelling and Grading works in CHP area at 5 X 800 MW Yadadri TPS

Ref.No.	Description	Unit of Measurement	Qty.	Weightage for amount of each item (Nearest to the 7 decimal points) w.r.t the total amount
2604.0	Earth work in excavation upto any depth below ground level in soft rock (rock without any recovery of excavated materials in the form of hard stone/boulder) including weathered rock which can be excavated by means of crow bar, pick axe, pneumatic rock breaker attachment with excavator machine etc (but does not require chiselling or blasting) for grading including setting out, levelling, dewatering (wherever required), dressing the sides & bottom, all lifts, ramming/compacting the excavated bottom, stacking/disposal of surplus excavated materials within a lead upto 1km, spreading/levelling of disposed materials etc all complete as per specification, drawing and as directed by the engineer-in-charge. (Exclusive of Royalty/ Seigniorage charges etc.)	CUM	150,000	.1941609
2605.0	Earth work in excavation upto any depth below ground level in hard rock requiring blasting (but excluding controlled blasting) including wedging, line drilling, pre shearing etc as required for grading, setting out, levelling, dewatering (wherever required), dressing the sides & bottom, all lifts, necessary licenses/statutory clearances for blasting, supply, storage & handling of blasting materials, stacking/disposal of surplus excavated material within a lead upto 1km, spreading / levelling of disposed materials etc all complete as per specification, drawing and as directed by the engineer-in-charge.	CUM	200,000	.3627105
2606.0	Earth work in excavation upto any depth below ground level in hard rock requiring controlled blasting including wedging, line drilling, pre shearing etc as required for grading, setting out, levelling, dewatering (wherever required), dressing the sides & bottom, all lifts, necessary licenses/statutory clearances for blasting, supply, storage & handling of blasting materials, stacking/disposal of surplus excavated materials within a lead upto 1km, spreading / levelling of disposed materials etc all complete as per specification, drawing and as directed by the engineer-in-charge. (Exclusive of Royalty/ Seigniorage charges etc.)	CUM	200,000	.3585574
2610.0	Extra over ST No. 2601 to 2609 for carriage of material/earth for every 500m or part thereof beyond an initial lead of 1km.	--		
b	Carriage for disposal of serviceable/unserviceable material/ earth to stockyard	CUM	400,000	.0276878

**Part C : Bill of Quantities**

**Tender Specification BHEL:PSSR:SCT:1989 for Levelling and Grading works in CHP area  
at 5 X 800 MW Yadadri TPS**

<b>Ref.No.</b>	<b>Description</b>	<b>Unit of Measurement</b>	<b>Qty.</b>	<b>Weightage for amount of each item (Nearest to the 7 decimal points) w.r.t the total amount</b>
<b>TOTAL Weightage</b>				1.0