Sohams Foundation Engg. Pvt. Ltd.Mumbai

SFE

Project :- Carrying Out Geo-Technical and Geo-Physical Investigations For Kaiga 5&6,Kaiga Site,PO Kaiga,Karwar, Uttara Kannada Dist. Karnataka State

Format No : SFE/KAIGA5&6/RD/01

Client:-NPCIL

Job No :- | Created By :- HPG | Created On:-

GEOLOGICAL LOG OF BORE HOLE

Hole No :- 110

Sheet : 4 OF 4

Feature: =

Location : TB-5 | Co-Ordinates :X-440226.0394,Y-1642944.9270 | GWL:-1.280m

Angle with vertical : 0° | Collar Elevation : | Existing Ground Elevation : 96.356m

Total depth : 56.10m | Type (s) of core barrel : D.Tube | Drilling Agency : SFE

Started :3 / 5 / 2018 | Completed : 8 / 7 / 2018

Depth , m	Elevation	Lithoiog: Description	Size of core pieces: < 10 mm	<10 to 25 mm	25 to 75 mm	75 to 150 mm	> 150 mm	Log	Percent Core recovery: 0-20	20-40	40-60	60-80	80-100	Type of Bit	R.Q.D . %	Facture Frequency per, m	SPT: SPT No	SPT Value: N1	N2	N3	N4	N	Drill Water loss: Partial	Complete	Permeability: Test section	lugeon	Penetration Rate,cm/hr	Special observations & interpretations
		SLIGHTLY WEATHERED LIGHT GREY GRANITE			216.221	218.219.220	215.217				92.88			NX Diamond	81.10												
56.10	40.256																										

SIGNATURE	SOHAMS		NPCIL	
	Logged By (Geologist)	Checked By (QA)	Civil	(QA)

Sohams Foundation Engg. Pvt. Ltd.Mumbai

SFE

Project :- Carrying out Geo-Technical and Geo-Physical investigasions for Kaiga 5&6,Kaiga Site, Karwar, Uttara Kannada Dist.Karnataka State

Format No:- SFE / KAIGA 5 & 6 / RD / 01

Client:-NPCIL

Job No :-

Created By :-

Created On:-

Hole No :- 113

GEOLOGICAL LOG OF BORE HOLE

Sheet : 1 of 4

Feature: =

Location : TB-6

Co-Ordinates :X-440322.6295,Y1642970.8180

GWL:- 4.300m

Angle with vertical : 0°

Collar Elevation :

Existing Ground Elevation : 97.745m

Total depth : 65m

Type (s) of core barrel : D.Tube

Drilling Agency : S.F.E. Pvt Ltd.

Started : 2 / 7 / 2018

Completed : 3 / 8 / 2018

Depth , m	Elevation	Litholog: Description	Size of core pieces: < 10mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	150 mm	Log	Percent Core recovery: 0-20	20-40	40-60	60-80	80-100	Type of Bit	R.Q.D . %	Facture Frequency per, m	SPT: SPT No	SPT Value: N1	N2	N3	N4	N	Drill Water loss: Partial	Complete	Permeability: Test section	lugeon	Penetration Rate,cm/hr	Special observations & interpretations
0.00														NX Diamond													
1.50	96.245	REDDISH COLOUR MURUM																8	9	11	-	20					3.17	
1.95																											
4.50	93.245	RED COLOUR LATERITIC SOIL																10	12	21	-	33					1.18	
4.95																											
7.50	90.245																										0.48	
10.5	87.245																										0.44	
13.5	84.245	Sand																									0.56	
16.0	81.745																										0.57	
18.5	79.245	LIGHT GREEN HIGHLY WEATHERED GRANITE	1	5,3,4	SP,SP,6				54.8						15.6												
22.5	75.245	LIGHT GREEN MODERATELY TO HIGHLY WEATHERED GRANITE		7,9,11,13	8,18,12	SP			17						7.25												

SIGNATURE	Sohams		NPCIL	
	Logged By (Geologist)	Checked By (QA)	Civil	(QA)

Sohams Foundation Engg. Pvt. Ltd.Mumbai

-SFE-

Project :- Carrying out Geo-Technical and Geo-Physical investigasions for Kaiga 5&6,Kaiga Site, Karwar, Uttara Kannada Dist.Karnataka State

Format No:- SFE / KAIGA 5 & 6 / RD / 01

Client:-NPCIL

Job No :-

Created By :-

Created On:-

Hole No :- 113

Sheet : 2 of 4

Feature: =

GEOLOGICAL LOG OF BORE HOLE

Location : TB-6

Co-Ordinates :X-440322.6295,Y1642970.8180

GWL:- 4.300m

Angle with vertical : 0°

Collar Elevation :

Existing Ground Elevation : 97.745m

Total depth : 65m

Type (s) of core barrel : D.Tube

Drilling Agency : S.F.E. Pvt Ltd.

Started : 2 / 7 / 2018

Completed : 3 / 8 / 2018

Depth , m	Elevation	Litholog: Description	Size of core pieces: < 10mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	150 mm	Log	Percent Core recovery: 0-20	20-40	40-60	60-80	80-100	Type of Bit	R.Q.D . %	Facture Frequency per, m	SPT: SPT No	SPT Value: N1	N2	N3	N4	N	Drill Water loss: Partial	Complete	Permeability: Test section	lugeon	Penetration Rate,cm/hr	Special observations & interpretations
22.5																												
		LIGHT GRAY MODERATELY WEATHERED GRANITE			14,19	15,16,17	SP,18			48.5				NX Diamond		21.5												
24.5	73.245				SP,20,22	21,23,24,25	SP			41.33						28.66												
26.0	71.745				26 TO 34	35				64						64												
27.0	70.745			41	36,37,38,39,42	40	SP			26.5						9.5												
29.0	68.745				43,SP,44		SP			29.3						NIL												
30.5	67.245	BROWN TO GRAY MODERATELY WEATHERED GRANITE			45		SP			16						NIL												
32.0	65.745				SP,46,47,48	49,50	SP			33.33						10.6												
33.5	64.245					51	SP			16						NIL												
35.0	62.745	BROWNISH HIGHLY WEATHERED GRANITE			52,SP		SP			22.66						NIL												
36.5	61.245				SP,53,54		SP			22.66						NIL												
38.0	59.745	LIGHT GRAY TO GREEN MODERATELY WEATHERED GRANITE		59	SP,55,56,58	57	SP			45						21												
39.0	58.745																											

Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	(QA)

Sohams Foundation Engg. Pvt. Ltd.Mumbai

SFE

Project :- Carrying out Geo-Technical and Geo-Physical investigasions for Kaiga 5&6,Kaiga Site, Karwar, Uttara Kannada Dist.Karnataka State

Format No:- SFE / KAIGA 5 & 6 / RD / 01

Client:-NPCIL

Job No :- | Created By :- | Created On:-

GEOLOGICAL LOG OF BORE HOLE

Hole No :- 113
Sheet : 3 of 4
Feature: =

Location : TB-6 | Co-Ordinates :X-440322.6295,Y1642970.8180 | GWL:- 4.300m
Angle with vertical : 0° | Collar Elevation : | Existing Ground
Total depth : 65m | Type (s) of core barrel : D.Tube | Elevation : 97.745m
Started : 2 / 7 / 2018 | Completed : 3 / 8 / 2018 | Drilling Agency : S.F.E. Pvt Ltd.

Depth , m	Elevation	Litholog: Description	Size of core pieces: < 10mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	150 mm	Log	Percent Core recovery: 0-20	20-40	40-60	60-80	80-100	Type of Bit	R.Q.D. %	Facture Frequency per, m	SPT: SPT No	SPT Value: N1	N2	N3	N4	N	Drill Water loss: Partial	Complete	Permeability: Test section	lugeon	Penetration Rate,cm/hr	Special observations & interpretations
40.0	57.745	LIGHT GRAY TO GREEN MODERATELY WEATHERED GRANITE			60,61		SP			62				NX Diamond	NIL													
41.0	56.745				62,66	64,65	SP,63			69					47													
42.5	55.245				69	63,67,70	SP		38.66						NIL													
44.0	53.745				81,82,80	SP,71 TO 75	75,77,78,79		49.33						46.66													
45.5	52.245		SP		83,84,85,86		SP		32						12													
47.0	50.745		89		87	SP			35.33						15.33													
48.5	49.245				91,92	90,93	SP		45.33						14													
50.0	47.745	LIGHT GRAY TO GREEN MODERATELY WEATHERED GRANITE			94,95,90,97		SP		40.66						NIL													
51.5	46.245				98		SP		42						NIL													
53.5	44.245				100,103 TO 108	101,102	99,SP		49.5						39.5													
55.0	42.745			109		110	SP		20.66						10													
56.5	41.245					111	SP		49.33						6.66													
									85						39													

SIGNATURE	Sohams		NPCIL	
	Logged By (Geologist)	Checked By (QA)	Civil	(QA)

Sohams Foundation Engg. Pvt. Ltd.Mumbai

SFE

Project :- Carrying out Geo-Technical and Geo-Physical investigasions for Kaiga 5&6,Kaiga Site, Karwar, Uttara Kannada Dist.Karnataka State

Format No:- SFE / KAIGA 5 & 6 / RD / 01

Client:-NPCIL

Job No :-

Created By :-

Created On:-

GEOLOGICAL LOG OF BORE HOLE

Hole No :- 113

Sheet : 4 of 4

Feature: =

Location : TB-6

Co-Ordinates :X-440322.6295,Y1642970.8180

GWL:- 4.300m

Angle with vertical : 0°

Collar Elevation :

Existing Ground

Total depth : 65m

Type (s) of core barrel : D.Tube

Elevation : 97.745m

Started : 2 / 7 / 2018

Completed : 3 / 8 / 2018

Drilling Agency : S.F.E. Pvt Ltd.

Depth , m	Elevation	Description	Size of core pieces: < 10mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	150 mm	Log	Percent Core recovery: 0-20	20-40	40-60	60-80	80-100	Type of Bit	R.Q.D , %	Facture Frequency per, m	SPT: SPT No	SPT Value: N1	N2	N3	N4	N	Drill Water loss: Partial	Complete	Permeability: Test section	lugeon	Penetration Rate,cm/hr	Special observations & interpretations
57.50	40.245	LIGHT GRAY TO GREEN MODERATELY WEATHERED GRANITE			117,118 SP,119	113 TO 116 SP	112,SP				85			NX Diamond	39												
58.00	39.745					120	SP				50				NIL												
60.50	37.245				SP	121,122,123,124	SP,SP,SP				55.2				12.4												
63.00	34.745				129,130,131	127,128,132,SP	125,126,SP				47.2				31.2												
65.00	32.745				133,134,SP	SP,138,135	136,137,138				54.75				27.75												

SIGNATURE	Sohams		NPCIL	
	Logged By (Geologist)	Checked By (QA)	Civil	(QA)



DETAILS OF BORE HOLES

BORE HOLE NO.	LOCATION	X-COORD.	Y-COORD.	FOUNDING LEVEL (EL) IN M.	DEPTH OF BORE HOLE (M) FROM FOUNDING LEVEL OR WEATHERED ROCK LEVEL WHICHEVER IS LOWER
BH-1		1M←(5)	11M↑(h2)	92.0	20.0
BH-2		5M←(9)	3M↓(e2)	92.0	20.0
BH-3	NDCT-5A	1M←(5)	1M↑(d2)	92.0	20.0
BH-4		4M←(1)	3M↓(e2)	92.0	20.0
*BH-5		0.5M←(3)	3.5M↓(e2)	92.0	20.0
BH-6		6M←(6)	11M↑(h2)	92.0	20.0
BH-7		9M←(3)	3M↓(e2)	92.0	20.0
BH-8	NDCT-5B	6M←(6)	1.5M↑(a2)	92.0	20.0
BH-9		1M←(10)	3M↓(e2)	92.0	20.0
*BH-10		5.5M←(8)	3.5M↓(e2)	92.0	20.0
BH-11		5M←(19)	11.5M↑(h2)	92.0	20.0
BH-12		11M←(22)	3M↓(e2)	92.0	20.0
BH-13	NDCT-6A	4M←(19)	1.5M↑(a2)	92.0	20.0
BH-14		1M←(15)	3M↓(e2)	92.0	20.0
*BH-15		4M←(19)	3.5M↓(e2)	92.0	20.0
BH-16		(30)	11M↑(h2)	92.0	20.0
BH-17		4M←(34)	3M↓(e2)	92.0	20.0
BH-18	NDCT-6B	0.5M→(30)	1.5M↑(a2)	92.0	20.0
BH-19		1M←(24)	3M↓(e2)	92.0	20.0
*BH-20		1M←(34)	3.5M↓(e2)	92.0	20.0
BH-21	CCWPH-5	6.5M←(11)	6M↑(m2)	92.0	20.0
*BH-22	CCWPH-6	6M→(13)	6M↑(m2)	90.0	20.0
BH-23	CHLORINATION PLANT D/M FILTERATION PLANT AREA	6M→(6)	8M↑(k1)	96.7	20.0
BH-24		10M→(21)	d	96.7	20.0
BH-25		5.5M→(3)	5.5M↓(k2)	94.0	20.0
BH-26		8.5M←(13)	(12)	94.0	20.0
BH-27	TUNNEL	10.5M←(19)	12M↑(1)	92.0	20.0
BH-28		2M→(22)	(1)	92.0	20.0
BH-29		3M→(28)	7M↑(h)	92.0	20.0
*BH-30		7M→(10)	3M↓(i)	96.5	40.0
BH-31	IDCT-5A	6.5M←(7)	2M↓(j)	96.5	40.0
*BH-32		7M←(20)	3M↓(i)	96.5	40.0
BH-33	IDCT-5B	6M→(21)	2M↓(j)	96.5	40.0
*BH-34		2M←(26)	2M↓(i)	96.5	40.0
BH-35	IDCT-6B	2M←(27)	2M↓(j)	96.5	40.0
*BH-36		2M←(30)	3M↓(i)	96.5	40.0
BH-37	IDCT-6A	3M→(24)	2M↑(j)	96.5	40.0
*BH-38	FWPH	(18)	13M↑(n)	89.9	20.0
BH-39	SREH-5	9.5M→(21)	3.5M↓(m)	96.7	20.0
*BH-40	SRPH-5	1M←(23)	3M↑(m)	92.5	20.0
BH-41	SRPH-6	10.5M→(24)	3M↑(m)	92.5	20.0
*BH-42	SREH-6	(26)	3M↓(m)	96.7	20.0
BH-43	PCTL	3.5M→(27)	1M↓(n)	92.0	20.0
BH-44	TUNNEL	7M←(17)	(q)	92.0	20.0
*BH-45	STACK	1M←(16)	7.5M↑(f)	88.5	20.0
BH-46	D20 PLANT	3M←(21)	10M↑(f)	96.7	20.0
BH-47		1.5M←(23)	10M↑(f)	96.7	20.0
*BH-48	NFSB	8.5M←(12)	6M↑(s)	96.7	20.0
BH-49	SMR	1M←(16)	6.5M↓(f)	94.8	20.0
BH-50	D20 PLANT	1M→(22)	7.5M↑(s)	96.7	20.0
*BH-51	FOSA-6	3.5M←(25)	4.5M↓(s)	94.5	20.0
BH-52	FOSA-5	1M←(19)	4.5M↓(s)	94.5	20.0
BH-53	F/M W/SHOP	8.5M→(A)	3M↓(s)	96.7	20.0
*BH-54		2.5M←(16)	(s)	91.0	40.0
BH-55	WMP	8M←(18)	(s)	91.0	40.0
*BH-56		1.5M←(2)	(s)	91.0	40.0
BH-57	D20 PLANT	1.5M←(23)	8.5M↑(t)	96.7	20.0
*BH-58	WMP	8M←(18)	(t)	91.0	40.0
BH-59		5M←(19)	(t)	91.0	40.0
BH-60	D20 PLANT	3.5M→(2)	5.5M↓(t)	96.7	20.0
BH-61		2M→(4)	1M↓(u)	84.0	100.0
BH-62	NB-5	7M←(16)	1M↓(u)	84.0	100.0
BH-63		4.5M→(17)	1M↓(u)	84.0	100.0
BH-64		1M←(19)	0.5M↓(u)	84.0	100.0
BH-65	NB-6	7M←(21)	0.5M↓(u)	84.0	100.0
BH-66		1M←(14)	6.5M↓(v)	84.0	100.0
BH-67	NB-5	7M←(16)	5.5M↓(w)	84.0	100.0
BH-68		6M→(17)	5.5M↓(w)	84.0	100.0
BH-69		0.5M←(19)	5.5M↓(w)	84.0	100.0
BH-70	NB-6	4.5M←(21)	6M↓(v)	84.0	100.0
BH-71		6.5M→(22)	2.5M↓(w)	84.0	100.0

BORE HOLE NO.	LOCATION	X-COORD.	Y-COORD.	FOUNDING LEVEL (EL) IN M.	DEPTH OF BORE HOLE (M) FROM FOUNDING LEVEL OR WEATHERED ROCK LEVEL WHICHEVER IS LOWER
BH-72	SAB-6B	2M→(2.5)	5.5M↓(w)	90.0	35.0
BH-73	SAB-5B	9M←(13)	5.5M↓(w)	90.0	35.0
BH-74	NB-5	4M→(12)	2.5M↓(w)	84.0	100.0
*BH-75	SAB-5B	5.5M←(13)	6M↑(y)	90.0	35.0
BH-76		4.5M→(12)	6M↑(y)	84.0	100.0
*#BH-77	NB-5	10.5M→(14)	(x)	84.0	100.0
BH-78		5.5M←(16)	8M↓(K)	84.0	100.0
*BH-79		4.5M→(17)	(x)	84.0	100.0
BH-80		3.5M←(19)	8M↓(x)	84.0	100.0
*#BH-81	NB-6	(20)	(x)	84.0	100.0
BH-82		6M→(2.5)	6M↓(y)	84.0	100.0
*BH-83	SAB-6B	4.5M→(2.5)	6M↓(y)	90.0	35.0
BH-84	SAB-5B	9M←(11)	1.5M↓(z)	90.0	35.0
BH-85		4M→(12)	1.5M↓(z)	84.0	100.0
BH-86		4.5M→(14)	1.5M↓(z)	84.0	100.0
BH-87	NB-5	4.5M←(16)	1.5M↓(z)	84.0	100.0
BH-88		4.5M←(17)	1.5M↓(z)	84.0	100.0
BH-89		3.5M←(19)	1.5M↓(z)	84.0	100.0
BH-90	NB-6	7M→(20)	1.5M↓(z)	84.0	100.0
BH-91		6.5M→(2.5)	1.5M↓(z)	84.0	100.0
BH-92	SAB-6B	2M→(2.5)	1.5M↓(z)	90.0	35.0
*BH-93	SAB-5A	5.5M←(13)	(y2)	90.0	35.0
*BH-94	SAB-6A	3.5M←(2.5)	(z2)	90.0	35.0
BH-95		3.5M←(14)	4M↓(z2)	90.0	45.0
BH-96	CB	5.5M←(16)	4M↓(y2)	90.0	45.0
*BH-97		2.5M→(18)	4M↓(z2)	90.0	45.0
BH-98		7M→(20)	4M↓(z2)	90.0	45.0
BH-99	SAB-5A	6M→(11)	2.5M↑(y2)	90.0	35.0
BH-100		3.5M→(14)	7.5M↓(y2)	90.0	45.0
BH-101	CB	7M→(20)	7.5M↓(y2)	90.0	45.0
BH-102	SAB-6A	4M→(2.5)	2.5M↑(y2)	90.0	35.0
BH-103	TB-5	6.5M←(14)	8M↑(w2)	90.0	48.0
BH-104		2M←(16)	8.5M↑(w2)	90.0	48.0
BH-105	TB-6	7M←(19)	8M↑(w2)	90.0	48.0
BH-106		2.5M←(21)	8M↑(w2)	90.0	48.0
BH-107	GT AREA-5	10M→(10)	3.5M↑(y2)	90.0	45.0
BH-108	GT AREA-6	2.5M←(24)	5.5M↓(y2)	96.7	20.0
BH-109		7M←(14)	(y2)	90.0	48.0
*#BH-110	TB-5	4.5M←(13)	(y2)	90.0	48.0
BH-111		2M←(16)	(y2)	90.0	48.0
BH-112		7M←(19)	(y2)	90.0	48.0
*#BH-113	TB-6	4.5M←(20)	(y2)	90.0	48.0
BH-114		2.5M←(21)	(y2)	90.0	48.0
BH-115	TB-5	7M←(14)	6.5M↑(z2)	90.0	48.0
BH-116		2M←(16)	6.5M↑(z2)	90.0	48.0
BH-117	TB-6	7M←(19)	6.5M↑(z2)	90.0	48.0
BH-118		2.5M←(21)	6M↑(z2)	90.0	48.0
BH-119	OHT	1.5M←(28)	6.5M↑(w2)	94.7	20.0
BH-120	CAS	9M→(27)	11M↓(y)	95.7	20.0
BH-121	220 KV SY	5.5M←(9)	3M↑(h)	96.7	20.0
BH-122	400 KV SY	5M←(8')	5.5M↑(s)	96.7	20.0
CH-77A		4.5M←(15)	(x)	84.0	100.0
CH-77B	RECEIVER HOLES FOR SOURCE HOLE BH-77 (RB-5)	0.5M←(15)	(x)	84.0	100.0
CH-77C		9.5M←(15)	5M↓(x)	84.0	100.0
CH-77D		9.5M←(15)	10M↓(x)	84.0	100.0
CH-81A		5M←(20)	(x)	84.0	100.0
CH-81B	RECEIVER HOLES FOR SOURCE HOLE BH-81 (RB-6)	10M←(20)	(x)	84.0	100.0
CH-81C		20	5M↓(x)	84.0	100.0
CH-81D		20	10M↓(x)	84.0	100.0
CH-110A		4.5M←(15)	5M↑(u2)	90.0	48.0
CH-110B	RECEIVER HOLES FOR SOURCE HOLE BH-110 (TB-5)	4.5M←(15)	10M↑(u2)	90.0	48.0
CH-110C		0.5M←(15)	(u2)	90.0	48.0
CH-110D		5.5M←(15)	(u2)	90.0	48.0
CH-113A		4.5M←(20)	5M↑(u2)	90.0	48.0
CH-113B	RECEIVER HOLES FOR SOURCE HOLE BH-113 (TB-6)	4.5M←(20)	10M↑(u2)	90.0	48.0
CH-113C		9.5M←(20)	(u2)	90.0	48.0
CH-113D		14.5M←(20)	(w2)	90.0	48.0



LEGENDS:-

- MAIN PLANT BOUNDARY
- PROPERTY BOUNDARY FENCING
- DOUBLE FENCING FOR PHYSICAL PROTECTION
- PLANT ROADS
- 400KV O/H TRANSMISSION LINES
- EXCLUSION ZONE
- SEPERATION FENCE BETWEEN KGS 1 TO 4 & KAIGA 5&6 DURING CONSTRUCTION
- BOREHOLES TO BE DRILLED
- BOREHOLES TO BE DRILLED FOR CONDUCTING CHST.

BH	BOREHOLE
EGL	EXISTING GROUND LEVEL
FGL	FINISHED GRADE LEVEL
NB	NUCLEAR BUILDING
RB	REACTOR BUILDING
RAB	REACTOR AUXILIARY BUILDING
SAB	STATION AUXILIARY BUILDING
CB	CONTROL BUILDING
SFSB	SPENT FUEL STORAGE BAY
TB	TURBINE BUILDING
ET4	400 KV TRANSMISSION LINE TOWER
GT	GENERATOR TRANSFORMER
SUT	START UP TRANSFORMER
UT	UNIT TRANSFORMER
TML	TURBINE MISSILE LINE
FOSA	FUEL OIL STORAGE AREA
PWPH	PLANT WATER PUMP HOUSE
FWPH	FIRE WATER PUMP HOUSE
SRPH	SAFETY RELATED PUMP HOUSE
CCWPH	CONDENSER COOLING WATER PUMP HOUSE
BOP	BURNT OIL PIT
NDCT	NATURAL DRAFT COOLING TOWER
IDCT	INDUCED DRAFT COOLING TOWER
DG	DIESEL GENERATOR
SREH	SAFETY RELATED ELECTRICAL HOUSE
CAS	CENTRAL ALARM STATION/CONTROL ACCESS SYSTEM
PPS	PHYSICAL PROTECTION SYSTEM
S.T.P.	SEWAGE TREATMENT PLANT
CPVS	CONTAINMENT FILTERED VENTING SYSTEM
DOT	DAY OIL TANK
MGH	MAIN GUARD HOUSE
STF	SPECIAL TASK FORCE
220 KV SY	220 KV SWITCH YARD
400 KV SY	400 KV SWITCH YARD

NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.
2. THE PLANT LAYOUT SHOWN IS INDICATIVE AND THE DIMENSIONS SHALL NOT BE SCALED.
3. FINISHED GRADE LEVEL FOR THE OPERATING ISLAND (AREA WITHIN PPS FENCE) SHALL BE RL 41300 ABOVE MSL WHICH CORRESPONDS TO EL. 99700.
4. DEPTHS OF BORE HOLES HAVE BEEN CALCULATED BASED ON REQUIREMENT FROM 'FOUNDING LEVEL', DEPTH OF DRILLING FROM EXISTING GROUND LEVEL SHALL BE CALCULATED BASED ON CONTOUR SURVEY AVAILABLE AT SITE.
5. ALL THE BORE HOLES SHALL BE OF 5x SIZE IN SOIL AND Nx SIZE IN ROCK STRATA.
6. SPT SHALL BE CONDUCTED IN THESE BOREHOLES AT 3M INTERVAL FROM EGL UP ROCK LEVEL.
7. (*) THESE BORE HOLES ARE TO BE COMPLETED DURING PHASE-1 AS THE BORE HOLE DATA IS REQUIRED FOR PREPARATION OF SER OF KAIGA - 5&6
8. (#) SOURCE HOLE FOR CROSS HOLE SEISMIC TEST.
9. LARGER DRILLING DEPTH HAS BEEN CONSIDERED FOR BORE HOLES ON THE BOUNDARY OF TWO ADJACENT BUILDINGS.
10. DUE TO SITE CONSTRAINTS, LOCATION OF BOREHOLES MAY BE MARGINALLY SHIFTED WITH APPROVAL OF ENGINEER.
11. GEOTECHNICAL INVESTIGATIONS/BOREHOLES IN INFRASTRUCTURE AREA ARE NOT COVERED IN THIS DRAWING.



APPROVAL OF THE DRAWING BY NPCIL DOES NOT RELIEVE THE SUPPLIER/CONTRACTOR IN RESPECT OF CORRECTNESS OF DESIGN, DRAWINGS AND SUITABILITY OF STRUCTURES/SYSTEM/EQUIPMENT.

THIS DRAWING AND DRAWING IS THE PROPERTY OF THE NUCLEAR POWER CORPORATION OF INDIA LTD. IT SHALL NOT BE REPRODUCED, MODIFIED OR USED FOR ANY PURPOSE WITHOUT PERMISSION IN WRITING FROM NPCIL. IT SHALL NOT BE LENT, COPIED OR DISCLOSED TO ANY UNAUTHORISED PERSON EXCEPT BY PERMISSION IN WRITING FROM NPCIL.

No.	REV.	DESCRIPTION	NPCIL	ISSUE SHT. No.
2	R1	FOR CONSTRUCTION	06-04-2018	
1	R0	FOR CONSTRUCTION	09-03-2018	

ISSUE No. / REV. No.

DRAWING ISSUED FOR

NUCLEAR POWER CORPORATION OF INDIA LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)

TITLE :- KAIGA-5&6
GEOTECHNICAL INVESTIGATIONS BOREHOLE LAYOUT FOR MAIN PLANT STRUCTURES

DES'D. – DATE	DR'N. DATE APL	REV'D.
DES.CHK'D.– DATE	DRG.CHK'D. DATE	APP'D.
PROJECT KAIGA-5 & 6		SCALE – 1:1
		PROJECTION
DRG. No. KAIGA-5 & 6/10120/2001/DD		REV. No. R1

FLOPPY'D "NO" FILE NAME: KAIGA5_10120_2001_DD_R1

DRG. TO BE READ IN CONJUNCTION WITH DCN/FCN/ECN, IF ANY.

DRG. No. KAIGA-5&6/10120/2001/DD

No.	LOCATION	DESCRIPTION	DR'N.	DES'D.	D.CHK'D.	REV'D.	APP'D.	CHK'D.	REV'D.	APP'D.
		REVISIONS	SIGNATURE WITH DATE (CONSULTANT)					SIGNATURE WITH DATE (NPCIL)		
1	R1	1. GRID NUMBERS OF CHLORINATION PLANT CORRECTED TO SUIT MAIN PLANT LAYOUT. 2. BOREHOLE NUMBERS IN LAYOUT REVISED TO SUIT THE TABLE. 3. ADDITION OF BOREHOLES IN 220 & 400 kV SWITCHYARD.	KAPS 06/04/2018							

No.	LOCATION	DESCRIPTION	DR'N.	DES'D.	D.CHK'D.	REV'D.	APP'D.	CHK'D.	REV'D.	APP'D.
		REVISIONS	SIGNATURE WITH DATE (CONSULTANT)					SIGNATURE WITH DATE (NPCIL)		

MAIN PLANT LAYOUT — KAIGA-5&6/10000/2001/GA
REFERENCE DRAWINGS — DRAWING No.

DO NOT SCALE THE DRAWING.

UNLESS OTHERWISE STATED :-
ALL DIMENSIONS ARE IN mm.
MACHINE ALL OVER.
SURFACE FINISH TO BE 3.2/ OR BETTER.
REMOVE ALL BURRS.
REMOVE ALL EXTERNAL SHARP CORNERS AND EDGES BY CHAMFERING TO 0 . 15 / 0 . 40 X 45°.
ROUND ALL INTERNAL CORNERS AND EDGES TO R 0 . 15 / 0 . 40.
TOLERANCES ON RADII AND CHAMFERS (IS : 2102)

RADII AND CHAMFERS	0.5–3	3–6	6–30
TOLERANCES	± 0.2	± 0.5	± 1.0

TOLERANCES ON LINEAR DIMENSIONS (IS:2102)

DIMENSIONS	TOL.	DIMENSIONS	TOL.
UPTO 6	± 0.1	315 – 1000	± 0.8
6 – 30	± 0.2	1000 – 2000	± 1.2
30 – 120	± 0.3	2000 – 4000	± 2.0
120 – 315	± 0.5	4000 – 8000	± 3.0

TOLERANCES ON LINEAR DIMENSIONS

SPECIFIED DIMENSIONS	TOLERANCE
XX	±
XX.X	±
XX.XX	±

TOLERANCES ON ANGULAR DIMENSIONS : ± 0° – 30'





ANNUAL WIND ROSE DIAGRAM (60m height)
(JAN TO DEC, 2017)
calms: 18.71%



ANNUAL WIND ROSE DIAGRAM (10m height)
(JAN TO DEC, 2017)
calms: 62.98%



KEY PLAN UNITS 1 to 6

LEGENDS:-

- MAIN PLANT BOUNDARY
- PROPERTY BOUNDARY FENCING
- DOUBLE FENCING FOR PHYSICAL PROTECTION
- PLANT ROADS
- 400KV O/H TRANSMISSION LINES
- EXCLUSION ZONE
- SEPERATION FENCE BETWEEN KGS 1 TO 4 & KAIGA 5&6 DURING CONSTRUCTION

FGL	FINISHED GRADE LEVEL
NB	NUCLEAR BUILDING
RB	REACTOR BUILDING
SAB	STATION AUXILIARY BUILDING
CB	CONTROL BUILDING
SFSB	SPENT FUEL STORAGE BAY
TB	TURBINE BUILDING
ET4	400 KV TRANSMISSION LINE TOWER
GT	GENERATOR TRANSFORMER
SUT	START UP TRANSFORMER
UT	UNIT TRANSFORMER
TML	TURBINE MISSILE LINE
FOSA	FUEL OIL STORAGE AREA
PWPH	PLANT WATER PUMP HOUSE
FWPH	FIRE WATER PUMP HOUSE
SRPH	SAFETY RELATED PUMP HOUSE
CWPH	COOLING WATER PUMP HOUSE
BOP	BURNT OIL PIT
NDCT	NATURAL DRAFT COOLING TOWER
IDCT	INDUCED DRAFT COOLING TOWER
DG	DIESEL GENERATOR
SREH	SAFETY RELATED ELECTRICAL HOUSE
CAS	CENTRAL ALARM STATION/CONTROL ACCESS SYSTEM
PPS	PHYSICAL PROTECTION SYSTEM
S.T.P.	SEWAGE TREATMENT PLANT
CFVS	CONTAINTMENT FILTERED VENTING SYSTEM
DOT	DAY OIL TANK
MGH	MAIN GUARD HOUSE
STF	SPECIAL TASK FORCE
SMR	STACK MONITORING ROOM

NOTES:-

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE. ALL CO-ORDINATES ARE IN METERS WITH RESPECT TO PLANT GRID SYSTEM. CENTER OF REACTOR BUILDING 2 (INTERSECTION OF GRID 20 & X), HAVING COORDINATES N=0.00, E=0.00.
2. FINISHED GRADE LEVEL FOR THE OPERATING ISLAND (AREA WITHIN PPS FENCE) SHALL BE RL 41.3M ABOVE MSL WHICH CORRESPONDS TO EL. 99700 MM.
3. ALL THE SERVICES OUTSIDE MAIN PLANT AREA SHALL BE AS PER THE SITE REQUIREMENT OR ENGINEERING OF RESPECTIVE EPC VENDOR.
4. LOCATION OF THE SERVICES SHOWN IN THE DRAWING IS INDICATIVE ONLY.FOR ACTUAL DETAILS REFER RESPECTIVE CONSTRUCTION DRAWING.
5. THE CONSTRUCTION OF APW STORAGE TANKS SUPPORTING STRUCUTRE, NEW FUEL STORAGE AREA, FOSA-5 & FOSA-6 SHALL BE TAKEN UP ONLY AFTER THE COMPLETION OF DOME STAGING ASSEMBLY AND END SHIELD BALL FILLING ACTIVITIES.
6. U/G SERVICES LIKE TUNNELS, TRENCHES, SURFACE DRAINS, SEWERAGE LINES BURIED PIPE LINES ETC ARE NOT SHOWN IN THIS DRAWING. TUNNELS, TRENCHES, DRAINS, SEWERAGE LINES MAY BE ADJUSTED TO CLEAR ANY FOULING WITH OTHER STRUCTURES.
7. SIZES OF BUILDING STRUCTURE SUCH AS NDCT, IDCT, DM /FILTRATION PLANT, TURBINE BUILDING VENTILATION, CONDENSATE STORAGE AREA, CWPH, SEWAGE TREATMENT PLANT ARE SHOWN AS INDICATIVE AND SAME SHALL BE FINALIZE AFTER GETTING INFORMATION FROM RESPECTIVE VENDORS.
8. FOR COMMON FACILITIES LIKE NSDF, FIRE STATION, DESC ETC., REFER COMPOSITE LAYOUT OF KAIGA SITE.
9. ADDITIONAL BOUNDARY IS PROVIDED ON THE EAST SIDE FOR KAIGA-5&6 TO COMPENSATE FOR THE SHORTFALL IN THE MINIMUM DISTANCE REQUIRED BETWEEN MPB AND OE.
10. LAND RECLAMATION ON THE EAST SIDE OF KAIGA-5&6 (NEAR KAIGA HOLE(NALLAH)) WILL BE CARRIED OUT AS PER SITE GRADING.

APPROVAL OF THE DRAWING BY NPCIL DOES NOT RELIEVE CONTRACTOR OF HIS RESPONSIBILITY IN RESPECT OF CORRECTNESS OF DESIGN DIMENSIONS AND SUITABILITY OF STRUCTURES/ SYSTEM/EQUIPMENT

THE DESIGN AND DRAWING IS THE PROPERTY OF THE NUCLEAR POWER CORPORATION OF INDIA LTD. IT SHALL NOT BE REPRODUCED, PUBLISHED OR USED IN ANY MANNER WITHOUT WRITTEN AUTHORITY AND MUST NOT BE USED EXCEPT FOR EXPANSION OF THE UNITS.

ISSUE No.	REV. No.	DESCRIPTION	NPCIL	ISSUE SHT. No.
1	R0	INFORMATION		

DRAWING ISSUED FOR

NUCLEAR POWER CORPORATION OF INDIA LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)

TITLE :- KAIGA-5&6
MAIN PLANT LAYOUT

DES'D. DATE	DR'N. KAPL DATE	REV'D. DATE
DES.CHK'D.- DATE	DRG.CHK'D. DATE	APP'D DATE
PROJECT KAIGA-5 & 6		SCALE - 1:2000
		PROJECTION
DRG. No. KAIGA-5 & 6/10000/2001/GA		REV. No. R0
FLOPPY/CD No.		FILE NAME: KAGA56_10000_2001_GA_R0

DRG. TO BE READ IN CONJUNCTION WITH DCN/FCN/ECN, IF ANY.

DO NOT SCALE THE DRAWING.

UNLESS OTHERWISE STATED :-
ALL DIMENSIONS ARE IN mm.
MACHINE ALL OVER.
SURFACE FINISH TO BE 3.2 OR BETTER.
REMOVE ALL BURRS.
REMOVE ALL EXTERNAL SHARP CORNERS
AND EDGES BY CHAMFERING TO 0 - 15 X 45°
ROUND ALL INTERNAL CORNERS AND EDGES TO R 0 - 15 / 0 - 40.
TOLERANCES ON RADII AND CHAMFERS (IS : 2102)

RADII AND CHAMFERS	0.5-3	3-6	6-30
TOLERANCES	± 0.2	± 0.5	± 1.0

TOLERANCES ON LINEAR DIMENSIONS (IS:2102)

DIMENSIONS	TOL.	DIMENSIONS	TOL.
UPTO 6	± 0.1	315 - 1000	± 0.8
6 - 30	± 0.2	1000 - 2000	± 1.2
30 - 120	± 0.3	2000 - 4000	± 2.0
120 - 315	± 0.5	4000 - 8000	± 3.0

TOLERANCES ON LINEAR DIMENSIONS

SPECIFIED DIMENSIONS	TOLERANCE
XX	±
XX.X	±
XX.XX	±

TOLERANCES ON ANGULAR DIMENSIONS : ± 0° - 30'

DRG. No.	REFERENCE DRAWINGS	DRAWING No.
KAIGA-5&6/10000/2001/GA		

No.	LOCATION	DESCRIPTION / REVISIONS	DR'N.	DES'D.	D.CHK'D.	REV'D.	APP'D.	CHK'D.	REV'D.	APP'D.
				SIGNATURE WITH DATE (CONSULTANT)				SIGNATURE WITH DATE (NPCIL)		

No.	LOCATION	DESCRIPTION / REVISIONS	DR'N.	DES'D.	D.CHK'D.	REV'D.	APP'D.	CHK'D.	REV'D.	APP'D.
				SIGNATURE WITH DATE (CONSULTANT)				SIGNATURE WITH DATE (NPCIL)		



THE DESIGN AND DRAWING IS THE PROPERTY OF THE NUCLEAR POWER CORPORATION OF INDIA LIMITED (NPCIL) AND IS ISSUED IN CONFIDENCE FOR THE PURPOSE OF EXECUTION OF WORK ON BEHALF OF NPCIL. IT SHALL NOT BE USED, REPRODUCED OR COPIED IN ANY MANNER, IN WHOLE OR IN PART, FOR THE MANUFACTURE OF EQUIPMENT AND MUST NOT BE USED EXCEPT AS PERMITTED BY THE OWNER.

REV. No.	DESCRIPTION	DATE	APP'D.

DRAWING ISSUED FOR

NUCLEAR POWER CORPORATION OF INDIA LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)

TITLE :- KAIGA ATOMIC POWER PROJECT – 5&6

EXCAVATION PLAN

DES'D.	DR'N.	REV'D.
DES. CHK'D.	DRG. CHK'D.	APP'D.

PROJECT KAIGA-5&6

SCALE – 1:1

PROJECTION

DRG. No. KAIGA-5&6/16000/2003/SK

REV. No.

FILE NAME:

DRG. TO BE READ IN CONJUNCTION WITH DCN/FCN/ECN, IF ANY.

DO NOT SCALE THE DRAWING.

UNLESS OTHERWISE STATED :-
ALL DIMENSIONS ARE IN mm.
MACHINE ALL OVER.
SURFACE FINISH TO BE $\sqrt{3.2}$ OR BETTER.
REMOVE ALL BURRS.
REMOVE ALL EXTERNAL SHARP CORNERS AND EDGES BY CHAMFERING TO $^{0\ .\ 15}_{0\ .\ 40}$ X 45°.
ROUND ALL INTERNAL CORNERS AND EDGES TO R $^{0\ .\ 15}_{0\ .\ 40}$.
TOLERANCES ON RADII AND CHAMFERS (IS : 2102)

RADII AND CHAMFERS	0.5–3	3–6	6–30
TOLERANCES	± 0.2	± 0.5	± 1.0

TOLERANCES ON LINEAR DIMENSIONS (IS:2102)

DIMENSIONS	TOL.	DIMENSIONS	TOL.
UPTO 6	± 0.1	315– 1000	± 0.8
6 – 30	± 0.2	1000– 2000	± 1.2
30 – 120	± 0.3	2000– 4000	± 2.0
120 – 315	± 0.5	4000– 8000	± 3.0

TOLERANCES ON LINEAR DIMENSIONS

SPECIFIED DIMENSIONS	TOLERANCE
XX	±
XX.X	±
XX.XX	±

TOLERANCES ON ANGULAR DIMENSIONS : ± 0° – 30'

REFERENCE DRAWINGS	DRAWING No.	REFERENCE DRAWINGS	DRAWING No.	REFERENCE DRAWINGS	DRAWING No.

REVISIONS

REV. No.	REV. LOCATION	DESCRIPTION	DR'N.	DES'D.	DES.CHK'D.	REV'D.	APP'D.

SIGNATURE (NPCIL)

A0

DRG. No. KAIGA-5&6/16000/2003/SK

NUCLEAR POWER CORPORATION OF INDIA LIMITED
(A GOVT. OF INDIA ENTERPRISE)

SPECIFICATION NO: PC-M- 00091-R0

TECHNICAL SPECIFICATION

ON

PASSIVE ROCK ANCHORS

REVISION NO.	:	R0				
DATE OF ISSUE (MONTH/YEAR)	:	JUN 2020				
TOTAL NO. OF PAGES	:	12				

ORIGINAL

PREPARED BY	:	D.P. JENA, ACE(C)	-sd-	30.06.2020
		DR. RAJIV RANJAN, ACE(C)	-sd-	30.06.2020
CHECKED BY	:	DHEERESH JAIN, CE(C)	-sd-	30.06.2020
REVIEWED BY	:	S.K. SHARMA, AD(C)	-sd-	30.06.2020
APPROVED BY	:	ARVIND SHRIVASTAVA AD & HEAD (Civil Engg. Group)	-sd-	30.06.2020
		(Name & Designation)	(Signature)	(Date)

Note: In consideration to the fact that work from home is being implemented at NPCIL, HQ in view of lock-down due to COVID 19 pandemic and thus the technical specification is being approved electronically without affixing physical signatures.

(For Revisions see Revision Control Sheet)

File Name: PC-M-00091-R0

REVISION CONTROL SHEET

DOCUMENT TYPE: ENGINEERING SPECIFICATION

NO.: PC-M-00091-R0

TITLE: TECHNICAL SPECIFICATION FOR

PASSIVE ROCK ANCHORS

REV NO & DATE	DESCRIPTION OF REVISION	REVISED BY NAME & SIGNATURE	CHECKED BY NAME & SIGNATURE	REVIEWED BY NAME & SIGNATURE	APPROVED BY NAME & SIGNATURE

NPCIL PROPRIETARY

This document contains confidential and protected information and that the same are the intellectual property of Nuclear Power Corporation of India Limited (NPCIL). No part of this document including notably any editorial elements, verbal and figurative marks and images included herein, shall be reproduced or transmitted or utilized or published or stored in any form or by any means now known or hereinafter invented, electronic, digital or mechanical, including photocopying, scanning, recording or by any information storage or retrieval system, without prior written permission from NPCIL, by any person or entity. Unauthorized use, disclosure or copying is strictly prohibited and may constitute unlawful act and can attract legal action.

INDEX

CL. NO.	DESCRIPTION	PAGE NO.
1.0	GENERAL	5
2.0	SCOPE	6
3.0	CODES & STANDARDS	6
4.0	MATERIALS	6
5.0	QUALIFICATION OF ROCK ANCHOR BAR	7
6.0	HDPE SHEATHING IN FREE LENGTH PORTION	7
7.0	DRILLING OF HOLE	7
8.0	WATER LOSS TEST AND CONSOLIDATION GROUTING	7
9.0	FABRICATION OF ROCK ANCHORS	8
10.0	INSTALLATION AND GROUTING OF ROCK ANCHORS	8
11.0	TESTING OF INSTALLED ROCK ANCHORS	9
12.0	MEASUREMENT, RATE AND PAYMENT	9

NOT FOR UNAUTHORISED PUBLICATION/PRESENTATION OUTSIDE NPCIL

1.0 GENERAL

Passive Rock Anchors are provided to prevent/ restrict the uplift of the foundation under earthquake situation as well as to prevent flotation of structures supported on raft foundation due to buoyancy effect on account of uplift water pressure. These anchors shall be provided in the foundations of various buildings depending upon the above requirements. The rock anchors will be placed in a pattern and spacing as shown in the drawing. The rock anchors consist of

(i) Single ribbed reinforcement bar of diameter and length as specified in the drawings having minimum grade of Fe500.

(ii) Bundled ribbed reinforcement bars of diameter and length as specified in the drawings having minimum grade Fe500 welded together along their length.

Top end of single ribbed bar anchors shall be either threaded to install the anchor plate with nut or welded with the base plate(s) as per drawings. Top end of bundled ribbed bars anchors shall be suitably welded with the base plate(s) as shown in the drawing. Rock anchors shall be supplied, installed and tested in accordance with the drawings, specifications and Engineer's instructions. The scope of work shall also include providing test anchors of each type/ length. The size of the hole to be drilled in the rock for installation of the rock anchors shall be as specified in the drawing. Due care should be taken during the installation of rock anchors to ensure that there exists no possibility for formation of leakage path for ground water to come up through the space in between and around the rock anchors. A typical indicative arrangement of a passive rock anchor is enclosed at Annexure-I for general reference only.

The scope of work shall include supply, qualification, testing, installation of passive rock anchors as described above including drilling and grouting. The Contractor shall submit a detailed work procedure for approval of Engineer before carrying out the work.

The details of rock anchors system including the fixed length & free length with other system information such as sleeve details, sealing arrangement of free length portion etc. are shown in the indicative sketch enclosed at Annexure-I for general understanding. The Contractor shall supply/ install test anchors in line with the above requirement and carry out pull out test as per the procedure indicated below. In case, the test rock anchors fail to qualify the test load, the same shall be investigated. If it is established that failure of test anchors is due to in-sufficient mobilization of bond, the fixed length of the rock anchor system shall be suitably increased.

NOT FOR UNAUTHORISED PUBLICATION/PRESENTATION OUTSIDE NPCIL

2.0 SCOPE

The scope of work covered under this specification is as follows:

- Drilling of holes in rock at the founding level of required diameter consistent with the rock anchor system selected.
- Conducting water loss test of holes, consolidation grouting, re-drilling of holes & re-test till acceptable limit of water loss is achieved.
- Supply and fabrication of anchor rods including shot/ grit blasting and supply and application of epoxy paint with compatible primer.
- Installation of rock anchors using a non-shrinking cementitious grout.
- The Contractor shall also arrange for supply and installation of at least 3 numbers of test anchors outside the structure, which shall be tested till failure before proceeding with the installation of the working rock anchors.
- In addition to above, pull out test should be carried out in-situ in selected working rock anchors below the foundation as defined subsequently up to the working load (0.9 times the specified yield strength of the rock anchor bar/ bars) to the satisfaction of the Engineer.

3.0 CODES AND STANDARDS

Latest versions of following codes shall be applicable.

- IS 1786 (High Strength Deformed Steel Bars and Wires for Concrete Reinforcement)
- IS: 2062 (Hot Rolled Medium and High Tensile Structural Steel)
- IS: 5529-2 (In-situ Permeability Test)
- IS: 6066 (Pressure Grouting of Rock Foundations in River Valley Projects)
- IS: 11309 (Conducting Pull Out Test On Anchor Bars and Rock Bolts)
- IS: 823 (Code of Procedure for Manual Metal Arc Welding of Mild Steel)
- IS:14333 (High density Polyethylene Pipes for Sewerage)
- PP-M-1219 (Specifications for Epoxy Coating for Reactor Building Internal Structure and Equipment)
- PP-M-400 (Technical Specification for two part Polysulphide Sealing Compounds for Containment Building)

4.0 MATERIALS

The materials to be used under this specification shall be as under:

- Rock Anchors (Single and/ or Bundled ribbed bars): TMT bars of specified dia. and length conforming to IS: 1786. (Min. grade Fe500)
- HDPE sheathing conforming to IS:14333
- Mild steel plates conforming to IS: 2062
- Epoxy paint and primer as approved by the Engineer
- Non-shrink cementitious grouting compound as specified in the drawing/ specification or as approved by the Engineer. The grouting compound shall pass the pull out test as specified in this specification.

NOT FOR UNAUTHORISED PUBLICATION/PRESENTATION OUTSIDE NPCIL

5.0 QUALIFICATION OF ROCK ANCHOR BAR

All single and bundled ribbed rock anchor bars shall be qualified as per the procedure mentioned in the specification for reinforcement bars.

6.0 HDPE SHEATHING IN FREE LENGTH PORTION

Plain HDPE pipe/ sheath without any corrugation shall be provided in the free length portion of the rock anchors. HDPE sheath material shall conform to IS:14333 (pressure rating PN 6). HDPE sheath with appropriate capping arrangement at both ends shall be provided in the free length portion of the rock anchor such that rock anchor penetrates through these caps with proper sealing arrangement around the bar/ bars to prevent ingress of grout/ foreign material during the grouting of the hole. The top cap shall be removable for subsequent filling of free length portion with lean grout. The sheathing should be strong and corrosion resistant. If any one of the samples fails to satisfy the acceptance criteria, then re-testing shall be done for six additional numbers of samples. If any one of the re-tested samples fails to satisfy the acceptance criteria, the whole lot shall be rejected.

7.0 DRILLING OF HOLE

The rock strata at the founding level shall be cleaned and the edges of the foundation shall be marked. After laying the mud mat PCC, the location of the rock anchors in the foundation shall be accurately marked on the PCC. Holes of required diameter and depth as specified in the drawings are to be drilled. The drilling method used shall be subject to the agreement of the Engineer. Wherever ground is likely to collapse, the sides of the drill hole shall be supported by suitable lining tubes until supported by the anchor itself. Usually the depth of the hole shall be 75 mm more than the required depth of embedment of the anchor. Verticality of the holes shall be maintained while drilling. Deviation from straight shall not exceed 20 mm in any 3 m length of drill hole. Immediately after completion of the drilling, the holes shall be plugged with suitable arrangement as approved by the Engineer, until the installation of the rock anchors, to prevent entry of foreign materials or rock pieces, which may obstruct the clearance of the hole. A cement mortar bund shall be made all around the hole to prevent entry of slush.

8.0 WATER LOSS TEST AND CONSOLIDATION GROUTING

After reaching the required depth, the hole shall be cleaned and a water loss test carried out in accordance with IS:5529-2. If the water loss is more than 3 Lugeon, grouting in line with the requirements specified for consolidation grouting, shall be carried out as per IS:6066/ NPCIL technical specifications. The hole shall be again re-drilled, cleaned and water loss test re-done. The operation of re-grouting, re-drilling and water loss test shall be carried out till the water loss test shows water intake to be less than 3 Lugeon.

NOT FOR UNAUTHORISED PUBLICATION/PRESENTATION OUTSIDE NPCIL

9.0 FABRICATION OF ROCK ANCHORS

TMT bars of specified diameter shall be cut to the required length in a shearing machine. The fixed length, free length and embedded length in the raft foundation shall be as specified in the drawings. Flame cutting of the rods shall not be permitted. The straightness of the rod shall be checked and if required shall be rectified. In case of single bar, the anchor plate is to be installed with nuts provided in the threaded end of rock anchor or by welding as specified in the drawing. In case of bundled bars, both the bars shall be welded along their length as specified in the drawing. The top anchor plate shall be fabricated by welding. The hole in the anchor plate for insertion of the rod(s) shall be drilled using drilling machine. Cutting the hole using gas cutting set shall not be permitted. The size of weld shall be as specified in the drawings. All welds shall be visually inspected and 100% DP tested. The entire length of the rock anchor rod including the anchor plate shall be cleaned of all rust, mill scale etc. by shot/ grit blasting. Two coats of approved brand of epoxy paint of total minimum 200 micron thickness shall be applied on the entire surface, over a coat of approved primer (zinc silicate) of minimum 75 micron thickness. Care shall be taken to paint the ends of the anchor rods also. Final inspection of the anchor rods shall be offered to the Engineer-In-Charge or his representative. The bars shall be shifted to the site only after obtaining clearance from the Engineer.

10.0 INSTALLATION AND GROUTING OF ROCK ANCHORS

The hole drilled in the rock shall be cleaned using air-water jet at a pressure of 7 kg/sq.cm to remove loose particles, if any. Entire assembly of rock anchor along with the HDPE sleeve capped at both ends shall be lowered in the hole. Due care should be taken to prevent the damage of the HDPE sheath/ capping and the epoxy paint on the surface of rock anchor. While lowering the rock anchor system, PVC grout pipe of 20mm dia. unless specified otherwise for grouting shall also be attached such that grout pipe for cement grout will have to be inserted up to 75mm above the bottom of the hole.

If while lowering, the rock anchor system gets stuck, the same shall be removed and hole shall be cleaned. The hole shall be inspected for obstructions, if any, and the rod(s) shall be inspected for its straightness. Rectification measures shall be taken before attempting to lower the anchor system.

The grout materials shall be 1:1 cement sand flowing grout with approved non-shrink compound. Grout shall be mixed in a high speed mechanical mixer. Hand mixing will not be allowed. In general, the water to be used for mixing shall be potable and shall conform to relevant clause mentioned in technical specifications of concrete. The quantity of grout required to fill one anchor hole shall be mixed per batch. The mixed grout shall be pumped into the anchor hole through the grout pipe using a positive displacement pump. The grouting shall continue until the grout starts over flowing from the annular space between the sheath and the hole. Finally, space between HDPE sleeve and the bar in the free length portion shall be

NOT FOR UNAUTHORISED PUBLICATION/PRESENTATION OUTSIDE NPCIL

filled with lean grout (1:3 cement sand grout). If settlement of grout occurs, it shall be filled with same grouting compound.

The rock anchor shall be supported suitably on the PCC to keep it in position until the final setting of the grout.

11.0 TESTING OF INSTALLED ROCK ANCHORS

The Contractor shall initially install and test at least 3 test anchors of each type up to failure in similar site conditions. Pull out test shall be performed on the test anchors by the Contractor to determine the strength of the rock anchors after the grout attains 28 days' strength. The pull out test shall be done in accordance with IS:11309. For pull out tests, suitable arrangement shall be done at the top end of the anchor bar to grip them firmly without any slippage. The grouting compound is deemed to have been accepted if the compressive strength of the grout is not less than that for M-20 grade concrete at 28 days. Only after satisfactory demonstration of the strength of the grout, shall the grouting compound be approved for use. Load settlement graphs shall be included in the test report for submission to NPCIL. The Contractor shall submit the scheme of testing for the approval of the Engineer before taking up such tests.

After satisfactory performance of such pull out test, the main rock anchors shall be installed below the foundations of the buildings as per drawing. Pull out test of selected rock anchors up to a working load of 0.9 times the yield strength of the rock anchor system, shall be done in accordance with IS:11309 after the grout attains 28 days' strength. During the test, if any of the working anchor is not found to be satisfactory, additional rock anchors shall be installed by the Contractor.

1% of the total number of anchors, subject to rounding off to next higher digit, in any particular structure shall be selected for pull out test at the specified working load to check the quality of workmanship as described above. This test shall be conducted for all structures wherein rock anchoring is specified. Selection of such anchors shall be done by the Engineer after completion of installation of the rock anchors in the structure.

12.0 MEASUREMENT, RATE AND PAYMENT

(This para is applicable for Item Rate Contracts only and is not applicable for EPC contracts.)

12.1 DRILLING OF VERTICAL HOLES, PRESSURE TESTING/ WATER LOSS TEST AND CONSOLIDATION GROUTING

Drilling holes: Measurement of drilling vertical holes of desired diameter shall be in running meter. Separate payment shall be made for drilling holes through grouted holes of specified diameter as per rates quoted by the contractor in schedule of quantities and rates.

NOT FOR UNAUTHORISED PUBLICATION/PRESENTATION OUTSIDE NPCIL

Pressure testing of holes/ Water loss test: Measurement for pressure testing of holes with water to the specified pressure shall be in numbers. The quoted rates shall include supply and use of mechanical packers. Payment for pressure testing of holes shall be made as per rates quoted by the contractor in schedule of quantities and rates.

Injection/ Consolidation grouting: Measurement for injection/ consolidation grouting shall be in kg. of cement consumed in cement/ cement-sand grout. Separate measurement shall be made for injection/ consolidation grouting using cement grout (with or without mineral admixture) and cement-sand grout. The quoted rates shall include supply and use of mechanical packers. Payment for injection/ consolidation grouting of holes shall be made as per rates under the items of injection/ consolidation grouting using cement grout/ grout using cement-sand separately as quoted by the contractor in schedule of quantities and rates.

12.2 SUPPLY, FABRICATION AND INSTALLATION OF ROCK ANCHOR ASSEMBLY

The measurement of supply, fabrication and installation of rock anchor assembly shall be in RM. It will be measured from the bottom of the rock anchor to the top of anchor plate. The quoted rate shall include supply, fabrication and installation of anchor rod assembly including fabrication of anchor plate with rod(s) of minimum Fe-500 grade, carrying out DP test on welding, shot/ grit blasting, painting with one coat of Zinc silicate primer (min. 75 micron thickness) followed by 2 coats of approved epoxy paint of total minimum 200 micron DFT and installation of fabricated anchor assembly including grouting by 1:1 cement sand grout with approved non-shrink compound and grout pipe, providing and installing HDPE sheathing in free length, grouting the inner volume of HDPE pipe with lean grout (1:3 cement sand grout) and sealing the ends of the HDPE pipe with polysulphide caulking compound, all complete including all materials, labour etc as per drawings and specifications.

In case of increase in fixed length of the anchor due to bond requirement, payment shall be made as per the actual length of the anchor rod assembly supplied and installed.

If while lowering, the rock anchor system gets stuck, necessary rectification measures shall be taken before attempting to lower the anchor system at no extra cost to NPCIL. During the test, if any of the working anchor is not found to be satisfactory, additional rock anchors shall be installed by the Contractor at no extra cost to NPCIL.

If settlement of grout occurs while installation of anchor rod assembly, the Contractor shall fill the settlement with same grouting compound at no extra cost to NPCIL.

NOT FOR UNAUTHORISED PUBLICATION/PRESENTATION OUTSIDE NPCIL

12.3 CARRYING OUT PULL OUT TEST ON TEST/ WORKING ANCHORS

The quoted rate shall include carrying out Pull out test on test/ working anchors till failure/ working load etc. including all materials required to carry out the test, facilitating inspection/ witness of test to NPCIL all complete as per drawings, specifications and instructions of Engineer. Measurement shall be in no. of rock anchors tested and payment shall be made based on rates quoted by the contractor in SOQR for the items provided for test/ working anchors.

NOT FOR UNAUTHORISED PUBLICATION/PRESENTATION OUTSIDE NPCIL

Annexure-I



TYPICAL DETAILS OF ROCK ANCHORS

DETAILS OF ROCK ANCHOR :

DESCRIPTION	ROCK ANCHOR DETAILS	
BAR	1–45DIA	2–45DIA
DIA OF DRILLED HOLE(D)	125	200
FREE LENGTH	2000	2000
FIXED LENGTH	7000	7000
DIA OF PVC PIPE	75	125

Typical (Indicative) Details of Passive Rock Anchor Systems

NOT FOR UNAUTHORISED PUBLICATION/PRESENTATION OUTSIDE NPCIL

NUCLEAR POWER CORPORATION OF INDIA LIMITED

(A Government of India Enterprises)

PROCUREMENT SPECIFICATION NUMBER:

GHAVP- 1&2/40000/PROCUREMENT SPECIFICATION/ MS-1
GHAVP- 3&4/40000/PROCUREMENT SPECIFICATION/ MS-1
KAIGA- 5&6/40000/PROCUREMENT SPECIFICATION/ MS-1

PROCUREMENT SPECIFICATION
FOR
TURBINE ISLAND PACKAGE

SECTION C -2-1: SPECIFIC TECHNICAL REQUIREMENTS OF CIVIL STRUCTURES: ADDENDUM -1

Revision No	R0			
Date Of Issue (Month / Year)	07/2019			
Total No of Pages (Including Cover Sheet)	7			

Prepared By	SUDHANSHU PANDEY, Sr. EE (Civil)		11/07/2019
	VIJAY SINGH, Sr. EE (Civil)		11/07/2019
Checked By	A.K.LAHARIA, SO/H (Civil)		11/07/2019
Reviewed By	N.M.RAO, CE (Civil)		11/07/2019
Approved By	ARVIND SHRIVASTAVA AD (Civil) & Head (Civil Engineering Group)		11/07/2019
	(Name & Designation)	(Signature)	(Date)

REVISION CONTROL SHEET

PROCUREMENT SPECIFICATION NUMBER:

GHAVP- 1&2/40000/PROCUREMENT SPECIFICATION/ MS-1
GHAVP- 3&4/40000/PROCUREMENT SPECIFICATION/ MS-1
KAIGA- 5&6/40000/PROCUREMENT SPECIFICATION/ MS-1

FOR
TURBINE ISLAND
SECTION C -2-1: SPECIFIC TECHNICAL REQUIREMENTS
OF CIVIL STRUCTURES: ADDENDUM - 1

REV. NO. / DATE	DESCRIPTION	PREPARED BY	CHECKED BY	REVIEWED BY	APPROVED BY

Specific Technical requirements of Civil Works: Addendum -1

S. No.	Project	Clause No.	Existing Provision	Revised Provision
1.	GHAVP – 1&2	10.9.1	These specifications cover coating of reinforcement bars with fusion bonded epoxy coating (FBEC) to be provided as corrosion protection measure, in construction of Nuclear Power plant. This coating shall be used, wherever specified so in the drawings.	Fusion Bonded Epoxy Coated reinforcement bars not to be used.
2.	KAIGA – 5&6	10.9.1	These specifications cover coating of reinforcement bars with fusion bonded epoxy coating (FBEC) to be provided as corrosion protection measure, in construction of Nuclear Power plant. This coating shall be used, wherever specified so in the drawings.	Fusion Bonded Epoxy Coated reinforcement bars not to be used.
3.	GHAVP – 1&2	1.11	• Backfilling: A) Area Grading: i) Upto EL 98.70m: Using soil (at OMC) with 5% cement (by weight of dry soil) and compacting the same as per relevant specifications for Backfilling /ground improvement unless approved otherwise. PCC may be used, only if specifically approved by the engineer without financial implication.	• Backfilling: C) Area Grading: i) Upto EL 95.4m: Using soil (at OMC) with 5% cement (by weight of dry soil) and compacting the same as per relevant specifications for Backfilling /ground improvement unless approved otherwise. PCC may be used without financial implication. ii) Above EL 95.4m upto EL98.7m: Using compacted soil as per technical specification (as per clause no. 4). PCC may

			ii) Above EL 98.70m: Soil suitable for land escaping/ Soil Cement mix as approved by the Engineer. B) Within Foot Print of structure/ equipment Foundation: PCC shall be used, unless specifically approved by the Engineer. The properties of the back fill material used shall be suitably accounted in the design.	be used without financial implication. iii) Above EL 98.70m: Compacted Soil/Soil suitable for land escaping as required and as approved by the Engineer. D) Within Foot Print of structure/ equipment Foundation: Soil-cement shall be used, unless specifically approved by the Engineer. The properties of the back fill material used shall be suitably accounted in the design. PCC may be used without financial implication.
4.	GHAVP – 1&2	1.6.7	The construction of 10 m wide road between grid 17-18 within terminal point is excluded from the scope of the bidder. However the bidder shall fill the area up to subgrade i.e. EL 98.0m, with soil cement mix as per the specification. The typical cross section to be followed for the road is given in Sketch No. GHAVP 1&2/15600/5001/SK attached with the tender.	The construction of 10 m wide road between grid 17-18 within terminal point and Hard Stand "C" is excluded from the scope of this tender. However, the bidder shall fill the area up to EL 95.4m with soil cement mix as per detailed technical specifications. From EL 95.4m to EL97.4m, compacted soil shall be used as per technical specification (as per clause no. 4).
5.	GHAVP – 1&2	1.6.8	The Hard Stand "C" is excluded from the scope of this tender. However, the area below the Hard stand within terminal point shall be graded upto EL 98.00 with soil cement mix as per detailed technical specifications.	The Hard Stand "C" is excluded from the scope of this tender. However, the area below the Hard stand within terminal point shall be graded upto EL 95.4m with soil cement mix as per detailed technical specifications. From EL 95.4m to EL97.4m,

				compacted soil shall be used as per technical specification (as per clause no. 4).
6.	GHAVP – 1&2	1.11	Structure above Raft: Reinforced Cement Concrete (RCC), unless approved otherwise by the Purchaser. RCC slabs and roofs shall be constructed using Galvanized deck sheets as left in shuttering, unless specifically approved otherwise.	Structure above Raft: The roof of Turbine buildings shall be cast in situ RCC over Steel Deck Span Sheets. The roof of Turbine Buildings shall be laid over steel roof trusses and purlins. Bidder may please note the specific requirements towards removal of generator stator as given in clause 1.6.1 of section C-2-1. The use of Steel Deck Span Sheets for construction of RCC slabs other than roof is optional. Secondary steel beam may be permitted in specific cases subject to approval of Purchaser, if this meets all the structural and functional requirements including the fire rating.
7.	GHAVP – 1&2	2.5.1.2	Similarly dynamic analysis shall be performed using dynamic modulus of elasticity, $E_{dynamic}$ (using correction factor of G/G_{max} = 0.4, where Gmax corresponds to low strain shear modulus) under sustained load plus Earthquake loading to obtain dynamic springs as $Kx_{dynamic}$, $Ky_{dynamic}$ and $Kz_{dynamic}$.	$E_{dynamic}$ data for soil is enclosed herewith. (Annexure -1)
8.	KAIGA – 5&6	2.5	ANALYSIS AND DESIGN	Soil Structure Interaction shall be done using ABAQUS methodology as given in clause no. 2.5 of GHAVP-1&2 specification.

9.	KAIGA – 5&6	1.7.2	The bidder has to carry out at least following confirmatory geological tests for both the buildings independently, to demonstrate the suitability of geotechnical parameters considered, in his design within the area covered in the scope of the bidder unless approved otherwise by the Engineer. • minimum one bore hole of nx size (As required, but not lesser than 60m depth from founding level), • analyzing & arriving at safe bearing capacity using RMR & Unconfined compressive strength of core (having a minimum factor of safety of 10) approach. and a lesser of these 2 values shall be considered in the design in case of rock. • cyclic plate load tests under TG foundation area & • Geological mapping at the founding level of foundation & its side area, The bidder shall also carry out the ground improvement by consolidation grouting as per IS 6066 & conduct the water loss test as per IS 5529(Part 2), unless	Following confirmatory test shall be conducted (for each unit): 1. Field Tests: a) 1 Plate load test (for SBC and E value) at founding level b) 2-borehole upto 70m depth. • For Soil portion– SPT shall be carried out at every 3 m interval • For Rock portion– RQD, CR at every 3m interval or change in strata c) 1 Borehole upto 70m depth (for E value by Pressuremeter test) at every 5m interval or change in strata 2. Lab tests: a) Dry Density b) Specific Gravity c) UCS (Soaked) for rock portion at every 3m interval d) Triaxial shear Test (in soil portion for both drained & undrained condition) at every 3m interval. 3. SBC & E value to be used in analysis and design, shall verified based on confirmatory test 4. Geological mapping at the founding level of foundation & its side area, The bidder shall also carry out the ground improvement by consolidation grouting as per IS 6066 & conduct the water loss test as per IS 5529(Part 2), unless approved otherwise by the Engineer. All the above activities shall be executed as

			approved otherwise by the Engineer. All the above activities shall be executed as per the relevant technical specifications detailed in subsequent clauses of this tender.	per the relevant technical specifications detailed in subsequent clauses of this tender.
10.	GHAVP-1&2	2.3.1.2	The value of subgrade reaction for both static and dynamic analysis shall be worked out as per detailed soil structure analysis using ABAQUS or equivalent software. The detailed approach for the same is given in clause 2.4 below.	The value of subgrade reaction for both static and dynamic analysis shall be worked out as per detailed soil structure analysis using ABAQUS or equivalent software. The detailed approach for the same is given in clause 2.5 below.
11.	GHAVP-1&2	2.4.1.3	Using spring values calculated by above approach further structural analysis shall be carried out using any standard Finite Element software like NISA, ANSYS, ABAQUS, and SAP etc.	Clause 2.4.1.3 shall be read as clause 2.5.1.3.

ANNEXURE – I

MEAN					
Elevation of Bottom of layer from FGL	Depth (m) of Bottom of Layer from EGL	Depth (m) of Bottom of Layer from FGL	Poisson's ratio μ = (Vp2-2Vs2)/(2*(Vp2-Vs2))	Ed=2G(1+ν) kN/m2	Mean Unit weight (kN/m3)
100					
95	0	5			
93.6	1.4	6.4	0.38	7.30E+06	19.61
92.2	2.8	7.8	0.38	7.02E+06	19.61
90.8	4.2	9.2	0.38	6.79E+06	19.61
89.4	5.6	10.6	0.38	6.53E+06	19.61
87.9	7.1	12.1	0.38	6.34E+06	19.61
86.4	8.6	13.6	0.38	6.05E+06	19.61
84.9	10.1	15.1	0.38	5.88E+06	19.61
83.4	11.6	16.6	0.38	5.63E+06	19.61
81.9	13.1	18.1	0.33	2.56E+05	18.3
80.4	14.6	19.6	0.33	2.77E+05	18.47
79	16	21	0.32	3.17E+05	18.18
78	17	22	0.32	3.06E+05	18.04
76.5	18.5	23.5	0.32	2.96E+05	18.12
75	20	25	0.32	3.08E+05	18.33
73.5	21.5	26.5	0.32	3.22E+05	18.44
72	23	28	0.31	3.23E+05	18.27
70.5	24.5	29.5	0.32	3.14E+05	18.28
69	26	31	0.32	3.20E+05	18.47
67.5	27.5	32.5	0.32	3.42E+05	18.44
66	29	34	0.31	3.65E+05	18.56
64.5	30.5	35.5	0.32	4.12E+05	18.56
63	32	37	0.32	4.19E+05	18.45
61.5	33.5	38.5	0.32	3.71E+05	18.45
60	35	40	0.32	3.77E+05	18.42
58.5	36.5	41.5	0.30	3.70E+05	18.38
57	38	43	0.29	3.82E+05	18.21
55.5	39.5	44.5	0.30	3.95E+05	18.22
54	41	46	0.31	4.30E+05	18.19
52.5	42.5	47.5	0.31	4.43E+05	18.09
51	44	49	0.30	4.74E+05	18.27
49.5	45.5	50.5	0.30	4.83E+05	18.31
48	47	52	0.31	4.76E+05	18.35
46.5	48.5	53.5	0.31	4.82E+05	18.07
45	50	55	0.35	4.01E+05	17.79
43.5	51.5	56.5	0.34	4.76E+05	17.54
42	53	58	0.34	4.52E+05	17.59
40.5	54.5	59.5	0.33	4.59E+05	17.57
39	56	61	0.34	4.67E+05	17.95
37.5	57.5	62.5	0.34	5.04E+05	18.49
36	59	64	0.34	5.40E+05	18.85
34.5	60.5	65.5	0.35	5.50E+05	18.99
33	62	67	0.34	5.36E+05	19.06
31.5	63.5	68.5	0.33	5.84E+05	19.09
30	65	70	0.33	6.20E+05	19.03
28.5	66.5	71.5	0.34	5.27E+05	19.25
27	68	73	0.33	5.54E+05	19.36
25.5	69.5	74.5	0.34	5.38E+05	19.41
24	71	76	0.35	5.51E+05	19.29
22.5	72.5	77.5	0.35	5.57E+05	19.31
21	74	79	0.35	5.68E+05	19.31
19.5	75.5	80.5	0.36	5.27E+05	19.32
18	77	82	0.35	5.57E+05	19.37
16.5	78.5	83.5	0.34	5.60E+05	19.12
15	80	85	0.36	5.42E+05	19
13.5	81.5	86.5	0.36	5.43E+05	18.94
12	83	88	0.35	6.17E+05	19.06
10.5	84.5	89.5	0.35	6.03E+05	19.04
9	86	91	0.36	5.94E+05	19.03
7.5	87.5	92.5	0.35	6.00E+05	19.03
6	89	94	0.36	5.95E+05	18.73
4.5	90.5	95.5	0.36	5.59E+05	18.54
3	92	97	0.36	5.47E+05	18.44
1.5	93.5	98.5	0.37	5.64E+05	18.39
-2.84217E-14	95	100	0.37	5.94E+05	18.66

-1.5	96.5	101.5	0.36	6.52E+05	18.65
-3	98	103	0.37	6.34E+05	18.64
-4.5	99.5	104.5	0.37	6.45E+05	18.64
-6	101	106	0.38	6.20E+05	18.34
-7.5	102.5	107.5	0.37	6.32E+05	18.66
-9	104	109	0.38	6.16E+05	18.82
-10.5	105.5	110.5	0.38	6.49E+05	18.9
-12	107	112	0.38	6.75E+05	19.08
-13.5	108.5	113.5	0.38	7.38E+05	19.12
-15	110	115	0.37	1.16E+06	19.12
-19	114	119	0.36	1.13E+06	19.12
-23	118	123	0.36	1.14E+06	19.12
-27	122	127	0.36	1.17E+06	19.12
-31	126	131	0.36	1.18E+06	19.12
-35	130	135	0.36	1.20E+06	19.12
-39	134	139	0.36	1.35E+06	19.12
-43	138	143	0.36	1.45E+06	19.12
-47	142	147	0.36	1.49E+06	19.12
-51	146	151	0.36	1.53E+06	19.12
-55	150	155	0.36	1.54E+06	19.12
-59	154	159	0.36	1.55E+06	19.12
-63	158	163	0.36	1.57E+06	19.12
-67	162	167	0.36	1.60E+06	19.12
-71	166	171	0.36	1.63E+06	19.12
-75	170	175	0.36	1.66E+06	19.12
-79	174	179	0.36	1.71E+06	19.12
-83	178	183	0.37	1.75E+06	19.12
-87	182	187	0.37	1.77E+06	19.12
-91	186	191	0.37	1.79E+06	19.12
-95	190	195	0.37	1.82E+06	19.12
-99	194	199	0.37	1.84E+06	19.12
-103	198	203	0.37	1.86E+06	19.12
-107	202	207	0.37	1.88E+06	19.12
-113	208	213	0.37	1.92E+06	19.12
-119	214	219	0.37	1.96E+06	19.12
-125	220	225	0.36	1.99E+06	19.12
-135	Half Space		0.37	1.99E+06	19.12

UPPER BOUND					
Elevation of Bottom of layer from FGL	Depth (m) of Bottom of Layer from EGL	Depth (m) of Bottom of Layer from FGL	Poisson's ratio $\mu = (V_p^2-2V_s^2)/(2*(V_p^2-V_s^2))$	Ed=2G(1+ν) kN/m^2	Mean Unit weight (kN/m3)
100					
95	0	5			
93.6	1.4	6.4	0.38	1.49E+07	19.61
92.2	2.8	7.8	0.38	1.45E+07	19.61
90.8	4.2	9.2	0.38	1.41E+07	19.61
89.4	5.6	10.6	0.38	1.39E+07	19.61
87.9	7.1	12.1	0.38	1.37E+07	19.61
86.4	8.6	13.6	0.38	1.35E+07	19.61
84.9	10.1	15.1	0.38	1.31E+07	19.61
83.4	11.6	16.6	0.38	1.27E+07	19.61
81.9	13.1	18.1	0.33	8.08E+05	18.3
80.4	14.6	19.6	0.33	8.75E+05	18.47
79	16	21	0.32	1.04E+06	18.18
78	17	22	0.32	1.00E+06	18.04
76.5	18.5	23.5	0.32	9.72E+05	18.12
75	20	25	0.32	1.01E+06	18.33
73.5	21.5	26.5	0.32	1.06E+06	18.44
72	23	28	0.31	1.06E+06	18.27
70.5	24.5	29.5	0.32	1.03E+06	18.28
69	26	31	0.32	1.05E+06	18.47
67.5	27.5	32.5	0.32	1.11E+06	18.44
66	29	34	0.31	1.16E+06	18.56
64.5	30.5	35.5	0.32	1.29E+06	18.56
63	32	37	0.32	1.32E+06	18.45
61.5	33.5	38.5	0.32	1.10E+06	18.45
60	35	40	0.32	1.12E+06	18.42
58.5	36.5	41.5	0.30	1.11E+06	18.38
57	38	43	0.29	1.15E+06	18.21
55.5	39.5	44.5	0.30	1.18E+06	18.22
54	41	46	0.31	1.30E+06	18.19
52.5	42.5	47.5	0.31	1.34E+06	18.09
51	44	49	0.30	1.46E+06	18.27
49.5	45.5	50.5	0.30	1.48E+06	18.31
48	47	52	0.31	1.46E+06	18.35
46.5	48.5	53.5	0.31	1.44E+06	18.07
45	50	55	0.35	1.17E+06	17.79
43.5	51.5	56.5	0.34	1.52E+06	17.54
42	53	58	0.34	1.45E+06	17.59
40.5	54.5	59.5	0.33	1.46E+06	17.57
39	56	61	0.34	1.49E+06	17.95
37.5	57.5	62.5	0.34	1.59E+06	18.49
36	59	64	0.34	1.69E+06	18.85
34.5	60.5	65.5	0.35	1.72E+06	18.99
33	62	67	0.34	1.68E+06	19.06
31.5	63.5	68.5	0.33	1.83E+06	19.09
30	65	70	0.33	1.95E+06	19.03
28.5	66.5	71.5	0.34	1.55E+06	19.25
27	68	73	0.33	1.65E+06	19.36
25.5	69.5	74.5	0.34	1.60E+06	19.41
24	71	76	0.35	1.65E+06	19.29
22.5	72.5	77.5	0.35	1.66E+06	19.31
21	74	79	0.35	1.70E+06	19.31
19.5	75.5	80.5	0.36	1.58E+06	19.32
18	77	82	0.35	1.67E+06	19.37
16.5	78.5	83.5	0.34	1.68E+06	19.12
15	80	85	0.36	1.64E+06	19
13.5	81.5	86.5	0.36	1.63E+06	18.94
12	83	88	0.35	1.84E+06	19.06
10.5	84.5	89.5	0.35	1.80E+06	19.04
9	86	91	0.36	1.78E+06	19.03
7.5	87.5	92.5	0.35	1.78E+06	19.03
6	89	94	0.36	1.77E+06	18.73
4.5	90.5	95.5	0.36	1.66E+06	18.54
3	92	97	0.36	1.62E+06	18.44
1.5	93.5	98.5	0.37	1.66E+06	18.39
-2.84217E-14	95	100	0.37	1.74E+06	18.66

-1.5	96.5	101.5	0.36	1.90E+06	18.65
-3	98	103	0.37	1.84E+06	18.64
-4.5	99.5	104.5	0.37	1.87E+06	18.64
-6	101	106	0.38	1.79E+06	18.34
-7.5	102.5	107.5	0.37	1.82E+06	18.66
-9	104	109	0.38	1.76E+06	18.82
-10.5	105.5	110.5	0.38	1.86E+06	18.9
-12	107	112	0.38	1.91E+06	19.08
-13.5	108.5	113.5	0.38	2.07E+06	19.12
-15	110	115	0.37	2.75E+06	19.12
-19	114	119	0.36	3.05E+06	19.12
-23	118	123	0.36	3.08E+06	19.12
-27	122	127	0.36	3.15E+06	19.12
-31	126	131	0.36	3.19E+06	19.12
-35	130	135	0.36	3.22E+06	19.12
-39	134	139	0.36	3.31E+06	19.12
-43	138	143	0.36	3.54E+06	19.12
-47	142	147	0.36	3.60E+06	19.12
-51	146	151	0.36	3.66E+06	19.12
-55	150	155	0.36	3.74E+06	19.12
-59	154	159	0.36	3.82E+06	19.12
-63	158	163	0.36	3.87E+06	19.12
-67	162	167	0.36	3.93E+06	19.12
-71	166	171	0.36	3.98E+06	19.12
-75	170	175	0.36	4.03E+06	19.12
-79	174	179	0.36	4.12E+06	19.12
-83	178	183	0.37	4.20E+06	19.12
-87	182	187	0.37	4.24E+06	19.12
-91	186	191	0.37	4.29E+06	19.12
-95	190	195	0.37	4.33E+06	19.12
-99	194	199	0.37	4.38E+06	19.12
-103	198	203	0.37	4.42E+06	19.12
-107	202	207	0.37	4.46E+06	19.12
-113	208	213	0.37	4.54E+06	19.12
-119	214	219	0.37	4.61E+06	19.12
-125	220	225	0.36	4.68E+06	19.12
-135	Half Space		0.37	4.69E+06	19.12

LOWER BOUND					
Elevation of Bottom of layer from FGL	Depth (m) of Bottom of Layer from EGL	Depth (m) of Bottom of Layer from FGL	Poisson's ratio $\mu = (V_p^2-2V_s^2)/(2*(V_p^2-V_s^2))$	Ed=2G(1+v) kN/m^2	Mean Unit weight (kN/m3)
100					
95	0	5			
93.6	1.4	6.4	0.38	3.59E+06	19.61
92.2	2.8	7.8	0.38	3.41E+06	19.61
90.8	4.2	9.2	0.38	3.26E+06	19.61
89.4	5.6	10.6	0.38	3.12E+06	19.61
87.9	7.1	12.1	0.38	2.96E+06	19.61
86.4	8.6	13.6	0.38	2.78E+06	19.61
84.9	10.1	15.1	0.38	2.69E+06	19.61
83.4	11.6	16.6	0.38	2.53E+06	19.61
81.9	13.1	18.1	0.33	8.41E+04	18.3
80.4	14.6	19.6	0.33	8.86E+04	18.47
79	16	21	0.32	8.37E+04	18.18
78	17	22	0.32	7.95E+04	18.04
76.5	18.5	23.5	0.32	7.64E+04	18.12
75	20	25	0.32	7.82E+04	18.33
73.5	21.5	26.5	0.32	8.25E+04	18.44
72	23	28	0.31	8.25E+04	18.27
70.5	24.5	29.5	0.32	8.05E+04	18.28
69	26	31	0.32	8.27E+04	18.47
67.5	27.5	32.5	0.32	8.76E+04	18.44
66	29	34	0.31	9.60E+04	18.56
64.5	30.5	35.5	0.32	1.10E+05	18.56
63	32	37	0.32	1.11E+05	18.45
61.5	33.5	38.5	0.32	1.19E+05	18.45
60	35	40	0.32	1.22E+05	18.42
58.5	36.5	41.5	0.30	1.21E+05	18.38
57	38	43	0.29	1.26E+05	18.21
55.5	39.5	44.5	0.30	1.28E+05	18.22
54	41	46	0.31	1.38E+05	18.19
52.5	42.5	47.5	0.31	1.44E+05	18.09
51	44	49	0.30	1.55E+05	18.27
49.5	45.5	50.5	0.30	1.58E+05	18.31
48	47	52	0.31	1.56E+05	18.35
46.5	48.5	53.5	0.31	1.58E+05	18.07
45	50	55	0.35	1.33E+05	17.79
43.5	51.5	56.5	0.34	1.27E+05	17.54
42	53	58	0.34	1.21E+05	17.59
40.5	54.5	59.5	0.33	1.22E+05	17.57
39	56	61	0.34	1.25E+05	17.95
37.5	57.5	62.5	0.34	1.34E+05	18.49
36	59	64	0.34	1.45E+05	18.85
34.5	60.5	65.5	0.35	1.48E+05	18.99
33	62	67	0.34	1.43E+05	19.06
31.5	63.5	68.5	0.33	1.57E+05	19.09
30	65	70	0.33	1.64E+05	19.03
28.5	66.5	71.5	0.34	1.70E+05	19.25
27	68	73	0.33	1.78E+05	19.36
25.5	69.5	74.5	0.34	1.72E+05	19.41
24	71	76	0.35	1.78E+05	19.29
22.5	72.5	77.5	0.35	1.78E+05	19.31
21	74	79	0.35	1.82E+05	19.31
19.5	75.5	80.5	0.36	1.69E+05	19.32
18	77	82	0.35	1.81E+05	19.37
16.5	78.5	83.5	0.34	1.81E+05	19.12
15	80	85	0.36	1.76E+05	19
13.5	81.5	86.5	0.36	1.76E+05	18.94
12	83	88	0.35	2.01E+05	19.06
10.5	84.5	89.5	0.35	1.97E+05	19.04
9	86	91	0.36	1.96E+05	19.03
7.5	87.5	92.5	0.35	1.98E+05	19.03
6	89	94	0.36	1.97E+05	18.73
4.5	90.5	95.5	0.36	1.85E+05	18.54
3	92	97	0.36	1.83E+05	18.44
1.5	93.5	98.5	0.37	1.89E+05	18.39
-2.84217E-14	95	100	0.37	2.00E+05	18.66
-1.5	96.5	101.5	0.36	2.15E+05	18.65
-3	98	103	0.37	2.10E+05	18.64

-4.5	99.5	104.5	0.37	2.15E+05	18.64
-6	101	106	0.38	2.08E+05	18.34
-7.5	102.5	107.5	0.37	2.11E+05	18.66
-9	104	109	0.38	2.05E+05	18.82
-10.5	105.5	110.5	0.38	2.18E+05	18.9
-12	107	112	0.38	2.27E+05	19.08
-13.5	108.5	113.5	0.38	2.48E+05	19.12
-15	110	115	0.37	3.99E+05	19.12
-19	114	119	0.36	3.90E+05	19.12
-23	118	123	0.36	3.95E+05	19.12
-27	122	127	0.36	4.04E+05	19.12
-31	126	131	0.36	4.10E+05	19.12
-35	130	135	0.36	4.16E+05	19.12
-39	134	139	0.36	4.31E+05	19.12
-43	138	143	0.36	5.01E+05	19.12
-47	142	147	0.36	5.27E+05	19.12
-51	146	151	0.36	5.48E+05	19.12
-55	150	155	0.36	5.48E+05	19.12
-59	154	159	0.36	5.34E+05	19.12
-63	158	163	0.36	5.38E+05	19.12
-67	162	167	0.36	5.62E+05	19.12
-71	166	171	0.36	5.72E+05	19.12
-75	170	175	0.36	5.83E+05	19.12
-79	174	179	0.36	6.26E+05	19.12
-83	178	183	0.37	6.56E+05	19.12
-87	182	187	0.37	6.60E+05	19.12
-91	186	191	0.37	6.67E+05	19.12
-95	190	195	0.37	6.83E+05	19.12
-99	194	199	0.37	6.94E+05	19.12
-103	198	203	0.37	6.98E+05	19.12
-107	202	207	0.37	7.06E+05	19.12
-113	208	213	0.37	7.25E+05	19.12
-119	214	219	0.37	7.45E+05	19.12
-125	220	225	0.36	7.65E+05	19.12
-135	Half Space		0.37	7.66E+05	19.12

NUCLEAR POWER CORPORATION OF INDIA LIMITED

(A Government of India Enterprises)

PROCUREMENT SPECIFICATION NUMBER:

KAIGA- 5&6/40000/PROCUREMENT SPECIFICATION/ MS-1

PROCUREMENT SPECIFICATION
FOR
TURBINE ISLAND PACKAGE

SECTION C -2-1: SPECIFIC TECHNICAL REQUIREMENTS OF CIVIL STRUCTURES: ADDENDUM -2

Revision No	R0	R1		
Date Of Issue (Month / Year)	08/2019	08/2019		
Total No of Pages (Including Cover Sheet)	12	13		

Prepared By	SUDHANSHU PANDEY, Sr. EE (Civil)	Sd/-	30/07/2019
	VIJAY SINGH, Sr. EE (Civil)	Sd/-	30/07/2019
Checked By	A.K.LAHARIA, SO/H (Civil)	Sd/-	30/07/2019
Reviewed By	N.M.RAO, AD (Civil)	Sd/-	05/08/2019
Approved By	ARVIND SHRIVASTAVA AD (Civil) & Head (Civil Engineering Group)	Sd/-	08/08/2019
	(Name & Designation)	(Signature)	(Date)

REVISION CONTROL SHEET

PROCUREMENT SPECIFICATION NUMBER:

KAIGA- 5&6/40000/PROCUREMENT SPECIFICATION/ MS-1

PROCUREMENT SPECIFICATION FOR TURBINE ISLAND SECTION C -2-1: SPECIFIC TECHNICAL REQUIREMENTS OF CIVIL STRUCTURES: ADDENDUM - 2

REV. NO. / DATE	DESCRIPTION	PREPARED BY	CHECKED BY	REVIEWED BY	APPROVED BY
1	Geotechnical/geophysical information included. Compensation provisions modified in line with the discussions and requirements of procurement directorate.	Sudhanshu Pandey 28/08/19 V.S 28/08/19	28/8/19	28/8/19	29/08/19

Specific Technical requirements of Civil Works: Addendum -2

S. No.	Project	Clause No.	Existing Provision	Revised Provision
1.	KAIGA 5-6	1.7.2. (a)	The excavation of site will be carried out within the terminal points of this package by the Purchaser as indicated in the drawing no KAIGA 5&6/16000/2003 /SK. However, additional excavation, if any required from functional reasons due to system requirements or due to geotechnical reasons, shall be carried out by the contractor at his own cost. Wherever, the founding levels are lower than the levels specified in above drawing the ground shall be lowered by bidder using appropriate cutting tool like, rock breaker, chisel etc. which does not disturb and damage the adjoining structure and also do not have any adverse effect on the existing works being executed by other contractors in adjoining areas. The excavation using controlled blasting may be resorted in specific cases with prior approval of Engineer. The over excavated / damaged ground, if any, shall be made good by the bidder at his own cost.	i) The excavation of site will be carried out within the terminal points of this package by the Purchaser as indicated in the drawing no KAIGA 5&6/16000/2003 /SK. However, additional excavation below EL 87.00m, if any required from functional reasons due to system requirements shall be carried out by the contractor at his own cost. ii) Bidder is requested to study the wide variation in the strata captured in all 16 bore holes while finalization of structural arrangement. iii) The Raft foundation of the structures other than Transformer Yard (i.e. foundation for equipment like SUTs, UTs, GTs, Rail, BOP and fire walls etc.) shall be laid at EL 87.00m. In case Piles are required below raft foundation at EL 87.00M, same shall also be provided by the Bidder without any extra cost to NPCIL. The foundations of equipment in transformer yard (like SUTs, UTs, GTs, Rail Yard) and other structures like BOP etc. shall be Raft or Raft with Pile and shall be provided at appropriate level, without any extra cost to the Purchaser. In case of Raft foundation for Equipment and structures of Transformer Yard, the safe allowable bearing pressure at founding level shall be established by the bidder by conducting plate load test (if founding on soil) or by

			Schedule of the additional excavation and backfilling shall be finalized in consultation with PURCHASER. Bidder must schedule his excavation and other activities considering the status of construction & schedule of construction of adjoining structure. Back filling of areas, wherever required, shall be done using suitable backfill material as decided by the Engineer, and is included in the scope of this tender. The same shall be done by the bidder at his own cost. The area under the structures shall be raised, by filling PCC only unless approved otherwise by the Engineer The bidder has to carry out at least following confirmatory geological tests for both the buildings independently, to demonstrate the suitability of geotechnical parameters considered, in his design within the area covered in the scope of the bidder unless approved otherwise by the Engineer. ▪ minimum one bore hole of nx size (As required, but not lesser than 60m depth from	UCS & RMR (if founding on rock), at no extra cost to Purchaser. In case of pile foundation relevant qualification test shall be performed as per specifications by the bidder at no extra cost to Purchaser. iv) Bidder shall use appropriate excavation equipment like mechanical excavator, rock breaker, chisel etc. which does not disturb and damage the adjoining structure and also do not have any adverse effect on the existing works being executed by other contractors in adjoining areas. The excavation using controlled blasting may be resorted in specific cases with prior approval of Engineer. v) Schedule of the additional excavation and backfilling shall be finalized in consultation with PURCHASER. Bidder must schedule his excavation and other activities considering the status of construction & schedule of construction of adjoining structure. vi) Back filling of areas, wherever required, above founding level shall be done by the bidder, using suitable backfill material as approved by the Engineer at his own cost, and is included in the scope of this tender. The area below the foundation of structures shall be raised, by filling PCC only, unless approved otherwise by the Engineer. vii) The bidder has to carry out at least following confirmatory

			founding level), ▪ analyzing & arriving at safe bearing capacity using RMR & Unconfined compressive strength of core (having a minimum factor of safety of 10) approach. and a lesser of these 2 values shall be considered in the design in case of rock. ▪ cyclic plate load tests under TG foundation area & ▪ Geological mapping at the founding level of foundation & its side area, The bidder shall also carry out the ground improvement by consolidation grouting as per IS 6066 & conduct the water loss test as per IS 5529(Part 2), unless approved otherwise by the Engineer. All the above activities shall be executed as per the relevant technical specifications detailed in subsequent clauses of this tender.	geological tests for both the buildings independently at his own cost, to demonstrate the suitability of geotechnical parameters considered, in his design within the area covered in the scope of the bidder unless approved otherwise by the Engineer. Following confirmatory test shall be conducted (for each unit): 1. Field Tests: a) 1 Plate load test (for SBC and E value) at founding level b) 2-borehole upto 70m depth. • For Soil portion– SPT shall be carried out at every 3 m interval • For Rock portion– RQD, CR at every 3m interval or change in strata c) 1 Borehole upto 70m depth (for E value by Pressuremeter test) at every 5m interval or change in strata 2. Lab tests: a) Dry Density b) Specific Gravity c) UCS (Soaked) for rock portion at every 3m interval d) Triaxial shear Test (in soil portion for both drained & undrained condition) at every 3m interval. 3. SBC & E value to be used in analysis and design, shall verified based on confirmatory test 4. Geological mapping at the founding level of foundation & its side area, viii) The bidder shall also carry out the ground improvement by consolidation grouting as per IS

				6066 & conduct the water loss test as per IS 5529(Part 2), unless approved otherwise by the Engineer. All the above activities shall be executed as per the relevant technical specifications detailed in subsequent clauses of this tender. **ix) Bidder shall be suitably compensated for extra excavation & backfilling, *in the area other than Transformer yard,* if required, due to non-availability of competent rock , at EL 87.00m and bidder needs to go for deeper excavation upto competent rock. In such case, the Bidder shall remove the soil / weathered rock upto competent strata and backfill the same with PCC (M15 Grade) upto EL 87.00M. In such case, the compensation shall be made in the following manner. However, no such compensation will be made for the transformer yard area.** A) **Compensation for Excavation**: The Bidder shall excavate the area upto EL 87.00M from the levels indicated in Drawing No. KAIGA-5&6/16000/2003/SK at his own cost. However, the bidder will be compensated for excavation (in soil and weathered rock) below EL 87.00M, if required due to non-availability of competent rock, at a rate finalized as per provisions of contract. **However, no compensation will be made towards dewatering (including for the portion below EL 87.00m) and is deemed to be**

				included in Lum-Sum Price quoted for the works. B) **Compensation for Backfilling**: Bidder shall be suitably compensated for backfilling with PCC, only upto EL 87.00m, for the area which is required to be backfilled due to non-availability of competent rock at a rate finalized as per provisions of contract . No extra payment shall be made for the backfilling above EL 87.00M and it is deemed to inclusive in Lum-Sum Price quoted by the contractor. No payment will be made for the shuttering used for PCC work mentioned above.
2.		2.3.1.1	The safe bearing capacity at founding level of any structure shall be computed based on standard codal approach/ practices considering the geotechnical parameters of the influence zone, based on dimension of structure and maximum intensity of pressure. For finalization of influence zone, the foundation profile up to a depth, where net increase in vertical pressure becomes less than 10% of the initial overburden pressure from founding level of the structure shall be considered in the analysis.	Following foundation parameters shall be followed in the design: A) For the structures (other than Transformer Yard) i.e Turbine Building, Turbine Generator, Electrical Bay Building, Annex Building, Pipe & Cable Bridge and Access Bridge etc., bidder shall consider following foundation design parameters as bid basis:

Founding Level	EL 87000
Net Safe/Allowable bearing pressure SBC (Ton/m^2)	150
Static modulus of Elasticity, E (kg/cm^2)	$9.84x10^3$ – $9.82x10^5$
Static shear modulus, G (kg/cm^2)	$4.33x10^3$ – $4.02x10^5$

			The geotechnical parameters shall be evaluated based on bore hole data obtained on ground and required field test. The foundation of all structures and major equipment of transformer yard (SUT, UT, GT etc.) & oil separation pit, CCW Inlet & hot water tunnel, PCB & Electrical bay, Turbine Building and Turbo-generator etc. shall be taken from competent rock or supported on pile unless specifically approved otherwise by the engineer and as approved by the engineer. All other tunnel / trenches may be engineered & founded on PCC / fillcrete, unless approved otherwise and as approved by the Engineer.	<table><tr><td>Shear Wave Velocity, V (m/s)</td><td>1800 to 2500</td></tr><tr><td>Poisson's ratio, μ</td><td>0.2</td></tr></table> In case based on confirmatory geotechnical investigations, different parameters are required to be followed than those specified above, the bidder shall be suitably compensated for same. B) The foundation of transformer yard structures (SUT, UT, GT etc.) & oil separation pit, CCW Inlet & hot water tunnel shall be taken on Raft foundation from competent rock or Raft supported on pile. In case of Raft foundation for Equipment and structures of Transformer Yard, the safe allowable bearing pressure at founding level shall be established by the bidder by conducting plate load test (if founding on soil) or by UCS & RMR (if founding on rock), at no extra cost to Purchaser. In case of pile foundation, relevant qualification tests shall be performed and necessary geotechnical parameters, if required, shall be obtained by the bidder at no extra cost to Purchaser as per technical specifications. Bidder is requested to study the relevant borehole data of Transformer Yard and plan the foundation accordingly. All other tunnel / trenches may be engineered & founded on PCC / fillcrete, unless approved otherwise and as approved by the Engineer.
3.		3.1	The excavation of site will be carried out within the	The excavation of site will be carried out within the terminal points of this

			terminal points of this package by the Purchaser as indicated in the drawing no KAIGA 5&6/16000/2003 /SK. However, additional excavation, if any required from functional reasons due to system requirements or due to geotechnical reasons, shall be carried out by the contractor at his own cost. Wherever, the founding levels are lower than the levels specified in above drawing the ground shall be lowered by bidder using appropriate cutting tool like , rock breaker, chisel etc. which does not disturb and damage the adjoining structure and also do not have any adverse effect on the existing works being executed by other contractors in adjoining areas. The excavation using controlled blasting may be resorted in specific cases with prior approval of Engineer. The over excavated / damaged improved ground, if any, shall be made good by the bidder at his own cost. Schedule of the additional excavation and backfilling shall be finalized in consultation with PURCHASER. Bidder	package by the Purchaser as indicated in the drawing no KAIGA 5&6/16000/2003 /SK. The bidder shall excavate the area other than Transformer yard area upto EL 87.00M at his own cost. Additional excavation below EL 87.0M , wherever required, due to non- availability of rock shall be carried out by the bidder and he will be suitably compensated for same as per provisions of contract. Wherever, the founding levels are required to be lowered , the excavation shall be done using appropriate cutting tool like , rock breaker, chisel etc. which does not disturb and damage the adjoining structure and also do not have any adverse effect on the existing works being executed by other contractors in adjoining areas. The excavation using controlled blasting may be resorted in specific cases with prior approval of Engineer. Schedule of the additional excavation and backfilling shall be finalized in consultation with PURCHASER. Bidder must schedule his excavation and other activities considering the status of construction & schedule of construction of adjoining structure. Contractor shall make necessary arrangement for Dewatering alongwith standby arrangement at his own cost. The contractor has also to make necessary arrangements for side protection to avoid any slippage of rock/ soil etc. at his own cost. No extra payment will be made to remove any of slipped rock/earth etc. in the excavated area. The contractor is also requested to visit the site prior to

			must schedule his excavation and other activities considering the status of construction & schedule of construction of adjoining structure. Contractor shall make necessary arrangement for Dewatering alongwith stand by arrangement at his own cost. The contractor has also to make necessary arrangements for side protection to avoid any slippage of rock/ soil etc. at his own cost. No extra payment will be made to remove any of slipped rock/earth etc in the excavated area. The contractor is also requested to visit the site prior to quoting & satisfy himself with the actual site conditions. In case further excavation is required, the same shall be carried out as per following specifications. A) This section covers all the excavation works to be performed under this contract which shall consist of clearing of site and excavation of all existing material of whatever nature, to the lines and grades shown on the construction drawing or as otherwise	quoting & satisfy himself with the actual site conditions. In case further excavation is required, the same shall be carried out as per following specifications. A) This section covers all the excavation works to be performed under this contract which shall consist of clearing of site and excavation of all existing material of whatever nature, to the lines and grades shown on the construction drawing or as otherwise directed by the engineer. The work shall also include drilling and blasting, loading, hauling and disposal of materials in designated spoil, stockpile areas or directly as construction materials. B) The contractor shall also be responsible for excavation which is not specifically required for the construction of permanent structures, but incidental to the installation of temporary facilities such as site roads, approach ramps etc. C) Slope protection and stabilization measures, which may be needed in conjunction with surface excavation work, shall be carried out as defined in other sections of these specifications. D) The approval given by the Engineer during the course of execution, to the contractor's methods and equipment shall not relieve the contractor of his full responsibility for the proper and safe execution of excavations, or of liability for

			directed by the engineer. The work shall also include drilling and blasting, loading, hauling and disposal of materials in designated spoil, stockpile areas or directly as construction materials. B) The contractor shall also be responsible for excavation which is not specifically required for the construction of permanent structures, but incidental to the installation of temporary facilities such as site roads, approach ramps etc. C) Slope protection and stabilization measures, which may be needed in conjunction with surface excavation work, shall be carried out as defined in other sections of these specifications. D) The approval given by the Engineer during the course of execution, to the contractor's methods and equipment shall not relieve the contractor of his full	injuries to, or death of persons, or any other obligations under this contract. It shall also not relieve his responsibilities for the accuracy or adequacy of the plan for obtaining the desired results in the stipulated time schedule.

			responsibility for the proper and safe execution of excavations, or of liability for injuries to, or death of persons, or any other obligations under this contract. It shall also not relieve his responsibilities for the accuracy or adequacy of the plan for obtaining the desired results in the stipulated time schedule.	
4	KAIGA 5-6	2.1.1	Seven Boreholes BH103, RBH-104, RBH-109, BH-110, RBH-111, BH-115 and BH- 116 covers Turbine Building-5. Seven Boreholes BH105, RBH-112, BH-113, BH-106, RBH-114, BH-117 and RBH- 118 exists covers Turbine Building-6. Boreholes RBH-107 & RBH -108 covers Transformer Yard of both the units. The representative borehole data BH-110 & BH-113 are attached as Annexure-1 for guidance. The soil/ rock samples from boreholes will be tested & relevant data will be provided to bidder subsequently. Subsurface profile at Turbine building -5 & 6 areas generally consists	Borehole data for all the 16 boreholes were shared on 3rd June 2019 with the bidders in response to the query raised by M/s L&T. The existing ground level of bore hole no 108,110, & 113 is modified. These revised borehole are attached in Annexure – 1.

			of top soil followed by laterite, boulders/sand and rock as indicated in representative borehole data BH-110 & BH-113.	

Annexure – 1

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Geotechnical Investigation of Kaiga 5&6.

Format No.: SFE/KAIGAS&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No: 108

Sheet: 1 of 6

Location: GT-AREA-6 | Co-ordinates: 24.2557N, 12.5509N, X=440403.0289, Y=1477986.8666

Feature:

Angle with vertical: — | UTM Co-ordinates:

Total depth: 30.50MTR | Collar Elevation:

Existing Ground Elevation: 98.574, 94.10 (B2 mean)

Type (s) of core barrel: Double Tube. | Started: 10/04/2019 | Completed: 27/05/2019

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Fracture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
0.00									Black humus soil						NX	NX							
1.90									Brownish Fine Grained sand			Diamond Bit			NX	NX							15 30 45 60 N 6 7 9 10 16
2.10									Brownish Fine to medium Grained sand with soft Clay						NX	NX							
4.50															NX	NX							15 30 45 60 N 6 9 10 11 19
5.70															NX	NX							
7.00															NX	NX							15 30 45 60 N 11 12 13 14 25
8.10															NX	NX							
10.00																							

Sohams | NPCIL

SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
	(Mohd Aasaq Khan)	(Nitesh D Shinde)	CN. Mohan Sole	Litholog and observed log Nirmal Das

Dr. Dhanajit Das (Nirmal) Total 6 pages

Scanned by CamScanner

Sohams Foundation Engineering Pvt. Ltd. Mumbai

.SFE

Project:

Format No. : SFE/KAIGAS&6/BD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 108

Sheet : 2 of 6

Location : | Co-ordinates | Feature :

Angle with vertical : | UTM Co-ordinates: | Existing Ground Elevation: 94.00 m

Total depth : | Collar Elevation:

Type (s) of core barrel : | Started : | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 35 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Water loss: Partial	Drill Water loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
10.00				4, 10	13,3SPS7 & 7SP89.5P SP,SP				Greenish to whitish, Highly fractured weathered, Granite with Chloritic material along the fracture zone	Shattered	53.334												
11.50				13 21,22,23,24,25 14,12,11SPS6&7&8&9 SP SP							55.334	Diamond BIT	Nil	NX	Nil	Nil	Pumped						
13.00				25,27,28,29,31,32 SP30,SP					Part Greenish, Highly fractured Moderately weathered, Quartz Chlorite schist (gneiss) (Schistosity)		39.334												
14.50																							

Contractor: | NPCIL

SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA

Scanned by CamScanner

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Format No. : SFE/KAIGAS&G/RO/01

Project:

Date:

Job No:

Created By:

Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 108

Sheet : 3 of 6

Location :

Co-ordinates

Feature :

Angle with vertical :

UTM Co-ordinates:

Total depth :

Collar Elevation:

Existing Ground Elevation: 94.00

Type (s) of core barrel :

Started :

Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
14.50																							
16.00				—	—	33.34 SP	36.37 SP	38 SP	SP	Shattered ←	46.66%	Diamond Bit	Nil	Nil	NX	Nil							
17.50				—	—	44.45 SP	39.94 SP	43 SP	Moderately Fractured, Dark Greenish, Highly Quartz chlorite schist. Silicification along the fracture zone)		90.66%							Partial					
19.00				—	52 SP	49.50 SP	51.55 SP	57 SP			86.66%		75.33%		NX	Nil							

	Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA

Scanned by CamScanner

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Format No. : SFE/TANGABEA/RD/01

Project:

Date: | Created By: | Created on:

Job No: | Hole No : 108

GEOLOGICAL LOG OF BORE HOLE

Sheet : 4 of 6

Location : | Co-ordinates | Feature :

Angle with vertical : | UTM Co-ordinates: | Existing Ground Elevation: 94.00

Total depth : | Collar Elevation: | Completed:

Type (s) of core barrel : | Started :

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Fracture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
19.00																							
20.50					60%	26%	6%	6%	SP 68 SS 59 Fo	Moderately Jointed, Rough Planar, Wavy (avg 12-60°)	88%	—	—	NX	Nil							
22.00					73	7%	7%	7%	SP 80 SS 78 Fo	Moderately fractured, Rough Planar, Wavy (avg 12-60°)	95.33%	Diamond Bit	76.66%	NX	Nil							
23.50					SP 80	81	7%	7%	SS 78 Fo	Dark Greenish Grey, Moderately Weathered, Meta Basalt	90%	—	85.33%	NX	Nil							

	Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA

Scanned by CamScanner

Sohams Foundation Engineering Pvt. Ltd. Mumbai

Project:

Date:

Job No:

Created By:

Format No.: SFE/LAN/66/66/RD/01

GEOLOGICAL LOG OF BORE HOLE

Created on:

Location :

Co-ordinates

Hole No : 10R

Sheet : 5 of 6

Angle with vertical :

Feature :

Total depth :

UTM Co-ordinates:

Type (s) of core barrel :

Collar Elevation:

Existing Ground Elevation: 94.00

Started :

Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery (0 20 40 60 80 100)	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
23.50																							
25.00					83.84.87		82.86	85.88.89	Fractured, moderately weathered, slightly rotten, Quartz vein (Angle 70°)		92%	Diamond BIT	88.66%	NX	NX								
26.50					92.95.96			90.91.93.94.97	Fractured, moderately weathered, Garnetiferous		93.33%		93.33%	NX	NX		Partial						
28.00				100				98.99.101	Dark Greenish,		94.66%		94.66%	NX	NX								

	Subsoils		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA

Scanned by CamScanner

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Geotechnical Investigation of Kaiga 5 & 6.

Format No.: SFE/KAIGA5&6/RD/01

Date:

Job No:

Created By:

Created on:

GEOLOGICAL LOG OF BORE HOLE

Location: GT-AREA-6 Co-ordinates: 24°25'51.42"-15'M

Hole No: 108

Sheet: 6 of 6

Angle with vertical:

UTM Co-ordinates: X=440203.0289 Y=1642 9[illegible].8666

Feature:

Total depth: 30.50MTR.

Collar Elevation:

Existing Ground Elevation: ~~98.574~~ 94.00 msl

Type (s) of core barrel: Double Tube

Started:

Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0	20	40	60	80	100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Water loss: Partial	Drill Water loss: Complete.	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
28.00							102,103,104		Dark Green ish, Moderately fractured & Moderately weathered, Medium Grained Gabbro					85.33%			Diamond BIT	85.33%		NX	NX		Partial					
29.50																												
30.50							106							79%				75%										

Borehole Terminated at Depth 30.50MTR.

SIGNATURE	Sohams: Logged By (Geologist)	Sohams: Checked By (QA)	NPCIL: Civil	NPCIL: QA
	(Mohd Aleem Khan)	(Sailesh Dighade)	(M. Mohan Rao)	Dr. Dhanjit Das (NPCIL)

Scanned by CamScanner

Rec. 27/11/18

water Table - 2.90 m

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date: —

Job No: — | Created By: — | Created on: —

GEOLOGICAL LOG OF BORE HOLE

Hole No : 110

Sheet : 1 of 10

Location : TB-5 | Co-ordinates 15+4.5M 70U2 | Feature : Quay wall

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: 96.356. ~~95.172~~ 96.356

Total depth : 56.10 MTR. | Type (s) of core barrel : Double Tube

Started : 3/5/2018 | Completed: 8/7/2018 | Drilling Agency : SFE

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery (0 20 40 60 80 100)	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Water loss: Partial	Drill Water loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
0.00									Red-sty muram						NX	NX							
1.50																							15 30 45 N 10 15 26 41
1.95									Boulders spill									Partial					
4.30															NX	NX							
4.86														Diamond Bit									15 30 45 N 11 17 23 40
7.50															NX	NX							
9.00				—	—	2.3	—	—	SPT 1.5P. Highly weathered Light Grey Fractured Granite.		5 — 62% — —	NX	16%		NX	NX							

Sohams		NPCIL	
Logged By (Geologist)	Checked By (QA)	Civil	QA
SIGNATURE	Badra	Pwar	mohan	Lithology and structural log verified

S.F.E.

(N. mohan)

total 10 pages Dr. Dhansi Das NIRM Total 10 pages

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 110

Sheet : 2 of 10

Location : TB-5 | Co-ordinates 15+46.559 70 U2 | Feature :

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: 96.356 ~~95.173~~

Total depth : 56.10 MTR | Type (s) of core barrel : Double Tube | Drilling Agency : SFE

Started : | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
9.00				1	1	4,5,	10,	SP,6,7,8,9,	Highly fractured & weathered Chlorite schist,		1 1 2 2 7 1 1	NX	53.33%		NX	Nil							
10.50				1	1	13,15,	14,	11, SP,16			1 1 5 8 7 1 1	NX	29.5		NX	Nil		Partial					
12.50				1	1	14,	18,19,	SP,20.			1 1 7 8 1 1	NX	78%		NX	Nil							
13.80				1	1	1	21,	22,23,24.	Greyish Highly fractured weathered		1 1 1 1 97%	NX	94%		NX	Nil							
14.00																							

Sohams

Logged By (Geologist)	Checked By (QA)
Rashmi	Pawar

NPCIL

Civil	QA
mehta	

SIGNATURE

Rashmi Pawar
Meshram Pawar

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RO/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : H10.

Sheet : 3 of 10

Location : TB 5 | Co-ordinates(5+4.5TM TOWER | Feature :

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: 96.356

Total depth : 56.10 MTR. | Type (s) of core barrel : Double Tube

Started : | Completed: | Drilling Agency : SFE

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
14.00																							
15.00						5P.	25, 27.	26.	Greyish, slightly weathered Charnockite Gneiss.		23%	NX	15%		NX	NX							
17.50						28, 5P	29, 31 33	30, 32	Light Greyish, Moderately weathered, Slightly fractured,		88%	NX	86.4%		NX	NX		→ Perfect					
18.50				37, 41	36, 38, 42,	34, 35, 39, 40, 43		5P, 5P	To Greyish White,		82%	NX	59%		NX	NX							
20.00				46, 47,	48, 50, 52, 53	54, 51		45, 49, 54.			83%	NX	73.33%		NX	NX							

	Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
Mahendra Meghshinde	Rachna	Pawar	Mohanty	

Sohams Foundation Engineering Pvt. Ltd. Mumbai

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : BH 110

Sheet : 4 of 10

Location : TB-5 | Co-ordinates 15+4.5mTO U2 | Feature :

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: 96.356

Total depth : 56.10MTR | Type (s) of core barrel Double Tube. | Drilling Agency : SFE

Started : | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
20.00						57, 58, 59, 62	60, 61, 62	55, 56, 57			80% 66%	NX	72%		NX	NIL							
21.50						65, 66, 67, 69	68, 69, 70, 71,	64, 73,			70.66%	NX	52%		NX	NIL							
23.00						75, 76, 77, 80	74, 78, 79	81, 82, 83.	Grey ish, TR. white sh, slightly, weathered Chlorite schist.		88% 80.50	NX	81.5%		NX	NIL		→ Partial					
25.00												NX			NX	NIL							

Ravindra Mukesh Shinde.

SIGNATURE	Sohams		NPCIL	
	Logged By (Geologist)	Checked By (QA)	Civil	QA
	Radha	Pwar		

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 110

Sheet : 5 of 10

Location : TB-5 | Co-ordinates 15+4.570 02 | Feature :

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: 96.356 ~~95.123.8~~ mslv

Total depth : 56.10 MTR. | Type (s) of core barrel DoubleTube

Started : | Completed: | Drilling Agency : SFE

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Water loss: Partial	Drill Water loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
25.00								84,85	SP		1 1 1	NX			NX	NX							
150						87,90,92		86,88,89,91,93,95	SP		1 1 1	NX			NX	NX		Partial					
28.00						96,	97	94,95,98	SP		1 1 1 1	NX	91.33%		NX	NX							
30.50								99,101,102,103 100,101,104,SP	SP		1 1 1 1	NX	91.33%		NX	NX							

- Grey, SH, FP, White SH slightly weathered chlorite schist, slightly fractured

18 Grade / 21 to 24 Grade

	Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
	Rachu	Rao	Mohanty	

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 110.

Sheet : 6 of 10

Location : TB 5 | Co-ordinates (54.5M N, 0 W) | Feature :

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: 96.356 (95.173 & 96.356)

Total depth : 56.10 MTR. | Type (s) of core barrel : Double Tube

Started : | Completed: | Drilling Agency : SFE

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
30.50						106.	105, 108.	107, 109.	Slightly weathered to fresh laminated schist, Greenish grey, Fg. Light		67.33%	NX	67.33%		NX	Nil		Partial					
32.00						111, 112,	SP, 113, 115.	110, 114			95.33%	NX	64%		NX	Nil							
33.50						118	117, 119, 121.	116, 120			71%	NX	63.5%		NX	Nil							
35.50						125	SP, 126, 127.	122, 123, 124			94.66%	NX	90.66%		NX	Nil							
37.00																							

Rubble / Rock chunks.

	Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
	Pacha	Ram		

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 110 .

Sheet : 7 of 10

Location : TB-5 | Co-ordinates 15+4.5M 90 02 | Feature :

Angle with horizontal : 90° | Collar Elevation: | Existing Ground Elevation: ~~95.173~~ 96.356

Total depth : 56.10MTR. | Type (s) of core barrel Double Tube | Drilling Agency : SFE

Started : | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Water loss: Partial	Drill Water loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
37.00					139,SP,133,	128,SP,129,131,SP	SP,132,134,135,SP		Slightly fractured chloritic schist.		73%	NX	40%		NX	NX							
40.00				141,SP,142,143,144 137,138,SP,139,149	136,SP.						83%	NX	32%		NX	NX		Partition					
43.00					145	146,147,148.	80		Slightly fractured moderately to slightly weathered		70%	NX	63.5%		NX	NX							
					149,150,152,SP	151,153,164			Coarse grained														

43.00 Rahul Shinde. / Nilesh Shinde.

SIGNATURE	Sohams		NPCIL	
	Logged By (Geologist)	Checked By (QA)	Civil	QA
	Prachi			

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 110 .

Sheet : 8 of 10

Location : TB 5 | Co-ordinates 5+4.5M 90 Rt | Feature :

Angle with horizontal : 90° | Collar Elevation: | Existing Ground Elevation: ~~95.171~~ 96.356 @ mod

Total depth : 56.10 MTR. | Type (s) of core barrel : Double Tube | Drilling Agency : SFE

Started : | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
43.00						157, 158, 161	157	155, 156, 157, 159, 160, 161	Moderately fractured Schistic Schist		96.5%	NX	74.5%		NX	NX							
45.00						163, 164, 165, 166, 167, 168, 169, 170, 171, 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200	SP	SP, 171	To white, Moderately weathered Schistic Schist		60.33%	NX	44.66%		NX	NX		Partial →					
48.00											2.46.6%	NX	10%		NX	NX							
49.50																							

Bhiwale Nileshchandra

SIGNATURE

Sohams		NPCIL	
Logged By (Geologist)	Checked By (QA)	Civil	QA

Sohams Foundation Engineering Pvt. Ltd. Mumbai

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGAS&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 110

Sheet : 9 of 10

Location : TB - 5 | Co-ordinates 15 44 0M 70 Ve | Feature :

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: ~~95.173~~ 96.356

Total depth : 56.10 MTR. | Type (s) of core barrel : DoubleTube | Drilling Agency : SFE

Started : | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
49.50						188, 190, 192, 193	191	189 SP	Highly weathered/ Schist.		71.33%	NX	51.33%		NX	NIL							
51.00				SP	195, 196, 197, 198, 200, 201	199	194 SP		Highly Slightly Chlorite		80.66%	NX	74%		NX	NIL							
53.50					203, 204, 208	205	202, SP, 207		P 3 Hi			NX			NX	NIL		→ Partial					
					213, 214, 209, 210, 212		208, 211, SP.		Greyish		92.88%	NX	81.07%		NX	NIL							

Pathinde Nilesh Shinde

	Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
	Rachel	Pw		

Sohams Foundation Engineering Pvt. Ltd. Mumbai

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO:Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. : SFE/KAIGAS&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 110

Sheet : 10 of 10

Location : TB-5 | Co-ordinates 15-4. 5TMDU2 | Feature :

Angle with horizontal : 90°. | Collar Elevation: | Existing Ground Elevation: ~~95.173.0~~ 96.356 mSL

Total depth : 56.10 MTR. | Type (s) of core barrel : DoubleTube

Started : | Completed: | Drilling Agency : SFE

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
56.10						216,221.	218,219,220,	215,217	slightly weathered light Grey fractured Chloritic schist.			NX.			NX. Nil.			Partial					

Borehole terminated at 56.10

Rohinde / Nilesh Rinde.

	Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
	Rohinde S.F.E.			Litholog and Structural log Verified

Rec 23/11/18

Water Table - 2.52 m

SFE

Sohams Foundation Engineering Pvt. Ltd. Mumbai

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No: SFE/KAIGA5&6/RD/01

Date: —

Job No. — | Created By: — | Created on: —

GEOLOGICAL LOG OF BORE HOLE

Hole No: 113.

Sheet: 1 of 8

Location: TB-6 | Co-ordinates 20-4.570 U2. | Feature: —

Angle with horizontal: 900 | Collar Elevation: | Existing Ground Elevation: ~~97.075~~ 97.745

Total depth: 65.00 MTR. | Type (s) of core barrel: Double Tube | Drilling Agency: SFE.

Started: 2-7-2018 | Completed: 3-8-2018

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery (0 20 40 60 80 100)	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Water loss: Partial	Drill Water loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
0.00									Reddish colour murum			NX			NX	Yes						3.17	
1.50																							
1.95									Red color laterite			NX			NX	Yes						1.18	15 30 45 N 8 9 11 20
4.50																							
4.95									Red colour laterite			NX			NX	Yes						0.48	15 30 45 N 10 12 21 33
7.50																							
									Sand			NX			NX	Yes		→ Penetration				0.44	
10.50																							
									Sand			NX			NX	Yes						0.56	
13.50																							
									Sand			NX			NX	Yes						0.57	
16.00																							

	Sohams		NPCIL	
	Logged By (Geologist)	Checked By (QA)	Civil	QA
SIGNATURE	Babal S.F.E			Litholog and Structural log verified

(N. MOHAN)
Total 8 Pages.

Dr. Dhansil Das (NIRM)
Total 8 pages

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 113

Sheet : 2 of 8

Location : TB-6 | Co-ordinates 20-4.570 02 | Feature :

Angle with horizontal : 90° | Collar Elevation: | Existing Ground Elevation: ~~97.745~~ 97.745

Total depth : 65.00MTR. | Type (s) of core barrel : Double Tube

Started : | Completed: | Drilling Agency : SPE

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
16.00						1,2,	5,3,4,	SP,SP,6,SP,SP	Light Green Highly weathered Granite		54-8 %	HX	15.6 %	NX	NX	NIL							
18.50																							
22.50						7,9,11,13,	8,10,12,	SP	Light Green Moderately to Highly weathered Chlorite Schist		17 %	HX	7.25 %	NX	NX	NIL		Partial					
24.50						14,19,	15,16,17,	SP 18.	Light Grey moderately weathered Granite		48.5	HX	21.5 %	NX	NX	NIL							
26.00						SP,20,22,	21,23,24,25,	SP.			41.33 %	HX	28.66	NX	NX	NIL							

Rounded Rajesh Shinde

SIGNATURE

Sohams		NPCIL	
Logged By (Geologist)	Checked By (QA)	Civil	QA

Sohams Foundation Engineering Pvt. Ltd. Mumbai

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 113

Sheet : 3 of 8

Location : TB6 | Co-ordinates 20-4-57 80 02. | Feature :

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: ~~96.075~~ 97.745

Total depth : 65-00 MTR. | Type (s) of core barrel : Double Tube | Drilling Agency : SFE

Started : | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0	20	40	60	80	100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
26.00				41,	36,37,38,39,42	25,25,28,29,30 31,32,33,34, 35								64%			NX	~~57~~ 64		NX	NIL							
28.00						40,			SP	Highly fractured			26.5%				NX	9.5%		NX	NIL		→ Portion					
30.00				43	44,				SP	TO Grey moderately weathered			29.33				NX	NILL		NX	NIL							
32.00				45.					SP.	Bouldering Highly weathered Granite		16%					NX	NIL		NX	NIL							
33.00				46	48,	49.50			SP				38.33%				NX	10.6		NX	NIL							
35.00						el.			SP	Bouldering Highly weathered Granite		16%,					NX	NIL		NX	NIL							

	Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
	Bachu	Pwm	mohan	

Sohams Foundation Engineering Pvt. Ltd. Mumbai

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No : SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 113

Sheet : 4 of 8

Location : TB-6 | Co-ordinates 20-G-5TD02 | Feature :

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: ~~96.075~~ 97.745

Total depth : 65.00MTR | Type (s) of core barrel : DoubleTube | Drilling Agency : SFE

Started : | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0	20	40	60	80	100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Water loss: Partial	Drill Water loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
35.00						52, SP.			SP.			22.66					NX	Nill		NX	NIL							
35.50						SP, 53, 54,			SP.			22.66					NX	Nill										
36.00					59,	SP, 55, 56,			SP.				45%				NX	Nill		21%	NIL		Partial					
40.00						60, 61,			SP, SP					62%			NX	Nill			NIL							
40.50						62, 66.			SP, 63,						69%		NX	47%										
41.00					64,	64, 67, 70,			SP.	Light Gray to Green, moderately weathered Granite		38.66%					NX	6%			NIL							

Sohams | NPCIL

SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
Nilesh Chhede	Rachel	Rajan	mohanty	

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 113

Sheet : 5 of 8

Location : TB-6 | Co-ordinates 20-4-5900 | Feature :

Angle with horizontal : 90° | Collar Elevation: | Existing Ground Elevation: 97.745

Total depth : 65.00 MTR. | Type (s) of core barrel Double Tube | Drilling Agency : SFE

Started : | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0	20	40	60	80	100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
42.50					81,82,80.	SP,71,72,73,74,75											NX	46.66		NX	NIL							
44.00																												
45.50				SP.	83,84,85,86,			SP					49.33				NX	32 %		NX	NIL							
47.00					87,88.			SP	Light Grey to Green in colour moderately weathered Garnetiferous Chlorite schist				65.33				NX	12 %		NX	NIL	→ Partial						
48.50					90,93.			SP					45.33				NX	14 %		NX	NIL							
50.00				94,95,96,97,98,99,91,92,				SP			40.66						NX	NIL		NX	NIL							

Sohams | NPCIL

SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
Nilesh Shinde	Rachel	Rao		

Sohams Foundation Engineering Pvt. Ltd. Mumbai

SFE

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No: 113

Sheet 6 of 8

Location: TB-6 | Co-ordinates 20-4-5T0 02 | Feature:

Angle with horizontal: | Collar Elevation: | Existing Ground Elevation: ~~96.075~~ 97.745

Total depth: 65.00 MTR. | Type (s) of core barrel: Double Tube | Drilling Agency: SFE

Started: | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0–20–40–60–80–100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
50.00						98	3P		Light Grey to Green moderately weathered Granite with chlorite schist		42%	NX	Nil		NX	Nil							
51.50				107,108, 100,103,104,105,106																			
53.50				101,102,							45.5%	NX	39.5%		NX	Nil		Practically					
55.00						109.	110.		Green, moderately weathered Granite		20.66%	NX	10.		NX	Nil							
56.50							111.	3P	Light Grey to Green weathered Granite		49.33%	NX	6.66		NX	Nil							

	Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
Rinda, Nagesh Shinde	Bachu	Pawar	Mohanty	

Sohams Foundation Engineering Pvt. Ltd. Mumbai

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 113

Sheet : 7 of 8

Location : TB-6 | Co-ordinates 20-G.5700 | Feature :

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: ~~97.5~~ 97.745

Total depth : 65.00MTR. | Type (s) of core barrel DoubleTube

Started : | Completed: | Drilling Agency : SFE

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Wate loss: Partial	Drill Wate loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
56.50					112,118, ~~SP~~, 119.	113,114,115,116,SP	112, SP.				85%	NX	89%		NX	NX							
57.50																							
58.00						SP.	120.				50%	NX	Nill		NX	NX							
60.58						121,122,123,124,	SP, SP, SP		To Green, moderately weathered		52%	NX	12.4%		NX	NX		Partial					
63.00					129,130,131	127,128,132,SP.	125,126,SP		Light Grey Granite		47.2%	NX	31.2		NX	NX							

Rshinde Nikesh Shinde

SIGNATURE

Sohams		NPCIL	
Logged By (Geologist)	Checked By (QA)	Civil	QA
Rachel	Pawar	mohay	

Sohams Foundation Engineering Pvt. Ltd. Mumbai

Project: Carrying out Geo-technical and Geo-Physical investigations for Kaiga 5&6, Kaiga Site, PO Kaiga, Karwar, Uttara Kannada Dist. Karnataka state

Format No. SFE/KAIGA5&6/RD/01

Date:

Job No: | Created By: | Created on:

GEOLOGICAL LOG OF BORE HOLE

Hole No : 113

Sheet : 8 of 8

Location : TB-6 | Co-ordinates 20-4'5"N 2 | Feature :

Angle with horizontal : | Collar Elevation: | Existing Ground Elevation: ~~97.745~~ 97.745

Total depth : 65.00MTR. | Type (s) of core barrel Double Tube | Drilling Agency : SFE

Started : | Completed:

Depth, m	Elevation	Litholog: Description	Litholog: Log	Size of core pieces: <10 mm	10 mm to 25 mm	25 to 75 mm	75 to 150 mm	>150 mm	Structural Condition: Description	Structural Condition: Log	Percent Core recovery: 0 20 40 60 80 100	Type of Bit	R.Q.D. %	Facture Frequency per m	Size of Hole	Casing	Depth of water level, m	Drill Water loss: Partial	Drill Water loss: Complete	Permeability: Test section	Permeability: Lugeon	Penetration Rate cm/hr	Special observations & interpretations (if any)
63.00					133, 134, SP	SP, 138, 135	136, 137, 138		Light Grey to Green moderately weathered Granite		54.75%	NX	27.75%		NX	NIL		Partial					
65.00																							

Bhimde Nilesh Bhimde

	Sohams		NPCIL	
SIGNATURE	Logged By (Geologist)	Checked By (QA)	Civil	QA
	S.F.E.			Lithology and structural log recorded

inspection of both the bellows and the support structures without any difficulty.

PURCHASER has carried out certain engineering activities related to safety class 2 portion of the secondary cycle system. (Refer section C-2-2-1)

15 Fire Hazard Analysis (FHA) of turbine building will be carried out by purchaser. Ratings are based on following considerations.

- All the Structures and components that form the compartment envelope shall have fire rating as stated.
- Containment envelope includes walls, ceiling ventilation dampers, doors and cable penetration seals. Vision panels in fire doors, wherever used shall be of the same rating as the doors.
- In case, a structure/component is shared between two compartments, then the rating of that structure/component is governed by maximum of the two estimated ratings.

Estimated and recommended ratings of Turbine Building

S.No.	Area	Required Rating
1	Various pits where pumps are located eg. MSDP, LPHDP or any other pump	60 min
2	Condensate Extraction Pump & Heat Exchanger Area	60 min
3	Generator seal oil unit area	90 min
4	Dry panel room (SWAS room)	60 min
5	Wet panel room (SWAS room)	60 min
6	H_2/CO_2 gas cylinder room	60 min
7	Open turbine building hall at all Elevations	60 min
8	Turbine oil storage tank room	180 min + active suppression
9	Lube oil room	180 min + active suppression
10	Turbine building annex building rooms and inside annex building	60 min
11	Battery Room	60 min
12	UPS Charger Room	60 min
13	AHU Room	60 min
14	Cable Spreader Room	60 min
15	Local Control room inside turbine building	60 min
16	Air Washer Plant	60 min

The above ratings are with assumption that lubricating oil for turbine generator & other equipment like BFP is mineral oil. Control fluid for turbine generator is fire resistance fluid and all cables are FRLS cables.

TBEB FIRE RATINGS

Ratings are based on following considerations.

- All the Structures and components that form the compartment envelope shall have fire rating as stated. (Refer Sec.3.2.4 of AERB Safety Standard No. AERB/NF/SS/FPS (Rev.1) "FIRE PROTECTION SYSTEMS FOR NUCLEAR FACILITIES")
- Containment envelop includes walls, ceiling ventilation dampers, doors and cable penetration seals. Vision panels in fire doors, wherever used shall be of the same rating as the doors.
- In case, a structure/component is shared between two compartments, then the rating of that structure/component is governed by maximum of the two estimated ratings.

Floor EL (M)	Room No	Room	Required Rating
95.5	TBE-101	Cable gallery	60 min
95.5	TBE-101	Cable shaft	60 min
100	TBE-201	Div-I 415v Swgr Room	60 min
100	TBE-202	Div-Ii 415v Swgr Room	60 min
100	TBE-203	Passage	60 min
100	TBE-204	Cable shaft	60 min
105.3	TBE-301	Cable gallery Div-I	60 min
105.3	TBE-302	Cable gallery Div-Ii	60 min
105.3	TBE-303	Passage	60 min
105.3	TBE-304	Cable shaft	120 min
105.3	TBE-305	Cable bridge	60 min
111	TBE-401	Div-I 6.6 Kv Swgr room	60 min
111	TBE-402	Div-Ii 6.6 Kv Swgr room	60 min
111	TBE-403	Passage	60 min
111	TBE-404	Cable shaft	60 min
118	TBE-501	Cable gallery Div-I	60 min
118	TBE-502	Cable gallery Div-Ii	60 min
118	TBE-503	Passage	60 min
118	TBE-504	Cable shaft	60 min
122	TBE-601	Div-I 415v Mcc room	60 min
122	TBE-602	Div-Ii 415v Mcc room	60 min
122	TBE-603	Passage	60 min
122	TBE-604	Cable shaft	60 min
126.5	TBE-701	Escada room	60 min
126.5	TBE-702	Ahu room	60 min
126.5	TBE-703	Passage	60 min
126.5	TBE-704	Cable shaft	60 min

All the remaining structures shall have the rating of 60mins.

- Fans
- Light fittings
- A/C Diffuser
- Fire detectors
- Sprinklers
- Speakers etc.

2.9 **Alternative routes for access to LCRs:** There shall be adequate alternate routes through which the control room staff can leave or reach the LCR.

2.10 **Space Requirement:**

Tentative requirement of space for local control rooms in turbine building is given below.

Sr. No	Description	Elevation in turbine building	Room size	Air conditioning with false ceiling and Anti-static flooring
1	SWAS room	Vendor to specify	Vendor to specify	Required for SWAS dry panel room
2	Test and calibration room	Vendor to specify	Vendor to specify (minimum 6m X 8m)	YES
3	Battery rooms (at least two separate rooms shall be provided. One for 'NSR-N' battery banks & another for 'NSR-X' battery banks)	Vendor to specify	Vendor to specify	For battery room dry And cool air shall be circulated in such that the temperature does not increase beyond 35^{o}C.
4	UPS/DCPS rooms (at least two separate rooms shall be provided. One for 'NSR-N' UPSs & DCPSs and another for 'NSR-X' UPSs & DCPSs)	Vendor to specify	Vendor to specify	YES
5	Local control center (LCC)	Vendor to specify	Vendor to specify	YES

Height of above mentioned rooms shall be minimum 4.5m. The battery, UPS, DCPS rooms and LCC shall be located such that the cabling distance is as minimum as achievable.

2.11 **Auditory environment**

The auditory environment in the LCRs shall be such that the operators can perform their tasks effectively & comfortably.

9.2 Wiring for Ceiling Light

a. Wiring for Ceiling Light:

i. Wiring for ceiling lights: For ceiling wiring inter looping will be done and switches will be provided.

ii. The system of wiring shall consist of Low Halogen Low Smoke (LHLS) copper conductor stranded flexible wires of 1100 volts grade of insulation, in metallic conduits for all exposed wiring and concealed wiring. Minimum size of copper conductor shall be 1.5 sq. mm for lighting and 2.5 sq.mm for power. Color code shall be maintained for the entire wiring installation.

iii. Appropriate ferrule will be used at both the ends.

9.3 SWITCHES & SOCKETS

a. Dual shutter mechanism for easy & better fitment Wide & flat switch knob for easy operation. FR grade polycarbonate with high impact resistance, shock proof & UV rays stabilized.

9.4 MCBs

a. For the control and protection of low voltage installations against overload and short circuits.
b. Ripping characteristic: C Curve – 5 to 10 x In
c. Isolation function
d. Double entry points, separate bus bar entry, open mouthed terminal and lift clamps.

10. FLOORING-

10.1 Acoustic & Antistatic Flooring: -

Acoustic flooring (shall reduce impact sound by 14dB) and an electrical resistance of more than 30MΩ. Flooring shall be decorative type of approved shade, pattern, texture and design and of approved manufacturer. Dimensions shall be as per the final approved design and site requirement. Flooring shall be laid over concrete floor with laying compound strictly as per manufacturer's specification.
Mandatory requirement: The Floor Surface material shall be Green guard (UL) certified to avoid VOC free / low emitting surface.

The Flooring material shall be Green guard (UL) Certified.

3.2 Warranty:

a. Five year's warranty against any manufacturing defect on 'control room area' design including but not limited to Illumination, Floorings, Custom designer metal ceilings, wall claddings and doors.

3.3 Design Criteria: -

a. The ceiling, Paneling and partition shall be of modular design, facilitating future equipment retrofits and full reconfigurations without requiring any major modification to the structure.

3.4 Product Specific Mandatory Requirement

Copy of Test certification for the surface burning characteristics of wall Paneling tiles and ceiling tiles to be submitted along with the technical Bid.

3.5 Quality Criteria: -

a. To ensure uniformity, consistency & quality in final product the 'control room area' & Control manufacturer preferably shall have In-house Powder Coating Plant, metal manufacturing and wood processing plant.

4. PANELING



4.1 Design & Material Specification for Paneling

a. Factory made removable type self inter lockable metal panels of Preformed textured hot dip galvanized strips and sheets of low carbon steel. Panel shall be of 0.75mm thick galvanized metal of NPCIL approved colour. Panels shall be designed to achieve shape and design as per the NPCIL approved design. Overall system thickness for panelling shall be 70mm to 85mm and for partition shall be 85mm to 110mm.

b. Panel shall be design in such a manner that it takes care of undulation of civil walls and gives perfect flat surface finish and compile easy service & maintenance procedure.

c. Sound transmission class (STC) value of 35 for Wall Paneling & Partition. Test report from NPCIL approved agency to be submitted during drawing approval stage before commencement of the job.

4.2 Design:

a. The cladding panels may be made up of combination of two sheets locked and riveted together and suitably infilled to achieve strength and acoustics. The front tile may be perorated/ non-perforated as per the design requirement. These tiles shall be bend, punched & cut to achieve perfect accuracy.

b. Structure shall be made from heavy duty powder coated modular steel frame (minimum sheet thickness 1 to 1.6mm) and shall allow uninterrupted flow of wires/cable/tubes of max. dia. 25mm.

c. Structure shall be securely grouted from wall, roof and floor. Grid of desired dimension shall be formed by Vertical and horizontal sections.

4.3 Surface Finish:

a. For Panels:

i. Front Panel: Fire retardant pre-coated GI sheet (sheet thickness: 0.6mm and coating: 0.15mm)

ii. Back Cover: Powder coated GI sheet. (sheet thickness: 0.6mm with powder coating:)

b. For Structure:

i. **Powder coated sheet. (sheet thickness: 1.0mm to 1.6mm with powder coating)** The metal sheet be able to undergo stretching up to 100% and therefore follow bend with the steel in all its deformation. The sheets shall have specific fire-retardant additives as an important barrier to slow down the combustion process. It shall have electrical insulation property and shall be sustainable and easy to maintain.

Panel shall provide better thermal, electrical insulation as compared to normal GI panels. It shall be non-reflective/glare free.

4.4 Material Testing/Certification (all certificates to be submitted during drawing approval stage before commencement of the job):

a. Fire retardant pre-coated sheet:

Fire rating and Low flame spread: EN ISO 11925-2, EN 13823 and ASTM E-84

b. Core material:

Acoustic test: 9301/ ISO: 140/ASTM 413, ASTM C 578.

c. Powder coating

i. Adhesion test: EN ISO 2409 (2 mm)
ii. Impact resistance test: ASTM D 2794 (5/9' ball)
iii. Flexibility test: EN ISO 1519
iv. Salt spry test: 600 hrs.
v. Resistance to humid atmosphere test: DIN 50017.

Supplier can submit available test report or certificate from the reputed labs and as per the international standards for purchaser's verification and acceptance.

4.5 Component Specification:

a. Floor Mounting: -

i. C channels of suitable thickness (around 3mm) are welded together to form an 'I' section having minimum height of 150mm. This 'I' section shall be welded on MS grouting plate.
ii. This assembly shall be grouted on the floor with the help of suitable Anchor Fasteners.
iii. These Floor Mountings shall be the base support to the vertical uprights spaced at a center to center distance of 1200mm maximum.
iv. Contractor must ensure proper marking and levelling before proceeding with any floor grouting.

b. Panel:

i. The panels shall be hooked/mounted on the uprights.
ii. Panels shall have integrated hooks.
iii. The panels shall have suitable gap between two tiles so that the tiles can be replaced and installed easily.
iv. The hooks of the Panels shall ensure that they firmly held on the uprights.
v. The panel shall have hook-in arrangement (with gravity lock).

c. Corner Cap:

i. On extreme ends of control room the wall connector (L- profile) may be fixed on the perimeter walls. This L-section may be snap fitted and then bolted to the walls.

d. Door Profile:

i. Door frame shall be fixed with these profile so as to have proper integration of doors with the overall system.

e. **Feature:**

i. Raw material for tile & powder coating should not affect environment, vendor to provide necessary test certificate.
ii. Colour should not fade over 10 years.
iii. No sagging
iv. Easy and quick installation
v. Easily cleanable
vi. Vendor to demonstrate one portion at wall paneling & ceiling at their premises before dismantling & shipping to site. In short a FAT (Factory acceptance test) to be carried out at vendors works for ceiling & paneling.
vii. 100 % modular design. At site, no cutting, chipping work is allowed.
viii. The tile shall be bend resistant

5. Straight Metal paneling

Paneling with factory made removable type self inter lockable metal panels of preformed fire retardant coated GI sheet panels. The metal panels fixed on structure made of 1.6 mm thick MS channels. Their properties shall be as follows:-

a. Resistance to extremes of weather exposure and temperature.
b. Very low coefficient of expansion.
c. Can be cleaned using detergents.
d. Superior flatness – ideal of creating smooth, monolithic surface.

All the properties and material of construction shall be like Metal paneling.

6. Cladding for Mounting the LVS/Screen

a. Suitable cladding with sturdy metal under-structure. The top finish must be fire retardant, Insulated, Water & Scratch resistance and shall have high hardness.
b. The material must be homogeneous throughout the depth with compliance to Green-Guard.
c. Thickness of the cladding shall be 12mm / 6mm, the ends shall have curvilinear design duly filleted / rounded.
d. The structure shall be modular to ensure easy maintenance and replacement.
e. All the fasteners should be hidden, and nuts/bolts shall not be visible on the exposed surface.
f. The top finish of material shall be Green guard Certified, and it shall be homogeneous throughout the depth.
g. It shall have Flame Spread Index FSI <25 as per ASTM E-84 surface Burning Characteristics of Building Materials.

7. DOORS

7.1 Metallic Door

With door spring and locking arrangements and both way handle. Specification: 0.6mm thick Metal panel sheets, cavity filled with glass wool insulation of sufficient density in roll form inside adequate quantity. Material of the partition and that of metal door will remain the same.

VOLUME: II B

SECTION - D

SUB-SECTION – D1

EARTHWORK IN EXCAVATION AND BACKFILLING

SPECIFICATION NO. PE-TS-999-600-C001

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.0	SCOPE	3
2.00.00	GENERAL	3
3.00.00	EXECUTION	6
4.00.00	TESTING AND ACCEPTANCE CRITERIA	19
5.00.00	RATES AND MEASUREMENTS	19
6.00.00	INFORMATION TO BE SUBMITTED BY THE BIDDER	20

STANDARD TECHNICAL SPECIFICATION FOR EARTHWORK IN EXCAVATION AND BACKFILLING

1.0.0 SCOPE

This specification covers earth work excavation in all types of soil, soft rock and hard rock including setting out, clearing and grubbing, shoring, dewatering, back filling around foundations/pipelines to grade, watering, compaction of fills, testing, approaches, disposal of surplus earth, protective fencing, lighting etc relevant to the structures and locations covered under this contract.

2.0.0 GENERAL

2.1.0 Work to be provided for by the Contractor

The work to be provided for by the contractor unless specified otherwise shall include but not be limited to the following.

a) Supplying and providing all labour, supervision services, earth moving machineries, surveying instruments including facilities as required under statutory labour regulations, materials, scaffolds, equipment, tools and plants, transportation, etc. required for the work.

b) Preparation and submission of working drawings showing the approaches, slopes, berms, shoring, sumps for dewatering including drainage, space for temporary stacking of soils, disposal area, fencing etc and all other details as may be required by the engineer.

c) To carry tests and submit to the Engineer, test results of fill materials and degree of soil compaction of fill whenever required by the Engineer to assess the quality of fill.

d) Design, construction and maintenance of Magazine of proper capacity for storage of explosives for blasting work and removal of the same after completion of the work etc. including procurement of necessary licenses from proper authorities.

2.2.0 Work to be provided by others

No work under this specification will be provided by any agency other than the contractor unless specifically mentioned elsewhere in the contract.

2.3.0 Codes and Standards

All works shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes unless specified otherwise.

IS-1200	Method of measurement of building and civil engineering works, Part-I: Earthwork
IS-2720	Method of test for soils (Relevant parts)
IS-3764	Excavation work - Code of safety
IS-4081	Safety code for blasting and related drilling operations
IS-4701	Indian Standard Code of Practice for earthwork on Canals
IS:6922	Criteria for safety and design of structures subject to underground blasts
IS: 3764	Excavation work – code of safety

In case of conflict between this specification and those (IS Codes) referred to herein, the former shall prevail. In case any particular aspect of work is not covered specifically by this specification/IS Codes, any other standard practice as may be specified by the engineer shall be followed.

2.4.0 Conformity with Designs

The contractor shall carry out the work as per the approved drawings, specification and as directed by the engineer.

2.5.0 Materials

2.5.1 General

All materials required for the work shall be of the best commercial variety and approved by the engineer.

2.5.2 Material for Excavation

For the purpose of identifying the various strata encountered during the course of excavation, refer clause no. 3.4.0 for the classification of earth strata.

2.5.3 Material for Filling

Material to be used for back filling shall be free from vegetations, roots, salts, rubbish, lumps, organic matter and any other harmful chemicals etc and shall be got approved by the engineer. Normally excavated earth shall be used for back filling. In case such earth contains deleterious salts, the same shall not be used. All clods of earth shall be broken or removed. Where the excavated material is mostly rock and if filling with the same is permitted by the engineer in writing, then the filling with rock shall be done in the following

manner. The boulders shall be broken into pieces not exceeding 150mm size in any direction and mixed with fine materials consisting of decomposed rock, moorum or any approved earth to fill the voids as for as possible and the mixture shall then be used for filling.

In case the earth required for backfilling is over and above the earth available from the compulsory excavations within the project area, then borrow areas for obtaining suitable fill material shall be arranged by the contractor himself from outside the plant boundary limits and all expenses including royalties, taxes, duties etc shall be borne by him. The selected earth from the borrow areas shall be got approved by the engineer. The borrowed material shall be free from roots, vegetations, decayed organic matter, harmful salts and chemicals, free from lumps and clods etc. The contractor shall obtain and submit necessary clearances/permissions from the concerned authorities for the borrow areas/materials acquired to the engineer.

If specified, the back filling shall be done with clean well graded sand from approved quarries free from harmful and deleterious materials.

2.6.0 Quality Control

All works shall confirm to the lines, levels, grades, cross sections and dimensions shown on the approved drawings and/or as directed by the engineer. The contractor shall establish and maintain quality control for the various aspects of the work, method of construction, materials and equipments used etc. The quality control operation shall include but not be limited to the following.

Sl. No.	Activity	Check
1	Lines, levels & grades	a) By periodic surveys b) By establishing markers, boards etc
2	Back filling	(a) On quality of fill material (b) On moisture content of back fill (c) On degree of compaction achieved

2.7.0 Information regarding site conditions

Surface and Sub-surface data regarding the nature of soil, rock, sub-soil water etc. shown on drawing or otherwise furnished to the Contractor shall be taken as a guidance only and variation therefrom shall not affect the terms of the contract. The Contractor must satisfy himself regarding the character and volume of all work under this contract and expected surface, sub-surface and / or sub-soil water to be encountered. He must also satisfy himself about the general conditions of site and ascertain the existing and future construction

likely to come up during the execution of the contract so that he may evolve a realistic programme of execution.

3.0.0 EXECUTION

The contractor shall prepare and submit the detailed drawings/schemes for excavation and back filling works as proposed to be executed by him showing the dimensions as per the construction drawings and specification adding his proposal of slopes, shoring, approaches, dewatering, drainage, berms etc. for the approval of engineer.

3.1.0 Setting out

On receiving the approval from the engineer with modifications and corrections if any, the contractor shall set out the work from the control points furnished by the engineer and fix permanent points and markers for ease of periodic checking as the work proceeds. These permanent points and markers shall be fixed at the interval as prescribed by the engineer and shall be got checked and certified by the engineer after whom the contractor shall proceed with the work. It should be noted that this checking by the engineer prior to the start of the work will in no way relieve the contractor of his responsibility of carrying out the work to true lines, levels and grades as per the drawings and specification. If any errors are noticed in the contractor's work at any stage, the same shall be rectified by the contractor at his own risk and cost.

3.2.0 Initial Levels

Initial levels of the ground either in a definite grid pattern or as directed by the Engineer will be taken by the Contractor jointly with the Engineer over the original ground prior to starting actual excavation work and after setting out. These initial levels will be used for preparing cross-sections for volume measurement or for cross-checking the depths obtained from tape measurements. All records of levels, measurements etc. and also any drawing, cross-section etc. made therefrom, shall be jointly signed by the authorised representative of the contractor and the Engineer before the commencement of work and they shall form the basis of all payments in future.

3.3.0 Clearing and Grubbing

The area to be excavated shall be cleared out of fences, trees, logs, stumps, bushes, vegetation, rubbish, slush etc. Trees upto 300mm girth shall be uprooted. Trees above 300mm girth to be cut shall be approved by the engineer and marked. Cutting of trees shall include removing roots as well. After the tree is cut and roots taken out, the pot holes formed shall be filled with good earth in 250mm layers and compacted unless directed otherwise by the engineer. The trees shall be cut in to suitable pieces as instructed by the

engineer. Before earthwork is started, all the spoils, unserviceable materials and rubbish shall be burnt or removed and disposed to the approved disposal area(s) as specified by the engineer. Useful materials, saleable timber, fire woods etc shall be the property of the owner and shall be stacked properly at the worksite in a manner as directed by the engineer.

3.4.0 Classification

All earthwork shall be classified under the following categories:

No distinction will be made whether the material is dry or wet.

a) **Ordinary Soil**

This shall comprise vegetable or organic soil, turf, sand, silt, loam, clay, mud, peat, black cotton soil, soft shale or loose moorum, a mixture of these and similar material which yields to the ordinary application of pick and shovel, rake or other ordinary digging implement. Removal of gravel or any other nodular material having diameter in any one direction not exceeding 75 mm occurring in such strata shall be deemed to be covered under this category.

b) **Hard Soil**

This shall include :
i) stiff heavy clay, hard shale, or compact moorum requiring grafting tool or pick or both and shovel, closely applied ;
ii) gravel and cobble stone having maximum diameter in any one direction between 75 and 300 mm ;
iii) soling of roads, paths, etc., and hard core ;
iv) macadam surfaces such as water bound, and bitumen/tar bound;
v) lime concrete, stone masonry in lime mortar and brick work in lime/cement mortar, below ground level ;
vi) soft conglomerate, where the stones may be detached from the matrix with picks ; and
vii) generally any material which requires the close application of picks, or scarifiers to loosen and not affording resistance to digging greater than the hardest of any soil mentioned in (i) and (vi) above.

c) **Soft and Decomposed Rock**

This shall include :
i) limestone, sandstone, laterite, hard conglomerate or other soft or disintegrated rock which may be quarried or split with crowbars ;
ii) unreinforced cement concrete which may be broken up with crowbars or picks and stone masonry in cement mortar below ground level ;
iii) boulders which do not require blasting having maximum diameter in any direction of more than 300 mm, found lying loose on the surface or embedded

in river bed, soil, talus, slope wash and terrace material of dissimilar origin ; and
iv) any rock which in dry state may be hard, requiring blasting, but which when wet becomes soft and manageable by means other than blasting.

d) **Hard Rock (requiring blasting)**

This shall include :
i) any rock or cement concrete for the excavation of which the use of mechanical plant or blasting is required ;
ii) reinforced cement concrete (reinforcement cut through but not separated from the concrete) below ground level; and
iii) boulders requiring blasting.

e) Hard Rock (blasting prohibited)

Hard rock requiring blasting as described under (d) but where blasting is prohibited for any reason and excavation has to be carried out by chiselling, wedging or any other agreed method.

In case of any dispute regarding classification, the decision of the Engineer shall be final.

3.5.0 Excavation for Foundations and Trenches

3.5.1 General

All excavation shall be done to the minimum dimensions as required for the safety and working facility. In each individual case, the contractor shall obtain prior approval of the engineer for the method he proposes to adopt for the excavation including dimensions, side slopes, shoring, dewatering, drainage and disposal etc. This approval however shall not in any way make the engineer responsible for any consequent loss or damage. The excavation must be carried out in the most expeditious and efficient manner. All excavation in open cuts shall be made true to the line, slopes and grades as shown on the drawings and/or as directed by the engineer. No material shall project within the dimension of minimum excavation lines marked. Boulders (if any) projecting out of the excavated surfaces shall be removed if they are likely to be a hindrance to the work/workers in the opinion of the engineer.

Method of excavation shall in every case be subject to the approval of the engineer. The contractor shall ensure the stability and safety of the excavation, adjacent structures, services and works etc including the safety of the workmen. If any slip occurs, the contractor shall remove all the slipped materials from the excavated pit without any extra cost to the engineer/owner. All loose boulders and semi detached rocks which are not inside but so close to the area to be excavated and may liable to fall or otherwise endanger the

workmen, equipment of the work etc during excavation in the opinion of the engineer shall be stripped off and removed away from the area of excavation. The method to be used for removal shall be such that it should not shatter or render unstable or unsafe the portion which was originally sound and safe. In case any material not required to be removed initially but later to become loose or unstable in the opinion of the engineer shall also be promptly and satisfactorily removed.

The rough excavation may be carried out upto a maximum depth of 150 mm above the final level. The balance shall be excavated with special care. If directed by the engineer, soft and undesirable spots shall be removed even below the final level. The extra excavation shall be filled up as instructed by the engineer. If the excavation (in all types of soil and rock) is done to a depth greater than that shown on the drawing or as directed by the engineer, the excess depth up to the required level shall be filled with cement concrete not leaner than 1:4:8 or richer as directed by the engineer at the own risk and cost of the contractor. In case where excavation in soil, soft rock (including weathered rock) and hard rock are involved, the excavation in each stratum shall be carried out separately with the approved methodology and as per the instructions of the engineer.

All excavated materials such as rock, boulders, bricks, dismantled concrete blocks etc shall be the property of the owner and shall be stacked separately as directed by the engineer. All gold, silver, oil, minerals, archeological and other findings of importance, trees cut or other materials of any description and all precious stones, coins, treasures, relics, antiquities and other similar things which may be found in or upon the site shall be the property of the owner and the contractor shall duly preserve the same to the satisfaction of the engineer/owner. The contractor shall deliver the same to such person or persons as may be authorized or appointed from time to time by the owner to receive the same.

Prior to starting the excavation, the ground level at the location shall be checked jointly with the engineer.

3.5.2 Excavation in All Type of Soil and in Soft Rock

The excavation in all type of soil, soft rock including decomposed rock etc shall be carried out as per the approved proposal and as directed by the engineer. The work shall be carried out in a workmanlike manner without endangering the safety of nearby structures/services or works and without causing hindrance to any other activities in the area. Foundation pits shall not be excavated to the full depth unless construction is imminent. The last 150mm depth shall be excavated once concreting work is imminent. At the discretion of the engineer, the full depth may be excavated and the bed be covered with lean concrete as specified after watering and compacting the bed. As the excavation reaches the required dimensions, lines, levels and grades

etc, the work shall be got checked and approved by the engineer. In cases where deterioration of the ground, upheaval, slips etc are expected, the engineer may order to suspend the work at any stage and instruct the contractor to carry out the protection works before the excavation will be restarted.

3.5.3 Excavation in Hard Rock

Hard rocks shall normally be excavated by means of blasting. In case where blasting is prohibited for any reasons, the excavation shall be carried out by chiselling or any other approved method as directed by the engineer. Personnel deployed for rock excavation shall be protected from all hazards such as loose rock/boulder rolling down and from general slips of excavated surfaces. Where the excavated surface is not stable against sliding, necessary supports such as props, bracings or bulkheads shall be provided and maintained during the period of construction. Where the danger of falling loose rock/boulder from the excavated surfaces deeper than 2m exist, steel mesh anchored to the lower edge of the excavation and extending over and above the rock face adequate to retain the dislodged material shall be provided and maintained.

3.5.4 Blasting

Storage, handing and use of explosives shall be governed by the current explosive rules/regulations laid down by the Central and the State Governments. The contractor shall ensure that these rules/regulations are strictly adhere to. The following instructions are also to be strictly followed and the instructions wherever found in variance with the above said rules/regulations, the former (instructions) shall be superseded with the later (above said rules/regulations).

No child under the age of 16 and no person who is in a state of intoxication shall be allowed to enter the premises where explosives are stored nor they shall be allowed to handle the explosives. The contractor shall obtain licence from the District Authorities for undertaking the blasting work as well as for obtaining and storing the explosives as per Explosives Rules, 1940 corrected upto date. The contractor shall purchase the explosives, fuses, detonators etc only from a licensed dealer and shall be responsible for the safe custody and proper accounting of the explosive materials. The engineer or his authorized representative shall have the access to check the contractor's store of explosives and his accounts at any time. It is the full responsibility of the contractor to transport the explosives as and when required for the work in a safe manner to the work spot.

Further, the engineer may issue modifications, alterations and new instructions to the contractor from time to time. The contractor shall comply with the same without these being made a cause for any extra claim.

3.5.4.1 Materials

All materials such as explosives, detonators, fuses, tamping materials etc proposed to be used in the blasting operation shall have the prior approval of the engineer. Only explosives of approved make and strength are to be used. The fuses known as instantaneous fuse must not be used. The issue of fuse with only one protective coat is prohibited. The fuse shall be sufficiently water resistant as to be unaffected when immersed in water for 30 minutes. The rate of burning of the fuse shall be uniform and shall be not less than 4 seconds per inch of length with 10% tolerance on either side. Before use, the fuse shall be inspected. Moist, damaged or broken ones shall be discarded. When the fuses are in stock for long, the rate of burning of fuses shall be tested before use. The detonators shall be capable of giving an effective blasting of the explosives. Moist and damaged detonators shall be discarded.

3.5.4.2 Storage of Explosives

The current Explosive Rules shall govern the storage of explosives. Explosives shall be stored in a clean, dry and well ventilated magazine to be specially built for the purpose. Under no circumstances should a magazine be erected within 400m of the actual work site or any source of fire. The space surrounding the magazine shall be fenced and the ground inside shall be kept clear and free from trees, bushes etc. The admission to this fenced space shall be through a single gate only and no person shall be allowed without the permission of the officer-in-charge. The clear space between the fence and the magazine shall not be less than 90m. The magazine shall be well drained. Two lightning conductors, one at each end shall be provided to the magazine. The lightning conductors shall be tested once in every year.

Explosives, fuses and detonators shall each be separately stored. Cases of explosives must be kept clear of the walls and floors for free circulation of air on all sides. Special care shall be taken to keep the floor free from any grains of explosives. Cases containing explosives shall not be opened inside the magazine and the explosives in open cases shall not be received into a magazine. Explosives which appear to be in a damaged or dangerous condition are not to be kept in any magazine but must be removed without delay to a safe distance and be destroyed.

Artificial light, matches, inflammable materials, oily cotton, rag waste and articles liable to spontaneous ignition shall not be allowed inside the magazine. Illumination shall be obtained from an electric storage battery lantern. No smoking shall be allowed within 100m distance from any magazine.

Magazine shoes without nails shall be used while entering the magazine. The persons entering the magazine must put on the magazine shoes which shall be

provided at the magazine for this purpose and should be careful

* not to put their feet on the clean floor unless the magazine shoes on.

* not to touch the magazine shoes on ground outside the clean floor.

* not to allow any dirt or grit to fall on the clean floor.

Persons with bare feet shall dip their feet in water before entering the magazine and then step directly from the tub to the clean floor. No person having article of steel or iron with/on him shall be allowed to enter the magazine. Workmen shall be examined before entering the magazine to check none of the prohibited articles are with them. A brush broom shall be kept in the lobby of the magazine for cleaning the magazine. Cleaning shall be done immediately after each occasion whenever the magazine is opened for receipt, delivery or inspection of the explosives.

The mallets, levers, wedges etc for opening the barrels or cases shall be of wood. The cases of explosives are to be carried by hand and shall not be rolled or dragged inside the magazine. Explosives which have been issued and returned to the magazine are to be issued first; otherwise those which have been stored long in the store are to be issued first. Neither the magazine shall be opened nor any person shall be allowed in the vicinity of the magazine during any dust storm or thunderstorm. All magazines shall be officially inspected at definite intervals and a record of such inspections shall be kept.

3.5.4.3 Carriage of Explosives

Detonators and explosives shall be transported separately to the blast site. Explosives shall be kept dry and away from direct rays of the sun, artificial lights, steam pipes or heated metal and other sources of heat. Before explosives are removed, each case or package shall be carefully examined to ascertain that it is properly closed and shows no sign of leakage.

No person except the driver shall be allowed to travel on the vehicle conveying explosives. No explosive shall be transported in a carriage or vessel unless all iron or steel therein the carriage or vessel which are likely to contact the package containing explosives are effectually covered with lead, leather, wood, cloth or any other suitable material. No light shall be carried on the vehicle carrying explosives and no operation connected with the loading, unloading and handling of explosives shall be conducted after sunset.

3.5.4.4 Use of Explosives

The contractor shall appoint an agent who shall personally superintend the firing and all operations connected therewith. The contractor shall satisfy himself that the person so appointed is fully acquainted with his

responsibilities.

Holes for charging the explosives shall be drilled with pneumatic drills and the drilling pattern shall be so planned that the rock pieces after blasting will be suitable for handling. The hole diameter shall be of such a size that the cartridges can easily pass down through them and any undue force is not required during charging. Charging operation shall be carried out by or under the personal supervision of the shot firer. Wrappings shall never be removed from the explosive cartridges. Only one cartridge at a time shall be inserted in a hole and wooden rods shall only be used for loading and stemming the shot holes. Only such quantities of explosives as are required for a particular work shall be brought to the work site. Should any surplus remain when all the holes have been charged shall be carefully removed to a point at least 300m away from the firing point.

The authorized shot firer himself shall make all the connections. The shot firing cable shall not be dragged along the ground to avoid any damage to the insulation. The shot firing cable shall be tested each time for its continuity and possible short circuiting. The shot firer shall always carry the exploder handle with him until he is ready to fire shots. The number of shots fired at a time shall not exceed the permissible limits. Before any blasting is carried out it shall be ensured that all workmen, vehicles and equipment on the site are cleared from an area of minimum 300m radius from the firing point or as required by the statutory regulations at least 10 minutes before the time of firing by sounding a warning siren and the area shall be encircled by red flags.

The explosives shall be fired by means of an electric detonator placed inside the cartridge. For simultaneous firing of a number of charges, the electric detonators shall be connected with the exploder through the shot firing cable in a simple series circuit. Due precautions shall be taken to keep the firing circuit insulated from the ground, bare wires, rails, pipes or any other path of stray current etc and keep the lead wires short circuited until it is ready to fire. Any kink in the detonator leading wire shall be avoided. For simultaneous firing of a large number of shot holes, use of cordtex may be done. An electric detonator attached to its side with adhesive tape shall initiate cordtex connecting wire or string. Blasting shall only be carried out at certain specified times to be agreed jointly by the contractor and the engineer.

At least five minutes after the blast has been fired in case of electric firing or as stipulated in the regulations, the authorized shot firer shall return to the blast area and inspect carefully the work and satisfy himself that all the charged holes have exploded. Cases of misfired unexploded charges shall be exploded by drilling a parallel fresh hole at a distance of not less than 600mm from the misfired hole and by exploding a new charge. The authorized shot firer shall be present during the removal of debris as it may contain unexploded explosives near the misfired hole. The workmen shall not return to the site of firing until at least half an hour after firing.

Where blasting is to be carried out in proximity of other structures, controlled blasting by drilling shallow shot holes and proper muffling arrangements with steel plates loaded with sand bags etc shall be used on top of the blast holes to prevent the rock fragments from causing any damage to the adjacent structures and other properties. Adequate safety precautions as per building byelaws, safety codes, statutory regulations etc shall be taken during blasting operations.

3.5.4.5 Restrictions in Blasting

a) Blasting which may disturb or endanger the stability, safety or quality of the adjacent structures/foundations shall not be permitted.
b) Blasting within 200m of a permanent structure or construction work in progress shall not be permitted.
c) Progressive blasting shall be limited to two third of the total remaining depth of excavation.
d) No large scale blasting operations will be resorted to when the excavation reaches the last one metre and only small charge preferably black powder may be allowed so as not to shatter the parent rock.
e) The last blast shall not be more than 0.50 m in depth.
f) In rocky formations, at locations where specifically indicated or ordered in writing by the engineer, the use of explosives shall be discontinued and excavation shall be completed by chiselling or any other suitable method as approved by the engineer.

3.5.5 Disposal

The excavated spoils shall be disposed of in any (or all) of the following manner as directed by the engineer.

a) By using it straightway for backfilling.

b) By stacking it temporarily to use for backfilling at a later date during execution of the contract.

c) i) By either spreading
or
ii) By spreading and compacting at designated disposal areas.

a) By selecting the useful material and stacking it neatly in designated areas as indicated by the engineer for use in backfilling by some other agency.

3.5.6 Disposal of Surplus Materials

All surplus material from excavation shall be removed and disposed of from the excavation site to the designated disposal area indicated by the engineer.

All good and sound rocks obtained from excavations and all assorted materials of dismantled structures are the property of the owner and if the contractor wants to use it, he shall have to obtain it from the engineer at a mutually agreed rate. All sound rocks and other assorted materials like excavated bricks etc shall be stacked separately.

3.5.7 Protection

The contractor shall notify the engineer as soon as the excavation is expected to be completed within a day so that he shall inspect it at the earliest. Immediately after approval of the engineer, the excavation must be covered up in a shortest possible time. But in no case the excavation shall be covered up or worked on before approval by the engineer. Excavated material shall be placed 1.5m or half the depth (of excavation) whichever is more from the edge of the excavation or further away if directed by the engineer. Excavation shall not be carried out below the foundation level of the structure close by until the required precautions are taken. Adequate fencing is to be made enclosing the excavation. The contractor shall protect all the underground services exposed during excavation. All existing surface drains in the work area shall be suitably diverted by the contractor before taking up excavation to maintain the working area neat and clean.

3.5.8 Dealing with Surface Water

All working areas shall be kept free of surface water as far as reasonably praticable. Works in the vicinity of cut areas shall be controlled to prevent the ingress of surface water.

No works shall commence until surface water streams have been properly intercepted , redirected or otherwise dealt with.

Where works are undertaken in the monsoon period, the Contractor may need to construct temporary drainage systems to drain surface water from working areas.

3.5.9 Dewatering

All excavation shall be kept free of water and slush. Grading in the vicinity shall be controlled to prevent the surface water running into the excavations. The contractor shall remove any water inclusive of rain water and subsoil water etc accumulated in the excavation by pumping or other means as approved by the engineer and keep the excavations dewatered and/or lower the subsoil water level to 300mm below the founding level until the construction of foundation and backfilling are completed in all respects.

Sumps made for dewatering must be kept clear of the foundations. The engineer’s prior approval on the method of pumping to be adopted shall be

taken; but in any case, the pumping arrangement shall be such that there shall be no movement or blowing in of subsoil due to the differential head of water during pumping.

3.5.10 Timber Shoring

Close or open type timber shoring as approved by the engineer depending on the nature of sub-soil, depth of pit or trench and the type of timbering shall be adopted. Timbers made out of approved quality shall only be used. It shall be the responsibility of the contractor to take all necessary steps to prevent the sides of trenches and pits from collapsing.

3.5.10.1 Close Timbering

Close timbering shall be done by completely covering the sides of the trenches and pits generally with short, upright members called "polling boards". These shall be of 250mm wide(min.) and 40mm thick(min.) sections as directed by the engineer. The boards shall generally be placed vertically in pairs, one on each side of the cut and shall be kept apart (maximum spacing is limited to 1.20m) by horizontal walers of strong wood cross strutted with wooden struts or as directed by the engineer. The length of wooden struts shall depend on the width of the trench or pit.

In case where the soil is very soft and loose, the boards shall be placed horizontally against the sides of excavation and supported by vertical walers which shall be strutted to similar timber pieces on the opposite face of the trench or pit. The lowest board supporting the sides shall be taken into the ground. No portion of the vertical side of the trench or pit shall remain exposed to avoid any slipping out of earth.

The withdrawal of the timber shall be done very carefully to prevent the collapse of the pit or trench. It shall be started from one end and proceeded systematically to the other end. Concrete or masonry shall not be damaged during the removal of the timber. No claim shall be entertained for any timber which cannot be withdrawn and is lost or buried.

3.5.10.2 Open Timbering

In case of open timbering, vertical board of 250mm wide(min.) and 40mm thick(min.) shall be spaced sufficiently apart to leave unsupported strips of maximum 500mm average width. The detailed arrangement, size of timber and the spacing etc shall be subjected to the approval of the engineer. In all other respects, the specification for close timbering shall apply to open timbering as well.

3.6.0 Treatment of Slips

The contractor shall take all precautions to avoid high surcharges and provide proper surface drainage to prevent flow of water over the sides of the excavations. These precautions along with proper slopes, berms, shoring and control of ground water should cause no slips to occur. If however slips still occur, the same shall be removed by the contractor with his own risk and cost.

3.7.0 Backfilling

3.7.1 General

The material to be used for backfilling shall be approved by the engineer which shall be obtained directly from the excavation, from the nearby areas where excavation work by the same agency is in progress, from the temporary stacks of excavated spoils or from the borrow pits as directed by the engineer. The material shall be free from lumps and clods, roots and vegetations, harmful salts and chemicals, organic materials etc.

In locations where sand filling is required, the sand used should be clean, well graded and be of the quality normally acceptable for use in concrete.

3.7.2 Filling and Compaction in Pits and Trenches all Around the Structures

As soon as the work in foundation has been accepted, the spaces around the foundation in pits and trenches shall be cleared of all debris, brick bats, mortar droppings etc and filled with approved earth in layers not exceeding 250mm (in loose thickness). Each layer(loose) shall be watered, rammed and properly compacted to the required degree to the satisfaction of the engineer. Earth shall be compacted with approved mechanized compaction machine. Usually, no manual compaction shall be allowed unless specifically permitted by the engineer. The moisture content of the fill material during compaction shall be controlled near to its optimum moisture content so as to obtain the required degree of compaction. The final surface shall be trimmed and levelled to proper profile as desired by the engineer.

3.7.3 Plinth Filling

The plinth shall be filled with earth in layers not exceeding 250mm (in loose thickness) and each layer shall be watered and compacted to the required degree with approved compaction machine or manually if specifically permitted by the engineer. When the filling reaches the finished level, the surface shall be flooded with water for at least 24 hours, allowed to dry and then rammed and compacted in order to avoid any settlement at a later stage. The finished surface of fill shall be trimmed to the slope intended to be provided for the floor.

3.7.4 Filling in Trenches for Water Pipes and Drains

Filling in trenches for pipes and drains shall be commenced as soon as the joints of pipes and drains have been tested and passed. Where the trenches are excavated in soil, the filling shall be done with earth on the sides and top of pipes in layers not exceeding 150mm, watered, rammed and compacted taking care that no damage is caused to the pipe below.

In case of trenches excavated in rock, the filling upto a height of 300mm or the diameter of the pipe whichever is more above the crown of the pipe or barrel shall be done with fine material such as earth, moorum, disintegrated rock or ash as per the availability at site and shall be filled in compacted layers not exceeding 150mm. The remaining filling shall be done in layers with the mixture of boulders (of size not exceeding 150mm) and fine material as specified elsewhere in the specification. Each layer shall be watered, rammed and compacted to the required degree and to the satisfaction of the engineer.

3.7.5 Filling in Disposal Area

Surplus materials from excavation which are not required for backfilling shall be disposed of in the designated disposal areas. The spoils shall not be dumped haphazardly but should be spread in layers approximately 250mm thick when loose, watered and compacted with the help of a compacting equipment as per the directions of the engineer. In wide areas, rollers shall be employed and compaction shall be done to the satisfaction of the engineer at the optimum moisture content which shall be checked and controlled by the contractor. In certain cases the engineer may direct the contractor to dispose the surplus materials without compaction which can be done by tipping the spoils from a high bench neatly maintaining a proper level and grade of the bench.

3.8.0 Approaches and Fencing

The contractor should provide and maintain proper approaches for the workmen and inspection. The roads and approaches around the excavation should be kept clear at all times so that there is no hindrance to the movement of men, material and equipment of various agencies connected with the project. Sturdy and elegant fencing is to be provided around the top edge of the excavation as well as around the bottom of the fill at the surplus disposal area where dumping from a high bench is in progress.

3.9.0 Lighting

Full scale area lighting is to be provided if night work is permitted or directed by the engineer. If no night work is in progress, red warning lights should be provided at the corners of the excavated pit and the edges of the fill.

4.0.0 TESTING AND ACCEPTANCE CRITERIA

4.1.0 Excavation

On completion of excavation, the dimension of the pits will be checked as per the drawings after the pits are completely dewatered. The work will be accepted after all undercuts have been set right and all over excavations are filled back to the required lines, levels and grades by placing ordinary cement concrete of 1:4:8 proportion and/or richer and/or by compacted earth as directed by the engineer. The choice of the grade of concrete will be a matter of unfettered discretion of the engineer. Over excavation of the sides shall be made good by the contractor while carrying out the backfilling. The excavation work will be accepted after the above requirements are fulfilled and all the temporary approaches encroaching inside the excavation have been removed.

4.2.0 Backfilling

The degree of compaction required will be as per the stipulation laid down in IS:4701 and the actual method of measuring the degree of compaction will be as decided by the engineer. The work of back filling will be accepted after the engineer is satisfied with the degree of compaction achieved.

5.0.0 RATES AND MEASUREMENTS

5.1.0 Rates

a) The item of work in the schedule of quantities describe the work very briefly. The various items of the schedule of quantities shall be read in conjunction with the corresponding section in the technical specification including amendments and additions if any. For each item in the schedule of quantities, the bidder's rate shall include all the activities covered in the description of the items as well as for all necessary operations in detail as described in the technical specification.

b) No claims shall be entertained if the details shown on the released for construction drawings differ in any way from those shown on the tender drawings.

c) The unit rate quoted shall include minor details which are obviously and fairly intended and which may not have been included in these documents but are essential for the satisfactory completion of the work.

d) The bidder's quoted rate shall be inclusive of supplying and providing all labour, men, materials, equipments, tools and plants, supervision, services, approaches, schemes etc.

f) In case blasting in hard rock is envisaged, the unit rate quoted for earth work shall include the cost of storage and safety arrangements for the materials required for blasting. No separate payment will be made on this account.

5.2.0 Measurements

Method of measurements are specified as below:

a) The length, breadth and depth shall be measured correct to the nearest centimeter if measurements are taken by tape. Rounding of numerical shall be as per relevant IS Codes. If the measurements are taken with staff and level, the levels shall be recorded correct to 5mm. The area and volume shall be worked out in square meter and cubic meter respectively correct to the nearest of two decimal places.

b) For earth work in excavation, the ground levels shall be taken before and after completion of the work in the actually excavated area. The quantity of earth work in excavation shall be computed from these levels in cubic meter.

c) In case of open footings (rafts/ pilecaps/ drains/ cable trench/ pipe trench/ sub soil beams etc.) up to the depth of 2.0 metres, alround excavation of 30 cm beyond the outer dimension of footing (not the PCC dimension below footing) shall be measured for payment to make allowances for centering and shuttering. Any additional excavation beyond this limit shall be at the risk and cost of the contractor and shall not be measured for payment for excavation, backfilling, carriage, dewatering etc. item of work in the schedule of quantities. (Required shoring & strutting, side slopes, benching, dewatering sump pits, approaches to the excavated pit etc. are deemed to be included in item of work in the schedule of quantities).

d) In case of open footings (Rafts/ pilecaps / drains/ cable trench/ pipe trench/ sub soil beams etc.) at a depth of more than 2.0 metre, alround excavation of 75 cm beyond the outer dimension of footing (not the PCC dimension below footing) shall be measured for payment to make allowances for centering and shuttering. Any additional excavation beyond this limit shall be at the risk and cost of the contractor and shall not be measured for payment for excavation, backfilling, carriage, dewatering etc. item of work in the schedule of quantities. (Required shoring & strutting, side slopes, benching, dewatering sump pits, approaches to the excavated pit etc. are deemed to be included in item of work in the schedule of quantities).

e) IN TRENCHES FOR BURIED PIPES & CABLES

Width of Trench

i) Upto one metre depth the authorized width of trench for excavation

shall be arrived at by adding 25 cm to the external diameter of pipe (not socket/ collar) cable, conduit etc. Where a pipe is laid on concrete bed/ cushioning layer, the authorized width shall be the external diameter of pipe (not socket/ collar) plus 25 cm or the width of concrete bed/ cushioning layer whichever is more.

ii) For depths exceeding one metre, an allowance of 5 cm per metre of depth for each side of the trench shall be added to the authorized width (that is external diameter of pipe plus 25 cm) for excavation. This allowance shall apply to the entire depth of the trench. In firm soils the sides of the trenches shall be kept vertical upto depth of 2 metres from the bottom. For depths greater than 2 metres, the excavation profiles shall be widened by allowing steps of 50 cm on either side after every two metres from bottom. Where the soil is soft, loose or slushy, width of trench shall be suitably increased or side sloped or the soil shored up as directed by the Engineer-in-Charge. However, any additional excavation beyond the limit specified for firm soil herein shall not be measured for payment for excavation, backfilling, carriage, dewatering etc. item of work in the schedule of quantities as these are deemed to be included in item of work in the schedule of quantities.

iii) Where more than one pipe, cable, conduit etc, are laid, the diameter shall be reckoned as the horizontal distance from outside to outside of the outermost pipes, cable, conduit etc.

f) Where soft rock and hard rock are mixed, the measurement shall be done as follows. The two types of rock shall be stacked separately and measured in stacks. The net quantity of each type of rock shall be so arrived by applying a deduction of 50% for looseness/voids in the stacks. If the sum of net quantity of the two types of rock so arrived exceeds the total quantity of excavation, then the quantity of each type of rock shall be worked out from the total quantity (from excavation) in the ratio of net quantities in stack measurements of the two types of rock. If stacking is not feasible, the method as suggested by the engineer shall be followed.

g) Where soil, soft rock and hard rock are mixed, the measurement shall be done as follows. The soft and hard rock shall be removed from the excavated material and stacked separately and measured in stacks. The net quantity of each type of rock shall be so arrived by applying a deduction of 50% for looseness/voids in stacks. The difference between the entire excavation and the sum of the quantities of soft and hard rock so arrived shall be taken as soil.

h) The authorized quantity (calculated on the basis of authorized width/ working space under clause no. 5.2.0 c, 5.2.0 d & 5.2.0 e) or those actually excavated, whichever, are less, shall be measured for payment.

i) Tree cutting having girth more than 300mm shall be measured in number and are separately payable as deemed not covered in excavation items of work in the schedule of quantities.

j) Special dewatering of ground water by well point method and side protection work by sheet piling are separately payable as deemed not covered in excavation items of work in the schedule of quantities.

6.0.0 INFORMATION TO BE SUBMITTED BY THE BIDDER

6.1.0 With Tender

Detail of equipments and machineries proposed to be used for excavation, backfilling and compaction shall be submitted along with the tender.

6.2.0 After Award

After award of the contract the successful bidder shall submit the following for approval.

a) Within 30 days of the award of contract, the contractor shall submit a detailed programme of the work as proposed to be executed giving completion dates of excavation for the various foundations and the time required for backfilling and compaction after completion of foundation for the structures. The earthwork programme shall be planned in accordance with the foundation programme. The programme should also show how the excavation and backfilling quantities will be balanced minimizing the temporary stacking of spoils. It is to be noted that the engineer even after initial approval of the programme may instruct the contractor to enhance or to retard the progress of work during the actual execution in order to match with the progress of foundations. The initial programme being submitted by the contractor should have sufficient flexibility to take care of such reasonable variations.

b) Within 15 days of the award of contract, the contractor shall submit the drawings for earth work in excavation and backfilling showing detail of slopes, shoring, approaches, sump pits, dewatering lines, fencing etc for the approval of the engineer.

VOLUME – II B
CIVIL, STRUCTURAL & ARCHITECTURAL WORKS

SPECIFICATION NO. PE-TS-999-600-C002

SECTION – D

SUB SECTION – D2

GENERAL TECHNICAL SPECIFICATION

CEMENT CONCRETE (PLAIN & REINFORCED)

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	GENERAL	3
3.00.00	INSTALLATION	12
4.00.00	SAMPLING AND TESTING	41
5.00.00	ACCEPTANCE CRITERIA	43
6.00.00	RATES AND MEASUREMENTS	43
7.00.00	LIST OF I.S.: CODES AND STANDARDS FOR REFERENCE	51

SUB-SECTION – D2

CEMENT CONCRETE (PLAIN & REINFORCED)

1.00.00 SCOPE

1.01.00 General

This specification covers all the requirements, described hereinafter for general use of Plain and Reinforced Cement Concrete work in Structures and locations, cast-in-situ or precast, and shall include all incidental items of work not shown or specified but reasonably implied or necessary for the completion of the work. Special requirements for structures such as reinforced concrete chimney, cooling towers, etc. have been covered under the respective specifications. Those specifications shall be used in conjunction with this specification.

1.02.00 IS: 456 shall form a part of this specification and shall be complied with unless permitted otherwise. For any particular aspect not covered by this Code, appropriate Code, specifications and/or replacement by any International code of practice as may be specified by the Engineer shall be followed. All codes and Standards shall conform to its latest revisions. A list of IS codes and Standards is enclosed hereinafter for reference. However, should the list be not exhaustive and does not cover any aspect of the work, then relevant Indian and, in its absence, relevant International code shall apply.

2.00.00 General

2.01.00 Work to be provided for by the Contractor

The work to be provided for by the Contractor, unless otherwise specified shall include but not be limited to the following

a) Furnish all labour, supervision, services including facilities as may be required under statutory labour regulations, materials, forms, templates, supports, scaffolds, approaches, aids, construction equipment, tools and plants, transportations, etc. required for the work.

b) Prepare Bar bending Schedules for reinforcement bars showing the positions and details of spacers, supports, chairs, hangers etc.

c) Prepare working drawings of formworks, scaffolds, supports, etc.

d) Prepare shop drawings for various inserts, anchors, anchor bolts, pipe sleeves, embedments, hangers, openings, frames etc.

e) Prepare detailed drawings of supports, templates, hangers, etc. required for

installation of various embedments like inserts, anchor bolts, pipe sleeves, frames, joint seals, frames, openings etc.

As decided by the Engineer some or all of the drawings & schedules prepared under item (b) to (e) above will have to be submitted for approval.

f) Submit for approval detailed schemes of all operations required for executing the work, e.g. material handling, Concrete mixing, Placement of concrete, Compaction, curing, services, Approaches, etc.

g) Design and submit for approval concrete mix designs required to be adopted on the job.

Furnish samples and submit for approval results of tests of various properties of the following:

i) The various ingredients of concrete

ii) Concrete

iii) Embedments

iv) Joint seals

i) Provide all incidental items not shown or specified in particular but reasonably implied or necessary for successful completion of the work in accordance with the drawings and specifications.

j) For supply of certain materials normally manufactured by specialist firms, the Contractor may have to produce, if directed by the Engineer, a guarantee in approved Performa for satisfactory performance for a reasonable period as may be specified, binding both the manufacturers and the Contractor, jointly and severally.

2.02.00 Work by others

No work under this specification will be provided by any agency other than the Contractor unless specifically mentioned elsewhere in the contract.

2.03.00 Information to be submitted by the Tenderer

2.03.01 With Tender

The following technical information's are required with the tender:

a) Source and arrangement of processing of aggregates proposed to be adopted.

b) Type of plant and equipment proposed to be used.

c) Names of firms with which association is sought for to execute the special items of work in the contract.

d) Types of formwork proposed to be used.

2.03.02 After Award

The Contractor shall submit the following information and data including samples where necessary, progressively during the execution of the contract.

a) Programme of Execution

Within 30 days of the award of contract, the Contractor will submit a Master Programme for completion of the work.

This Master Programme may have to be reviewed and updated by the Contractor, quarterly or at more frequent intervals as may be directed by the Engineer depending on the exigencies of the work.

Detailed day-to-day Programme of every month is to be submitted by the Contractor before the end of the previous month.

b) Samples

Samples of the following materials and any other materials proposed to be used shall be submitted as directed by the Engineer, in sufficient quantities free of cost, for approval. The Engineer for future reference will preserve approved samples. The approval of the Engineer shall not, in any way, relieve the Contractor of his responsibility of supplying materials of specified qualities:

i) Coarse and fine aggregates.

ii) Admixtures.

iii) Plywood for Formwork.

iv) Embedded and anchorage materials as may be desired by the Engineer.

v) Joint sealing strips and other*waterproofing materials.

vi) Joint filling compounds.

vii) Foundation quality Rubber Pads.

c) Design Mix

Design mix as per specification giving proportions of the ingredients, sources of aggregates and cement, along with test results of trial mixes as per relevant I.S., is to be submitted to the Engineer for his approval before it can be used on the works.

d) Bar Bending Schedules

Bar Sending Schedules in accordance with Clause 2.01.00 (b) and 3.16.01 of this specification.

e) Detailed Drawings and Designs of Formworks to be used

Detailed design data and drawings of standard formworks to be used as per clause 2.01.00 (c).

f) Detailed Drawings for Templates & Temporary Supports for embedment As per Clause 2.01.00 (e).

g) Mill Test Reports for Cement & Reinforcing Steel.

h) Inspection Reports

The Engineer in accordance with Clause 2.04.00 of this specification may desire inspection Reports in respect of Formwork and Reinforcement and any other item of work as.

i) Test Reports

Reports of tests of various materials and concrete as required under Clause 4.0: SAMPLING & TESTING of this specification or as directed by the Engineer.

j) Any other data, which may be required as per this specification or as directed by the Engineer.

2.04.00 Conformity with Design

The Contractor will prepare checklists in approved Performa, which will be called "Pour Cards". These Pour Cards will list out all items of work involved. The Contractor will inform the Engineer, sufficiently in advance, whenever any particular pour is ready for concreting. He shall accord all necessary help and assistance to the Engineer for all checking required in the pour. On satisfying himself that all details are in accordance to the drawings and specifications, the engineer will give written permission on the same Pour

Cards allowing the contractor to commence placement of concrete. Details of all instructions issued by the Engineer and the records of compliance by the Contractor, deviations allowed by the Engineer and any other relevant information will be written on accompanying sheets attached to the Pour Cards. The Pour Cards along with accompaniments will be handed over to the Engineer before starting placement of concrete. One of the mix designs developed by the Contractor as per the I.S. Specifications and established to the satisfaction of the Engineer by trial mixes shall be permitted to be used by the Engineer, the choice being dictated by the requirements of designs and workability. The methods of mixing, conveyance, placement, vibration, finishing, curing, protection and testing of concrete will be as approved or directed by the Engineer.

2.05.00 Materials to be used

2.05.01 General Requirement

All materials whether to be incorporated in the work or used temporarily for the construction shall conform to the relevant IS Specifications unless-stated otherwise and be of best approved quality.

2.05.02 Cement

Ordinary Portland cement of grade-43 as per IS:8112/fly ash based Portland puzzolona cement conforming to IS:1489 (Part-1) shall preferably be used in reinforced/plain cement concrete works for all areas other than for the critical structures identified below. However, other types of cement such as ordinary Portland cement conforming to IS:269, Portland slag cement conforming to IS:455 respectively can be used under special circumstances. Cement used in all concrete mixes shall be in general of grade 33/43 unless design requires a higher grade. Ordinary Portland cement shall be used for following structure.

a) TG foundation top deck and sub structures including raft.

b) Spring Supporting decks of all machine foundations.

c) Structures requiring grade of concrete of M30 and above.

In special cases, Rapid Hardening Portland Cement, Low Heat Cement, Sulphate resistant cement, high strength Ordinary Portland Cement etc. may be permitted or directed to be used by the Engineer.
For Brickwork, plaster, flooring and other finishing works, ordinary Portland cement of 33/43 grade shall be used.

2.05.03 Coarse Aggregate

Aggregate of sizes ranging between 4.75 mm and 150 mm will be termed as

Coarse Aggregate. Coarse aggregate for concrete shall be chemically inert, hard, strong durable against weathering, of limited porosity, and free from deleterious materials. It shall be properly graded. Coarse aggregates shall be either crushed gravel or stone. All aggregates shall meet the requirement of IS:383:1970. Only Coarse Aggregate from, approved quarries and conforming to IS-383 will be allowed to be used on the works. Petrographic test shall be carried out by the contractor free of cost for checking the quality of rock from quarry. This test shall be repeated by the Contractor free of cost for change in quarry or as directed by the Engineer. The results shall be checked for reactivity of silica in aggregate with alkalis of cement.

2.05.04 Fine Aggregate

Aggregate smaller than 4.75 mm and within the grading limits and other requirements set in IS: 383 are termed as Fine Aggregate or Sand. Only Fine Aggregate from approved sources and conforming to the above IS Specification will be allowed to be used in works. Sand shall be hard, durable, clean and free from adherent coatings or organic matter and clay balls or pellets. Sand when used as fine aggregate in concrete shall conform to IS:383. For plaster, it shall conform to IS:1542 and for masonry work to IS:2116.

2.05.05 Water

Water for use in Concrete shall be clear and free from injurious oils, acids, alkalis, organic matter, salt, silts, or other impurities. Generally, IS: 3550 will be followed for routine tests. Acceptance of water shall be as per IS: 456.

2.05.06 Admixture

Only admixtures of approved quality will be used when directed or permitted by the Engineer. The different types of admixtures, which may be necessary to satisfy the concrete mix and the design requirement, shall be as per IS-9103 and may be one of the followings:

a) Accelerating admixture

b) Retarding admixture

c) Water reducing admixture

d) Air entraining admixture

e) Water proofing admixture

The contractor shall inform the Engineer about the type of admixture which he is planning to use in different areas within the scope of work for the approval

of the Engineer. The admixture shall be of proven make and from a reputed manufacturer. It should not have any adverse effect on strength, durability of concrete and reinforcement. Super plasticizers conforming to IS: 9103 or ASTMC-494 shall only be used as admixture having the above properties either individually or in a combination as per the direction of the Engineer.

2.05.07 Reinforcement

Reinforcement shall be as per relevant IS Specification as mentioned in the Contract/Drawing/Instructions. All bars shall be of tested quality.

2.06.00 Storage of Materials

2.06.01 General

All materials shall be stored so as to prevent deterioration or intrusion of foreign matter and to ensure the preservation of their quality and fitness for the work. Any material, which has deteriorated or has been damaged or is otherwise considered defective by the Engineer, shall not be used for concrete and shall be removed from site immediately, failing which, the Engineer shall be at liberty to get the materials removed and the cost incurred thereof shall be realised from the Contractor's dues. The Contractor shall maintain upto-date accounts of receipt, issue and balance (stack wise) of all materials. Storage of materials shall conform to IS: 4082.

2.06.02 Cement

Sufficient space for storage, with open passages between stacks, shall be arranged by the Contractor to the satisfaction of the Engineer.

Cement shall be stored off the ground in dry, leak proof, well-ventilated warehouses at the works in such a manner as to prevent deterioration due to moisture or intrusion of foreign matter.

Cement shall be stored in easily countable stacks with consignment identification marks. Consignments shall be used in the order of their receipts at site. Sub-standard or partly set cement shall not be used and shall be removed from the site, with the knowledge of the Engineer, as soon as it is detected.

2.06.03 Aggregates

Aggregates shall be stored on raised surface constructed by providing planks or steel plates or on concrete or brick masonry pavement. Each size shall be kept separated with wooden or steel or concrete or masonry bulkheads or in separate stacks and sufficient care shall be taken to prevent the material at the

edges of the stock piles from getting intermixed. Stacks of fine and coarse aggregates shall be kept sufficiently apart with proper arrangement of drainage. The aggregates shall be stored in easily measurable stacks of suitable depths as may be directed by the Engineer.

2.06.04 Reinforcement

Reinforcing steel shall be stored consignment-wise and size-wise off the ground and under cover, if desired by the Engineer. It shall be protected from rusting, oil, grease, and distortions.

If necessary, the reinforcing steel may be coated with cement wash before stacking to prevent scale and rust at no extra cost to the Owner. The stacks shall be easily measurable. Steel needed for immediate use shall only be removed from storage.

2.07.00 Quality Control

Contractor shall establish and maintain quality control for different items of work and materials as may be directed by the Engineer to assure compliance with contract requirements and maintain and submit to the Engineer records of the same. The quality control operation shall include but not be limited to the following items of work:

a) Admixture:	Type, quantity, physical, and chemical properties that affects strength, workability, and durability of concrete. For air entraining admixtures, dosage to be adjusted to maintain air contents within desirable limits.
b) Aggregate:	Physical, chemical and mineralogical qualities. Grading, moisture content and impurities.
c) Water:	Impurities tests.
d) Cement:	Tests to satisfy relevant IS Specifications.
e) Formwork:	Material, shapes, dimensions, lines, elevations, surface finish, adequacy of form, ties, bracing and shoring and coating.
f) Reinforcement:	Shapes, dimensions, length of splices, clearances, ties and supports. Quality and requirement of welded splices.

Material tests or Certificates to satisfy relevant IS Specification.

g) Grades of Concrete: Usage and mix design, testing of all properties.

h) Batching & Mixing: Types and capacity of plant, concrete mixers and transportation equipment.

i) Joints: Locations of joints, water stops and filler materials. Dimension of joints, quality, and shape of joint material and splices.

j) Embedded and Anchorage Items: Material, shape, location, setting.

k) Placing: Preparation, rate of pouring, weather limitations, time intervals between mixing and placing and between two successive lifts, covering over dry or wet surfaces, cleaning and preparation of surfaces on which concrete is to be placed, application of mortar/slurry for proper bond, prevention of cold joint, types of chutes or conveyors.

l) Compaction: Number of vibrators, their prime mover, frequency and amplitude of vibration, diameter and weight of vibrators, duration of vibration, hand-spreading, rodding and tamping.

m) Setting of base & Bearing plates: Lines, elevations, and bedding mortar.

n) Concrete Finishes: Repairs of surface defects, screening, floating, steel trowelling and brooming, special finishes.

o) Curing: Methods and length of time.

Copies of records and tests for the items noted above, as well as, records of corrective action taken shall be submitted to the Engineer for approval as may be desired.

3.00.00 INSTALLATION

All installation requirements shall be in accordance with IS: 456 and as supplemented or modified herein or by other best possible standards where the specific requirements mentioned in this section of the specification do not

cover all the aspects to the full satisfaction of the Engineer.

3.01.00 Washing and Screening of Aggregates

Washing and screening of coarse and fine aggregates to remove fines, dirt, or other deleterious materials shall be carried out by approved means as desired by the Engineer.

3.02.00 Admixture

All concrete shall be designed for normal rate of setting and hardening at normal temperature. Variations in temperature and humidity under different climatic conditions will affect the rate of setting and hardening, which will, in turn, affect the workability and quality of the concrete. Admixtures including plasticisers of approved make may be used with the Engineer's approval in accordance with IS-456 to modify the rate of hardening, to improve workability or as an aid to control concrete quality. The Engineer reserves the right to require laboratory test or use test data, or owner satisfactory reference before granting approval. The admixture shall be used strictly in accordance with the manufacturer's directions and/or as directed by the Engineer.

3.03.00 Grades of Concrete

Concrete shall be in one of the grades designated in IS: 456. Grade of concrete to be used in different parts of work shall be as shown on the drawing. In case of liquid retaining structures, IS: 3370 will be followed. Minimum cement content shall be as per IS: 456.

3.04.00 Proportioning and Works Control

3.04.01 General

"Design Mix Concrete" and "Nominal Mix Design" is defined as follows for use in this specification:

a) Proportioning of ingredients of concrete made with preliminary tests by designing the concrete mix. Such concrete shall be called "Design Mix Concrete".

b) Proportioning of ingredients of concrete made without preliminary tests adopting nominal concrete mix. Such concrete shall be called "Nominal Mix Concrete".

As far as possible, design mix concrete shall be used on all concrete works. Nominal mix concrete, in grades M-15 or lower only may be used if shown on drawings or approved by the Engineer. In all cases the Proportioning of ingredients and works control shall be in accordance with IS: 456 and shall be

adopted for use after the Engineer is satisfied regarding its adequacy and after obtaining his approval in writing.

3.04.02 Mix Design Criteria

Concrete mixes will be designed by the Contractor to achieve the strength, durability, and workability necessary for the job, by the most economical use of the various ingredients. In general, the design will keep in view the following considerations

a) Consistent with the various other requirements of the mix, the quantity of water should be kept at the lowest possible level.

b) The nominal maximum size of coarse aggregate shall be as large as possible within the limits specified.

c) The various fractions of coarse and fine aggregates should be mixed in such a proportion as to produce the best possible combined internal grading giving the densest and most workable mix.

d) The finished concrete should have adequate durability in all condition, to withstand satisfactorily the weather and other destruction agencies, which it is expected to be subjected to in actual service.

e) The mix design shall have required workability and characteristic strength as per IS: 456. The quantity of cement, aggregates, and admixtures shall be determined by mass.

The requirement of adequate structural strength is catered for by the choice of proper grade of concrete in structural design. The Contractor will strictly abide by the same in his design of concrete mix installation. Various trials shall be given by the contractor with specific cement content on each trial. In some cases, plasticizers and other admixtures may be necessary to achieve the desired results.

3.05.00 Strength Requirements

The strength requirements of both design mix and nominal mix concrete where ordinary Portland Cement or Portland Blast furnace slag cement is used, shall be as per IS:456. All other relevant clauses of IS:456 shall also apply.

3.06.00 Minimum Cement Content

The minimum cement content for each grade of concrete shall be as per IS: 456. Contractor has to consider actual environmental exposure condition at

site. Based on various tests results and as per Engineer, the environment condition shall be adopted for which minimum cement content shall be considered. No extra payment shall be made on account of any variation in environment condition.

a) Sufficient number of trial mixes (to be decided by the Engineer) will be taken at the laboratory for the various designs and graphs of w/c ratio Vs crushing strengths at various ages will be plotted.

b) All tests will be done in presence of the Engineer who shall be the final authority to decide upon the adoption of any revised minimum cement content. The Contractor will always be responsible to produce quality concrete of the required grade as per the acceptance criteria of IS: 456.

c) The Engineer will always have the unquestionable right to revise the minimum cement content as decided above, if, in his opinion, there is any chance of deterioration of quality on account of use of lower cement content or any other reason.

3.07.00 Water-Cement Ratio

The choice of water-cement ratio in designing a concrete mix will depend on:-

a) The requirement of strength.

b) The requirement of durability.

3.07.01 Strength Requirement

In case of "Design Mix Concrete" the water-cement ratio of such value as to give acceptable test results as per IS: 456, will be selected by trial and error. The values of water-cement ratios for different grade and mix designs will have to be established after conducting sufficiently large number of preliminary tests in the laboratory to the satisfaction of the Engineer. Frequent checks on test will have to be carried out and the water-cement ratios will be revised if the tests produce unsatisfactory results. Notwithstanding anything stated above the Contractor's responsibility to produce satisfactory test results and to bear all the consequences in case of default remains unaltered.

In case of nominal mix concrete, the maximum water-cement ratio for different grades of concrete is specified in Table-5 of IS: 456 and no tests are necessary. The acceptance test criterion for nominal mix concrete shall be as per IS: 456.

3.07.02 Durability Requirement

Tables 4 & 5 of IS: 456 give the maximum water-cement ratio permissible from the point of view of durability of concrete subjected to adverse exposure to weather, sulphate attacks, and contact with harmful chemicals. Impermeability may also be an important consideration.

Whenever the water-cement ratio dictated by Durability consideration is lower than that required from strength criteria, the former should be adopted.

In general the water cement ratio between 0.4 and 0.45 will be desirable to satisfy the durability requirement and from the consideration of impermeability of concrete. The contractor may propose lower water cement ratio as mentioned above by addition of a suitable plasticizer/super-plasticizer. Trial mix shall be carried out accordingly. However, the contractor has to propose specifically along with field trials in the event of lower cement content if found suitable along with a plasticizer.

3.08.00 Workability

The degree of workability necessary to allow the concrete to be well consolidated and to be worked into the corners of formwork and around the reinforcement and embedments and to give the required surface finish shall depend*on the type and nature of structure and shall be based on experience and tests. The usual limits of consistency for various types of structures are given below:

TABLE-V

LIMITS OF CONSISTENCY

Degree of	Slump in mm with Standard Cone as	Use for which concrete is suitable

workability	per IS: 1199		
	Min.	Max.	
Very low	0	25	Large Mass concrete structure with heavy compaction equipments, roads
Low	25	50	Uncongested wide and shallow R.C.C. structures
Medium	50	100	Deep but wide R.C.C. structures with congestion of reinforcement and inserts
High	100	150	Very narrow and deep R.C.C. structures with congestion due to reinforcement and inserts.

Note: Notwithstanding anything mentioned above, the slump to be obtained for work in progress shall be as per direction of the Engineer.

With the permission of the Engineer, for any grade of concrete, if the water has to be increased in special cases, cement shall also be increased proportionately to keep the ratio of water to cement same as adopted in trial mix design for each grade of concrete. No extra payment will be made for this additional cement.

The workability of concrete shall be checked at frequent intervals by slump tests.

3.09.00 Size of coarse Aggregates

The maximum size of coarse aggregates for different locations shall be as follows unless otherwise directed by the Engineer

Very narrow space	- 12 mm
Reinforced concrete Except foundation	- 20 mm
Ordinary Plain concrete and Reinforced concrete foundations	- 40 mm
Mass concrete	- 80 mm

Lean concrete - 40 mm

Grading of coarse aggregates for a particular size shall conform to relevant I.S. Codes and shall also be such as to produce a dense concrete of the specified proportions, strength and consistency that will work readily into position without segregation.

Coarse aggregate will normally be separated into the following sizes and stacked separately in properly designed stockpiles

80 mm to 40 mm, 40 mm to 20 mm and 20 mm to 5 mm. In certain cases it may be necessary to further split the 20 mm to 5 mm fraction into 20 mm to 10 mm and 10 mm to 5 mm fractions.

This separation of aggregates in different size fractions is necessary so that they may be remixed in the desired proportion to arrive at a correct internal grading to produce the best mix.

3.09.01 Temperature control of concrete in top decks of machine foundations (i.e. of TGs, BFPs, Fans and Mills) as extra payable over RCC item of BOQ:

The temperature of fresh concrete shall not exceed 23°C when placed. A suitable measuring device for measuring the temperature of concrete as approved by the Engineer shall be used. For maintaining the limiting temperature of the 23°C, crushed ice shall be used as mixing water. The ice shall be formed of water conforming IS: 456. The Contractor shall establish the quantity of crushed ice to be mixed in order to achieve the limiting temperature of 23°C.

3.09.02 Base raft of Turbo Generator foundations and top decks of all machine foundations shall be cast in a continuous operation without any construction joint.

3.10.00 Mixing of Concrete

Ingredients of the concrete mix shall be measured by weight. Concrete shall always be mixed in mechanical mixer. Water shall not normally be charged into the drum of the mixer until all the cement and aggregates constituting the batch are already in the drum and mixed for at least one minute. Mixing of each batch shall be continued until there is a uniform distribution of the materials and the mass is uniform in colour and consistency, but in no case shall mixing be done for less than 2 (two) minutes and at least 40 (forty) revolutions after all the materials and water are in the drum. When absorbent Aggregates are used or when the mix is very dry, the mixing time shall be extended as may be directed by the Engineer. Mixers shall not be loaded above their rated capacity as this prevents thorough mixing.

The entire contents of the drum shall be discharged before the ingredients for the next batch are fed into the drum. No partly set or remixed or excessively wet concrete shall be used. Such concrete shall be immediately removed from site. Each time the work stops, the mixer shall be thoroughly cleaned & when the next mixing commences, the first batch shall have 10% additional cement at no extra cost to the Owner to allow for loss in the drum.

Regular checks on mixer efficiency shall be carried out as directed by the Engineer as per IS: 4634 on all mixers employed at site only those mixers whose efficiencies are within the tolerances specified in IS: 1791 will be allowed to be employed.

Batching Plant shall conform to IS: 4925. The measuring gauges of batching plant shall be periodically calibrated for which the contractor shall provide standard weights. The accuracy of all gauges shall be within limits prescribed by the Engineer.

When hand mixing is permitted by the Engineer, for unimportant out of the way locations in small quantities, it shall be carried out on a water-tight platform and care shall be taken to ensure that mixing is continued until the mass is uniform in colour and consistency. In case of hand-mixing, 10% extra cement shall be added to each batch at no extra cost to the owner.

3.11.00 Conveying Concrete

Concrete shall be handled and conveyed from the place of mixing to the place of laying as rapidly as practicable by approved means and placed and compacted in the final position before the initial setting of the cement starts. Concrete should be conveyed in such a way as will prevent segregation or loss of any of the ingredients. For long distance haulage, agitator cars of approved design will be used. If, in-spite of all precautions, segregations does occur during transport, the concrete shall be properly re-mixed before placement. During very hot or cold weather, if directed by the Engineer, concrete shall be transported in deep containers, which will reduce the rate of loss of water, by evaporation or loss of heat. If necessary, the container may have to be covered and insulated. Conveying equipments for concrete shall be well maintained and thoroughly cleaned before, commencement of concrete mixing. Such equipments shall be kept free from set concrete.

3.12.00 Placing and Compacting Concrete

Where specifically covered, the relevant I.S. Code will be followed for the procedure of surface preparation, placement, consolidation, curing, finishes, repairs and maintenance of concrete. If, however, there is no specific provision in relevant I.S. code for any particular aspect of work, any other standard code of practice, as may be specified by the Engineer, will be

adopted. Concrete may have to be placed against the following types of surfaces:

a) Earth foundation

b) Rock foundation

c) Formwork

d) Construction joint in concrete or masonry

The surface on or against which concrete is to be placed has to be cleaned thoroughly. Rock or old construction joint has to be roughened by wire brushing, chipping, sand blasting or any other approved means for proper bond. All cuttings, dirt, oil, foreign and deleterious material, laitance, etc. are to be removed by air water jetting or water at high pressure. Earth foundation on which direct placement of concrete is allowed, will be consolidated as directed by the Engineer such that it does not crumble and get mixed up with the concrete during or after placement, before it has sufficiently set and hardened.

Formwork, reinforcement, preparation of surface, embedments, joint seals etc., shall be approved in writing by the Engineer before concrete is placed. As far as possible, concrete shall be placed in the formwork by means approved by the Engineer and shall not be dropped from a height or handled in a manner which may cause segregation. Any drop over 1500 mm shall have to be approved by the Engineer.

Rock foundation or construction joint will be kept moist for at least 72 hours prior to placement. Concrete will be placed always against moist surface but never on pools of water. In case the foundation cannot be dewatered completely, special procedure and precaution, as directed by the Engineer will have to be adopted.

Formwork will be cleaned thoroughly and smeared lightly with form oil or grease of approved quality just prior to placement.

A layer of mortar of thickness 12 mm of the same or less w/c ratio and the same proportion as that of the concrete being placed or cement slurry will be spread thoroughly on the rock Foundation or construction joint just prior to placement of concrete.

After concrete has been placed, it shall be spread, if necessary & thoroughly compacted by approved mechanical vibration to maximum, subsidence without segregation and thoroughly worked around shape. Vibrators shall not be used for pushing concrete into adjoining areas. Vibrators must be operated by experienced workmen and the work carried out as per relevant IS Code of

Practice: In thin members with heavy congestion of reinforcement or other embedments, where effective use of internal vibrator is, in the opinion of the Engineer, doubtful, in addition to immersion vibrators the contractor may have to employ form vibrators conforming to IS: 4656. For slabs and other similar structures, the contractor will additionally employ screed vibrator as per IS: 2506. Hand tamping may be allowed in rare cases, subject to the approval of the Engineer. Care must be taken to ensure that the inserts, fixtures, reinforcement, and formwork are not displaced or distorted during placing & consolidation of concrete.

The rate of placement of concrete shall be such that no cold joint is formed and fresh concrete is placed always against green Concrete, which is still plastic and workable. No concrete shall be placed in open, during rains. During rainy season, no placement in the open is to be attempted unless sufficient tarpaulins or other similar protective arrangement for completely covering the still green concrete from rain is kept at the site of placement. If there has been any sign of washing of cement and sand, the entire affected concrete shall be removed immediately. Suitable precautions shall be taken in advance to guard against rains before leaving the fresh concrete unattended. No accumulation of water shall be permitted on or around freshly laid concrete.

Slabs, beams, and similar members shall be poured in one operation, unless otherwise instructed by the Engineer. Mouldings, throating, drip course, etc., shall be poured as shown on the drawings or as directed by the Engineer. Holes shall be provided and bolts, sleeves, anchors, fastenings, or other fixtures shall be embedded in concrete as shown on the drawings or as directed by the Engineer. Any deviation there from shall be set right by the Contractor at his own expense as instructed by the Engineer.

In case the forms or supports get displaced during or immediately after the placement and bring the concrete surface out of alignment beyond tolerance limits, the Engineer may direct to remove the portion and reconstruct or repair the same -at the Contractor's expense.

The Engineer shall decide upon the time interval between two placements of concrete of different ages coming in contact with each other, taking in consideration the degree of maturity of the older concrete, shrinkage, heat dissipation and the ability of the older concrete to withstand the load imposed upon it by the fresh placement.

Once the concrete is deposited, consolidated and finished in its final position, it shall not be distributed.

3.13.00 Construction Joints and Cold Joints

3.13.01 Construction Joints

It is always desirable to complete any concrete structure by continuous pouring in one operation. However, due to practical limitation of methods and equipment and certain design considerations, construction joints are formed by discontinuing concrete certain predetermined stages. These joints will be formed in a manner specified in the drawings/Instruction.

Vertical construction joints will be made with rigid stop-board forms having slots for allowing passage of reinforcement rods and any other embedments and fixtures that may be shown. Next stage concrete shall be placed against construction joint as per clause 3.12.

Where the location of the joints are not specified, it will be in accordance with the following:

a) In a column, the joint shall be formed 75 mm below the lowest soffit of the beam framing into it.

b) Concrete in a beam shall preferably be placed without a joint, but if Provision of a joint is unavoidable, the joint shall be vertical and at the middle of the span.

c) A joint in a suspended floor slab shall be vertical and at the middle of the span and at right angles to the principal reinforcement.

d) Feather-edges in concrete shall be avoided while forming a joint.

e) A construction joint should preferably be placed in a low-stress zone and at right angles to the direction of the principal stress.

f) In case the Contractor proposes to have a construction joint anywhere to facilitate his work, the proposal should be submitted well in advance to the Engineer for study and approval without which no construction joint will be allowed.

3.13.02 Cold Joint

An advancing face of a concrete pour, which could not be covered by fresh concrete before expiry of initial setting time (due to an unscheduled stoppage or delay on account of breakdown in plant, inclement weather, low rate of placement or any other reason), is called a cold joint. The Contractor should always remain vigilant to avoid cold joints.

If, however, a cold joint is formed due to unavoidable reasons, the following procedure shall be adopted for treating it:

a) If the concrete is so green that it can be removed manually and if vibrators

can penetrate the surface without much effort, fresh concrete can be placed directly against the old surface. The old concrete should be covered by fresh concrete as quickly as possible and the joint thoroughly and systematically vibrated.

b) In case concrete has hardened a bit more than (a) but can still be easily removed by a light hand pick, the surface will be raked thoroughly and the loose concrete removed completely without disturbing the rest of the concrete in depth. A rich mortar layer 12 *mm* in thickness, will be placed on the cold joint fresh concrete shall be placed on the mortar layer and the joint will be thoroughly and systematically vibrated penetrating the vibrator deep into the old layer of concrete.

c) In case the concrete at the joint has become so stiff that it cannot be remoulded and mortar or slurry does not raise inspite of extensive vibration, the joint, will be left to harden for at least 12 - 24 hrs. It Will then be treated as a regular construction joint, after cutting the concrete to required shape and preparing the surface as described under clause 3.12.

3.14.00 Repairs, Finishes, and Treatment of Concrete surfaces

3.14.01 Adequate and sound concrete surfaces, whether formed or unformed, can be obtained by employing a concrete mix of proper design, competent formwork, appropriate methods of handling, placing, and consolidation by experienced workmen.

Unsound concrete resulting from improper mix design, incompetent methods, equipment and formwork, poor workmanship and protection will not be accepted and will have to be dismantled, removed and replaced by sound concrete at the Contractor's cost. The Engineer may, at his sole discretion, allow to retain concrete with minor defects provided the Contractor is able to repair it by approved methods at no extra cost to the Owner, All concrete work shall be inspected by the Contractor immediately after the forms are removed & he will promptly report occurrence of any defects to the Engineer. All repair works will be carried out as per the instructions and in the presence of the Engineer or his representative. Generally, repair work will consist of any or all of the following operations:

a) Sack rubbing with mortar and stoning with carborundum stone.

b) Cutting away the defective concrete to the required depth shape.

c) Cleaning of reinforcement & embedments. It may be necessary to provide an anti-corrosive coating on the reinforcement.

d) Roughening by sand blasting or chipping.

e) Installing additional reinforcement/welded mesh fabric.

f) Dry packing with stiff mortar.

g) Plastering, guniting, shotcreting etc.

h) Placing and compacting concrete in the void left by cutting out defective concrete.

i) Grouting with cement sand slurry of 1:1 mix.

j) Repairing with a suitable mortar either cement or resin modified mortars.

k) Polymer modified patching and adhesive repair& mortar for beams & columns.

3.14.02 Finishing unformed Surface

The contractor shall provide normal finishes in unformed surfaces which can be achieved by screeding, floating, trowelling etc. A few typical and common cases of treatment of concrete surface are cited below

a) Floor

Whenever a non-integral floor finish is indicated, the surface of reinforced concrete slab shall be struck off at the specified levels and slopes and shall be finished with a wooden float fairly smooth removing all laitance. No over trowelling, to obtain a very smooth surface, shall be done, as it will prevent adequate bond with the subsequent finish. If desired by the Engineer, the surface shall be scored and marked to provide better bond.

Where monolithic finish is specified or required, concrete shall be compacted and struck off at the specified levels and slopes with a screed, preferably a vibrating type and then floated with a wooden float. Steel trowelling is then started after the moisture film and shine have disappeared from the surface and after the concrete has hardened enough to prevent excess of fines and water to rise to the surface but not hard enough to prevent proper finishing of aberrations. Steel trowelling properly done will flatten and smoothen sandy surface left by wooden floats and produce a dense surface free from blemishes, ripples, and trowel marks.

A fine textured surface that is not slick and can be used where there is likelihood of spillage of oil or water can be obtained by trowelling the surface lightly with a circular motion after initial trowelling keeping the steel trowel flat on the surface.

To provide a better grip the Engineer may instruct marking the floor in a regular geometric pattern after initial trowelling.

b) Beans, Columns & Walls

If on such or any other concrete structure it is intended to apply plaster or such concrete surfaces against which brickwork or other allied works are to be built, the Contractor shall hack the surface adequately as soon as the form is stripped off so that proper bond can develop. Pattern, adequacy, and details of such hacking shall meet with the approval of the Engineer, who shall be informed to inspect such surfaces before they are covered up.

3.15.00 Protection and Curing of concrete

Newly placed concrete shall be protected by approved means from rain, sun, and wind. Concrete placed below the ground level shall be protected against contamination from falling earth during and after placing. Concrete placed in ground containing deleterious substances, shall be protected from contact with such ground, or with water draining from such ground, during placing of concrete and for a period of at least three days, or as otherwise instructed by the Engineer. The ground water around newly poured concrete shall be kept to an approved level by pumping out or other adequate means of drainage to prevent floatation or flooding. Steps, as approved by the Engineer, shall be taken to protect immature concrete from damage by debris, excessive 'Loadings, vibration, abrasion, mixing with earth or other deleterious materials, etc. that may impair the strength and durability of the concrete.

As soon as the concrete has hardened sufficiently, it shall be covered either with sand, hessian, canvas, or similar materials and kept continuously wet for at least 14 (fourteen) days after final setting. Curing by continuous sprinkling of water will be allowed if the Engineer is satisfied with the adequacy of the arrangements made by the Contractor. Quality of water for curing shall be as per IS: 456.

If permitted by the Engineer, liquid curing compound may be used for prevention of premature water loss in concrete and thereby effecting curing of concrete. This type of curing compound shall be sprayed on newly laid concrete surfaces to form a thin film barrier against premature water loss without disturbances to normal setting action. The curing compound shall be emulsified paraffin based and shall comply with ASTM requirements for acceptance.

The curing compound shall be applied following the final finishing operation and immediately after disappearance of water from concrete surface. It is important not to apply the curing compound when standing water is still present on concrete.

The contractor shall arrange for the manufacturer's supervision at no extra cost.

The Contractor shall remain extremely vigilant and employ proper equipment and workmen under able supervision for curing. The Engineer's decision regarding the adequacy of curing is final. In case the Engineer notices any lapse on the part of the Contractor, he will inform the Contractor or his supervisor verbally or in writing to correct the deficiency in curing. If no satisfactory action is taken by the Contractor within 3 (three) hours of issuance of such instruction, the Engineer will be at liberty either to employ sufficient means through any agency to make good the deficiency and recover the cost thereof from the Contractor, or deduct certain amount from contractor's payment for the part where inadequate curing was noticed entirely at the discretion of the Engineer.

3.16.00 Reinforcement

Mild steel round bars, TMT bars, Hot rolled deformed bars or cold twisted deformed bars as medium tensile or high yield strength steel, plain hard drawn steel wire fabric etc, will be used as reinforcement as per drawings and directions. In an aggressive environment an anti-corrosive coating on the reinforcement may be provided as per IS: 9077, as shown on the drawing or as directed by the Engineer.

3.16.01 Bar Bending Schedules

The Contractor shall prepare Bar Bending Schedules showing clearly the arrangements proposed by the Contractor to match available stock of reinforcing steel, progressively, starting within one week of receipt of approval on corresponding design of RCC structure. As decided by the Engineer, some or all the detailed drawings and schedules will have to be submitted for approval. Approval of such detailed drawings by the Engineer shall not relieve the Contractor of his responsibility for correctness nor of any of his obligations to meet the other requirements of the contract. The contractor for record and distribution shall submit six prints of the final drawings & schedules with one reproducible print.

3.16.02 Cleaning

All steel for reinforcement shall be free from loose scales, oil, grease, paint or other harmful matters immediately before placing the concrete.

3.16.03 Bending

Unless otherwise specified, reinforcing steel shall be bent in accordance with the procedure specified in IS: 2502 or as approved by the Engineer. Bends and shapes shall comply strictly with the dimensions corresponding with the

final Bar Bending Schedules. Bar Bending Schedules shall be rechecked by the Contractor before any cutting, bending is done.

No reinforcement shall be bent when already in position in the work, without approval of the Engineer, whether or not it is partially embedded in concrete. Bars shall not be straightened in a manner that will injure the material. Rebending can be done only if approved by the Engineer. Reinforcing bars shall be bent by machine or other approved means producing a gradual and even motion. All the bars shall be cold bent unless otherwise approved. Bending hot at a cherry-red heat (not exceeding 845°C) may be allowed under very exceptional circumstances except for bars whose strength depends on cold working. Bars bent hot shall not be cooled by quenching.

3.16.04 Placing in Position

All reinforcements shall be accurately fixed and maintained in position as shown on the drawings by such approved and adequate means like mild steel chairs and/or concrete spacer blocks. Bars intended to be in contact at crossing points, shall be securely tied together at all such points by No. 20 G annealed soft iron wire or by tack welding in case of Bar larger than 25 mm dia., as may be directed by the Engineer. Binders shall tightly embrace the bars with which they are intended to be in contact and shall be securely held. The vertical distance between successive layers of bars shall be maintained by provision of mild steel spacer bars. They should be spaced such that the main bars do not sag perceptibly between adjacent spacers. Before actual placing, the Contractor shall study the drawings thoroughly and inform the Engineer in case he feels that placement of certain bars is not possible due to congestion. In such cases he should not start placing any bar before obtaining clearance from the Engineer.

3.16.05 Welding / Coupler for Splicing

Lapping shall normally do splicing of reinforcement. For M.S. reinforcement bars, butt-welding may be done, if permitted by the Engineer, under certain conditions. The work should be done with suitable safeguards in accordance with relevant Indian Standards for welding of mild steel bars used in reinforced concrete construction as per IS: 2751 and IS: 456. For High yield strength deformed bars, lap welding may be done, if permitted by the Engineer, under certain conditions. The work should be done with suitable safeguards in accordance with relevant Indian Standards as per IS: 9417. Welding of High yield strength deformed bar shall not be allowed.

Splicing of reinforcement using mechanical coupler may be done, if permitted by the Engineer, under certain conditions. The work should be done with suitable safeguards in accordance with relevant Indian standards for “Reinforcement couplers for mechanical splices of bars in concrete” as per IS: 16172. Corrosion test in the coupler-bar connections exposed to marine or

severe environmental conditions to rule out any risk of galvanic corrosion will be done by the contractor at no extra cost. Proper fitting & fixing of mechanical coupler to rebar shall be ensured at site for each coupled joint as per inspection testing plan developed at site in consultation with manufacturer of coupler. If so required at site, coupler/ threading on rebar shall be such that two bars can be coupled by moving couplers not rebar (as being heavy reinforcement weight and L shaped, it is not feasible to rotate the rebar for fixing up the coupler) at no extra cost.

3.16.06 Control

The placing of reinforcements shall be completed well in advance of concrete pouring. Immediately before pouring, the reinforcement shall be examined by the Engineer for accuracy of placement and cleanliness. Necessary corrections as directed by him shall be carried out. Laps and anchorage lengths of reinforcing bars shall be in accordance with IS: 456, unless otherwise specified. The laps shall be staggered as far as practicable and as directed by the Engineer. Arrangements for placing concrete shall be such that reinforcement in position does not have to bear extra load and get disturbed. The cover for concrete over the reinforcements shall be as shown on the approved drawings unless otherwise directed by the Engineer. Where concrete blocks are used for ensuring the cover and positioning reinforcement, they shall be made of mortar not leaner than 1 (one) part cement to 2 (two) parts sand by –volume and cured in a pond for at least 14 (fourteen) days. The type, shape, size and location of the concrete blocks shall be as approved by the Engineer.

3.17.00 Cold Weather Concreting

When conditions are such that the ambient temperature may be expected to be 5°C or below during the placing and curing period, the work shall conform to the requirement of IS: 456 and IS: 7861.

3.18.00 Hot Weather Concreting

When depositing concrete in very hot weather, the Contractor shall take all precautions as per IS: 7861 and stagger the work to the cooler parts of the day to ensure that the temperature of wet concrete used in massive structures does not exceed 38°C while placing. Positive temperature control by precooling, post cooling or any other method, if required, will have to be done by the contractor at no extra cost.

3.19.00 Concreting under water

When it is necessary to deposit concrete under water it shall be done in accordance with the requirements of IS: 456.

3.20.00 Form Work

3.20.01 General

If it is so desired by the Engineer, the contractor shall prepare, before commencement of actual work, designs and working drawings for formwork and centring and get them approved by the Engineer. The formwork shall conform to the shape, grade, lines, levels and dimensions as shown on the drawings.

Materials used for the formwork inclusive of the supports and centring shall be capable of withstanding the working load and remain undistorted throughout the period it is left in service. All supports and scaffolds should be manufactured from structural or tubular steel except when specifically permitted otherwise by the Engineer.

The centring shall be true to vertical, rigid and thoroughly braced both horizontally and diagonally. Rakers are to be used where forms are to support inclined members. The forms shall be sufficiently strong to carry without undue deformation, the dead weight and horizontal pressure of the concrete as a liquid as well as the working load. In case the contractor wishes to adopt any other design criteria, he has to convince the Engineer about its acceptability before adopting it. Where the concrete is vibrated, the formwork shall be strong enough to withstand the effects of vibration without appreciable deflection, bulging, distortion or loosening of its components. The joints in the formwork shall be sufficiently tight to prevent any leakage of slurry or mortar.

To achieve the desired rigidity, tie bolts, spacer blocks, tie wires and clamps as approved by the Engineer shall be used but they must in no way impair the strength of concrete or cause stains or marks on the finished surface. Where there are chances of these fixtures being embedded, only mild steel and concrete of adequate strength shall be used. Bolts passing completely through liquid retaining walls/slabs for the purpose of securing and aligning the formwork shall not be used.

The formwork shall be such as to ensure a smooth uniform surface free from honeycombs, air bubbles, bulges, fins and other blemishes. Any blemish or defect found on the surface of the concrete must be brought to the notice of the Engineer immediately and rectified as directed by him.

For exposed interior and exterior concrete surfaces of beams, columns and wall, plywood or other approved form shall be thoroughly cleaned and tied together with approved corrosion-resistant devices. Rigid care shall be exercised in ensuring that all column forms are in true plumb and thoroughly cross-braced to keep them so. All floor and beam centring shall be crowned

not less than 8 mm in all directions for every 5 metres span. The formwork should lap and be secured sufficiently at the lift joints to prevent bulges and offsets.

Temporary openings for cleaning, inspection and for pouring concrete shall be provided at the base vertical forms and at other places, where they are necessary and as may be directed by the Engineer. The temporary openings shall be so formed that they can be conveniently closed when required, during pouring operations without leaving any mark on the concrete.

3.20.02 Cleaning and Treatment of Forms

All parts of the forms shall be thoroughly cleaned of old concrete, wood shavings, saw dust, dirt and dust sticking to them before they are fixed in position. All rubbish, loose concrete, chippings, shavings, sawdust etc. shall be scrupulously removed from the interior of the forms before concrete is poured. Compressed air jet and/or water jet along with wire brushes brooms etc. shall be used for cleaning. The inside surface of the formwork shall be treated with approved non-staining oil or other compound before it is placed in position. Care shall be taken that oil or other compound does not come in contact with reinforcing steel or construction joint surfaces. They shall not be allowed to accumulate at the bottom of the formwork. The oiling of the formwork will be inspected just prior to placement of concrete and redone wherever necessary.

3.20.03 Design

The formwork shall be so designed and erected that the forms for slabs and the sides of beams, columns, and walls are independent of the soffits of beams and can be removed without any strain to the concrete already placed or affecting the remaining formwork.

Removing any props or repropping shall not be done except with the specific approval of the Engineer. If formwork for column is erected for the full height of the column, one side shall be left open and built up in sections, as placing of concrete progress. Wedges, spacer bolts, clamps or other suitable means shall be provided to allow accurate adjustment and alignment of the formwork and to allow it to be removed gradually without jarring the concrete.

3.20.04 Inspection of Forms

Casting of' Concrete shall start only after the formwork has been inspected and approved by the Engineer. The concreting shall start as early as possible within 3 (three) days after the approval of the formwork and during this period the formwork shall be kept under constant vigilance against any interference. In case of delay beyond three days, a fresh approval from the Engineer shall be obtained.

3.20.05 Removal of Forms

Formwork shall be kept in position after casting of concrete for a minimum period as mentioned in IS: 456, however the period of retaining form in position can be extended as per drawing, instruction of Engineer or as required for satisfactory completion of work without any extra cost. Before removing any formwork, the Contractor must notify the Engineer well in advance to enable him to inspect the concrete if the Engineer so desires.

The Contractor shall record on the drawing or in any other approved manner, the date on which concrete is placed in each part of the work and the date on which the formwork is removed there from and have this record checked and countersigned by the Engineer regularly. The Contractor shall be responsible for the safe removal of the formwork and any work showing signs of damage through premature removal of formwork or loading shall be rejected and entirely reconstructed by him without any extra cost to the Owner, The Engineer may, however, instruct to postpone the removal of formwork if he considers it necessary.

If any other type of cement other than ordinary Portland cement and Rapid hardening cement is used, the time of removal of forms shall be revised such that the strength of this cement at the time of removal of forms match with strength of Portland cement at the time of removal of form.

3.20.06 Tolerance

The formwork shall be so made as to produce a finished concrete, true to shape, lines, levels, plumb and dimensions as shown on the drawings subject to the following tolerances unless otherwise specified in this specification or drawings or directed by the Engineer:-

For - a) Sectional dimension - ± 5 mm
b) Plumb - 1 in 1000 of height
c) Levels - ± 3 mm before any deflection has taken place

The tolerance given above are specified for local aberrations in .the finished concrete surface & should not be taken as tolerances for the entire structure taken as a whole or for the setting and alignment of formwork, which should be as accurate as possible to the entire satisfaction of the Engineer. Any error, within the above tolerance limits or any other as may be specially set up by the Engineer, if noticed in any lift of the structure after stripping of forms, shall be corrected in the subsequent work to bring back the surface of the structure to its true alignment.

3.20.07 Re-use of Forms

Before re-use, all forms shall be thoroughly scraped, cleaned, joints and planes examined and when necessary repaired, and inside surface treated as specified hereinbefore. Formwork shall not be used/re-used if declared unfit or unserviceable by the Engineer.

3.20.08 Classification

Generally, the "ordinary" class formwork shall be used unless otherwise specified.

a) **Ordinary:** These shall be used in places where ordinary surface finish is required and shall be composed of steel and/or approved good quality partially seasoned timber.

b) **Plywood:** These shall be used in exposed surfaces, where specially good finish is required and shall be made of approved brand of heavy quality plywood to produce a perfectly uniform and smooth surface conforming to the shape described in the drawing with required grain texture on the concrete. Re-use may only be permitted after special inspection and approval by the Engineer. He may also permit utilization of used plywood for the "ordinary" class, if it is still in good condition.

c) **Ornamental:** These shall be used where ornamental and curved surface are required and shall be made of selected best quality well seasoned timbers or of plywood, which can be shaped correctly.

3.21.00 Opening, Chases, Grooves, Rebates, Blockouts etc.

The Contractor shall leave all openings, grooves, chases, etc. in concrete work as shown on the drawings or as specified by the Engineer.

3.22.00 Anchor Bolts, Anchors, Sleeves, Inserts, Hangers/Conduits/Pipe and other misc. Embedded Fixtures

The Contractor shall build into concrete work all the items noted below and shall embed them partly or fully as shown on drawings and secure the same as may be required. The materials shall be as specified and be of best quality available according to relevant Indian Standards of approved manufacture and to the satisfaction of the Engineer. Exposed surfaces of embedded materials are to paint with one coat of approved anti- corrosive paint and/or bituminous paint without any extra cost to the Owner. If welding is to be done subsequently on the exposed surface of embedded material, the paint shall be cleaned off the member to a minimum length of 50 mm beyond each side of the weld line.

Necessary templates, jigs, fixtures, supports etc. shall be used as may be

required or directed by the Engineer.

Items to be embedded

a) Inserts, hangers, anchors, frame around openings, manhole covers, frames, floor clips, sleeves conduits and pipes.

b) Anchor bolts and plates for machinery, equipment and for structural steel work.

c) Steel structurals to be left embedded for future extension, special connection etc.

d) Dowel bars, etc. for concrete work falling under the scope of other contractors.

e) Lugs or plugs for door and window frames occurring in concrete work.

f) Flashing and jointing in concrete work.

g) Any misc. embedments and fixture as may be required.

Correct location and alignment, as per drawings/instruction of all these embedded items shall be entirely the responsibility of the Contractor.

3.23.00 Expansion and Isolation Joints

3.23.01 General

Expansion and isolation joints in concrete structures shall be provided at specific places as per details indicated on the drawings. The materials and types of joints shall be as specified hereinafter. In case of liquid retaining structures, additional precautions shall be taken to prevent leakage of liquids as may be specified on the drawings or as directed by the Engineer. All materials are to be procured from reliable manufacturers and must have the approval of the Engineer. Where it is the responsibility of the Contractor to supply the material, the Engineer may demand test certificates for the materials and/or instruct the Contractor to get them tested in an approved laboratory free of cost to the Owner. Joints shall be formed true to line, level, shape, dimension, and quality as per drawings and specifications. Prior approval of the method of forming the joints should be obtained from the Engineer before starting the work.

3.23.02 Bitumen Board/ Expanded Polystyrene Board

a) Bitumen Board

Bitumen impregnated fibreboard of approved manufacturer as per IS: 1838 may be used as fillers for expansion joints. It must be durable and waterproof. It shall be compressible and possess a high degree of rebound. The dimensions of the board should be equal to that of the joint being formed. It should, preferably be manufactured in one piece, matching the dimension of the joint and not prepared by cutting to size smaller pieces from larger boards at site. At the exposed end, the joint shall be sealed with approved sealing compound to a depth of at least 25 mm after application of an approved primer. The sealing compound and the primer shall be applied as specified by the manufacturer.

b) Expanded Polystyrene Boards

If required, commercial quality of expanded polystyrene products commonly used for thermal insulations may also be used as filler material in expansion joints. The thickness may vary from 12 mm to 50 mm. The material will have to be procured from reliable manufacturers as approved by the Engineer. The method of installations will be similar to that recommended by the manufacturers for fixing on cold storage walls. A coat of Bitumen paint may have to be applied on the board against which concrete will be placed.

3.23.03 Joint sealing strips

Joint sealing strips may be provided at the construction, expansion, and isolation joints as a continuous diaphragm to contain the filler material and/or to exclude passage of water or any other material into or out of the structure. The sealing strips will be either metallic like G.I., Aluminums, or Copper, or non-metallic like rubber or P.V.C.

Sealing strips will not have any longitudinal joint and will be procured and installed in largest practicable lengths having a minimum number of transverse joints. The material is to be procured from reputed manufacturers having proven records of satisfactory supply of joint strips of similar make and shape for other jobs. The jointing procedure shall be as per the manufacturer's recommendations, revised if necessary, by the Engineer. The Contractor is to supply all labour and material for installation -including the material and tools required for jointing, testing, protection, etc. If desired by the Engineer, joints in rubber seals may have to be vulcanized.

a) Metal Sealing Strips

Metal sealing strips shall be either G.I., Aluminium or Copper and formed straight, U shaped, Z shaped or any other shape and of thickness as indicated in the drawing. The transverse joints will be gas welded using brass rods and approved flux and will be tested by an approved method to

establish that it is leak proof. If required, longer lap lengths and different method of brazing which will render it leak proof, will be adopted by the Contractor. The edges shall be neatly crimped and bent to ensure proper bond with the concrete.

i) G.I. Strips

G.I. strips shall be minimum 1.5 mm thick and 150 mm in width unless specified otherwise. The standard of Galvanizing shall be as per relevant Indian Standards for heavy-duty work. At the joints, the overlapping should be for a minimum length of 50 mm.

ii) Aluminium Strips

Aluminium strips shall be minimum 18 SWG thick and 300 mm wide unless specified otherwise and shall conform to IS: 737 of 19000 grades or 31000 grade (Designation as per IS: 6051). A minimum lap of 50 mm length is required at the joints.

iii) Copper Strips

The Copper strips shall be minimum 18 SWC in thickness and 300 mm width unless specified otherwise and shall conform to the relevant Indian Standards. It should be cleaned thoroughly before use to expose fresh surface, without any reduction in gauge. A minimum lap of 50 mm in length is required at the joints.

b) Non-metallic Sealing Strips

These will be normally in Rubber or P.V.C. Rubber or P.V.C. joint seals can be of shape having any combination of the following features:

i) Plain

ii) Central bulb

iii) Dumb-bell or flattened ends

iv) Ribbed and Corrugated Wings

v) V shaped

As these types of seals can be easily handled in very large lengths unlike metal strips, transverse joints will be allowed only under unavoidable circumstances and with the specific approval of the Engineer. The method of forming these joints, laps etc. shall be as specified by the Manufacturer and/or as approved by the Engineer taking particular care to match the

central bulbs & the edges accurately.

c) Rubber Sealing Strips

The minimum thickness of Rubber sealing strips shall be 3 mm and the minimum width 100 mm. The actual size and shape will be as shown in drawings or as directed by the Engineer. The material will be natural rubber and be resistant to corrosion, abrasion, and tear and also to attacks from the acids, alkalis and chemicals normally encountered in service. The physical properties will be generally as follows. The actual requirements may be slightly different as decided by the Engineer:

Specific Gravity	:	1.1 to 1.15
Shore Hardness	:	65A to 75A
Tensile Strength	:	25 - 30 N/Sq.mm
Maximum Safe Continuous Temperature	:	75°C
Ultimate Elongation	:	Not less than 350%

b) P.V.C., Sealing Strips

The minimum thickness of P.V.C. sealing strips will be 3 mm and the minimum width 100 mm. The actual size and shape will be as shown in drawings or as directed by the Engineer. The material should be of good quality Polyvinyl Chloride highly resistant to tearing, abrasion, and corrosion as well as to chemicals likely to come in contact with during use. The physical properties will generally be as follows. The actual requirements, which will be directed by the Engineer, may vary slightly

Specific Gravity	:	1.3 to 1.35
Shore Hardness	:	60A to SOA
Tensile Strength	:	10 - 15 N/Sq.mm
Maximum Safe Continuous Temperature	:	70 Deg.C
Ultimate Elongation	:	Not less than 275%

3.23.04 Bitumen Compound

When shown in drawing or directed, the gap in expansion joints shall be

thoroughly cleaned and bitumen compound laid as per manufacturer's specifications. The compound to be used shall be of approved manufacture and shall conform to the requirements of IS: 1834.

3.23.05 Isolation Joints

Strong and tough alkathene sheet or equivalent, about 1 mm in thickness and as approved by the Engineer shall be used in isolation joints. It shall be fixed by an approved adhesive compound on the cleaned surface of the already set concrete to cover it fully. Fresh concrete shall be laid against the sheet, care being taken not to damage the sheet in any way.

3.23.06 Pad

Hard foundation quality rubber pads of required thickness and shapes shall be put below machine or other foundations as shown on the drawings. The rubber shall have a unit weight of 1500 Kg/Cu.m, a shore hardness - 65A to 70A and be of best quality of approved manufacture, durable, capable of absorbing vibration and must be chemically inert in contact with moist or dry earth or any other deleterious material expected under normal conditions.

3.24.00 Grouting under Machinery or Structural Steel Bases

If required, grouting under base plates of machines or structural steel etc. shall be carried out by the Contractor. In general, the mix shall be 1 (one) part cement and 1 (one) part sand and just enough water to make it flow as required. The areas to be grouted shall be cleaned thoroughly with compressed air jet and/or with water in locations where accumulated surplus water can be removed. Where directed by the Engineer, 6 mm down stone chips may have to be used in the mix. Surface to be grouted shall be kept moist for at least 24 hours in advance. The grout shall be placed under expert supervision, so that there is no locked up air. Edges shall be finished properly. If specified on drawings, admixtures like Aluminium powder, "Ironite" etc. may have to be added with the grout in required proportions. Premixed non-shrink grout of approved manufacture having proper strength shall be used with Engineer's approval for important machineries.

3.25.00 Precast Concrete

The Specification for precast concrete will be similar as for the cast-in-place concrete described herein and as supplemented in this section. All precast work shall be carried out in a yard made for the purpose. This yard shall be dry, properly levelled and having a hard and even surface. If the ground is to be used as a soffit former of the units, it shall be paved with concrete or masonry and provided with a layer of plaster (1:2 proportion) with smooth neat cement finish or a layer of M.S. sheeting. Where directed by the Engineer, casting will have to be done on suitable vibrating table. The yard,

lifting equipment, curing tank, finished material storage space etc. shall be designed such that the units are not lifted from the mould before 7 (seven) days of curing and can be removed for erection after 28 (twenty-eight) days of curing. The moulds shall preferably be of steel or of timber lined with G.I. sheet metal. The yard shall preferably be fenced.

Lifting hooks, where necessary or as directed by the Engineer, shall be embedded in correct position of the units to facilitate erection, even though they may not be shown on the drawings, and shall be burnt off and finished after erection.

Precast concrete units, when ready, shall be transported to site by suitable means approved by the Engineer. Care shall be taken to ensure that no damage occurs during transportation. All adjustments, levelling, and plumbing shall be done as per instructions of the Engineer. The Contractor shall render all help with instruments, materials, and men to the Engineer for checking the proper erection of the precast units.

After erection and alignment, the joints shall be filled with grout or concrete as per drawings. If centrings have to be used for supporting the precast units, they shall not be removed until the joints have attained sufficient strength and in no case before 14 (fourteen) days. The joint between precast roof planks shall be pointed with 1:2 cement: sand mortar where called for in the drawings.

3.26.00 Waterproofing of Concrete Structure

3.26.01 General

Where required, waterproofing of concrete structures shall be ensured internally by suitable design of the concrete mix, addition of suitable admixtures in the concrete or mortar at the time of mixing and/or installing water bars at the joints. In addition to the above measures, the structures shall be made watertight by adopting "structural waterproofing" as per specification. The design, material, and workmanship shall conform to the relevant I.S. Codes where applicable. The Engineer's approval of the materials shall be obtained by the Contractor before procurement. If desired by the Engineer, test certificates for the materials and samples shall be submitted by the Contractor free of charge. The materials shall be of best quality available indigenously, fresh clean and suitable for the duties called upon.

3.26.02 Water Bar/Seal/Special Treatment of Construction Joint

Water bearing structures and underground structures may have water bar/seals installed at the joints. They may be metallic, rubber, or P.V.C. The materials and installation will be as described under Clause 3.23.3. Construction joint shall be provided as per clause 3.13.1 with or without water bar/seal as shown

on the drawing. In case of water bars being used at the construction joint, fixing of the same has to be done carefully, so that the water bar is not disturbed during concreting. The construction joint shall also be treated by any one of the following methods.

Method 1: A surface retarder in the form of a thixotropic gel shall be applied on the joint surface of the previous pour in case of joint on the wall and in case of floor the same shall be applied on the formwork against which previous pour of concreting shall be done. The retarder may be liquid or paste form depending on the type of formwork. The formwork shall be removed within 24 hours after concreting. Within 2 hours of striking of the formwork the retarder shall be washed off with strong water jet to make surface rough and clean. Then a rich cement mortar using cement, sand and aggregates (maximum size 8 mm) along with synthetic rubber emulsion type water resistant bonding agent shall be applied for a depth of 50 mm just before pouring the next stage of concreting. In case of walls, the above bonding agent will be mixed with water, which will be used for making the cement mortar. The proportion of mixing of this bonding agent with water shall be as per manufacturer's specification. In case of floor joint, however, after washing of retarder a solvent free two-component epoxy resin-bonding agent will be used at the joint before the next pour of concrete. The above bonding agent shall have the following properties after 28 days

Compressive strength	-	55 to 60 N/Sq.mm
Flexural strength	-	5 to 30 N/sq.mm
Tensile strength	-	15 N/Sq.mm (approx.)
Bonding strength to concrete	-	3 N/Sq.mm (approx.)
Bonding strength to steel	-	20 N/Sq.m (approx.)

The whole operation shall be done as per manufacturers specification. The contractor shall provide manufacturer's supervision at no extra cost to the owner.

Method 2: One row of threaded nozzles at regular intervals not exceeding l.5 m centre to centre shall be placed in concrete along the construction joint during casting. Injection of cement water together with a suitable waterproof expanding grouting admixture of approved quality shall be done through the nozzles after the concrete has set to seal the voids in concrete near the construction joint in walls and slabs. The injection shall be done under pressure of approximately 2 to 4 kg/sq.cm. The nozzles shall be sealed off with suitable admixture after the injection is over. The whole operation shall be carried out as per manufacturer's specification and supervision. The cost of such manufacturer's supervision shall be borne by the contractor.

3.26.03 Waterproofing Admixtures

The waterproofing admixture for concrete and cement mortar/plaster shall conform to IS: 2645. The admixture shall not cause decrease of strength of concrete/plaster at any stage and it shall be free from chlorides and sulphates. The admixture shall not affect the setting time by more than 5%. The maximum permissible dosage of admixture will be 3% (three percent) by weight of cement, but a lower dosage will always be preferred. The product shall be stored in strong moisture proof packings. However, in case of important structures where M25 or higher grade concrete is specified, the use of melamine based, high range water reducing concrete admixture shall be used to provide a waterproof concrete, For achieving high strength concrete having cement content around 400 kg/cu.m. a melamine based super plasiticizer will be preferable.

a) In concrete: The admixtures shall be procured from reliable and reputed manufacturers and approved by the Engineer. The method of application and other details shall conform to the manufacturer's specification and/or as instructed by the Engineer. The Contractor shall have the services of the manufacturer's supervisor at no extra cost to supervise the work, if desired by the Engineer.

b) In Plaster: The concrete surface, to be plastered, shall be hacked to Engineer’s satisfaction, cleaned thoroughly and kept wetted for 24 hours. The plaster shall be in cement sand mortar mixed in proportion varying from 1:1 to 1:4 by volume along with the approved waterproofing admixture and laid in appropriate thickness and in layers not exceeding 15 mm/layer or as per manufacturer's specification. The additive shall be of quality and type approved by the Engineer. If desired by the Engineer, the Contractor shall have the work supervised by the manufacturer's supervisor at no extra cost. On completion, the Plastered surface shall be cured continuously for a minimum period of 14 days like concrete.

3.26.04 Structural waterproofing

a) Nozzles spaced as required after the concrete is completed shall be drilled into surfaces to be rendered watertight. Non-shrink cement grout with waterproofing compound as per manufacturers specifications shall be injected under pressure to seal all voids. Special care shall be taken at joints by providing additional nozzles. The pressure grouting shall be done on the internal surface.

b) External Treatment

Two layers of (1:4) plaster of 12 mm thick each with waterproofing compound as per manufacturer's specification shall be provided on outer

surface of concrete underground structures.

3.26.05 Protective coating on Inside Surface.

Two coats of cement based two components polymer modified flexible protective and waterproofing slurry having 1 mm thick for each coat shall be applied on the walls/floor after proper surface preparation as mentioned above. The slurry shall be applied by brush.

3.26.06 Bitumen Felt: Application for Tanking

This specification shall cover laying the waterproof course on the outside and inside of the walls and bases of structures.

The materials shall conform to IS: 1322, and the workmanship to IS: 1609. The bitumen felt should be hessian base and/or fibre base as specified in Drawing. If required by the Engineer, tests as specified in relevant IS Codes shall be arranged by the Contractor without charging any extra to the Owner.

The Contractor shall execute this work in direct collaboration with one of the well-known specialized firm approved by the Engineer.

Cleaning the surface, keeping it dry, providing, necessary corner fillets and cement rendering and cutting chases, etc. shall be done as per drawings and/or instructions. If any protective brickwork on/against concrete sub-bases or walls are required, the same shall be provided. A twenty (20) years guarantee for satisfactory performances shall be given by the Contractor as well as his specialist sub-contractor jointly and severally, for this work. Free rectification of any defects noted in the work within this guarantee period will be carried out by the Contractor even if it is beyond the specified maintenance period of the contract as a whole.

3.26.07 Polyethylene Films: Application in Walls or base of structures

Waterproof treatment shall be applied as outlined and as per sequence given hereunder

i) the concrete surface shall be made smooth with 12 mm cement plaster 1:6.

ii) apply hot bitumen 80/100 grade (IS: 73-1961) at the rate of 1.0 Kg/Sq.m minimum

iii) lay black polyethylene film 250-micron (IS: 2508-1977) with cut back bitumen adhesive in overlaps over hot bitumen surface, gently pressed, taking care not to puncture the film.

Alternatively, the overlaps shall be heat sealed by an electric iron having

three parallel sealing bars. A long piece of plywood is to be placed below the polyethylene film to be heat-sealed. On the plywood a rubber gasket is to be laid to provide a cushion for better welding of the film. On the rubber padding, a cellophane tape is to be spread and on this the LDPE film, with 100 mm overlap, is to be stretched. On the overlapped film another cellophane tape is to be placed to prevent the heat sealer from sticking to the LDPE film. After this, the electric iron is to be pressed on the overlap joint for sufficient time so as to allow perfect welding. The operation is to be repeated for subsequent lengths of joints. After heat-sealing, the cellophane tape is to be removed and the joints are to be tested for leaks.

iv) Lay 100 gm brown craft paper laminated with a layer of straight run bitumen,

v) Lay hot bitumen 80/100 grade (IS: 73-1961) at 1.0 Kg/Sq.m minimum.

vi) Lay 250-micron polyethylene film as second layer similar to (iii)above.

viii) Lay second layer of 100 gm. brown craft paper laminated similar to (iv) above.

ix) Apply hot bitumen (straight run grade) to IS: 73-1961 at 1.0 Kg/Sq.m dusted with fine sand.

x) Protecting with a layer of 75 mm plain cement concrete M-10, or a layer of brick laid in cement mortar 1:6 in case of wall apply a 12 mm thick plaster as shown on the drawing or a protective brick wall in 1:6 cement mortar as shown on the drawing.

3.27.00 Protective Coating on Concrete Surface

3.27.01 On Foundation

The outside faces of foundation of important structures will be protected from adverse effect of soil/underground water, if shown on drawing by using rubber/bitumen emulsion protective coating of approved manufacturer.

4.00.00 SAMPLING AND TESTING

4.01.00 General

The Contractor shall carry out all sampling and testing in accordance with the relevant Indian Standards and as supplemented herein for the following items at his own cost unless otherwise specified in this specification. The Contractor shall get the specimens tested in a laboratory approved by the Engineer and submit to the Engineer the teat results in triplicate within 3 (three) days after completion of the test.

4.02.00 Cement

Representative samples will be taken from each consignment of cement received from the manufacturer/supplier for carrying out the tests for fineness (by hand sieving), setting time and compressive strengths as per guidelines of IS: 269. Soundness Tests may also be required to be carried out if required by the Engineer. The Contractor shall carry out the tests without any expense to BHEL. No cement from a particular consignment/batch will be used on the works unless satisfactory 3 (three) days and 7 (seven) days test results for compressive strength are known. The Engineer and Contractor will jointly associate themselves with the tests irrespective of whether they are carried out by the BHEL or the Contractor. These tests are of great importance, as their results will have a bearing on the acceptance of concrete or otherwise as per the terms and conditions of the Contract.

4.03.00 Aggregates

The contractor shall carry out any or all the tests on aggregates as may be required by the Engineer in accordance with IS: 2386 PARTS-I to VIII. The acceptance criteria of the samples tested shall be in accordance with the requirements of the relevant Indian Standards.

4.04.00 Water

Sampling and Testing of water being used for concrete works as per IS: 3550 will be carried out by the Contractor at regular intervals and whenever directed by the Engineer. The acceptance criteria will be as per IS: 456.

4.05.00 Admixture

4.05.01 Air Entraining Agents

Initially, before starting to use A.E.A., relationship between the percentage of air entrained and the cylinder cube crushing strength vis-a-vis quantity of A.E.A. used for all types of concrete will be established by the Contractor by carrying out sufficiently large number of tests. After that, at regular intervals and whenever directed by the Engineer, the Contractor will check up the actual percentages of air entrained and corresponding crushing strengths to correlate with the earlier test results.

4.05.02 Other Admixtures

Tests for establishing the various properties of any other admixtures, which may be required to be added, shall be carried out by the Contractor.

4.06.00 Concrete

The sampling of concrete, making the test specimens, curing and testing procedure etc. shall be in accordance with IS: 516 and IS: 1199, the size of specimen being 15 cm cubes. Normally, only compression tests shall be performed but under special circumstances the Engineer may require other tests to be performed in accordance with IS: 516. Sampling procedure, frequency of sampling and test specimen shall conform to IS: 456. To control the consistency of concrete from every mixing plant, slump tests shall be carried out by the Contractor every two hours or as directed by the Engineer. Slumps corresponding to the test specimens shall be recorded for reference. The acceptance criteria of concrete shall be in accordance with IS: 456. Concrete work found unsuitable for acceptance shall have to be dismantled and replacement is to be done as per specification by the Contractor at his own cost. In the course of dismantling, if any damage is done to the embedded items or adjacent structures, the same shall be made good, free of charge by the Contractor, to the satisfaction of the Engineer.

5.00.00 ACCEPTANCE CRITERIA

5.01.00 Standard Deviation

Standard deviation shall be based on test results and determination of Standard deviation shall conform to IS: 456.

5.02.00 Acceptance Criteria

The strength requirements and acceptance criteria shall conform to IS: 456.

5.03.00 Inspection and Core Tests

Inspection of concrete work immediately after stripping the formwork and core test of structures shall conform to IS: 456.

5.04.00 Load Test

Load tests of structural members as per IS:456 may be required by the Engineer, when the strength of test specimen results falls below the required strength.
If the member shows evident failure, the Contractor shall make the structure adequately strong free of cost to BHEL.

The entire cost of load testing shall be borne by the Contractor. If a portion of the structure is found to be unacceptable, it shall be dismantled and replaced by a new structure as per specification. The entire cost of dismantling and replacement and restoration of the site being borne by the Contractor.

If, in the course of dismantling, any damage is done to the embedded items

and or other adjacent structures, the same will be made good, free of charge by the Contractor to the satisfaction of the Engineer.

6.00.00 RATES AND MEASUREMENTS

6.01.00 Cast-in-situ Concrete

6.01.01 Rates

a) The unit rates shall include the cost of labour, materials, equipment, handling, transporting, botching, mixing, placing in position, vibrating, compacting, finishing, curing, testing, etc. at all elevations. This shall include the cost of curing by regular wetting or by using curing compound.

b) The unit rates shall include for all working conditions including at locations under water, liquid, mud, in or under foul positions and extreme weather conditions.

c) The unit rates for exposed concrete works (including machine foundations) shall include all incidentals, rendering, smoothening with carborandum stone, finishing with a paste of cement sand mortar, curing, etc.

d) The unit rates shall include all arrangement for maintaining stability of structure during execution.

e) Nothing extra shall be payable for the handling/mixing of extra cement on account of any reason or pouring of second stage concrete.

f) Nothing shall be payable to the Contractor on account of facilities and arrangement provided by him for conducting ultrasonic pulse velocity (UPV) tests or other relevant tests to ascertain grade and quality, etc. of the concrete in case the concrete quality is in doubt and contractor has to establish the quality by further tests. In case of any defects, the Contractor shall rectify the same by cement/epoxy grout at his own cost.

However, mandatory UPV test as specified in the drawings shall be carried out including arrangement of all its facilities, staging, etc. and shall be payable to the contractor as per BOQ item.

g) The unit rates for controlling of the temperature of concrete shall include storing and mixing of ice, water, cooling of aggregate etc.

h) The quoted rate shall include the cost of MIX design, making of all trial mixes using admixtures and mixing in concrete etc. complete.

6.01.02 Measurements

a) Actual volume of concrete work as executed or as per drawings issued, whichever is less shall be measured in cubic metres to the nearest two decimals.

b) No deductions shall be made for the following:

i) Ends of dissimilar materials embedded inside for example, beams, posts, girders, rafters, purlins, trusses, corbels and steps upto 500 sqcm in cross section;

ii) Opening upto 0.1 sq.m.

iii) Volume occupied by reinforcement, sleeves, anchor bolts, and similar items.

iv) Volume occupied by pipes, conduits, sheathing, etc. not exceeding 100 sq.cm. each in cross sectional area.

c) The concrete works of different grades; below and above ground floor finished level shall be measured separately, unless otherwise specified in the schedule of items. Accordingly rates shall be applied for concrete in foundation for concrete below ground floor finished level and concrete in superstructure for concrete above ground floor finished level.

d) For temperature control measures, measurement shall be done in terms of quantity of concrete in cum. in concreting of which the ice have been used or cooling of aggregates has been done to keep the temperature of freshly laid concrete to less than 23^0C.

6.02.00 Reinforcement

6.02.01 Rates

a) The unit rates shall include for cover block, providing binding wire, welding, separator pieces between two or more layers of reinforcement required for keeping the steel in position, etc. at all elevations.

b) No extra will be paid for transportation from stores, cleaning, straightening of steel, cutting, bending, binding with annealed wire, welding, tack welding, placing the reinforcement modification of already embedded reinforcement, if required, due to faulty fabrication or placement and other cost of tools and plants, materials, labours, return of unused steel to the store, etc.

c) However, lap welding of reinforcement steel if permitted shall be paid under separate item as provided in the BOQ and no deduction for labour

and binding wire saved for not providing lap length shall be made. Similarly, splicing of reinforcement bars using mechanical couplers if permitted shall be paid under separate item as provided in the BOQ and no deduction for labour and binding wire saved for not providing lap length shall be made.

d) No extra shall be paid for preparing and getting approved bar bending schedules (including all revisions).

e) Generally members are straight and have straight edges. However, for bending, binding, placing of reinforcement in any curved member in length or cross section or both, no extra payment shall be made.

6.02.02 Measurements

a) Bar or any other type of reinforcement used like hard drawn steel wire fabric etc. for reinforced concrete shall be measured by weight in tonnes. The weight shall be arrived at by multiplying the actual or theoretical length measured alongwith standard hooks, cranks, bends, authorized laps, etc. whichever is less by the sectional weights. Claims for payment for this item shall be submitted with supporting documents giving the schedule of bars with sketches. The sectional weight to be adopted shall be IS Section weight. Nothing extra will be payable to the Contractor on account of, difference in weight, if any, due to different methods adopted for issue and measurement.

b) Standard hooks, cranks, bends, authorised laps, supports, hangers and chairs which are covered in approved bar bending schedule shall be measured in tonnes.

6.03.00 Formwork and Staging

6.03.01 Rates

a) The unit rates shall be inclusive of all staging, scaffolding, making the formwork watertight, etc. for all elevations and in all types of works.

b) No separate payment shall be made for providing fillets, for rounding or chamfering at junctions, comers, etc.

c) The unit rates shall include the cost of labour, materials etc. and the extra time, which shall be required for the removal of shuttering/ support for satisfactory completion of work.

d) No extra payment shall be made on account of difficulty, wastage etc. for placement/removal of formwork between the network of closely placed steel beams or for the lacing/bracing portions and ribbed slab constructions.

e) Payment for curved shuttering shall be made for curved members/wall whose centerline radius in plan is less than 6m.

f) If the contact surface area in pockets is less than or equal to 0.1 sq.m. in each case, payment shall be done under item for providing formwork in pockets.

6.03.02 Measurements

a) Formwork for different classes (types) shall be measured separately as the actual surface in contact with the concrete and paid on area basis unless included in the rate for concrete. The unit of measurement shall be in sq.m.

b) Openings upto 0.1 sq.m or boxing left for inserts etc. for facility of Contractor's work, shall be neglected as if nonexistent for the purpose of formwork measurement of surface in which the openings occur.

For suspended floor, no deduction shall be made for flange area of secondary steel beams.

d) No measurement shall be taken for the formwork in pockets, openings, chases, blockouts, etc. in concrete, the contact surface area is less than or equal to 0.1 sq.m. in each case.

e) For pockets, if the contact surface area is less than or equal to 0.1 sq.m. in each case, measurement shall be done under item for providing formwork in pockets.

e) Formwork, if required, for joints shown on drawing or instructed by the Engineer, shall be paid for the 'leading side' only.

6.04.00 Embedded Parts

6.04.01 Rates

a) The unit rate for erection of embedded steel parts, supplied by Engineer shall include transportation from Owner's store to the place of work, erection & installation including setting material in concrete, etc. complete.

b) The unit rate for MS pipe embedments and PVC pipe embedments shall include cutting, welding, fabrication, erection, embedding, and transportation to site. Unit rate shall also include the cost of the pipes.

c) Rate for expansion fasteners shall include cost of fasteners, installation, and fixing including cost of washers and nuts and site testing if required.

6.04.02 Measurements

a) The measurement of the embedded steel parts fabricated and installed by the Contractor shall be based on the calculated weight of steel sections in tonne corrected to second place of decimal.

b) Embedded steel parts supplied by Owner and installed by Contractor Measurement shall be done for the net weight of the embedments installed in tonnes correct to second place of decimal.

c) For PVC pipes/conduits, measurements shall be in quintals correct to second place of decimal for the net weight.

d) For mild steel pipes, measurement shall be in quintals, correct to second place of decimal, for the net weight of the steel pipe supplied, fabricated, and installed.

e) The lugs shall be measured in Kg. correct to second place decimal for the net weight.

f) The expansion fasteners shall be measured in number according to tension capacity.

g) The rails shall not be treated as embedded steel part and the track shall be measured in running metres along the centre line and paid for under separate item of work as specified in schedule of items. Other related civil items associated with the laying of track shall be measured separately and paid under respective items of works.

6.05.00 Groutings

6.05.01 Rates

Rate shall include the cost of surface preparation, admixtures, and curing.

6.05.02 Measurements:

a) Measurement shall be in cubic decimeters.

b) Measurement for grouting shall be by volume of the block out, pockets or bolt hole upto the top surface of foundation concrete and shall be calculated from the dimensions shown on the drawings.

c) Measurement for underpinning shall be by volume between the top surface of the foundation concrete and the underside of the base plate, the plan dimensions being as indicated on the drawings.

d) No deduction shall be made for shims, bolts, shear keys and such other embedments.

f) Pressure injection grouting with cement based grout if required as per drawing shall be applied at appropriate spacing to cover the desired surface area and measurement shall be made for the surface area grouted in sqm as per BOQ item. However in water retaining structures, the structural grouting if required to ensure water tightens shall not be payable separately as deemed to be covered in water retaining concrete item of BOQ.

6.06.00 Joints

6.06.01 Rates

The unit rate shall include all the activities described in the schedule of items.

6.06.02 Measurements

a) Bitumen Board/Expanded polystyrene.

The measurement for bitumen board shall be based on actual finished surface area in square meters nearest to second decimal, for the specified thickness.

b) Water Stops

The measurement for water stops shall be in running metres of actual length of the joint covered, for specified thickness, width, and shapes. No separate measurement shall be made for laps/splices for cross-joints and mitered joints.

c) Metal Cover Strips

The measurement for Metal Cover Strips shall be based on actual finished surface area in square metres for the specified thickness.

d) Vibration Damping Resilient Pads

The measurement for this item shall be in square metres for the specified thickness, measured correct to the second place of decimal, of the actual finished surface area.

6.07.00 Dismantling/Demolishing Work – RCC and PCC and Chipping of Concrete

6.07.01 Rates

The unit rates shall include the cost of all necessary propping, shoring, underpinning scaffolding, safety measures, temporary enclosures, disposal/ stacking of serviceable/unserviceable materials, etc. for all types of work and for all grades of concrete.

In the case of dismantling/demolishing work, the cutting of reinforcement shall also be included in the rate.

In the case of chipping work, the cutting of reinforcement shall be paid separately.

If the serviceable material including reinforcement steel from dismantled structure is allowed to be used/taken out by bidder, suitable rebate shall be given by bidder.

6.07.02 Measurements

a) Dismantling of PCC and RCC work shall be measured in cu.m separately. Measurement of all work, except hidden work shall be taken before execution of work and no allowance for increase in bulk shall be allowed. Specifications for deductions of voids, openings etc, shall be done on the same basis as that applied for construction work.

b) Chipping of concrete, making holes/pockets etc. shall be measured in cubic decimeters (i.e. 0.001 cu.m.).

c) Cutting of reinforcement in chipping work for making of pockets and openings shall be measured in sq. cm. of cross-sectional area.

6.08.00 Precast Concrete

This clause shall be read in conjunction with relevant provisions specified elsewhere for cast in-situ Concrete.

6.08.01 Rates

a) The unit rate shall include cost of preparation of casting yard, formwork, concrete and its casting, finishing as specified, setting filling of gaps between adjacent pre-cast concrete units with concrete, or cement mortar, curing, handling, erection, grouting, welding, preparation of supporting surface, etc.

6.08.02 Measurements

The measurement of pre-cast concrete members shall be on the basis of

volume of concrete in cubic metres nearest to second place of decimal. No deduction shall be made for volume occupied by reinforcement/inserts/sleeves and for openings up to 0.1 sq.m. The setting of element with cement mortar shall not be measured separately The filling of concrete cement mortar between the gaps of adjacent precast units shall be considered while computing the volume of pre-cast concrete work and shall be paid for under this item itself.

7.00.00 LIST OF IS CODES AND STANDARDS FOR REFERENCE

All work under this specification shall, unless specified otherwise, conform to the latest revisions and/or replacements of the following or any other Indian Standard Specifications and Codes of Practice. In case any particular aspect of work is not specifically covered by Indian standard Specifications, any other standard practice, as may be specified by the Engineer, shall be followed:-

IS: 73 - Indian Standard Specification for Paving Bitumen

IS: 216 - Indian Standard Specification for Coal Tar Pitch

IS: 383 - Indian Standard Specification for Coarse and Fine Aggregates from Natural Sources for Concrete

IS: 432 - Indian Standard Specification for Mild Steel and Medium Tensile Steel Bars and Hard Drawn Steel Wire for concrete Reinforcement

IS: 455 - Indian Standard Specification for Slag Cement

IS: 456 - Indian Standard Code of Practice for Plain and Reinforced Concrete

IS: 457 - Indian Standard Code of Practice for General Construction of Plain and Reinforced Concrete for Dams and other Massive Structures

IS: 516 - Indian Standard Specification for Methods of Test for Strength

of Concrete

IS: 702 - Indian Standard specification for industrial bitumen.

IS: 1199 - Indian Standard Specification for Methods of Sampling and Analysis of Concrete

IS: 1322 - Indian Standard Specification for Bitumen Felts for Waterproofing and Damp-proofing

IS: 1489 - Indian Standard Specification for Portland Pozzolona Cement

IS: 1566 - Indian Standard Specification for hard drawn steel wire fabric for concrete reinforcement.

IS: 1609 - Code of Practice for Laying Damp-proof Treatment using Bitumen Felts

IS: 1786 - Indian Standard Specification for High Strength Deformed Steel Bars and Wires for Concrete Reinforcement.

IS: 1791 - Indian Standard Specification for Batch Type Concrete Mixers.

IS: 1838 - Indian Standard Specification for preformed fillers for expansion joints in concrete pavements and structures (non-extruding and resilient type.

IS: 2185 - Indian Standard Specification for Hollow Cement Concrete Blocks

IS: 2210 - Indian Standard Specification for Design of Reinforced Concrete shell Structures and Folded Plates

IS: 2386 - Indian Standard Specification for Methods of Test for Aggregates for Concrete - Part-I to VIII

IS: 2502 - Indian Standard Code of Practice for Bending and Fixing of Bars for Concrete Reinforcement

IS: 2505 - Indian Standard Specification for Concrete Vibrators, Immersion Type

IS: 2506 - Indian Standard Specification for Screed Board Concrete Vibrators

IS: 2514 - Indian Standard Specification for Concrete Vibrating Tables

IS: 2571 - Code of practice for laying in-situ cement concrete floors.

IS: 2645 - Integral cement water proofing compound

IS: 2722 - Indian Standard Specification for Portable Swing Weigh Batchers for Concrete (Single and Double Bucket type)

IS: 2750 - Indian Standard Specification for steel scaffoldings.

IS: 2751 - Code of Practice for Welding of Mild Steel Bars used for Reinforced Concrete Construction

IS: 2770 - Indian Standard Specification for Method of Testing Bond in Reinforced Concrete

IS: 3025 - Indian Standard specification for Methods of Sampling and Test (Physical and Chemical) for Water used in Industry

IS: 3067 - Code of practice for general design details and preparatory work for damp proofing and water proofing of building.

IS: 3201 - Indian Standard Specification for Design and Construction of Precast Concrete Trusses

IS: 3370 - Indian Standard Specification for Code of Practice for Concrete Structures for Storage of Liquids

IS: 3414 - Code of practice for design and installation of joints in buildings.

IS: 3550 - Indian Standard Specification for Method of Test for Routine Control for Water used in Industry

IS: 3558 - Code of Practice for use of Immersion vibrators for Consolidating Concrete

IS: 3696 - Safety Code for Scaffolding and Ladders

IS: 3812 - Indian Standard Specification for Fly Ash for Use as Admixture for Concrete

IS: 4014 - Code of practice for steel tubular scaffolding.

IS: 4031 - Indian Standard Specification for Method of Tests for Hydraulic Cement

IS: 4082 - Indian Standard Specification for Recommendation on

Stacking and Storage of Construction Materials at site

IS: 4090 - Indian Standard Specification for Design of Reinforced Concrete Arches

IS: 4634 - Indian Standard Specification for Method of Testing Performance of Batch-type Concrete Mixes

IS: 4656 - Indian Standard Specification for Form Vibrators for Concrete

IS: 4925 - Indian Standard Specification for Concrete Batching and Mixing Plant

IS: 4926 - Indian Standard Specification for Ready Mixed Concrete

IS: 4990 - Indian Standard Specification for Plywood for Concrete Shuttering work

IS: 4991 - Indian Standard Specification for Blast Resistant Design of structure for Explosion above ground

IS: 4995 - Indian Standard Specification for Design of Reinforced Part-I & II Reinforced Concrete Bins for the Storage of Granular and Powdery Materials

IS: 4998 - Indian Standard Specification for Design of Reinforced Concrete Chimneys.

IS: 5256 - Code of practice for sealing joints in concrete lining on canals.

IS: 5512 - Indian Standard Specification for Flow Table for use in Tests of Cement and Pozzolanic materials

IS: 5513 - Indian Standard Specification for vacate Apparatus.

IS: 5515 - Indian Standard Specification for Compaction Factor Apparatus.

IS: 5525 - Recommendation for detailing of reinforcement in reinforced concrete works.

IS: 5624 - Indian Standard Specification for foundation bolts.

IS: 5751 - Indian Standard Specification for Precast Concrete Coping Blocks.

IS: 5816 - Indian Standard Specification for Method of Test for Splitting

Tensile strength of Concrete Cylinders.

IS: 5891 - Indian Standard Specification for Hand operated Concrete Mixers.

IS: 5892 - Indian Standard Specification for transit mixer and agitators.

IS: 6452 - Indian Standard Specification for High Alumina Cement for Structural Use

IS: 6909 - Indian Standard Specification for Super sulphated Cement

IS: 6923 - Indian Standard Specification for Method of Test for Performance of Screed Board Concrete Vibrators.

IS: 6925 - Indian Standard Specification for Method of Test for Determination of Water Soluble Chloride in Concrete Admixtures.

IS: 7242 - Indian Standard Specification for Concrete Spreaders.

IS: 7246 - Indian Standard Specification for Table Vibrators for Consolidating Concrete.

IS: 7251 - Indian Standard Specification for Concrete Finishers.

IS: 7293 - Safety code for working with construction machinery.

IS: 7320 - Indian Standard Specification for Concrete Slump Test Apparatus.

IS: 7861 - Indian Standard Specification for Recommended Practice Part-I&II for Extreme Weather Concreting.

IS: 7969 - Safety Code for Storage and Handling of Building Materials.

IS: 8041 - Indian Standard Specification for Rapid Hardening Portland cement.

IS: 8112 - Indian Standard Specification for high strength Ordinary Portland Cement.

IS: 8142 - Indian Standard Specification for Determining Setting time of concrete by Penetration Resistance.

IS: 8989 - Safety Code for Erection of Concrete Framed Structures.

IS: 9012 - Recommended method for shortcreting.

IS: 9013 - Indian Standard Specification for Method of Making, Curing, and determining compressive Strength of Accelerated-cured Concrete Test Specimens.

IS: 9077 - Code of Practice for Corrosion Protection of Steel Reinforcement in RB and RCC Construction.

IS: 9103 - Indian Standard Specification for Admixtures for Concrete.

IS: 10262 - Recommended Guidelines for Concrete Mix Design.

IS: 13311 - Non-destructive testing of concrete.

SP: 34 - Handbook of concrete, reinforcement and detailing.

VOLUME: II B

SECTION - D

SUB-SECTION – D3

CARPENTRY AND JOINERY

SPECIFICATION NO. PE-TS-999-600-C003

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	3
3.00.00	ACCEPTANCE CRITERIA	5
4.00.00	I.S. CODES	6
5.00.00	RATES AND MEASUREMENTS	6

CARPENTRY AND JOINERY

1.00.00 SCOPE

This section covers supply, fitting and fixing of timber frames to doors and windows with M S holdfasts, flush doors, windows, shutters, partitions, wall panelling, pelmets, shelves, furniture, etc. as shown in drawings, including a prime coat of approved paint, varnish, or fixing of decorative plastic laminate where called for. This shall also include the supply and fixing of all hardware and fixtures shown in drawing or specified.

2.00.00 INSTALLATION

2.00.01 Materials

a) Timber

Unless otherwise specified, all timber shall be best quality well-seasoned CP teakwood free from large or loose knots, cracks or any other defects. All timber shall be treated with approved wood preservative before use, unless specified otherwise. The rough timber shall be approved by the Engineer before incorporating in the works and starting the carpenter's work.

b) Plywood

Plywood shall be of commercial quality or with decorative surface veneer. Unless specifically permitted otherwise, the adhesive used in plywood shall be phenol formaldehyde synthetic resin of BWP grade conforming to IS: 848.

c) Decorative Laminated Plastic Sheets

The colour, pattern, finish and texture shall be approved by the Engineer. The bulk supply shall be procured in full sheet sizes which will ensure the least number or joints in one surface.

d) Flush Doors

Flush doors shall be solid core doors with commercial or decorative faces and hardwood edges conforming to IS: 2202 (Part-1). The core for solid core doors shall be of block board or wood particle board. Manufacturer's literature and test certificates shall be submitted for the approval of the Engineer. The Contractor shall give a guarantee that the adhesive used is BWP grade phenol formaldehyde synthetic resin conforming to IS: 848. The thickness shall be as specified.

e) Panel Doors

Panel door shall be of teakwood shutter frame, unless otherwise noted and panels with teakwood/commercial ply/teakwood particle board. Other considerations shall be as mentioned in item (d) above.

f) Windows, Ventilators

Windows and ventilators shall be made of teakwood shutter frame, unless specified otherwise and glazing of specified thickness shall be fixed with wooden beadings.

g) Fixtures

Fixtures for doors, windows, furniture etc. shall be as shown on drawing or specified.

2.02.00 Workmanship

2.02.01 General

The work shall be done by skilled carpenters as per details shown on drawing or instructed by the Engineer.

Framing timber and other work shall be close - fitting with proper wood joinery, accurately set to required lines or levels and rigidly secured in place. The surface of frames etc., which will come in contact with masonry after fixing, shall be given two coats of approved paint before fixing. Mastic caulking shall be done after fixing external door and window frames. Special care shall be taken to match the grain of timber or plywood, which will be subsequently polished. Screwing or nailing will not be permitted to the edge of plywood and particle board. The edge of all plywood, blackboard and particle board shall be finished with teakwood lipping unless otherwise shown on drawings.

Fixing to frames and partitions shall generally be with 40 mm x 6 mm x 300 mm long M S holdfasts bifurcated at end and grouted with 1:2:4 cement concrete. The gap between masonry and external door and window frame shall be caulked with polysulphide mastic. M.S. grills or guard bars shall be provided to windows where called for in the drawings.

2.02.02 Finish

All carpentry work after finishing shall be sand papered smooth. A prime coat paint shall be given after inspection of the Engineer to all surfaces other than those, which shall be subsequently polished or covered with laminated plastic sheet.

2.02.03 Surface Treatment

When shown on drawings or called for, decorative ply or laminated plastic sheets shall be bonded under pressure to the surface to be finished. The adhesive used shall be of brand and brought to site in sealed containers. The rate of application and the length of time for which the pressure is to be applied shall be as per the manufacturer's instructions. The edge of sheets shall be protected by teak lipping or bevelled as shown on drawings.

3.00.00 ACCEPTANCE CRITERIA

3.00.01 Door and Window Frames

All frames shall be square and flat at the time of delivery and shall be checked for dimensions and corner angles. After fixing they shall be on a fine vertical plane. All external door and window frames shall be caulked with mastic.

3.02.00 Door and Window Shutters

All doors and window shutters shall be of proper size, shape, and design and free of warp. When fixed to frames, these shall operate smoothly without jamming and all latching or locking devices shall engage properly without undue pressure.

3.03.00 Partitions, Panelling, Pelmets, Furniture, etc.

3.03.01 General

These shall conform to drawings in all details. No unsightly nail marks etc. shall be permitted. Plywood grains shall be matched to give a uniform and pleasing appearance.

3.03.02 Partition

Shall be checked for rigidity of fixing, plumb and horizontal as well as vertical alignment.

3.03.03 Pelmets

Shall be checked for rigidity of fixing and adequate clearance of fixture.

3.03.04 Cupboard Shutters

Shall operate smoothly without jamming and locks, bolts and double ball catches shall engage securely. Single ball catches shall not be used.

3.03.05 Drawers

Shall operate smoothly and have backstops to prevent them from being pushed too far. Locks shall engage securely.

3.03.06 Loose Furniture

When placed on a level surface, tables tops etc. shall be horizontal and the pieces stand stably on legs or supports.

4.00.00 IS CODES

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS: 848	-	Synthetic resin adhesives for plywood (Phenolic and Aminoplastic)
IS: 1003	-	Timber panelled and glazed shutters.
IS: 2191	-	Wooden flush door shutter (Cellular and hollow core type).
IS: 2202	-	Wooden flush door shutters (solid core type).
IS: 4021	-	Timber door, window, and ventilator frames.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall include of all activities mentioned in "Schedule of Item" for completion of the work. No separate payment shall be made for fixing, caulking, application of primer coat, polishing, providing of butt hinges, holdfasts, sliding/tower bolts, door stoppers, door closers and other fittings and fixtures.

5.02.00 Measurement

Measurement shall be done in Sqm for doors, windows, ventilators, shutters, partitions etc.

Measurement for wooden frame shall be in CuM.

Pelmets shall be measured in RM.

VOLUME: II B

SECTION – D

SUB-SECTION – D4

ROOF AND UNDERGROUND STRUCTURES WATER PROOFING, INSULATION AND ALLIED WORKS

SPECIFICATION NO. PE-TS-999-600-C004

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	3
3.00.00	ACCEPTANCE CRITERIA AND GUARANTEE	13
4.00.00	I.S. CODES AND STANDARDS	14
5.00.00	RATES AND MEASUREMENTS	15

ROOF AND UNDERGROUND WATER PROOFING, INSULATION AND ALLIED WORKS

1.00.00 SCOPE

This section covers furnishing, installation, repairing, finishing, curing, testing, protection, maintenance till handing over of roof and underground water-proofing, insulation and allied works for buildings and at locations covered under the scope of this package.

2.00.00 INSTALLATION

2.01.00 GRADING UNDERBED

The surface to receive the underbed shall be roughened and thoroughly cleaned with wire brush and water. Oil patches if any shall be removed with detergent. The surface shall be soaked with water and all excess water removed just before laying of the underbed.

The underbed shall not be laid under direct hot sun and shall be kept in shade immediately after laying so as to avoid quick loss of water from the mix and separation from the roof surface. The underbed shall be cured under water for at least 7 days.

The underbed shall be laid to provide an ultimate run off gradient not less than 1 in 120 and as directed by the Engineer. Upto an average thickness of 25mm the underbed shall usually be composed of cement and sand plaster. For higher thickness the underbed shall be made with cement concrete. The underbed shall be finished to receive the waterproofing treatment direct or insulation as the case may be.

2.01.01 Cement Mortar Underbed

The underbed grading plaster shall be average 25 mm thick maximum. It shall consist of cement and coarse sand in the ratio 1:4 nominal by volume. The sand and cement shall be thoroughly mixed dry and then water added. Each batch of mix shall be consumed before the initial set starts.

The plaster shall be fully compacted to the desired grade in continuous operation. The surface shall be even and reasonably smooth.

2.01.02 Cement Concrete Underbed

The underbed cement concrete shall be used where the subgrade is more than average 25 mm thick. It shall consist of cement concrete 1:2:4 nominal mix

by volume with 12 mm down stone chips and coarse sand. The aggregate shall be mixed dry and minimum quantity of water shall be added to make the mix workable.

The mix shall be laid to proper grade, fully consolidated and surface shall be smooth and even.

2.02.00 INSULATION

The Tenderer shall, along with the tender, send specifications of insulating materials he proposes to use and the proposed method of laying. Before bulk supply, the contractor shall send samples of insulating material to the Engineer, and after approval of the samples, the Contractor shall procure and transport the bulk material to the site. Whenever asked by the Engineer, the Contractor shall furnish test certificates from testing laboratory on the insulating and other properties of the materials.

After laying the insulation, the surface shall be made ready as required to receive the waterproofing treatment. If any plastering is used it shall be not leaner than 1:4 cement sand by volume and not thinner than 12 mm and it shall be cured for seven days.

2.02.01 Foam Concrete

This shall be of lightweight foam concrete of average 50 mm thickness or as specified or as shown on drawings. This may be laid in situ in suitable panels or precast blocks. The insulating properties shall be such that the thermal conductivity shall not exceed 0.125 Kcl/sq.m. hr degree C. Before starting the laying of foam concrete samples shall be prepared at site and got tested for approval of the Engineer.

The foam concrete laid shall be sufficiently strong to withstand the usual workload and standard loads expected on the roof. Any damaged portion shall be removed and replaced forthwith. Approval of the Engineer shall be taken before laying the waterproofing over the insulation.

While laying the foam concrete, samples from each batch of the mix shall be kept for test if so desired by the Engineer.

2.02.02 Expended Polystyrene Blocks

The expanded polystyrene block Insulation shall be fire retardant quality and shall have a maximum thermal conductivity of 0.026 Kcl m/sq.m h °C. It must be strong enough to withstand without any deformation under the workload and standard loads expected on the roof.

The Contractor shall lay the expanded polystyrene block as per manufacturer's approved specification. Only specifically experienced workers shall be used for this work. If the Engineer is not satisfied about the efficiency of the workers the Contractor shall secure manufacturers supervision at no extra cost to the Owner.

2.03.00 Fillets

Fillets at Junction of roofs and vertical walls shall be provided with the same insulating material as provided for the main roof insulation. The fillets shall be 150 mm x 150 mm in size unless otherwise shown on drawings or instructed by the Engineer.

Where there is no insulation over roof slab, fillets shall be cast-in-situ cement concrete (1:2:4) nominal mix volume.

2.04.00 Waterproofing Treatment

2.04.01 Bitumen Felt Treatment

Waterproofing treatment shall be laid by a specialist firm with long experience in the particular trade.

The waterproofing treatment for roofs with bitumen felts shall be done following relevant IS: 1346. Bitumen felt shall conform to IS: 1322 and Bitumen primer to IS: 3384.

The bonding materials shall consist of blown type conforming to IS: 702 or residual bitumen conforming to IS: 73 or a mixture of the two to withstand local conditions of prevailing temperature or gradient of roof surface. The Contractor shall convince the Engineer that the bonding material proposed to be used is suitable for the particular job.

The Contractor shall state the source from where he proposed to procure the materials. Samples of the self-finished felt shall be submitted in advance to the Engineer along with test certificates for his review. Test certificates for the bonding materials shall also be submitted and samples, if desired by the Engineer, shall be provided for confirmatory tests. Samples shall be submitted if instructed by the Engineer.

Minimum overlaps of 100 and 75 mm shall be given at the end and sides of strips of felt and properly bonded with bitumen. Joints in successive layers of felt shall be staggered.

Normal treatment with one layer of felt, heavy treatment with two layers of felt or Extra Heavy treatment with three layers of felt shall be indicated. Brief details of the various treatments shall be as follows:

a) Normal Treatment - Five courses

1) Primer coat conforming to IS:3384 applied at the rate 0.27lits/sqm min.

2) Hot applied bitumen at the rate of 1.2 kg/sq.m. (min.)

3) Hessian base self-finished felt, type 3, grade 1.

4) Hot applied bitumen at the rate of 1.2 kg/sq.m. (min.)

5) 20 mm thick pressed precast concrete tiles with 15 mm, thick 1:4 cement-sand mortar underbed.

b) Heavy Treatment - Seven Courses

With Hessian base felt

1) Primer coat conforming to IS:3384 applied at the rate 0.27lits/sqm min.

2) Hot applied bitumen at the rate of 1.2 kg/sq.m (Min.)

3) Hessian base self-finished felt, type 3, grade 1.

4) Hot applied bitumen at the rate of 1.2 kg/sq.m (Min.)

5) Hessian base self-finished felt, type 3, grade I.

6) Hot applied bitumen at the rate of 1.2 kg/sq.m (Min.)

7) 20 mm thick pressed precast concrete tiles with 15 mm thick 1:4 cement: sand mortar underbed.

or

With fibre base felt

1) Primer coat conforming to IS:3384 applied at the rate 0.27lits/sqm min.

2) Not applied bitumen at the rate of 1.2 kg/sq.m (Min.)

3) Fibre base self-finished felt, type 2, grade 2.

4) Hot applied bitumen at the rate of 1.2 kg/sq.m (Min.)

5) Fibre base self-finished felt, type 2, grade 2.

6) Hot applied bitumen at the rate of 1.2 kg/sq.m (Min.)

7) 20 mm thick pressed precast concrete tiles with 15 mm thick 1:4 cement: sand mortar underbed.

c) Extra Heavy Treatment – Nine courses

With fibre based felt

1) Primer coat conforming to IS:3384 applied at the rate 0.27lits/sqm min.

2) Hot applied bitumen at the rate of 1.2 kg/sqm. (min.)

3) Fibre-base self-finished felt type 2, grade 1.

4) Hot applied bitumen at the rate of 1.2 kg/sq.m (min.)

5) Fibre base self-finished felt type 2, grade 1.

6) Hot applied bitumen at the rate of 1.2 kg/sqm. (min.)

7) Fibre base self-finished felt type 2, grade 1.

8) Hot applied bitumen at the rate of 1.2 kg/sqm. (min.)

9) 20 mm thick pressed precast concrete tiles with 15 mm thick 1:4 cement: sand mortar underbed.

or

With Hessian base felt

1) Primer coat conforming to IS:3384 applied at the rate 0.27lits/sqm min.

2) Hot applied bitumen at the rate of 1.2 kg/sqm. (min.)

3) Hessian base self-finished felt, type 3, grade 1.

4) Hot applied bitumen at the rate of 1.2 kg/sqm. (min.)

5) Hessian base self-finished felt, type 3, grade 1.

6) Hot applied bitumen at the rate of 1.2 kg/sqm. min.

7) Hessian base self-finished felt, type 3, grade 1.

8) Hot applied bitumen at the rate of 1.2 kg/sqm. min.

9) 20 mm thick pressed precast concrete tiles with 15 thick 1:4 cement: sand mortar underbed.

However, in special cases, more courses, or a combination of fibre base and hessian base felts may be asked for.

The surface to receive the waterproofing treatment must be cleaned and dried satisfactorily and the Engineer's approval taken before starting the work. If any existing waterproofing treatment is being augmented the existing top course shall be completely removed and all damaged felts or other defects repaired.

The Engineer may instruct the Contractor to lay part of the stipulated courses at the first instant to be followed later on with the balance courses. This interim finish shall be done with a course of hot applied bitumen. While doing the balance again hot bitumen shall be applied to start with after repair of all damages to the already laid course.

After completion the surface shall be cleaned taking care that felt cuttings etc. do not find their way into rainwater down comers.

2.04.02 Elastomeric Membrane

a) Material

The material shall consist of high solid content Polyurethane based cold liquid applied coatings as per ASTMC 836-89a comprising of urethane pre-polymers extended with flexible material, which cure by reaction with atmospheric moisture to give a continuous film which is rubbery and elastic or any other equivalent material permitted as per ASTM and approved by the Engineer. The material shall consist of high solid coating designed to give a high-build film. The material shall not be diluted. The coating shall have physical feature like high viscosity, 90% solids, high resistance to impact, abrasion and cracking, superior tensile strength, application limit of 70^0C minimum, 300%

elongation and forming a perfectly smooth permanently flexible seamless membrane which should have good adhesion to roof substrates (RCC, tiles, brick, and metals), having a minimum life of 10 years. It should also be resistant to acid (mild concentrated), alkali and have a very low water absorption rate (0.5%) max. at ambient temp. after 7 days.

The pack shall not be older than 9 months after the date of manufacture and packing.

b) Primer coat

It shall consist of polyurethane (P.U.) or any other equivalent material. Primer coat shall be a special blend of moisture curing urethane pre-polymers in solvent. A single coat of this primer shall be applied by brush over the prepared bed as an adhesion coat of an application rate of minimum 6 sq.m per litre.

The primer shall be allowed to dry for minimum of 2hrs. time before the successive finishing coats of P.U. liquid membrane is applied.

c) Finishing coats:

The finishing coats shall consist of two successive liquid coatings of high solids content urethane pre-polymers or equivalent material to form an elastomeric membrane. The overall dry film thickness shall be 1.5mm subject to minimum 500 gm per sq.m per coat application rate.

Each coat shall be allowed to dry for minimum 12 hours before applying the next coat. The surface should be dry and smooth before application.

The coating shall be continued up the parapets/walls for a minimum of 150mm over the finished roof surface. It shall be continued into rain water pipes by atleast 100mm.

The final coat of P.U. liquid when tacky shall be sprinkled with the sand.

For edges, expansion joints and any vulnerable points a later of polyscrim cloth /fabric to be embedded between 2 finishing coats.

d) Surface Finish:

Areas of roof treatment which are vulnerable to accidental damage shall be provided with wearing course consist of minimum 20 mm thick PCC of Grade M15 (using12.5mm size aggregate) cast in panel of maximum size of 1.20m x 1.20m and reinforced with 0.56mm diameter galvanised chicken wire mesh

and sealing of joints using sealant or elastomeric compound.

When the roof surface is subjected to foot traffic or used as a working area, a cement mortar (1:4) shall be applied over the top most layer of roofing treatment. Over this, a layer of chequered cement concrete flooring tiles conforming to IS:13801 shall be provided in place of stone grit and cement painted. The tiles shall be laid as per IS:1443.

2.04.03 Waterproofing by Epoxy Resin Based Application

Exposed surfaces of cement concrete, lime concrete or brickwork to be treated for waterproofing by the resin-based application shall be thoroughly cleaned and the epoxy resin based material to be applied as directed by the manufacturer. The material shall not have any adverse effect on the surface on which it is applied and must stick to it uniformly to make a strong durable bond. It shall not be affected by short duration fire, sun exposure, and light duty traffic. The application shall be resistant to growth of fungus and proof against saltpetre action. If desired by the Engineer, a sample shall be prepared in advance and tested for waterproofness for 48 hours under 300 mm depth of standing water. The Contractor shall arrange the demonstration by providing free the materials and labour for the application as free of cost to Owner. This item shall carry a guarantee as specified.

2.04.02 Flashing

Unless otherwise stated flashing shall be done in the same way as the waterproofing except that the last layer shall be finished with two coats of bituminous primer. The flashing shall be extended up the vertical surfaces as shown on drawing. The flashing shall end in grooves in vertical walls. The grooves shall be at least 65 mm deep and caulked with waterproof mastic cement. The minimum overlap with horizontal roofing felt shall be 100 mm.

Where specified or directed by the Engineer, metal flashing shall be provided. The materials shall be 18 Gage or 22 G G.I. sheets, as specified or as directed by the Engineer.

2.05.00 WATER-PROOFING OF UNDERGROUND STRUCTURES

Basements, ducts, pits, tunnels (excluding tanks) etc below the ground water table and in contact with soil are covered under this. Bonding material shall be blown bitumen of 65/25 grade conforming to IS: 702.

Waterproofing shall be provided on the outside of walls and top of RCC slab and shall be carried out upto 150mm above ground level. The number of layers of bitumen felt to be used for walls and floor unless otherwise shown in the drawing shall be:

a) 2 layers - for depths up to 5m below ground level

b) 3 layers - for depths beyond 5m below ground level

2.05.01 Method of laying the bitumen felts and workmanship shall be as per IS: 1609 and IS: 3067. Water proofing work shall be taken in hand only when the sub-soil water level is at its lowest; the site shall be kept dry by adequate arrangements for pumping out water till the work has been completed.

For this purpose, drains shall be formed along the edges of the excavation but beyond the building line, with suitable collecting sumps.

In case of large excavation areas where it is necessary to dewater under the floor, additional land drains shall be formed across the excavation, to adequately drain the area.

Adequate arrangement shall be made to protect the sides of excavation from slipping while the work is in progress.

The base concrete or mud-mat shall be rendered smooth by a 20mm thick sand-cement plaster (6:1). Any sharp edges/corners, over which the waterproofing course is to be laid, shall be eased out by means of cement.

The surface must be dry before the next operation is carried out.

Water proofing/damp proofing treatment:

A) Heavy Treatment (Two layers of felt)

i) Primer (For vertical faces only), as per I.S. 3384.

ii) Hot applied blown bitumen at the rate of 1.2 Kg/m2

iii) Hessian base, bitumen felt type 3 grades 2

iv) Hot applied blown bitumen @ 1.2 Kg/m2

v) Hessian base, bitumen felt type 3 grade 2

vi) Hot applied blown bitumen @ 1.2 Kg/m2

B) Extra Heavy treatment (Three layers of felt)

i) Primer (for vertical faces only) as per I.S. 3384

ii) Hot applied bitumen at the rate of 1.2 Kg/m2

iii) Hessian base bitumen felt type 3 grades 2

iv) Hot applied bitumen at the rate 1.2 Kg/m2

v) Hessian base bitumen felt type 3 grades 2

vi) Hot applied bitumen at the rate of 1.2 Kg/m2

vii) Hessian base bitumen felt type 3 grades 2

viii) Hot applied bitumen at the rate of 1.2 Kg/m2

The surface must be dry before the next operation is carried out at each stage said above.

The laying of felt over the bitumen so applied that it shall always commence on the floor, and shall be carried over to the walls only after treatment of the floor is complete. The minimum over lapping at sides and ends of strips shall be 10cm. Point for subsequent layers completely sealed by blow lamp.

A protective flooring of either brick flat in cement mortar (1:3) or 6cm thick cement concrete (M 15) or a coat of cement plaster (1:3) 4 cm thick shall be constructed over the bitumen layers to prevent damage to the latter during subsequent construction of the structural floor.

The walls shall be treated in a similar way; the bitumen felts joining at the base with the projecting felt laid over the mud-mat. The wall surface shall be made smooth where necessary with a coat of cement plaster (1:3), the felts laid as for the floor, ensuring that the surface to be treated is dry and then a protective brick wall, 12.5 cm nominal thickness shall be built in cement mortar (1:3) over the projecting mud-mat, the space between the wall and felt being grouted with cement.

3.00.00 ACCEPTANCE CRITERIA AND GUARANTEE

The surface level shall be such as to allow quick draining of rains without leaving any pool anywhere. The finishing course shall be fully secured and shall have an even density. There shall not be any bubble formation or crushed or squeezed insulation or underbed.

The contractor shall give a guarantee in writing for all works executed under this specification supplemented by a separate and unilateral guarantee from the specified agency for the roof waterproofing treatment work. The guarantee shall be for materials and workmanship as under:

For Bitumen Felt Treatment under clause no. 2.04.01: 5 years in case of normal treatment, 10 years for heavy treatment and 20 years for extra heavy treatment.

For Elastomeric Membrane under clause no. 2.04.02: 10 (ten) years.

In case guarantee is more stringent in owner specification, more stringent guarantee shall be applicable. The mode of execution of the guarantee shall be such, which shall be acceptable to the Owner.

4.00.00 I.S. CODES AND STANDARDS

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

a)	IS: 73	-	Paving Bitumen
b)	IS: 702	-	Industrial Bitumen
c)	IS: 1203	-	Methods of testing tar and bitumen
d)	IS: 1322	-	Bitumen felts for waterproofing and damp proofing.
e)	IS: 1346	-	Code of practice for waterproofing of roofs with bitumen felts.
f)	IS: 1609	-	Damp-proofing Treatment using Bitumen Felts – Code of Practice
g)	IS: 3067	-	Code of practice for General design details and preparatory work for Damp-proofing and water-proofing of buildings
h)	IS: 3384	-	Bitumen primer for use in waterproofing and damp proofing.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall be for complete work, including the cost of all materials and labor, as detailed in the specification unless any portion is specifically excluded in the "Schedule of Items".

No extra shall be paid for finishing around opening, sleeves, pipes, ducts, inserts, etc.

No separate payments shall be made for cleaning of surface, treating of cracks and surface preparation.

5.02.00 Measurement

The finished work shall be measured in Sqm of actual surface area for the purpose of payment.

No deduction shall be made and no extra shall be paid for openings upto 0.4 sqm.

VOLUME: II B

SECTION - D

SUB-SECTION – D5

METAL DOORS, WINDOWS, VENTILATORS, LOUVERS ETC.

SPECIFICATION NO. PE-TS-999-600-C005

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	3
3.00.00	ACCEPTANCE CRITERIA	8
4.00.00	INFORMATION TO BE SUBMITTED	9
5.00.00	I.S. CODES	10
6.00.00	RATES AND MEASUREMENTS	10

ATTACHMENT

ANNEXURE – A	SCHEDULE OF FIXTURES	12

METAL DOORS, WINDOWS, VENTILATORS, LOUVERS ETC.

1.00.00 SCOPE

This section covers supplying and/or erecting and installing of all metal doors, windows, ventilators, louvers, glazed partitions, etc. The scope of work shall also include the assembly and erection of all doors, windows, louvers, glazed partitions, etc. Supplying and/or fixing of all door and window accessories and hardware are also included in the scope.

2.00.00 INSTALLATION

2.01.00 Materials

Steel sections used for fabrication of doors, windows etc. shall be standard rolled steel sections specified in IS: 1038 and IS: 1361 or as specified.

Steel sheets for frames, shutters, louver blades etc. shall be of gauge mentioned in drawings and schedules.

Aluminium sections for fabricating doors, windows, partitions etc. shall be extruded sections conforming to IS:733 or IS:1285 or as manufactured by Indian Aluminium Company Limited or approved equivalent. Aluminium door, windows and ventilator shall be fabricated as per IS:1948 and IS:1949. The alloy used shall conform to IS Designation HE 9-WP of IS: 733.

Hardware and fixtures shall be as specified and the best quality from approved manufacturers shall only be used. The tenderer shall specifically state the particular manufacturer's materials he proposes to use. Improper alignment or faulty operation due to inadequate strength of hardware or fixture shall entirely be the Contractor's responsibility.

All hardware and fixtures shall be able to withstand repeated use. Door closures shall conform to IS: 3564 and shall be suitable for doors weighing 61-80 Kg. unless otherwise stated. Each closer shall be guaranteed against manufacturing defect for one year and any defect found within this period shall be rectified or shall be replaced free of charge. Concealed door closers shall be either floor mounted or transom mounted, suitable for installation with metal doors. It shall conform to the performance Requirements and endurance test stated in IS: 3564 - Appendix-A. The Contractor shall submit samples of each type of hardware to the Engineer. The approved samples shall be retained by the Engineer for comparison of bulk supply. The samples shall be returned to the Contractor towards end for incorporation in the job. The mastic for caulking shall be of best quality from a manufacturer approved by, the Engineer. In general, mastic for fixing of metals frames shall be as per IS: 1081 or as approved by the Engineer.

2.02.00 Fabrication

2.02.01 Steel Doors, Windows, Ventilators, louvers etc.

a) Door Frames

Frames shall be fabricated from 16 gage(G) sheets. They shall, be mortised, reinforced, drilled, and tapped for hinge lock and bolt strikes. Where necessary, frames shall be reinforced for door closers. Welded construction with mitered Corners shall be used. Rubber door silencers shall be furnished for the striking jamb. Loose "T" masonry anchors shall be provided. Frames shall finish flush with floor and adjustable floor anchors shall be installed. Frames shall be brought to site with floor ties/weather bars installed in, place.

b) Double Plate Flush Door Shutters

Door shutters shall be 45 mm thick, completely flush design and shall comprise of the outer sheets or 18 G steel sheets, rigidly connected and reinforced inside with continuous vertical 20 G stiffeners, spot welded in position at not more than 150 mm on centres.

Both edges of doors shall be joined and reinforced full height by steel channels placed immediately inside and welded to the door faces. Top and bottom of doors shall be reinforced horizontally as shown on drawing by steel channels running full width of door. Doors shall not have more than 2.5 mm clearance at jambs and heads, shall have proper level on lock stiles and rails to operate without binding, and shall be reinforced at corners to prevent sagging or twisting. Pairs or double doors shall have meeting-stile edges bevelled or rebated. Where shown on drawing, or called for in the schedule of items, the doors shall be sound deadened by filling the inside voids with mineral wool or other suitable approved materials.

Doors shall be mortised, reinforced, drilled, and tapped in shop for hinges, locks, and bolts. They shall also be reinforced for closers, push-plates, and other surface hardware's where necessary. Any drilling and tapping required for surface hardware shall be done at site. Where shown drawing, provision shall be made for fixing glazing, vision panels, louvers etc. glazing mouldings shall be of 18 G steel or extruded aluminium sections and suitable for fixing 6 mm. glass. Louvers blades shall be V or Z shaped and made out of 16 G sheets.

c) Single Sheet Door Shutters

Single sheet doors shall be made from best quality 18 G mild steel sheets, and shall present a flush surface on the outside. The inside shall be stiffened with semi tubular edge and central stiffening rail, which shall convey the lock and other fixture. The frames shall be made from best quality, 16 G mild steel sheets.

Wherever required, provisions for fixing glass panes, louvers etc. shall be made.

The manufacturing shall be done as specified in 2.02.01 (b) “Double Plate Flush Door Shutters.”

d) Sliding Door

Sliding doors shall be either double plate or single plate Construction made out of 18-gauge steel sheets with adequate stiffeners. The contractor shall specify the weight of the door in his shop and submit the manufacturer's catalogue of the sliding gear he proposes to use. Where called for the Contractor shall make provision for openings to the door for monorail beams. Doors shall close positively to exclude rainwater from seeping in. When called for, sliding doors shall withstand specified wind loads without buckling or jamming. The door shall slide freely under all ambient conditions.

e) Door Threshold

Door threshold shall be provided. Doors without threshold shall have bottom tie of approved type.

f) Steel Windows, Sashes, and Ventilators etc.

These shall conform in all respects to IS: 1038 and IS: 1361 latest editions. The details as called for in the above codes shall be applicable for coupling mullions, transoms, weather bars, and pivot arrangements for ventilators, etc. or as called for. All welds shall be dressed flush on all exposed and contact surfaces. Where composite unit openings are required the individual window units shall be joined together with requisite transoms and mullions. All windows shall be outside glazed, fixed with putty or metal glazing beads as specified. Where aluminium glazing beads are specified, they shall be extruded aluminium channel 9.5 mm x 9.5 mm x 1.6 mm (Jindal Section No. 2209) unless otherwise shown on drawings. Aluminium beads shall be given one coat of zinc chromate primer before fixing to windows.

2.02.02 Aluminium Door, Windows, and Frames

Extruded sections shall have a minimum 3 mm wall thickness. All sections shall be approved by the Engineer before fabrication is taken up. Doors frames, mullions, transom etc. shall be anodized in a bath of sulphuric acid to provide a clear coating of minimum 15-micron thickness. The anodized materials shall then be sealed by immersing in boiling water for 15 minutes. A protective transparent Coating shall be applied to the sections before shipment from the factory.

All work shall be fitted and shop assembled to a first class job, and ready for erection. Shop joints shall be made to hair lines and then welded or braced by such method as will produce a uniform colour throughout the work. Work on the above, other than described, shall be carefully fitted and assembled with neat joints with concealed fasteners. Wherever possible, joints shall be made in concealed locations and on edges of doors. Field connections of all work may be made with concealed screws or other approved type of fasteners. Glazing beads shall be snap fit type without visible screws and shall be of sizes to accommodate 6 mm thick glazing. All work shall be adequately braced and reinforced as necessary for strength and rigidity.

2.03.00 Shop Coat or Paint

The shop Paint for steel doors, windows etc. shall be best lead or zinc chromate primer paint from, approved manufacturer. All surfaces shall be thoroughly cleaned of rust, grease, loose mill scales etc. and given one coat of shop paint. Portions like mullions, transoms etc. that will be inaccessible after assembly of units shall be given an extra coat of paint before assembly.

Where called for, all steel doors, windows, etc. shall be hot dip galvanized to give a coating weight of 1½ - 2 oz. per sqft. One coat zinc chromate primer coat shall then be applied as shop paint.

Portions of aluminium frame, which come in contact with masonry construction shall be (before shipment from workshop) protected with a heavy coat of alkali resistant paint. Aluminium coming in contact with other incompatible metals shall be coated with zinc chromate primer.

2.04.00 Handling & Storage of Fabricated Material

All metal doors, windows, etc. shall be packed and crated properly before dispatch, to ensure that there will be no damage to the fabricated materials. Loading into wagons and trucks shall be done with all care to ensure safe arrival of materials at site in undamaged condition.

When taking delivery of items supplied by Owner, the Contractor shall satisfy himself that the items supplied are up to the specified standard. Any defect detected shall promptly be brought to the notice of the Engineer.

All metal doors, windows etc. shall be stored under cover in a way to prevent damage or distortion. Special care shall be taken to prevent staining of aluminium products by rust, mortar etc.

2.05.00 Assembly & Erection at Site

In general, the fixing of steel doors, windows, ventilators, louvers, etc. shall conform to IS: 1081. The Contractor shall assemble and install all steel doors, windows, sashes, fixed metal louvers, etc. including transoms and mullions for composite units in respective places, keening proper “Lines and levels”, and in approved workmanlike manner, to give trouble free and leak-proof installations. Installation shall be done according to instructions of the manufacturer, and/or as approved by the Engineer. If required by the Engineer, the installation shall have to be carried out under the supervision of the manufacturer's staff. The Contractor shall take all precaution against damage of the components during installation. Necessary holes, chases, etc. required for fixing shall be made by the Contractor and made good again as per original, after installation, without any extra charge.

After installation of steel doors, windows, etc. all abrasions to shop-coat of paint shall be retouched and made good the same quality of paint used in shop coat.

All coupling mullions, transoms, frames, etc. in contact with adjacent steel and other members, shall be well bedded in mastic. The Contractor shall bring to the site the cement in original sealed containers of manufacturer and shall apply it as per the instruction. For all frames supplied by either the owner or the Contractor, mastic shall be supplied by the Contractor and caulking done properly as per drawings, specifications and as per instructions of the Engineer.

Door shutters, partitions hardware fixtures etc. shall be fixed only after major equipments have been installed in rooms.

Wherever required, nylon cords of approved quality shall be supplied along with pivoted sashes and shall be of adequate length to terminate one meters from the floor. Loose ends of cords shall end in metal or plastic pull as approved by the Engineer.

2.06.0 Fire proof Door

Fire proof doors shall be provided at all fire exit points as specified and also to restrict the spread of fire within buildings whether from internal fire or from external fire. The construction details of door shall conform to the requirements stipulated in IS:3614 (Part-1). Doors shall comply with the testing requirement mentioned in IS:3614 (Part-2). The doors shall be approved by Tariff Advisory Committee and shall have minimum 2 hrs. fire rating.

Metal covered (on both sides) Doors having insulating core filled up with mineral wool shall be used at all fire exit points and shall open outside.

All necessary accessories and hardware shall also be supplied along with doors. Fire proof door shall be provided with zinc silicate primer (minimum DFT 75 micron) after blast cleaning the surface to near white metal surface and shall be finished painted with epoxy based painting.

3.00.00 ACCEPTANCE CRITERIA

3.01.00 For fabricated Items

a) Overall dimensions shall be within ±1.5 mm of the size shown on drawings.

b) Mullions, transoms etc. shall be in one length and permissible deviations from straightness shall be limited to ±1.5 mm from the axis of the member.

c) Door and window shutters shall operate without jamming. The clearance at head and jamb for door shutters shall not exceed 1.5 mm for double leaf doors; the gap at the meeting stiles shall not be more than 1.5 mm.

d) Door leaves shall be undercut where shown on drawings.

e) Doors, windows, frames, etc. shall be on a true plane, free from warp or buckle.

f) All welds shall be dressed flush on exposed and contact surfaces.

g) Correctness of location and smoothness of operations of all shop installed hardware and fixtures

h) Provision for hardware and fixtures to be installed at site.

i) Glazing beads shall be cut with mitered corners.

j) Glazing clips, fixing devices etc. shall be supplied in adequate numbers.

k) Shop coats shall be properly applied.

l) Exposed aluminum surfaces shall be free from scratches, stains, and discoloration. Anodized surfaces shall present a uniform and pleasing look.

3.02.00 For installed Items

a) Installations shall be at correct location, elevation and in general, on a true vertical plane.

b) Fixing details shall be strictly as shown on drawings.

c) Assembly of composite units shall be strictly, as per drawings with mastic caulking of transoms and mullions, gaskets, weather strips etc. complete.

d) All frames on external walls shall be mastic caulked to prevent leakage through joint between frames and masonry.

e) All openable section shall operate smoothly without jamming.

f) Locks, fasteners etc. shall be engage positively. Key shall, be non-interchangeable.

g) Cutting to concrete or masonry shall be made good and all abrasions to shop paint shall be touched up with paint of same quality as shop paint.

h) Aluminium doors, windows, etc. shall be free from scratches stain or discoloration.

4.00.00 INFORMATION TO BE SUBMITTED

4.01.00 With Tender

a) Names of manufacturers for Doors, windows etc.

b) Manufacturer's catalogue for all hardware and fixtures proposed to be used.

4.02.00 After Award

a) Before starting fabrication of all metal doors, windows, etc. the Contractor shall submit detailed fabrication drawings to the Engineer for approval. The fabrication shall be started only after approval of drawings.

b) He shall submit a programme of work to be done for the approval of the Engineer.

c) Before bulk supply, he shall submit for the approval of the Engineer samples of all bought out items and samples of each type of fabricated items. The samples shall by retained by the Engineer for comparison of bulk supply and returned to the Contractor towards the end for final incorporation in the job.

5.00.00 IS CODES

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

Specification for Wrought Aluminium and Aluminium Alloy bars, rods and sections (for general engineering purpose)	-	IS: 733
Specification for Wrought Aluminium and Aluminium Alloy, extruded round tube, hollow section (for general engineering purpose)	-	IS: 1285
Steel doors, windows, and ventilators	-	IS: 1038
Steel windows for industrial, building	-	IS: 1361
Aluminium doors windows, and ventilators	-	IS: 1948
Aluminium windows for industrial buildings	-	IS: 1949
Steel doorframes	-	IS: 4351
Code of practice for fixing and glazing of Metal (steel and aluminium) doors, windows and Ventilators.	-	IS: 1081
Specification for Fire-check Doors – Part 1: Plate, Metal covered and Rolling type	-	IS: 3614
Hot Rolled Steel Sections for Doors, Windows and Ventilators – Specification	-	IS: 7452

6.00.00 RATES AND MEASUREMENT

6.01.00 Rates

Rates shall be applicable of all elevation. Rates shall include preparation of working drawings (if required), supply of material, fixtures, gaskets, erection of unit, caulking and jamming of frames, including cutting/drilling/welding, grouting, grinding, making good of the structure for installing the unit etc. complete as per “Schedule of Items”.

Rates shall also include cost of surface preparation, application of primer, enamel painting or anodizing as applicable.

Rate for fire proof door is inclusive of providing insulation core, primer, shop painting (epoxy based), all hardware as specified in Schedule of items.

6.02.00 Measurement

Supply and installation of doors, windows, and ventilators shall be measured in Sqm or Kg as per BOQ item. If measured in sqm, it shall be for net outer to outer (excluding frame) area of doors, windows, and ventilators of each type used as described in “Schedule of Items”. Frame for steel or aluminum shall be measured in Kgs. Wooden frames shall be measured in Cum. Measurement for aluminum partition frames shall be in Kg. Paneling and glazing shall be paid separately if not covered in BOQ item description.

Measurement for fire proof door shall be in Sqm in net area outer to outer of the door.

ANNEXURE-A

SCHEDULE OF FIXTURES

A. TIMBER DOORS

1. For single leaf panel/flush doors

   i) 100 mm brass butt hinges with screws - 3 Nos.

   ii) 150 mm brass tower bolts with screws - 1 No.

   iii) 100 mm x 225 mm clear plastic push Plate with counter sunk brass screws - 1 No.

   iv) 30 mm brass ring pull handle with Plates and screws - 1 No.

   v) 150 mm brass coat hook with screws - 1 No.

   vi) Heavy duty, cylinder looks on active leaf - for flush door. For door-closure, see "Door Schedule".

B. ALUMINIUM DOORS

1. For double leaf door

   i) Concealed hanging arrangement for door leaves.

   ii) Concealed two points bolt encasing simultaneously at head and threshold on inactive leaf, operable from inside.

   iii) Heavy duty, cylinder look on active leaf.

   iv) Pull handle of approved design on both leaves.

   v) Doors stops for both leaves.

   vi) Overhead door closure for both leaves.

ANNEXURE-A

C. STEEL DOORS AND WINDOWS

1. Doors

a) Double leaf doors

i)	100 mm butt hinges	- 3 Nos. on each leaf.
ii)	300 mm aluminum tower bolt	- 2 Nos. (top and bottom) On inside of inactive Leaf. 1. No. (Top only) On inside active leaf.
iii)	200 mm anodized aluminum pull handle	- 1 No. of each leaf.
iv)	Door stop of approved design	- 1 No. of each leaf.

NOTE: For locks, door closure and threshold, see "Door Schedule".

b) Single leaf doors

i)	100 mm butt hinges	- 3 Nos.
ii)	300 mm aluminum tower bolt	- 2 Nos. top & bottom of Inside face
iii)	200mm anodised aluminum Pull handle	- 1 No.
iv)	Door stop of approved design	- 1 No.

NOTE: For locks, door closures and threshold, see “Door Schedule".

2. Windows, Ventilators, etc.

a) Side Hung Windows

i)	Hinges	- As per standard Practice of the Manufacturer, but minimum two hinges Per leaf.
ii)	12" peg stays	- 1 No. per leaf

iii) 2 point handles - 1 No. per leaf

b) Top Hung Ventilators (Projecting Out)

i) Hinges - As per standard Practice of the Manufacturer, but minimum two hinges Per leaf.

ii) Adjustable sliding fabrication assembles - 2 Nos. per leaf.

iii) 2 point handles - 1 No. per leaf.

c) Bottom Hung Ventilators (Projecting in)

i) Hinges - As per standard Practice of the Manufacturer, but minimum two hinges Per leaf.

ii) Concealed side arms for opening adjustment. - 2 Nos. per leaf.

iii) Spring Catch - 1 No. per leaf.

ANNEXURE-A

D. ALUMINIUM WINDOW, VENTILATORS, ETC.
(As per IS-1948 latest editions)

a) Side Hung Windows

i) Hinges - As per standard Practice of the Manufacturer, but minimum two hinges Per leaf.

ii) 300 mm peg stays - 1 No per leaf

iii) 2 point handles - 1 No per leaf

b) Top Hung Ventilators (Projecting out)

i) Hinges - As per standard Practice of the Manufacturer, but minimum two hinges Per leaf.

ii) Adjustable sliding fabrication assembles - 2 Nos. per leaf

iii) 2 Point handles - 1 No. per leaf

c) Bottom Hung Ventilation & (Projecting In)

i) Hinges - As per standard Practice of the Manufacturer, but minimum two hinges Per leaf.

ii) Concealed side arms for opening adjustment - 2 Nos. per leaf

iii) Spring Catch - 1 No. per leaf

VOLUME: II B

SECTION - D

SUB-SECTION – D6

GLASS AND GLAZING

SPECIFICATION NO. PE-TS-999-600-C006

Maharatna Company

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	3
3.00.00	ACCEPTANCE CRITERIA	4
4.00.00	I.S. CODES	4
5.00.00	RATES	5

GLASS AND GLAZING

1.00.00 SCOPE

This section covers supplying and fixing of all glass and glazing including all clips, putty, mastic cement etc. wherever required as per specifications.

2.00.00 INSTALLATION

2.01.00 General

The Contractor shall supply and install all glass and glazing as required for various doors, windows, sashes, ventilators and fixed louvers, miscellaneous glazing and partitions, from approved manufacturer like Hindustan Pilkinton or equivalent, having uniform refractive index and free from flaws, specks, and bubbles. The glass shall be brought to site in the original packing from the manufacturer and cut to size at site.

Materials:

a) Glare reducing or beat absorbing glass shall be "Calorex" of Hindustan Pilkinton or approved equivalent and special care shall be taken to grind smooth and round off the edges before fixing.

b) Clear glass shall be flat draw sheet glass and shall be at least 4 mm thick. Sheet glass for doors shall be minimum 5.5 mm thick.

c) Wired glass shall be thick- rolled glass with centrally embedded 42g wire mesh of Georgian type. This may be of clear or coloured glass, as required.

d) Obscure glasses shall have a cast surface in one side.

e) Coloured and figured glass shall be as per approved sample.

f) In general, the putty shall conform to IS: 400 and be of best quality from approved manufacturer. It shall be brought to site in the manufacturer's original packing.

g) Neoprene gaskets with snap-fit glazing beads shall be fixed as per manufacturer's instructions and shall sit snugly against glass to give a leak proof installation.

2.03.00 Glazing, Setting, and Finish

All glazing clips, bolts, nuts, putty, mastic cement etc. as required shall be supplied by the Contractor.

All glass shall be thoroughly cleaned before putting in position. Each glass pane shall be held in place by special glazing clips of approved type. As specified in relevant I.S. Codes, four glazing chips shall be provided per glass pane, except for large panes were six or more clips shall be used as per engineer's instructions. All holes that may be necessary for holding the clips glazing heads and all other attachments shall be drilled by, the Contractor.

Glass panes shall be set without springing, and shall be bedded in putty and back puttied, except where mouldings or gasket are specified, putty, mastic cement etc. shall be smoothly finished to the even line and figured glass shall be set with smooth side out.

Where owner will supply glass, the Contractor shall cut it to size and fix them in the same as specified above.

The Contractor shall supply necessary glazing clips, putty, mastic cement etc.

After completion of glazing, the Contractor shall remove all dirt stains, excess putty etc. clean glass panes and leave the work in perfectly acceptable condition. All broken cracked or damaged glass shall be replaced by new ones at the contractor’s own cost.

3.00.00 ACCEPTANCE CRITERIA

a) All installation shall be free from cracked, broken, or damaged glass. Edges of large panes of thicker glass and heat absorbing glass shall be inspected carefully for chipped, cracked, or underground edges.

b) Glazing shall be carefully done to avoid direct contact with metal frames.

c) All glass shall be embedded in mastic or fixed by neoprene gaskets to give a leak proof installation.

d) At completion, the panes shall be free from dirt, stains, excess putty etc. to the complete satisfaction of the Engineer.

4.00.00 I.S. CODES

Following are some of the important I.S. Codes relevant to this Section:

IS: 3548 - Code of practice for glazing in building.

IS: 1081 - Code of practice' for fixing and glazing metal doors, windows ventilators.

5.00.00 RATES

Rates of glass and glazing if not included in respective items for supply and installation of window, ventilator, and partitions shall be paid separately as per BOQ items provided. No separate payment shall be made for glazing clips, mastic cement, putty, screws; rails, etc. nor for drilling holes in frames for inserting glazing clips.

VOLUME: II B

SECTION - D

SUB-SECTION – D7

ROLLING STEEL SHUTTERS AND GRILLS

SPECIFICATION NO. PE-TS-999-600-C007

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	3
3.00.00	ACCEPTANCE CRITERIA & GUARANTEE	5
4.00.00	I.S. CODES	5
5.00.00	RATES AND MEASUREMENTS	5

ROLLING STEEL SHUTTERS AND GRILLS

1.00.00 SCOPE

This Section covers the design and supply of materials, fabrication, delivery and erection of Rolling Shutters/Grills with motor drive and/or manual operation including all accessories as hereinafter specified.

2.00.00 INSTALLATION

2.01.00 Components

a) Slats for rolling shutters shall be made from tested bright cold rolled, annealed M.S. strips, not less than 0.9 mm thick for shutters upto 4.5 M wide and not less than 1.25 mm thick for shutters having width more than 4.5 M, wide and above, machine rolled at 75 mm rolling centers, interlocking with each other. The profile will be such as to prevent excessive deflection under specified wind load.

b) Rolling grills shall be constructed out of 6mm rods at 35 mm on centers running horizontally flexible connected with vertical links spaced not more than 200 centers. Alternatively, rolling grills shall be made from perforated slats of approved design reinforced with 6mm dia. rods.

c) End locks shall be heavy type M.C.I./C.I. and shall be provided at each end of alternate slats unless specified otherwise.

d) Bottom bars shall be finished with two angles not less than 6 mm thick for external shutters. When shown on drawings, a flexible weather strip shall be applied to make tight contact with the floor.

e) Guides shall be of such depth as to retain the shutter under a wind pressure of 100 Kg/Sq.m.

f) Shafts shall be of steel pipe of sufficient size to carry the tensional load with a maximum deflection of 1/360th of span. Grease packed ball bearings or bushings shall be provided for smooth trouble free operation.

g) Hoods shall be formed of not less than 20-gauge steel, suitable reinforced to prevent sag.

h) Locks shall be slide bolt and hasp, or cylinder lock operable from one or both sides. Provision securing hand chain with pad-lock, provision for removable handle for hand cranks etc. shall be made as prescribed by the Engineer.

i) Power unit shall be suitable for 3 phase, 50 cycles, 400-volt A.C. power supply and be either floor or wall mounted unit. The motor shall be of sufficient capacity, to move the shutter in either direction at a speed of 0.3 metres per second. In addition to the gear motor each standard power unit shall include a magnetic brake, a reversing starter with built-in overload protection, a geared limit switch and one push button station located inside the building unless otherwise stated in drawing.

It is desirable that the bottom bar of motor operated doors shall be provided with a sensitive edge, electrically connected to stop the travel of the door on meeting an obstruction.

j) Operating chains shall be of tested quality, heavily galvanized and with all ends rounded to assure smooth operation and hand protection.

k) Reduction gears shall be high strength grey cast iron, machine moulded from machine out patterns.

2.02.00 Manually Operated Shutters/Grills

Manually operated shutters shall be easily operable by one person. The speed of operation shall be about 1.3 metres per second. In general, manually operated shutters shall be push pull type for opening up to 9 Sq. metre in area. Larger shutters shall, be either chain and gear operated or crank and gear operated. The crank handle shall be removable. All shutters shall be lockable from one or both sides as desired by the Engineer.

2.03.00 Power operated Shutters/Grills

These shall be operable from a push button station conveniently located beside the door. One emergency hand chain/crank operation shall also be provided for use in case of failure of the electric system. Where called for, externally mounted shutters shall be operated by control mechanism located inside the building.

2.04.00 Shop Coat

Shutters shall be painted with one coat of red lead or zinc chromate primer. Where specified, doors shall be galvanized and subsequently painted one coat of zinc chromate for adhesion of field coat.

2.05.00 Erection

Door shall be installed by the manufacturer or his authorized representative and all work shall be as per manufacturer's instructions. Any drilling or cutting to concrete, masonry etc. shall be made good after erection of shutters

and all abrasion to shop coat shall be touched up. All electrical work shall be in strict accordance with the latest Indian Electricity Rules.

3.00.00 ACCEPTANCE CRITERIA AND GUARANTEE

3.01.00 Shop Inspection

After completing the manufacture of the different components of the rolling shutter, an arrangement for shop inspection by the Engineer shall be made to check the conformity with approved shop drawings.

3.02.00 Field Inspection

After installing the shutters, the Contractor shall test the performance of the shutter in the presence of the Engineer. The doors shall be smoothly operable under all ambient conditions. All control and locking devices shall give fault free performance.

3.03.00 Guarantee

The Contractor shall give one year's guarantee for the successful operation of the shutters. This shall be supported by a separate and unilateral guarantee from the manufacturer of the shutters.

4.00.00 I.S. CODE

IS: 6248 - Metal rolling shutters and rolling grills.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates for rolling shutters and grill shall include the cost of the locks, guide channels, cost of drive as specified. In case of electrically operated rolling shutters, the rate shall also include the mounting of controls, wire and wiring from the nearest junction box, conduit and other electrical connections and cost of electric motor.

5.02.00 Measurement

Supply and installation of rolling shutter and grill shall be measured in Sqm in net outer to outer (including frame) area of each type used as described in “Schedule of Items”.

VOLUME: II B

SECTION - D

SUB-SECTION – D8

MISCELLANEOUS METAL

SPECIFICATION NO. PE-TS-999-600-C008

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	3
3.00.00	ACCEPTANCE CRITERIA	7
4.00.00	IS CODES	8
5.00.00	RATES AND MEASUREMENTS	8

MISCELLANEOUS METAL

1.00.00 SCOPE

This section covers supply, fabrication and erection of miscellaneous metal items of light nature in gates, balcony and stair hand rails, structural works, ladders, hangers, masonry anchors, anchor bolts, fasteners, chain link fencing, barbed wire fencing etc. as specified or shown on drawing or as instructed by the Engineer. The above items shall be of fabricated or cast of mild steel, aluminium, brass, cast iron, M.S.& galvanized M.S. sheets, aluminium sheets, expanded metal, wire mesh as shown on drawings or specified.

2.00.00 INSTALLATION

2.01.00 Fabrication/casting

2.01.01 General

All work shall be done according to approved shop drawings. All workmanship shall be equal to the best practice in modern structural or foundry shop.

2.01.02 Shop Connections

a) All shop connections shall be riveted or welded except when noted otherwise on drawings.

b) Welding of steel shall be done in accordance with IS: 816.

c) Welding of aluminium shall be done accordance with IS: 2812, “Arc welding of Aluminium and Alloys.” Special care shall be taken to grind smooth all welded surface that shall remain exposed to view. Welds shall be electrically continuous if so required by the Engineer.

2.01.03 Shop Coat

Before leaving the shop, all metal work shall be thoroughly cleaned by effective means of all loose mill seals, rust and foreign matter. Except where encased in concrete, all steelwork shall be given one coat of approved metal protective paint, applied be brush thoroughly and evenly, well worked into joints and other open spaces. All paint shall be applied to dry surfaces. When specified steel work shall be galvanised or painted with a coat of zinc chromate primer. Aluminium surfaces, which shall come in contact with masonry, shall be given one coat of bituminous paint.

2.02.00 Erection

2.02.01 Bracing

The Contractor shall provide all necessary temporary guys and braces to ensure alignment and stability of the members and to take care of all loads to which the structure may be subjected, including erection of equipment and operation of the same.

2.02.02 Temporary Bolting-Up

As erection proceeds the Contractor shall plum up and level all members and shall securely bolt up to take care of all dead load, wind load and erection stresses. Wherever erection equipment or other loads are carried by members during erection, proper provision shall be made to take care of the stresses resulting from the same.

2.02.03 Turned Bolt

For field connections where bolting is specified, holes for the turned bolts may be reamed in the field, if required. All drilling or reaming for turned bolts shall be done after the parts to be connected are assembled.

2.02.04 Welding

Where specified on drawings, welding shall be done in accordance with IS: 816 for steel and IS: 2812 for Aluminium & Alloys.

2.02.05 Cutting and Fitting

No cutting of sections, flanges, webs of angles shall be done without the approval of the Engineer. Where indicated on the drawings holes, cuttings, etc. shall be provided as required for installation, to the work by the other Contractors. No additional holes or cuttings, then those shown on drawings, shall be made without the approval of the Engineer.

2.02.06 Drifting

Correction minor misfits and a reasonable amount of reading and cutting of excess stock from rivets may be permitted. For this, light drifting may be allowed to draw holes together. Twist drills shall be used to enlarge as necessary to make connections, reaming that weakness the members or make it impossible to fill the holes properly or to adjust accurately after reaming shall not be allowed.

Any error in shop work which prevents the proper assembling and fitting of parts by moderate use of drift pins or a moderate amount or reaming and slight chipping and cutting shall immediately be called to the attention of the Engineer-and approval of the method of correction obtained. The use of cutting torches to enlarge or alter rivet holes shall not be permitted.

2.02.07 Spot Painting

All field rivets and bolts and also any serious abrasion to shop paint shall be spot painted with the same materials and used for the shop paint or equivalent.

2.02.08 Good

All cutting to concrete or masonry shall be made good to the satisfaction of the Engineer.

2.02.09 Grouting

All bearing plates, loose, lintels and beams, etc. shall be set to proper grade and level by the Contractor and the Engineer's approval obtained before proceeding with the grouting. Grouting shall be done in 1:1½:3 concrete with 6 mm down stone chips or as specified in schedule of items.

2.02.10 Anchor Fasteners

The anchor fasteners shall be of two type viz. light duty for carrying tensile load upto 0.5MT per fasteners and heavy duty for carrying tensile load of 0.5MT to 5.0MT per fasteners. These anchor fasteners shall be fixed into concrete. The Contractor shall submit the Manufacture's literature showing the average pull out and average shear value for anchor of various sizes. Anchors shall be fixed in position strictly as per the manufacturer's instructions and as approved by the Engineer.

Heavy Duty Anchor Fasteners

The safe tensile load carrying capacity of the anchors shall be arrived by providing the minimum factor of capacity of 2.5 for the characteristic load of the anchor. Minimum size of anchor shall be M8 (8mm). All anchors shall be from the approved manufacturers like HILTI or equivalent.

a) Anchor fasteners shall be supplied and fixed in position by the contractor. Anchor fasteners can be of mechanical bonding or chemical bonding.
b) Capacity of the anchor shall be established after considering the effect of concrete grade, embedment depth, concrete thickness, anchor spacing and edge distance from the concrete edge.

c) The selection for the particular type of bonding for the anchors shall be made after considering the concrete grade, available embedment depth, load to be transferred, space available for installing anchors.

d) The mechanical bonding anchor are torque controlled anchors made from carbon steel of grade 8.8 as per IS:1367 part 3. Anchors in bolt as well as nut version are acceptable. The bolt version anchors consist of bolt washer, sleeves, plastic section, expansion sleeves and a cone. Nuts version anchor consists of nuts, threaded rod, washer, sleeves, plastic section, expansion sleeves and a cone. All steel component of anchor shall be electro galvanised to minimum 5 micron coating thickness. The plastic section shall be of polyacetal Derlin 100 or equivalent.

e) Chemical bonding anchor shall consist of foil capsule and threaded rod. The foil capsule shall contain the resin and hardener. The threaded rod shall have chiselled tip. The behaviour of anchors under fire shall conform the heating curves as per ISO:834. Anchors of size M8 to M24 shall conform to grade 5.8 and anchors of size M27 to M39 shall conform to grade 8.8 as per IS:1367 part 3. All steel components of the anchors shall be electro-galvanised to minimum 5-micron thickness.

Light Duty Anchors

This anchor shall comprise of stud, nut, washers, expansion sleeve. The one end of the stud shall have thread and the other end shall have cold formed conical head. All steel components of the anchors shall be electro-galvanised to minimum 5-micron thickness. The expansion sleeve shall preferably be of stainless steel of SS316. The anchors shall conform to minimum grade 5.8 as per IS:1367 part 3.

2.02.11 Pipe Joints

MS pipes or GI pipes shall be joined by threaded sockets or by welding. Cast iron pipes shall be socket and spigot joined and caulked with hemp and molten head.

2.03.0 FENCING

2.03.01 Chain Link Fencing

The material requirement shall conform to IS: 2721 latest edition. The chain link fencing shall be woven from 3.15mm dia. wire with mesh size of 50mm. The mesh wire shall not vary from specified dia. by more than $\pm$0.05mm. all steel wire shall be hot dipped galvanised wire. The Dia. shall be measured over the galvanised coating. The line wire shall be 4.0mm dia. mild steel. The stirrup wires for securing the line wire to the intermediate post (RCC/structural steel) shall be 2.5 mm diameter mild steel. The tying wire for securing the chain link fencing to the line wire shall be 1.6mm diameter mild

steel. Hair pin chain staples for fastening down the bottom of galvanised chain line fencing to the concrete sill shall be 3.15mm wire. The ends shall be bent outwards for securing anchorage.

Cleat for eye bolts shall be of uniform size and shall consist of mild steel angle of 75 x 50 x 8 mm. The eye bolts strainer shall consist of bolt with welded eye sufficiently threaded and fitted with a nut and washer. Two-way eye bolt strainer shall have suitable ring nuts fitted after the wires have been strained on one side. Stretcher bar shall consist of mild steel flats 25 x 4.75 mm. They shall be secured to the cleats by steel bolts.

The chain link fencing shall be strained between each pair of straining posts and secured to each straining posts by means of a stretcher bar. One of top line wire shall be threaded through appropriate adjacent row of mesh, care being taken that no meshes in the row are bypassed by the line wire except where deviation is necessary at the straining posts. The second top line wire shall be strained in front of the fencing. The fencing shall be attached to the top and bottom line wire by wire ties spaced at 150mm apart and to the other middle line wire by wire ties spaced at 450mm apart.

The bottom of fencing shall be treated as follows:
Continuous concrete sill 125mm wide x 225mm high for full length between posts shall be cast with the top 25mm above GL and 25mm below the chain link fencing. Hair pin staples shall be threaded through the bottom row of mesh at 750mm c/c and set in the sill to a depth of 150mm.

2.03.02 Barbed Wire Fencing

The barbed wire shall be conforming to IS:278 latest editions. The barbed wire shall be galvanised and galvanising shall conform to the requirement laid down for 'light-coated wire' of IS:4826 and it shall be smooth and relatively free of lumps etc. Wire with excessive roughness blisters, salammoniac spots shall be rejected. The barbed wire shall be made from two-line wire and two-point wire of 2.5 mm thickness each. The barbs shall have four point and shall be formed by twisting two point wires, each two turns, tightly around both or one-line wire (Type A - around both line wire, Type B - around one-line wire) making altogether four complete turns. The barbs shall be so finished that four points are set and located or locked as far as possible at right angle to each other. The barbs shall have a length of not less than 13mm and not more than 18mm. The distance between two barbs shall be 75$\pm$12mm.

Straining posts shall be provided at all ends and corners of fences or at changes in direction or acute variation in level and at intervals not exceeding 66 M on straight lengths of fence. Intermediate posts shall be spaced at regular intervals not exceeding 3.0m. Struts shall be fitted to all straining posts behind the chain link fabric in the direction of line of fence. There shall be four

evenly spaced row of line wire in all. The top line wire shall be doubled, making five-line wire in all. The bottom wire shall be closed to the ground. Each line wire shall be strained tightly by means of eyebolts strainers or winders at each straining points. Each line wire shall be secured to each intermediate post by a wire stirrup passed through a hold in the post and secured to the line wire by three complete turns on each sides of the post. The barbed wire shall be fitted with one dropper at the centre of each bay, secured to the wire so that they could not be bunched together. Droppers for barbed wire shall be of mild steel of not less than 25 x 4.75 mm thick with 38 x 4.85 mm half round staples for fastening the barbed wire to them. Bracing for the rows of barbed wire shall be approved by the Engineer.

3.00.00 ACCEPTANCE CRITERIA

a) All items shall be correct shape, size, weight etc. shown on drawings and schedule of items.

b) For installed items, the tolerances shall be as follows

   i) Permissible deviation from, straightness – 1 in 1000.

   ii) Seats, stiffener connections etc. shall be as per approved drawings and shall not interfere with architectural clearances.

c) All castings shall be free from blowholes, cracks, and other blemishes.

d) All MS wire fencing shall be in true vertical plain, and shall not bulge.

4.00.00 IS CODES

IS:278	Specification for Galvanized Steel Barbed wire for fencing.
IS:816	Code of practice for use of Metal Arc welding for general construction in mild steel.
IS:1367	Industrial Fasteners – Threaded steel fasteners - Technical supply condition.
IS:2721	Specification for Galvanized Steel Chain Link fence fabric.
IS:2812	Arc welding of Aluminum and Alloy

5.00.00 RATES AND MEASURMENTS

5.01.0 Rates

Rates shall include supply, fabrication and installation for misc. metals works as required for completion of works like gates, fencing, handrails, ladders, hangers, anchors etc., unless otherwise specified in Schedule of Items.
Rate for fencing shall also include excavation, concreting and supply, erection & fabrication of post (post made of either structural steel or reinforced cement concrete), unless any specific item is excluded.

5.02.0 Measurements

Measurement for MS gates shall be in MT.

Measurement for galvanised MS wire fencing shall be in Sqm.

Measurement for Anchors shall be in nos. for the type as specified in schedule of items.

Measurement of other misc. metals shall be done in MT unless otherwise specified in schedule of items.

VOLUME: II B

SECTION - D

SUB-SECTION – D9

MASONRY AND ALLIED WORKS

SPECIFICATION NO. PE-TS-999-600-C009

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	PAGE NO.
1.00.00	SCOPE	3
2.00.00	MATERIALS	3
3.00.00	INSTALLATION	6
4.00.00	I.S. CODES	10
5.00.00	RATES AND MEASUREMENTS	11

MASONRY AND ALLIED WORKS

1.00.00 SCOPE

This section covers furnishing, installation including handling, transporting, batching, mixing, laying scaffolding, centering, shuttering, finishing, curing, protection, maintenance and repair of common building materials till handing over of masonry and allied works for use in structures and locations covered under the scope of this package.

2.00.00 MATERIALS

a) Brick

Bricks for general masonry work shall be of class designation 7.5 of nominal dimensions as per standard specification under IS: 1077, well burnt, of uniform size, shape and colour, free from cracks, flaws or modules of free lime and emit clear ringing sound when struck. Fractured surface shall show uniform texture free from grits, lumps holes etc. Water absorption after 24 hours' immersion shall not exceed 20% by weight for bricks. Dimensional tolerance shall not exceed 8% of the size shown in drawings for bricks. All bricks shall have rectangular faces and sharp straight edges. The bricks shall show no efflorescence after soaking in water and drying in shade.

Each brick shall have the manufacturer's identification marks clearly marked on the frog. Representative samples shall be submitted and approved samples shall be retained by the Engineer for further comparisons and reference. Any brick not found up to the specification shall be removed immediately from site at the Contractor's own cost.

Bricks shall not be dumped at site. They shall be stacked in regular tiers, even as they are unloaded; to minimize breakage and defacement of bricks. Bricks selected for different situation of use in the work shall be stacked separately.

b) Stone

All stones shall be obtained from approved quarries, hard, tough, durable compact grained, uniform in texture and colour and free from decay, flaws, veins, cracks and sand holes. The surface of a freshly broken stone shall be bright, clean, and sharp and shall show uniformity of texture, without loose grains and free from any dull, chalky, or earthly appearance. Stone showing mottled colours shall not be used for face work. A stone shall not absorb more than 5 per cent of its weight of water after 24 hours'

immersion. The type of stone shall be as specified on drawings and/or instructed by the Engineer. Samples shall be submitted by the Contractor and approved samples shall be retained by the Engineer for comparison of bulk supply.

c) Cement

Cement used shall be Ordinarily Portland Cement or Portland Slag Cement or Portland Pozzolana Cement conforming to IS Codes and shall be fresh when delivered. In special cases, Rapid Hardening Portland Cement, Low Heat Cement etc. may be permitted or directed to be used by the Engineer. The Contractor shall submit the manufacturer's certificate for each consignment of cement procured to the Engineer. If at any time, the Engineer feels that the cement being used by the Contractor is not up to specification, he may stop the work and send the samples of the cement to a testing laboratory for standard tests and all expenses incurred thus shall be borne by the Contractor. The Contractor shall also have no claim for this type of suspension of work.

The cement shall be stored above the ground level in perfectly dry and watertight sheds. The bags shall be stacked in a manner so as to facilitate removal or first in first out basis. Any material considered defective by the Engineer shall not be used by the Contractor and shall be removed from the site immediately.

d) Coarse Aggregate

Coarse aggregates shall be as per IS: 383 latest editions, consisting of hard, strong and durable pieces of crushed stone and shall be free from organic or clay coatings and other impurities like disintegrated stones, soft flaky particles etc. and any other material liable to affect the strength, durability or appearance of concrete.

Aggregates other than crushed stone conforming to the provisions of specification may be used if permitted by the Engineer.

Washing of aggregates by approved means shall be carried out, if desired

by the Engineer.

Grading of coarse aggregates shall generally conform to IS: 383 and shall be such as to produce a dense concrete or the specified proportions and strength and of consistence that will work readily into position without segregation.

Aggregates shall be stored on brick soling or an equivalent platform so that they do not come in contact with dirt, clay, grass, or any other injurious substances at any stage.
Aggregate of different size shall be kept in separate stacks. If so desired by the Engineer aggregate from different sources shall be stacked separately with proper care to prevent intermixing.

e) Sand

Sand shall be hard, durable, clean, and free from adherent coatings or organic matter and shall not contain clay balls or pellets. The sand shall be free from impurities such as iron pyrites, alkalis, salts, coal, mica, shale or other laminated materials in such forms or quantities as to affect adversely the hardening, strength, durability or appearance of mortar, plaster or concrete or to cause corrosion to any metal in contact with such mortar, plaster or concrete. All sand shall be properly graded and shall be as per relevant IS Code. Sand for concrete shall conform to IS: 383.

f) Water

Water shall be clean, fresh and free from organic matters, acids or soluble salts and other deleterious substances which may cause corrosion, discoloration, efflorescence etc.

g) Reinforcement

Reinforcement steel shall be clean and free from loose mill scales, dust, loose rust, oil and grease or other coatings, which may impair proper bond. Structural steel shall conform to IS: 2062. Mild steel and medium tensile steel bars and hard-drawn steel wire for concrete reinforcement shall conform to IS: 432. Cold twisted steel bars shall conform to IS: 1786. Hand drawn steel wire fabric shall conform to IS: 1566. Hexagonal wire netting shall conform to IS: 3150. All steel bars including and above 10 mm diameter shall be of tested quality. All wire netting shall be galvanized.

Reinforcement bars shall be stored off the ground and under cover if so desired by the Engineer. If necessary, a coat of cement wash shall be given to the bars to guard against rusting.

3.00.00 INSTALLATION

3:01.00 Soling

3.01.01 Brick Soling

The ground shall be dressed, consolidated by ramming, or by light rolling and a 12 mm thick cushion of sand laid. On the sand cushion the bricks shall be laid with fine joints and placed firmly in position by hammering with wooden mallet. The surface shall be free from undulations. The 'frog' side shall be on the underside. The joints shall be broken the in all direction and bricks cut as required. The pattern of laying and number of layers shall be as per Schedule of item. Orientation shall be as desired by the Engineer. After laying of each layer of bricks sand shall be spread over and worked into the joints to pack the bricks tight.

3.01.02 Stone Soling

The stones for soling shall be selected on the basis of thickness of soling specified in the Schedule of Items. The larger stones shall be laid and the gaps filled by smaller stones. The interstices shall then be firmly packed with sand by flooding with water.

3.02.00 Brick-on-Edge

Excavation shall be done close to the brick dimensions and in perfect alignment. Bricks shall be firmly placed by hammering with wooden mallets and sides and joints packed firmly with earth so that the edging is not disturbed easily. Alignment and level shall be acceptable to the Engineer.

3.03.00 Masonry

3.03.01 General

All masonry work shall be true to lines and levels as shown on drawings. All masonry shall be tightly built against structural members and bonded with dowels, inserts etc. as shown on drawings.

3.03.02 Cement Mortar

Cement mortar shall be prepared with materials specified in clause 2.00.00. Sand for masonry mortar shall conform to IS: 2116. Cement and sand in the specified proportion shall be mixed dry thoroughly and minimum water added to attain required workability.

Surplus mortar droppings from masonry, if received on surface free from dirt may be mixed with fresh mortar if permitted by the Engineer who may direct addition of additional cement without any extra payment. No mortar, which has stood for more than half an hour, shall be used.

3.03.03 Brick Masonry

Bricks shall be soaked by submergence in clean water for at least two hours in approved vats before use. Bricks shall be laid in English bond unless specified otherwise. Broken bricks shall not be used. Cut bricks shall be used if necessary to complete bond or as closers. Bricks shall be laid with frogs upwards over full mortar beds. Bricks shall be pressed into mortar and tapped into final position so as to embed fully in mortar. Inside faces shall be buttered with mortar before the next bricks is placed and pressed against it. Thus all joints between bricks shall be fully filled with mortar.

Mortar joints shall be kept uniformly 10 mm thick. All joints on face shall be raked to minimum 10 mm depth using raking tool while the mortar is still green to provide bond for plaster or pointing.

Where plaster or pointing is not provided, the joints shall be struck flush and finished immediately. Brickworks two bricks thick or more shall have both faces in true plane. Brickwork of lesser thickness shall have one selected face in true plane.

3.03.04 Exposed Brickwork

Brickwork in superstructures, which is not covered by plaster, shall be as shown on drawing and executed by especially skilled mason. Courses shall be truly horizontal and vertical joints truly vertical. Wooden straight edges with brick course graduations and position of window sills and lintels shall be used to control uniformity of brick courses. Masons must check workmanship frequently with plumb, spirit level, rule, and string. All brickwork shall be cleaned at the end of days' work. If face bricks are specified, the brickwork shall be in composite bricks, with face bricks on the exposed face and balance in routine bricks, but maintaining the bond fully. Where face bricks are not specified, bricks for the exposed face shall be specially selected from routine bricks. All exposed brickwork on completion of work shall be rubbed down, washed clean, and pointed as specified. Where face bricks are used carborundum stone shall be used for rubbing down.

3.03.05 Reinforced Brickworks

Reinforcements shall be as specified. All reinforcements shall be thoroughly cleaned and fully embedded in mortar. Where M.S. bars are used as reinforcement, these shall be lapped with dowels if left in R.C. columns or welded to steel stanchions.

3.03.06 Stone Masonry

Stones shall be thoroughly soaked before laying. Stones shall be laid on their natural quarry beds. Individual stones shall be fitted with mallet and properly wedged to reduce thickness of mortar joints. Thickness of joint shall be not less than 8 mm and not greater than 25 mm. At least two stones shall run the full width of the wall for every square meter of surface area.

3.03.07 Exposed Stone work

Stonework, which is to be kept exposed, shall be as shown on approved drawing. It shall be executed by especially skilled mason. Stones used for exposed face shall be specially selected. All exposed stone faces shall be kept clean and free from mortar and pointed up neatly as the work proceeds in a manner called for in the drawings or instructions. A sample wall, 10 Sq.M. area shall be built and approved by the Engineer and all works shall match with this sample.

3.03.08 Composite Masonry

Where stonework facing with brick masonry backing is specified the bond between them shall be achieved by bond stones of dimensions and frequency as desired by the Engineer.

3.03.09 Expansion & Separation Joints

Location of joints shall strictly be as shown on drawings or as instructed by the Engineer. Expansion joints shall be as shown on drawings and specified. Expansion joint filler boards and sealing strips shall have minimum transverse joints. Transverse joints shall meet the approval of the Engineer.

Separation joints shall be with standard waterproof paper or with alkathene sheets about 1 mm in thickness. Length and sealing of laps shall be to the satisfaction of the Engineer.

3.03.10 Mouldings, Cornices, Drip Course

These shall be made as shown in drawings. Bricks or stone shall be cut and dressed as required. If no subsequent finish is envisaged, these shall be rubbed to correct profile with Carborundum stone.

3.03.11 Curing

Masonry shall be cured by keeping it wet for seven days from the date of laying. In dry weather at the end of days' work top surface of masonry shall be kept wet by ponding.

3.03.12 Embedding of fixtures

All fixtures shall generally be embedded in mortar and masonry units shall be cut as required.

3.03.13 Encasing of Structural Steel

This shall be done by building masonry work round flanges, webs etc., and filling the gap between steel and masonry by minimum 12 mm thick mortar. Encased members shall be wrapped with chicken wire mesh when shown on drawings or instructed by the Engineer. The minimum lap in chicken wire mesh shall be 50 mm.

3.04.00 Damp Proof Course (DPC)

Unless otherwise specified Damp-proof course shall be 40 mm thick 'artificial stone' in proportion 1:1½:3 cement sand stone-chips (10 mm down) with admixture of a waterproofing compound as approved by the Engineer. The percentage of admixture shall be as per manufacturer's specifications but not less than 2% by weight of cement. The top surface shall be double Chequered and cured by ponding for seven days.

3.05.00 Damp Proof Membrane

Damp proof treatment using fibre or hessian base bitumen felt shall be 6, 8 or 10 course treatment as specified in IS: 1609. The number of courses shall be as shown as drawings or as specified. Sequence of work shall be as directed by the Engineer. Extreme care shall be taken to prevent damage to felt during and after laying. The Contractor shall be obliged, at his own expense, to rectify any leakage appearing within 5 years of installation by removing and renewing the coats at the point of leakage.

Where shown on drawing, damp proof membrane with one-layer bitumen paper or one layer alkathene sheet shall be laid with minimum 150 mm lap under slabs on grade.

3.06.00 Plinth Protection

Plinth of buildings shall be protected with brick-on-edge paving of minimum 750mm width unless otherwise shown on the drawings. The treatment shall consist of laying bricks in cement mortar 1:6 (1 cement: 6 sand) over a 75mm thick bed of dry graded brick aggregate, 40mm nominal size, grouted with sand. The top shall be finished with 1:2 cement mortar pointing (1 cement: 2 sand). Plinth protection shall be laid with a minimum outward slope of 1 in 50. The brick aggregate shall be well graded, broken from well burnt or slightly over burnt and dense brickbats. It shall be homogeneous in texture, roughly cubical in shape, clean and free from dirt or any other foreign matter.

The ground shall first be prepared to the required slope around the building. The high portions of the ground should be cut down; hollows and depressions filled up to the required level from the excavated earth and rammed so as to give uniform outward slope. The bed shall be watered and rammed with heavy iron square rammers. Surplus earth, if any, shall be disposed off beyond a lead of 50m or as directed by the Engineer.

Over this, 75mm thick bed of aggregate of 40mm nominal size, shall be laid with a minimum outward slope of 1 in 50. Aggregates shall be carefully laid and packed, bigger sized being placed at the bottom. The brick aggregates shall be consolidated dry with heavy iron rammers.

The aggregates shall then be grouted evenly with sand at the rate of 0.6 cubic metre per square metre area, adequately watered to ensure filling of voids by sand and again rammed with heavy iron rammers. The finished surface shall give uniform appearance. After the subgrade has been compacted thoroughly, brick flooring with bricks of specified strength in cement mortar 1:6 (1 cement: 6 sand) shall be laid.

The bricks shall be laid on edge in Diagonal/Herring Bone Bond or other pattern as specified or as directed by the Engineer. Bricks shall be laid on 12mm thick mortar bed and each brick shall be properly bedded and set home by gentle tapping with handle of trowel or wooden mallet. Its inside face shall be buttered with mortar before the next brick is laid and pressed against it. On completion of the portion of flooring, the vertical joints shall be fully filled from the top with mortar. The surface shall present a true plain surface with the required slope.

The pointing shall be done in cement mortar 1:2 (1 cement: 2 sand). The mortar shall be pressed into the joints and shall be finished off flush and level with the edges of the bricks so as give a smooth appearance. The edges shall be neatly trimmed with a trowel and a straight edge. The mortar shall not spread over surface of the masonry.

Brick flooring & pointing shall be kept wet for a minimum period of seven days. These shall be protected from rain by suitable covering when the mortar is green.

4.00.00 I.S. CODES

Some of the important relevant codes for this section are:

IS: 1127: Recommendations for dimensions and workmanship of natural building stones for masonry work.

IS: 1597: Code of Practice for Construction of stone Masonry.

IS: 1609: Code of Practice for laying Damp proof treatment using bitumen felts.

IS: 2212: Code of Practice for Brickwork.

IS: 2250: Code of Practice for preparation and use of masonry Mortar.

IS: 5134: Bitumen Impregnated Paper & Board.

5.00.00 RATES AND MEASUREMENTS

5.01.00 Rates

Unit rate for masonry work shall include the following:

a) Raking out joints for plastering or pointing or finishing the joint flush as the work proceeds.

b) Preparing top sand sides of existing wall for joining old with new work.

c) Providing, dismantling and removing the scaffolding.

Unit rate for DPC shall be inclusive of formwork and bitumen painting.

5.02.00 Measurement

Brickwork in wall of half brick thickness shall be measured separately in Sqm stating the wall thickness and more than half brick thickness shall be measured by volume. Plaster thickness shall not be considered for computation of volume.

Masonry work in sub structure and super structure shall be measured separately, unless otherwise specified in the Schedule of items.

No deductions shall be made and no extra payment shall be made for following:

a) Opening upto 0.1 Sqm each in area. In calculating the area of the opening lintels or sills shall be included along with the size of the opening.

b) Drainage holes and recesses for cement blocks to embed holdfasts for doors, windows etc.

c) Pipe and fixtures upto 300mm dia. and nothing extra shall be paid for the mortar used for fixing.

d) Ends of dissimilar materials (i.e. joists, beams, lintels, posts, girders, rafters, purlins, trusses, corbels, steps, etc.); up to 0.1 sqm in section;

e) Chases of section not exceeding 50 cm in girth;

f) Iron fixtures, such as wall ties and hold fasts for doors and windows;

g) Cement concrete blocks as fcr hold fasts and holding down bolts;

h) Wall plates, bed plaros, and bearing of slabs, CHAJJAS and the like, where thickness does not exceed 10 cm and bearing does not extend over the full thickness of wall;

Reinforcement in masonry work shall be paid separately under respective items.

Damp proof course shall be measured in Sqm. No deduction shall be made and no extra shall be paid for opening upto 0.1 Sqm in area.

Plinth protection shall be measured under respective item of works executed required for completion of the work as specified.

VOLUME: II B

SECTION - D

SUB-SECTION – D10

FINISH TO MASONRY AND CONCRETE

SPECIFICATION NO. PE-TS-999-600-C010

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	3
3.00.00	ACCEPTANCE CRITERIA	8
4.00.00	I.S. CODE	8
5.00.0	RATES AND MEASUREMENTS	9

FINISH TO MASONRY AND CONCRETE

1.00.00 SCOPE

This Section covers finishing, installation, repairing, finishing, curing, testing, protection, maintenance till handing over of finishing items for masonry and concrete. This shall also include the work to be done to make the surface suitable for receiving the finishing treatment.

Before commencing finishing items, the Contractor shall obtain the approval of the Engineer regarding the scheduling of work to minimize damage by other trades. He shall also undertake normal precaution to prevent damage or disfiguration to work of other trades or other installation.

2.00.01 INSTALLATION

2.01.00 Preparation of Surface

All joints in masonry walls shall be raked out to a depth of at least 10 mm with a hooked tool made for the purpose while the mortar is still green. Walls shall be rushed down with stiff wire brush to remove all loose dust from joints and thoroughly, washed with water. All laitance shall be removed from concrete to be plastered.

For all types of flooring, skirting and dado work, the base cement concrete slab or masonry surface shall be roughened by chipping and cleaned of all dirt, grease or loose particles by hard brush and water. The surface shall be thoroughly moist to prevent absorption of water from the base course. Any excess of water shall be mopped up.

At any point, the level of base shall be lower than the theoretical finished floor level by the thickness of floor finish. Any chipping or filling to be done to bring the base in the required level shall be brought to the notice of the Engineer and his approval shall be taken regarding the method and extent of rectification work required.

Prior to commencement of actual finishing work, the approval of the Engineer shall be taken as to the acceptability of the base.

2.02.00 PLASTERING

2.02.01 Mortar

Mortar for plastering shall be as specified.
For sand cement plaster, sand and cement in the specified proportion shall be

mixed dry, on a watertight platform and minimum water added to achieve working consistency. The sand for plaster shall conform to IS: 1542.

No plaster, which has stood for more than half an hour, shall be used; plaster that shows tendency to become dry before this time shall have water added to it.

2.02.02 Application of Plaster

Plaster, when more than 12 mm thick, shall be applied in two coats a base coat followed by the finishing coat. Thickness of the base coat shall be sufficient to fill up all unevenness in the surface; no single coat, however, shall exceed 12 mm in thickness. The lower coat shall be thicker than the upper coat; the overall thickness of the coats shall not be less than the minimum thickness shown on the drawings. The undercoat shall be allowed to dry and shrink before applying the second coat of plaster. The undercoat shall be scratched or roughened before it is fully hardened to form a mechanical key. The method of application shall be 'thrown on' rather than 'applied by trowel'.

To ensure even thickness and true surface, patches of plaster about 100 mm to 150 mm square or wooden screed 75 mm wide and of the thickness of the plaster, shall be fixed vertically about 2000 mm to 3000 mm apart, to act as gauges. The finished wall surface shall be true to plumb, and the Contractor shall, without any extra cost to the Owner, make up any irregularity in the brickwork with plaster.

All vertical edges of brick pillars, doorjambs etc. shall be chamfered or rounded off as directed by the Engineer. All drips, grooves, mouldings and cornices as shown on drawing or instructed by the Engineer shall be done with special care to maintain true lines, levels and profiles. After the plastering work is completed, all debris shall be removed and the area left clean. Any plastering that is damaged shall be repaired and left in good condition at the completion of the job.

2.02.03 Finish

Generally, the standard finish shall be used unless otherwise Shown on drawing or directed by the engineer. Wherever any special treatment to the plastered surface is indicated, the work shall be done exactly as shown on the drawings, to the entire satisfaction of the engineer regarding the texture, color and finish.

a) Standard Finish

Wherever punning is indicated, the interior plaster shall be finished rough; otherwise the interior plaster shall generally be finished to a smooth surface. The exterior surface shall generally be finished with a wooden float.

b) Neat Cement Finish

Immediately after achieving a true plastered surface with the help of a wooden straight edge, the entire area shall be uniformly treated with a paste of neat cement at the rate of one (1) kg. per Sq.M. and rubbed smooth with a trowel.

c) Coloured Plaster Finish

This shall be done in the same way as specified in Clause 2.02.02 but using Coloured cement in place of ordinary cement. When coloured plastering is specified in more than one coat, the topcoat only shall be made with coloured cement.

Coloured cement shall be either ready mixed material or may be obtained by mixing pigments and cement at site, as approved by the Engineer. The pigments to be mixed with cement shall conform to Appendix-A of IS: 2114 latest editions.

Samples of colouring material shall be submitted to the engineer for approval and material procured, shall conform in all respects to the approved samples, which shall remain with the Engineer. All coloured cement and/or pigments shall be stored in an approved manner in order to prevent deteriorations.

d) Pebble-dash Finish

Mortar of required thickness consisting of 1-part cement and 4 parts sand by volume shall be applied in the usual manner as described under plastering Clause 2.02.02. While the mortar is still plastic small pebbles or crushed stone of size generally from 10mm to 20mm as approved by the

Engineer shall be thrown on the plastered surface. The aggregate shall be lightly tapped into the mortar with a wood float or the flat end of oil a trowel, in order to ensure satisfactory bond between the dashing and the mortar.

e) Rough-cast Finish

A wet plastic mix of 3 parts coloured cement 6 parts sand and 4 parts aggregate by volume (gravel or crushed stone of size from 6 mm to 12 as approved by the Engineer) shall be thrown on to the wall by means of a plaster's trowel and left in the rough condition.

f) Scraped Finish

Ordinary plaster as described under Clause 2.02.02 after being leveled and allowed to stiffen for a few hours, shall be scraped with a steel straight edge to remove the surface skin. The pattern shall be as approved by the Engineer.

g) Textured Finish

Mortar consisting of 1-part cement and 3 parts sand by volume shall be applied in a manner as specified under "Plastering" Clause 2.2.2 Ornamental treatments in the form of horizontal or vertical rib texture fan texture etc. shall be applied by means of suitable tools to the freshly applied plastered surface, as approved by the Engineer.

h) Sand Faced Plaster

The plaster shall be applied in 2 coats. The first coat or the scratch coat should be approximately 14mm and shall be continuously carried out without break to the full length of wall or natural breaking points such as doors, windows, etc. The scratch coat shall be dashed on the prepared surface with heavy pressure, brought to true and even surface and then lightly roughened by cross scratch lines, to provide bond for the finishing coat. The mortar proportion for this scratch coat shall be as specified in the respective item or work. The scratch coat shall be cured for at least 7 days & then allowed to dry. The second coat shall be 6mm thick and it shall not be applied until at least 10 days have elapsed after the application of scratch coat. Before application of the second coat, the scratch coat shall be evenly damped. This coat shall be applied from top to bottom in one operation & without joints; finish shall be straight, true, & even. The mortar of this coat shall be as specified under the respective item of work. White sand for finish shall be used for the second coat & for finishing work. Sand for finish shall be of even coarse size & shall be dashed on the surface & sponged.

2.02.04 Curing

All plastered surfaces after laying shall be watered, for a minimum period of seven days, by an approved method, and shall be protected from excessive heat and sunlight by suitable approved means. Moistening shall commence, as soon as the plaster has hardened sufficiently and not susceptible to damage. Each individual coat of plaster shall be kept damp continuously, for at least two days, and then dried thoroughly, before applying the next coat.

2.03.00 Pointing to masonry

All Joints of brickwork shall be raked out to a depth of 10 mm with a hooked tool made for the purpose while the mortar is still green. The brickwork shall then be brushed down with a stiff wire brush, so as to remove all loose dust from the joints and thoroughly washed with water. Mortar consisting of 1-part cement and 3 parts clean, sharp, well graded sand by volume shall be pressed carefully into the joints and finishes with suitably tools to shape as shown on the drawings. Any surplus mortar shall be scalped off the wall face leaving the surface clean.

The pointed surface shall be kept wet for at least three days for curing.

2.04.00 Plaster with Metal Lath

The supports, hangers, brackets, cleats etc. shall be as shown on drawings and/or as approved by the Engineer. These shall have a coat of prime paint before and another coat of approved paint after erection.

The metal lath shall be expanded metal, with 12 mm x 38 mm mesh, 16 thick and 3 mm wide strands. Side laps shall be minimum 12 mm and end laps 25 mm minimum. The plastering shall be minimum 20 mm thick measured from the back of lath and applied in two-layers. The mortar for plastering shall consist of 1-part cement and 4 parts sand by volume mixed as specified in plastering, Clause 2.02.01. The application, finish etc. shall be as specified under relevant clause above. Where called for a 2 mm Plaster of Paris punting shall be applied over plaster as a finishing coat to give perfectly smooth and even finish.

2.05.00 Lime Punning

For plastered surfaces, where an even smooth surface is specified, lime punning with 5 parts of shell lime properly slaked, strained and aged, mixed with 1 part clean, washed, sieved, fine sand by volume shall be done. The thickness of lime punning shall be not less than 2 mm and more than 3 mm. The plastered surface shall be saturated with water before application of the

lime punning. The punting shall be applied by skilled workman and given a smooth and ever finish free from undulations, cracks etc. and to the satisfaction of the Engineer.

2.06.00 Plaster of Paris Punning

Plastered surfaces, where specified shall be finished with Plaster-of-Paris punning. The material shall be from approved manufacturers and approved by the Engineer. The thickness of the punning shall be 2 mm and shall be applied by skilled workmen. The finish shall be smooth, even and free from undulation, cracks etc.

Before bulk work is taken in hand, a sample of punning shall be done on roughly 10 Sq.M. areas and approval of the Engineer taken. The work shall then be taken in hand as per approved sample.

2.07.00 Stone Facing

Stone facing where specified shall be done as shown on design drawings and approved shop drawings. The stone shall be as specified on drawings. Samples of stone shall be submitted to the Engineer for approval and then bulk purchase made. The Contractor shall submit three copies of shop drawings for the Engineer's approval before commencing the work.

The thickness of facing stone shall be not less than 25 mm unless otherwise specified on drawings.

The stone slabs shall be cut and finished to sizes as per pattern shown on drawings. They shall be fastened to wall with suitable non-corrodible anchorage as approved by the Engineer. Where mild steel clamps, stays etc. are used for anchorage, they shall be galvanized (weight of zinc coating shall. not be less than 700 gms per square meter of surface) to prevent rust stains developing on the finished surface. There shall be at least 12 mm gap between the stone and masonry, which shall be filled up and packed by a mortar of 1-part cement and 3 parts of sand by volume. After the mortar is set and cured for at least four days, the exposed surface shall be rubbed and polished as approved by the Engineer.

The completed surface shall be neat, or uniform texture and acceptable to the Engineer.

Where pointing is specified on drawings it shall be done by mortar as specified on drawings.

3.00.00 ACCEPTANCE CRITERIA

Finish to masonry and concrete shall fully comply with the Specifications, approved samples and instructions of the Engineer with respect to lines, levels, thickness, colour, texture, pattern and any other special criteria as mentioned in the body of the specification or as shown on drawings.

4.00.00 I.S. CODE

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS: 1661: Code practice for cement and cement-lime plaster finish on wall & ceilings.

IS: 4101: code of practice for external facings and veneers.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall also include providing, dismantling and removing of scaffolding, surface preparation, curing and all type of surface, shapes/ profiles and at all elevations.

5.02.00 Measurement

All plastering shall be measured net (on surface area on which it is applied) in Sqm. Plaster work shall be classified according to the type used and shall be measured separately. Plaster on ceiling and walls shall be measured separately. Soffits of stairs shall be measured as plastering on ceiling.

No deduction shall be made for opening not exceeding 0.5 Sqm and for ends of beams, joints, etc. also no payment shall be made for reveals, jams, soffits, sills of these openings.

50% deduction shall be made for opening exceeding 0.5 Sqm but not exceeding 3.0 Sqm each and no addition shall be made for reveals, jams, soffits, sills etc.

In case of opening exceeding 3.0 Sqm each, deduction shall be made for opening but jams, soffits, and reveals shall be measured and paid for.

VOLUME: II B

SECTION - D

SUB-SECTION – D11

PAINTING, WHITEWASHING, POLISHING

SPECIFICATION NO. PE-TS-999-600-C011

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	3
3.00.00	ACCEPTANCE CRITERIA AND TESTING	10
4.00.00	I.S. CODES AND STANDARDS	11
5.00.00	RATES AND MEASUREMENTS	12

PAINTING, WHITE WASHING, POLISHING, ETC.

1.00.00 SCOPE

This section covers painting, white washing, varnishing, polishing etc. of both interior and exterior surfaces of wood work, masonry, concrete plastering, plaster of Paris, false ceiling, structural and other miscellaneous steel items, rain water down comer, floor and roof drains, soil, waste and service water pipes, and other ferrous and non-ferrous metal items.

Copper, bronze, chromium plate, Nickel, stainless steel and aluminium shall generally not be painted or finished except if otherwise specified.

Before commencing painting, the Contractor shall obtain the approval of the Engineer in writing regarding the schedule of work to minimize damage; disfiguration or staining to work of other trades or other installations.

2.00.00 INSTALLATION

2.00.01 Materials

Materials shall be highest grade products or well-known approved manufacture and shall be delivered to the site in original sealed containers, bearing brand name, manufacturer's name and colour shade, with labels intact and seals unbroken. All materials shall be subject to inspection, analysis and approved by the Engineer. It is desired that materials of one manufacturer only shall be used as far as possible and paint of one shade is obtained from the same manufacturing batch. Each and every supply of primer, finish paint etc. shall be accompanied by manufacturer’s test certificate. All paint shall be subject to analysis from random samples taken at site from painter’s bucket, if so desired by the Engineer.

All prime coats shall be compatible to the material of the surface to be finished as well as to the finished coats to be applied.

All unspecified materials such as shellac, turpentine or linseed oil shall be of the highest quality available and shall conform to the latest IS standards. All such materials shall be made by reputable recognized manufacturers and shall be approved by the Engineer.

All colours shall be as per painting schedule and tinting and matching shall be done to the satisfaction of the Engineer. In such cases, where samples are required, they shall be executed in advance with the specified materials for the approval of the Engineer.

a) White Wash/Colour Wash

Shall be done from pure shell lime or fat lime, or a mixture of both as instructed by the engineer, and shall conform to IS: 712 latest editions. Samples of lime shall be submitted to the Engineer for approval, and lime as per approved sample shall be brought to site in unslaked condition. After slaking, it shall be allowed to remain in a tank for two days and then stirred up with a pole, until it attains the consistency of thin cream. 100 grams of gum to 6 litres of white wash water and a little of indigo or synthetic ultramarine blue shall be added to the lime. Mineral colour not affected by lime shall be added to white wash to get the required tint/shade approved by the Engineer.

b) Dry distemper

Shall be made from suitable pigments, extenders, lime proof tinters, water-soluble binders etc. and share conform to IS: 427. The distemper shall be diluted with prescribed thinner in a manner recommended by the manufacture. Only sufficient quantity of distemper required for a day's work shall be prepared.

c) Oil Bound Washable Distemper

Shall be of oil emulsion type containing suitable preservatives and shall conform to IS: 428. The distemper shall be diluted with prescribed thinner in a manner recommended by the manufacturer. Only sufficient quantity of distemper required for a day's work shall be prepared.

d) Waterproof Cement Paint

Shall be made from best quality white cement and lime resistant colours with accelerators, waterproofing agents and fungicides. The paint shall conform to IS: 5410.

e) Acrylic Emulsion Paint

Shall be water-based acrylic copolymer emulsion with rutile titanium dioxide and other selected pigments and fungicide conforming to IS: 5411 (Part-1). It shall exhibit excellent adhesion to plaster and cement surface and shall resist deterioration by alkali salts. The paint film shall allow the moisture in wall to escape without peeling or blistering. The paint, after it is dried, shall be able to withstand washing with mild soap and water without any deterioration in colour, or without showing flaking, blistering, or peeling.

f) Synthetic Enamel Paint

Shall be made from synthetic resins and drying oil with rutile titanium dioxide and other selected pigments to give a smooth, hard, durable and glossy finish to all exterior and resist interior surfaces. White and pastel shades shall not be yellowing and darkening with aging. The paint shall conform to IS: 2932 and IS: 2933.

g) Aluminium Paint

Shall be in two pack containers and shall resist weathering. The paint shall conform to IS: 2339.

h) Varnishing

Shall be best quality alkyd varnish suitable for brushing over the tint of paint or light natural wood and shall not darken or yellow with age.

i) French Polish

Shall be made from best quality shellac, denatured spirit and other suitable alcohol soluble ingredients and made by a well-known approved manufacturer. The material shall conform to IS: 348.

French polish shall not be used on bare wood it shall only be used as finishing coat on wood after the woods pre-treated with a liquid wood filler conforming to IS: 345 is applied and rubbed out.

j) Bitumen paint (black bituminous anti-corrosive paint)

Bitumen based anti-corrosive paint conforming to IS: 158 shall be used.

2.00.02 Storage

The Contractor shall arrange for safe and proper storage of all materials and tools. The storage space if allotted within the building shall be adequately protected from damage, disfigurement, & stains. Paint shall be kept covered at all times and mixing shall be done in suitable containers. All necessary precautions shall be taken by the contractor to prevent fire.

2.01.00 Preparation of surface

Before starting the work, the Contractor shall obtain the approval of the Engineer regarding the soundness & readiness of the surface to be painted on.

2.01.02 Wood

All surfaces shall be free from, dirt and loose or peeling paints. The surface shall be rubbed down smooth. All nails & screws shall be sunk below the surface and filled with putty after applying an under coat. Small knots that do not justify cutting and sap streaks shall be covered with minimum 2 coats of pure shellace coating applied thinly & extended 25 mm beyond the area. All large, loose, or resinous knots shall be removed and filled with sound wood. All work shall be done as per IS: 2338.

2.01.02 Masonry, Concrete, and Plastered Surface

Surface shall be free from all oil, grease, efflorescence, mildew, loose paint, or other foreign and loose materials. Masonry cracks shall be cleaned out and patch filled with mortar similar to the original surface and uniformly textured. Where this type of resurfacing may lead to the finishing paint being different in shade from, the original surfaces, the resurfaces area shall be treated with minimum one coat of cement primer, which should be continued to the surrounding area for a distance of minimum 100 mm.

Surface with **Mildew or Efflorescence** shall be treated as below:

All mildewed surfaces shall be treated with an approved fungicide such as ammoniacal wash consisting of 7g of copper carbonate dissolved in 80ml liquor ammonia and diluted to water, or 2.5 percent magnesium silicofluoride solution and allowed to dry thoroughly before paint is applied.

2.01.03 Metal

The surface preparation shall be done in accordance with IS:1477 (Part-1) ‘Code of practice for painting of ferrous metals in building’ and as directed by Engineer. All metal surfaces shall be absolutely clean, dry, and free from rust, scales, weld slag, flux deposit, wax, grease, dried soap films, foreign matters like cement mortar etc. and free from existing loose red oxide zinc chromate primer and should be removed by means of wire brushes, hand scrappers, sand paper, emery cloth, emery papers, or by mechanical power tools etc. or as directed by Engineer. For exposed chemical resistant paints, surfaces shall be blast cleaned to near white metal. All galvanized iron surfaces shall be pre-treated with a compatible primer according to the manufacturer's direction. Any abrasion in shop coat shall be touched up with the same quality of paint as the original coat. The actual painting work should be commenced only after obtaining clearance from the Engineer regarding proper cleaning of the surface.

2.02.00 Application

2.02.01 General

The method of application shall be as recommended by the manufacturer. In case of selection of special shades and colour (not available in standard shades) the Contractor shall mix different shades and prepare test panels of minimum size 1 meter square as per instruction of the Engineer and obtain his approval prior of application of finishing paints.

Proper tools and implements shall be used. Scaffoldings used shall be independent of the surface to be painted to avoid shade differences of the freshly repaired anchor notes.

Painting shall be done by skilled labours in a workmanlike manner. All materials shall be evenly applied so as to free of sags, runs, crawls, or other defects. All coats shall be of proper consistency. In case of application by brush, no brush marks shall be visible. The brushes shall be clean and in good condition before application of paint.

All priming undercoat for painting shall be applied by brush only, and rollers spray equipments etc. shall not be used.

No work shall be done under conditions that are unsuitable production of good results. No painting shall be done when plastering is in progress or is drying. Application of paint, which seals the surfaces to moisture shall only be done after the moisture on and below the surface has dried out.

All coats shall be thoroughly dry before succeeding coat is applied. Coats of painting as specified are intended to cover surfaces perfectly. In case the surface is not covered property by applying the specified number of coats, further coats shall be applied by the Contractor when so desired by the Engineer.

All primers and undercoats shall be tinted to approximate the colour of the finishing coats. Finished coats shall be of exact colour and shade as per approved samples and all finish shall be uniform in colour and texture. All parts of mouldings and ornaments shall be left clean and true to finish.

Painting on ferrous metal surface shall, be done as per IS: 1477 (Part I & 2). The total dry thickness of film should not be less than 120 Micron.

2.02.02 White Washing

The surface where white washing is to be applied shall be cleared of all loose materials and dirt. All holes and irregularities of the surface shall be filled up with lime putty and shall be allowed to dry up before white washing.

One coat of whitewash shall consist of one stroke from top downwards, another from bottom upwards over the first stroke and another from left to right before the previous one dries up. Second coat shall be applied and in case the Engineer feels that one or more coats are required the Contractor shall do so without any extra cost to the Owner. No brush marks shall show on the finished surface.

2.02.03 Dry Distemper

New plastered surface shall be allowed to dry for at least two months. New lime or lime cement plastered surface shall be washed with a solution of 1-part Vinegar to 12 parts water or 1:50 sulphuric acid solution and for 24 hours after which the wall shall be thoroughly washed with clean water. For cement-plastered surface, the surface shall be washed with solution of 100 gms. of zinc sulphate to 1 litre of water and allowed to dry.

Dry distempering shall be done as per manufacturers instruction. In applying the distempers, the brush, should first be applied horizontally and immediately crossed off perpendicularly. Brushing shall not be continued too long, otherwise brush marks may result.

2.02.04 Oil bound washable distemper

The distemper shall be applied after surface is primed with an alkali resistant primer, and followed by minimum two coats of oil bound washable distemper all as per manufacturer's instruction.

2.02.05 Waterproof Cement Paint

Surface to be coated with cement paint shall be washed and brushed down. As soon as the moisture has disappeared, the surface shall be given one coat of paint. Care shall be taken so that the paint does not dry out too rapidly. After 4 to 6 hours, the water shall be sprinkled over the surface to assist curing and prevent cracking. After the first coat has dried (24 to 48 hours) the second coat shall be applied in a similar manner. The finished surface shall be kept moist by occasional sprinkling with water for seven days after painting.

2.02.06 Acrylic Emulsion Paint

Paint shall be applied after providing one coat of cement primer solvent of approved quality and primer shall be conforming to IS: 109. Lime gauged cement plastered surfaces shall not be painted for at least one month after plastering. A sample patch shall be painted to check alkali reaction if so desired by the Engineer. Painting shall be done strictly as per manufacturer's specification.

2.02.07 Synthetic Enamel Paint

Shall be applied on properly primered surface. Sub sequential coat shall not be applied till the previous coat is dry. The previous shall be lightly sand papered for better adhesion of subsequent coats.

2.02.08 Aluminium Paint

The paint, supplied in two pack containers shall be mixed and applied strictly as per manufacturer's direction. When more than one coat of paint is required or indicated, the next coat shall only be applied after the previous coat become hard dry.

2.02.09 Clear Synthetic Varnish

The Varnish shall be applied on wood surface after (a) filling, (b) staining & (c) sealing operations are carried out. The application of a combination of filler and stain shall not be permitted.

For the finishing coats of varnish, the surface shall be allowed to dry and be rubbed down lightly, wiped off and allowed to dry. Careful attention to cleanliness is required for varnishing. All dust and dirt shall be removed from the surface as well as from the neighbourhood. Damp atmosphere and draughts shall be avoided, and exposure to extreme heat or cold & dampness shall not be allowed.

The varnish shall be applied liberally with a brush and spread evenly over a portion of the surface with light strokes to avoid frothing. It shall be allowed to flow on white the next section is being laid on excess varnish shall then be scrapped off the brush and the first section be crossed, recrossed and then laid off lightly. The varnish once it has begun to set shall not be retouched. In case of any mistake in application, the varnish shall be removed and the work started afresh.

The varnish shall be minimum of two coats, with the first coat being a flatting varnish. This shall be allowed to dry hard and be flatted down, before applying the next coat. Sufficient time must be allowed between coats to get a

hard dry surface before next coat is applied. All work shall be as per relevant IS Code.

2.02.10 French polish

All unevenness of the surface shall be rubbed down to smoothness with sand paper and the surface shall well dusted. The pores in the shall be filled up with a paste of whitening in water or methylated spirit with a suitable pigment like burnt siemme or umber.

After application of the filler paste, the French polish shall be applied with a pad of woollen cloth covered by a fine cloth. The pad shall be moistened with polish and rubbed hard on the surface in a series of overlapping circles so that the polish is sparingly but uniformly applied over the entire area to give an even surface. A trace of linseed oil may be used on the pad for case of application. The surface shall be allowed to dry before further coats are applied in the same manner. To finish off, the pad shall be covered with a fresh piece of clean fine cloth, slightly damped with methylated spirit, and rubbed lightly and quickly with circular motions to leave the finished surface with a uniform texture and high gloss.

2.02.11 Chemical Resistant Paint

For chemical resistant paints, epoxy, chlorinated rubber, or vinyl butryl paint system shall be used. Manufacturer's recommendation shall be followed regarding the paint system, exposed to moderately to severe corrosive condition and subject to acid/alkali spillage & fumes, shall be followed.

2.03.00 Protection

Furniture and other movable objects, equipment, fittings and accessories shall be moved, protected and replaced upon completion of work. All stationary equipment shall be well covered so that no paint can fall on them. Work finished by other agencies shall be well protected. All protections shall be done as per instructions of the Engineer.

2.04.00 Cleaning up

In addition to provisions in general conditions the Contractor shall, upon completion of painting etc. remove all marks and make good surfaces, where paint has been splashed or splattered, including all equipment, fixtures, glass, furniture, fittings etc. to the satisfaction of the Engineer.

3.00.00 ACCEPTANCE CRITERIA AND TESTING

a) All painted surfaces shall be uniform and pleasing in appearance.

b) All varnished surfaces shall be of uniform texture and high glossy finish.

c) The colour, texture etc. shall match exactly with those of approved samples.

d) All stains, splashes, and splatters of paints and varnishes shall be removed from surrounding surfaces.

Testing

a) As, each part of the work is under progress, i.e. preparation of surface, providing primer, providing different coats of finishing paints, it shall be passed by the Engineer. Variation from the drawings or specification or standard etc. shall not be accepted. The Contractor shall ascertain from the Engineer as to which parts will be inspected and passed from time to time. The Contractor shall provide all necessary arrangement for inspection of the painting work during its different working phase. The Contractor shall provide necessary scaffolding, approach for inspection of the above as per direction and satisfaction of the Engineer. All the necessary cost for scaffolding, approach, platform, lighting arrangement testing and inspection shall be borne by the Contractor. Such inspection and testing will not, however, exonerate the Contractor from his responsibilities for proper workmanship, material etc.

b) The Contractor shall carry out all sampling and necessary testing in accordance with the relevant Indian Standards and shall conduct such tests as called for by the Engineer. Where no specific testing procedure is mentioned in the relevant codes, the tests shall be carried out as per the prevalent accepted Engineering practice as per the direction of the Engineer. Tests shall be done in a laboratory, approved by the Engineer, and cost of testing shall be borne by the contractor.

c) Material/workmanship unsuitable for acceptance shall he removed and replaced by the Contractor. The work shall be redone as per Specification of the contract and direction of the Engineer without extra cost to owner.

4.00.00 I.S. CODE

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS: 348	Specification for French polish
IS: 427	Specification for Distemper, dry colour as required.
IS: 428	Specification for Distemper oil emulsion, colour as required.
IS: 1477 (I & II)	Code of Practice for painting of ferrous metal in buildings.

IS: 2338 (I & II)	Code of Practice for finishing of wood and wood based materials.
IS: 2339	Specification for Aluminium, Paints for general purposes in dual containers.
IS: 2395	Code of Practice for painting concrete, masonry, and Plaster surface.
IS: 2932	Specification for enamel, exterior type-1.
IS: 5410	Specification for cement paint, colour as required.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall be unit rates for complete items described in the "Schedule of Items".

Rate shall include cleaning, preparation of surface, supply and application of primer, painting and providing all protection and scaffolding required at site.

5.02.00 Measurements

Painting over the concrete/masonry/wooden surface shall be measured net (on the surface area on which it is applied) in Sqm.

No deduction shall be made for opening not exceeding 0.5 Sqm and ends of beams, joints, etc. also no payment shall be made for reveals, jams, soffits, sill of these openings.

50% deduction shall be made for opening exceeding 0.5 Sqm but not exceeding 3.0 Sqm each and no addition shall be made for reveals, jams, soffits, sills etc.

In case of opening exceeding 3.0 Sqm each, deduction shall be made for opening but jams, soffits, and reveals shall be measured and paid for.

Corrugated surfaces shall be measured flat and measured area shall be increased by 15%.

Painting of structural steel works shall be measured in M.T. of fabricated steel (as per section D-17 clause 6.02.00 i.e. Mode of measurement of technical specification for fabrication of structural steel works) unless specified otherwise.

VOLUME: II B

SECTION - D

SUB-SECTION – D12

FLOOR FINISH AND ALLIED WORKS

SPECIFICATION NO. PE-TS-999-600-C012

Maharatna Company

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	4
3.00.00	ACCEPTANCE CRITERIA	20
4.00.00	I.S. CODES	21
5.00.00	RATES AND MEASUREMENTS	21

FLOOR FINISH AND ALLIED WORKS

1.00.0 SCOPE

This section covers furnishing, installation, finishing, curing, testing, protection, maintenance till handing over various types of floor finishes, and allied items of work as listed below

a) In Situ Finishes

i) Integral finish to concrete base

ii) Terrazzo finish

iii) Granolithic finishes

iv) Patent Stone

v) Metallic Hardener like “Ironte”/Hardonate Finish

vi) Mastic Asphalt finishes

vii) Chemical Resistant finish

b) Tiled Finishes

i) Terrazzo tile

ii) Chequered tile

iii) Glazed tile

iv) Tesse rae (Mosaic etc.)

v) Chemical Resistant

vi) Rubber, Vinyl etc.

vii) Stone Slab including Kota Stone.

1.01.00 Base

The base to receive the finish is covered under other relevant specifications.

1.01.01 Sequence

Commencement, scheduling and sequence of the finishing works shall be planned in detail and must be specifically approved by the Engineer in view the activities of other agencies working in that area. However, the Contractor for the finishing items shall remain fully responsible for all normal precautions and vigilance to prevent any damages whatsoever till handing over.

2.00.00 INSTALLATION

2.00.01 Special Materials

Basic materials are covered elsewhere under the Specification. In general, all such materials shall be as per relevant Codes where available. In all cases these materials shall be of the best quality available indigenously unless specified otherwise.

The materials for finishing items must be procured from well-reputed specialized manufacturers and on the basis of approval of samples by the Engineer. The materials shall be ordered, procured and stored well in advance to avoid compulsion to use substandard items to maintain in the construction schedule.

2.00.02 Workmanship

Only workers specially experienced in particular items of finishing work shall be engaged, where such workers are not readily available, with the Engineer's permission, experienced supervisors recommended by the manufacturer shall be engaged. In particular cases where the Engineer so desires the Contractor shall get the finishing items installed by the manufacturer.

2.00.03 Preparation of the Base Surface

The surface to be treated shall be thoroughly examined by the Contractor. Any rectification necessary shall be brought to the notice of the Engineer and his approval shall be taken regarding method and extent of such rectification work.

For all types of flooring, skirting, dado and similar locations, the base to receive the finish shall be adequately roughened by chipping, raking out joints and cleaning thoroughly all dirts, grease etc. with water and hard brush and

detergent if required, unless otherwise directed by the manufacturer of any special finishing materials or specifically indicated in this specification.

To prevent of water from the finishing treatment the base shall be thoroughly soaked with water and all excess water mopped up.
The surface shall be bone dry where adhesives are used for fixing the finishes.

Prior to commencement of actual finishing work, the approval of the Engineer shall be taken as per the acceptability of the surface.

2.01.00 In Situ Finishes

2.01.01 Integral Finish to Concrete Base

While the surface of the concrete laid as per specification for 'Cement Concrete' has been fully compacted and levelled but the concrete is still `green' thick slurry, made with neat cement shall be applied evenly and worked in with iron floats. When the slurry starts to set it shall be pressed with iron floats to have a firm compact smooth surface without trowel mark or undulations. This finish shall be as thin as possible by using 2.2 kg. of cement per Sq.M. of area.

The surface shall be kept in shade for 24 hours and then cured for at least 7 days continuously by flooding with water. The surface shall not be subjected to any load or abrasion till 21 days after lying.

As desired by the Engineer the surface, while still 'green' shall be indented by pressing strings, the marking shall be of even depth, in straight lines and the panels shall be of uniform and symmetrical patterns.

2.01.02 Terrazzo Finish in Situ

It shall consist of an underbed and a topping laid over an already laid and matured concrete base.

a) Thickness

Unless otherwise specified the total thickness of the 'finish shall be minimum 40 mm for horizontal and 25 mm for vertical surface of which the topping shall be not less than 10 mm. While the topping shall be of uniform thickness the underbed may very in thickness to provide necessary slopes. The vertical surface shall project out 6 mm from the adjacent plaster or other finish. Necessary cutting into the surface receiving the finish shall be done to achieve the specified thickness. All junctions of vertical with horizontal shall be rounded neatly to uniform radius of 25 mm.

b) Mix

i) Underbed

The underbed for floors and similar horizontal surfaces shall consist of a mix of 1 parts cement, 1½ parts sand and 3 parts stone chips by volume. For vertical surfaces the mix shall consist of 1-part cement to 3 parts sand by volume. The sand shall be coarse. The stone chips shall be 10 mm down well graded. Only sufficient water to be added to give a workable consistency.

ii) Topping

The mix for the topping shall be composed of cement, colour Pigment, marble dust and marble chips. Proportions of the ingredients shall be such as to produce the terrazzo of colour texture and pattern approved by the Engineer. The cement shall be white or gray or a mixture of the two to which pigment shall be added to achieve the desired colour. To 3 parts of this mixture 1-part marble powder by volume shall be added and thoroughly mixed dry. To 1 part of this mix 1 to 1½ parts of marble chips by volume shall be added and thoroughly mixed dry again.

The pigment must be stable and nonfading. It must be very finely ground. The marble powder shall be from White marble and shall be finer than IS Sieve No.: 30. The size of marble chips shall be between 1 mm to 20 mm. Sufficient quantity to cover each visible area shall be prepared in one lot to ensure uniform colour. Water to make it just workable shall be added to a quantity that can be used up immediately before it starts to set.

c) Laying

The underbed shall be laid in panels. The panels shall not be more than 5 Sq.M. in area of which no side shall be more than 2.5 M. long. For exposed locations the maximum area of a panel shall be 2.0 Sq.M. The panel shall be laid in alternate bays or chequered board pattern. No panel shall be cast in contact with another already laid until the latter has contracted to the full extent.

Dividing strips made of aluminium or glass shall be used for forming the panels. The strips shall exactly match the total depth of underbed plus topping.

After laying, the underbed shall be levelled compacted and brought to proper grade with a screed or float. The topping shall be laid after about 24 hours while the underbed is still somewhat “green” but firm enough to receive the

topping. A slurry of the mixture of cement and pigment already made shall be spread evenly and brushed in just before laying the topping. The topping shall be rolled for horizontal areas and thrown and pressed for vertical areas to extract all superfluous cement and water and to achieve a compact dense mass fully bonded with the underbed. The surface of the topping shall be trowelled over, pressed and brought to a smooth dense surface showing a minimum 75% area covered by marble chips in an even pattern of distribution.

d) Curing

The surface shall be left for curing for about 12 to 18 hours and then cured by allowing water to stand on the surface or by covering with wet sack for four days.

e) Grinding and Polish

When the surface has sufficiently hardened it shall be watered and ground evenly with rapid cutting coarse grade (no.80) grit blocks, till the marble chips are exposed and the surface is smooth. Then the surface shall be thoroughly washed and cleaned. A grout with already prepared mixture of cement and pigment shall be applied to fill up all pinholes. The surface shall be cured for 7 days by keeping it moist and then ground with fine grit blocks (no.: 120). It shall again be cleaned with water, the slurry applied again to fill up any pinholes that might have appeared and allowed to be cured again for 5 days. Finally, the surface is ground a third time with very fine grit blocks (no.: 320) to get smooth surface without any pinhole. A suitable machine shall do the grinding. Where grinding machine cannot be used hand grinding may be allowed when the first rubbing shall be with carborundum stone of coarse grade (no.:60), second rubbing with medium grade (no.: 80) and final rubbing and polishing with fine grade (no.: 120). The surface shall be cleaned with water, dried, and covered with soil free, clean sawdust if directed by the Engineer. The final polishing shall be postponed till before handing over if desired by the Engineer. Just before handing over the surface shall be dusted with oxalic acid at the rate of 0.33 gm. per. Sq.M., water sprinkled on to it and finished by buffing with felt or hessian bobs. The floor shall be cleaned with soft moist rag and dried. However, all excess wax polish to be wiped off and the surface to be left glossy, but not slippery.

2.01.03 Granolithic Finish

Granolithic finish shall either be laid monolithically over base concrete or separately over hardened base concrete.

a) Thickness

The finish shall be average 20 mm and minimum 12 mm thick, unless specified otherwise.

b) Mix

The mix shall consist of 1-part cement, 1-part coarse sand, 2 parts coarse aggregate by volume. The coarse aggregate shall be very hard like granite and well graded between 6 mm and 12 mm. Minimum quantity of water to get workability shall be added.

c) Laying of Monolithic Topping

The concrete base shall be laid as per specification “Cement Concrete” and levelled upto the required grade. The form shall remain sufficiently protruding to take the finish.

Within about 3 hours of laying the base while it is still fully -green- the topping shall be laid evenly to proper thickness and grade. If considered necessary, the surface ‘of the base shall roughened by wire brushing. Unless manual operation is permitted by the Engineer, mechanical vibrators of suitable design shall be used to press the topping firmly and work vigorously and quickly secure full bond with concrete base.

The laitance brought to the surface during compression shall be removed carefully without disturbing the stone chips. The surface shall then the lightly trowelled to remove all, marks. When sufficiently set, hand trowelling shall be done to secure a smooth surface without disturbing the stone chips.

For large areas the laying shall be in panels of maximum 25 Sq.M. area. The panels shall be laid in chequered board pattern.

d) Laying of Topping Separately on Hardened Base

The base concrete shall be prepared as stated in clause 2.00.03 and a slurry of neat cement applied just prior to laying the granolithic concrete mix (1:1:2). The method of compaction etc. shall be same as for monolithic topping.

Curing

Immediately after laying, the finish shall be protected against rapid drying. As soon as the surface had hardened sufficiently, it shall be kept continuously moist for at least 10 days by means of wet gunny bags or pounding of water on the surface. The floor shall not be exposed to heavy traffic during this period.

f) Grinding

If grinding is specified, it shall start only after the finish has fully set. Clause 2.01.02 (e) shall be followed. However, the Engineer shall decide upon the ultimate polish required.

g) Finishing

Where specified, sodium, silicate or magnesium or zinc silico fluoride treatment shall be done. The number of coats to be applied shall be as per approved drawings or as instructed. The concentration and method of application of the solutions shall be as specified in IS: 5491.

2.01.04 Patent Stone

It shall consist of an underbed and a topping laid on an already laid and matured concrete base.

a) Thickness

The patent stone finish shall have thickness as stipulated under clause 2.01.02 (a) except that the topping shall be 12 mm thick.

b) Mix

i) Underbed

The mix shall be as stipulated under clause 2.01.02 (b).

ii) Topping

The mix for the topping shall consist of 1-part cement and 2-part stone aggregate 6mm nominal size by volume.

c) Laying

The Patent Stone finish including the underbed shall be laid in alternate bays or in Chequered board pattern. No panel shall be cast in contact with another already laid till the contraction of the latter has already taken place.

The maximum area of each panel shall be 3 Sq.M. of which no side shall be more than 2 M. long.

A cement grout shall be applied and worked into the surface to receive the finish; the underbed then laid, compacted, and leveled to proper grade with

a screed or float. The topping shall be applied evenly on the underbed while it is not fully set but firm enough and rolled and pressed to get full bond. The topping shall be trowelled to a dense finish to the satisfaction of the Engineer. All trowel marks shall be mopped out with a soft cloth to give a clean smooth surface.

After the surface is sufficiently set, the finished floor shall be kept moist for 7 days for curing. If desired the finish shall be polished as directed by the Engineer.

2.01.05 Metallic Hardener Like 'Ironite'/ `Hardonate' Finish

This will consist of a topping (incorporating iron particles) to bond with concrete base while the latter is `green'.

a) Thickness

Unless otherwise specified the metallic hardener finish shall be of 12 mm depth.

b) Material

The hardening compound shall be uniformly graded iron particles free from non-ferrous metal impurities, oil, grease, sand soluble alkaline compounds or other injurious materials when desired by the engineer, actual samples shall be tested.

c) Mix

Proportion of the metallic hardener shall be as specified or as indicated by the manufacturer. However, in absence of any such direction 1 part metallic hardener shall be mixed dry, with 4 parts cement, by weight. To this mixture 6 mm nominal size stone chips shall be added in proportion of 1-part cement (mixed with hardener) to 2 parts of stone chips by volume and uniformly mixed. Minimum quantity of water shall be added to make it workable.

d) Laying

The concrete floor shall be laid as per specification 'Cement Concrete' and levelled upto required grade. The forms, if any, shall remain sufficiently projecting to make the finish. The surface shall be roughened by wire brash as soon as possible.

The finish shall be laid while the concrete underbed is still very `green' within about 3 hours of laying of the latter. The finish shall be of uniform thickness and even dense surface without trowel marks, pin holes etc. This topping layer shall be pressed firmly and worked vigoursly and quickly to secure full bond with the concrete base. Just when the initial set starts the surface shall be finished smoothened with steel trowel.

The finished floor shall be cured for 7 days by keeping it wet.

2.01.06 Mastic Asphalt Finish

This is a one-layer treatment on concrete or brick base.

a) Thickness

The thickness shall be as specified in the drawing.

b) Materials

Bitumen shall be industrial Bitumen of the grade 90/15 and 75/15 conforming to IS: 702.

Mineral filler shall be dry stone dust passing through 75 micron IS Sieve.

Fine aggregate shall be crushed and graded natural limestone or other hard work.

Coarse aggregate shall be crushed siliceous stone or other approved aggregate 6 mm stone chips shall be used for finish upto 20 mm thick & 10 mm chips for thicker finish.

c) Composition

Bitumen mastic shall conform IS: 1195 and shall be either brought to site in blocks weighing about 25 Kg or prepared at site. If brought in blocks, these shall be remelted in mechanically agitated mastic cookers and coarse aggregate, preferably preheated fed in successive portions until the complete change is thoroughly, incorporated. At no stage during the remelting and mixing process, shall the temperature exceed 205°C.

d) Laying

The hot mastic shall be laid on dry base surface cleaned thoroughly by wire brushing and sweeping. The mastic shall be levelled and when cooled to some extent shall be finished with a wooden float with addition of small

quantity of fine sand if required. No load shall be allowed till the finish has cooled to normal temperature.

The mastic shall be laid in suitable panels of about 1.5 Sq.M. in area each formed by formers. Succeeding panels shall be laid overlapping the finish panel so as to melt its edges and form a continuous finish without joint.

2.01.07 Chemical Resistant in Situ Finish

Chemical resistant in situ finish shall be as epoxy resin with suitable filler material over a primer. The minimum thickness shall be 6 mm. About its performance the Engineer shall have to be fully satisfied by test results and examination of similar treatment already in existence. The contractor shall get it done by a specialized Manufacturer and get guarantee of performance from the organization and pass it on to the Owner in addition to his own guarantee.

2.02.00 Tiled Finish

These shall include finish tiles, stone slabs, and similar manufactured or natural items over already laid and matured base of concrete or masonry by means of an underbed or an adhesive layer.

2.02.01 Terrazzo Tile Finish

The finish will consist of manufacture terrazzo and an underbed.

a) Thickness

The total thickness including the underbed shall be minimum 40 mm for floors 30 mm for walls unless otherwise specified.

The skirting, dado and similar vertical surfaces shall project out 6 mm uniformly from the adjacent plaster or other wall finishes. The necessary cutting into the surface receiving the tiled finish, to accommodate the specified thickness shall be done.

b) Tiles: Terrazzo

The tiles shall, unless specifically permitted in special cases be machine made under quality control in a shop. The tile shall be pressed hydraulically to a minimum of 140 Kg. per Sq.cm.

Each tile shall bear on its back permanent and legible trademark of the manufacturer. All angles of the tiles shall be right angles all arises sharp and true, colour and texture of the wearing face uniform throughout. Maximum tolerance allowance length and breadth shall be ± 1 mm and the

thickness ± 3 mm. Face of the tile shall be plane, free from pinholes and other blemishes.

The tiles shall be composed of a backing and topping. The topping shall be of uniform thickness not less than 10 mm.

The total thickness including the topping shall be as specified but not less than 20 mm in any case.

The backing shall be composed of 1 part ordinary gray cement and 3 parts of stone chips by weight mixed with water.

The topping shall be as specified under clause 2.01.02 (b).

The tile shall be cured at the shop for at last 14 days before delivery to the site. First grinding shall be given to the tiles at the shop before delivery. Tiles shall be packed properly to prevent damage during transit and storage. The tiles must be carefully stored to prevent staining by damp, rust, oil, and grease or other chemicals.

Tiles made in each batch shall be kept and used separately so that colour of each area of the floor may remain uniform.

The manufacturer shall supply along with the tiles the grout mix containing cement and pigment in exact proportions as used in topping of the tiles. The containers for the grout mix shall be suitably marked to relate it to the particular type and batch of tiles.

c) Mix: Underbed

The underbed for floor and similar horizontal surfaces shall be 1-part lime putty: 1 part surkhi: 2 parts coarse sand by weight mixed with sufficient water to form a stiff workable mass. For skirting and dado and all vertical surfaces it shall be about 12 mm thick and composed of 1-part cement and 3 parts coarse sand by weight.

d) Laying

The underbed mortar shall be evenly spread and brought to proper grade and consolidated to a smooth surface. The surface shall be roughened for better bond. Before the underbed had time to set and while it is still fairly moist but firm, cement shall be hand dusted over it or a cement slurry applied and the tiles shall immediately be placed upon and firmly pressed by wooden mallet on to the underbed until it achieves the desired level. The tiles shall be kept soaked for about 10 minutes just before laying. The

joints between tiles shall be as close as possible and not more than 1.5 mm wide.

Special care shall be taken to check the level of the surface and the lines of the joints frequently so that they are perfect.

When tiles are required to be cut to match the dimensions these shall be sawn and edges rubbed smooth. The location of cut tiles shall be planned in advance and approval of the Engineer taken.

At the junction of horizontal surface with vertical surface the tiles on the former shall enter at least 12 mm under the latter.

After fixing, the floor shall be kept moist and allowed to mature undisturbed for 7 days. Heavy traffic shall not be allowed.

If desired dividing strips as specified under Clause 2.01.02(c) may be used for dividing the work into suitable panels.

e) Grinding and Polishing

Procedure shall be same as Clause 2.01.02(e). Grinding shall not commence earlier than 14 days after laying of tiles.

2.02.02 Chequered Tile Finish

The finish shall consist of manufactured gray or coloured cement tiles or terrazzo tiles with chequered face and an underbed laid over concrete or brick surface.

a) Thickness

Thickness shall be same as in clause 2.02.01 (a).

b) Tiles: Chequered

The tiles shall have chequers not less than 2.5 cm. c/c and not more than 5 cm. c/c. Depth of grooves shall be not less than 5 mm. The grooves shall be uniform and straight.

The tiles shall conform to clause 2.02.01 (b) except that these may have the topping in terrazzo or plain gray cement or colour pigment added to cement.

c) Under-bed
As per clause 2.02.01 (c).

d) Laying
As per clause 2.02.01 (d).

e) Grinding and Polishing

As per clause 2.02.01 (e) except that the tiles shall be ground and polished by hand and after laying taking special care in polishing the grooves properly and uniformly.

2.02.03 Glazed Tiles Finish

This finish shall be composed of glazed earthenware tiles with an underbed laid over a concrete or masonry base.

a) Thickness

The total thickness shall be between 20mm and 25mm including the underbed.

The tile finish on vertical surface shall project out 6 mm uniformly from the adjacent plaster or other wall finishes. The necessary cutting into the surface receiving the finish, to accommodate the specified thickness shall be done.

b) Tiles: Glazed

The tiles shall be of earthenware, covered with glaze white or coloured, plain or with designs, of 150 mm x 150 mm nominal sizes and 5.5 mm to 6 mm on thick unless otherwise specified. The tolerance shall be ± 1.5 mm for length and breadth and ± 0.5 mm for thickness specials like internal and external angles; beads, covers, cornices, corner pieces etc. shall match. The top surface of the tiles shall be glazed with a gloss or matt, unfading stable finish as desired by the Engineer. The tiles shall be flat and true to shape. The colour shall be uniform and fractured section shall be fine grained in textures, dense and homogeneous. The tiles shall be strong and free from flaws like cracks, craze, specks, crawling, etc. and other imperfections. The edge and the underside of the tiles shall be completely free from glaze and the underside shall have ribs or indentations for better anchorage with the fixing mortar.

The coloured tiles, when supplied, shall preferably come from one batch to avoid difference in colour.

c) Mix: Underbed

The mix for the underbed shall consist of 1-part cement and 3 parts coarse sand by weight mixed with sufficient water or any other mix if specified.

c) Laying
Same as clause 2.02.01 (d).

e) Finishing

The joints shall be cleaned and flush pointed with white cement and cured for 7 days by keeping it wet. The surface shall be cleaned with soap or suitable detergent, washed fully, and wiped with soft cloth to prevent scratching before handing over.

2.02.04 Tesserae Finish (Mosaic etc.)

This finish consists of manufactured vitreous, glass, ceramic or similar hard small pieces set in an underbed over a concrete or masonry surface, already laid.

a) Thickness

The total thickness including the underbed shall be between 16 mm & 25 mm.

b) Tesserae Finish

These shall usually be 6 mm thick small piece of ceramic vitreous china, tinted glass, or similar hard wearing, strong, and durable material in desired shapes and sizes and patterns.

The supply shall come in the desired pattern in full or sections conveniently for handling, stuck to pieces of strong thick paper on the surface to be exposed. The gum used for this purpose must be water soluble and non-staining. The sections shall be properly marked to avoid mistakes and master drawing shall be available at the site for guidance.

c) Mix: Underbed
Same as clause 2.02.03 (c)

d) Laying

The specification for laying if given by the manufacturer of the item shall be followed provided it is approved by the Engineer. Otherwise clause 2.02.03 (d) shall generally be followed. However, instead of gray cement the slurry shall be made with white cement to fix the panels. The paper-

mounted patterns in sections shall be carefully placed and pressed in position true to lines and levels. Earliest possible the paper shall be peeled off and surface examined and cleaned, joints flush pointed with white cement and cured for 7 days by keeping it wet.

2.02.05 Chemical Resistant Tiled Finish

This shall include all verities of special tiles used for specific chemical resistance function and an underbed over already laid concrete or masonry.

a) Tiles

The chemical resistant tiles shall be of the best indigenous Manufacture unless otherwise specified and shall be resistant to the chemical (both acid and alkali). The tiles shall have straight edges, uniform thickness, plain surface, uniform nonfading colour, and textures.

Usually the chemical resistant tiles shall not absorb water more than 2% by weight. The tiles shall have at least compression strength of 700 Kg/cm^2. The surface shall be abrasion resistant and durable.

b) Laying

The mortar used for setting or for underbed these tiles shall be durable, strong and chemical resistant epoxy mortar. The grout, which shall be to the full depth of tile, shall have equal chemical resistant properties. Joints shall be pointed if so desired. The setting and fixing shall be according to the manufacturer's specification approved by the Engineer.

2.02.06 Rubber, Vinyl, or Vinyl Asbestos Tiles Finish

This shall include various types of tiles manufactured from rubber, vinyl etc. set with an adhesive on concrete or masonry base. An underbed may be required to secure desirable surface and grade.

a) Thickness

The thickness of the tiles shall be as incorporated in drawing.

b) Tiles

Unless otherwise desired the tiles shall be squares of approved dimensions. The tolerance in dimensions shall be ± 1.5 mm.

The face of the tiles shall be free from porosity, blisters, cracks, embedded foreign matters or either physical defects which affect appearance or serviceability. All edges shall be cut true and square. The colour shall be nonfading and uniform in appearance, insoluble in water and resistant to alkalies, cleaning agents and usual floor polishes.

Each tile shall be marked on the back legibly and indelibly with manufacturer's trademark, the thickness, sizes, batch number, and date of manufacturer.

Tiles shall be delivered securely packed and stored in clean, dry well ventilated place at a temperature near about to that the tiles shall be called upon to stand ultimately.

Adhesive to be used for sticking the tiles shall be approved by the tile manufacturer. The adhesive shall have a short drying time and long life in addition to toughness.

c) Mix: Underbed

The underbed where required to make up the specified thickness or to give the required grade or to get the right type of surface shall be composed of 1 part like putty:1-part cement: 3 parts coarse sand mixed with just sufficient water to make it workable.

d) Laying

The tiles shall be kept in the room to be tiled for at least 24 hours to bring them to the same temperature as the room. For air-conditioned space, the air-conditioning shall be completed before tiling is taken up.

The surface to receive this finish shall be firm even textured but not too smooth, without undulations and other deficiencies. If an underbed is laid the same shall be cured for at least 7 days by keeping it moist and then fully dried.

The surface shall be thoroughly cleaned. All loose dust particles shall be removed. Oil and grease if any shall be completely cleaned by use of detergent.

The adhesive shall be applied to fully dry surface in desired thickness uniformly. The adhesive shall also be applied to the backs and edges of the tiles and allowed to surface dry. The tiles shall be placed neatly on the surface exactly to the approved pattern and set with a suitable tool. If the edges tend to curl, weights are to be used to keep the edges down. Special care shall be taken to avoid formation of air pockets under the tiles. The

joints shall be very fine. Any adhesive squeezed out through the joints shall be removed immediately.

e) Finishing

If any adhesive mark is there on the surface a soft cloth soaked in solvent shall be used to wipe it off. The surface shall be cleaned with soft soap, dried, and polished with an approved type of polish just before handing over.

2.02.07 Stone Slab Finish: Marble, Stone, and Similar Fine Grained Stone including Kota stone

a) Thickness

The underbed shall be minimum 12 mm and average 20 mm thick. The slabs will be 20 mm thick.

b) Stone Slab

The stone slabs shall be made from selected stock, which is hard, sound, homogeneous and dense in texture and free from flaws. Angles and edges shall be true, square, and free from chipping and surface shall be plane. The slabs shall preferably be machine cut to the required dimensions. Tolerance of ± 5 mm in dimensions and ± 2 mm in thickness will be allowed. Unless specified the slabs shall be minimum 300 mm x 300 mm.

The stone slabs shall come from specific regions and in specified quality with top surface fine chisel dressed. All sides shall also be fine chisel dressed to the full depth to allow finest possible joints.

The slabs shall be delivered to the site well protected against damages and stored in dry place under cover.

c) Mix: Underbed
Same as clause 2.02.01 (c).

d) Laying

The sides and top surface of the slabs shall be machine rubbed or table rubbed with coarse sand stone and washed before laying.

The underbed mortar shall be evenly spread and brought to proper level on the area under each slab. The slab shall be laid over the underbed, pressed, and tapped down with wooden mallet to the proper level. The slab shall then be lifted and the underbed corrected as necessary and allowed to

stiffen a little. Next, thick cement slurry shall be spread over the surface. The edges of the slab shall be buttered with slurry of cement, gray / white / mixed with pigment matching the colour of the stone slabs. The slab shall

be gently laid and tapped with wooden mallet to bed properly to a very fine joint and to the required level. All surplus cement slurry shall be removed and the surface mopped clean with wet soft cloth. The laid finish shall be cured for 7 days by keeping it wet.

e) Polishing, Finishing

Fine chiselling shall be done to remove the slight undulations that usually exist at the joints. The polishing and finishing shall be done as specified under clause 2.02.01 (e). However, the joints shall be so fine in the case of stone slabs that grouting shall not be called for.

2.02.08 Stone Slab Finish: Sand Stone and Similar Coarse Grained Stone Finish

Generally, clause 2.02.07 shall be followed except that the workmanship and finish shall not be fine as which are explained hereunder.

The slabs shall be rough chiselled or fine chiselled as specified. Tolerance may be allowed upto ± 6 mm for rough finish, but no sharp unevenness and shall be allowed. For fine chiselling the unevenness shall be limited to ± 2 mm. The sides shall be chisel dressed at least to half slab depth so that the maximum deviation from straight line shall be within 25 mm. Beyond this depth the edge may be slightly splayed.

The joint thickness shall be kept limited to 5 mm in case of rough finish and 3 mm in case of fine finish unless wider joints are specified. The joints shall be grouted with white or coloured cement. If fine joints in the flooring are specified, the edges of slabs shall be cut in such a way that it shall form an inverted 'Y'.

3.00.00 ACCEPTANCE CRITERIA

The finish shall be checked specially for:

a) Level, Slope, Plumb as the case may be

b) Pattern and Symmetry

c) Alignment of joints, dividing strip etc.

d) Colour, texture

e) Surface finish

f) Thickness of joints

g) Details at edges, junctions etc.

h) Performance

i) Precautions specified for durability

4.00.00 I.S. CODES

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS: 777	:	Glazed earthenware tiles
IS: 1196	:	Code of practice for laying bitumen mastic flooring.
IS: 1197	:	Code of practice for laying of rubber floors
IS: 1237	:	Cement concrete flooring tiles
IS: 1443	:	Code of practice for laying and finishing of cement concrete flooring tiles.
IS: 2114	:	Code of practice for laying in situ terrazzo floor.
IS: 3461	:	PVC asbestos floor tiles
IS: 4860	:	Specification for acid resistant bricks
IS: 5518	:	Code of practice for laying of flexible PVC Sheet and tile flooring.
IS: 5491	:	Code of practice for laying in situ granolithic floor topping.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall be for the complete work (including dividing strips, Ironite, metals, tiles etc. if any) as per the schedule of items. Rates shall be applicable for application on horizontal and vertical surfaces at all elevations and for all types of work including stairs tread and riser, laying in desired pattern and panels, cost of specials (if any) rounding of corners, mouldings etc.

Rates shall be including provision of side shuttering (if required) for casting of floor in alternate panels and or without dividing strips.

5.02.00 Measurement

The finished surface shall be measured in Sqm for area unless otherwise specified. Deduction shall not be made for opening or embedded articles having area not exceeding 0.1 Sqm.

VOLUME: II B

SECTION - D

SUB-SECTION – D13

SHEET WORK IN ROOF AND SIDING

SPECIFICATION NO. PE-TS-999-600-C013

Maharatna Company

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	3
3.00.00	ACCEPTANCE CRITERIA	5
4.00.00	I.S. CODES	5
5.00.00	RATES AND MEASUREMENTS	6

SHEET WORK IN ROOF AND SIDING

1.00.00 SCOPE

This section covers supply, cutting & fabrication and erection of corrugated/plain asbestos, corrugated galvanized iron, aluminum, permanently colour coated troughed zinc-aluminium alloy coated M.S. sheet or other sheet for covering to roof and sides at various elevations as specified.

2.00.00 INSTALLATION

2.01.00 Storage of Materials

All materials shall be stored by the Contractor in proper way to prevent all damage.

2.02.00 Workmanship

The workmanship shall be according to best construction practice to give a watertight finish to the satisfaction of the Engineer. Fixing of gutters and down pipes shall be according to IS: 2527.

2.02.01 Asbestos Sheeting

Asbestos sheets of profiles as specified shall be fixed with minimum 150 mm end lap and side laps as per manufacturer's specification. Hook bolts or J-bolts shall be 8 mm dia. at 305 mm centres. Six (6) mm dia. galvanized iron seam bolt and nut with G.I. flat washers and bitumen washers shall be used for stiching ridge cappings, corner pieces, ventilators, north light curves etc.

2.02.02 C.G.I. Sheeting and Aluminium Sheeting

Side laps shall be 2 corrugations for roof and one corrugation for side sheeting. End laps shall be minimum 150 mm for roof and 100 mm for side sheeting. In ridges and hips where plain sheets are used, the end laps shall be minimum 100 mm. Holes in C.G.I. sheets shall preferably be made on the ground. The sheets should be placed on purlins/trestles and holes punched in the ridge of the corrugation from the outside inward for obtaining proper seating of limpet washers. Sheets shall be secured to sheet framing by 8 mm dia. galvanised iron hooks or J-bolts and maximum spacing of the bolts shall be 305 mm. The length of the hook or J-bolts shall be to suit the sections of the bearers. Sheets shall also be bolted at the ends at every third corrugation with 6 mm dia. galvanized iron seam bolts and G.I. flat washers and bituminous washers.

2.02.03 Fibre Glass Reinforced Plastic Sheeting

This shall be of thickness and profile as specified. Colour and light transmittance shall be as mentioned. Where used in conjunction with C.G.I. or asbestos sheeting, the end and side laps and fixing device shall be same as used for general sheeting. Where used in lieu of glass, the fixing shall be by means of timber or metal glazing beads. In all cases, the installation shall be completely watertight and able to withstand the designed wind-pressure.

2.02.04 PERMANENT COLOUR COATED (SANDWICHED INSULATED) METAL CLADDING SYSTEM

i. Troughed zinc-aluminium alloy coated (both sides) M.S. sheet having 0.6mm minimum thickness (or high tensile steel sheet having minimum yield strength of 350 Mpa of 0.5mm minimum thickness) shall be used on external face (outer face) of cladding system. Weight of coating shall not be less than 150 gm/sq.m. The outer side (exposed face) shall be permanently colour coated with Polyfluro Vinyl Coating (PVF_2) of Dry Film Thickness (DFT) 20 microns (minimum) over primer. Inner side of external sheet shall be provided with suitable pre-coating of minimum 7 microns.

ii. Galvanised M.S. sheets of minimum 0.6mm thickness shall be used as inner liner (internal face) of cladding system. The exposed face shall be permanently colour coated with silicon modified polyester paint of DFT 20 microns (minimum) over primer. Inner face of external sheet shall be provided with suitable pre-coating of minimum 7 microns. The rate of galvanization shall not be less than 275 gm/sqm.

iii. The permanent colour coated sheet shall meet the general requirements of IS:14246 and shall conform to class 3 for the durability.

iv. Inner sheet shall be fixed directly to side runners and Z spacers made out of at least 2 mm thick galvanized steel sheet of grade 375 as per IS:277. Inner sheet shall be fixed at the rate not more than 1.50M centre to centre to hold the insulation and external sheeting. The fasteners shall be of high quality corrosion resistant grade of self tapping / self drilling type provided with suitable cap.

v. The insulation shall be of bonded mineral wool of minimum thickness 50mm conforming to IS:8183, having a density of 32 Kg/cum. for glass wool & 48 Kg/cum. for rock wool.

2.02.05 PERMANENT COLOUR COATED (NON-INSULATED) METAL CLADDING SYSTEM

i. Troughed zinc-aluminium alloy coated not less than 150 gm/sq.m M.S. sheets having 0.6 mm minimum thickness (or High tensile steel sheet having minimum yield strength of 350 Mpa of 0.5mm minimum thickness) shall be used for the cladding system. The outer side (exposed face) shall be permanently colour coated with PVF_2 paint of minimum DFT 20 microns over primer and the inner side (internal face) shall be coated with same paint of minimum DFT 12 microns over primer. These shall be fixed directly to runners. The sheets shall meet the general requirement of IS:14246 and shall conform to class 3 for the durability.

ii. **FLASHING, CAPS, TRIM CLOSURES ETC.**

All flashings, trim closures caps etc. required for the metal cladding system shall be made out of plain sheets having same material and coating specification as mentioned above for the outer face of the sandwiched metal cladding.

3.00.00 ACCEPTANCE CRITERIA

The installations shall present a neat appearance and shall be checked for water tightness. The following shall be checked:

a) Side and end laps

b) Absence of cracks, holes or damages in sheet

c) Spacing of bolts

d) Provision of double washers (G.I. and asbestos or bituminous washers)

e) Proper installation of flashing.

4.00.00 I.S. CODE

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS: 3007 : Code of practice for laying of asbestos cement sheets.

IS: 2527 : Code of practice for fixing rainwater gutters and down pipes for roof drainage.

IS: 1626 : Specification for asbestos cement building pipes, gutters and fittings.

IS: 277 : Specification for galvanized steel sheets (plain and corrugated).

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall be unit rate for complete item described in "Schedule of Items" and shall include all wastage.

5.02.00 Measurement

Sheeting work in roof & sides shall be measured in Sq.M. for net area of the work done. Profiled sheeting shall be measured flat and not girthed. Opening less than 0.40 Sqm shall not be deducted. No extra shall be paid for extra labour in cutting and for wastage etc. No payment shall be made for laps, flashings, sealing, fasteners etc. in sheeting works.

VOLUME: II B

SECTION - D

SUB-SECTION – D14

SUSPENDED CEILING

SPECIFICATION NO. PE-TS-999-600-C014

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	INSTALLATION	3
3.00.00	SAMPLES	5
4.00.00	SHOP DRAWINGS	5
5.00.00	ACCEPTANCE CRITERIA	6
6.00.00	RATES AND MEASUREMENTS	6

SUSPENDED CEILING

1.00.00 SCOPE

This section covers supply and installation of suspended ceiling together with the suspension system as shown on drawing or specified in schedule of item with all materials, labour and equipments. The work shall also include providing of openings in the ceiling for lighting, air-conditioning diffusers etc. as shown on drawings or as instructed by the Engineer.

2.00.00 INSTALLATION

2.01.00 Suspension System

2.01.01 General

Suspension system shall consist of the grid supporting the ceiling panels, intermediate runner supports for the grid if any and hangers, wall angles etc. required to suspend the grid or the runners from structural works, slabs and beams.

All members of the suspension system shall be of sufficient strength and rigidity to carry, the ceiling boards or sheets in a true and level plane without exceeding a deflection of 1/360th of their span. All joints in ceiling panels shall run straight and cross joint shall be at perfect right angles. Angle moulds where shown on drawings shall be securely fixed to walls. All drillings of structural concrete and installation of suitable anchoring device for installation including welding of the suspension system shall be included in the rate. All M.S. sections used for supports etc. shall be given one coat of synthetic enamel paint over a coat of red lead primer.

2.01.02 Metal Grid Suspension System

Aluminium grid ceiling system shall be “Bead lock” as manufactured by W A Beard shell and Co. Pvt. Ltd. or Ajit India Limited or approved equal. Steel grid ceiling system shall be 'Jolly Snap Grid' as manufactured by Jolly Board Limited or approved equal.

Steel tees as intermediate members and steel channels, as end pieces will be assembled in the form of grid. Size of tees and channels shall be as required.

The cross-tees shall intersect main tee runners in pattern shown on drawing and positively locked together with intersection members. All perimeter areas shall have tee runners fixed to vertical wall surfaces and end channels shall be fixed to runners leaving return air space between vertical wall and channels,

unless otherwise shown on drawings. Angle cleats or other suitable fixing device shall be fixed to the structural beams above for fixing of hangers. Main runners shall be hung by M.S. flats, angles, rods or 12G or heavier galvanized tie wire hangers at maximum 1.2 metre centres. Extra hangers shall be provided at light fixtures that are supported from the ceiling system. The spacing of main and cross runners shall be as shown on drawings. Turnbuckles shall be provided in M.S. rods for adjustment in levels.

2.02.00 Ceiling Panels

2.02.01 Material

Ceiling panels shall be best quality material in thickness and properties called for in the "Schedule of items". The Contractor shall submit test certificates to the Engineer for approval before bulk supply. The ceiling panels may be of following type:

a) Plaster of Paris board (decorative)

b) Expanded polystyrene insulation board with plastic fascia.

c) Fibre Insulation board.

d) Bonded wooden particle board (Plain and decorative)

e) Glass fibre reinforced polystyrene sheets.

f) Flat asbestos sheets (with plastic fascia).

2.02.02 Installation of Ceiling Panels

Installation of Ceiling panels shall be strictly as per manufacturer's instruction.

For concealed grid system, tiles shall be fixed to the supporting grid in manner shown on drawing or as specified by the manufacturer. Where V joints in tiles are called for in drawings, these shall be in true lines. Where flush surface is required, the joints shall be filled with approved filler material and finished to give a neat uniform surface. Special care shall be taken to neatly finish the ceiling at junctions with walls, light fixtures, diffusers etc.

2.02.03 Aluminium Lineal Ceiling System

Aluminium lineal ceiling system shall be "Luxalon 84C" or approved equal and the installation shall be strictly as per manufacturer's instruction/ specification subject to approval of the Engineer.

Aluminium lineal ceiling shall comprise of plain panels, 84 mm wide and 12.5 mm deep with a 23.9 mm recessed flange, roll formed out of 0.5 mm thick aluminium alloy panels stove enamelled on both sides, fixed on roll-formed carriers made of enamelled 0.95 mm thick aluminium, 32 mm wide and 39 mm deep with prongs to hold panels in the module of 100mm, at maximum spacing 1.2 M centre to centre. The carriers shall be suspended from roof by 4 mm dia. galvanised steel wire hangers with special height adjustment clips made out of spring steel at maximum spacing of 1.2 M c/c. Hangers shall be fixed to roof by 'J' hooks and nylon inserts. 25 mm thick resin bonded mineral wool (spintex 300 or equivalent) insulation bound in polythene shall be laid on top of panels. Lineal ceiling shall be fixed in pattern as per detailed drawings.

3.00.00 SAMPLES

Samples of Ceiling panels and metal suspension system components as noted below shall be submitted for Engineer's approval:

Panels : 3 samples approximately 300 mm square/long each

Suspension System : 3 samples of short length: each of main and secondary system

4.00.00 SHOP DRAWINGS

Shop drawings shall be submitted for approval as required and approval shall be obtained prior to delivery of suspended ceiling components. Shop drawings shall be co-coordinated with all related work and shall show the following information:

a) A reflected ceiling plan of areas indicated to receive the ceiling showing electrical and mechanical features.

b) Typical Intermediate framing for support where required.

c) Hanger fastening details.

d) Panels - unit support at ceiling penetrations.

e) Details of splicing method for main and cross runners.

f) A table indicating load bearing capacity of main and cross runner

g) A note stating that the suspension system member furnished will not deflect more than 1/360 of the span under the indicated loading.

5.00.00 ACCEPTANCE CRITERIA

Finished ceiling shall be at the correct plane and present a pleasing and uniform appearance, free from, sags, warps, disfigured, or damaged board. Cut-outs for light fixtures, diffusers etc. shall be of exact dimensions and in exact locations.

6.00.00 RATES AND MEASUREMENT

6.01.00 Rates

Rates shall be for the complete item called for in the "Schedule of Items". No extra payment will be made for alignment and adjustment of lighting fixtures, air-conditioning diffusers, access panels etc. The rate shall include all cutting and wastage from standard size sheets, runners/carries etc.

6.02.00 Measurement

Actual area of work shall be measured in Sqm correct to second place of decimal. However, no deduction will be made for opening upto 0.25 Sqm. each in area.

VOLUME: II B

SECTION - D

SUB-SECTION – D15

WATER SUPPLY, DRAINAGE AND SANITATION

SPECIFICATION NO. PE-TS-999-600-C015

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	MATERIAL	3
3.00.00	INSTALLATION	6
4.00.00	TESTING AND ACCEPTANCE CRITERIA	17
5.00.00	I.S. CODES	20
6.00.00	RATE AND MEASUREMENT	21

WATER SUPPLY, DRAINAGE AND SANITATION

1.00.00 SCOPE

This section covers supply of all materials labour and incidentals required for supply, laying and installation of under/over ground pipes for water supply, drainage and sanitation with all fittings, fixtures and jointing, construction of ancillary works like manholes, drop connections, gully chambers, septic tank, soak pits, surface drain etc.

The supply and installation of water supply/sanitation fixtures and accessories like water closets, urinals, wash basins, sinks, mirrors, shelves, towel rail, soap container etc. with all fittings, fixtures, water supply/sanitation pipes and water storage tanks etc.

2.00.00 MATERIAL

All materials, fittings, fixtures, and appliances shall be of the best quality conforming to relevant Indian Standard and shall be procured from approved manufacturers. Unless specifically allowed by the Engineer, the Contractor shall submit samples of fittings and fixtures, which will be retained by him for comparison when bulk supplies are received at the site. Ultimate choice of type, model, and manufacturer lies completely with the Engineer.

It shall be the responsibility of the Contractor to procure the materials selected by the Engineer. Hence orders are to be placed with the manufacturers in time, so that the materials are available at the site well ahead of their requirement.

The materials brought to the site, shall be stored in a separate secured enclosure away from the building materials. Pipe threads, sockets, and similar items shall be specially protected till final installation. Brass and other expansive items shall be kept under lock and key. Fragile items shall be checked thoroughly when received at the site and items found damaged shall not be retained at the site.

2.01.01 Pipes and Pipe Fittings

For water supply, galvanised mild steel pipe of medium grade confirming to IS: 1239 shall be used. The galvanising shall not be less than 400gm/sqm of pipe surface area. Galvanising shall be smooth and shall be subjected to testing as per IS: 2633 for uniformity of coating. The zinc coating shall be free from defects.

For Roof drainage and building sanitation works following type of pipe are coved in this Section:

a) Cast Iron pipe

b) Steel pipe (lined, coated with bituminous composition, out coated with cement concrete or mortar or galvanized)

c) Concrete pipe

d) Asbestos cement pipe

e) PVC pipe

f) Stoneware pipe

g) Vitrified pipe

h) Lead pipe (not to be used for portable water)

2.02.01 Fixtures

All material, fittings, fixtures, appliances, accessories shall be of approved quality and shall be procured from reputed brands like Hindustan/Pasriware/ Cera or equivalent or as approved by Engineer. The bidder shall procure the fixtures from the above named reputed manufacturers and shall mention in his bid the type & make of the fixtures he intends to use.

All items brought to the site must bear the manufacturer's identification mark. Procurements shall be made well in advance and should get inspected & approved immediately by the Engineer. All fixtures shall be adequately protected, covered, and plugged till handing over.

All fittings, gratings, fasteners, unless specified otherwise, shall be chromium plated. The chromium plating shall be of grade-2 (10micron thickness) confirming to IS: 4827. Powder coating shall be of approved colour and shall have minimum thickness (DFT) of 20micron. Stainless steel accessories shall be of grade SS-304 and from reputed manufacturer (like Salem Steel) and shall be polished bright finish.

Unless specified in the contract the fixtures shall be as specified hereinafter.

Water closet

a) **European type**

It shall consist of European type glazed vitreous china basin (confirming to IS: 2556, part-II), with siphon open front solid plastic seat and plastic cover, low level glazed stoneware flushing cistern with valve less fittings, supply connections and necessary fittings. All fittings shall be chromium plated. Colour of basin, cistern, seat and cover shall be as approved by the Engineer.

b) **Squatting type**

It shall consist of Orissa pattern glazed vitreous china squatting pan with integral foot rests (confirming to IS:2556, part-III) and high level cast iron flushing cistern with valve less fittings, supply connections and necessary fittings. All fittings shall be chromium plated. The flushing cistern shall be painted as specified by the Engineer.

Urinals

It shall consist of wall type glazed vitreous china urinals (conforming to IS:2556), cast iron automatic flushing cistern complete with supply connections, flush pipe, lead pipes, gratings, traps and all other necessary fittings. Frequency of automatic flushing shall be approximately once every five minutes. For every four urinals (maximum) located together may be served by one cistern of adequately capacity. All fittings shall be chromium plated.

Wash Basin

It shall be made of glazed vitreous china conforming to IS:2556, part-IV. The basin shall be flat back, wall hung by painted cast-iron brackets and complete with hot and cold CP brass faucets with nylon washers, PVC connection pipe with CP brass nuts, CP brass chain with rubber plug, 32mm dia. Chromium plated brass waste of standard pattern, 32mm dia. CP brass trap union complete with necessary fittings.

Sink

It shall be made of glazed vitreous china conforming to IS:2556, Part-V. It shall be wall hung by painted cast iron brackets and complete with one CP brass faucet with nylon washers, PVC connection pipe with CP brass nuts, CP brass chain with rubber plug, 40mm dia. chromium plated brass waste of standard pattern, 40mm dia. CP brass trap union complete with necessary fittings.

Bathroom mirror

It shall be made of the best quality 6 mm thick glass and produced by a reputed mirror manufacturer. It shall be wall mounted with adjustable revolving brackets. The brackets, screws, and other fittings shall be chromium plated.

Glass shelves

Class shelves shall consist of 6 mm thick clear glass with guardrails and shall be wall mounted with brackets. All brackets, guardrails, and screws shall be chromium plated.

Towel rail

Towel rails shall be 20 mm dia chromium plated MS pipes wall mounted with steel brackets. The brackets, screws etc. shall also be chromium plated.

Soap holder

It shall be made of chromium plated strong members. The holders shall be wall mounted with chromium-plated screws.

Liquid Soap Dispenser

It shall be round and easily revolving with removable threaded nozzle. The body, bracket for wall mounting and screws shall be chromium plated.

Toilet roll bolder

It shall be made of glazed vitreous china with suitable cover cum cutter. Wall mounting screw shall be chromium plated.

Valve, cocks, Taps

All valves, stop cocks, taps etc. shall conform to relevant Indian standard specification and shall be of best quality from approved manufacturers. These shall be suitable for normal working pressures. Nominal size and material shall be as required / specified.

2.03.00 Water Storage Tank

Water storage tank shall be PVC of approved brand and make (Syntex or equivalent). Reservoirs made of concrete masonry or fabricated steel shall be covered by respective work specifications.

3.00.00 INSTALLATION

3.01.00 General

Basic layouts may be available in the drawings provided, the details might have to be supplemented by the Contractor and get the approval of the Engineer before installation. Special attention shall be given to economise the layout. Symmetry of layout is very important. Fittings meant for operation shall be located and oriented to allow easy reach and operation. Maintenance, repairs, and replacements of pipes, fittings, and fixtures must be conveniently possible. All pipe lines, locations of fittings and fixtures, etc. shall be as per drawings or as directed by the Engineer. Correctness of lines, plumb, orientation, symmetry, and levels shall be strictly ensured. All items shall be fully secured against movement in any direction and so located as to allow easy maintenance.

All pipelines, fittings, and fixtures shall be installed leak proof. When the works under scope of this specification linked up with works executed by others, the connections shall be such as to prevent any splashing or spilling or emission of foul odour and gases.

3.02.00 Portable water supply Pipe Lines

3.02.01 Laying

In addition to fulfilling the functional requirements all pipelines shall be laid true to line, plumb and level and shall run on the surface of the walls, ceiling or in chases. Any deviation shall need approval of the Engineer. Meticulous care shall be taken to avoid chances of airlock and water hammer.

Pipes shall be laid on continuous unyielding surface or on reliable supports at least one near each joint and spacing as directed by the Engineer. The support must be strong, neat and shall have provisions for securing the pipes in every direction and easy maintenance. All pipes used for water supply should be thoroughly and efficiently disinfected before taken in to use.

3.02.02 Back Flow

The layout of pipe work shall be such that there is no possibility of back flow towards the source of supply from any cistern or appliances, whether by siphonage or otherwise. All pipe works shall be so laid or fixed and maintained as to be and to remain completely watertight, thereby avoiding waste of water, damage of property and the risk of contamination of the water conveyed.

3.02.03 Contamination

There shall be no cross connection whatsoever between a pipe/fitting for conveying or containing wholesome water and a pipe/fitting for containing impure water or water liable to contamination or of uncertain quality of water which has been used for any other purpose. No piping shall be laid or fixed so as to pass into or through any sewer, scour outlet or drain or any manhole connected therewith.

3.02.04 Underground Piping

Underground piping shall be laid at such a depth that it is not likely to be damaged by traffic and other loads and frost, where applicable. The size and depth of the trench shall be as approved by the Engineer. Back filling shall be done with selected fine earth, unless otherwise permitted, in 150 mm layers and carefully consolidated. Special care shall be taken while filling in the vicinity of the pipe to avoid damage. Before backfilling, the laid pipe shall be fully tested and approved.

Where the pipe rests on rock it may be bedded on a layer of fine selected material or concrete to avoid local point support. The trench shall be so treated by gradient and filling in the area that it does not act as a drainage channel.

3.02.05 Concealed Piping

Where desired by the Engineer or shown on the drawings the pipes shall be concealed in masonry or concrete of the structure. The Contractor may co-ordinate with the building Contractor for leaving the chases, openings, and conduits as necessary. However, the Contractor will rectify if required the chases, openings, and conduits, supplement and make good after laying and testing of the concealed pipelines.

3.02.06 Jointing of Pipes

All G.I. pipes shall be properly thread/weld jointed and made completely water tight and durable. Burr from the joints shall be removed after screwing. Union joints shall be provided for all required location to facilitate maintenance.

3.02.07 Painting

Where required, underground G.I. pipes shall be given 2 coats of bituminous paint on the outside after laying. When painting is to be done above ground G.I. pipes shall be given one coat of red lead or zinc chromate primer and top coats shall be minimum 2 coats of best quality paint as specified.

3.03.00 RAINWATER DOWN COMERS

3.03.01 Pipes

Rainwater down comers shall be standard Cast Iron or Asbestos Cement Pipes. In case where specifically desired, M.S. pipes may also be used. M.S. pipes shall be painted outside with two coats of anticorrosive paints under a coat of primer.

Rainwater down comers shall run along and be secured to walls, columns etc. Where desired by the Engineer these may have to be installed in chases cut in the structure. All pipes shall be well secured and supported by adequately strong brackets. The brackets may be wrought iron clevis type, split ring type, or perforated strap iron type as approved by the Engineer. For vertical runs each pipe shall hang freely on its brackets fixed just below the socket. Suitable spacer blocks shall be provided against the vertical surface to which the pipe is fixed.

All bends and junctions shall be supplied with watertight cleanouts.

Roof and floor drains and yard gullies shall be installed, if required, by cutting into the structure and grouted with 1:2:4 cement concrete. All gutters shall be provided with removable gratings.

All horizontal pipes shall have a minimum fall of 1 in 100.

3.03.02 Khurras

The khurras shall be constructed before the work in parapet wall is taken up and it shall be 45x45 cm in size, unless otherwise specified and shall be formed of cement concrete of M-20 grade.

3.03.03 Gutters

The gutters shall be made of G.I. or A.C and procured from reputed specialised manufacturers. Each section shall be sufficiently rigid, edges and corners straight and the slopes perfectly uniform. G.I. gutters shall have the edges strengthened by suitable means.

Unless noted otherwise the gutters shall have a minimum fall of 1 in 120. Adequate number of string supports shall be provided so that there is no sagging even when the gutter is full. Each joint must have a support. Unless otherwise specified the supports shall be fabricated M.S. brackets. All junctions shall be thoroughly watertight. The joints may be made by riveting, bolting or soldering. All joints between successive lengths of gutters shall

have on overlap of at least 5 cm. The drop in the overlap shall always be in the direction of the fall of the gutter. Ends of gutters shall be closed watertight. Junction with rainwater down comers shall be made fully watertight and secured.

3.04.00 SOIL AND DRAINAGE PIPES

3.04.01 Gradients

If not specified, the minimum gradients of soil and drainage pipeline shall be as follows:

100 mm nominal dia.	:	1 in 35
150 mm nominal dia.	:	1 in 65
230 mm nominal dia.	:	1 in 120
300 mm nominal dia.	:	1 in 200

3.04.02 Relation with water supply pipelines

Unless specifically cleared by the Engineer, under no circumstances shall drainage and sewer pipes be allowed to come close to water supply pipelines.

3.04.03 Laying

Each separate pipe shall be individually set for line and for level. Where lengths of sewer or drain pipes are laid in trench, properly painted sight rails shall be fixed across the trench at a height, equal to length of the boning rod to be used, above the required invert level of the drain or sewer at the point where the sight is fixed. More sight rails shall be required at manholes, change of gradient and intermediate positions if the distance for sighting is more than 50 ft. apart. The excavation shall be boned in at least once in every 6 ft. The foot of the boning rod shall be set on a block of wood of the exact, thickness of the wall of the pipe. Each pipe shall be separately and accurately boned between sight rails.

3.04.04 Support and Protection of Pipelines

All pipes shall be laid with sockets leading uphill. Preferably the pipe shall rest on solid and even foundations for the full length of the barrel. However, the pipe manufacturer's instruction as approved by the Engineer shall be followed in the matter of support and jointing.

To achieve full and continuous support, concrete for bedding and packing is the best. Where pipes are not bedded on concrete, the floor shall be left slightly high and carefully placed so that the pipe barrels rest on undisturbed ground. If anywhere the excavation has been carried too low packing shall be

done in concrete. Where laid on rock or very hard ground which cannot be easily excavated to a smooth surface, the pipes shall be laid on a cradle of fine concrete floor of gravel and crushed stone over laid with concrete or on a well consolidated gravel and crushed stone bed as desired by the Engineer. PVC or similar pipes shall be laid directly on stable soil and packed with selected soil.

The minimum support and protection for glazed stoneware pipes shall be as follows:

a) When cover is less than 2 metre below ground level and where pipes are unavoidably exposed above ground surface, the pipes shall be completely encased or surrounded with concrete.

b) Where pipes are laid on soft soil with the maximum water table laying at the invert of the pipe, the sewer shall be bedded on concrete.

c) Where the pipes have to be laid on soft soil with the maximum water table rising above the invert of the pipe, but below the top of the barrel, the pipe sewer shall be haunched.

d) Where maximum water table is likely to rise above the top of the barrel or wherever the pipe is laid on soft soil the pipe sewers shall be completely encased or surrounded with concrete.

Vitrified clay pipes shall be laid on a bed of 150 mm thick cement concrete (1:3:6) nominal mix by volume.

Cast iron pipes and concrete pipes may be supported on suitable concrete or brick support, where specified. The supports shall be unyielding and strong enough. At least one support shall be located close to ends. Spacing of intermediate supports shall be as decided by the Engineer. Pipes shall be secured to the supports by approved means.

Anchoring of pipes where necessary shall be achieved by suitable concrete encasing designed for the expected thrust.

3.04.05 Entry into structures

For entry of the pipe lines into any building of structure suitable conduits under the structure or sleeves shall be used. The conduits and sleeves shall be such as to allow easy repairs and replacement of the pipes. When openings or chases are required to be made in the structure for entry of pipelines, locations and sizes shall be marked and checked by the Engineer. After laying of the pipeline the openings and chases shall be mended.

3.04.06 Ducts

Where solid, waste and ventilating pipes are accommodated in ducts, access to cleaning areas shall be provided. Connection to drain shall be through a gully with sealed cover to guard against ingress of sewer gas, vermin, or backflow.

3.04.07 Traps and Ventilating Pipes

Pipes are carrying off the waste from water closets and waste water and overflow water from baths, wash basins, sinks to drains shall be trapped immediately beneath such fixtures. Traps shall have minimum water seal of 50 mm and shall be ventilated whenever such ventilation is necessary to maintain water seal of the trap. Ventilating pipes shall be carried up vertically from the drain to a height of at least 600 mm above the outer covering of the roof of the building or as shown on drawings. All vertical ventilating, anti-syphonage and similar pipe shall be covered on top with a cowl. The cowl shall be made of C. I. unless desired otherwise by the Engineer.

3.04.08 Manhole & Inspection Chambers

At every change of alignment, gradient or diameter there shall be a manhole or inspection chamber. The maximum distance between manholes shall be 30 meter unless specially permitted otherwise. However, for truck route (for pipes above 900 mm dia.) this distance can be increased to 45 M. The distance between manhole or inspection chamber and gully chamber shall not exceed 6 metres unless desired otherwise provision of IS: 4111 (Part-1) shall be followed for construction of a manhole. Manhole shall be constructed so as to be watertight under test. The change in alignment shall be carried out in such a manner as to provide no lodgement for any splashing in case of accidental flashing of the chamber. The channel or drain at the bottom of chamber shall be plastered with 1:2 cement, sand mortar and finished smooth to the grade. The channels and drains shall be shaped and laid to provide smooth flow.

Connecting to existing sewer lines shall be through a manhole.

Unless otherwise specified, 560 mm dia. circular cast iron manhole cover with frame, heavy-duty, conforming to IS: 1726 shall be provided. The covers shall be close fittings so as to prevent gases from coming out.

3.04.09 Cutting of Pipes

Manufacturer's instructions shall be followed for cutting of pipes where necessary. Suitable and approved tools shall be used for the cutting so as to leave surface clean and square to the axis of the pipe.

3.04.10 Jointing

Jointing of pipes shall be so planned as to avoid completely any movement or strain to the joints already made. If any joint is suspected to be damaged it shall be opened out and redone.

All joints between pipes, pipes and fittings and manholes shall be gas-tight when above ground and watertight when underground. Method of jointing shall be as per instructions of the pipe and fittings manufacturer and as approved by the Engineer. However, in the absence of any instruction available from the manufacturer the methods as detailed hereunder shall be used.

a) Cast Iron Pipes

Socket and spigot pipes shall be jointed by the cast lead joints. The spigot shall be centred in the socket of the pipe by tightly caulking in sufficient turns of tarred gasket or hemp yarn to have unfilled half the depth of socket. When the gasket or hemp yarn has been caulked tightly a jointing shall be placed round the barrel and tightened against the face of the socket to prevent airlock. Molten lead shall then be poured in to fill the remainder of the socket and caulked with suitable tools right round the joint to make up for shrinkage of the molten metal on cooling and shall be finished 3 mm behind the socket face.

Joints in cast iron pipes with special jointing arrangements like 'Tyton' Joints etc. shall follow the instructions of the manufactures.

In special cases if flanged joints are accepted by the Engineer the joints shall be made leak proof by inserting approved type of rubber gaskets. The bolts shall be secured in stages to avoid uneven strain.

b) Concrete Pipes

Jointing of concrete pipes shall be generally of rigid type. Unless otherwise stated collar type joint shall be provided. IS: 783 shall be followed for general guidance.

The two adjoining pipes shall be butted against each other and adjoined in correct position. The collar shall then be slipped over the joint, covering equally both the pipes. The angular space shall be filled with stiff mixture of cement mortar 1:2 (1 cement: 2 sand) which shall be rammed with caulking tool. After a day’s work, any extraneous material shall be removed from the inside of the pipe and the newly made joint shall be cured for 7 days.

c) Glazed Stoneware Pipes

Tarred gasket or hemp yarn soaked in thick cement slurry shall first be placed round the spigot of each pipe and the spigot shall then be placed into the socket of the pipe previously laid. The pipe shall then be adjusted and fixed in the correct position and the gasket caulked tightly so as not to fill more than 1/4 of the total depth of the socket. The remainder of the socket shall be filled with a stiff mixture of cement mortar 1:1 (1 cement: 1 sand). A fillet shall be formed round the joint with a trowel, forming an angle of 45 deg. with the barrel of the pipe. The newly made joints shall be protected, until set and shall be cured by covering with damp cloth or other suitable materials.

d) Vitrified clay pipes

The vitrified clay pipe shall be made from refractory clay mixed with crushed pottery and stone and burnt at a high temperature. These shall be hard, compact, and glazed to make them acid resistant and impervious, and shall be obtained from approved manufacturer.

Special care shall be taken in handling these pipes. The pipes shall not be jointed until the earth has been partly refilled over the portion of the pipe between the joint holes. Before laying the second pipe, the socket of the first pipe laid shall be thinly painted all round on the inside with cement slurry (1 part of cement and 2 parts of clean, sharp sand). A ring of rope yarn (closely twisted hemp or jute) dipped in neat cement paste or tar or bitumen, shall be inserted in the socket of pipe and driven home with caulking tools. The rope shall fully encircle the spigot with a slight overlap and shall not occupy more than one-fourth of the total depth of the socket. Where the spigot end of the pipe is made for receiving the gasket, it shall be wrapped with two or three turns of tarred spun, as close to the end as possible, before inserting into the socket. The joint shall then be completely filled with cement mortar (1:1), which shall have very little water. A fillet shall be formed round the joint with trowel, forming an angle of 45 degrees with the outside pipe. Special care shall be taken so that any excess mortar etc. left inside the pipe joints is neatly cleaned off immediately after each joint is made. A semi-circular wooden scrapper or a rubber disc to which a long handle is fixed could be used for this purpose.

e) Lead Pipes

The joints in lead pipes shall be made as wiped solder joint. The minimum and the maximum length of the wiped solder joints shall be 8 cm. and 9 cm. respectively. The solders shall generally consist of two parts of lead and one part of tin.

f) Polyethylene Pipes

The joints shall be thermo welded or bolted as per manufacturer's instructions.

g) Jointing Cast Iron Pipes with Stoneware Pipes

Where any cast iron drain pipe, ventilating pipe or trap is connected with a stoneware or semi-vitrified waste pipe, the beaded spigot end of such cast iron drain pipe, waste or ventilating pipe or trap shall be inserted into a socket of such stoneware pipe and the joint made with mortar consisting of one part of cement and one part of clean sand after placing a ratted gasket or hemp yarn soaked in neat cement slurry round the joint and inserted in it by means of a caulking tool.

h) Jointing Stoneware with Cast Iron Pipes

Where any water closet pan or earth ware trap connected to such a pan is to be jointed with a cast iron soil pipe, the joint between the stoneware spigot and the cast iron socket shall always be of a flexible nature. Such joint shall be made with a mixture of bitumen and chopped asbestos fibre.

3.04.11 Trenches and other excavations

Width of the trench at the bottom shall be such as to provide 200 mm clearance on either side of the pipe for facility of laying and jointing.

Excavated material shall be stacked sufficiently away from the edge of the trench and the side of the spoil bank shall not be allowed to endanger the stability of the excavation. Spoil may be carted away and used for filling the trench behind the work.

Turf, top soil or other surface material shall be set aside, turf being carefully rolled and stacked for use in reinstatement.

All excavation shall be properly timbered, where necessary.

Efficient arrangements for dewatering during excavation and keeping it dry till backfilling shall be made to the satisfaction of the Engineer. Sumps for dewatering shall be located away from the pipe layout.

Where the excavation proceeds through roads necessary permissions shall be secured by the Contractors from the appropriate authorities.

Special care shall be taken not to damage underground services, cables etc. These when exposed shall be kept adequately supported till the trench is backfilled.

The backfilling shall be done only after the pipeline has been tested and approved by the Engineer. Special care shall be taken under and sides of the pipe during hand packing with selected material. At least 300 mm over the pipe shall also be filled with soft earth or sand. Consolidation shall be done in 150 mm layers. The surface water shall be prevented from getting into the filled up trench. Traffic shall not be inconvenienced by heaping up unduly the backfilling material to compensate future settlement. All future settlements shall be made good regularly to minimize inconvenience of traffic where applicable.

3.04.12 Protection

Open end of each pipe shall be protected during installation by suitable covers or plugs so that the ends, threads, sockets, or spigot are not damaged and no foreign material can find its way into the pipeline. Fittings and fixtures liable to be misused or stolen during the construction phase shall be fitted only before testing and handing over.

3.05.00 WATER STORAGE TANKS

Overhead/loft type water storage tank shall be made of PVC. These tanks shall be provided for each toilet block and placed on the roof/loft of the building. Tank shall be installed with proper supports and anchorage for applicable wind and seismic condition. Installation of tank shall be carried out according to the recommendation of IS: 12701. These tanks shall rest preferable on flat surface so as to distribute the load evenly. The tank shall be leak-proof and water tight.

The outlet pipe shall be 50 mm above the bottom of the tank and provided preferably with strainers. The wash out or draining pipe shall be connected at the lowest point and flush with bottom of tank.

Tank shall be provided with all fittings for inlet, outlet, overflow pipes and ball valves.

3.06.00 SEPTIC TANK AND EFFLUENT DISPOSAL

3.06.01 Septic tank

Septic tank shall consist of the tank itself with inlet and outlets there from complete with all necessary earthwork and backfilling. The details of septic tank shall be as shown on drawings. This item shall also include ventilating

pipe of at least 100 m dia. whose top shall he provided with a suitable mosquito proof wire mesh and cowl. Ventilating pipe shall extend to a height of about 2 meter when the septic tank is at least 15 meter away from the nearest building and to a height of 2 meter above the top of building when it is located closer than 15 meter. Ventilating pipes can be connected to the normal soil ventilating system of the building where allowed.

3.06.02 Effluent Disposal

The effluent from the septic tank shall be disposed by allowing it into an open channel or a body of water if the concerned authority approves or into a soak pit for absorption by soil or shall be allowed to be absorbed by soil through open jointed SW pipes laid in a trench filled with broken bricks.

3.06.03 Soak pit

The soak pit shall be complete. It shall consist of a 900 mm dia. pit 1000 mm in depth below the invert level of the inlet pipe. The pit shall be lined with stone; brick or concrete blocks set in cement mortar (1:6) and filled with brickbats. Inlet pipe shall be taken down to a depth of 900 mm from the top as an anti-mosquito measure.

3.06.04 Open joined SW Pipe/dispersion trenches

Minimum dia. of the SW pipes shall be 150 mm nominal. The trench for laying the pipes shall be a minimum 600 x 600 mm. The joints of the pipes shall be left unsealed. The entire length of the pipe within the trench shall be buried in a 250 mm layer gravel or crushed stone of uniform size. On top of gravel/crushed stone layer is a 150 mm bed of well-graded coarse aggregate. Ordinary soil is used for filling the top of trench.

3.06.05 Commissioning septic tank

After the septic tank has been proved watertight and the sewage system is checked the tank shall be filled with water to its outlet level before the sewage is let into the tank. It shall be seeded with well digested sludge obtained from septic tank or sludge digestion tank. In the absence of digested sludge, a small quantity of decaying organic matter such as digested cow-dung may be introduced.

3.07.00 Related Works

All works, like earthwork, masonry, concrete, steelwork, cutting holes, chases, repairs and rectification associated directly with installation of water supply and sanitation systems shall come under scope of the Contractor unless specifically excluded. These works are not detailed out in this Section.

3.08.00 Regulation

The work which is required to be carried out under this section, shall be executed by a licensed Plumber only (engaged by the Contractor) and he shall obtain all necessary sanctions, permissions, certificates etc., from Municipal and/or other Local Authorities and shall abide by all the rules of such Authorities.

4.00.00 TESTING AND ACCEPTANCE CRITERIA

4.01.00 Inspection Before installation

All pipes, fittings, and appliance shall be inspected, before delivery at the site to see whether they conform to accepted standards. The pipes and fittings shall be inspected on site before laying and shall be sounded to disclose cracks. Any defective items shall be clearly marked as rejected and forthwith removed from the site.

4.02.00 Testing of Water Supply pipe line

4.02.01 Testing of Mains After Laying

After laying and jointing, the main shall be slowly and carefully charged with water, so that all air is expelled from the main by providing a 25 mm inlet with a stop-cock, allowed to stand full of water for a few days if time permits, and then tested under pressure. The test pressure shall be 5 Kg/sq.cm or double the maximum working pressure, whichever is greater. The pressure shall be applied by means of a manually operated test pump, or in the case of long mains or mains of a large diameter, by a power driven test pump, provided that the pump is not left unattached. In either case due precaution shall be taken to ensure that the required test pressure is not exceeded. Pressure gauges shall be accurate and shall preferably have been recalibrated before the test. The pump having been stopped, the test pressure shall maintain itself without measurable less for at least five minutes. The end of the main shall be closed by fitting a watertight expanding plug and the plug shall be secured by struts to resist the end thrust of the water pressure in the mains.

4.02.02 Testing of Service Pipes and Fittings

The service pipes shall be slowly and carefully charged with water allowing all air to escape avoiding all shock or water hammer. The service pipe shall then be inspected under working conditions of pressure and flow. When all draw-off taps are closed, the service pipes shall be absolutely watertight. All piping, fittings, and appliances shall be checked for satisfactory support and protection from damage, corrosion, and frost.

4.03.00 Testing of Drain and Sewerage Pipelines

All soil pipes, waste pipes, ventilating pipes and all other pipes, when above ground, shall be gas tight. All sewers and drainpipes laid below ground shall be tested water tight. The method of actual tests shall be decided by the Engineer. All test data shall be recorded and submitted to the Engineer for review and instruction. The Engineer's discretion regarding tolerance shall be final.

General guidance for the tests are given below:

a) Smoke test

All soil pipes, waste pipes and vent pipes and all other pipes when above ground shall be approved gastight by a smoke test conducted under a pressure of 25 mm of water and maintained for 15 minutes after all trap seals have been filled with water. The smoke is produced by burning oily waste or tarpaper or similar material in the combustion chamber of a smoke machine. Chemical smokes shall not be used.

b) Water test

The pipes shall be subjected to a test pressure of at least 1.5 m head of water at the highest point of the section under tests. The tolerance figure of two litres per centimetre of diameter per kilometre may be allowed during a period of 10 (ten) minutes. The test shall be carried out by suitably plugging the low end of the drain and the ends of connections, if any, and filling the system, with water. A knuckle bend shall be temporarily jointed in at the top end and a sufficient length of the vertical pipe jointed to it so as to provide the required test head or the top end may be plugged with a connection to a hose ending in a funnel which could be raised or lowered till the required head is obtained and fixed suitably for observation.

Subsidence of test water may be due to one or more of the following cases:

a) Absorption by pipes and joints

b) Sweating of pipes or joints

c) Leakage at joints or from defective pipes

d) Trapped air.

Allowance shall be made for (a) by adding water until absorption has ceased and after which the test proper should commence. Any leakage and the defective part of the work shall be cut out and made good.

c) For straightness

i) By inserting at the high end of the sewer or drain a smooth ball of a diameter 13 mm less than the pipe bore. In the absence of obstruction, such as yarn or mortar projecting through the joints, the ball with roll down the invert of the pipe end emerge at the lower end; and

ii) By means of a mirror at one end of the line and lamp at the other. If the pipeline is straight, the full circle of light may be observed. The mirror will also indicate obstruction in the barrel if the pipeline is not straight.

4.04.00 Fittings and Fixtures etc.

All fittings and fixtures shall be connected by water tight joints. No dripping of water shall be acceptable.

4.05.00 Testing Septic Tank

The septic tank shall be tested for water tightness. It shall be filled up with water and allowed to soak for 24 hours. Then, it shall be topped up and allowed to stand again for 24 hours and loss of level recorded. The fall shall not be more than 15 mm in 24 hrs.

5.00.00 I.S. CODES

Important relevant IS Codes for this specification are listed below:

Latest editions shall always be consulted.

IS: 404	:	Lead pipes.
IS: 407	:	Brass tubes for general purposes.
IS: 458	:	Concrete pipes (with or without reinforcement)
IS: 783	:	Code of Practice for laying of concrete pipes.
IS: 1172	:	Code of basic requirements for water supply, drainage and sanitation.
IS: 1200 (Pt. XVI)	:	Laying of water and sewer lines, including appurtenant items.

IS: 1230	:	Cast iron rain water pipes and fittings.
IS: 1239 (Pt. I & III)	:	Specification for Mild Steel Tubes and Mild Steel Tubulars and other wrought steel pipe fittings (10 mm to 15 mm nominal diameter).
IS: 1536	:	Specification for centrifugally cast (Spun) iron pressure pipes for water gas and sewage.
IS: 1537	:	Specification for vertically cast iron pressure pipes for water, gas and sewage.
IS: 1592	:	Asbestos cement pressure pipes,
IS: 1626	:	Asbestos cement pressure pipes, gutters and fittings (Spigot and Socket types).
IS: 2065	:	Code of Practice for Water Supply in buildings.
IS: 2501	:	Copper tubes for general engineering purposes.
IS: 2556	:	Specification for vitreous sanitary appliances (vitreous china) Part – I - General requirement
IS: 2633	:	Method of testing, uniformity of coating on zinc coated articles.
IS: 3076	:	Low density polyethylene pipes for portable water supplies.
IS: 3486	:	Specification for Cast iron spigot and socket drain pipes (80 mm to 250 mm nominal diameter).
IS: 3589	:	Specification for Electrically welded steel pipe for water, gas and sewage (200 mm to 2000 mm nominal diameter).
IS: 4827	:	Specification for electro plated coatings of nickel and chromium on copper and copper alloy.
IS: 4964	:	High-density polyethylene pipes for portable water supplies.
IS: 12701	:	Rotational moulded polyethylene water storage tanks

6.00.00 RATE AND MEASUREMENT

6.01.00 RATE

6.01.01 G.I. Pipes for Water Supply

Rate shall include providing and fixing of the pipes including all specials and fittings, such as tees, bands, elbows, clamps, drain heads, cleanouts etc. with cutting, making chases and jointing of pipes, making good the walls.

6.01.02 Rainwater Down-comers

Rate shall include providing and fixing of the pipes including all specials and fittings, such as tees, bands, elbows, clamps, drain heads, cleanouts etc. The rate also includes cost of jointing and making good the opening in structure.

6.01.03 Sanitary Fixtures

Rate shall include providing and fixing of sanitary appliances & fixtures and at all elevation, including all accessories and fittings, connections pipes, waste trap and pipes all complete as per description of “Schedule of Items”. Rate shall also include the jointing of waste & traps to drain pipes.

6.01.04 Drainage and Sewer Pipes

Rate shall be inclusive of providing, laying and jointing of pipes as specified. Rate also include cost of lead joints or other joint as specified, cost for painting and cutting and making good walls, floors etc.

6.01.05 Floor and Gully Traps

Rate of traps is inclusive of all excavation, filling, repair, making good of opening in floor and walls, grating, painting etc. complete as described in “Schedule of Items”.

6.01.06 Manholes, Septic Tank, Soak Pit and Cover

Rate of manholes, septic tank, soak pit shall be paid under respective items of work executed like brick work, plastering, concrete, reinforcement steel etc. provided for completion of the structure as per drawing and specifications. Manhole cover shall be paid separately as per description of item.

6.01.07 Water Storage Tank

The rate for water storage tank is inclusive of supply and installation of tank with all fittings, inlets, outlets, valves etc. complete.

6.02.00 MEASUREMENTS

6.02.01 Pipe for Water Supply and Drainage

For G.I. Pipe of water supply line, rainwater down comers, drainage and sewer pipe, the measurements shall be in running metres and shall be taken along centre line of pipe or specials.

The pipe shall be measured separately according to dia. and class of pipe.

Fixtures like bibcock, stopcocks, valves etc. shall be measured in numbers.

6.02.02 Sanitary Appliances & Fixtures and Allied Works

All sanitary appliances & fixtures like sink, washbasin, WC, shall be measured in numbers for the complete work as described in schedule of items.

Floor and gully traps shall be measured in numbers unless otherwise specified.

Water storage tank shall be measured in numbers for the capacity as specified in “Schedule of Items”.

The item of work executed for completion of manholes, septic tank & soak pit shall be measured in respective items of work like brick work, RCC, plastering etc. CI cover shall be measured in numbers as specified in “Schedule of Items”.

VOLUME: II B

SECTION - D

SUB-SECTION – D16

SPECIFICATION NO. PE-TS-999-600-C016

ROAD AND DRAINAGE

Maharatna Company

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.0	CODES AND STANDARDS	4
3.00.0	EXECUTION	7
4.00.00	TESTING AND ACCEPTANCE CRITERIA	36
5.00.00	MEASUREMENT	36

Standard Technical Specification
For Road and Drainage

1.00.00 Scope

The scope include all works required for the construction of road including construction of embankment, sub-base course, base course, tack coat, bituminous macadam, wearing course, liquid seal coat, shoulder and all incidental items of work specified or not shown but reasonably implied or necessary for the completion of the work etc.

The scope also include all works required for the construction of drainage including construction of road side drains, RCC culverts, pipe culverts, drainage pipes, manholes and all other incidental items necessary for the completion of the work etc.

1.01.00 Works to Be Provided by The Contractor

The works to be provided by the contractor unless specified otherwise shall include but not be limited to the following.

a) Construction of roads including providing all materials, labour, supervision, services, equipments, tools and plants, transportation etc. all required for the completion of the work.

b) Submission of detailed scheme of all operations required for executing the work (e.g. material handling, placement, services, approaches etc.) to the engineer for approval.

c) Carrying out tests whenever required by the engineer to assess the quality of work and submission of the test results to the engineer after completion of the same etc.

1.02.00 Work to Be Provided by Others

No work under this specification will be provided for by any agency other than the contractor unless specifically mentioned elsewhere in the contract.

1.03.00 Conformity with Designs

The contractor shall carryout the work as per the construction drawings, specification and as directed by the engineer.

1.04.00 Materials to Be Used

All materials required for the work shall be the best commercial variety and as approved by the engineer.

2.00.00 Codes and Standards

All works under this specification shall conform to the latest revision and/or replacement of the following or any other IRC/IS Codes and Standard Practices unless specified otherwise.

a) Specification for road and bridge works of Ministry of Shipping & Transport (Road Wing) Published by the IRC

b) IRC: 19 - Standard specification and code of practice for Water bound Macadam

c) IRC: SP 11 - Hand Book of Quality Control for Construction of Roads and Runways

d) IS:456 - Indian Standard Code of Practice for Plain and Reinforced Concrete.

e) IS:2212 - Code of Practice for Brick work

f) IS: 783 - Code of Practice for Laying of Concrete Pipes

g) IS: 1201 - Methods of testing tar and bituminous materials to 1220

h) IS: 73 - Specification for paving bitumen

i) IS: 215 - Specification for Road tar

j) IS: 216 - Coal tar pitch

k) IS: 217 - Specification for cut-back bitumen

l) IS: 454 - Specification for cut-back bitumen from waxy crude

m) IS: 1834 - Specification for hot applied sealing compound for joint in concrete

n) IS: 1838 - Specification for performed fillers for expansion joints in concrete, non-extruding and resilient type
Part I Bitumen impregnated fibre

Part II CNSL Aldehyde resin and coconut pith

o) IS: 334 - Glossary of terms relating to bitumen and tar

p) IS: 1077 - Common burnt clay building bricks

q) IS: 3117 - Specification for bitumen emulsion roads (anionic type)

r) IS: 1200 - Method of measurement of building and civil engineering work (Part-17)- Road work including airfield pavements

s) Other specifications mentioned elsewhere in this specification.

In case any particular aspect of work is not covered specifically by the specification/Indian Standard Code of practices, any other standard practice as may be specified by the engineer shall be followed.

2.01.00 Quality Control

The Contractor shall establish and maintain quality control for all materials, procedures, workmanship and equipments used. All works shall conform to the lines, grades, cross sections and dimensions shown on the drawings, specification and as directed by the engineer. Permitted tolerances for road works are described hereinafter.

a) Horizontal Alignment

Horizontal alignment shall be reckoned with respect to the centre line of the carriageway as shown on the drawings. The edges of the carriageway as constructed shall be correct within a tolerance of ± 25mm therefrom. The corresponding tolerance for edges of the roadway and lower layers of the pavement shall be ± 40mm.

b) Longitudinal Profile

The finished levels of the sub-grade and different pavement courses as constructed shall not vary from those calculated with reference to the longitudinal and cross-profile of the road shown on the drawings or as directed by the engineer and shall not exceed the tolerances as mentioned below.

Sub-grade ± 25 mm
Sub-base ± 20 mm
Base course ± 15 mm
Wearing course ± 10 mm

Tolerance in wearing course shall not be permitted in conjunction with the positive tolerance on base course if the thickness of the wearing course is thereby reduced by more than 6 mm.

c) Surface Regularity of Sub-grade and Pavement Courses

The surface regularity of the completed sub-base, base course and wearing surfaces in the longitudinal and transverse directions shall be within the tolerances indicated in Table - I. The longitudinal profile shall be checked with a 3m long straight edge at the middle of each traffic lane along a line parallel to the center of the road. The transverse profile shall be checked with a set of three camber boards at intervals of 10m.

TABLE –I

PERMITTED TOLERANCE OF SURFACE REGULARITY FOR PAVEMENT COURSES

Sl. No.	Type of Construction	Longitudinal profile with 3m straight edge					Cross Profile
		Maximum permissible Undulation (mm)	Maximum number of undulations permitted in any 300m length with undulation exceeding (mm)				Maximum permissible variation from specified profile under camber template (mm)
			18	12	10	6	
1	2	3	4	5	6	7	8
1.	Earthen sub-grade	25	30	-	-	-	15
2.	Granular sub-base	15	-	30	-	-	12
3.	Water Bound Macadam with oversize metal (40-90 mm size)	15	-	30	-	-	12
4.	Water Bound Macadam with normal size metal (20-50 mm and 40-63 mm size), Bituminous Penetration Macadam	12	-	-	30	-	8

5.	Surface dressing** (two coat) over WBM (20-50 mm or 40-63 mm size metal), Bituminous penetration macadam	12	-	-	20	-	8
6.	Open graded premix carpet, mix seal Surfacing	10	-	-	-	30	6
7.	Bituminous macadam	10	-	-	-	20***	6
8.	Semi-dense carpet	10	-	-	-	20***	6
9.	Asphaltic Concrete	8	-	-	-	10***	4

Notes:

1. ** For surface dressing in all other cases, the standards of surface evenness will be the same as those for the surface receiving the surface dressing.

2. *** These are for machine laid surfaces. If laid manually due to unavoidable reasons, tolerance upto 50 percent above these values in this column may be permitted at the discretion of the Engineer. However, this relaxation does not apply to the values of maximum undulation for longitudinal and cross profiles mentioned in columns 3 and 8 on the table.

3. Surface evenness requirements in respect of both the longitudinal and cross profiles should be simultaneously satisfied.

3.00.00 Execution

3.01.00 Setting Out

Within 15 days of the award of contract, the contractor shall prepare and submit to the Engineer detailed drawings/schemes of embankment filling and excavation works as proposed to be executed by him showing the dimensions as per construction drawings and specification adding his proposals of drainage and dewatering of pits, watering and compacting the embankment fill etc. On receiving the approval from the Engineer with modifications and corrections if any, the contractor shall set out the work from the control points furnished by the Engineer and fix permanent points and markers for ease of future checking. These permanent points and markers will be checked by the Engineer and certified by him after which the contractor shall proceed with the work. It should be noted that this checking by the Engineer prior to the start of the work will in no way absolve the contractor of his responsibility of carrying out the work to true lines and levels as per the approved drawings. If any errors are noticed in the Contractor's work at any stage, the contractor at his own risk and cost shall rectify the same. Profiles of the embankment made with Bamboo, earth or other convenient materials and strings shall be set up at suitable intervals for the guidance of the workmen.

3.02.00 Clearing and Grubbing

Before commencement of earthwork, the surface area of ground to be occupied shall be cleared of all fences, trees, logs, stumps, bushes, vegetation, rubbish, slush etc. Cutting of trees shall include trees having girth of any size and removing roots upto a depth of 600mm below ground level or 300mm below formation level whichever is deeper. After the removal of roots of trees, the pot holes formed shall be filled with good earth in 250mm layers (loose thickness) and compacted unless otherwise directed by the Engineer. The trees shall be cut into suitable pieces as instructed by the Engineer. Before earthwork is started, all the spoils and unserviceable materials and rubbish shall be burnt or removed from the site to the approved disposal areas as may be specified. Useful materials, saleable timbers, firewood etc. shall be the property of the Owner and shall be stacked properly at the work site in a manner as directed by the Engineer.

3.03.00 Filling in Embankment

3.03.01 General

The material used for constructing the embankment shall be earth, moorum, gravel or a mixture of the above or any other material approved by the Engineer. The material shall be free from lumps and clods, boulders and rock pieces, roots and vegetation, harmful salts and chemicals, organic materials, loose silts, fine sands and expansive clays in order to provide a stable embankment. The filling and compaction operation should be such that the best available materials are saved for the top portion and will result in an acceptable and uniform gradation of material and provide impermeability and stability to the embankment when compacted. The size of the coarse material in the mixture of earth shall ordinarily not exceed 75mm. However, the Engineer may at his discretion permit the use of material coarser than the specified if he is satisfied that the same will not present any difficulty as regard to the placement and compaction of the fill material are concerned. Ordinarily, only the materials satisfying the density requirements as given below in Table-II shall be employed for embankment construction.

Table - II

Density Requirements of Embankment Materials

Sl. No.	Type of Work	Maximum laboratory dry density when tested as per IS: 2720 (Part - VII)
1.	Embankment upto 3m height	Not less than 1.44 gm/cc
2.	Embankment exceeding 3m height and embankment of any height subject to long period of inundation	Not less than 1.52 gm/cc
3.	Top 0.5m of the embankment below sub-base and shoulders (where earth shoulders are specified)	Not less than 1.65 gm/cc

Expansive clays exhibiting marked swell and shrinkage properties shall not be used for embankment construction.

The material for embankment construction shall be obtained from approved sources with preference given to the materials available from nearby road excavation or any other excavation under the same contract.

3.03.02 Setting Out

After the site clearance, the work shall be set out true to lines, curves, slopes, grades and sections as shown on the approved drawings or as directed by the Engineer. The contractor shall provide all labour, survey instruments and materials such as strings, pegs, nails, bamboo, stones, lime, mortar, concrete etc. required in connection with the setting out of the works and establishment of the bench marks. The limits of the embankment shall be marked by fixing batter pegs on both sides at regular intervals as guides before commencing the earthwork. To ensure the safety, the pegs should normally be fixed about 500mm away from the actual limits of the fill and to be painted in a distinct colour. The centreline of the embankment shall be pegged at regular intervals of 25/30m and at all skews/curves. The actual profile of the embankment shall be made at every third centre line peg with bamboo posts and strings. Preferably prototype profiles developed with wooden planks need to be fixed at every 200m and at the intersection points at curves. The profile shall be about 3m long.

3.03.03 Stripping and Storing top soil

The construction of the earthen embankment by filling shall conform to the dimensions, slopes and other details shown in the approved drawings. Before commencement of the embankment construction, the surface area of ground to be occupied after clearing and grubbing shall be stripped off to a minimum depth of 150mm or more as directed by the Engineer in order to remove all perishable materials and any soil which may become unstable on saturation or may interfere with the development or proper bonding between the foundation and embankment. It is not necessary to remove all the soil containing fine hair like roots but only the rather heavy mats are to be removed. In localities where most of the available embankment fill materials are not conducive to plant growth or when so directed by the Engineer, the top soil suitable for plant growth existing over the embankment foundation areas shall be stripped to specified depths not exceeding 150mm and stored for covering the embankment slopes where revegetation is desired.

3.03.04 Compacting Original Ground

In all cases, the original ground after stripping shall be compacted by rolling with a minimum six passes of 8-10 tons' roller and as directed by the Engineer.

Where the height of the proposed embankment is less than 0.5m and the original ground does not already have a relative compaction of atleast 95 percent of Standard Proctor density (maximum dry density), the same shall be loosened upto a depth of 0.5m and filled in layers not exceeding 250mm in loose thickness and each layer shall be watered and compacted to 100% maximum dry density of the fill material determined in accordance with IS:2720, Part-VII. However before relaying and compacting the loosened material, the surface below this level shall be suitably compacted as directed by the Engineer with a minimum six passes of 8 - 10 tonne roller.

Where so directed by the Engineer, any unsuitable material occurring in the embankment foundation shall be removed and replaced with approved materials suitably compacted. Embankment work shall not proceed until the foundation soil of the embankment is inspected by the Engineer and approved.

3.03.05 Filling

The embankment material shall be spread uniformly over the entire width of the embankment in layers not exceeding 250mm in loose thickness. Successive layers of embankment shall not be placed until the layer under construction has been thoroughly compacted to the requirements set down hereunder. Moisture content of the fill material shall be checked at the source of supply and if found less than that specified for compaction, the same shall

be made good either at the source or after spreading the soil in loose thickness for compaction. In the latter case water shall be sprinkled directly from a hose line or from a truck mounted water tank and flooding shall not be permitted under any circumstances. After adding required amount of water, the soil shall be processed by means of harrows, rotary mixers or by any other approved method until the layer is uniformly wet.

If the material delivered to the road bed is too wet, it shall be dried by aeration and exposure to the sun till the moisture content is acceptable for compaction. Should circumstances arise where owing to wet weather, the moisture content cannot be reduced to the required amount by the above procedure, the work on compaction shall be suspended.

Moisture content of each layer shall be checked in accordance with IS:2720, Part-II and unless otherwise specified shall be so maintained making due allowance for evaporation losses that during compaction, the moisture content shall be in the range of 1 percent above to 2 percent below the optimum moisture content as determined in accordance with IS:2720, Part-VII.

Clods or hard lumps of earth shall be broken to have a maximum size of 150mm when being placed in the lower layers of the embankment and a maximum size of 60mm when being placed in the top 0.5m portion of the embankment below sub-base.

Hauling equipment shall be dispersed uniformly over the entire surface of the previously constructed layer to minimise rutting or uneven compaction.

Where the embankment is to be constructed across a low swampy ground that will not support the weight of trucks or other hauling equipments, the lower part of the fill shall be constructed by dumping successive loads in a uniformly distributed layer to a thickness not greater than that necessary to support the hauling equipment while placing subsequent layers.

3.03.06 Compaction

Compaction equipment approved by the Engineer shall only be employed for construction. If directed by the Engineer, the Contractor shall demonstrate the efficiency of the plant he intends to use by carrying out compaction trials.
Each layer shall be thoroughly compacted to the density as specified in Table-III. Subsequent layers shall be placed only after the finished layer has been tested and accepted by the Engineer.

Table - III

Compaction Requirements for Embankment

Sl. No.	Type of work/material	Field dry density as a percentage of maximum laboratory dry density as per IS: 2720, Part-VII
1.	Top 0.5m portion of embankment below sub-base and shoulders	Not less than 100
2.	Other portions of embankment	Not less than 95

When density measurements reveal any soft area in the embankment, further compaction shall be carried out as directed by the Engineer. If in spite of that the specified compaction is not achieved, the material in the soft area shall be removed and replaced with approved material and compacted to the density requirements and satisfaction of the Engineer.

3.03.07 Drainage

The surface of the embankment at all times during construction shall be maintained at such a cross fall as will shed water and prevent ponding.

3.03.08 Finishing Operations

Finishing operations shall include the work of shaping and dressing the shoulders, road bed and side slopes to conform the alignment, levels, cross sections and dimensions as shown on the drawings or as directed by the Engineer. Both the upper and lower ends of the side slopes shall be rounded off to improve the appearance and merge the embankment with the adjacent terrain.

3.04.00 Turfing with Sods

3.04.01 General

This work shall consist of furnishing and laying live sod of perennial turf forming grass on embankment slopes, shoulders or other locations as shown on the drawings or as directed by the Engineer. Unless otherwise specified the work shall be taken up following the construction of embankment provided the season is favourable for establishment of the sod.

3.04.02 Materials

The sod shall consist of dense, well rooted growth of permanent and desirable grasses indigenous to the locality where it is to be used and shall be practically

free from weeds and other undesirable matters. At the time the sod is cut, the grass shall have a length of approximately 50mm and the sod shall be free from any debris.

Thickness of the sod shall be as uniform as possible with about 50 to 80mm of soil covering the grass roots depending on the nature of the sod so that practically all the dense root system of the grass is retained in the sod strip. The sods shall be cut in rectangular strips of uniform width not less than 250mm x 300mm in size but not so large so that it is convenient to handle and transport without damage. During wet weather the sod shall be allowed to dry sufficiently to prevent rearing during handling and during dry weather it shall be watered before lifting to ensure its vitality and to prevent dropping of soil during handling.

3.04.03 Placing The Sods

The area to be sodded shall be previously constructed to the required slope and cross section. Soil in the area shall be loosened, freed from all stones larger than 50mm size, sticks, stumps and any other undesirable foreign matters etc. and brought to a reasonably granular texture to a depth not less than 25mm for receiving the sod.

Where required, top soil shall be spread over the slopes. Prior to placing the top soil, the slopes shall be roughened and wetted in order to have a satisfactory bond. The depth of top soil (to be spread) shall be 75mm.

Following soil preparation and top soiling (if required), fertilizer and ground limestone when specified shall be spread uniformly. After spreading, the materials shall be incorporated in the soil by discing or other means. The prepared sod bed shall be moistened if not already sufficiently moist and the sod shall be placed thereon within 24 hours after the same has been cut. Each sod strip shall be laid in close contact with each other and shall be lightly tamped with suitable wooden or metal tampers so as to eliminate air pockets and to press it into the underlying soil. At points where water may flow over the sod, the upper edges of the sod strips shall be turned into the soil below the adjacent area and a layer of earth shall be placed over it followed by thorough compaction.

3.04.04 Staking the Sods

Where the side slope is 2 to 1 or steeper and the distance along the slope is more than 2m, the sods shall be staked with pegs or nails spaced approximately 500 to 1000mm along the longitudinal axis of the sod strips. Stakes shall be driven approximately plumb through the sods and to be almost flushed with them.

3.04.05 Top Dressing

After the sods have been laid in position, the surface shall be cleaned of any loose sod, excess soil and other foreign materials. Thereafter a thin layer of top soil shall be scattered over the top dressed surface and the area shall be thoroughly moistened by sprinkling water.

3.04.06 Watering and Maintenance

The turfing so laid shall be well watered and protected until final acceptance. Watering shall be done in such a way that no erosion or damage to the sodded areas/embankment occur. The Contractor shall erect necessary warning signs and barriers, repair or replace the sods which are failing to show uniform growth of grass or damaged by his operation and shall maintain the sod at his own cost until final acceptance.

3.05.00 Shoulder Construction

3.05.01 Description

This work shall consist of constructing shoulder on either side of the pavement in accordance with the requirements of this specification and in conformity with the lines, grades and cross sections shown on the approved drawings and as directed by the Engineer.

3.05.02 Materials

Shoulder shall be made of selected earth or granular material as specified conforming to relevant IRC standards.

3.05.03 Construction Operations

Except in the case of bituminous pavements, the shoulders shall be constructed in advance to the laying of pavement courses. The compacted thickness of each layer of shoulder shall correspond to the compacted layer of pavement course to be laid adjacent to it. After compaction, the inside edges of shoulders shall be trimmed vertical and the area enclosed between the shoulders shall be cleaned of all spilled materials before proceeding with the construction of the pavement layer.

In the case of bituminous pavements, shoulder shall be constructed only after the pavement courses have been laid and compacted.

Regardless of the method of laying, all shoulder construction material shall be placed directly on the shoulder. Any spilled material dragged on to the pavement surface shall be immediately removed without any damage to the

pavement and the area so affected shall be thoroughly cleaned. During all stages of shoulder construction, the required cross fall shall be maintained to drain off surface water.

3.06.00 Kerb

3.06.01 Material

Kerb if required for the construction of footpath shall consist of precast concrete blocks with concrete grade of M-20. The blocks shall be of 100mm thick and of suitable length. The depth of blocks unless otherwise mentioned elsewhere shall be 375mm considering 225mm height of footpath above the road level.

3.06.02 Laying

The kerb shall be laid by cutting trenches of 150mm deep. The width of the trench shall be minimum and just sufficient to insert the kerbs. The inside faces of the kerbs shall be in plumb and the gap between the block shall not be more than 10mm.The gap shall be filled with cement mortar as specified.

The kerbs shall be thoroughly packed with a mixture of stone chips (50%) and moorum (50%) at the outside face. The laying and packing shall be done in a proper workmanlike manner acceptable to the Engineer.

3.07.00 Sub-base (Granular Sub-base)

3.07.01 Description

This work shall consist of laying and compacting well graded material on the prepared sub-grade in accordance with the specification. The material shall be laid in one or more layers as shown on the drawings and shall conform to the lines, grades and cross sections shown on the drawings and as directed by the Engineer.

3.07.02 Materials

The materials to be used for the work shall be natural sand, moorum, gravel, crushed stone, crushed slag, crushed concrete, brick metal, laterite, kankar etc or combinations thereof depending upon the grading required. The mixed materials shall be free from organic and other deleterious constituents and conform to one of the three grading given in Table - IV below.

Table - IV
Grading for Granular Sub-Base Material

Sieve designation	Percent by weight passing the sieve		
	Grading 1	Grading 2	Grading 3
80 mm 63 mm 4.75 mm 75 micron	100 90 - 100 35 - 70 0 - 20	100 90 - 100 40 - 90 0 - 25	100 90 - 100 50 - 100 0 - 30
Minimum CBR value for the fraction of material passing 20 mm sieve.	30 %	25%	20%

Note: The materials passing 425micron sieve for all the three gradings when tested according to IS: 2720, Part V shall have liquid limit and plasticity index not more than 25 percent and 6 percent respectively.

3.07.03 Physical Requirements

The fraction of materials passing 20mm sieve shall give a CBR value as specified in Table – IV when tested in accordance with IS: 2720, Part XVI after preparing the samples at maximum dry density and optimum moisture content corresponding to IS: 2720, Part VII and soaking the same in water for 4 days.

3.07.04 Spreading and Compacting

Immediately prior to laying of sub-base, the sub-grade already finished shall be prepared by removing all vegetation's and other extraneous matters, lightly sprinkled with water if necessary and rolled with one pass of 8 - 10 tonne smooth wheeled roller.

The sub-base material shall be spread on the sub-grade with the help of a drag spreader, motor grader or other approved means. The thickness of loose layers shall be so regulated that the maximum thickness of each layer after compaction shall not exceed 150mm.

Moisture content of the loose material shall be checked in accordance with IS: 2720, Part II and shall be suitably adjusted by sprinkling additional water from a hose line, truck mounted water tank or other approved means so that at the time of compaction it shall be from 1 percent above to 2 percent below the optimum moisture content. While adding water, due allowance shall be made for evaporation losses. After water has been added, the material shall be processed by mechanical or other approved means if so directed by the Engineer until the layer is uniformly wet.

Immediately thereafter, rolling shall be done with 8 to 10 tonne smooth wheeled rollers or with any other approved plant. Rolling shall commence from the edges and progress towards the centre longitudinally except on super elevated portions where it shall progress from the lower to the upper edge parallel to the centre line of the pavement. Each pass of the roller shall uniformly overlap not less than one third of the track made in the preceding pass. During rolling, the grade and camber shall be checked and any high spots or depressions which become apparent shall be corrected by removing or adding fresh material.

Rolling shall be continued till the density achieved is at least 100% of the maximum dry density of the material determined as per IS: 2720, Part VII. The surface of any layer of material on completion of compaction shall be well closed, free from movement under compaction plant and from compaction planes, ridges, cracks or loose materials. All loose, segregated or otherwise defective areas shall be made good to the full thickness of layer and recompacted.

3.08.00 Water Bound Macadam Sub-base/Base Course

3.08.01 Description

Water bound macadam shall consist of clean crushed aggregates mechanically interlocked by rolling and bonded together with screenings, binding material wherever necessary and water, laid on the prepared sub-grade or sub-base as the case may be and finished in accordance with the specification and in conformity with the lines, grades and cross-sections shown on the approved drawings.

3.08.02 Materials

a) Coarse Aggregates - General Requirements

Coarse aggregates shall be either crushed or broken stone. The aggregates shall conform to the physical requirements set forth in Table - V.

Table – V

Physical Requirements of Coarse Aggregates for Water Bound Macadam

S.No.	Type of Construction	Test	**Test method**	Requirements
1.	Sub-base	Los Angeles Abrasion Value *	IS: 2386 (Part IV)	50 percent maximum
		or		
		Aggregate Impact Value	IS: 2386 (Part IV) or IS: 5640**	40 percent maximum
2.	Base	a) Loss Angeles Abrasion value*	IS: 2386 (Part IV)	50 percent maximum
		or		
		Aggregate Impact Value	IS: 2386 (Part IV) or IS: 5640 **	40 percent maximum
		b) Flakiness Index ***	IS: 2386 (Part I)	15 percent maximum

* Aggregates shall satisfy requirements of either of the two tests.

** Aggregates like brick metal, kankar and laterite which get softened in presence of water shall be tested for impact value under conditions in accordance with IS: 5640.

*** The requirements of Flakiness Index shall be enforced only in case of crushed or broken stone and crushed slag.

b) Crushed or Broken Stone

Crushed or broken stone shall be hard, durable and free from excess flat, elongated, soft and disintegrated particles, dirt and other objectionable matters.

c) Grading Requirements of Coarse Aggregates

The coarse aggregates shall conform to one of the gradings given in Table – VI. However, the use of Grading-1 shall be restricted to sub-base courses only.

Table - VI
Grading Requirements of Coarse Aggregates

Grading	Size range	Sieve designation	Percent by weight passing the sieve
1.	90mm to 40 mm	100 mm 80 mm 63 mm 40 mm 20 mm	100 65 - 85 25 - 60 0 - 15 0 - 5
2.	63 mm to 40 mm	80 mm 63 mm 50 mm 40 mm 20 mm	100 90 - 100 35 - 70 0 - 15 0 - 5
3.	50 mm to 20 mm	63 mm 50 mm 40 mm 20 mm 10 mm	100 95 - 100 35 - 70 0 - 10 0 - 5

d) Screenings

Screenings to fill the voids in the coarse aggregate shall generally consist of the same material as the coarse aggregates. However, where permitted, predominantly non-plastic material such as moorum or gravel (other than rounded river borne material) may be used for this purpose provided liquid limit and plasticity index of such material is below 20 and 6 respectively and fraction passing 75-micron sieve does not exceed 10 percent.

As far as possible, screenings shall conform to the grading set forth in Table-VII. Screenings of Type-A in Table-VII shall be used with coarse aggregates of Grading-1 in Table-VI. Screenings of Type-A or B shall be used with coarse aggregates of Grading-2. Screenings of Type-B shall be used with coarse aggregates of Grading-3.

Table - VII
Grading for Screenings

Grading classification	Size of screenings	Sieve designation	Percent by weight passing the sieve
A	12.5 mm	12.5 mm 10.0 mm 4.75 mm 150 micron	100 90 - 100 10 - 30 0 - 8
B	10 mm	10 mm 4.75 mm 150 micron	100 85 - 100 10 - 30

e) Binding Material

Binding material to be used for water bound macadam construction shall comprise of a suitable material approved by the Engineer having plasticity index value less than 6 as determined in accordance with IS: 2720, Part V. Application of binding material may not be necessary when the screenings used are of crushable type such as moorum or gravel.

3.08.03 Construction Operations

a) The sub-grade/sub-base to receive the water bound macadam coarse shall be prepared to the specified grade and camber and made free of any dust and other extraneous materials. Any ruts or soft yielding places shall be corrected in an approved manner and rolled until firm. Where water bound macadam is to be laid over an existing black topped surface, 50mm x 50mm furrows shall be cut at an angle of 45 degrees to the center line of the road at 1m intervals in the latter before laying the coarse aggregates.

b) Inverted Choke

If water bound macadam is to be laid directly over the sub-grade without any other intervening pavement course, a 25mm course of screenings (Grading-B) shall be spread on the prepared sub-grade before application of coarse aggregates is taken up.

c) Spreading Coarse Aggregates

The coarse aggregates shall be spread uniformly over the prepared surface in such quantities that the thickness of each compacted layer is limited to 100mm for Grading-1 and 75 - 100mm for Grading-2 and 3. The spreading shall be

done from stockpiles along the side of the roadway or directly from the vehicles. In no case shall the aggregate be dumped in heaps directly on the surface prepared to receive the aggregates nor shall hauling over permitted. The surface of the aggregates spread shall be carefully checked with templates and all high or low spots remedied by removing or adding aggregates as may be required. No segregation of large or fine particles shall be allowed and the coarse aggregates as spread shall be of uniform gradation with no pockets of fine material. The coarse aggregates shall not normally be spread more than 3 days in advance of the subsequent construction operation.

d) Rolling

Immediately following the spreading of the coarse aggregates, rolling shall be started with three wheeled power rollers of 8 to 10 tonne capacity or with tandem or vibratory rollers of approved type. The weight of the roller shall depend upon the type of the aggregate and be indicated by the Engineer.

Except on super elevated portions where the rolling shall proceed from inner edge to the outer, rolling shall begin from the edges gradually progressing towards the centre. First the edge/edges shall be compacted with roller running forward and backward. The roller shall then move inwards parallel to the centre line of the road. Each pass of the roller shall uniformly overlap not less than one half the width of the track made in the preceding pass.

Rolling shall continue until the aggregates are thoroughly keyed and the creeping of aggregates ahead of the roller is no longer visible. During rolling slight sprinkling of water may be done if necessary. Rolling shall not be done when the sub-grade is soft or yielding or when it causes a wavelike motion in the sub-grade or sub-base course.

The rolled surface shall be checked transversely and longitudinally with templates and any irregularities found shall be corrected by loosening the surface, adding or removing necessary amount of aggregates and rerolled until the entire surface conform to the desired camber and grade. In no case shall the use of screenings be permitted to make up the depressions.

e) Application of Screenings

After the coarse aggregate has been rolled, screenings to completely fill the interstices shall be applied gradually over the surface. These shall not be damp or wet at the time of application. Dry rolling shall be done while the screenings are being spread so that vibrations of the roller cause them to settle into the voids of the coarse aggregates. The screenings shall not be dumped in piles but be spread uniformly in successive thin layers either by the spreading motion of hand shovels or by mechanical spreader or directly from trucks. Trucks operating for spreading the screenings shall be so driven as not to disturb the coarse aggregates.

The screenings shall be applied at a slow and uniform rate (in three or more applications) so as to ensure filling of all voids. This shall be accompanied by dry rolling and brooming with mechanical brooms or hand brooms or with both. In no case shall the screenings be applied so fast and thick as to form cakes or ridges on the surface in such a manner as would prevent filling of voids or prevent the direct bearing of the roller on the coarse aggregate. These operations shall continue until no more screenings can be forced into the voids of the coarse aggregates.

The spreading, rolling and brooming of screenings shall be carried out in only such lengths of road which could be completed within one day's operation.

f) Sprinkling and Grouting

After the screenings have been applied, the surface shall be copiously sprinkled with water, swept and rolled. Hand brooms shall be used to seep the wet screenings into the voids and to distribute them evenly. The sprinkling, sweeping and rolling operations shall be continued with additional screenings applied as necessary until the coarse aggregates are thoroughly keyed, well bonded and firmly set to its full depth and a grout has been formed of screenings. Care shall be taken to see that the base or sub-grade does not get damaged due to the addition of excess quantity of water during construction.

g) Application of Binding Material

After the application of screenings, the binding material where it is required to be used shall be applied successively in two or more thin layers at a slow and uniform rate. After each application, the surface shall be copiously sprinkled with water and the resulting slurry shall be swept in with hand brooms or mechanical brooms to fill the voids properly and rolled during which water shall be applied to the wheels of the rollers if necessary to wash down the binding material sticking to them. These operations shall continue until the resulting slurry after filling the voids form a wave ahead of the wheels of the moving roller.

h) Setting and Drying

After the final compaction of water bound macadam course, the road shall be allowed to dry overnight. Next morning hungry spots shall be filled with screenings or binding material as directed, lightly sprinkled with water if necessary and rolled. No traffic shall be allowed on the road until the macadam is set. The Engineer shall have the discretion to stop hauling traffic from using the complete water bound macadam course if in his opinion it would cause excessive damage to the surface.

3.09.00 Tack Coat

3.09.01 Description

The work shall consist of application of a single coat of low viscosity liquid bituminous material to an existing road surface preparatory to another bituminous construction.

3.09.02 Materials

The binder used for tack coat shall be bitumen of a suitable grade as approved by the Engineer and conforming to IS-73, IS-217 or IS-454 as applicable or any other approved cutback.

3.09.03 Construction Operations

a) Preparation of Base

The surface on which the tack coat is to be applied shall be thoroughly swept and scraped clean of dust and any other extraneous materials before the application of the binder.

b) Application of Binder

Binder shall be heated to the temperature appropriate to the grade of bitumen used and approved by the Engineer and sprayed on the base at the rate specified below. The rate of spread in terms of straight run bitumen shall be 5 kg per 10 square metre area for an untreated water bound macadam surface. The binder shall be supplied uniformly with the aid of sprayers. The tack coat shall be applied just ahead of the oncoming bituminous construction.

3.10.00 Bituminous Macadam Binder Course

3.10.01 Description

This work shall consist of construction in a single course of 50mm/75mm thickness of compacted crushed aggregates premixed with a bituminous binder laid immediately after mixing on a base prepared previously in accordance with the specification and in conformity with the lines, grades and cross sections shown on the approved drawings.

3.10.02 Materials

a) Binder

The Binder shall be straight run bitumen of a suitable grade as directed by the Engineer complying with IS: 73.

b) Aggregates

The aggregates shall consist of crushed stone, crushed gravel (shingle) or other stones. They shall be clean, strong, durable, fairly cubical in shape and free from any disintegrated pieces, organic and other deleterious matter and adherent coats. The aggregates shall preferably be hydrophobic and of low porosity.

The aggregates shall satisfy the physical requirements set forth in Table - VIII.

Table – VIII

Physical Requirements of Aggregates for Bituminous Macadam

Sl. No.	Test	Test method	Requirements
1.	Los Angeles Abrasion Value *	IS: 2386 (Part IV)	35 percent maximum
2.	Aggregate Impact Value *	IS: 2386 (Part IV)	30 percent maximum
3.	Flakiness Index	IS: 2386 (Part I)	35 percent maximum
4.	Stripping Value	IS: 6241 (Part IV)	25 percent maximum
5.	Water Absorption	IS: 2386 (Part III)	2 percent maximum

*Aggregates may satisfy requirements of either of the two tests.

The aggregates for bituminous macadam for different thickness shall conform to Grading- A or B as given in Table-IX or X as the case may be.

Table-IX
Aggregates Grading for 75mm Compacted Thickness of Bituminous Macadam

Sieve Designation	Percent by weight passing the sieve	
	Grading A	Grading B
63 mm	100	
50 mm	90 - 100	
40 mm	35 - 65	100
25 mm	20 - 40	70 - 100
20 mm	-	50 - 80
12.5 mm	5 - 20	-
4.75 mm	-	10 - 30
2.36 mm	-	5 - 20
75 micron	0 - 5	0 - 4

Table-X
Aggregates Grading for 50mm Compacted Thickness of Bituminous Macadam

Sieve Designation	Percent by weight passing the sieve	
	Grading A	Grading B
50 mm	100	
40 mm	90 - 100	
25 mm	50 - 80	100
20 mm	-	70 -100
12.5 mm	10 - 30	-
10 mm	-	35 - 60
4.75 mm	-	15 - 35
2.36 mm	-	5 - 20
75 micron	0 - 5	0 - 4

c) Proportioning of Materials

The binder content for premixing shall be 3.5 and 4.0 percent by weight of the total mix for aggregate Grading-A and B respectively unless directed otherwise by the Engineer. The quantity of aggregates to be used shall be sufficient to yield the specified thickness after compaction.

d) Variation in Proportioning of Materials

The Contractor shall have the responsibility for ensuring proper proportion of materials and producing a uniform mix. A variation in binder content upto ± 0.3 percent by weight of total mix shall however be permissible for individual specimens taken for quality control tests.

3.10.03 Construction Operations

a) Weather and Seasonal Limitations

Bituminous macadam shall not be laid during rainy weather or when the base course is damp or wet.

b) Preparation of Base

The base on which the bituminous macadam is to be laid shall be prepared, shaped and conditioned to the specified lines, grade and cross sections as shown on the drawings and as directed by the Engineer. The surface shall be thoroughly swept and scraped clean and free of any dust and foreign matter.

c) Tack Coat

A tack coat shall be applied over the base.

d) Preparation and Transport of Mix

Hot mix plant of adequate capacity shall be used for preparing the mix. The temperature of binder at the time of mixing shall be in the range 150 Deg. - 165 Deg. C and to that of aggregates shall be in the range 125 Deg. - 150 Deg. C provided the temperature difference between the binder and the aggregate at no time exceeds 25 Deg. C. Mixing shall be thorough to ensure that a homogenous mixture is obtained in which all particles of the aggregates are coated uniformly. The mixture shall be transported from the mixing plant to the point of use in a suitable vehicle. The vehicle employed for transport shall be clean and be covered over in transit if so directed by the Engineer.

e) Spreading

After mixing, the mix shall be spread immediately by means of a self-propelled mechanical paver with suitable screeds capable of spreading, tamping and finishing the mix to the specified lines, grade and cross sections. However, in restricted locations and in narrow widths where the available plants cannot operate in the opinion of the Engineer may permit manual laying of the mix. The temperature of mix at the time of laying shall be in the range 110 Deg. - 135 Deg. C.

In multilayer construction, the longitudinal joint in one layer shall offset into the layer below by about 150mm. However, the joint in the topmost layer shall be at the centre line of the pavement.

Longitudinal joints and edges shall be constructed true to the delineating lines parallel to the centre line of the road. All joints shall be cut vertical to the full thickness of the previously laid mix and the surface painted with hot bitumen before placing fresh material.

f) Rolling

After spreading of mix, the rolling shall be done with 8 to 10 tons' power roller or with any other approved plant. Rolling should start as soon as the materials are spread. Rolling shall be done with care to avoid any undulation in the pavement surface.

Rolling on the longitudinal joint shall be done immediately after the paving operation. After this, the rolling shall commence at the edges and progress towards the center longitudinally except on superelevated portions where it shall progress from the lower to the upper edge parallel to the center line of the pavement.

The initial or breakdown rolling shall be done as soon as it is possible to roll the mixture without cracking the surface and no mix pick up on the roller wheels. The second or intermediate rolling shall follow the break down rolling as early as possible and be done while the paving mix is still at a temperature that will result in maximum density. The final rolling shall be done while the material is still workable enough for removal of roller marks.

When the roller has passed over the whole area once, any high spots or depressions which become apparent shall be corrected by removing or adding fresh materials. The rolling shall then be continued till the entire surface has been rolled to compaction and there is no crushing of aggregates and till all the roller marks are eliminated. Each pass of the roller shall uniformly overlap not less than one third of the track made in the preceding pass. The roller wheels shall be kept damp if necessary to avoid the bituminous material from sticking on the wheels and being picked up. In no case shall fuel/lubricating oil be used for this purpose.

Rolling operation shall be completed in every respect before the temperature of the mix fall below 80 Deg. C.

Rollers shall not stand on the newly laid material as it may lead to undue deformation. The edges along and transverse of the bituminous macadam laid and compacted earlier shall be cut to their full depth so as to expose fresh

surface which shall be painted with a thin surface coat of appropriate binder before the new mix is placed against it.

The bituminous macadam shall be provided with a final surfacing without any delay. If there is to be any delay the course shall be covered by seal coat before allowing any traffic over it.

3.11.00 Open Graded Premix Carpet

3.11.01 Description

This work shall consist of laying and compacting open graded carpet of specified thickness in a single course of suitable small sized aggregates premixed with bituminous binder on a previously prepared base to form wearing course in accordance with the specification.

3.11.02 Materials

a) Binder

The binder shall be bitumen of suitable grade as approved by the Engineer and satisfying the requirements of IS: 73, 217, 454 or any other approved cutback as applicable.

b) Aggregates

The aggregates shall consist of angular fragments of clean, hard, tough and durable rock of uniform quality throughout. They shall be obtained by crushing rock, gravel or river shingle and be free of elongated and flaky pieces, soft and disintegrated materials, vegetable and any other deleterious matter etc. They shall preferably be hydrophobic type. The aggregates shall satisfy the quality requirements set forth in Table-VIII except that the flakiness Index shall be limited to a maximum of 30.

c) Proportioning of Materials

The materials shall be proportioned as per the quantities given in Table-XI for 20mm thick open graded premix carpet.

Table - XI

Quantity of Materials Required for 10 Sq. M of Road Surface for 20mm Thick Open Graded Premix Carpet

Aggregates for Carpet		
i)	Stone Chippings - 12mm size; passing 20 mm sieve and retained on 10 mm sieve	0.18 Cu.m
ii)	Stone Chippings - 10 mm size; passing 12.5 mm sieve and retained on 6.3 mm sieve	0.09 Cu.m
	Total	0. 27 Cu.m
Binder for premixing (quantities in terms of straight run bitumen)		
i)	For 0. 18 Cu.m of 12 mm size stone Chippings at 52 Kg per Cu.m	9.5 Kg
ii)	For 0.09 Cu. M of 10mm size stone Chippings at 56 Kg per Cu.m	5.1 Kg
	Total	14.6 Kg

3.11.03 Construction Operation

a) Weather and Seasonal Limitations

Open graded premix carpet shall not be laid during rainy weather or when the base course is damp or wet or when the atmospheric temperature in shade is 16 Deg. C or below.

b) Preparation of Base

The underlying base on which the bituminous carpet is to be laid shall be prepared, shaped and conditioned to the specified lines, grade and cross section in accordance with the drawing, specification and as directed by the Engineer. The surface shall be well cleaned by removing caked earth and other foreign matters with wire brushes, sweeping with brooms and finally dusting with sacks as necessary.

c) Tack Coat

A tack coat complying with clause 3.09.00 shall be applied over the base preparatory to laying of the carpet. However, application of tack coat shall not be necessary when the laying of carpet follows soon after laying the bituminous course.

d) Preparation of Premix

Mixers of approved type shall be employed for mixing the aggregates with the bituminous binder. The binder shall be heated to the temperature appropriate to the grade of bitumen approved by the Engineer in boilers of suitable design avoiding local overheating and ensuring a continuous supply. The aggregates shall be dry and suitably heated to a temperature as directed by the Engineer before these are placed in the mixer. After about 15 seconds of dry mixing, the heated binder shall be distributed over the aggregates at the rate specified. The mixing of binder with chipping shall be continued until the chippings are thoroughly coated with the binder. The mix shall be immediately transported from the mixer to the point of use in suitable vehicles or wheel barrows. The vehicles employed for transport shall be clean and be covered over in transit if so directed.

e) Spreading and Rolling

The premixed material shall be spread on the road surface with rakes to the required thickness and camber or distributed evenly with the help of a drag spreader without any undue loss of time. The camber shall be checked by means of camber boards and inequalities evened out. As soon as sufficient length of bituminous material is laid, rolling shall be commenced with 6 to 8 tons' power rollers preferably with smooth wheel tandem type or with any other approved plant. Rolling shall begin at the edges and progress toward the center longitudinally except on the superelevated portions where it shall progress from the lower to upper edge parallel to the center line of the pavement.

When the roller has passed over the whole area once, any high spots or depressions which become apparent shall be corrected by removing or adding premixed materials. Rolling shall then be continued until the entire surface has been rolled to compaction and all the roller marks have been eliminated. In each pass of the roller, preceding track shall be overlapped uniformly by at least 1/3 width. The roller wheels shall be kept damp to prevent the premix from adhering to the wheels and being picked up. In no case shall fuel/lubricating oil be used for this purpose. Rollers shall not stand on newly laid material as it may lead to undue deformations.

The edges along and transverse of the carpet laid and compacted earlier shall be cut to their full depth so as to expose fresh surface which shall be painted

with a thin surface coat of approved binder before the new mix is placed against it.

f) Seal Coat

A seal coat conforming to clause 3.12.00 shall be applied to the surface immediately after laying the carpet. No traffic shall be allowed on the road till the seal coat has been placed.

3.12.00 Seal Coat

3.12.01 Description

This work shall consist of application of a seal coat as specified for sealing the voids in the bituminous surface laid to the specified levels, grade and camber.

Type-A: Liquid seal coat comprising of an application of a layer of bituminous binder followed by a cover of stone chippings.

Type-B: Premixed seal coat comprising of a thin application of fine aggregate premixed with bituminous binder.

3.12.02 Materials

a) Binder

The binder shall be bitumen of suitable grade as directed by the Engineer and conforming to the requirements of IS: 73, 217 or 454 as applicable or any other approved cutback.

The quantity of binder to be adopted in terms of straight run bitumen shall be 9.8 Kg and 6.8 Kg per 10 square metre area for Type-A and Type-B seal coat respectively.

b) Stone Chippings for Type a Seal Coat

The stone chippings shall consist of angular fragments of clean, hard, tough and durable rock of uniform quality throughout. They shall be free of elongated or flaky pieces, soft or disintegrated stone, vegetable or other deleterious matters etc. Stone chippings shall be of 6mm size defined as 100 percent passing through 10mm sieve and retained on 2.36mm sieve. The quantity used for spreading shall be 0.09 cu.m. per 10 sq.m area. The chippings shall satisfy the quality requirements spelled out in Table- VIII except that the upper limit for flakiness Index shall be 30.

c) Fine Aggregate for Type B Seal Coat

The fine aggregate shall be sand or fine grit and shall consist of clean, hard, durable, uncoated dry particles and shall be free from dust, soft or flaky material, organic matter or other deleterious substances. The aggregate shall pass 1.7 mm sieve and be retained on 180-micron sieve. The quantity used for premixing shall be 0.06 cubic metre per 10 square metre area.

3.12.03 Construction Operations

a) Preparation of Base

The seal coat shall be applied immediately after laying the bituminous course which is required to be sealed. Before application of seal coat, the surface shall be cleaned free of any dust or other extraneous matters.

b) Construction of Type-A Seal Coat

The binder shall be heated in boilers of suitable design to the temperature appropriate to the grade of bitumen approved by the Engineer and sprayed on the dry surface in a uniform manner preferably with the help of mechanical sprayers. Excessive deposits of binder caused by stopping or starting of the sprayer or through leakage or due to any other reason shall be suitably corrected before the stone chippings are spread.

Immediately after the application of binder, stone chippings in a dry and clean state shall be spread uniformly on the surface preferably by means of a mechanical grittier or otherwise manually so as to cover the surface completely. If necessary, the surface shall be broomed to ensure uniform spread of chippings. Immediately after the application of the cover material, the entire surface shall be rolled with a 8 - 10 tonne smooth wheeled roller. Rolling shall commence from the edges and progress towards the centre except in superelevated portions where it shall proceed from the inner edge to the outer. Each pass of the roller shall uniformly overlap not less than one third of the track made in the preceding pass. While rolling is in progress additional chippings shall be spread by hand in whatever quantities required to make up the irregularities. Rolling shall continue until all aggregate particles are firmly bedded in the binder and present a uniform closed surface.

c) Construction of Type-B Seal Coat

Mixers of approved type shall be employed for mixing the aggregates with the bituminous binder. The binder shall be heated in boilers of suitable design to the temperature appropriate to the grade of bitumen approved by the Engineer. Also the aggregates shall be dry and suitably heated to a temperature as directed by the Engineer before the same are placed in the mixer. Mixing of

binder with aggregates to the specified proportions shall be continued till the latter is thoroughly coated with the former. The mix shall be immediately transported from the mixing plant to the point of use and spread uniformly on the bituminous surface to be sealed. As soon as sufficient length has been covered with the premixed material, the surface shall be rolled with 6 - 8 tonne smooth wheeled power rollers. Rolling shall be continued till the premixed material completely seals the voids in the bituminous course and a smooth uniform surface is obtained.

3.12.04 Opening to Traffic

In case of Type-B Seal coat, traffic may be allowed soon after the final rolling when the premixed materials are cooled down to the surrounding temperature. However, in case of Type- A seal coat, the traffic shall not be permitted until the following day.

3.13.00 Repair of Existing Water Bound Macadam Surfaces

Pot holes or patches and ruts in the water bound macadam base or surface course which is to be surface treated shall be repaired by removing all loose materials by cutting in rectangular patches and replacing with suitable materials. The repair shall be done as under.

Pot holes, patches and ruts shall be drained of any water and cut to regular shape with vertical sides and then be filled either with i) coarse aggregates and screenings conforming to the specification for water bound macadam and compacted with rollers or other approved rammer etc. or with ii) premixed material conforming to the specification for open graded premix carpet and compacted with rollers or other approved means after painting the sides and bottom of the holes with a thin application of bitumen or a combination of both as directed by the Engineer.

3.14.00 Road Side Drains

3.14.01 Drains

The road side drains shall be made in sizes and slopes as shown on the approved drawings. The sides and bottom shall be neatly dressed after excavation. Proper connections shall be made to the culverts outside the plant area as per the drawings and instructions of the Engineer.

The excavated spoils other than that required for backfilling shall be transported and filled in low areas within the plant area or in embankments as instructed by the Engineer. The lining for drains shall be as per the drawings. Lining of drains may be of bricks or cement concrete blocks of specified grade as shown on the approved drawing or as directed by the Engineer. If shown

on approved drawing, drains shall be of R.C.C. construction with necessary slopes.

3.15.00 Culverts

Excavation in trenches for foundation of culverts and wing walls shall be done with side slopes as per the drawings and instructions of the Engineer after clearing the site etc. As described in the "Specification for Earthwork in Excavation and Backfilling", backfilling in layers with watering and compaction shall be done after the construction of foundations. The construction of culverts shall be done true to the lines and levels as shown on the drawings. The specification for Masonry and/or Plain and Reinforced Cement concrete shall be followed as applicable.

3.16.00 Pipe Culverts and Drainage Pipes

3.16.01 Materials

The drainage pipes shall be made of R.C.C and shall be either class NP-2 or NP-3 as shown on the approved drawings. Pipe culverts shall be made of reinforced concrete pipe and shall be of class NP4 or RDSO class for railways as shown in the drawing. All pipes shall meet the requirements of IS: 458 and shall be procured from approved manufacturers with collars as per manufacturer's specification. The tenderer shall specifically mention the particular manufacturer's product he proposes to use.

Cement shall be ordinary Portland Cement as per IS:269. Coarse Aggregates shall be as per IS:383. Maximum size shall not exceed one third the thickness of the pipe or 20 mm whichever is smaller. Fine aggregates for concrete shall be as per IS:383.

3.16.02 Laying of Pipes

Laying of concrete pipes shall correspond to IS:783 and as per the specification given below.

a) The foundation bed for pipe shall be excavated true to lines and grades shown on the drawings and as directed by the Engineer. When trenching is involved, its width on either side of the pipe shall not be less than 150mm and not more than one third the diameter of pipe unless otherwise instructed/permitted by the Engineer. The sides of the trench shall be as nearly vertical as possible. Side slope, shoring, bailing out water etc. as required shall be done by the Contractor.

Side slips if there be any shall be removed by the Contractor. After laying of the pipes are completed, backfilling of the trenches shall be done as per "Specification for Earthwork in Excavation and Backfilling" to the

satisfaction of the Engineer. The surplus spoils shall be transported and filled in low areas within the plant area as instructed by the Engineer.

When bedrock or boulder stratum is encountered during excavation, the excavation shall be taken down to at least 200mm below the bottom of the pipe with prior permission of the Engineer and all rock/boulders in the area shall be removed and space filled with approved earth free from stone or fragmented materials, shaped to the requirements and thoroughly compacted to provide adequate support for the pipe.

Filling of trench shall be carried out simultaneously on both sides of the pipe in such a manner that unequal pressures do not occur and shall be done as per the "Specification for Earthwork in Excavation and Backfilling". When two or more pipes are to be laid adjacent to each other, they shall be separated by a distance equal to at least half the diameter of the pipe subject to a minimum of 450 mm. Laying of pipes shall start from the outlet and proceed towards inlet. All pipes and fittings shall be gradually lowered into the trench or placed on the supports by approved means taking due care to avoid any damage. Under no circumstances the pipes shall be dropped into the trench or on supports from heights.

b) Pipe bedding shall be first class projection bedding for positive projecting pipes as per IS: 783 having a projection ratio not greater than 0.70. The pipe shall be carefully laid on bedding made up of fine granular materials in an earth foundation; the bedding shall be carefully shaped to fit the lower part of the pipe exterior for at least ten percent of its overall height and in which the fill material is thoroughly compacted in layers not exceeding 150mm in depth around the pipe for the remainder of the pipe laid in trench.

When indicated on the drawings or directed by the Engineer, the pipe shall be bedded on a cradle constructed of concrete having a mix not leaner than M-15. The shape and dimension of the cradle shall be as indicated on the drawing or as directed by the Engineer. The pipe shall be laid on the concrete bedding before the concrete is set.

c) The drop walls shall be made with first class brickwork in 1:4 cement mortar.

d) The pipe culverts shall be made with proper care with respect to the invert of the pipe, gradient if any etc. as specified on the drawings and as instructed by the Engineer.

e) Where R.C.C pipes are encased in concrete at road crossings or at other places the pipes need be suitably supported avoiding reinforcements of concrete blocks, joints properly done before concreting is taken up. Concreting of total height of block may be done in a single operation or may be done upto some height for pipes to be properly laid in position and the balance height of the block shall be concreted subsequently.

f) The R.C.C. pipes shall be joined with cement mortar. Cement mortar shall consist of 1 part of cement and 2 part of clean sand with only enough water for workability. Procedure of jointing shall be as per IS: 783.

3.16.03 Relation with Water Supply Pipeline

Unless specifically cleared by the Engineer, under no circumstances shall the drainage pipes be allowed to come close to water supply pipelines.

3.17.00 Manholes and Inspection Chambers

The maximum distance between the manholes shall be 30m unless specifically permitted otherwise. In addition, at every change of alignment, gradient or diameter there shall be a manhole or inspection chamber. The distance between the manhole or inspection chamber and gully chamber shall not exceed 6 meters unless permitted otherwise. Manhole shall be constructed so as to be water tight under test. The channel or drain at the bottom of chamber shall be plastered with 1:2 cement sand mortar and finished smooth to the grade. The channels and drains shall be shaped and laid to provide a smooth flow. Connection to the existing pipelines shall be through a manhole. Manholes shall be provided with standard covers usually of C.I. or as directed by the Engineer. The cover shall be closely fitted so as to prevent gases from coming out.

4.00.00 Testing and Acceptance Criteria

All testing as mentioned in the specification and as mentioned in Clause No. 900 of the "Specification for Roads and Bridge Works, 1983" published by IRC on behalf of Ministry of Shipping and Transport (Roads Wing) shall be carried out by the Contractor as per the direction of the Engineer.

5.00.00 MEASUREMENT

Method of measurement shall be as per the latest version of IS:1200, Part-17 and as directed by the Engineer.

VOLUME: II B

SECTION - D
(PART I)

SUB-SECTION – D 17

FABRICATION OF STRUCTURAL STEEL WORK

Maharatna Company

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	GENERAL	3
3.00.00	WORKMANSHIP	19
4.00.00	INSPECTION, TESTING, ACCEPTANCE CRITERIA AND DELIVERY	29
5.00.00	INFORMATION TO BE SUBMITTED	33
6.00.00	RATES AND MEASUREMENTS	34

SUB-SECTION – D XVII

FABRICATION OF STRUCTURAL STEEL WORK

1.00.00 SCOPE

This specification covers supply, fabrication, testing, painting and delivery to site of structural steelwork including supply of all consumable stores and rivets, bolts, nuts, washers, electrodes and other materials required for fabrication and field connections of all structural steelwork covered under the scope of the contract.

2.00.00 GENERAL

2.01.00 Work to be provided for by the Contractor

The work to be provided for by the Contractor, unless otherwise specified elsewhere in the contract, shall include, but not be limited to the following

a) Preparation of complete detailed fabrication drawings and erection marking drawings required for all the structures covered under the scope of the contract based on the approved design drawings. As decided by the Engineer, some or all of these detailed drawings will have to be submitted for approval.

b) To submit revised design with calculations and detailed fabrication drawings in case any substitution of the designed sections are to be made.

c) To submit design calculations for joints and. connections developed by the contractor along with detailed fabrication drawings.

d) Furnish all materials, labour, tools and plant and all consumables required for fabrication and supply, all necessary rivets, bolts, nuts, washers, tie rods and welding electrodes for field connections,

e) Furnish shop painting of all fabricated steelwork as per requirements of this Specification.

f) Suitably mark, bundle, and pack for transport all fabricated materials.

g) Prepare and furnish detailed Bill of Materials, Drawing Office Dispatch lists, Rivet and Bolt List and any other list of bought out items required in connection with the fabrication and erection of the structural steelwork.

h) Insure, load and transport all fabricated steelwork field connection materials to site.

i) Maintain a fully equipped workshop at site for fabrication, modification and repairs of steelwork at site as may be required to complete the works in accordance with the Contract.

2.02.00 Work by others

No work under this specification will be provided for by any agency other than the contractor, unless specifically mentioned otherwise elsewhere in the contract.

2.03.00 Codes and standards

All work under this specification shall, unless otherwise specified in the contract, conform to the requirements of the latest revision and/or replacements of the following or any other relevant Indian Standard specifications and codes of practice. In case any particular aspect of the work is not specifically covered by any Indian Standard specification, any other standard practice, as may be specified by the Engineer shall be followed:

IS: 226 - Structural steel (Standard Quality)

IS: 800 - Code of Practice for general construction in steel.

IS: 806 - Code of practice for use of steel tubes in general building construction.

IS: 808 - Rolled steel beams, channels, and angle sections

IS: 813 - Scheme of symbols for welding

IS: 814 - Covered electrodes for metal arc welding of structural steel

IS: 815 - Classification and coding of covered electrodes for metal arc welding of structural steels.

IS: 816 - Code of practice for use of metal arc welding for general construction in mild steel

IS: 817 - Code of practice for training and testing metal arc welders

IS: 818 - Code of practice for safety and health requirements in electric and gas welding and cutting operations

IS: 822 - Code of practice for inspection of welds

IS: 919 - Recommendations for limits and fits for Engineering

IS: 961 - Structural Steel (High Tensile)

IS: 1148 - Rivet bars for structural purposes

IS: 1149 - High tensile rivet bars for structural purposes

IS: 1161 - Steel Tubes for structural purposes

IS: 1200 - Method of measurement of steelwork and ironwork (Part 8)

IS: 1239 - Mild Steel Tubes

IS: 1363 - Black hexagon bolts, nuts and lock nuts (dia. 6 to 30 mm) and black hexagon screws (Dia 6 to 24 mm)

IS: 1364 - Precision and semi-precision hexagon bolts, screws, nuts and l locknuts (Dia, range 6 to 39 mm)

IS: 1367 - Technical supply conditions for threaded fasteners

IS: 1442 - Covered electrodes for the metal are welding of high tensile structural steel

IS: 1608 - Method for tensile testing of steel products other than sheet strip, wire and tube

IS: 1730 - Dimensions for steel plate, sheet, and strip for structural and general engineering purposes.

IS: 1731 - Dimensions for steel flats for structural and general engineering purposes

IS: 1852 - Rolling and cutting tolerances for hot-rolled steel products

IS: 1977 - Structural steel (ordinary quality) St-42-0

IS: 2062 - Steel for General Structural Purposes

IS: 2074 - Ready mixed paint, red oxide Zinc chromate priming

IS: 2595 - Code of Practice for Radiographic Testing

IS: 2629 - Recommended practice for Hot-Dip Galvanizing of Iron and Steel

IS: 2633 - Method for testing uniformity of coating on Zinc Coated Articles

IS: 3757 - High strength structural bolts

IS: 4759 - Specifications for Hot-Dip Zinc Coatings on Structural Steel and other allied products

IS: 7205 - Safety Code for Erection of Structural Steelwork

IS: 7215 - Tolerances for fabrication of steel structures

IS: 7280 - Bare wire electrodes for submerged arc welding of structural steels.

IS: 9595 - Recommendations for metal arc welding of carbon and carbon manganese steels.

2.04.00 Conformity with Designs

The contractor shall design all connections, supply and fabricate all steelwork and furnish all connection materials in accordance with the approved drawings and/or as instructed by the Engineer keeping in view the maximum Utilization of the available sizes and sections of steel materials. The methods of painting, marking, packing and delivery of all fabricated materials shall be in accordance with the provisions of the contract and/or as approved by the Engineer. Provision of all relevant Indian Standard Specifications and Codes of Practice shall be followed unless otherwise specified in the contract.

2.05.00 Materials to be used

2.05.01 General

All steel materials required for the work will be supplied by the contractor unless otherwise specified elsewhere in the contract. The materials shall be free from all imperfections, mill scales, slag intrusions, laminations, fittings, rusts etc. that may impair their strength, durability, and appearance. All materials shall be of tested quality only unless otherwise permitted by the Engineer and/or Consultant. If desired by the Engineer, Test Certificates in respect of each consignment shall be submitted in triplicate. Whenever the materials are required to be used from unidentified stocks, if permitted by the Engineer, a random sample shall be tested at an approved laboratory from each lot of 50 tones or less of any particular section.

The arc welding electrodes shall be of approved reputed manufacture and conforming to the relevant Indian Standard Codes of Practice and Specifications and shall be of heavily coated type and the thickness of the coating shall be uniform and concentric. With each container of electrodes, the manufacturer shall furnish instructions giving recommended voltage and

amperage (Polarity in case of D.C. supply) for which the electrodes are suitable.

2.05.02 Steel

All steel materials to be used in construction within the purview of this specification shall comply with any of the following Indian Standard Specifications as may be applicable:

a) IS: 2062 - Steel for general structural purposes

b) IS: 961 - Structural steel High Tensile

c) IS: 1977 - Structural steel (Ordinary quality) St-42-0

In case of imported steel materials being used, these shall conform to specifications equivalent to any of the above as may be applicable.

2.05.03 Rivet Steel

All rivet steel used in construction within the purview of this Specification shall comply with one of the following Indian Standard Specifications as may be applicable:

a) IS: 1148 - Rivet Bars for structural purpose

b) IS: 1149 - High tensile rivet bars for structural purposes. Where high tensile steel is specified for rivets, steps shall be taken to ensure that the rivets are so manufactured that they can be driven and heads formed satisfactorily without the physical properties of steel being impaired.

2.05.04 Electrodes

All electrodes to be used under the Contract shall be of approved reputed manufacture, low hydrogen electrode and shall comply with any of the following Indian Standard Specifications as may be applicable

a) IS: 814 - Covered electrodes for metal arc welding of structural steel

b) IS: 815 - Classification and coding of covered electrodes for metal arc welding of mild steel and low alloy high tensile steel

c) IS: 1442 - Covered electrodes for the metal arc welding of high tensile structural steel

d) IS: 7280 - Bare wire electrodes for submerged arc welding of structural steels

2.05.05 Bolts and Nuts

All bolts and nuts shall conform to the requirements of Indian Standard Specification IS: 1367 - Technical Supply Conditions for Threaded Fasteners.

Materials for Bolts and nuts under the purview of this contract shall comply with any of the following Indian Standard Specifications as may be applicable.

a) Mild Steel

All mild steel for bolts and nuts when tested in accordance with the following Indian Standard Specification shall have a tensile strength of not less than 44 Kg/mm² and a minimum elongation of 23 per cent on a gauge length of 5.6 _/A, where "A" is the cross sectional area of the test specimen

i) IS: 1367: Technical supply conditions for threaded fasteners

ii) IS: 1608: Method for tensile testing of steel products other than sheet, strip, wire and tube

b) High Tensile Steel

The material used for the manufacture of high tensile steel bolts and nuts shall have the mechanical properties appropriate to the particular class of steel as set out in IS: 1367 or as approved by the Engineer.

2.05.06 Washers

Washers shall be made of steel conforming to any of the following Indian Standard Specifications as may be applicable under the provisions of the Contract:

a) IS: 2062 - Steel for general structural purposes

b) IS: 961 - Structural Steel (High Tensile Quality)

c) IS: 1977 - Structural steel (Ordinary Quality) St-42-0

d) IS: 6649 - Hardened washers

2.05.07 Paints

Paints to be used for shop coat of fabricated steel under the purview of this contract shall conform to the Indian Standard Specification IS: 2074 - Ready Mixed Paint, Red oxide Zinc Chromate Priming.

2.06.00 Coal Bin

2.06.01 Shape of bins shall be circular, polygonal, square, or rectangular in plan. Bottom hopper portion may have been conical-cum-hyperbolic or any other profile shape as shown in the drawing. Bin shall be termed as bunkers or silos according to their shape and plane of rupture of coal.

2.06.02 For general requirements, fabrication and construction details IS: 9178 (Pt. l & 11) shall be followed as general guidance. The bins shall be fabricated and erected in segments.

2.06.03 The Coal bins shall be made of mild steel plates joined together with full strength butt weld and provided with stiffeners at regular interval. Stiffeners shall be provided on the external face and it may be welded with external face.

2.06.04 Bending of plates and rolled sections to the required shape for fabrication shall be done by plate bending machine or cold bending process Without resorting to heating, hammering, angle smithy and black smithy process.

2.06.05 Poking hole (manual or pneumatic) and striking plate shall be provided to facilitate coal flow. Poking holes shall have circular MS pipe and cover cap as detailed in the drawing.

2.07.00 New Erection Marks

2.07.01 Additional structures involving new erection marks may be required to be added at any stage of work.

2.07.02 All such new erection marks shall be detailed and included in marking schemes and fabrication carded out thereafter.

2.07.03 All such new erection marks shall be considered under item of original fabrication work. As a result of additional structures becoming necessary if the work is delayed beyond the time schedule stipulated, the Engineer shall give suitable extension of time provided he is satisfied about the reasonableness of the delay involved. However, no claim for extra payments or revision of rates due to delay shall be entertained.

2.08.00 ELECTRO FORGED STEEL GRATINGS

2.08.01 Factory made fabricated electro forged gratings unit with steel conforming to IS: 2062 shall be supplied, fabricated, transported, erected and aligned in floorings, platforms, drain and trench covers, walkways, passages, staircases with edge binding strips and anti skid nosing in treads etc.

2.08.02 All grating units shall be rectangular in pattern and electro forged. The size and the spacing of the bearing bars and cross bars shall be as detailed in fabrication drawings. The contractor shall submit the grating design for different spans and load intensities along with fabrication drawings. The depth of the grating unit shall be 40 mm, unless specified otherwise.

2.08.03 The gratings shall be made up in panel units designed to coincide with the span of the structural steel framing or openings as indicated in the design/ scope drawings. Maximum possible standardization of the grating panel sizes shall be tried and designed.

2.08.04 The grating unit shall be accurately fabricated and finished, free from wraps, twists, or any defects that would impair their strength, serviceability, and appearance.

2.08.05 Grating work shall include cut outs and clearance opening for all columns, pipes, ducts, conduits or any other installation penetrating through the grating work. Such cut outs and clearances shall be treated as specified in subsequent clauses.

2.08.06 The gratings shall be notched, trimmed and neatly finished around flanges and webs of the columns, moment connections, cap plates, and such other components of the steel structures encountered during the placement of the gratings. In all such cases, the trimming shall be done to follow the profile of the components encountered. After trimming, the binding strip shall be provided on the grating to suit the profile so obtained.

2.08.07 Opening in gratings for pipes or ducts that are 150mm in size or diameter or larger shall be provided with steel bar toe plates of not less than 5mm thickness and appropriate width, set flush with the bottom of the bearing bars.

2.08.08 Penetrations in gratings that are more than 50mm but less than 150mm in size or diameter shall be welded with plates of size shown in the detailed drawings set flush with the bottom of the grating panel.

2.08.09 Unless otherwise indicated on the drawings, grating units at all penetrations shall be made up in split section, accurately fitted and neatly finished to provide for proper assembly and erection at the job site.

2.08.10 Grating units shall be provided with all necessary clips, bolts, nuts and lock washers required for proper assembly and rigid installation and fastening to abutting units supporting structural steel framing members.

2.08.11 The gratings shall be of reputed make and manufacturer, as approved by Engineer. The unit rate quoted by him for this item shall be inclusive of transport of gratings to the project site, all taxes, duties etc. He shall also provide all facilities and access to the Engineer or his representative to carry out inspection during all stages of manufacturing of gratings.

2.08.12 Maximum deviation in linear dimension from the approved dimension shall not exceed 12mm.

2.08.13 All fabricated grating section and accessories shall be blast cleaned to near white metal surface (Sa 2½) followed by either of the following two:

(a) Two coats of red lead primer and two coats of black enamel finish paint.

(b) Hot dipped galvanization at 610 gm/sq.m.

in the shop prior to erection at site, as the approved drawing.

2.08.14 Prior to finishing all surfaces shall be cleaned, free from rust, mill scale, grease, oil, or any other foreign matter by blast cleaning. BS: 4232 shall be followed for blast cleaning.

2.08.15 Primer can be applied by spray guns or by brushes, however the finish paint shall necessarily be applied by means of spray guns. The applied coatings shall be uniform, free from voids and streaks; drilled or punched holes shall be touched up prior to erection or assembly.

2.09.00 GALVANIZATION OF GRATINGS

2.09.01 Purity of Zinc to be used-for galvanizing shall be 99.5% as per IS: 2 15

2.09.02 After the shop work is complete, the structural material shall be punched with erection mark and be hot double dip galvanized. Before galvanizing the steel section shall be thoroughly blast cleaned to near white metal surface (Sa 2½).

2.09.03 The weight of the zinc coating shall be at least 610 gm/m² - unless noted otherwise.

2.09.04 The galvanized surface shall consist of a continuous and uniformly thick coating of zinc, firmly adhering to the surface of steel. The finished surface shall be cleaned and smooth and shall be free from defects like discoloured patches, bare spots, unevenness of coating, spelter that is loosely attached to

the steel, blistered surface, flaking or peeling off etc. The presence of any of these defects noticed on visual or microscopic inspection shall render the material liable to rejection.

2.09.05 There shall be no flaking or loosening when struck squarely with a chisel faced hammer. The galvanized steel member shall withstand minimum four one minute dips in copper sulphate solution as per IS: 2633.

2.09.06 When the steel section is removed from the galvanizing kettle, excess spelter shall be removed by 'bumping'. The processes known as 'wiping' or 'scrapping' shall not be used for this purpose.

2.09.07 Defects in certain members indicating presence of impurities in the galvanizing bath in quantities larger than that permitted by the specifications or lack of quality control in any manner in the galvanizing plant, shall render the entire, production in the relevant shift liable to rejection.

2.09.08 All structural steel shall be treated with sodium dichromate or an approved equivalent solution after galvanizing; so as to prevent white storage stains.

2.09.09 If the galvanizing of any member is damaged, the Engineer shall be shown of the extent of damage, if so directed the galvanizing may have to the redone in the similar manner as stated above at no extra cost to the Owner.

2.10.00 STAINLESS STEEL HOPPERS (As per BOQ item)

2.10.01 Material

In case SS Hopper is to be fabricated & erected as per BOQ item with SS415M, following specification shall be followed.
Stainless steel hopper of grade SS 415M as manufactured by SAIL or equivalent shall be provided in the lower portion of bunker hopper. SS 4 15M having the following chemical composition shall be used.

Material	**%**	**Remarks**
Carbon	10.03%	Max.
Silicon	1.60%	Max.
Manganese	0.80% to 1.50%	
Phosphorous	0.03%	Max.
Sulphur	0.03%	Max.
Chromium	10.80% to 12.50%	

Nickel	1.50%	Max.
Titanium	0.75%	Max.
Nitrogen	0.03%	Max.

The mechanical properties shall be as follows:

Description	**Value**	**Remarks**
Hardness Rock Well B Scale	90	Max.
Tensile Strength	450 MPa	Min.
Yield Strength	300 MPa	Min.
Elongation	25%	Min.

2.10.02 Fabrication

The fabrication, erection, alignment and welding shall be carried out as per the accepted practice and in accordance with relevant I.S. and international specification as well as stipulations contained herein. Fabrication drawings shall be prepared by the contractor on the basis of the design / scope drawings furnished by Engineer. The fabrication and erection works shall be done as per the approved fabrication drawings.

2.10.03 Fabrication Drawings

a) Fabrication drawing shall give the cutting plan for each hopper plate. Such, cutting plan shall be based on the size of the Stainless Steel plate available at store. In order to reduce the wastage and ensure the maximum utilization of stainless steel plate, the cutting plan shall take in the consideration of the reverse curvature and place the various elements of hopper plate in opposite fashion to reduce the end wastage. Similarly, the hopper plate element having different radii shall be placed one inside the other, to optimize the stainless steel plate use. Such optimization may also require adjustment in the size of each element of hopper plate and also additional weld joints.

b) The bill of material of hopper plate shall indicate the inner surface area of the hopper, weight of the hopper based on the inner surface area, weight of each of the cut plate of hopper fabrication, weight of cut and scrap pieces generated. Contractor shall return to the Owner's store all unutilized (surplus) stainless steel plates and all waste and cut pieces generated. Non return of any part of the surplus/waste steel pieces to the Owner's store

will call for the penal recovery at three (03) times the maximum procurement rate for the weight of stainless steel pieces not returned to the store.

c) In case the contractor does the cutting of the stainless steel without approved cutting plan then all the wastage (i.e. the difference between the weight of stainless steel plate cuts and the actual finished weight considered for the measurement for payment) shall be subjected to the penal recovery at the rate mentioned above.

2.10.04 Cuffing

Cutting may be affected by shearing, or by using plasma. The cut edges of all plates shall be perfectly straight and uniform through out. Cutting shall be done as per the cutting plan shown in the fabrication drawing. Should the Engineer find it necessary, the edges shall be ground smooth afterwards by contractor within the unit rates quoted by him. All the edge s shall be ground smooth before they are welded.

2.10.05 Jointing

Welding shall join stainless steel. All weld joints (along the inclined plane) shall be staggered. Any common welding process can weld stainless steel viz. MIG, metal arc or plasma using the covered compatible electrodes as per IS: 5206 or by inert gas arc welding as per IS: 2811. Shielding gas shall be Argon + Hydrogen mixture or Argon + Oxygen mixture. However, Argon + Oxygen mixture shall be preferred. Carbon-di-oxide mixture shall be avoided. 308L and 315L electrodes/fillers shall be used for the welding of Stainless Steel to Stainless Steel and Stainless Steel to Mild Steel respectively. However, the welding process and the type of the electrodes to be used for welding shall be as per welding procedure, as approved by the Engineer. On the basis of the welding procedure, the Contractor shall conduct qualification test.

2.10.06 Bending

The stainless steel plates shall be subjected to cold forming and bending in order to get the desired shape and profile.

2.10.07 Welding sequence

The type of electrodes, welding sequence, preheat and interpass temperature and post weld heat treatment shall be as approved by the Engineer.

2.10.08 Acceptance Criteria of Fabricated Structures

The acceptance of the fabricated structure work shall depend upon correct dimensions and alignment, absence of distortion in the structure, satisfactory

results from the inspection and testing of the welded structure joints and the test specimens, general workmanship being good meeting the tolerance requirements given in IS: 7215.

2.11.00 BEARINGS

2.11.01 PTFE (Poly tetra fluorethylene) slide bearing

a) General

The bearings shall consist of upper and lower units. The upper unit shall include a sole plate with mirror finish stainless steel facing bonded to the bottom surface of the sole plate. The lower unit shall consist of a relevant laminated elastomers pad surfaced with PTFE. A rigid confining medium substructure bonds the PTFE to the pad. When the upper and lower units are mated the stainless steel slides on the PTFE surface with an extremely low coefficient of friction. These bearings shall be designed as per the performance requirements. The bearing shall be of reputed make and manufacturer as approved by Engineer, for required vertical loads, as per the construction drawings and for a maximum displacement of ± 50 mm.

b) Material

PTFE bearing shall be sliding against highly polished stainless steel and the coefficient of friction between them shall be less than 0.06 at 55 kg/cm². In order to prevent cold flow in the PTFE surface it shall be rigidly bonded by a special high temperature resistant adhesive to the stainless steel sub-strata. The stainless steel surface, which slides against the PTFE, is mirror polished. The stainless steel shall be bonded to the top plate by special high strength adhesive. The thickness of the stainless steel shall be between 1.0 to 1.5mm.

The resilient bearing pad shall consist of multiple layers of lightweight fabric impregnated with a high quality elastomer compound vulcanized into slabs of uniform standard thickness as per the requirement. This shall withstand vertical (compressive) load not less than 500 kg/cm² and shear loads upto 40 kg/cm².

c) Installation

The seating area for PTFE bearing shall be prepared accurately level and furnished with a thin layer of epoxy resin mortar. The bearing will be placed on this layer while it is still workable and the bearing is levelled. The bearing should not be displaced as the beam is lowered into position. When the mortar and adhesive are fully set and the beam slightly above the top of the bearing. The upper surface of the bearing shall then be coated with sufficient thickness of epoxy resin mortar so that when the

beam is lowered on to the temporary supports it comes into full contact with the mortar and some is squeezed out. The surplus shall be troweled off and after the mortar is fully set the temporary supports removed.

2.12.00 Storage of material

2.12.01 General

All materials shall be so stored as to prevent deterioration and to ensure the preservation of their quality and fitness for the work. Any material, which has deteriorated or has been damaged, shall be removed from the contractor's yard immediately, failing which, the Engineer shall be at liberty to get the material removed and the cost incurred thereof shall be realised from the Contractor. The Contractor shall maintain upto date accounts in respect of receipt, use, and balance of all sizes and sections of steel and other materials. In case the fabrication is carried out in contractor's fabrication shop outside the plant site where other fabrication works are also carried out, all materials meant for use in this contract shall be stacked separately with easily identifiable marks.

2.12.02 Steel

The steel to be used in fabrication and the resulting cut-pieces shall be stored in separate stacks off the ground section wise and lengthwise so that they can be easily inspected, measured, and accounted for at any time. If required by the Engineer, the materials may have to be stored under cover and suitably painted for protection against weather.

2.12.03 Electrodes

The electrodes for electric arc welding shall be stored in properly designed racks, separating different types of electrodes in distinctly marked compartments. The electrodes shall be kept in a dry and warm condition if necessary by resorting to heating.

2.12.04 Bolts, Nuts and Washers

Bolts, nuts and washers and other fastening materials shall be stored on racks off the ground with a coating of suitable protective oil. These shall be stored in separate gunny bags or compartments according to diameter, length, and quality.

2.12.05 Paints

Paints shall be stored under cover in air tight containers. Paints supplied in sealed containers shall be used up as soon as possible once the container is opened.

2.13.00 Quality Control

The Contractor shall establish and maintain quality control procedures for different items of work and materials to the extent he deems necessary to ensure that all work is performed in accordance with this specification. In addition to the Contractor's quality control procedures, materials and workmanship at all times shall be subjected to inspection by the Engineer or Engineer's representative. As far as possible, all inspection by the Engineer or Engineer's representative shall be made at the Contractor's fabrication shop whether located at Site or elsewhere. The Contractor shall co-operate with the Engineer or Engineer's representative in permitting access for inspection to all places where work is being done and in providing free of cost all necessary help in respect of tools and plants, instrument, labour and materials required to carry out the inspection. The inspection shall be so scheduled as to provide the minimum interruption to the work of the Contractor.

Materials or workmanship not in reasonable conformance with the provisions of this Specification may be rejected at any time during the progress of the work.

The quality control procedure shall cover but not be limited to the following items of work

a) Steel: Quality manufacturer's test certificates, test reports of representative samples of materials from unidentified stocks if permitted to be used.

b) Rivets, Bolts, Nuts & Washers : Manufacturer's certificate, dimension checks, material testing.

c) Electrodes : Manufacturer's certificate, thickness and quality of flux coating.

d) Welders : Qualifying Tests

e) Welding sets : Performance Tests

f) Welds : Inspection, X-ray, Ultrasonic tests

g) Paints : Manufacturer's certificate, physical inspection reports

h) Galvanizing : Tests in accordance with IS 2633 - Method for testing uniformity of coating on Zinc Coated Articles and IS : 4759 - Specification for Hot-Dip Zinc coatings on Structural Steel and other allied products.

2.14.00 Standard dimensions, forms and weights

The dimensions, forms, weights and tolerances of all rolled shapes rivets, bolts, nuts, studs, washers etc. and other members used in the fabrication of any structure shall, wherever applicable, conform to the requirements of the latest relevant Indian Standards, wherever they exist, or, in the absence of Indian Standards, to other equivalent standards.

2.15.00 Fabrication Drawings

The contractor shall within thirty (30) days after the award of the Contract submit to the Engineer the Schedule of Fabrication and erection of structural Steelworks, for approval. Within one week after receipt of approval on design of any steel structure (part or full) based on the approved design. As decided by the Engineer, six (6) copies each of some or all of the detailed fabrication drawings will have to be submitted for approval.

The sequence of preparation of fabrication drawings shall match with the approved fabrication and erection schedule. The above-mentioned approval for fabrication drawings will be accorded only towards the general conformity with the design requirements as well as specifications. The approval of drawing however shall not relieve the contractor of his sole responsibility in carrying out the work correctly and fulfilling the complete requirements of contract documents.

The fabrication drawings shall include but not limited to the following:

a) Assembly drawings giving exact sizes of the sections to be used and identification marks of the various sections.

b) Dimensional drawings of base plates, foundation bolts location etc.

c) Comparison sheets to show that the proposed alternative section, if any, is as strong as the original sections shown on the Design Drawings.

d) Complete Bill of Materials and detailed drawings of all sections as also their billing weights.

e) Any other drawings or calculations that may be required for the clarification of the works or substituted parts thereof.

These drawings shall give all the necessary information for the fabrication, erection, and painting of the steelwork in accordance with the provisions of this Specification. Fabrication drawings shall be made in accordance with the best modern practice and with due regard to sequence, speed and economy in fabrication and erection. Fabrication drawings shall give complete information

necessary for fabrication of the various components of the steelwork, including the location, type, size, and extent of welds. These shall also clearly distinguish between shop and field rivets, bolts, and welds and specify the class of bolts and nuts. The drawings shall be drawn to a scale large enough to convey all the necessary information adequately. Notes on the fabrication drawings shall indicate those joints or groups of joints in which it is particularly important that the welding sequence and technique of welding shall be carefully controlled to minimize the locked up stresses and distortion. Welding symbols used shall be in accordance with the requirements of the Indian Standard Specification. IS: 813 - Scheme of symbols for Welding, and shall be consistent throughout. Weld lengths called for on the drawings shall mean the net effective length.

The Contractor shall be responsible for and shall carry out at his cost any alterations of the work due to any discrepancies, errors or omissions on the drawings or other particulars supplied by him, whether such drawings or other particulars have been duly approved or not in accordance with the Contract.

3.00.00 WORKMANSHIP

3.01.00 Fabrication

3.01.01 General

All workmanship shall be equal to the best practice in modern structural shops, and shall conform to the provisions of the Indian Standard IS: 800 - Code of Practice for general construction in steel and other relevant Indian Standards or equivalent.

3.01.02 Straightening Material

Rolled materials before being laid off or worked, must be clean, free from sharp kinks, bends or twists and straight within the tolerances allowed by the Indian Standard Specification on IS: 1552 - Specification for rolling and cutting tolerance for hot-rolled steel products. If straightening is necessary, it may be done by mechanical means or by the application of a limited amount of localized heat. The temperature of heated areas, as measured by approved methods, shall not exceed 600°C.

3.01.03 Cutting

Shearing, cropping, or sawing shall affect cutting. Use of a mechanically controlled gas-cutting torch may be permitted for mild steel only. Gas cutting of high tensile steel may also be permitted provided special care is taken to leave sufficient metal to be removed by machining, so that all metal that has been hardened by flame is removed. Gas cutting without a mechanically controlled torch may be permitted if special care is taken and done under

expert hand, subject to the approval of the Engineer.

To determine the effective size of members cut by gas, 3 mm shall be deducted from each cut edge. Gas cut edges, which will be subjected to substantial stress or which are to have weld metal deposited on them, shall be reasonably free from gouges, occasional notches or gouges not more than 4 mm deep will be permitted. Gouges greater than 4 mm that remain from cutting shall be removed by grinding. All re-entrant corners shall be shaped notch free to a radius of at least 12 mm. Shearing, cropping and gas cutting shall be clean, reasonably square and free from any distortion.

3.01.04 Planning of edges

Planning or finishing of sheared or cropped edges of plates or shapes or of edges gas-cut with a mechanically controlled torch shall not be required, unless specifically required by design and called for on the drawings, included in a stipulation for edge preparation for welding or as may be required after the inspection of the cut surface. Surface cut with hand-flame shall generally be ground, unless specifically instructed otherwise by the Engineer.

3.01.05 Clearances

The erection clearance for cleated ends of members connecting steel to steel shall preferably be not greater than 2 mm at each end. The erection clearance at ends of beams web shall be not more than 3 mm at each end, but where for practical reasons greater clearance is necessary, suitably designed cheatings shall be provided.

3.02.00 Riveted and bolted construction

3.02.01 Holes

Holes through more than one thickness of material for members, such as compound stanchions and girder flanges, shall be drilled after the members are assembled and tightly clamped or bolted together. Punching may be permitted before assembly, if the thickness of the material is not greater than the nominal diameter of rivet or bolt plus 3 mm subject to a maximum thickness of 16 mm provided that the holes are punched 3 mm less in diameter than the required size and reamed after assembly to the full diameter.

Holes for rivets or black bolts shall be not more than 1.5 mm or 2.0 mm (depending on whether the diameter of the rivet or bolt is less or more than or equal to 25 mm) larger in diameter than the nominal diameter of the rivet or black bolt passing through them.

Holes for turned and fitted bolts shall be drilled to a diameter equal to the nominal diameter of the shank or barrel subject to a tolerance grade of BS as

specified in IS: 919. Parts to be connected shall be firmly held together by tacking welds or clamps and the holes drilled through all the thicknesses in one operation and subsequently reamed to size. Holes not drilled through all thickness in one operation shall be drilled to a smaller size and reamed out after assembly.

Holes for rivets or bolts shall not be formed by gas cutting process.

3.02.02 Assembly

All parts of riveted members shall be well pinned or bolted and rigidly held together while riveting. Drifting to enlarge unmatching holes shall not generally be permitted. In case drifting is permitted to a slight extent during assembly, it shall not distort the metal or enlarge the holes. Holes that must be enlarged to admit the rivets or bolts shall be reamed. Poor matching of holes shall be cause for rejection. The component parts shall be so assembled that they are neither twisted not otherwise damaged, and shall be so prepared that the specified cambers, if any, are maintained.

Rivets shall ordinarily be hot driven, in which case their finished heads shall be approximately hemispherical in shape and shall be of uniform size throughout the work for rivets of the same size full, neatly finished and concentric with he holes. Rivets shall be heated uniformly to a temperature not exceeding 1 125°C they shall not be driven after their temperature has fallen below 540°C.

Rivets shall be driven by power riveters, of either compression or manually operated type, employing pneumatic, hydraulic or electric power. Hand driven rivets shall not be allowed unless in exceptional cases specifically approved by the Engineer. After driving, rivets shall be tight, shall completely fill the holes and their heads shall be in full contact with the surface. In case of countersunk rivets, the countersinking shall be fully filled by the rivet, any proudness of the countersunk head being dressed off flush, if required.

Riveted members shall have all parts firmly drawn and held together before and during riveting and special care shall be taken in this respect for all single riveted connections. For multiple riveted connections, a service bolt shall be provided in every third or fourth hole.

All loose, burnt, or otherwise defective rivets shall be cut out and replaced and special care shall be taken to inspect all single riveted connections. Special care shall also be taken in heating and driving long rivets. The Contractor shall prove the quality of riveting by cutting some rivets chosen at random by the Engineer. No extra payment will be made to the Contractor for such cutting and replacing. Riveting work, for any particular section or group, will be considered satisfactory when at least 90% of the corresponding cut rivets is found to be sound. If the ratio is below 75%, all the rivets in the particular

section or group shall be cut, removed and replaced and tested again at the Contractor's expense. For cases between 75% and 90% the engineer shall have the option to instruct cutting and replacing any number of further rivets at the Contractor's cost as he deems necessary.

Bolted construction shall be permitted only in case of field connections if called for on the Drawings and is subjected to the limitation of particular connections as may be specified. In special cases, however, shop bolt connections may be allowed if shown on drawing or directed by the Engineer.

Washers shall be tapered or otherwise suitably shaped, where necessary, to give the heads and nuts of bolts a satisfactory bearing. The threaded portion of each bolt shall project trough the nut at least one thread. In all cases the bolt shall be provided with a washer of sufficient thickness under the nut to avoid any threaded portion of the bolt being within the thickness of the parts bolted together. In addition to the normal washer one spring washer or lock nut shall be provided for each bolt for connections subjected to vibrating forces or otherwise as may be specified on the Drawings.

3.03.00 Welded Construction

3.03.01 General

Welding shall be in accordance with relevant Indian Standards and as supplemented in the Specification. Welding shall be done by experienced and good welders who have been qualified by tests in accordance with IS: 817.

3.03.02 Preparation of material

Surface to be welded shall be free from loose scale, slag, rust, grease, paint, and any other foreign material except that mill scale, which withstands vigorous wire brushing, may remain. Joint surfaces shall be free from fins and tears. Preparation of edges by gas cutting shall, wherever practicable, be done by a mechanically guided torch.

3.03.03 Assembling

Parts to be fillet welded shall be brought in, as close contact as practicable and in no event shall be separated by more than 4 mm. If the separation is 1.5 mm or greater, the size of the fillet welds shall be increased by the amount of the separation. The fit of joints at contact surfaces, which are not completely sealed by, welds, shall be close enough to exclude water after painting. Abutting parts to be butt-welded shall be carefully aligned. Misalignments greater than 3 mm shall be corrected and in making the correction the parts shall not be drawn into a sharper slope than two degrees (2°).

The work shall be positioned for flat welding whenever practicable.

3.03.04 Welding Sequence

In assembling and joining parts of a structure or of built-up members, the procedure and sequence of welding shall be such as will avoid needless distortion and minimize shrinkage stresses in the closing welds of a rigid assembly, such closing welds shall be made in compression elements.

In the fabrication of cover-plated beams and built-up members, all shop splices in each component part shall be made before such component part is welded to other parts of the member. Long girders or girder sections may be made by shod splicing not more than three sub-sections, each made in accordance with this paragraph.

When required by the Engineer, welded assemblies shall be stress relieved by heat-treating in accordance with the provisions of the relevant Indian Standard or any other Standard approved by the Engineer.

3.03.05 Welding technique

All complete penetration groove welds made by manual welding, except when produced with the aid of backing material not more than 8 m thick with root opening not less than one-half the thickness of the thinner part joined, shall have the root of the initial layer gouged out on the back side before welding is started from that side, and shall be so welded as to secure sound metal and complete fusion throughout the entire cross-section. Groove welds made with the use of the backing of the same material, as the base metal shall have the weld metal thoroughly fused with the backing material. Backing strips need not be removed. If required, they may be removed by gouging or gas cutting after welding is completed, provided no injury is done to the base metal and weld metal and the weld metal surface is left flush or slightly convex with full throat thickness.

Groove welds shall be terminated at the ends of a joint in a manner that will ensure their soundness. Where possible, this should be done by use of extension bars or run-off plates. Extension bars or run-off plates need not be removed upon completion of the weld unless otherwise specified elsewhere in the contract.
To get the best and consistent quality of welding, automatic submerged arc process shall be preferred. The technique of welding employed, the appearance and quality of welds made, and the methods of correcting defective work shall all conform to the relevant Indian Standards.

3.03. 12 Temperature

No welding shall normally be done on parent material at a temperature below (-) 5°C. However, if welding is to undertaken at low temperature, adequate

precautions as recommended in relevant Indian Standard shall be taken. When the parent material is less than 40 mm thick and the temperature is between (-) 5°C and 0°C, the surface around the joint to a distance of 100 mm or 4 times the thickness of the material, whichever is greater, shall be preheated till it is hand warm. When the parent material is more than 40 mm thick, the temperature of the area mentioned above shall be in no case be less than 20°C. All requirements regarding preheating of the parent material shall be in accordance with the relevant Indian Standard.

3.03. 13 Peening

Where required, intermediate layers of multiple-layer welds may be peened with light blows from a power hammer, using a round-nose tool, peening shall be done after the weld has cooled to a temperature warm to the hand. Care shall be exercised to prevent scaling or flaking of weld and base metal from over peening.

3.03. 14 Equipment

These shall be capable of producing proper current so that the operator may produce satisfactory welds. The welding machine shall be of a type and capacity as recommended by the manufacturers of electrodes or as may be approved by the engineer.

3.04.00 Finish

Column splices and butt joints of compression members depending on contact for stress transmission shall be accurately machined and close-butted over the whole section with a clearance not exceeding 0.1 mm locally at any place. In column caps and bases, the ends of shafts together with the attached gussets, angles, channels etc; after welding/riveting together, should be accurately machined so that the parts connected butt over the entire surfaces of contact. Care should be taken that those connecting angles of channels are fixed with such accuracy that they are not reduced in thickness by machining by more than 1.0 mm.

3.05.00 Slab bases and caps

Bases and caps fabricated out of steel slabs, except when cut material with true surface, shall be accurately machined over the bearing surface and shall be in effective contact with the end of the stanchion. A bearing face, which is to be grouted direct to a foundation, need not be machined if such face is true and parallel to the upper face.

To facilitate grouting, holes shall be provided, where necessary, in stanchion bases for the escape of air.

3. 12.00 Lacing bars

The ends of lacing bars shall be neat and free from burns.

3. 13.00 Separators

Rolled section or built-up steel separators or diaphragms shall be required for all double beams except where encased in concrete, in which case, pipe separators shall be used.

3.14.00 Bearing Plates

Provision shall be made for all necessary steel bearing plates to take up reaction of beams and columns and the required stiffeners and gussets whether or not specified in Drawings.

3.15.00 Floor Grating

All grating units shall be rectangular in pattern and of pressure locked assembly. The size and spacing of bearing bars and cross bars shall be as approved in detailed drawings. Alternatively, diamond pattern grating if approved may be used.

The grating shall be made in panel units designed to span as indicated in structural steel framing drawing or as directed by the Engineer.

The grating units shall be finished free from warps, twists, or any other defects. Grating work shall include cutouts and clearance openings for all columns, pipes, ducts, conduits etc. The gratings shall be notched, trimmed, and neatly finished around components of the steel structures encountered. Binding strip shall be provided on the grating to suit the profile. Openings in gratings shall be provided with steel bar toe plates of not less than 5 mm thickness and 100 mm width.

Unless otherwise indicated on drawings, all penetrations of grating units shall be made up in split section, accurately fitted, and neatly finished. Grating units shall be provided with all necessary clips, bolts, lock washers etc. for proper assembly and installation on supporting steel members. Maximum deviation in linear dimension shall not exceed 12 mm.

3.10.00 Chequered Plates

Minimum thickness of chequered plate floorings, covers etc. shall be 6 mm O/P. Chequered plate shall be accurately cut to the required sizes and shapes and the cut edges properly ground. Stiffeners shall be provided wherever required from design consideration.

3.11.00 Architectural Clearances

Bearing plates and stiffener connections shall not be permitted to encroach on the designed architectural clearances.

3.11.00 Shop connections

a) All shop connections shall be otherwise riveted or welded as specified on the Drawings.

b) Heads of rivets on surfaces carrying brick walls shall be flattened to 10 mm thick projection.

c) Certain connections, specified to be shop connections, may be changed to field connections if desired by the Engineer for convenience of erection and the contractor will have to make the desired changes at no extra cost to the exchequer.

3.13.00 Castings

Steel castings shall be annealed.

3.14.00 Shop erection

The steelwork shall be temporarily shop-erected complete or as directed by the Engineer so that accuracy of fit may be checked before dispatch. The parts shall be shop-erected with a sufficient number of parallel drifts to bring and keep the parts in place. In case of parts drilled or punched using steel jigs to make all similar parts interchangeable, the steelwork shall be shop erected in such a way as will facilitate the check of interchange ability.

3.15.00 Shop painting

3.15.01 General

Unless otherwise specified, steelwork, which will be concealed by interior building finish, need not be painted; steelwork to be encased in concrete shall not be painted. Unless specifically exempted, all other steelwork shall be given one coat of shop paint, applied thoroughly and evenly to dry surfaces which have been cleaned, in accordance with the following paragraph, by brush, spray, roller coating, flow-coating or dipping as may be approved by the Engineer.

After inspection and approval and before leaving the shop, all steelwork specified to be painted shall be cleaned by hand-wire brushing or by other methods of loose mill scale, loose rust, weld slag or flux deposit, dirt and other foreign matter. Oil and grease deposits shall be removed by the solvent. Steelwork specified to have no shop paint shall, after fabrication, be cleaned of oil or grease by solvent cleaners and be cleaned of dirt and other foreign material by trough sweeping with a fibre brush.

3.15.02 Inaccessible parts

Surfaces not in contact, but inaccessible after assembly, shall receive two coats of shop paint, positively of different colours to prove application of two coats before assembly. This does not apply to the interior of sealed hollow sections.

3.15.03 Contact surfaces

Contact surface shall be cleaned in accordance with sub-clause 3.13.1 before assembly.

3.15.04 Finished surfaces

Machine finished surfaces shall be protected against corrosion by a rust inhibiting coating that can be easily removed prior to erection or which has characteristics that make removal unnecessary prior to erection.

3.15.05 Surfaces adjacent to field welds

Unless otherwise provided for, surfaces within 50 of any field weld location shall be free of materials that would prevent proper welding or produce objectionable fumes while welding is being done.

3.16.00 Galvanizing

3.16.01 General

Structural steelwork for switchyard or other structures as may be specified in the contract shall be hot dip galvanized in accordance with the American Society for Testing and Materials Specification ASTM-A 123 or IS: 2629 - Recommended practice for Hot-Dip Galvanizing of Iron and steel. Where the steel structures are required to be galvanized the field connection materials like bolts, nuts and washers shall also be galvanized.

3.16.02 Surface Preparation

All members to be galvanized shall be cleaned, by the process of pickling of rust, loose scale, oil, grease, slag and spatter of welded areas and other foreign substances prior to galvanizing. Pickling shall be carried out by immersing the steel in an acid bath containing either sulphuric or hydrochloric acid at a suitable concentration and temperature. The concentration of the acid and the temperature of the bath can be varied, provided that the pickling time is adjusted accordingly.

The pickling process shall be completed by thoroughly rinsing with water, which should preferably be warm, so as to remove the residual acid.

3.16.03 Procedure

Galvanizing shall be carried out by hot dip process in a proper and uniformly heated bath. It shall meet all the requirements when tested in accordance with IS: 2633 - Method for testing uniformity of coating on Zinc Coated Articles and IS: 4759 - Specification for Hot-dip zinc coatings on Structural Steel & other allied products.

After finishing the threads of bolts, galvanizing shall be applied over the entire surface uniformly. The threads of bolts shall not be machined after galvanizing and shall not be clogged with zinc. The threads of nuts may be tapped after galvanizing but care shall be taken to use oil in the threads of nuts during erection.

The surface preparation for galvanizing and the process of galvanizing itself, shall not adversely affect the mechanical properties of the materials to be galvanized. Where members are of such lengths as to prevent complete dipping in one operation, great care shall be taken to prevent warping.

Materials on which galvanizing has been damaged shall be acid stripped and re-galvanized unless otherwise directed, but if any member becomes damaged after leaving been dipped twice, it shall be rejected. Special care shall be taken

not to injure the skin on galvanized surfaces during transport, handling, and erection. Damages, if occur, shall be made good in accordance or as directed by the Engineer.

4.00.00 INSPECTION, TESTING, ACCEPTANCE CRITERIA AND DELIVERY

4.01.00 Inspection

Unless specified otherwise, inspection to all, work shall be made by the or Engineer's representative at the place of manufacture prior to delivery. The Engineer or his representative shall have free access at all reasonable times to those parts of the manufacturer's works which are concerned with the fabrication of the steelwork under this Contract and he shall be afforded all reasonable facilities for satisfying himself that the fabrication is being done in accordance with the provisions of this Specification.

The Contractor shall provide free of charge, such labour, materials, electricity, fuel, water, stores, tools and plant, apparatus and instruments as may be required by the Engineer to carry out inspection and/or tests in accordance with the Contract. The Contractor shall guarantee compliance with the provisions of this Specification.

4.02.00 Testing and Acceptance Criteria

4.02.01 General

The Contractor shall carry out sampling and testing in accordance with the relevant Indian Standards and as supplemented herein for the following items at his own Cost. The Contractor shall get the specimens tested in a laboratory approved by the Engineer and submit to the Engineer the test results in triplicate within 3 (three) days after completion of the test.

4.02.02 Steel

All steel supplied by, the Contractor shall conform, to the relevant Indian Standards. Except otherwise mentioned in the contract, only tested quality steel having mill test reports shall be used. In case unidentified steel materials are permitted to be used by the Engineer, random samples of materials will be taken from each unidentified lot of 50 M.T or less of any particular section for tests to conform to relevant Indian Standards. Cost of all tests shall be born by the contractor.

All material shall be free from all imperfections, mill scales, slag intrusions, laminations, fittings, rusts etc. that may impair their strength, durability, and appearance.

4.02.02 Welding

a) The weld surface shall be cleaned with steel wire brush to remove spatter metal, slag etc. and 100% of welds shall be inspected visually for size, length of weldment and external defects. Weld gauges shall be used for checking weld sizes. The surface shall be clean with regular beads and free from slags, cracks, blow-holes etc.

b) Non-destructive examination shall be carried out to determine soundness of weldments as follows:

i) 10% at random on fillet-joints.

ii) 100% on all butt-joints.

c) Should the ND tests indicate defects like improper root penetration, extensive blowholes, slag intrusion etc., such welds shall be back gauged, joints prepared again and rewelded. All defects shall be rectified by the Contractor at no extra costs.

d) All electrodes shall be procured from approved reputed manufacturers with test certificates. The correct grade and size of electrode, which has not deteriorated in storage, shall be used. The inspection and testing of welding shall be performed in accordance with the provisions of the relevant Indian Standards or other equivalents. For every 50 tones of welded fabrication, the Engineer may ask for 1(one) test-destructive or non-destructive including X -ray, ultrasonic test or similar, the cost of which shall be borne by the Contractor.

4.02.04 Rivets, bolts, nuts and washers

All rivets, bolts, nuts, and washers shall be procured from M/s. Guest Keen William Ltd. or equivalent and shall confirm to the relevant Indian Standards. If desired by the Engineer, representative samples of these materials may have to be tested in an approved laboratory and in accordance with the procedures described in relevant Indian Standards. Cost of all such testing shall have to be borne by the Contractor. In addition to testing the rivets by hammer, 2% (two per cent) of the rivets done shall have to be cut off by chisels to ascertain the fit, quality of material and workmanship. The removal of the cut rivets and re-installing new rivets shall be done by the Contractor at his own cost.

4.02.05 Shop painting

All paints and primers shall be of standard quality and procured from approved manufacturers and shall conform to the provisions of the relevant Indian Standards.

4.02. 12 Galvanizing

All galvanizing shall be uniform and of standard quality when tested in accordance with IS: 2633 - Method for testing uniformity of coating on Zinc Coated Articles and 15: 4759 - specification for Hot-Dip Zinc Coatings on Structural Steel & other allied products.

4.03.00 Tolerance

The tolerances on the dimensions of individual rolled steel components shall be as specified in IS: 1852 - specification for rolling and Cutting Tolerances for Hot-rolled Steel Products. The tolerances on straightness, length etc. of various fabricated components (such as beams and girders, columns, crane gantry girder etc.) of the steel structures shall be as specified in IS: 721 - Tolerances for Fabrication of Steel Structures.

4.04.00 Acceptance

Should any structure or part of a structure be found not to comply with any of the provisions of this specification, the same shall be liable to rejection. No Structure or part of the structure once rejected, shall be offered again for test, except in cases where the Engineer considers the defects rectifiable. The Engineer may, at his discretion, check some of the tests at an appropriate laboratory at the contractors cost.

When all tests to be performed in the Contractor's shop under the terms of this contract have been successfully carried out, the steelwork will be accepted forthwith and the Engineer will issue acceptance certificate, upon receipt of which, the items will be shop painted, packed and dispatched. No item to be delivered unless an acceptance certificate for the same has been issued. The satisfactory completion of these tests or the issue of the certificates shall not bind the Owner to accept the work, should it, on further tests before or after erection, be found not in compliance with the Contract.

4.05.00 Delivery of materials

4.05.01 General

The Contractor will deliver the fabricated structural steel materials to site with all necessary field connection materials in such sequence as will permit the most efficient and economical performance of the erection work. The Owner may prescribe or control the sequence of delivery of materials, at his own discretion.

4.05.02 Marking

Each separate piece of fabricated steelwork shall be distinctly marked on all surfaces before delivery in accordance with the markings shown on approved erection drawings and shall bear such other marks as will further facilitate identification and erection.

4.05.03 Shipping

Shipping shall be strictly in accordance with the sequence stipulated in the agreed Programme. Contractor shall dispatch the materials to the e worksite securely protecting and packing the materials to avoid loss or damage during transport by rail, road or water. All parts shall be adequately braced to prevent damage in transit.

Each bundle, bale or package delivered under this contract shall be marked on as many sides as possible and such distinct marking (all previous irrelevant markings being carefully obliterated) shall show the following:

a) Name and address of the consignee

b) Name and address of the consignor

c) Gross weight of the package in tonnes and its dimensions

d) Identification marks and/or number of the package

e) Custom registration number, if required

All markings shall be carried out with such materials as would ensure quick drying and indelibility.

Each component or part or piece of material when shipped, shall be indelibly marked and/or tagged with reference to assembly drawings and corresponding piece numbers.

Each packing case shall contain in duplicate in English a packing list pasted on to the inside of the cover in a water-proof envelope, quoting especially -

a) Name of the Contractor

b) Number and date of the Contract

c) Name of the office placing the contract

d) Nomenclature of stores

e) A schedule of parts or pieces, giving the parts or piece number with reference to assembly drawings and the quantity of each.

The shipping dimensions of each packing shall not exceed the maximum dimensions permissible for transport over the Indian Railways/Roads.

After delivery of the materials at site, all packing materials shall automatically become the property of the Owner.

Notwithstanding anything stated hereinbefore, any loss or damage resulting from inadequate packing shall be made good by the Contractor at no additional cost to the Owner. When facilities exist, all shipments shall be covered by approved Insurance Policy for transit at the cost of the Contractor.

The contractor shall ship the complete materials or part on board a vessel belonging to an agency approved by the Owner or on rail and/or road transport as directed. The Contractor shall take all reasonable steps to ensure correct appraisal of freight rates, weights and volumes and in no case will the Owner be liable to pay any warehouse, wharfage, demurrage and other charges.

If, however, the Owner has to make payment of any of the above-mentioned charges, the amount paid will be deducted from the bills of the Contractor.

Necessary advice regarding the shipment with relevant details shall reach the Engineer at least a week in advance.

5.00.00 INFORMATION TO BE SUBMITTED

5.01.00 With Tender

The following information is required to be submitted with the Tender:

a) Progress Schedule

The Contractor shall quote in his Tender a detailed schedule of progress of work and total time of completion, itemizing the time required for each of the following aspects of work.

i) Preparation and approval of fabrication drawing

ii) Procurement of Materials

iii) Fabrication and shipping of all anchor bolts

iv) Fabrication and shipping of main steelwork.

v) Fabrication and shipping of steelwork for bunkers, tanks and/or silos as applicable.

vi) Fabrication and shipping of all other remaining steelwork including miscellaneous steelwork.

vii) Final date of completion of all shipments.

b) Shop

Location of the Tenderer's fabrication workshop giving details of equipment, manpower, the total capacity, and the capacity that will be available exclusively for this contract shall be submitted.

5.02.00 After Award

After award of the Contract the successful Tenderer is to submit the following:

a) Complete fabrication drawings, material lists, cutting lists, rive and bolt lists, field welding schedules based on the approved design drawings prepared by him in accordance with the approved schedule.

b) Monthly Progress Report with necessary photographs in six (6) copies to reach the Engineer on or before the 7th day o. each month, giving the up-to-date status of preparation of detailed shop drawings, bill of materials, procurement of materials, actual fabrication done, shipping and all other relevant information.

c) Detailed monthly material reconciliation statements relevant to the Work done and reported in the Progress Report, giving the stock at hand of raw steel, work in progress, finished materials.

d) Results of any test as and when conducted and as require by the engineer.

e) Manufacturer’s mill test report in respect of steel materials, rivets, bolts, nuts, and electrodes as may be applicable.

6.00.00 RATES AND MEASUREMENT

6.01.00 Rates

6.01.01 The items of work in the Schedule of items describe the work in brief. The various items of the Schedule of items shall be read in conjunction with these specifications including amendments and additions, general conditions of contract, special conditions of contracts, and other tender documents, if any. For each item of Schedule of Items, the bidder's rates shall include the activities covered in the description of the item as well as all necessary operations described in the Specifications.

6.01.02 The bidder's rates shall include cost of all minor details which are obviously and fairly intended and which may not have been included in the description in these documents but are essential for the satisfactory completion of the work. Rates shall also include for taking all safety measures.

6.01.03 The bidder's -rates for all items of schedule of items shall include complete cost towards plant, equipment, erection and dismantling of scaffolding, men, materials and consumables, skilled and unskilled labour, levies, taxes, royalties, duties, transport, storage, repair/rectification/maintenance until handing over, contingencies, overhead and all incidental items not specifically mentioned but reasonably implied and necessary to complete the work.

6.01.04 No claims shall be entertained, if the details shown on the `Released for Construction' drawings differ from those shown on the bid/tender drawings.

6.01.05 Rates shall be inclusive of all leads and lifts/elevation.

6.01.06 The bidder's rates for Structural Steel shall include for fabrication and erection, transportation to site, preparation checking collecting and distributing of the fabrication drawings and design calculations, erection scheme, alignment, welding, including preheating and post heating, testing of welders, inspection of welds, visual inspection, non destructive and special testing, rectification and correction of defective welding works, production test plate, inspection and testing, erection scheme, protection against damage in transit, stability of structures, etc. The rates shall also be inclusive of providing and installing temporary structures, transport of Owner issue material from store, return of surplus/waste steel materials including cut pieces'/waste steel, provision of additional butt/weld joint to reduce the wastage and all other general, special, such requirements as may be required, for the successful completion of the work.

The rates for fabrication are inclusive of all tests on welds and material and no extra shall be payable for quality tests specified for fabrication of structure in shop or at site.

Separate BOQ items for test on welds like radiography or Ultrasonic, DPT, magnetic particle tests are kept for tests on material/fabrication not covered under regular fabrication item of BOQ.

6.01.07 The bidder's rates for foundation bolts assembly shall include fabrication, threading, heat treatment, erection, installation, and alignment of complete bolt assembly with nuts, locknuts, anchor plates, stiffener plates, protective tape, etc. This shall also include the cost of all materials not issued by the Owner. Material issued by Owner will be specified in GCC.

6.01.08 The bidder’s rates for application of inorganic primer shall include surface preparation to near white metal surface by blast cleaning, abrasives, touch up painting, suitable enclosure to avoid contamination and the necessary statutory approval from the factory inspector/pollution control board etc. regarding the method of blast cleaning and abrasives used, and getting approval of the specialized agency supplying the primer specified.

6.01.09 The bidder's rates for application of finish painting system shall include surface preparation, application of intermediate (under) coat, finish coat and final finish coat, and getting approval of the specialized agency supplying the finish paint.

6.01.10 The bidder's rates for electro-forged gratings (if specified) shall include supply, fabrication, transportation to the site, erection and alignment of factory made electro-forged gratings, all taxes, duties thereon etc. The rates shall also include preparation of grating design for different spans and load intensifies, preparation of design and fabrication drawings, edge preparation, blast cleaning followed by finish paint.

6.01.11 The bidder's rates for galvanization of factory made electro-forged gratings (if specified) shall include the application of hot dipped galvanization as finish over the fabricated gratings and the treatment to be given for prevention of white storage stains, as per the technical Aspiration.

6.01.12 The bidder’s rates for permanent mild steel bolts, nuts and washers shall include the supply and fixing of such bolts, nuts and washers in position, for various types of Structural Steel works, as per the technical specification.

6.01.13 The bidder’s rates for high strength structural bolts, nuts and washers shall include the supply and fixing of such bolts, nuts and washers in position, for various types, of Structural Steel works, as per the technical specification.

6.01.14 The bidder's rates for dismantling, additions to, alterations in and/or modifications shall be inclusive of all operations such as lowering of material, carriage etc., as mentioned in the technical specification. Unutilised steel pieces cut/removed shall be returned to the project stores free of charge. Non-return of unublized steel pieces to the Owner's store would be considered as wastage and recovery would be affected as per the provision of contract for structural steel consumption. This shall not include the weight of temporarily dismantled/supported members, connected member.

The bidder should prepare an optimised cutting plan as per fabrication drawing to utilise the steel material upto maximum extent and minimise the wastage/scrap. Quantity of wastage/scrap of material should be limited to the percentage mentioned elsewhere in the conditions of tender/ contract specifications.

6.01.15 The bidder's rates for re-erection of erection marks after additions to, alterations in and/or modifications shall be inclusive of all operations mentioned in technical specification for the calculated weight of the rectified/modified erection mark rejected at site. This shall not include the weight of temporarily dismantled/supported members, connected member. All the operations mentioned above for restoring such members shall be carried out at no extra cost. The work of erection of any erection mark which has not been dismantled but have been modified/rectified before erection shall not be paid under this item but shall be paid under relevant item of fabrication and erection of steel work of Schedule of items for the modified weight.

6.01.16 The bidder's rates for PTFE shall include design, supply, transportation of the complete assembly with guides and dust protection cover and installation of bearings in position drilling, bolting, erecting aligning etc. along with any taxes, duties thereon etc.

6.01.17 The bidder's rates for Stainless Steel hopper (if specified) shall include fabrication and erection, transportation to site, preparation checking collecting and distributing of the fabrication drawings and design calculations, all other operations mentioned in the technical specification. The rates shall also include for erection scheme, alignment, making cutting plan, cutting, jointing, bending, rolling, grinding, drilling, bolting, assembly, edge preparation, welding including pre-heating, post-heating, testing of welders, inspection of welds, inspection and testing, protection against damage in transit, stability of structures, installation of temporary structures etc. The rates shall also be inclusive of providing and installing temporary structures, transport of Owner issue material from store, return of surplus / waste steel materials including cut pieces'/waste steel, provision of additional butt / weld joint to reduce the wastage and all other general, special, such requirements as may be required, for the successful completion of the work.

6.01.18 The bidder's rates for preformed flexible open ended bellow strap of neoprene (if specified) shall include supply and transportation, installation in position, drilling, bolting, aligning etc. complete along with any taxes, duties thereon etc.

6.01.19 The bidder's rates for Stainless Steel Hand Rail (if specified) shall include complete Hand Rail including, materials, fabrication, grinding & finishing, stainless steel beading, stainless steel cleats, stainless steel fasteners, neoprene gaskets, preparation of shop drawing but excluding the cost of glazing. The Owner shall supply no material for this item of work.

6.02.00 MODE OF MEASUREMENT

6.02.01 The measurement for the item of foundation bolts assembly including that of nuts; locknuts shall be based on the calculated weight of steel installed in Metric Tonne, corrected to second place of decimal. The weight of the foundation bolt shall be calculated in the same way as that done for the item of fabrication, erection, alignment of structural steel. The weight of the nut / locknut shall be taken as per actual weight supplied by the contractor and accepted by the Engineer.

6.02.02 The measurement for the item of fabrication, erection, alignment, welding, etc. of structural steel work shall be based on the approved weight of steel nearest to a Kg, by applying the unit weight as adopted at the time of issue of structural steel on the measurements worked out as given below.

6.02.03 For ISMB, ISMC, ISA, flats, round bars, square bars and pipes, length shall be taken as per distance between planes normal to the axis of the member passing through the extreme points of the section.

6.02.04 Gussets plates in trusses, and bracings, brackets plates, stiffeners, and skew cuts if any in plates for butt welds, the area shall be assumed as the minimum circumscribed rectangle. However, deduction for any notch/skew cut shall be made as mentioned in clause no-6.02.06.

6.02.05 For bunker wall plates, the minimum-circumscribing rectangle of the individual plate/pieces out of which these wall plates are assembled by butt-welding, shall be measured. Care shall be taken to ensure maximum utilization of cut-pieces generated by providing extra butt joints (for which no extra payment shall be made).

6.02.06 For all other plates, where the area of any notch/skew cut in the plate is less than 0.05 sq.m. the area of the plate shall be assumed as that of the minimum circumscribing rectangle for the purpose of measurement and calculation of area for the purpose of payment. However, if the area of any notch/skew cuts in a plate is more than 0.05 sq.m, the area of notch/skew cut shall be deducted

from assumed minimum circumscribing rectangular area for the purpose of payment.

6.02.07 No deduction shall be made for the hole in the members, if the area of individual hole is less than 0.05 sq.m. The weight shall be calculated by deducting the area of holes, if area of individual hole is more than 0.05 sq.m.

6.02.08 All cut-pieces and scrap generated due to cutting of holes, skew-cuts of plates, gussets, brackets, stiffeners, etc. shall be stacked separately and handed over to the project stores without being considered for material accounting as the circumscribing rectangle has been considered for payment.

6.02.09 The splice plate shown in the fabrication drawing or approved by the Engineer shall only be measured for payment.

6.02.10 The weight of permanent bolts, washers and nuts and welds shall not be included in the weights of the members. No extra payment shall be made for welding/bolting.

6.02.11 The bolts and nuts required for erection purpose shall not be paid for and may be taken away by the Contractor after final welding for members. Erection boltholes left after removal of erection bolts shall be suitably plugged with welds.

6.02.12 The measurement for the item of application of inorganic primer including blast cleaning of steel surfaces shall be based on the weight on which the zinc silicate primer is applied, after blast cleaning in Metric Tonne, corrected to third place of decimal. The weight shall be the weight as approved, for erection mark/element of the mark painted, for payment of the item of fabrication and erection of structural steel works.

6.02.13 The measurement for the item of application of finish primer system shall be based on the weight on which the epoxy based finish primer is applied in Metric Tonne, corrected to third place of decimal. The weight shall be the weight as approved, for erection mark/element of the mark painted, for payment of the item of fabrication and erection of structural steel works.

6.02.14 The measurement for the item of gratings shall be based on the actual weight in Kgs, corrected to second place of decimal, as supplied by the Contractor, and accepted by the Engineer. Nothing extra shall be payable for making cutouts, notches, openings of any profile, trimming profiles etc. in the grating units.

6.02.15 The measurement for the item of hot dipped galvanization of gratings shall be based on the actual weight in Kgs, corrected to second place of decimal of gratings galvanized by the Contractor and accepted by the Engineer.

6.02.16 The measurement for the item of permanent bolts with nuts and washers shall be based on the actual weight in Kgs, corrected to second place of decimal, as supplied by the Contractor and accepted by the Engineer, and as per the approved bolts and nuts schedules.

6.02.17 The measurement for the item of High Strength Structural bolts with nuts and washers shall be based on the actual weight in Kgs, corrected to second place of decimal, as supplied by the Contractor and accepted by the Engineer, and as per the approved bolts and nuts schedules.

6.02.18 The measurement for the item of the work of dismantling, additions, alterations, reerection etc. shall be as given below

6.02.19 For dismantling, the unmodified weight of the actually dismantled erection marks shall only be measured.

6.02.20 For the work of addition to, alteration in and / or modification of 'erection marks' either in erected position or in the fabrication yard, measurement of weight for payment purpose shall be calculated as the arithmetic sum of weight of steel cut and removed from the erection mark, weight of steel reutilised out of such cut and removed pieces and weight of additional new steel pieces added to the erection mark.

6.02.21 For re-erection the weight of the modified erection mark shall only be measured.

6.02.22 The weight shall be measured nearest to kg. and shall be arrived in a manner similar to the measurement for the item of fabrication, erection, alignment and welding of structural steel.

6.02.23 The measurement for the item of PTFE bearings shall be based on the load carrying capacity of PTFE in MT, corrected to third place of decimal, supplied by the contractor and as accepted by the Engineer and as per the approved bearing schedule, for the total vertical load carrying capacity, for all bearings.

6.02.24 The measurement for the item of stainless steel hopper shall be based on the actual finished weight of hopper weight in Kgs, corrected to second place of decimal. The hopper weight shall be arrived by multiplying of the inner surface area of the hopper with the unit weight of the hopper plate.

6.02.25 The measurement for the item of flexible open-ended bellows straps of neoprene shall be based in running meter, corrected to second place of decimal. Bellow Straps shall be supplied as per the requirement of the approved drawings. The measurement shall be done for the inner circumference of the bunker on which neoprene has been fixed and for the length supplied by the Contractor 'and as accepted by the Engineer.

6.02.26 The measurement for the item of Stainless Steel Hand Railing shall be based on finished weight of handrail in Kgs corrected to second place of decimal. The weight shall also include the weight of Stainless Steel fasteners, Stainless Steel beading, Stainless Steel cleats etc. The weight shall be the finished weight of Hand Rail, as accepted by the Engineer.

VOLUME: II B

SECTION - D
(PART I)

SUB-SECTION – D 18

ERECTION OF STRUCTURAL STEELWORK

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	GENERAL	3
3.00.00	WORKMANSHIP	6
4.00.00	TESTING AND ACCEPTANCE CRITERIA	12
5.00.00	INFORMATION TO BE SUBMITTED	16

SUB-SECTION – D 18

ERECTION OF STRUCTURAL STEELWORK

1.00.00 SCOPE

This specification covers the erection of structural steelwork including receiving and taking delivery of fabricated structural steel materials arriving at site, installing the same in position, painting and grouting the stanchion bases all complete as per Drawings, this Specification and other provision of the Contract.

2.00.00 GENERAL

2.01.00 Work to be provided for by the Contractor, unless otherwise specified in the Contract, shall include but not be limited to the following:

a) The Contractor shall provide all construction and transport equipment, tools, tackle, consumables, materials, labour, and supervision required for erection of the structural steelwork.

b) Receiving, unloading, checking, and moving to storage yard at Site including prompt attendance to all insurance matters as necessary for all fabricated steel materials arriving at Site. The Contractor shall pay all demurrage and/or wharfage charges etc. on account of default on his part.

c) Transportation of all fabricated structural steel materials from Site storage yard, handling, rigging, assembling, riveting, bolting, welding and satisfactory installation of all fabricated structural steel materials in proper location according to approved erection drawings and/or as directed by the Engineer. If necessary suitable temporary approach roads to be built for transportation of fabricated steel structures.

d) Checking centre lines, levels of all foundation blocks including checking line, level, position and plumb of all bolts and pockets. Any defect observed in the foundation shall be rectified with Engineer's approval. The Contractor shall fully satisfy himself regarding the correctness of the foundations before installing the fabricated steel structures on the foundation blocks.

e) Aligning, plumbing, levelling, riveting, bolting, welding and securely fixing the fabricated steel structures including floor gratings, chequered plates etc. in accordance with the Drawings or as directed by the Engineer.

f) Painting of the erected steel structures.

g) All minor modifications of the fabricated steel structures as directed by the Engineer including but not limited to the following:

i) Removal of bends, kinks, twists etc. for parts damaged during transport and handling.

ii) Cutting, chipping, filling, grinding, etc. if required for preparation and finishing of site connections.

iii) Reaming of holes for use of higher size rivet or bolt if required.

iv) Refabrication of parts damaged beyond repair during transport and handling or refabrication of parts, which are incorrectly fabricated.

v) Fabrication of parts omitted during fabrication by error, or subsequently found necessary.

vi) Drilling of holes which are either not drilled at all or are drilled in incorrect location during fabrication.

vii) Carry out tests in accordance with this specification.

2.02.00 Work by Others

No work under this Specification will be provided for by any agency other than the Contractor unless specifically mentioned elsewhere in the contract.

2.03.00 Codes and Standards

All work under this Specification shall, unless specified otherwise, conform to the latest revisions and/or replacements of the following or any other Indian Standard Specification and codes of Practice of equivalent:

IS: 800 - Code of practice for general construction in steel.

IS: 456 - Code of practice for main or reinforced concrete.

2.04.00 Conformity with Designs

The Contractor will erect the entire fabricated steel structure, align all the members, complete all field connections and grout the foundations all as per the provisions of this specification and the sequence and the design criteria laid down by the Engineer. All work shall conform to the provisions of this specification and /or instructions of the engineer. The testing and acceptance of the erected structures shall be in accordance with the provisions of this Specifications and/or the instructions o the Engineer.

2.05.00 Material

2.05.01 General

All fabricated steel structures and connection materials shall be supplied by the Contractor to the site. The Contractor shall take delivery from railway wagons or trucks at site, and unload the materials and perform all formalities like checking of materials and attend to insurance matters in accordance with Sub-Clause 2.01.00 and as specified hereinbefore.

2.05.02 Materials to conform to Indian standards

All materials required to be supplied by the Contractor under this contract shall conform to the relevant Indian Standard specifications.

2.06.00 Storage of Materials

2.06.01 General

All material shall be so stored as to prevent deterioration and to ensure the preservation of their quality and fitness for use in the works. Any material which has been deteriorated or damaged beyond repairs and has become unfit for use shall be removed immediately from the site, failing which, the engineer shall be at liberty to get the materials removed by agency and the cost incurred thereof shall be realised from the Contractor's dues.

2.06.02 Yard

The Contractor will have to establish a suitable yard in an approved location at site for storing the fabricated steel structures and other raw steel materials such as structural sections and plates as required. The yard shall have facilities like drainage, lighting, and suitable access for large cranes, trailers, and other heavy equipments. The yard shall be fenced all around with security arrangement and shall be of sufficiently large area to permit systematic storage of the fabricated steel structures without overcrowding and with suitable access for cranes, trailers and other equipment for use in erection work in proper sequence in accordance with the approved Programme of work.

The Tenderer must visit the site prior to submission of his tender to acquaint himself with the availability of land and the development necessary by way of filling, drainage, access roads, fences, sheds etc. all of which shall be carried out by the Contractor at his own cost as directed by the Engineer.

2.06.03 Covered Store

All field connection materials, paints, cement etc. shall be stored on well designed racks and platforms off the ground in a properly covered store building to be built at the cost of the Contractor.

2.07.00 Quality Control

The contractor shall establish and maintain quality control procedures for different items of work and materials as may be directed by the Engineer to assure compliance with the provisions of the Contract and shall submit the records of the same to the Engineer. The quality control operation shall include but not be limited to the Following items of work:

i) Erection: Lines, levels, grades, plumbs, joint characteristics including tightness of bolts.

ii) Grouting: Cleaning and roughness of foundation, quality of materials used for grouting, admixtures, consistency, and strength of grout.

iii) Painting: Preparation of surface for painting, quality of primers and paints, thinners, application and uniformity of coats.

2.08.00 Taking Delivery

The Contractor shall take delivery of fabricated structural steel and necessary connection materials from railhead/trucks as may be necessary and as directed by the Engineer. He shall check, unload; transport the materials to his stores for proper storing at his own cost. The Contractor shall submit claims to insurance or other authorities and pursue the same in case of loss or damage during transit and handling and all loss thereof shall be borne by him.

The Contractor shall also take all precautions against damage of the materials in his custody after taking delivery and till the same are erected in place and accepted. The Contractor shall salvage, collect, and deliver all the packing materials to the Owner free of charge.

3.00.00 WORKMANSHIP

3.01.00 Erection

3.01.01 Plant and Equipment

The suitability and adequacy of all erection tools and plant and equipment proposed to be used shall be thoroughly verified. They shall be efficient, dependable, in good working condition and shall have the approval of the Engineer.

3.01.02 Method and sequence of erection

The method and sequence of erection shall have the prior approval of the Engineer. The Contractor shall arrange for most economical method and sequence available to him consistent with the drawings and specifications and other relevant stipulations of the contract.

3.01.03 Temporary Bracing

Unless adequate bracing is included as a part of the permanent framing, the erector during erecrtion shall install, free of cost to the Owne, temporary guys and bracings where needed to secure the framing against loads such as wind or seismic forces comparable in intensity to that for which the structure has been designed, acting upon exposed framing as well as loads due to erection equipment and erection operations.

If additional temporary guys are required to resist wind or seismic forces acting upon components of the finished structure installed by others during the course of the erection of the steel framing, arrangement for their installation by the erector shall be made free of cost to the Owner.

The requirement of temporary bracings and guys shall cease when the structural steel is once located, plumbed, levelled, aligned, and grouted within the tolerances permitted under the specification and guyed and braced to the satisfaction of the Engineer.

The temporary guys, braces, false work, and cribbing shall not be the property of the Owner and they may be removed immediately upon completion of the steel erection.

3.01.04 Temporary Floors for Buildings

It shall be the responsibility of the Contractor to provide free of cost planking and to cover such floors during the work in progress as may be required by any Act of Parliament and/or bylaws of state, Municipal or other local authorities.

3.01.05 Setting Out

Positioning and levelling of all steelwork, plumbing of stanchions and placing of every part of the structure with accuracy shall be in accordance with the approved Drawings and to the satisfaction of the Engineer. For heavy columns, etc. the Contractor shall set proper screed bars to maintain proper level. No extra payment shall be made for this.

Each tier of column shall be plumbed and maintained in a true vertical position subject to the limits of tolerance under this Specification.
No permanent field connections by riveting, bolting or shall be carried out until proper alignment and plumbing has been attained.

3.01.06 Field Riveting

All rivets shall be heated and driven with pneumatic tools. Hand passing or "throwing" of rivets are desirable. Any other method of conveying hot rivets from the furnace to the driving point must be approved by the engineer. No-cold rivets shall be driven. All other requirements of riveting including quality and acceptance criteria shall be in accordance with the relevant portions of the Specification for Fabrication of Structural Steelwork of the Project.

3.01.07 Field Bolting

All relevant Portions in respect of bolted construction of the Specification for Fabrication of Structural Steelwork applicable to the Project shall also be applicable for field bolting in addition to the following:

Bolts shall be inserted in such a way so that they may remain in position under gravity even before fixing the nut. Bolted parts shall fit solidly together when assembled and shall not be separated by gaskets or any other interposed compressible materials. When assembled, all joint surfaces, including those adjacent to the washers shall be free of scales except tight mill scales. They shall be free of dirt, loose scales, burns, and other, defects that would prevent solid seating of the parts. Contact surfaces within friction type joints shall be free of oil, paint, lacquer, or galvanizing.

All high tensile bolts shall be tightened to provide, when all fasteners in the joint are tight, the required minimum bolt tension by any of the following methods.

a) Turn-of-nut Method

When the turn-of-nut method is used to provide the bolt tension, there shall first be enough bolts brought to a "snug tight" condition to ensure that the parts of the Joint are brought into good contact with each other. 'Snug tight" is defined as the tightness attained by a few impacts of an impact wrench or the full effort of a man using an ordinary spud wrench. Following this initial operation, bolts shall be placed in any remaining holes in the connection and brought to snug tightness. All bolts in the joint shall then be tightened additionally by the applicable amount of nut rotation specified in Table-I with tightening progressing systematically from the most rigid part of the joint to its free edges. During this operation

there shall be no rotation of the part not turned by the wrench.

TABLE-I

Bolts length not exceeding 8 times Dia or 200 mm	Bolt length exceeding 8 times Dia or 200 mm	Remarks
1/2 turn	2/3 turn	Nut rotation is relative to bolt regardless of the element (nut or bolt) being turned. Tolerance on rotation-30° over or under.

Bolts may be installed without hardened washers when tightening is done by the turn -of-nut -method. However, normal washers shall be used.

Bolts tightened by the turn-of-nut method may have the outer face of the match-marked with the protruding bolt point before final tightening, thus affording the inspector visual means of noting the actual nut rotation. Such marks can be made by the wrench operator by suitable means after the bolts have been brought up snug tight.

b) Torque Wrench Tightening

When torque wrenches are used to provide the bolt tensions, the bolts shall be tightened to the torques specified in TABLE-II (See Note below the Table). Nuts shall be in tightening motion when torque is measured. When using torque wrenches to install several bolts in a single joint, the wrench shall be returned to touch up bolts previously tightened, which may have been loosened by the tightening of subsequent bolts, until all are tightened to the required tension.

TABLE-II

Nominal Bolt Diameter (mm) (Kg.M) of IS:1367	Torque to be applied for bolt class 8.8
20	59.94
22	81.63
24	103.73

Note: The above torque values are approximate for providing tensions of 14. 7 T for 20 mm dia.; and 21.2 T for 24 mm dia. bolts under moderately lubricated condition. The torque wrench shall be calibrated at least once daily to find out the actual torque required to produce the above required tension in the bolt by placing it in a tension indicating device. These torques shall be applied for tightening the bolts on that day with the particular wrench.

In either of the above two methods, if required, for bolt entering and wrench operation clearances, tightening may be done by turning the bolt while the nut is prevented from rotating.

Impact wrenches if used shall be of adequate capacity and sufficiently supplied with air to perform the required tightening of each bolt in approximately ten seconds. Holes for turned bolts to be inserted in the field shall be reamed in the field. All drilling and reaming for turned bolts shall be done only after the parts to be connected are assembled. Tolerances applicable in the fit of the bolts shall be in accordance with relevant Indian Standard Specifications. All other requirements regarding assembly and bolt tightening shall be in accordance with this sub clause.

3.01.08 Field Welding

All field assembly and welding shall be carried out in accordance with the requirements of the specification for fabrication work applicable to the project, excepting such provisions therein which manifestly apply to shop conditions only. Where the fabricated structural steel members have been delivered painted, the paint shall be removed before field welding for a distance of at least 50 mm on either side of the joints.

3.01.09 Holes, Cutting and Fitting

No cutting of sections, flanges, webs, cleats, rivets, bolts, welds etc. shall be done unless specifically approved and /or instructed by the Engineer.

The erector shall not cut, drill, or otherwise alter the work of other trades, unless such work is clearly specified in the Contract or directed by the Engineer. Wherever such work is obtain specified the Contractor shall obtain complete information as to size, location and number of alterations prior to carrying out any work. The Contractor shall not be entitled for any payment on account of any such work.

3.02.00 Drifting

Correction of minor misfits and reasonable amount of reaming and cutting of excess stock from rivets will be considered as permissible. For this, light drifting may be used to draw holes together and drills shall be used to enlarge

holes as necessary to make connections. Reaming, that weakens the member or makes it impossible to fill the holes properly or to adjust accurately after reaming, shall not be allowed.

Any error in shop work which prevents the proper assembling and fitting of parts by moderate use of drift pins and reamers shall immediately be called to the attention of the Engineer and approval of the method of correction obtained. The use of gas cutting torches at erection site is prohibited.

3.03.00 Grouting of stanchion bases and bearings of beams and girders on stone, brick or concrete (Plain or reinforced)

Grouting shall be carried out with Ordinary Cement grout as described below:

The mix shall be one (1) part cement and one (1) part sand and just enough water to make it workable. The positions to be grouted shall be cleaned thoroughly with compressed air jet and wetted with water and any accumulated water shall be removed. These shall be placed under expert supervision, taking care to avoid air locks. Edges shall be finished properly. If the thickness of grout is 25 mm or more, two (2) parts of 6 mm down graded stone chips may be added to the above noted cement-sand grout mix, if required, by the Engineer or shown on the drawings.

No grouting shall be carried out until a sufficient number of bottom lengths of stanchions have been properly lined, leveled, and plumbed and sufficient floor beams are tied in position.

Whatever method of grouting is employed, the operation shall not be carried out until the steelwork has been finally levelled and plumbed, the stanchion bases being supported meanwhile by steel wedges, and immediately before grouting, the space under steel shall be thoroughly cleaned.

If required by the Engineer, certain admixtures like aluminium powder, “ironite” or equivalent, may be required to be added to the grout to enhance certain desirable properties of the grout. Approved non-shrink pre-mixed grout having required flowability and compressive strength may also be used with Engineer's approval.

3.04.00 Painting after Erection

Field painting shall only be done after the structure is erected, levelled, plumbed, aligned and grouted in its final position, tested and accepted by the Engineer. Normally, final painting shall be done only after the floor slabs are concreted and masonry walls are built. However, touch up painting, making good any damaged shop painting and completing any unfinished portion of the shop coat shall be carried out by the Contractor free of cost to the Owner. The materials and specification for such painting in the field shall be in accordance

with the requirements of the specification for fabrication of structural steelwork applicable for the project.

Painting shall not be done in frosty or foggy weather or when humidity is such as to cause condensation on the surfaces to be painted. Before painting of steel, which is delivered unpainted, is commenced, all surfaces to be painted shall be dried and thoroughly cleaned from all loose scale and rust.

All field rivets, bolts, welds, and abrasions to the shop coat shall be spot painted with the same paint used for the shop coat. Where specified, surfaces, which will be in contact after site assembling, shall receive a coat of paint (in addition to the shop coat, if any) and shall be brought together while the paint is still wet.

Surface, which will be inaccessible after field assembly shall receive the full, specified protective treatment before Bolts and fabricated steel members who are galvanized or otherwise treated and steel members to be encased shall not be painted.

The final painting shall be of tow coats of Synthetics Enamel painting or Aluminium paint of approved manufacture as per the approved "Schedule of Painting". The shades shall also be as per the approved schedule. Synthetic enamel paint shall conform to IS: 2932.

3.05.00 Final cleaning up

Upon completion of erection and before final acceptance of the work by the Engineer, the contractor shall remove free of cost all false work, rubbish and all Temporary Works resulting in connection with the performance of his work.

4.00.00 TESTING AND ACCEPTANCE CRITERIA

4.01.00 General

Loading tests shall be carried out on erected structures, if required by the Engineer, to check adequacy of fabrication and/or erection. Any structure or a part thereof found to be unsuitable for acceptance as a result of the test shall have to be dismantled and replaced with suitable member as per the Contract and no payment towards the cost of the dismantled portion and any connected work shall be made to the contractor. In course of dismantling, if any damage is done to any other parts of the structure or to any fixtures, the same shall be made good free of cost by the Contractor, to the satisfaction of the Engineer. The Cost of the tests specified hereinafter shall be borne by the Owner; but if the structure fails to pass the tests, the cost of the tests shall be recovered from the Contractor. Any extra claim due to loss of time, idle labour, etc. arising out of these testing operations shall not be entertained, however, only reasonable

and appropriate time extensions will be allowed.

The structure or structural member under consideration shall be loaded with its actual dead load for as long a time as possible before testing and the tests shall be conducted as indicated in the following sub-clauses 4.01.01, 4.01.02 and 4.01.03. The method of testing and application of loading shall be as approved by the Engineer.

4.01.01 Stiffness Test

In this test, the structure or member shall be subjected, addition to its actual dead load, to a test load equal to 1.5 times the specified superimposed load, and this loading shall be maintained for 24 hours. The maximum deflection attained during the test shall be within the permissible limit. If, after removal of the test load, the member or structure does not show a recovery of at least 80 per cent of the maximum strain or deflection shown during 24 hours under load, the test shall be repeated. The structure or member shall be considered to have sufficient stiffness, provided that the recovery after this second test is not less than 90 per cent of the maximum increase in strain or deflection recorded during the second test.

4.01.02 Strength Test

The structure or structural member under consideration shall be subjected, in addition to its actual dead load, to a test load equal to the sum of the dead load and twice the specified superimposed load, and this load shall be maintained for 24 hours.

In the case of wind load, a load corresponding to twice the specified wind load shall be applied and maintained for 24 hours, either with or without the vertical test load for more severe condition in the member under consideration or the structure as a whole. Complete tests under both conditions may be necessary to verify the strength of the structure. The structure shall be deemed to have adequate strength if, during the test, no part fails and if on the removal of the test load, the structure shows a recovery of at least 20 per cent of the maximum deflection or strain recorded during the 24 hours under load.

4.01.03 Structure of same design

Where several structures are built to the same design and it is considered unnecessary to test all of them, one structure, as a prototype, shall be fully tested, as described in previous Sub-clauses, but in addition, during the first application of the test load, particular note shall be taken of the strain or deflection when the test load 1.5 times the specified superimposed load has been maintained for 24 hours. This information is required as a basis of comparison in any check test carried out on samples of the structure.

When a structure of the same type is selected for a check test, it shall be subjected, in addition to its actual dead load, to a superimposed test load, equal to 1.5 time the specified live load, in a manner and to an extent prescribed by the Engineer. This load shall be maintained for 24 hours, during which time, the maximum deflection shall be recorded. The check test shall be considered satisfactory, provided that the maximum strain or deflection recorded in the check test does not exceed by more than 20% of the maximum strain or deflection recorded at similar load in the test on the prototype.

4.01.04 Repair for subsequent test and use after strength tests

An actual structure which has passed the "Strength Test" as specified in Sub-clause 4.1.2 hereinbefore and is subsequently to be erected for use, shall be considered satisfactory for use after it has been strengthened by replacing any distorted members and has subsequently satisfied the 'Stiffness Test' as specified in Sub-clause 4.01.01 hereinbefore.

4.02.00 Tolerances

Some variation is to be expected in the finished dimensions of structural steel frames. Unless otherwise specified, such variations are deemed to be within the limits of good practice when they are not in excess of the cumulative effect of detailed erection clearances, fabricating tolerances for the finished parts and the rolling tolerances for the profile dimensions permitted under the Specifications for fabrication of structural steel work applicable to this Project and as specified below: The specified tolerance is mainly for welded erection. In case of bolted erection, no tolerance is desired so that all prefabricated bolt holes are matched on erection.

I. For Buildings Containing Cranes

Component	Description	Variation Allowed
1.	2.	3.
Main columns	a) shifting of column axis at foundation level with respect to building line	
	i) In longitudinal direction	i) ± 3.0 mm
	ii) In lateral direction	ii) ± 3.0 mm
	b) Deviation of both major column axis from vertical between foundation and	

	other member connection levels:	
	i) For a column upto and including 10M height	i) ± 3.5 mm from true vertical
	ii) For a column greater than 10M but less than 40M height	ii) ± 3.5 mm from true vertical for any 10 M length measured between connection levels, but not more than ±7 mm per 30m length.
	c) For adjacent pairs of columns across the width of the building prior to placing of truss	± 9.0 mm on true span.
	d) For any individual column deviation of any bearing or resting level from levels shown on drawings.	± 3.0 mm
	e) For adjacent pairs of columns either across the width of building or longitudinally level difference allowed between bearing or seating	3.0 mm
Trusses	a) Deviation at centre of span of upper chord member from vertical plane running through centre of bottom chord.	1/1500 of the span or greater than 10mm whichever is the least.
Trusses	b) Lateral displacement of top chord at center of span from vertical plane running through center of supports.	1/250 of depth of truss or 20 mm which ever is the - least.
Crane Cirders	a) Difference in levels of crane rail measured between adjacent columns.	2.0 mm.
	b) Deviation to crane rail-gauge	± 3.0 mm

	c) Relative shifting of ends of adjacent crane rail in plan and elevation after thermite welding.	1.0 mm.
	d) Deviation of crane rail axis from centre line of web.	± 3.5 mm
Setting of Expansion gaps	At the time of setting of the expansion gaps, due regard shall be taken of the ambient temperature above or below 30°C. The coefficient of expansion or contraction shall be taken as 0.000012 per °C per unit length.	

iv) For Building without Cranes

The maximum tolerances for line and level of the steel work shall be ±3.0 mm on any part of the structure. The structure shall not be Out of Plumb more than 3.5 mm on each lox section of height and not more than 7.0 mm per 30 m section.

These tolerances shall apply to all parts of the structure unless the drawings issued for erection purposes state otherwise.

4.03.00 Acceptance

Structures and members have passed the tests and conform to all requirements specified in the foregoing Sub-clause 4.01.00, 4.01.01, 4.01.02, 4.01.03 and 4.01.04 and other applicable provisions of this specification and are within the limits of tolerances specified in Sub-clause 4.02.00 and/or otherwise approved by the Engineer shall be treated as approved and accepted for the purpose of fulfillment of the provisions of this contract.

5.00.00 INFORMATION TO BE SUBMITTED

5.01.00 Before Tender

5.01.01 Tentative Programme

The Tenderer shall submit a tentative programme based on the information available in the Tender Document and visit to site indicating the structure-wise erection schedule proposed to be maintained by the Contractor to complete the job in time in accordance with the Contract.

5.01.02 Constructional Plant and Equipment, Tools, Temporary works & manpower A detailed list of all constructional plant and equipment like cranes, derricks, winches, welding sets, erection tools etc. along with their make, model, present condition and location available with the Tenderer which he will be able to employ on the job to maintain the progress of work in accordance with the Contract shall be submitted along with the Tender. The total number of each category of experienced personnel like fitters, welders, riggers etc. that he will be able to employ on the job shall also be indicated.

5.01.03 Erection Yard

A site plan showing the layout and location of the erection yard proposed to be established by the tenderer shall also be attached with the tender indicating the storage space for fabricated steel materials, site-fabrication and repair shop, covered stores, offices, locations of erection equipments and other facilities. The Engineer shall have the right to modify the arrangement and location of the proposed yard to suit site conditions and the Contractor shall comply with the same without any claim whatsoever.

5.02.00 After award of the Contract

After award of the contract, the Contractor shall submit the following:

5.02.01 Detailed Programme

The Contractor shall submit a detailed erection programme within a month of the award of the Contract for completion of the work in time in accordance with the Contract. This will show the target programme, with details of erection proposed to be carried out in each fortnight, details of major equipment required, and an assessment of required strength of various categories of workers in a proforma approved by the Engineer.

5.02.02 Fortnightly Progress Report

The Contractor shall submit fortnightly progress reports in triplicate to the Engineer showing along with necessary photographs, 125 mm x 90 mm size, and all details of actual achievements against the target programme specified in Sub-clause 5.02.01 above. Any shortfall in the achievement in a particular fortnight must be made up within the next fortnight. Along with this report, the Contractor shall also furnish details of fabricated materials in hand at site and the strength of his workers.

VOLUME: II B

SECTION - D

SUB-SECTION – D19

ROOF DECKING

SPECIFICATION NO. PE-TS-999-600-C019

Maharatna Company

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	SCOPE	3
2.00.00	MATERIALS	3
3.00.00	INSTALLATION	3
4.00.00	ACCEPTANCE CRITERIA	6
5.00.00	IS CODES	6
6.00.00	RATES AND MEASUREMENTS	7

ROOF DECKING

1.00.00 Scope

This section of the specification covers the supply, fabrication and erection of profiled light gauge Metal Decks (coated and painted) as roof decking to the main plant building and any other area as indicated in the drawings.

2.00.00 Material

2.01.01 Roof of main plant TG and Deaerator bay and bunker building consists of permanently colour coated (on exposed face) galvanized MS trough metal sheet decking plate of approved colour over roof purlins for cast-in-situ roof slab as per IS: 14246 and conform to class 3. Thickness of deck plate shall be minimum 0.8mm and minimum trough depth of 44 mm and center to center of the valley shall be 130mm with minimum yield strength of 250 Mpa. Silicon modified polyester paint shall be used for permanent coating over galvanized surface with minimum rate of galvanization 150 gm/sqm. DFT of permanent colour coating shall be 20 microns. It shall serve as permanent shuttering for cast-in-situ roof slab. It should have adequate strength to support weight of green concrete and imposed load during construction. The thickness of the deck plate shall however be designed suitably according to the spacing of roof purlins.

3.00.00 INSTALLATION

The Contractor shall furnish all labour, equipment and materials as required for the design, fabrication, coating, erection and fixing of the decking over purlins, painting and for the complete performance of the work in accordance with the construction drawings and as described herein.

The description, which follows, gives a general indication of the nature and extent of the work but is not necessarily exhaustive and does not purport to cover all the details/operations which will be necessary in order to carry out the work.

3.01.00 Detailed Design of Roof Decking

The Contractor, in conjunction with the manufacturer, shall be responsible for the detailing of the profiled decking, fittings and fixtures and shall submit with his tender particulars of the proposed manufacturer and of the particular product proposed for use. The detailing is to be based on typical details furnished by the Engineer. The Contractor shall submit to the Engineer, two copies of the general arrangement and detailed working drawings for the proposed design, together with all calculations necessary to verify the adequacy and completeness of the design & detailing of decking sheets, fixtures, flashings and trims. After approval he shall supply further eight copies.

The Engineer will verify the correct interpretation of his requirements but may not necessarily check the design and details, and the Contractor shall be entirely responsible for the accuracy of the drawings and the correctness of the design and the suitability of the details. Manufacture of roof decking sheets shall not commence until the necessary approval of the Engineer has been obtained.

3.02.00 Erection & Fixing

3.02.01 Sequence of Manufacture/Erection

Cutting Schedules, delivery to site and stacking arrangements in store shall ensure that sheets are erected in a sequence which follows that for the manufacture. The decking sheets shall be erected using an arrangement of sheets and joints to conform with the requirements of this specification. Decking erection for each elevation or feature shall commence at one end only and proceed towards the other end, in order to ensure tight fitting laps.

3.02.02 Position and Location of Laps

Side and end laps of roof decking sheets shall be located and positioned in such a manner as to provide the maximum weather protection taking into account the direction of the prevailing wind.

The lines formed by horizontal laps and fixing shall where possible, be continuous and coincide with the edges of large openings in the roof.

3.02.03 Alignment of Sheets and Fixings

All roof decking sheets shall be fixed plumb and level with all fixings evenly spaced and accurately lined. All dirt and grease shall be removed from the surfaces of the sheets as the work proceeds.

3.02.04 Site Cutting

Approval must be obtained before the roof decking sheets are cut at site. Generally cutting of sheets to length will not be permitted, only special cutting and trimming for small openings shall allowed. Where possible, site cut edges shall be concealed at laps.

3.02.05 Damaged Sheets

Distorted, blemished or water stained sheets and any other fittings shall not be used.

3.02.06 Laps

End laps and side laps to roof decking sheets shall be sufficiently large to ensure that the decking complies with the weather tightness and other requirements of this specification. The length of each decking sheet shall be adjusted so that the end laps shall bear on the purlins. In no case end laps shall not be less than 150 mm and side laps shall not be less than 53 mm.

3.02.07 End Lap Fixings

End lap fixings shall be located at least 25 mm from the end of each sheet.

3.02.08 Side Lap Fixings

The spacing of side lap fixings shall ensure compliance with this specification regarding tightness. The spacing of these fixing screws shall not exceed 500mm. The fixing shall be located in the bottom flat of the corrugation.

3.02.09 Holes

Holes in MS decking sheets shall be punched. In case holes are drilled holes, it is to be ensured that the holes do not go oversize due to the small thickness of the sheeting. All drilling swarf shall be removed from the surfaces of decking, supporting steel work, purlins etc.

3.02.10 Location and Spacing of Fixings

Fixings shall be accurately located in position in the centre of the corrugations to ensure that the heads of bolts, nuts and washers bear squarely down on the surface of the sheeting and are not located at the edge or on the joints in supporting purlins.

3.02.11 Fixings

The tenderer shall submit with his tender details of the proposed method for securing the roofing sheets to the metal purlins. The roof decking sheets are to be fixed to the roof purlins with hex washer head white zinc plated heat treated carbon steel self-drilling / self-tapping screws of minimum thread diameter of 5.6mm. These self-drilling screws shall be drilled through the roofing sheets and purlins supporting the roofing sheets. These purlins shall be suitably spaced as per the requirement of roofing sheets and the roofing sheets shall not sag more than span/250 for the loads likely to be imposed during concreting and in future. The self-drilling screws are to be spaced at a maximum distance of 390mm centre to centre along the length of the purlins and top chord of truss. The screws are to be located preferably in the valley only and shall be installed in accordance with the manufacturer's

recommendations using tools approved by the manufacturer which do not damage the coating of the decking sheets.

3.03.00 Protection during Construction

Precautions shall be taken during the erection of the roof decking to ensure that partially erected decking are protected during inclement weather and damage at all times.

3.04.00 Damage

Any damage to coating & primer during transportation is to redone with the similar type of coating as per the manufacturer's specification at no extra cost to the Owner.

4.00.00 Acceptance Criteria

The installation shall present a neat appearance and shall be checked for water tightness. The following shall be checked:

a) Side and end laps

b) Absence of damage in the sheeting.

c) Conformity of fixings with the approved design.

5.00.00 IS Codes

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS: 513 - Specification for cold rolled carbon steel sheets.

IS: 3618 - Specification for phosphate treatment of iron and steel for protection against corrosion.

IS: 4431 - Specification for carbon & carbon manganese free cutting steel.

IS: 1573 - Electroplated Coatings of zinc on iron and steel.

6.00.0 RATES AND MEASUREMENTS

6.01.00 Rates

Rates shall be unit rate for complete item described in the Schedule of Items and shall include all wastage.

6.02.00 Method of Measurement

Roofing shall be measured for net area of the work done. Profiled sheeting (coated & painted) shall be measured in plan area of sheets and not girthed. No deduction shall be made for openings measuring up to 0.1 sq.m. in area. No extra shall be paid for extra labour in cutting and for wastage etc. in making opening and cutting to size.

No payments shall be made for laps.

VOLUME: II B

SECTION - D

SUB-SECTION – D20

FALSE FLOORING

SPECIFICATION NO. PE-TS-999-600-C020

Maharatna Company

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	GENERAL	3
2.00.00	MATERIALS	3
3.00.00	INSTALLATION	4
4.00.00	ACCEPTANCE CRITERIA	5
5.00.00	IS CODES	6
6.00.00	RATES AND MEASUREMENTS	6

FALSE FLOORING

1.00.00 General

This section of the specification covers the supply, fabrication and installation of false flooring system having PVC top finish particle board, GI supporting system, painting etc. as per schedule of items in the main plant building and any other area as indicated in the drawings.

The scope of contractor covers supplies of all materials, fabrication & installation works required to be carried out for completion of false flooring in the area specified in the drawings.

2.00.00 MATERIAL

2.01.00 Supporting structure

Supporting pedestals shall be made of steel and will be of height as required. Supporting pedestal shall be truly vertical and located at distances to conform with size of floor panels and shall be equipped with locking devices to prevent disturbances of finished elevation. Base of pedestal shall have integral load dispersion plate of size 100x100x8mm to transmit the load evenly to the base floor. Adjustment of pedestal shall be provided by threaded vertical rod of 25mm diameter and elevating nut. The pedestal head shall provide positive interlocking of the steel grid channels supporting system and shall prevent lateral shifting.

The grid channels shall be made of galvanised steel of 40mm x 40mm x 3.15mm thick and shall be placed at 610mm centre to centre both ways to support floor panels in uniform levelled elevations. Nominal height of the false flooring system shall be 600 mm unless otherwise indicated. Pedestal head shall be equipped with conducting grounding pad if so desired by the Engineer

2.02.00 Floor Panels

The floor panels shall be made of fire resistant particle board, phenol formaldehyde bonded. Size of each panel shall be 610mm x 610mm with all panel edges finished to a tolerance of + 0.2mm. Floor panel shall have 2mm thick non-static PVC on top, 2mm thick hard PVC strip lipping on four edges and 26 G aluminium sheet fixed with araldite at bottom. Minimum thickness of the panel shall be 35mm, unless otherwise noted. All panels shall be completely interchangeable and easily removable with a suction lift tool. Panels shall be square within a tolerance of $\pm$ 0.25 mm on the diagonal. The floor panels shall be cut, wherever required for providing suitable outlets for cables and edges shall be lipped with hard PVC sheets.

2.02.01 Strength

Each 610mm x 610 mm floor panel must be capable of withstanding the designed service load. The ultimate strength shall provide a safety factor of 3. The false flooring shall be capable of carrying a axial load of 800 kg and uniform load of 2000 kg/sq.m with maximum deflection of 1/350. If required by the Engineer, the samples shall be accepted only after carrying out load tests. The Engineer may relax the test requirements with concentrated load in case cabinets are not handled with castor fitting arrangement.

One additional pedestal shall be provided under floor stringer along front panel area of each control board for taking possible additional load that may occur from time to time.

2.02.02 Surface finish

All removable panels shall have the top surface finished with 2 mm thick flexible PVC flooring conforming to IS:3462 and shall be fixed to the surface with compatible high-creep resistant adhesive. The PVC floor tile shall be in single piece for each floor panel. Under side of panels shall also be painted with suitable epoxy or oil based paint.

2.02.03 Damaged Floor Panels

Distorted, blemished or stained floor panels shall not be used.

2.03.00 Skirting

Skirting shall be 150 mm high and 2 mm thick, completely matching with false flooring surface finish materials and shall be fixed to the wall surface as per manufacturer's installation instructions.

3.00.00 INSTALLATION

3.01.00 Base

The system shall be placed over a base of RCC floor slab and beams. Any grouting etc. that is necessary to fix the supporting structure shall be done.

The concrete sub floor shall be sealed with two coats of polyurethane paint to prevent moisture from coming in contact with cables and to minimize dust problem.

The floor panels and channels shall be completely interchangeable and remain in position without screwing or bolting under working/imposed loadings.

Any damage to the sub floor during installation of the false flooring system

shall be made good by the contractor without any extra cost to the Owner. All steel surfaces are to be protected by two coats of polyurethane paint over a compatible primer and any damage to the paint during installation shall be made good. In case the loads exerted by the weight of machines are above the stated characteristics of floor finish material, the floor shall be protected by overlaying hard board during installation of machine or equipment.

All installation work of the false flooring system shall be supervised by the manufacturer's authorized representative.

3.03.00 Painting

After fixing the false flooring supporting system the sub floor shall be given a coat of polyurethane paint.

3.04.00 Protection during Construction

All precautions shall be taken during the erection of the false flooring to ensure that partially erected flooring are protected and shall not be damaged before handing over to owner.

3.05.00 Damage

Any damage of coating to supporting system caused during transportation is to be redone with the similar type of coating as per the manufacturer’s specification at no extra cost to the Owner.

4.00.00 ACCEPTANCE CRITERIA

The false flooring system shall only be accepted after completion of following checks:

a. Level

b. Alignment of joints

c. Thickness of joints

d. Surface finish

e. Colour and texture

f. Details of edges, junctions etc.

g. Performance

h. Criteria specified for strength.

5.00.00 IS CODES

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS:5318 Laying of flexible sheet and flooring.

IS:3462 Flexible PVC flooring

IS:3087 Wood particle boards (medium density) for general purposes.

6.00.0 RATES AND MEASUREMENTS

6.01.00 Rates

Rates shall be unit rate for complete item described in the Schedule of Items and shall include, but not limited to, supply & installation of floor panels, supporting systems, paintings etc.

6.02.00 Method of Measurement

False flooring shall be measured in Sq.M for net area of the work done. No deduction shall be made for openings measuring up to 0.4 sq.m. in area. No extra shall be paid for extra labour in cutting and for wastage etc. in making opening and cutting to size.

VOLUME: II B

SECTION - D

SUB-SECTION – D21

BORED CAST-IN-SITU RCC PILES

SPECIFICATION NO. PE-TS-999-600-C021

Maharatna Company

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

CONTENTS

CLAUSE NO.	DESCRIPTION	
1.00.00	SCOPE	3
2.00.00	GENERAL REQUIREMENTS	3
3.00.00	MATERIALS	5
4.00.00	PILE INSTALLATION	6
5.00.0	SAMPLING, TESTING, AND QUALITY ASSURANCE	12
6.00.00	PILE TESTING	15
7.00.00	CODES AND STANDARDS	16
8.00.00	RATES AND MEASUREMENT	17
	ANNEXURE-A	
	ANNEXURE-B	
	ANNEXURE-C	
	ANNEXURE-D	
	TABLE - 1	

TECHNICAL SPECIFICATION FOR INSTALLATION OF BORED CAST-IN-SITU PILES

1.00.00 SCOPE

This specification covers the installation of bored cast-in-situ reinforced concrete vertical piles of specified load carrying capacity and diameter for various structures. This specification also covers carrying out initial and routine load tests on piles to assess their vertical, horizontal and pull out load carrying capacities.

2.00.00 GENERAL REQUIREMENTS

2.01.00 This specification along with specific requirements under Annexure-A covers the technical requirements for piling work.

2.02.00 The work shall include supplying and providing necessary materials, mobilization of all necessary equipments (Annexure-B), providing necessary engineering supervision through qualified and technical personnel, skilled and unskilled labour, etc. as required to carry out the complete piling work, and submission of records as per schedule.

2.03.00 The Contractor shall carryout all works as mentioned in Scope above. All works shall be executed to the satisfaction of the Engineer.

2.04.00 Pile capacities in vertical compression, horizontal, pull-out loads for various pile diameters are given in Annexure-A.

2.05.00 The Contractor shall confirm and guarantee the "Safe Load" capacities by conducting both initial and working load test on piles as mentioned in the specific requirements.

2.06.00 The Contractor shall submit along with tender documents his tender design of piles based on soil data furnished by the Owner along with this specification. The ultimate load capacity of a pile may be estimated using suitable static formula and the minimum factor of safety shall be 2.5. However, safe load carrying capacity shall be conformed and guaranteed by conducting initial and routine load tests.

2.07.00 In case of initial or routine load test piles, if the Contractor fails to establish the safe load capacity as per his design, the Owner has the right to either derate the pile capacity on prorata basis or insist the Contractor to modify the pile design, to achieve the desired safe load capacity at no extra cost to the Owner.

2.08.00 Derating is acceptable up to 90 percent. In such case, additional piles shall be installed as per the design requirements.

2.09.00 The Owner shall decide whether to derate or modify the design based on the design considerations such as providing additional piles in the designed pile cap, provision for extending the pile cap size, etc.

2.10.00 In case the Owner decides to modify the design instead of derating the pile, the contractor shall carry out the same and install separate test piles and test the same to guarantee the safe load at no extra cost to the Owner. However, no extra shall be charged for the additional test piles as well as testing of these piles as per agreed contract conditions.

2.11.00 In case of working piles, if the pile does not meet the guaranteed capacity or rejected due to any other reason, the Contractor shall install extra piles at no extra cost to the Owner. Further, the extra cost, due to the increase in the pile cap size if any, on account of extra piles, shall be borne by the Contractor.

2.12.00 It is essential that all equipment and instruments are properly calibrated both at commencement and immediately after the completion of tests so that they represent true values. Certificates to this effect from an approved institution shall be furnished to the Engineer. If the Engineer so desires the Contractor shall arrange for having the instruments tested at an approved laboratory at no extra cost to the Owner and the test report shall be submitted to the Engineer. If the Engineer desires to witness such tests Contractor shall arrange to conduct the test in his presence.

2.13.00 The Contractor shall make his own arrangements for locating the coordinates and position of piles as per drawings supplied to him and for determining the Reduced Levels (RL) of these locations with respect to the benchmark indicated by the Engineer. Two established reference lines in mutually perpendicular direction shall be indicated to the Contractor. The Contractor shall provide at site all the required survey instruments to the satisfaction of the Engineer so that the work can be carried out accurately according to specifications and drawings.

2.14.00 The contractor shall assure the quality of piling work including cleaning of pile bore, quality of concrete, integrity of piles, etc.

2.15.00 **AVAILABLE SUB-SOIL DATA**

An abstract of the sub soil data is furnished in the tender document. However, the detailed soil investigation report shall be made available for reference of the bidder, if so required, at the office of the Owner. The soil data furnished is in good faith and only for the guidance of the Bidder, to arrive at design parameters and construction methods.

3.00.00 MATERIALS

3.01.00 General

All materials viz cement, steel, aggregates, water, etc. which are to be used for pile construction shall conform to relevant IS codes for properties, storage and handling of common building materials. However, aggregates more than 20 mm size shall not be used.

3.02.00 CONCRETE

Concrete shall be manufactured either by central batching plant or Ready Mix concrete. However, for initial test piles suitable method as approved by the Engineer may be used. Concrete shall conform to IS: 10262 & IS: 456.

3.02.01 Technical Specification for Cement Concrete (Plain and Reinforced) works along with IS: 2911 Part I/Sec 2 shall be followed for concrete works of piles. Use of plasticiser to control the water cement ratio shall be permitted on specific approval from the Engineer. Water cement ratio shall not be greater than 0.5.

3.02.02 Grade and minimum cement content
Minimum grade of concrete shall be as per Annexure-A conforming to IS: 456. Minimum cement content of 400 Kg/M³ of concrete shall be used for M-20 grade concrete.

3.02.03 Slump of concrete
The slump of concrete shall vary between 150 to 180 mm.

3.03.00 REINFORCEMENT

3.03.01 Longitudinal reinforcement in pile shall be high strength deformed steel bars conforming to IS: 1786 unless specified otherwise. Lateral reinforcement in pile shall be of mild steel conforming to IS: 432 Part-1 or HYSD bars as per IS: 1786.

3.03.02 The longitudinal reinforcement shall be provided considering the combination of vertical (compression and tension) and horizontal loads. However, the minimum longitudinal reinforcement shall be 0.4 percent of the sectional area calculated on the basis of nominal pile diameter. Minimum six numbers of bars shall be provided for longitudinal reinforcement. The diameter of longitudinal reinforcement bars shall not be less than 12mm. The stipulated minimum reinforcement shall be provided for the full length of pile.

3.03.03 The longitudinal reinforcement shall project 50 times its diameter above cut off level unless otherwise indicated.

3.03.04 The laterals shall be tied to the longitudinal reinforcement to maintain its shape and spacing. The laterals may in the form of links or spirals. The minimum diameter of the links or spirals shall be 6 mm and the spacing of the links or spiral shall not be less than 150 mm and in no case more than 250 mm.

3.03.05 Reinforcement cage shall be sufficiently rigid to withstand handling and installation without any deformation and damage. As far as possible number of joints (laps) in longitudinal reinforcement shall be minimum. In case the reinforcement cage is made up of more than one segment, these shall preferably be assembled before lowering into casing tube/pilebore by providing necessary laps as per IS: 456.

3.03.06 The minimum clear distance between the two adjacent main reinforcement bars shall normally be 100 mm for the full depth of cage.

3.03.07 The laps in the reinforcement shall be such that the full strength of the bar is effective across the joint and the reinforcement cage is of sound construction.

3.03.08 Laps shall be staggered as far as practicable and not more than 50% bars shall be lapped at a 'particular section. Lap joints shall be staggered by at least 1.3 times the lapped length (Centre to Centre).

3.03.09 Proper cover and central placement of the reinforcement cage in the pile bore shall be ensured by use of suitable concrete spacers or rollers, cast specifically for the purpose.

3.03.10 Minimum clear cover to the longitudinal reinforcement shall be 50 mm, unless otherwise mentioned.

3.03.11 Bundling of bars is not permitted.

4.00.00 PILE INSTALLATION

Installation of piles shall be carried out as per pile layout drawings, installation criteria, and the direction of the Engineer.

4.01.00 Equipment and Accessories

4.01.01 The equipment and accessories for installation of bored cast-in-situ piles shall be selected giving due consideration to the sub soil conditions, ground water conditions and the method of casting, etc. These shall be of standard type and shall have the approval of the Engineer.

4.01.02 List and details of equipment and accessories proposed to be used for the job shall be submitted along with the bid.

4.01.03 The capacity of the rig shall be adequate so as to reach the specified founding level.

4.01.04 Provision shall be kept for chiselling within the pilebore, as specified elsewhere in this specification. Chiselling shall be carried out only with the approval of Engineer.

4.02.00 Installation Criteria

4.02.01 For determining the founding level of piles in soil as specified elsewhere, the Contractor shall have to perform Standard penetration test (SPT) as per IS: 2131 in a separate bore hole. The SPT shall be conducted at 1.0 m interval between the depths covering 5 metres each above and below the specified founding level. The bore shall be 100 mm diameter and method of boring shall conform to IS: 1892.

4.02.02 For determining founding level of piles in rock, as specified elsewhere socketing horizon shall be established by the Contractor by collecting rock cores of NX size in a separate borehole, and testing the same for uniaxial compressive strength (UCS). Cores shall be collected by double tube core barrel attached with diamond bit. Coring shall be done upto a depth as indicated in the "specific requirements." Coring in rock shall conform to IS: 6926.

4.02.03 In case it is not possible to test the cores so obtained for uniaxial compressive strength, cores shall be tested for point load strength index and correlated to obtain uniaxial compressive strength.

4.02.04 Number of boreholes for carrying out SPT in soil or uniaxial compressive strength in rock, shall vary from one in 100 to 150 piles or pile group of 150 Sqm depending on the site condition and as decided by the Engineer. However, at the location of initial load test piles, one such borehole shall be done.

4.02.05 A protocol between contractor and BHEL site shall be maintained regarding the strata at founding level. SPT value and UCS from the nearest borehole shall be indicated therein.

4.02.06 The founding level of the pile shall be decided based on the criteria elaborated in the specific requirements under Annexure-A. Concreting shall not be done until the above conditions for founding level are satisfied.

4.02.07 Approval of founding level by the Engineer shall in no way absolve the Contractor of his responsibility to guarantee the Safe load capacity of the piles as indicated in this document.

4.03.00 Control of position and alignment

4.03.01 Piles shall be installed as accurately vertical as possible. The permissible limits for deviation with respect to position and (inclination) alignment shall conform to IS: 2911 Part I/Sec. 2, which is reproduced below for ready reference.

a) The maximum deviation of vertical piles shall not exceed 1.5 per cent in alignment.

b) Piles shall not deviate more than 75 mm or D/4 whichever is less (75mm or D/10 whichever is more in case of piles having diameter more then 750mm) from their designed position at the working level.

4.04.00 Boring

4.04.01 Boring operations shall be done by rotary or percussion type drilling rigs using reverse mud circulation (RMC) method. Rotary hydraulic pulley shall be preferred.

4.04.02 The Contractor shall satisfy himself about the suitability of the method to be adopted for site. If DMC (direct mud circulation) or RMC is used Bentonite slurry shall be pumped through drill rods by means of high-pressure pumps. The cutting tool shall have suitable ports for the bentonite slurry to flow out at high pressure. If on mobilisation, the Contractor fails to make a proper bore for any reason, the Contractor has to switchover to other boring methods as approved by the Engineer at no extra cost to the Owner.

4.04.03 Working level shall be above the cut off level. After the initial boring of about 1.0m a temporary guide casing of suitable length shall be lowered in the pile bore. The diameter of guide casing shall be of such diameter, so as to give the necessary finished diameter of the concrete pile. The centre line of guide casing shall be checked before continuing further boring. Guide casing shall be minimum of 1.0m length. Additional length of casing may be used depending on the condition of the strata, ground water level etc.

4.04.04 Use of drilling mud (bentonite slurry) for stabilizing the sides of the pile bore is necessary wherever subsoil is likely to collapse in the pile bore. Drilling mud to be used shall meet the requirement as given in Annexure-C.

4.04.05 The bentonite slurry and the cuttings, which are carried to the surface by the rising flow of the slurry, shall pass through settling tanks of adequate size to remove the sand and spoils from the slurry before the slurry is recirculated to the boring. The bentonite slurry mixing and recirculation plant shall be suitably designed and installed.

4.04.06 The bentonite slurry shall be maintained at 1.5m above the ground water level during boring operations and till the pile is concreted. When DMC or RMC

method is used the bentonite slurry shall be under constant circulation till start of concreting.

4.04.07 The size of cutting tools shall not be less than the diameter of the pile by more than 75mm. However, the pile bore shall be of the specified size.

4.05.00 Chiselling

4.05.01 Chiselling may be resorted to with the permission of the Engineer below the socketing horizon. The chiselling tool or bit shall be of adequate size and weight so as to reach the desired depth.

4.06.00 Cleaning of Pile bore

4.06.01 On completion of the pile bore upto the required depth, the bottom of the hole shall be cleaned very carefully before concreting work is taken up. Cleaning shall ensure that the pile bore is completely free from sludge/bored materials, debris of rock/boulder etc. Necessary checks shall be made as given in clause 5.0 to confirm the thorough cleaning of the pile bore.

4.06.02 Pile bore shall be cleaned by fresh drilling mud through tremie pipe after placing reinforcement and just before start of concreting.

4.06.03 Pile bore spoil along with used drilling mud shall be disposed off from site as directed by the Engineer.

4.06.04 Pile bore bottom shall be thoroughly cleaned to make it free from sludge or any foreign matter before and after placing the reinforcement cage.

4.07.00 Adjacent Structures

4.07.01 When working near existing structures care shall be taken to avoid any damage to such structures.

4.08.00 Concreting

4.08.01 The Contractor shall carry out concrete mix design in accordance with IS: 10262 and submit mix design calculations and get them approved from the Engineer well in advance for installation of piles. Adequate number of tests on cubes, etc. shall be carried out as mentioned in clause 5.0 to ensure concrete of the minimum specified strength in accordance with IS: 456 at requisite workability (slump).

4.08.02 Concreting shall not be done until the Engineer is satisfied that the bearing strata (soil/rock) met with at the termination level of pile.

4.08.03 The time interval between the completion of boring and placing of concrete shall not exceed 6 hrs. In case the time interval exceeds 6 hrs the pilebore shall be abandoned. However, the Engineer may allow concreting provided the Contractor extends the pile bore by 0.5 m beyond the proposed depth, and clean the pilebore. The entire cost of all operation and materials for this extra length shall be borne by the Contractor.

4.08.04 Proper placement of the reinforcement cage to its full length shall be ensured before concreting.

4.08.05 Concreting shall be done by tremie method as specified by IS: 2911 (Part I /Sec.2). The level of drilling mud shall be maintained sufficiently above the ground water level.

4.08.06 The concreting operations shall not be taken up when the specific gravity of bottom slurry is more than 1.2 and sand content more than 7%. The drilling mud sample shall be collected from the bottom of pilebore as mentioned in clause 5.

4.08.07 Consistency of the drilling mud suspension shall be controlled throughout the concreting operations in order to keep the bore stabilized as well as to prevent concrete getting mixed up with the thicker suspension of the mud.

4.08.08 It shall be ensured that volume of concrete poured is at least equal to the theoretically computed volume of pile shaft being cast.

4.08.09 The temporary guide casing shall be withdrawn cautiously, after concreting is done upto the required level. While withdrawing the casing concrete shall not be disturbed.

4.09.00 Cut off level (COL)

4.09.01 Cut off level of piles shall be as indicated in drawings released for construction or as indicated by the Engineer.

4.09.02 The top of concrete in pile shall be brought above the COL to remove all laitance and weak concrete and to ensure good concrete at COL for proper embedment in to pile cap.

4.09.03 When the pile cut off level is less than 1.0 metre below the working level, concrete shall be cast to the piling platform level to permit overflow of concrete for visual inspection. In case COL of pile is more than 1.0 metre below working level then concrete shall be cast to a minimum of one metre above COL.

4.10.00 Sequence of Piling

4.10.01 Each pile shall be identified with a reference number.

4.10.02 The convenience of installation may be taken into account while scheduling the sequence of piling in a group. This scheduling shall avoid piles being bored close to other recently constructed piles.

4.11.00 Building up of Piles

4.11.01 If any pile, already cast as per construction drawing, requires any extra casting due to any change in cut off level or the cast pile top level is less than the specified level or for any other reason, then the pile shall be built-up by using atleast one grade higher concrete than that used for concreting of the same pile, ensuring proper continuity with the existing concrete and to the satisfaction of the Engineer. Necessary reinforcement as per design requirement and suitable shuttering shall be provided before casting the concrete. Surrounding soil shall also be built up to the required level by proper compaction to ensure lateral capacity of the pile.

4.12.00 Breaking off of Piles

4.12.01 If any pile already cast, requires breaking due to lowering in cut off level or for any other reason, then the same shall be carried out, not before seven days of casting without affecting the quality of existing pile such as loosening, cracking etc. and to the satisfaction of the Engineer.

4.13.00 Preparation of Pile head

4.13.01 The soil surrounding the piles shall be excavated upto the bottom of the lean concrete below the pile cap, with provision for working space, sufficient enough to place shuttering, reinforcement, concreting and any other related operations.

4.13.02 The exposed part of concrete above the COL shall be removed/chipped off and made to a uniform level at COL, but not before seven days of casting of pile.

4.13.03 The projected reinforcement above COL shall be properly cleaned and bent to the required shape and level to be anchored into the pile cap.

4.13.04 The pile top shall be embedded into the pile cap by 50mm or clear cover to reinforcement, whichever is higher.

4.13.05 All loose material, like debris due to chipping/breaking of pile head to the desired level, shall be removed and disposed off as directed by the Engineer.

4.14.00 Rejection and Replacement of Defective Piles

4.14.01 The Engineer reserves the right to reject any pile which in his opinion is defective on account of load capacity, structural integrity, position, alignment, concrete quality etc. Piles that are defective shall be pulled out or left in place as judged convenient by the Engineer, without affecting the performance of adjacent piles. The Contractor shall install additional piles to substitute the defective piles as per the directions of the Engineer, at no extra cost to the Owner.

4.15.00 Recording of Piling Data

4.15.01 The Contractor shall record all the information during installation of piles. Typical data sheet for recording pile data shall be as shown in Appendix D of IS: 2911 Part I/Sec.2. The pile data shall also include all the details as in Annexure-D. On completion of each pile installation, pile record in triplicate shall be submitted to Engineer within two days of completion of concreting of the pile.

5.00.00 SAMPLING, TESTING AND QUALITY ASSURANCE

5.01.00 Facilities required for sampling and testing of materials, concrete, etc. in field and in laboratory should be provided by the Contractor. The Contractor shall carry out all sampling and testing in accordance with the relevant Indian Standards and this Specification. Where no specific testing procedure is mentioned the tests shall be carried out as per the prevalent accepted engineering practice and as per the directions of the Engineer. Tests shall be done in the presence of the Engineer or his authorized representative. In case the Engineer requires additional tests, the Contractor shall arrange to get these tests done and submit to the Engineer the test results in triplicate within three days after completion of any test.

5.02.00 The Contractor shall maintain records of all inspection and testing, which shall be made available to the Engineer. The Engineer at his discretion may waive some of the stipulations for small and unimportant concreting operations and other works.

5.03.00 Materials found unsuitable for acceptance shall be removed and replaced by the Contractor. The work done by this unsuitable material shell be redone as per specification requirements & and to the satisfaction of the Engineer at no extra cost to the Owner.

5.04.00 Quality Assurance Programme

a) The Contractor shall submit and finalize a detailed Field Quality Assurance Programme within 30 days from the date of award of the contract, according to the requirements of this specification. This shall include setting

up of a testing laboratory, arrangement of testing apparatus/equipment, deployment of qualified/experienced manpower, preparation of field quality plan, etc. On finalized field quality plan, the Owner shall identify, customer hold points, beyond which work shall not proceed without written approval from the Engineer. The testing apparatus/equipment installed in the field laboratory shall be calibrated/ corrected by the qualified persons as frequently as possible to give accurate testing results.

b) Frequency of sampling and testing, etc. and Acceptance Criteria are given in Table - 1. The testing shall be done at field laboratory or any other laboratory approved by the Engineer. However, the testing frequencies set forth are the desirable minimum and the Engineer shall have the full authority to call for tests as frequently as he may deem necessary to satisfy himself that the materials and works comply with the appropriate specifications. The materials shall be tested to meet all the specified requirements before acceptance at manufacturers premises or at independent government approved laboratory. Tests indicated in the table are for cross checking at site the conformity of the materials to some of the specifications.

5.05.00 Testing of Concrete

5.05.01 Concrete and other materials shall be tested for quality, strength and other properties. Details of testing shall be as specified under technical specification for Cement concrete (Plain and Reinforced).

5.05.02 One sample consisting of six test cubes shall be made from the concrete used in each test pile, three to be tested after 7 days and three after 28 days.

5.05.03 For working piles, minimum one sample consisting of six test cubes shall be made from the concrete for the first ten piles, three to be tested after 7 days and three after 28 days. Thereafter, minimum one sample consisting of three test cubes for every 10 piles shall be tested for the 7-days & 28-days cube strength.

5.05.04 In preparation of test cubes or specimen's vibrators shall not be used.

5.05.05 Concrete shall be tested for slump at every 1-hour interval during concreting of piles.

5.05.06 The frequency of sampling and testing of concrete and materials shall be done as per technical specification for cement concrete (Plain & Reinforced).

5.05.07 The acceptance criteria shall be as mentioned in Table-1.

5.06.00 Testing for position and alignment

5.06.01 Each pile shall be checked for its position with respect to specified location. Each pile bore shall be checked for its alignment.

5.06.02 Permissible limits for deviation shall be as specified under clause no. 4.03.

5.07.00 Properties of Drilling mud

5.07.01 Properties of drilling mud shall be checked as per requirement under Annexure C. Prior to the commencement of piling work and thereafter minimum once in a week or as found necessary by the Engineer, one sample consisting of 3 specimens shall be tested. Acceptance criteria applicable are as specified elsewhere with 5% variation. This relaxation is not applicable for properties of drilling mud before concreting.

5.07.02 Density of the drilling mud shall be checked in each pile before concreting.

5.08.00 Check for Pile bore

5.08.01 On completion of boring and cleaning the bottom of each pilebore shall be checked from the sample collected from near the bottom of pile bore or by any other methods as approved by the Engineer, to ensure that it is free from pilebore spoil/debris and any other loose material, before concreting. Concreting shall be done only after the approval of the Engineer.

5.08.02 For sampling of drilling mud from the pilebore the following method or any other suitable method shall be adopted.

a) A solid cone shall be lowered by a string to the bottom of pilebore. A sampler tube closed at top with a central hole (hollow cylinder) is lowered over the cone, and then a top cover shall be lowered over the cylinder. Care shall be taken for proper fittings of assembly to minimize the leakage while lifting the cone assembly to the ground surface. The slurry collected in the sampler tube shall be tested for density and sand content.

b) Use of borehole camera for checking the pile bore spoil and strata is acceptable on approval of the Engineer.

5.09.00 Pile Integrity test

5.09.01 Low strain integrity test shall be conducted on 50% of the jobs piles and on all test piles or as directed by Engineer. The system shall have the computer readout facility and report on the findings of this shall be furnished to the Owner. This test shall be used to identify the job piles for routine load test.

Piles shall be trimmed to cut off level or sound concrete level. No pile cap blindage work should be undertaken prior to this test. The cast in-situ piles should not be tested before 14 days of casting.

5.09.02 The test shall be undertaken by persons trained and experienced and capable of interpreting the results with specific regard to piling. This test is limited to

testing the integrity of the shaft and is not intended to replace the use of static load testing.

5.09.03 Low Strain Integrity Test Methodology:

a) In this test, a low stress wave is set up in the pile shaft and is also known as Sonic Integrity or Sonic Echo test.

b) A small metal/hard rubber hammer is used to produce a light blow on top of the pile. The shock wave travelling down the length of the pile is reflected back from the toe of the pile and recorded through a suitable transducer/ accelerometer in a computer for subsequent analysis.

c) The primary shockwave, which travels down the length of the shaft, is reflected from the toe by the change in density between the concrete and sub strata. However, if the pile has any imperfections or discontinuities within its length these will set up secondary reflections, which will be added to the return signal.

d) By analysis of the captured signal and knowledge of the conditions of the ground, age of concrete, etc. a picture of the locations of pile shaft defects can be built up. The observed signals are amplified into digital display as velocity versus length records providing information on structural integrity of piles.

e) The stress wave velocity and approximate pile lengths are provided as input for the integrity testing. The stress wave velocity is dependent on the Young's Modulus and mass density of pile concrete.

f) More than one recording of signals shall be done until repeatability of signals is achieved on the same pile.

g) The tests shall be conducted at 3-6 locations to cover the entire cross section of the pile.

6.00.00 PILE TESTING

Pile load test shall be carried out as per IS:2911 Part-4 (latest edition) or as directed by Engineer.

6.01.00 INITIAL LOAD TEST

Initial load test shall be carried out on separately cast piles for confirmation of estimated pile capacities and to fix a more accurate driving criteria viz. set/bow, total number of blows and approximate depth etc. of founding level. At least 2 nos. of tests shall be conducted for each mode (vertical compression, pull out and lateral). The maximum test load shall be as

mentioned in bill of quantities.

6.02.00 ROUTINE LOAD TEST

Routine load tests shall be carried out on job (working) piles for 0.5% of total no. of piles (for each mode and type). Maximum test load shall be 1.5 times the design safe load capacity. Piles showing unsatisfactory results as per load test results shall be treated as defective piles. Defective piles shall be removed or left in place and replaced by additional piles as directed by Engineer at no extra cost to the owner. Any additional cost towards design implications, if any, due to above shall be borne by the contractor.

7.00.00 CODES AND STANDARDS

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS: 432 (Part 1 & 11)	-	Specification for mild steel and medium tensile steel bars and hard drawn steel wire for concrete reinforcement.
IS: 456	-	Code of practice for plain and reinforced concrete.
IS: 1200 (Part 23)	-	Measurement of Building and Civil Engineering works Piling.
IS: 1786	-	Code of practice for twisted steel high strength deformed bars for concrete reinforcement.
IS: 1892	-	Code of practice for Subsurface Investigation for foundation.
IS: 2131	-	Method of Standard Penetration Test for Soils
IS: 2911 Part I/Sec 2	-	Code of practice for design and construction of pile foundations - Bored cast-in-situ concrete piles.
IS: 2911 Part IV	-	Code of practice for design and construction of pile foundation - Load test on piles.
IS: 6926	-	Code of practice for Diamond Core Drilling for Site Investigation for River Valley Projects.
IS: 10262	-	Recommended guidelines for concrete mix design.

8.00.00 RATES AND MEASUREMENTS

The clauses below shall apply for item rate contracts only. They shall not be applicable to turnkey/lump sum Contracts.

8.01.00 Rates

8.01.01 The items of work in the schedule of items, describe the work in brief. The various items in schedule of items shall be read in conjunction with the corresponding sections in the Technical Specifications, including amendments, and additions, if any. For each item in schedule of items, the unit rate shall include for the activities covered in the description of the item as well as for all necessary operations described in the specification and specific requirements.

8.01.02 The unit rates shall include for minor details which are obviously and fairly intended, and which may not have been included in the description in these documents, but are essential for the satisfactory completion of the work. Unit rates shall also include for all safety measures as required by codal provisions, local regulations, acts, bye-laws, etc. and for execution of work to the satisfaction of the Engineer.

8.01.03 The quoted rate for each item shall be inclusive of mobilization of all plant, equipment, scaffolding, labour, materials, skilled and unskilled labour, and demobilization after completion of work, supervision, establishing the level and coordinates at each work.

8.01.04 The quoted rate for piling for a particular diameter and capacity of pile shall remain valid for the actual lengths provided /to be provided irrespective of the minimum length specified elsewhere in this specification.

8.01.05 The quoted rate for piling as per description of item works shall be inclusive of providing all plant equipment, labour, materials, skilled and unskilled labour, making observations, establishing the ground level and coordinates at each location of pile by carrying levels from one established bench mark and distances from one set of grid lines furnished by the owner.

8.01.06 The quoted rate for piling shall be inclusive of bailing out all the pile bore spoil from the pilebore, keeping the borehole free from bored material/debris etc. and disposing the bored/chiselled material along with the drilling mud upto 2 Km. beyond plant boundary or as directed by Engineer, flushing the pile bore by fresh bentonite before concreting, collection of samples from bottom of pilebore, transporting to laboratory, testing and reporting of results.

8.01.07 The quoted rate for piling shall include shifting of plant and equipment from one pile location to another pile location, providing temporary casing pipe and removal of the same after completing, concreting, supply of necessary materials,

equipment and manpower, cost of boring by approved method as specified, circulation of bentonite slurry and cleaning of borehole free from sludge, as specified, etc.

8.01.08 The quoted rate for piling shall also include chiselling, if any, required for socketing the pile in rock.

8.01.09 The quoted rate for the piling shall include concreting by termite method, length of pile above COL, withdrawal of guide casing, cost for preparation of pile head and disposal of debris etc., resulting from breaking off of pile upto COL, upto a distance of 2 Km from the plant boundary or as directed by Engineer.

8.01.10 The quoted rate for piling shall also include providing reinforcement and its cleaning, straightening, cutting, bending, binding with annealed wire, welding, tack welding, providing concrete cover blocks, spacers, placing the reinforcement cage in pile casing/bore and other cost of tools and plants, materials, labours, carting the steel from store to piling site and return of unused steel to the Owners storage point, etc.

8.02.11 Plasticiser/Admixture when used as directed by the Engineer shall be included in piling rates.

8.01.12 The quoted rate for piling shall include for all quality assurance requirements, but not limited to providing for technical inspection, transportation of samples to laboratory, testing samples, maintaining and submitting all test records, etc.

8.01.13 The quoted rate for boring in separate borehole shall be inclusive of performing of SPT at regular intervals as specified and collecting rock cores from boreholes, upto the depth as specified shall be inclusive of transporting to laboratory, testing and reporting of the results.

8.01.14 Unit rate for low integrity test shall be inclusive of mobilization of the entire set of equipment, computer readout, printer, and equipment which may not lave been included in the description but are essential for the satisfactory completion of the work as per internationally accepted practice. The rate quoted shall be inclusive of repeatability of test, preparation of pile top surface etc.

8.02.00 Measurement

8.02.01 Piling length shall be measurement by linear measurement from pile cut-off level to the tip of pile in meters upto second place of decimal separately for each diameter and capacity of pile. The length of pile to be cast above cut off level, as per specification, and as approved by Engineer, shall be considered for cement reconciliation only. Theoretical diameter of piles shall be

considered for reconciliation of cement consumption. No extra payment shall be made for the length from existing ground to cut-off level.

8.02.02 Reinforcement steel shall be measured for reconciliation purpose only and the measurement shall be done for providing and placing reinforcement in piles, by weight in tones, up to third place of decimal in the following manner:

i) The weight shall be arrived at by multiplying the actual length measured along with standard hooks, rings or spirals, spacers, cranks, bends, authorized laps, etc. by sectional weight. These shall be submitted with supporting documents giving the schedule of bars with sketches. The sectional weight to be adopted shall be IS code's sectional weight. Nothing extra shall be payable to the contractor on account of difference in weight, if any, due to different methods adopted for issue and measurement.

ii) Standard hooks, cranks, bend, authorized laps, supports, hangers and chairs which are covered in approved bar bending schedule shall be measured in tones.

iii) Dowels, neither shown on the drawings nor instructed by the Engineer, but required for construction facilities shall not be measured.

8.02.03 Breaking off of piles, due to subsequent change in design cut off level, shall be measured separately. This shall be measured in cubic metres upto second place of decimal. This will be payable only when the pile is cast and on the basis of written instruction of the Engineer for lowering of COL.

8.02.04 Measurements for the item of boring in a separate borehole shall be measured in metres from ground level upto the depth as specified, upto second place of decimal. Item of work of boring in soil and coring in rock shall be measured separately for the actual length of boring in soil and coring in rock.

8.02.05 The item for pile integrity test shall be measured in terms of no. of piles tested.

ANNEXURE-A

Specific Requirements for Bored Cast-in-situ RCC Piles

A1.0 Minimum cement concrete grade M-25

Minimum cement content 400 Kg/M³

A1.1 Safe load

Diameter of Pile

Diameter of Pile (mm)	Vertical/ Compression (MT)	**Horizontal/ Lateral (MX)**	**Pul lout/Tension (MT)**
*	*	*	*
*	*	*	*

A2. Installation criteria

The installed pile(s) shall satisfy the following criteria.

A2.1 In Soil/weathered Rock

a) Minimum length of the pile shall be _____* m below COL.

b) The pile shall be terminated after penetrating through the strata having SPT penetration less than __* cm for ____* blows, for a minimum length of _____* times the diameter of the pile.

A2.2 In Rock

a) Piles shall be installed and socketed into the rocks for a length (socketing length) equal to _____* times the pile diameter subject to a minimum of _____* meter below the socketing horizon.

b) Socketing horizon shall consist of rock strata having minimum uniaxial compressive strength of _____* kg/sq.cm.

A3. Average cut-off level for tender design and initial load test can be assumed as _____* m below ground level.

A4. A protocol shall be signed between BHEL site and contractor regarding,

Strata at the founding depth

Installation criteria

Socketing depth

Density of bentonite before concreting

Slump of concrete.

Time interval between end of boring and start of concreting,

* Values shall be indicated separately depending upon subsoil strata of the site.

ANNEXURE-B

List of Equipments

S. No	Description	Capacity No.
1.	Piling Rigs	
2.	Chisel	3 T min 6 T max
3.	High pressure Mud Pumps	10 HP min 25 HP max
4.	Bentonite mixing plants	
5.	Concrete batching plant	
6.	Soil testing equipments	

Note:

1. The no. and capacity of the piling equipment varies for each work.
2. Additional equipments shall be mobilized if required as per the directions of the Engineer to match the work schedule at no extra cost to the Owner.

ANNEXURE-C

Bentonite suspension used for piling work shall satisfy the following requirements

a) Liquid limit of bentonite when tested in accordance with IS: 2720(Part V) shall be more than 300 percent and less than 450 percent.

b) Sand content of the bentonite powder shall not be greater than 7 percent.

c) Bentonite solution should be made by mixing it with fresh water using pump for circulation. The density of the freshly prepared bentonite suspension shall be between 1.034 and 1.10 gm/ml depending upon the pile dimensions and type of soil in which the pile is to be installed. However, the density of bentonite suspension after mixing with deleterious materials in the pilebore may be upto 1.25 gm/ml.

d) The Marsh viscosity when tested by a Marsh cone shall be between 30 to 60 seconds.

e) The differential free swell shall be more than 540 percent.

f) The pH value of the bentonite suspension shall be between 9 and 11.5.

ANNEXURE-D

PILE DATA

1. Reference No. Location (Co-ordinates) _____area.
2. Sequence of Piling
3. Pile diameter & Type
4. Working level (Platform level)
5. Cut off level (COL)
6. Actual length below COL
7. Pile termination level
8. Top of finished concrete level
9. Date and time of start and completion of boring.
10. Depth of Ground water table in the vicinity.
11. Type of soil at pile tip
12. Method of boring operation
13. Details of drilling mud as used:

    i) Freshly supplied mud
    Liquid limit -

    Sand content -

    Density -

    Marsh viscosity -

    Swelling index -

    pH value -

    ii) Contaminated mud
    Density -

    Sand content -

14. SPT* N values in soil (from the nearest bore hole).
+UCS** value in rock (from the nearest bore hole).

* Standard penetration Test
** Unconfined compression strength

15. Chiselling if any, from..….. m to ….... m

16. Date and time of start and completion of concreting.

17. Method of placing concrete

18. Concrete quantity
Actual

Theoretical

19. Ref. Number of test cubes

20. Grade and slump of concrete

21. Results of test cubes

22. Reinforcement details:

Main Reinforcement	Stirrups: Type
No._____	No._____
Dia. _____	Dia._____
Depth _____	Spacing _____

23. Any other information regarding obstructions, delay and other interruption to the sequence of work.

TABLE -1

FREQUENCY OF SAMPLING AND TESTING

SI. No	Type of material work	Nature of Test/ characteristics	Method of Test & frequency	No. of test	Acceptance Criteria
1.	Pilebore size a) diameter b) length		Physical measurement	each pile	as per specification
2.	Founding level	to establish socketing horizon/ and or founding level & upto depth 5m below founding level.	in separate borehole meant for the purpose a) SPT in soils/ weathered rock b) Core & UCS value of rock	1 borehole for 100-150 piles or group of 150 Sqm	Annexure - B
3.	Bentonite (Mud) properties. a) Basic properties of bentonite before use. b) Contaminated mud from pile bore bottom before concreting	Liquid Limit, Marsh Viscosity, Specific gravity, sand content, swelling index, pH value. Density, sand content	in lab in lab	As per Cl. 5.7 Each Pile	As per Annexure C As per annexure C
4.	Position and Alignment	-	Physical or any Approved method	Each Pile	As per Cl. 4.3
5.	Cleaning of pilebore	-	As per Cl. 5.8	Each Pile	Pilebore be free from bored material debris/sludge
6.	Reinforcement (R/F) Spacing of longitudinal R/F cover laps binding of laterals		Physical inspection and measurement	each cage	As per approved design
7.	Concrete a) Workability b) Cubes	 Slump cone test Compressive Strength test	 Each pile As per spec.	 As per Cl. 5.5 As per Cl. 5.5	 As per specification. As per IS: 456
8.	Materials like aggregate, sand etc.	As per technical specification for concrete and relevant IS codes			
9.	Pile head		Physical	each pile	

VOLUME: II B

SECTION - D

SUB-SECTION – D22

SITE LEVELLING & GRADING WORKS

SPECIFICATION NO. PE-TS-999-600-C022

Maharatna Company

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

C 0 N T E N T

CLAUSE NO.	DESCRIPTION	SHEET NO.
1.00.00	GENERAL	3
2.00.00	SCOPE	3
3.00.00	MATERIALS	4
4.00.00	QUALITY CONTROL	6
5.00.00	EXECUTION	6
6.00.00	RATES AND MEASUREMENTS	15

GENERAL TECHNICAL SPECIFICATION FOR SITE LEVELLING AND GRADING

1.00 GENERAL

This specification covers the works to be carried out for **"Site Levelling and Grading Works including Slope Protection"** etc. for the entire plant and associated areas. The specified formation level(s) shall be achieved either by excavation or by raising with controlled fill with excavated/borrowed earth as the case may be.

2.00 SCOPE

2.01 The scope include all works involved in levelling the site to the lines, grades, cross sections and dimensions as shown on the approved drawings and/or as directed by the engineer including site clearance, setting out, earth work in excavation, stacking, loading, transportation, unloading, dewatering, drainage, filling, watering, compaction, turfing on slopes (if required), lighting, disposal of residual/surplus earth etc. It also includes supplying and providing all labour, materials, supervision, services, equipments, tools and plants, testing and all incidental items of work not shown or specified but reasonably implied or necessary for the completion of the work etc.

2.02 All tools and plants, equipments and machineries to be used in this work shall be of standard quality and manufactured by reputed concerns conforming to Indian Standard (IS) codes or equivalent thereof.

2.03 Work to be provided by the Contractor

The works to be provided by the contractor unless specified otherwise shall include but not be limited to the following.

a) Supplying and providing all labour, supervision, services including as required under statutory labour regulations, materials, equipments, tools and plants, approaches, transportation etc. required for the completion of the work.

b) Preparation and submission of detailed scheme of all operations required for executing the work (material handling, placement, services, approaches etc.) to the engineer for approval.

c) Carrying out sampling and testing on fill materials/fills to assess the quality/moisture content/degree of compaction and submission of the test results whenever required by the engineer.

d) Design, construction and maintenance of Magazine of proper capacity for storage of explosives for blasting work and removal of the same after completion of the work etc.

2.04 Work to be provided by others

No work under this specification will be provided for by any agency other than the contractor unless specifically mentioned elsewhere in the contract.

2.05 Codes and Standards

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) codes unless specified otherwise.

IS: 1200 Methods of measurement of building and civil engineering works, Part-1: Earthwork

IS: 2720 Method of test for soils (Relevant parts)

IS: 3764 Excavation work- Code of safety

IS: 4081 Safety code for blasting and related drilling operations

IS: 4701 Code of practice for earthwork on canals

IS: 6922 Criteria for safety and design of structures subject to underground Blasts

In case of conflict between this specification and those (IS codes) referred to herein, the former shall prevail. In case any particular aspect of work is not covered specifically by the specification or/and by the IS codes, any other standard practice as may be specified by the engineer shall be followed.

2.06 Conformity with Designs

The contractor shall carry out the work as per the approved drawings, specification and as directed by the engineer.

3.00 MATERIALS

All materials required for the work shall be of best variety and approved by the engineer.

3.01 Materials for Excavation

For the purpose of identifying the various strata met during the course of excavation, the following classification is to be followed.

a) Soil

It includes all type of soil including laterite, moorum etc. with/without any percentage of kankar which can be excavated by normal means such as shovel, pick axe, crow bar, spade etc. and those which do not fall under **clause** 3.01 (b) and (c) etc.

b) Soft Rock

It includes the rocks (including weathered rock) which are removable by splitting with the help of crow bar, pick axe, wedges, pavement breakers, pneumatic tools, hammers or such implements etc. and not requiring blasting (for excavation) in the opinion of the engineer.

c) Hard Rock

It includes the rocks, which require blasting for excavation in the opinion of the engineer. Where blasting is prohibited for any reasons, the excavation shall be carried out by chiseling or any other method as approved by the engineer. The mere fact that the contractor resorts to blasting shall not classify the soft rock under hard rock.

However, the engineer's decision on the type of strata encountered during excavation shall be the final and binding on the contractor.

3.02 Materials for Filling

Any coarse grained or fine grained low plastic soil free from vegetation, roots, shingle, salts, organic matters, sod and any other harmful chemicals shall be used for filling. The contractor shall test the fill material to establish its suitability and submit the results to the engineer for approval. Fill material shall be got approved by the engineer. The following type of materials shall not be used for filling.

a) Materials from swamps, marshes and bogs
b) Expansive clays
c)Peat, logs, sod and perishable materials
d)Materials susceptible to combustion
e) Any material or industrial and domestic produce which will adversely affect other materials of work
f) Materials from prohibited areas

The earth available by cutting the high grounds within the project site and the materials (if) available from the road excavation or any other excavation under the same contract shall be used for filling depending upon its suitability as fill material. Filling with excavated rock (in the project site) shall be done only with the written permission of the engineer in the following manner. The boulders shall be broken into pieces not exceeding 150mm size in any direction and mixed with fine materials consisting of decomposed rock, moorum or any

approved earth to fill the voids as for as possible and the mixture shall then be used for filling. In case the earth required for filling is over and above the earth available from the compulsory excavations within the project area, then borrow areas for obtaining suitable fill material shall be arranged by the contractor himself from outside the plant boundary limits and all expenses including royalties, taxes, duties etc. shall be borne by him. He shall obtain and submit the necessary clearances/permissions from the concerned authorities to the engineer for the borrow areas/materials acquired.

4.00 QUALITY CONTROL

All works shall conform to the lines, levels, grades, cross sections and dimensions shown on the approved drawings and/or as directed by the engineer. The contractor shall establish and maintain quality control for the various aspects of the work, method of construction, materials and equipments used etc. The quality control operation shall include but not be limited to the following.

Sl. No.	Activity	Check
1	Lines, levels & grades	a) By periodic surveys b) By establishing markers, boards etc
2	Filling	(a) On quality of fill material (b) On moisture content of fill material (c) On degree of compaction achieved

5.00 EXECUTION

The contractor shall prepare and submit the detailed drawings/schemes for excavation and filling works as proposed to be executed by him showing the dimensions as per the construction drawings and specification adding his proposal of approaches, dewatering (if any), drainage and compaction etc. within 15 days of award of the contract to the engineer for approval.

5.01 Site Clearance

Before the commencement of earthwork, the entire area of cutting and filling shall be cleared of all trees, stumps, bushes, grasses, vegetation etc. with their roots, fences, logs, rubbish, water, slush etc. It is not necessary to remove all the soil containing fine hair like roots but only the rather heavy mats are to be removed. Cutting of trees shall include trees having girth of any size and removing roots upto a depth of 600mm below the existing ground level or 300mm below the formation level whichever is deeper. After the removal of roots of trees, the pot holes formed shall be filled with good earth in 250mm layers (loose thickness) and compacted unless otherwise directed by the engineer. The trees shall be cut in to suitable pieces as instructed by the engineer. Before earthwork is started, all the spoils, unserviceable materials and rubbish shall be burnt or removed and disposed off to the approved disposal area(s) as specified by the engineer. Useful materials, saleable timbers, fire

woods etc. shall be the property of owner and shall be stacked properly at the worksite in a manner as directed by the engineer.

5.02 Setting Out

On receiving the approval from the engineer with modifications and corrections if any, the contractor shall set out the work from the control points furnished by the engineer and fix permanent points and markers for the ease of periodic checking as the work proceeds. These permanent points and markers shall be fixed at the interval as prescribed by the engineer and shall be got checked and certified by the engineer after whom the contractor shall proceed with the work. It should be noted that this checking by the engineer prior to the start of the work will in no way relieve the contractor of his responsibility of carrying out the work to true lines, levels and grades as per the drawings and specification. If any errors are noticed in the contractor's work at any stage, the contractor at his own risk and cost shall rectify the same. The contractor shall take spot levels of the area (with respect to the bench mark/ available source as provided by the engineer) to be excavated or to be filled at an interval of not more than 10m or as directed by the engineer before starting any earth work and shall be submitted to the engineer for prior approval.

5.03 Excavation

Levelling by excavation shall be carried out where the existing ground levels are higher than the specified formation level. Excavation shall include removal of all materials whatever nature as may be and whether wet or dry shall be carried out exactly in accordance with the line, levels, grades and curves shown on the approved drawings and/or as directed by the engineer. All excavations shall be done to the minimum dimensions as required. The contractor shall obtain prior approval of the engineer for the method he proposes to adopt for excavation in different types of strata including dimensions, side slopes and dewatering if any, stacking or disposal etc. This approval however shall not in any way make the engineer responsible for any consequent loss or damage. The excavation must be carried out in the most expeditious and efficient manner. The work shall be carried out in a workmanlike manner without endangering the safety of nearby structures/services or works and without causing hindrance to any other activities in the area. **Prior to starting the excavation, the ground level at the location shall be checked jointly with the engineer.**
The rough excavation may be carried up to a maximum depth of 150mm above the final formation level. The balance shall be excavated with special care and the final surface shall be compacted by rolling with 6 passes of 8 to 10 tonne roller. If directed by the engineer, soft and undesirable spots shall be removed even below the final level. The extra excavation shall be filled up with good earth in 250mm layers (loose thickness) and compacted unless otherwise directed by the engineer. The contractor shall be paid for the extra excavation and filling at the appropriate items of work.

If the excavation is done to a depth greater than that shown on the drawing or as directed by the engineer due to the contractor's fault, the excess depth shall be

filled up to the required level with good earth in 250mm layers (loose thickness) and compacted unless otherwise directed by the engineer at the own risk and cost of the contractor.

Suitable slope in cutting as per the requirements and as directed by the engineer shall be adopted to withhold the face of earth. The contractor shall be held responsible for any damage to any part of the work caused by the collapse of the side of excavations.

5.03.01 Excavation in Hard Rock

Excavation in hard rock shall normally be done with blasting. In case where blasting is prohibited for any reasons, the excavation shall be carried out by chiselling or any other approved method as directed by the engineer. Personnel deployed for rock excavation shall be protected from all hazards such as loose rock/boulder rolling down and from general slips of excavated surfaces.

5.03.02 Blasting

a) General

Storage, handing and use of explosives shall be governed by the current explosive rules/regulations laid down by the Central and the State Governments. The contractor shall ensure that these rules/regulations are strictly adhere to. The following instructions are also to be strictly followed and the instructions wherever found in variance with the above said rules/regulations, the former (instructions) shall be superseded with the later (above said rules/regulations).

No child under the age of 16 and no person who is in a state of intoxication shall be allowed to enter the premises where explosives are stored nor they shall be allowed to handle the explosives. The contractor shall obtain licence from the District Authorities for undertaking the blasting work as well as for obtaining and storing the explosives as per Explosives Rules, 1940 corrected upto date. The contractor shall purchase the explosives, fuses, detonators etc only from a licensed dealer and shall be responsible for the safe custody and proper accounting of the explosive materials. The engineer or his authorized representative shall have the access to check the contractor's store of explosives and his accounts at any time. It is the full responsibility of the contractor to

transport the explosives as and when required for the work in a safe manner to the work spot.

Further, the engineer may issue modifications, alterations and new instructions to the contractor from time to time. The contractor shall comply with the same without these being made a cause for any extra claim.

b) Materials

All materials such as explosives, detonators, fuses, tamping materials etc proposed to be used in the blasting operation shall have the prior approval of the engineer. Only explosives of approved make and strength are to be used. The fuses known as instantaneous fuse must not be used. The issue of fuse with only one protective coat is prohibited. The fuse shall be sufficiently water resistant as to be unaffected when immersed in water for 30 minutes. The rate of burning of the fuse shall be uniform and shall be not less than 4 seconds per inch of length with 10% tolerance on either side. Before use, the fuse shall be inspected. Moist, damaged or broken ones shall be discarded. When the fuses are in stock for long, the rate of burning of fuses shall be tested before use. The detonators shall be capable of giving an effective blasting of the explosives. Moist and damaged detonators shall be discarded.

c) Storage of Explosives

The current Explosive Rules shall govern the storage of explosives. Explosives shall be stored in a clean, dry and well-ventilated magazine to be specially built for the purpose. Under no circumstances should a magazine be erected within 400m of the actual work site or any source of fire. The space surrounding the magazine shall be fenced and the ground inside shall be kept clear and free from trees, bushes etc. The admission to this fenced space shall be through a single gate only and no person shall be allowed without the permission of the officerin-charge. The clear space between the fence and the magazine shall not be less than 90m. The magazine shall be well drained. Two lightning conductors, one at each end shall be provided to the magazine. The lightning conductors shall be tested once in every year.

Explosives, fuses and detonators shall each be separately stored. Cases of explosives must be kept clear of the walls and floors for free circulation of air on all sides. Special care shall be taken to keep the floor free from any grains of explosives. Cases containing explosives shall not be opened inside the magazine and the explosives in open cases shall not be received into a magazine. Explosives which appear to be in a damaged or dangerous condition are not to be kept in any magazine but must be removed without delay to a safe distance and be destroyed.

Artificial light, matches, inflammable materials, oily cotton, rag waste and articles liable to spontaneous ignition shall not be allowed inside the magazine.

Illumination shall be obtained from an electric storage battery lantern. No smoking shall be allowed within 100m distance from any magazine.
Magazine shoes without nails shall be used while entering the magazine. The persons entering the magazine must put on the magazine shoes which shall be provided at the magazine for this purpose and should be careful

* not to put their feet on the clean floor unless the magazine shoes on.

* not to touch the magazine shoes on ground outside the clean floor.

* not to allow any dirt or grit to fall on the clean floor.

Persons with bare feet shall dip their feet in water before entering the magazine and then step directly from the tub to the clean floor. No person having article of steel or iron with/on him shall be allowed to enter the magazine. Workmen shall be examined before entering the magazine to check none of the prohibited articles are with them. A brush broom shall be kept in the lobby of the magazine for cleaning the magazine. Cleaning shall be done immediately after each occasion whenever the magazine is opened for receipt, delivery or inspection of the explosives.

The mallets, levers, wedges etc for opening the barrels or cases shall be of wood. The cases of explosives are to be carried by hand and shall not be rolled or dragged inside the magazine. Explosives which have been issued and returned to the magazine are to be issued first; otherwise those which have been stored long in the store are to be issued first. Neither the magazine shall be opened nor any person shall be allowed in the vicinity of the magazine during any dust storm or thunderstorm. All magazines shall be officially inspected at definite intervals and a record of such inspections shall be kept.

d) Carriage of Explosives

Detonators and explosives shall be transported separately to the blast site. Explosives shall be kept dry and away from direct rays of the sun, artificial lights, steam pipes or heated metal and other sources of heat. Before explosives are removed, each case or package shall be carefully examined to ascertain that it is properly closed and shows no sign of leakage.

No person except the driver shall be allowed to travel on the vehicle conveying explosives. No explosive shall be transported in a carriage or vessel unless all iron or steel therein the carriage or vessel which are likely to contact the package containing explosives are effectually covered with lead, leather, wood, cloth or any other suitable material. No light shall be carried on the vehicle carrying explosives and no operation connected with the loading, unloading and handling of explosives shall be conducted after sunset.

e) Use of Explosives

The contractor shall appoint an agent who shall personally superintend the firing and all operations connected therewith. The contractor shall satisfy himself that the person so appointed is fully acquainted with his responsibilities. Holes for charging the explosives shall be drilled with pneumatic drills and the drilling pattern shall be so planned that the rock pieces after blasting will be suitable for handling. The hole diameter shall be of such a size that the cartridges can easily pass down through them and any undue force is not required during charging. Charging operation shall be carried out by or under the personal supervision of the shot firer. Wrappings shall never be removed from the explosive cartridges. Only one cartridge at a time shall be inserted in a hole and wooden rods shall only be used for loading and stemming the shot

holes. Only such quantities of explosives as are required for a particular work shall be brought to the work site. Should any surplus remain when all the holes have been charged shall be carefully removed to a point at least 300m away from the firing point.

The authorized shot firer himself shall make all the connections. The shot firing cable shall not be dragged along the ground to avoid any damage to the insulation. The shot firing cable shall be tested each time for its continuity and possible short circuiting. The shot firer shall always carry the exploder handle with him until he is ready to fire shots. The number of shots fired at a time shall not exceed the permissible limits. Before any blasting is carried out it shall be ensured that all workmen, vehicles and equipment on the site are cleared from an area of minimum 300m radius from the firing point or as required by the statutory regulations at least 10 minutes before the time of firing by sounding a warning siren and the area shall be encircled by red flags.

The explosives shall be fired by means of an electric detonator placed inside the cartridge. For simultaneous firing of a number of charges, the electric detonators shall be connected with the exploder through the shot firing cable in a simple series circuit. Due precautions shall be taken to keep the firing circuit insulated from the ground, bare wires, rails, pipes or any other path of stray current etc. and keep the lead wires short circuited until it is ready to fire. Any kink in the detonator leading wire shall be avoided. For simultaneous firing of a large number of shot holes, use of cordtex may be done. An electric detonator attached to its side with adhesive tape shall initiate cordtex connecting wire or string. Blasting shall only be carried out at certain specified times to be agreed jointly by the contractor and the engineer.

At least five minutes after the blast has been fired in case of electric firing or as stipulated in the regulations, the authorized shot firer shall return to the blast area and inspect carefully the work and satisfy himself that all the charged holes have exploded. Cases of misfired unexploded charges shall be exploded by drilling a parallel fresh hole at a distance of not less than 600mm from the misfired hole and by exploding a new charge. The authorized shot firer shall be

present during the removal of debris as it may contain unexploded explosives near the misfired hole. The workmen shall not return to the site of firing until at least half an hour after firing.

Where blasting is to be carried out in proximity of other structures, controlled blasting by drilling shallow shot holes and proper muffling arrangements with steel plates loaded with sand bags etc. shall be used on top of the blast holes to prevent the rock fragments from causing any damage to the adjacent structures and other properties. Adequate safety precautions as per building byelaws, safety codes, statutory regulations etc. shall be taken during blasting operations.

5.03.04 Restrictions on Blasting

a) Blasting which may disturb or endanger the stability, safety or quality of the adjacent structures/foundations shall not be permitted.
b) Blasting within 200m of a permanent structure or construction work in progress shall not be permitted.
c) Progressive blasting shall be limited to two third of the total remaining depth of excavation.
d) No large scale blasting operations will be resorted to when the excavation reaches the last one meter and only small charge preferably black powder may be allowed so as not to shatter the parent rock.
e) The last blast shall not be more than 0.50 m in depth.
f) In rocky formations, at locations where specifically indicated or ordered in writing by the engineer, the use of explosives shall be discontinued and excavation shall be completed by chiseling or any other suitable method as approved by the engineer.

5.04 Sorting of Excavated Materials

The excavated material shall be carefully sorted for use in filling the areas in the project site by removing roots, grasses, organic matters and other objectionable materials and be sorted out into different types of materials for use and as directed by the engineer. The excavated material which is not considered fit for filling purpose shall be immediately removed and disposed at such a place and in such a manner as will be directed by the engineer. The material found unusable should be got approved by the engineer before actually disposing it off. The useful materials that cannot be used directly shall be heaped in separate area as stock piles. Stockpiles shall be of regular size as for as possible for ease of measurement. The materials heaped shall be utilized as and when required and as directed by the engineer. The cost of complete item of earthwork includes the cost of rehandling of the materials and temporarily heaped and reused.

5.05 Disposal of Surplus/ Waste Materials

Surplus and other waste materials shall be removed and disposed of from the construction site to the area demarcated by the engineer. No material shall be wasted unless approved by the engineer.

5.06 Earth Work in Filling

Levelling by raising with controlled fill of approved excavated/borrowed earth shall be carried out where the existing ground levels are lower than the specified formation level. After clearing site as per clause 5.01, the original ground shall be compacted by rolling subject to a minimum 6 passes of 8 to 10 tons' roller. The approved earth/fill material shall then be spread in horizontal layers' not exceeding 300mm in compacted thickness. Each layer shall be watered and thoroughly compacted with proper moisture content and such equipments as may be required to obtain a minimum of 95% of its maximum dry density as

determined by standard Proctor's test as per IS: 2720 part-VII or 85% of relative density as per IS:2720 part-XIV as specified. Moisture content of the fill material shall be controlled near optimum moisture content during compaction.

The fill material shall be tested for its optimum moisture content and maximum dry density as per IS: 2720, part-VII. Moisture content shall be checked at the source of supply in accordance with IS:2720 part- II and if found less than that required for proper compaction, the same shall be made good either at the source or after spreading the soil in loose thickness for compaction. In the latter case, water shall be sprinkled directly from the hose line or from the truck-mounted water tank etc. making due allowance for evaporation losses and the fill material be thoroughly mixed by means of harrows, rotary mixers or by any other suitable approved method until the layer is uniformly wet. **Flooding shall not be permitted for watering purpose under any circumstances.** If the material delivered is too wet, it shall then be dried by aeration and exposure to the sun till the moisture content is suitable for compaction. Should circumstances arise owing to wet weather the moisture content cannot be reduced to the required amount by the above procedure, the work on compaction shall be suspended. Clods or hard lumps of earth shall be broken to have a maximum size of 150mm when being placed in the layers before compaction. For each of the above tests on the fill material, one sample for every 10,000cu.m shall be tested. Additional samples shall be tested whenever there is a change of source or type of material.

Before start of filling, the contractor shall submit the engineer his proposal for the methodology to be adopted for compaction. The compaction equipments as approved by the engineer shall only be employed to compact the different type materials encountered during construction. If directed by the engineer, the contractor shall demonstrate the efficacy of the plant he intends to use by carrying out compaction trials. Moisture content of the fill material shall be controlled near optimum moisture content during compaction.

The compacted layer shall be tested for its dry density as per IS:2720**,** part-XXVIII or XXIX as directed by the engineer. Samples shall be taken at the rate of one sample for every 10,000sq.m area of each compacted layer. In addition random checks shall be carried out in compacted layers by means of Proctor needle penetration test. Contractor shall submit all the test results to the engineer immediately after completion of the tests. A sample shall be deemed to have passed the test when the dry density of the compacted fill is equal to or more than 95% of its maximum dry density. When field density measurements reveal any soft areas in the fills, further compaction shall be carried out as directed by the engineer. If in spite of that, the specified compaction is not achieved, the material in the soft areas shall be replaced with approved material compacted to the density requirements and satisfaction of the engineer.

Subsequent layers shall be placed only after the finished layer has been tested and accepted by the engineer.

Where the filling is to be done across low swampy ground that will not support the weight of trucks or other hauling equipments, the lower part of the fill shall be constructed by dumping successive loads in a uniformly distributed

layer of a thickness not greater than that necessary to support the hauling equipment while placing subsequent layers.

5.07 Dewatering and Drainage

It shall be ensured that the area to be excavated/filled shall be free from water. The contractor shall remove the water (if any) by pumping or by any other means as approved by the engineer. At all times, the surface of cutting/filling during execution shall be maintained at such a cross fall as will shed water and prevent ponding. All existing drains/channels (if any) in the work area shall be suitably diverted by the contractor before taking up any excavation or filling. These diversions shall be such that it shall ensure effective disposal of water without any accumulation or flooding within the project site and in adjoining areas.

5.08 Finishing Operations

Finishing operation shall include the work of shaping and dressing the excavated/filled ground to the required grades, levels, lines, side slopes, cross-sections
and dimensions as shown on the approved drawings or as directed by the engineer.

5.09 Turfing

Turfing shall be provided at the slopes and other locations as shown on the drawings or as directed by the engineer. The turf shall be of approved quality of grass. The sod shall consist of dense, well rooted growth of permanent and desirable grasses indigenous to the locality where it is to be used and shall be practically free from weeds or other undesirable matter. The grass on the sod shall have a length of approximately 50mm and the sod shall be free of any

debris. Thickness of the sod shall be as uniform as possible with 50 to 80mm of soil covering the grass roots depending on the nature of the sod so that all the dense root system of the grasses is retained in the sod strip. The sods shall be cut in rectangular strips of uniform width not less than about 300mm x 250mm size but not so large so that it is convenient to handle and transport without damage.

The area to be sodded shall be previously constructed to the required slope and cross section. Prior to placing the sods, the slopes shall be **roughned** and wetted in order to have a satisfactory bond. The strips of sod shall be laid in close contact with each other and be tamped firmly in place so as to fill and close the joints between them. The turfing so laid shall be well watered and protected until final acceptance.

5.10 Approaches

The contractor shall provide proper approaches for workmen and inspection.

5.11 Lighting

Full scale lighting is to be provided if night work is permitted or directed by the engineer. If no night work is in progress, red warning lights should be provided at the edges of excavations and fills.

6.00 RATES AND MEASUREMENTS

6.01 Rates

a) The item of work in the schedule of quantities describe the work very briefly. The various items of the schedule of quantities shall be read in conjunction with the corresponding sections in the technical specification including amendments and additions if any. For each item in the schedule of quantities, the bidder's rate shall include all the activities covered in the description of the items as well as for all necessary operations in detail as described in the technical specification.

b) No claims shall be entertained if the details shown on the released for construction drawings differ in any way from those shown on the tender drawings.

c) The unit rate quoted shall include minor details which are obviously and fairly intended and which may not have been included in these documents but are essential for the satisfactory completion of the work.

d) The bidder's quoted rate shall be inclusive of supplying and providing all labour, men, materials, equipments, tools and plants, supervision, services, approaches, schemes etc.

6.02 Measurements

Method of measurements are specified in the proceeding sections. Where not so specified, the latest version of IS:1200, Part-1 shall be applicable.

a) The length, breadth and depth shall be measured correct to the nearest centimeter if measurements are taken by tape. Rounding of numerical shall be as per relevant IS Codes. If the measurements are taken with staff and level, the levels shall be recorded correct to 5mm. The area and volume shall be worked out in square meter and cubic meter correct to the nearest of two decimal places.

b) For earth work in excavation, the ground levels shall be taken before and after completion of the work in the actually excavated area. The quantity of earth work in cutting shall be computed from these levels in cubic meter.

c) Where soft rock and hard rock are mixed, the measurement shall be done as follows. The two types of rock shall be stacked separately and measured in

stacks. The net quantity of each type of rock shall be so arrived by applying a deduction of 50% for looseness/voids in the stacks. If the sum of net quantity of the two types of rock so arrived exceeds the total quantity of excavation then the quantity of each type of rock shall be worked out from the total quantity (from excavation) in the ratio of net quantities in stack measurements of the two types of rock. If stacking is not feasible, the method as suggested by the engineer shall be followed.

d) Where soil, soft rock and hard rock are mixed, the measurement shall be done as follows. The soft and hard rock shall be removed from the excavated material and stacked separately and measured in stacks. The net quantity of each type of rock shall be so arrived by applying a deduction of 50% for looseness/voids in stacks. The difference between the entire excavation and the sum of the quantities of soft and hard rocks so arrived shall be taken as soil.

e) For earth work in filling, the actual measurements of fill shall be calculated by taking levels of the original ground before start of the work but after site clearance and after compaction of fills. The quantity of earth work in filling shall be computed from these levels in cubic meter.

f) For turfing, the measurement shall be made on the finished work in square meter.

VOLUME – II B

SECTION – D

SUB SECTION – D23

ANTI-TERMITE TREATMENT

SPECIFICATION NO. PE-TS-999-600-C023

Maharatna Company

Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida (U.P.)-201301

TABLE OF CONTENTS

CLAUSE NO.	DESCRIPTION	PAGE NO.
1.00.00	SCOPE	3
2.00.00	EXECUTION	3
3.00.00	ACCEPTANCE CRITERIA	4
4.00.00	RATES	4
5.00.00	METHOD OF MEASUREMENT	4
6.00.00	I.S. CODES	5

TECHNICAL SPECIFICATION FOR ANTI-TERMITE TREATMENT

1.00.00 SCOPE

The scope of work is to set up a chemical barrier against attack by subterranean termites while the building is under construction.

2.00.00 EXECUTION

2.01.00 General

All work shall in general be executed as specified in IS: 6313 Part II-1981 and as per approved specification of the agency having special know-how for the job.

All necessary work to ensure uniform distribution and proper penetration of treatment of treating solution shall be done according to the instruction of the Engineer.

Soil treatment shall not be done when it is raining or when the soil is wet with rain or subsoil water. Once formed, the treated soil barrier shall not be disturbed.

2.02.00 Chemicals and Rate of Application

Any of the following chemicals (conforming to relevant Indian Standards) in water emulsion shall be applied by pressure pumps, uniformly over the area treated.

Chemicals		Concentration by Weight, Percentage
Chlorpyrifos Emulsifiable (IS 8944 - 1978)	:	1.0
Heptachlor Emulsifiable Concentrate (IS: 6439 - 1978)	:	0.5
Chlordane Emulsifiable Concentrate (IS: 2682 - 1984)	:	1.0

2.02.01 Treatment of Column Pits, Wall Trenches and Basement Excavations

Foundations, basements etc. may either be fully enveloped by the chemical barrier or the treatment may start 500 mm below ground level. The bottom surface and sides of excavation (upto a height of about 300 mm) for column

pits, walls trenches and basements shall be treated with chemicals at the rate of 5 litres / M^2 of surface area. Backfills around columns, walls etc. shall be treated at the rate of 7.5 litres / M^2 of the vertical surface.

Chemical treatment shall be done in stages following the compaction of earth in layers. The treatment shall be carried out after the ramming operation is done by rodding the earth at 150 mm centres close to the wall surface and spraying the chemicals in the specified dose.

2.02.02 Treatment of Top Surface of Plinth Filling

Holes 50 mm to 75 mm deep at 150 mm centres both ways shall be made with crowbars on the surface of compacted plinth fill. Chemical emulsion at the rate of 5 litres / M^2 of surface shall be applied prior to laying soling or sub-grade. Special care shall be taken to maintain continuity of the chemical barrier at the junction of vertical and horizontal surfaces.

2.02.03 Treatment of Soil Surrounding Pipes, Wastes and Conduits

Special care shall be taken at the points where pipes and conduits enter the building and the soil shall be treated for a distance of 150 mm and a depth of 75 mm at the point where they enter the building.

2.02.04 Treatment of Expansion Joints

These shall receive special attention and shall be treated in a manner approved by the Engineer.

2.02.05 Treatment at Junction of the Wall and the Floor

Special care shall be taken to establish continuity of the vertical chemical barrier on inner wall surfaces from ground level up to the level of the filled earth surface.
A small channel 30 x 30 mm shall be made at all the junctions of wall and columns with the floor. Rod holes made in the channel up to the ground level 150 mm apart and the chemical emulsion poured along the channel at the rate of 7.5 litres per square meter of the vertical wall or column surface. The soil should be tamped back into place after this operation.

3.00.00 ACCEPTANCE CRITERIA

The Contractor shall give a 10-year service guarantee in writing supplemented by a separate and unilateral guarantee from the specialised agency for the job to keep the building free of termites for the specified period.

4.00.00 RATES

Rates shall be of complete work per unit area as stated in the Schedule.

5.00.00 METHOD OF MEASUREMENT

Complete work of anti-termite treatment shall be measured for plinth area treated.

This includes treatment, to foundations, walls, trenches, basements, plinth, burried pipes, conduits etc. The extended portions of foundation and like beyond plinth limit shall be the part of complete work.

6.00.00 I.S. CODE

Relevant code applicable for this Specification.

IS: 6313 (Part-II) 1981 : Code of Practice of Anti-Termite Measures in Buildings
Pre-constructional chemical treatment measures.

GUIDELINES NO. AERB/NRF/SG/IS-1 (Rev. 1)

GUIDELINES NO. AERB/NRF/SG/IS-1 (Rev. 1)

GOVERNMENT OF INDIA

AERB SAFETY GUIDELINES

CONTROL OF WORKS

ATOMIC ENERGY REGULATORY BOARD

AERB SAFETY GUIDELINES NO. AERB/NRF/SG/IS-1 (Rev. 1)

CONTROL OF WORKS

Atomic Energy Regulatory Board
Mumbai-400 094
India

December 2011

Price

Order for this guidelines should be addressed to:

The Administrative Officer
Atomic Energy Regulatory Board
Niyamak Bhavan
Anushaktinagar
Mumbai-400 094
India

FOREWORD

Activities concerning establishment and utilisation of nuclear facilities and use of radioactive sources are to be carried out in India in accordance with the provisions of the Atomic Energy Act, 1962. In pursuance of the objective of ensuring safety of members of the public and occupational workers as well as protection of environment, the Atomic Energy Regulatory Board (AERB) has been entrusted with the responsibility of laying down safety standards and enforcing rules and regulations for such activities. The Board, therefore, has undertaken a programme of developing safety standards, safety codes and related guides and manuals for the purpose. While some of the documents cover aspects such as siting, design, construction, operation, quality assurance and decommissioning of nuclear and radiation facilities, other documents cover regulatory aspects of these facilities.

Safety codes and safety standards are formulated on the basis of nationally and internationally accepted safety criteria for design, construction and operation of specific equipment, structures, systems and components of nuclear and radiation facilities. Safety codes establish the objectives and set requirements that shall be fulfilled to provide adequate assurance for safety. Safety guides and guidelines elaborate various requirements and furnish approaches for their implementation. Safety manuals deal with specific topics and contain detailed scientific and technical information on the subject. These documents are prepared by experts in the relevant fields and are extensively reviewed by advisory committees of the Board before they are published. The documents are revised when necessary, in the light of experience and feedback from users as well as new developments in the field.

Construction work is a labor-intensive industrial activity with large number of unskilled and migratory workforce under various contracts ranging from a mega package contract to a small work contract. Accidents during construction work are of major concern because of the high severity of injuries. The analysis of the accidents at construction sites indicates that 'fall from height' type of accidents are significantly higher than the other types of accidents. AERB safety guide titled 'Works Contract' (AERB/SG/IS-1) was issued in 1991 to emphasise safety requirements and ensure their implementation in execution of contracts. In view of the continual development of construction technologies and the need for enhancement of indutrial safety in DAE units, inputs from AERB discussion meets on the subject, safety and occupational health professionals of DAE, AERB Fatal accident Assessment Committee, and directives on industrial safety issued by Chairman, AERB, the need for revision of the safety guide was felt.

This revised 'safety guidelines' is effective from the date of issue and supersedes the earlier guide on the subject. Part-A of the revised safety guidelines highlights safety requirements by 'Facilities' and Part-B highlights the requirements on safe execution of jobs by 'Contractors'. The facility management shall be strictly liable as a principal

employer for ensuring the compliance with the safety requirements by the contractors as laid down in Part-B. It should be noted that Part-A and Part-B should be read in conjunction, as the requirements are complementary to each other. However the 'Facility' may issue the Part-B along with the tender documents. The requirements spelt out in this 'safety guidelines' are in addition to the statutory requirements such as Factories Act 1948, Atomic Energy (Factories) Rules, 1996 and other applicable statutory requirements.

Consistent with the accepted practice, 'shall' and 'should' are generally used to distinguish between a firm requirement and a desirable option respectively. Appendices are an integral part of the document, whereas bibliography are included to provide further information on the subject that might be helpful to the user.

Specialists in the field drawn from the Atomic Energy Regulatory Board, the Bhabha Atomic Research Centre and the Nuclear Power Corporation of India Limited and other consultants have prepared this 'safety guidelines' document. It has been reviewed by the Advisory Committee on Industrial and Fire Safety (ACIFS).

AERB wishes to thank all individuals and organisations who have prepared and reviewed the document and helped in its finalisation. The list of persons, who have participated in this task, along with their affiliations, is included for information.



(S. S. Bajaj)
Chairman, AERB

SPECIAL DEFINITIONS
(Specific for the Present 'Guidelines')

Approval

A type of written consent issued by the designated authority.

Construction Agency/Contractor

An individual or organisation rendering services of design/construction/fabrication/ installation/repair/inspection/review/maintenance/supplying items by the deployment of workers at site.

Dangerous Manufacturing Processes or Operations

The manufacturing processes or operations as specified under Rule 88 of the Atomic Energy (Factories) Rules, 1996.

Engineer-in-charge

A person designated by the Facility to act as an overall in-charge of work.

Facility

Any Unit of the Department of Atomic Energy awarding the contract.

Head, Industrial Safety

The chief safety officer or the overall in charge of Industrial Safety Section of the facility.

Line Managers

The person who has the field level managerial and supervisory control on the concerned work.

Safety Related Deficiency

The unsafe acts/unsafe practices/unsafe conditions in the work area, which have potential to cause injury/accident resulting into undesirable consequences to human beings or damage to the equipment/property/environment.

CONTENTS

FOREWORD i

SPECIAL DEFINITIONS iii

PART - A

1. INTRODUCTION 1
   - 1.1 General 1
   - 1.2 Objective 1
   - 1.3 Scope 2

2. SAFETY ORGANISATION 3
   - 2.1 General 3
   - 2.2 Organisational Structure for Safety Management 3

3. SAFETY MANAGEMENT 6
   - 3.1 General 6
   - 3.2 Safety Policy 7
   - 3.3 Safety Plan 7
   - 3.4 Roles, Responsibility and Authority 9
   - 3.5 Design and Engineering 10
   - 3.6 Construction Planning 11
   - 3.7 Safety Communication 12
   - 3.8 Safety Monitoring Programme 12
   - 3.9 Training/Orientation 17
   - 3.10 Permit to Work System 18
   - 3.11 Job Hazard Analysis 19
   - 3.12 Reward and Reprimand 21

4. WORK SPECIFIC SAFETY MEASURES 23
   - 4.1 General 23
   - 4.2 Rock Blasting 24
   - 4.3 Excavation, Trenching and Earth Removal 25
   - 4.4 Safe Means of Access/Platforms 28
   - 4.5 Work at Height 29
   - 4.6 Electrical Safety 30
   - 4.7 Material Handling, Lifting Machines and Tackles 31
   - 4.8 Welding and Gas Cutting 33
   - 4.9 Rotary Cutters/Grinders 34
   - 4.10 Concrete Mixing Equipment 34
   - 4.11 Painting 36

4.12 Demolition 37
4.13 Traffic 37
4.14 Work in Radiation Area 38
4.15 Work in and around Water Bodies 38
4.16 Fire Safety 39
4.17 Environmental Safety 40
4.18 Public Protection 40
4.19 Safety of Visitors 40
4.20 Housekeeping 40
4.21 Other Statutory Provisions 41

5. PERSONAL PROTECTIVE EQUIPMENT 42
4.1 General 42
4.2 Personal Protective Equipment (PPE) 42

6. MEDICAL MANAGEMENT 44
6.1 General 44
6.2 Medical Facilities 44
6.3 Medical Management of Serious Injuries 44

APPENDIX - A APPLICATION FOR HEIGHT PASS 46

APPENDIX - B APPLICATION FOR TEMPORARY POWER SUPPLY AT SITE AND USE OF ELECTRICITY AT WORKSITE DURING CONSTRUCTION 50

APPENDIX - C CHECKLIST FOR OPERATION OF READY MIX CONCRETE(RMC) PLANT 57

PART - B

7. INTRODUCTION 63
7.1 General 63
7.2 Objective 63
7.3 Scope 64

8. SAFETY ORGANISATION 65
8.1 General 65
8.2 Organisational Structure for Safety Management 65

9. SAFETY MANAGEMENT 68
9.1 General 68
9.2 Safety Policy 68

9.3 Safety Plan 68
9.4 Roles, Responsibility and Authority 70
9.5 Design and Engineering 71
9.6 Construction Planning 72
9.7 Safety Communication 72
9.8 Safety Monitoring Programme 73
9.9 Training/Orientation 76
9.10 Permit to Work System 77
9.11 Job Hazard Analysis 78
9.12 Reward 81

10. WORK SPECIFIC SAFETY MEASURES 82
10.1 General 82
10.2 Rock Blasting 83
10.3 Excavation, Trenching and Earth Removal 84
10.4 Safe Means of Access/Platforms 87
10.5 Work at Height 89
10.6 Electrical Safety 89
10.7 Material Handling, Lifting Machines and Tackles 90
10.8 Welding and Gas Cutting 92
10.9 Rotary Cutters/Grinders 93
10.10 Concrete Mixing Equipment 93
10.11 Painting 95
10.12 Demolition 96
10.13 Traffic 96
10.14 Work in Radiation Area 97
10.15 Work in and Around Water Bodies 97
10.16 Fire Safety 98
10.17 Environmental Safety 99
10.18 Public Protection 99
10.19 Safety of Visitors 99
10.20 Housekeeping 99
10.21 Other Statutory Provisions 100

11. PERSONAL PROTECTIVE EQUIPMENT 101
11.1 General 101
11.2 Personal Protective Equipment (PPE) 101

12. MEDICAL MANAGEMENT 103
12.1 General 103
12.2 Medical Facilities 103
12.3 Medical Management of Serious Injuries 104

APPENDIX - D APPLICATION FOR HEIGHT PASS 104

APPENDIX - E APPLICATION FOR TEMPORARY POWER SUPPLY AT SITE AND USE OF ELECTRICITY AT WORKSITE DURING CONSTRUCTION 109

BIBLIOGRAPHY 115

LIST OF PARTICIPANTS 117

EXPERT COMMITTEE FOR REVIEW OF GUIDELINES ON CONTROL OF WORKS 117

ADVISORY COMMITTEE ON INDUSTRAIL AND FIRE SAFETY (ACIFS) 118

PROVISIONAL LIST OF REGULATROY DOCUMENTS ON INDUSTRAIL AND FIRE SAFETY 119

PART-A

CONTROL OF WORKS
(FACILITIES)

1. INTRODUCTION

1.1 General

Department of Atomic Energy (DAE) through its constituent units execute various site works either by their own manpower or by manpower of various outside agencies. The nature of contracts with outside agencies can be works contracts, engineering procurement contracts, minor fabrication contracts etc. These site works involve entire gamut of conventional industrial activities like excavation, rock blasting, earth handling, construction, material handling, fabrication, installation, operation, maintenance etc. of nuclear or conventional plants/facilities. This is a challenging responsibility for the facility due to the complexity of problems like quality of workforce (which may be unskilled, illiterate, migratory) available for labor-intensive jobs, lack of coordination among agencies at site, lack of safety awareness among concerned authorities, time schedules of project etc. As primary employer of the workforce (facility or contractor) at site, it is the responsibility of the facility management to ensure health and safety of personnel engaged for the work. Any accidental injury or loss of life is detrimental to the facility as well as the society. This 'guidelines' covers the safety organisation and the safety management system requirements in sections two and three. The work specific safety precautions are covered in section four. The requirements relating to personal protective equipment and medical management are covered in sections five and six.

1.2 Objective

This 'guidelines' has a basic framework of industrial safety organisation, safety management systems, safe work procedures to maintain a safe working environment for all personnel and to prevent any unsafe condition/act endangering the life of personnel engaged for industrial activities. The major objectives of this 'guidelines' are:

(i) To create awareness among workers about industrial hazards and safe working procedures.

(ii) To lay down safe work procedures and systems to be followed for different type of industrial activities

(iii) To establish a robust safety management system.

(iv) To protect the health and ensure the safety of the workers from industrial activities.

1.3 Scope

This 'guidelines' is essential for implementation and assurance of conventional safety in areas such as industrial, chemical, electrical, fire, environmental and is applicable for all works taken up by the facility as well as contracted works like engineering procurement contract, minor fabrication contract etc. Where the execution of work is envisaged in radiation controlled area or involves handling and fabrication of any nuclear material, additional precautions noted in relevant AERB safety documents on radiation protection shall also be applicable.

2. SAFETY ORGANISATION

2.1 General

(a) Construction projects have significant health and safety hazards, which need to be managed systematically since the project inception stage to achieve adverse incident free completion. A well-defined safety organisation helps in effective implementation of safety management systems and ensures health and safety of workers.

(b) The safety organisation should assure the management that all the provisions of relevant Acts and Rules are conformed to.

(c) Safety organisation should comply with all the requirements such as safety surveillance, safety training, safety enforcement measures, safety audit etc. related to all works to fulfill the overall safety requirements of this 'guidelines'.

(d) Safety functionaries should be exclusively assigned with the work related to protection of health and safety of workers.

(e) Safety organisation should directly report to the Project Director / Project Manager.

(f) IS: 18001: 2007 gives detailed requirements of health and safety management system requirements. IS: 15793 gives requirements of good practices for managing environment, occupational health and safety legal compliance. This 'guidelines' prescribes requirements in addition to IS: 18001: 2007 and IS: 15793 and gives guidelines on implementing these specific to a construction project.

(g) The requirements prescribed in various central and state regulations including *Building and other Construction Workers (Regulation of Employment and Conditions of Service) Act*, 1996 and rules framed thereunder with respect to managing health and safety in construction projects, shall be complied with.

2.2 Organisational Structure for Safety Management

(a) Organisational structure depends on the construction project. As an example, a typical organisational chart for safety management in a construction project would be as given in Fig 1.



Fig -1 : Typical Organisation Chart

(b) The organisational structure for Health and Safety will vary from project to project. On large and medium projects, it may be necessary to have a separate safety team for each sub-contractor who in turn shall report to safety team of the main construction agency.

(c) The qualification, experience and the minimum number of safety professionals to be deployed should be as per the following table:

TABLE-1 : QUALIFICATION, EXPERIENCE & NUMBER OF SAFETY PROFESSIONALS FOR CONSTRUCTION PROJECTS

Category of safety person	Mandatory requirement	Qualification
Head, industrial safety	One at each site/unit	Degree in engineering/technology and diploma in industrial safety with minimum three years of experience
Safety officer	One in each shift (minimum) up to 1000 workers. If number of workers in a shift (including contractor's workers) exceeds 1000, additionally one safety officer should be deployed for every 1000 workers or part thereof.	Degree in engineering/technology and diploma in industrial safety with minimum two years of experience or Diploma in engineering with diploma in industrial safety with minimum 6 years experience or A recognised degree in physics or chemistry and has practical experience of working in a factory in a supervisory capacity for a period of not less than 5 years.

Category of safety person	Mandatory requirement	Qualification
	One in each shift (minimum) up	Not withstanding the provision contained in the above criteria any person who (i) possesses a recognised degree or diploma in engineering or technology and has had experience of not less than five years in a department of the central or state government which deals with the administration of the Factories Act, 1948 or the Dock Workers (safety, health and welfare) Act, 1986 (54 of 1986) or (ii) Possesses a recognised degree or diploma in engineering or technology and has had experience of not less than 5 years, fulltime on training, education, consultancy, or research in the field of accident prevention in industry or in any institution, shall also be eligible for appointment as a safety officer: Provided that competent authority may, subject to such condition as it may specify, grant exemption from the requirement of this sub rule if in its opinion, a suitable person possessing the necessary qualification and experience is not available for appointment.
Safety supervisor	to 500 workers. If number of persons working in a shift (including the contractors' workers) exceeds 500, additionally one safety supervisor should be deployed for every 500 workers or part thereof.	Diploma in engineering and diploma in industrial safety

3. SAFETY MANAGEMENT

3.1 General

(a) Pre-construction stage activities of the project shall be required to be reviewed before the project management processes are initiated for the construction stage. While the project documents and proposals are reviewed for the adequacy of health and safety measures, it is essential to ascertain timeframes and budgets relating to health and safety measures, including extent of management systems proposed to be employed during construction.

(b) A concise safety management system of the facility shall be established from the pre-construction stage itself. The tender documents of the project shall clearly communicate the health and safety requirements of the project to the prospective contractors. These may include:

(i) Project specific objectives and targets

(ii) Project specific health and safety requirements (technical as well as management systems)

(iii) Requirement of posting safety officers

(iv) Coordination among owner/client, project manager, consultants and facility

(v) Welfare facilities at the project for workmen

(vi) Reward system for good health and safety performance

(vii) Penalty system for non-compliances, violation and adverse incidents

(viii) Health and safety monitoring measures

(ix) Health and safety reports to be submitted and frequency.

(c) The construction agencies (contractors) should be asked to submit a project specific health and safety plan (construction safety management plan) proposing the methodology for managing health and safety and their capability in completing the project in a safe manner.

(d) The proposed construction safety management plans of the construction agencies and their past health and safety performance shall be considered as one of the criteria during pre-qualification and selection of construction agencies.

3.2 Safety Policy

(a) The facility and the construction agency jointly or separately shall have a written statement prescribing the health and safety policy of the organisation. The health and safety policy conveys the management commitment and intent of the organisation towards health and safety, its organisation and arrangements to ensure that the set objectives are met. It also provides a framework for establishing, maintaining and periodically reviewing health and safety objectives and targets.

(b) Health and safety policy shall meet the requirements of *Building and other Construction Workers (Regulation of Employment and Conditions of Service) Act*, 1996 and IS 18001.

(c) The policy shall be communicated to all stakeholders through display and other means. The policy shall be displayed in local language(s) which may be understood by majority of the workmen.

3.3 Safety Plan

(a) A project specific health and safety plan shall be developed by the facility. On approval by the project director, the project health and safety plan shall be reference document for implementation, control and monitoring of health and safety aspects of the project by the facility.

(b) Project health and safety plan shall describe how the project specific health and safety objectives and targets shall be achieved. It shall define the road map for achieving the standards that an organisation lays down for itself so that efforts can be coordinated, synergised and monitored.

(c) Health and safety plan shall explain the means of establishing a positive health and safety culture at the project site. Health and safety plan shall identify and enumerate the control measures to mitigate the risks to the project completion arising out of health and safety issues so that the project is allowed to proceed without interruption and executed as per schedule.

Salient aspects that may be covered in the project health and safety plan are:

(i) Project specific health and safety objectives, targets and programmes in line with health and safety policy

(ii) Hazard identification and risk assessment

(iii) Meeting legal and other requirements

(iv) Health and safety organisation

(v) Resources, roles, responsibility and authority

(vi) General health and safety rules

(vii) Health and safety requirements to be followed by sub-contractors

(viii) Operation control procedure

(ix) Activities requiring work permit system and its procedure

(x) Safe handling of chemicals, explosives, gas cylinders, electrical equipment etc.

(xi) Access control of employees

(xii) Safety of visitors

(xiii) Management of critical activities such as work at height, material handling and working with plant and machinery

(xiv) Ensuring the competency and awareness of the workmen

(xv) Fire prevention and fire fighting plan

(xvi) Emergency preparedness and response plan

(xvii) Traffic management plan

(xviii) Training matrix

(xix) Personal protective equipment matrix

(xx) Health and safety performance monitoring measures such as inspection and audit

(xxi) Incident reporting and investigation procedure

(xxii) Proactive and reactive indicators of health and safety

(xxiii) Reward and reprimand for health and safety performance

(xxiv) Checklist and formats

(xxv) Health monitoring plan for employees/workers enposed to hazardus job.

(d) The risk control measures identified shall meet the provisions of *Building and other Construction Workers (Regulation of Employment and Conditions of Service) Act*, 1996, other legislations and provisions of various safety related standards.

(e) Procedures shall be established for timely recording and reporting of information required for continual improvement of health and safety performance. Internal reporting procedures shall cover:

(i) Incident reporting

(ii) Non-conformance reporting

(iii) He alth and safety performance reporting

(iv) Hazard identification reporting

External reporting shall cover

(i) Statutory reporting requirements

The recording of reporting of health and safety performance shall be clearly documented in the project health and safety plan.

3.4 Roles, Responsibility and Authority

(a) Project manager shall define, document and communicate the roles, responsibilities and authorities of all personnel who manage, perform and verify activities having an effect on health and safety risks. It shall also include contractors and visitors.

(b) Ultimate responsibility for health and safety shall rest with top management of the respective organisation.

(c) The line management personnel who are responsible for execution of activities are directly responsible for health and safety in the work under their control.

(d) Health and safety group and health and safety officers are responsible for guiding the top management on health and safety issues and facilitating the implementation of health and safety in the project site. For duties and responsibilities of health and safety officers refer Atomic Energy (Factories) Rules-1996.

(e) Health and safety officers shall administratively report to the project manager and functionally report to the senior health and safety representative of the organisation.

(f) Health and safety officers and health and safety group shall be empowered by the project manager for stopping any unsafe practices which are of imminent danger to employees. Health and safety group shall directly report to no less than the head of the project.

(g) Health and safety supervisors shall be engaged to assist the health and safety officers in performing their duties.

(h) Management shall provide adequate resources essential to effectively manage the health and safety requirements of the project. The resources shall include human resources, organisational infrastructure, technology and financial resources.

3.5 Design and Engineering

(a) Design drawings, construction methodology and plans shall be reviewed to determine whether any additional risks may arise during the construction due to the features in the design or methodology.

Attention shall be paid to:

(i) Providing permanent hooks and loops for tying safety slings of workers

(ii) Providing holes or such arrangements to the structure to which safe working platforms and safety nets can be connected

(iii) Significant risks from construction materials, which cannot be avoided in the design

(iv) Laying permanent slings, grab rails/bars to be used by the workers

(v) Permanent provision for attaching railings

(vi) Provision for alternative access to the trapped or distressed workers

(vii) Provision for communication

(viii) Design facilitating barricading of the area around work site without causing hindrance to building functional activities

(ix) Durability of such safety related permanent design integrated elements

(x) Other safety practices required for the type of woks involved.

(b) Analysis of design and integration of safety measures, as described above, should be undertaken as value engineering through multi-stakeholder consultation, necessarily involving designers, owner/ client, operation/maintenance management and construction agency.

(c) While need for special work methodology and enabling infrastructure is considered to make conditions safe for construction, attention shall also be drawn to the safety during maintenance operations (including inspections which may be necessary before project commissioning as well as maintenance).

(d) It shall also be ascertained whether it would be feasible (within the time and cost considerations) to erect necessary temporary enabling infrastructure. If, in the due assessment by the project manager, it is established that the design, as proposed, would continue to be unsafe during construction and maintenance operations unless special

enabling infrastructure is created and work procedures specifically drawn, the design shall be reviewed.

3.6 Construction Planning

(a) Prior to the start of construction work, detailed planning shall be carried out which may include:

(i) Identifying aspects of design that have bearing on health and safety during construction stage.

(ii) While scheduling the various activities of the construction, allowing adequate time to carry work in accordance with health and safety requirements.

(iii) Reviewing the proposed work method of various activities, identifying health and safety hazards of activities in the project and assessment of the risk level.

(iv) When the risk level is unacceptable, taking additional control measures including revision of the work methodology so that identified risk is at ALARP (as low as reasonably practicable) level.

(v) Planning and establishing the facilities for implementation of health and safety such as workmen training facility, health centre for medical check-up and first aid, access control of employees, etc.

(vi) Ensuring that the temporary establishments at project site such as site offices, workmen camps, toilets, canteens and rest sheds, etc. are created meeting the requirements of the relevant statutes and standards.

(b) Facility shall ensure that the construction agency has understood the challenges and has planned to meet the project specific health and safety requirement through appropriate competencies.

(c) Health and safety measures need proper coordination by the construction agency and such efforts of the construction agency shall be reviewed, monitored and appropriately guided by the facility.

(d) In respect of sub-contractors, project manager of the construction agency shall ensure that the sub-contractors meet the health and safety requirements of the project. Health and safety control and monitoring shall be established specific to the needs of the project.

(e) Past health and safety performance and capability of contractors to complete the job safely shall be given due consideration during selection of contractors. The project specific health and safety

requirements shall be clearly communicated to the contractors and a commitment obtained from them on meeting the requirements.

3.7 Safety Communication

(a) Procedures shall be established to communicate significant hazards and risks to and from employees and other interested parties. The health and safety hazards and risks may be communicated in the following ways:

(i) Sharing of accidents case studies which occurred in the project site as well in other similar projects

(ii) Health and safety posters and displays

(iii) Health and safety campaigns and competition involving the employees

(iv) Sharing of results of the audits, inspections and other monitoring systems

(v) Establishing a system for collecting feedback on health and safety from employees and other interested parties

(vi) Tool box meeting

(vii) Safety signage.

(b) Health and safety communications addressed to workmen shall preferably be in local language(s) understandable by majority of the workmen.

(c) The owner/client, consultant and construction agency shall jointly endeavour to promote a positive health and safety culture at the project. Top management of the organisations should exhibit a visible management commitment and felt leadership towards health and safety. This shall be achieved by participating in health and safety programmes such as,

(i) Project health and safety committee meeting

(ii) Health and safety walk down

(iii) Including health and safety in all performance review meetings

(iv) Exhibiting a safe behaviour while at site.

(d) The top management should clearly communicate that it considers safety as core value and it shall not allow it to get compromised. Such messages when it reaches down the level in the organisation enable to create a positive health and safety culture.

3.8 Safety Monitoring Programme

(a) The objective of the safety surveillance programme should address

assurance of effective implementation of safety measures in execution of works. Following surveillance programme should be in place at sites. The safety organisation should monitor, maintain record and follow up for corrective actions.

(b) The surveillance programme should consist of identification of safety related deficiencies and status of corrections thereof, the implementation of protective measures, the safe work practices, human behavior etc.

(c) Specific surveillance should be ensured with respect to testing of equipment, portable power tools, electrical equipment and tools, hand tools, surveillance of material handling equipment, transport equipment, earth moving equipment, gas cylinders etc. to comply with various statutory requirements.

(d) Surveillance on safety awareness and training compliance including induction training, on the job training and refresher training, job specific pre-job briefing, job hazard analysis, etc. as per facility's guidelines should be ensured.

(e) Safety related deficiencies should be detected by any employee of the facility and communicated by the safety officer to their line managers with a record and corrective measures monitored and recorded. The engineer-in-charge should specifically ensure this. These should be informed to Head, Industrial Safety within the stipulated time period as per the category of safety related deficiencies (SRDs).

(f) Systematic record of safety related deficiencies (SRDs) attended and pending should be made by the facility and other executing agencies.

(g) Head, Industrial Safety should verify periodically, at least once in 15 days that all safety related work permits issued are executed and recorded.

(h) The health and safety performance monitoring and measurement procedures shall provide for:

(i) Both qualitative and quantitative measures appropriate to the project

(ii) Monitoring the extent to which project health and safety objectives are met

(iii) Proactive measures of compliance that measures compliance with health and safety plan, operational control procedures and legislation

(iv) Reactive measures of performance to monitor accidents, ill health, near misses and non-conformances

(v) Monitoring dangerous occurrances

(vi) Fire occurrances

(vii) First aid injuries.

(i) Health and safety audit is a systematic and independent examination to estimate if planned arrangements and activities are effectively fulfilling organisation's health and safety policy, plan and objectives. Its purpose is to find out:

(i) Whether the organisation has adequate procedures for identifying specific health and safety requirements

(ii) Whether such laid down procedures are followed and specific health and safety responsibilities are understood

(iii) Whether health and safety policies and risk assessment procedures identify the measures needed to avoid risks to employees and other interested parties

(iv) Whether the company has adequate procedures for devising, reviewing its health and safety standards

(v) Whether the company's health and safety standard identifies measurable targets

(vi) Whether the company has established adequate procedures for planning, implementing, controlling, monitoring and reviewing the health and safety measures.

(j) Project health and safety management audits provide the method for monitoring and controlling health and safety activities and procedures throughout the life of the project. Audits can be internal or external. Internal audit can be conducted by the persons from the same organisation who are not directly connected with the work site to be audited. The external audits are performed through external professional experts.

(k) Health and safety inspections shall be preferably conducted by a team of the concerned engineer, health and safety officer and area in-charge. Project manager and other senior personnel shall also join in some of the health and safety inspections.

(l) The type of inspections that shall be carried out and the frequency shall be decided during the planning stage and documented in the project health and safety plan. The health and safety inspections should include:

(i) General site health and safety inspection

(ii) Electrical safety inspection

(iii) Plant and machinery inspection

(iv) Health and hygiene inspection

(v) Scaffolding safety inspection

(vi) Portable tools and tackles

(vii) Lifting tools and tackles

(viii) Fire equipment inspection

(ix) Illumination level and noise level monitoring

(m) Project health and safety committee shall be constituted with project manager as the chairman, health and safety head as the secretary and representatives from various groups including workmen representatives as the members. The constitution and functioning of the committee shall meet the provisions of *Building and other Construction Workers (Regulation of Employment and Conditions of Service) Act*, 1996.

(n) This committee shall review the status of implementation of project health and safety plan, health and safety objectives and targets. Health and safety indicators and findings of the walk down by the committee members shall also be discussed and action plan derived.

(o) Status of health and safety implementation shall be measured and monitored by several proactive indicators which include the following:

(i) Compliance level of project health and safety plan

(ii) Compliance level of health and safety observations with in the target date

(iii) Implementation status of training plan

(iv) Implementation status of corrective and preventive actions

(v) Compliance level of pre-employment medical checks and periodic medical checkups

(vi) Compliance level of legal and other requirements

(vii) Percentage of activities for which detailed project specific risk assessment is conducted.

(p) Procedures shall be established to report, investigate and analyze incidents. The procedures shall involve:

(i) Members of the incident investigation team

(ii) Agencies to be reported in case of incidents

(iii) Time period within which incidents need to be reported

(iv) Methodology for investigation and determining the root cause of accidents.

These procedures shall form a part of the project health and safety plan and monitored on a regular basis for its effectiveness.

(q) All incidents including near miss cases, accidents and dangerous occurrences shall be thoroughly investigated, direct and root causes determined and corrective action planned. Incidents should be analysed covering the following ways to prepare and implement an effective prevention plan:

(i) Body part injured

(ii) Age of the victims

(iii) Time of accidents

(iv) Causes of accidents

(v) Nature of injury.

For detailed guidelines on analysis of incidents and computation of injury rate refer IS 3786.

(r) The following reactive health and safety indicators should be used to measure and monitor the health and safety performance of the project site:

(i) Number of near miss cases

(ii) Number of first aid cases

(iii) Lost time injury frequency rate

(iv) Lost time injury severity rate.

(s) The health and safety performance of contractors shall be monitored on a regular basis and necessary directive and support shall be given to achieve the set health and safety objectives and targets.

(t) All accidents leading to property damage/fatal accidents/personnel injuries/near miss and dangerous occurrence should be reported to the engineer-in-charge immediately.

(u) All 'near-miss' accidents should also be recorded/reported and investigated and recommendations arising out should be implemented on priority.

(v) Facility/Contractor should also submit a monthly statement of accidents to engineer-in-charge/head, industrial safety by 4th of the following month showing details of accident, nature of injury including disability, days lost, treatment required, etc. and the extent of property damage.

3.9 Training/Orientation

(a) It shall be ensured that all employees are competent to perform the assigned work safely on the basis of appropriate education, training or experience. The competency requirements of different categories of employees shall be mapped and procedures shall be implemented to ensure that those deployed meet the competence requirements.

(b) Training needs of the different category of employees shall be identified at the beginning of the project and a training matrix and plan shall be prepared for implementation.

(c) The objective of health and safety training shall be to equip the employee with necessary knowledge and skill to perform the work assigned to him in a safe manner, to foster continual improvement and to imbibe safety culture.

(d) Preferably, the training should be carried out away from the working place of the participants to ensure focused attention on the training for both trainer as well as trainees.

(e) After completion of training due procedure shall be followed for obtaining the feedback from the participants on the effectiveness of the training. Effectiveness of training imparted shall be monitored for continual improvement and necessary corrections in implementation.

(f) The training/orientation programme should be implemented to meet the mandatory requirements. [Rule 43(2) (m) of the Atomic Energy (Factories) Rules 1996]. The training should be phased as follows:

(g) Induction cum orientation training should include the overall safety aspects of the work and give a general overview of the various hazards, the particular activities and the do's and don'ts. As a part of training, workers should also be given demonstrations on use of

personal protective equipment, first aid, fire-fighting equipment, fire mock drills, other emergency preparedness etc.

(h) The line manager along with the safety representative should conduct pre-job briefing on day-to-day basis prior to specific hazardous jobs. This will make the workers aware of the hazards and the precautions to be taken.

(i) Refresher training should be imparted to each worker at least once in a year.

(j) A training schedule should be prepared by the facility for implementation.

(k) Records of training, demonstration and pep talk should be maintained.

3.10 Permit to Work System

(a) Activities requiring permit to work shall be decided before starting the construction and shall be suitably documented in the project health and safety plan. Some of the activities which should require permit to work are:

(i) Excavation

(ii) Entry into confined spaces

(iii) Electrical work (HV/LV)

(iv) Opening manholes, covers and grills

(v) Blasting operation

(vi) Hot work

(vii) Work on plant and machinery & other power driven equipment

(viii) Working at height

(ix) Working at night

(b) The facility should establish a permit to work system for any other hazardous activity, which it feels necessary to be controlled administratively for safe execution.

(c) Record of safety work permit should be maintained in a systematic manner. All the safety conditions and requirements stipulated in the safety work permit should be ensured strictly.

(d) Occupier should ensure that only authorized personnel are deployed for hazardous works/jobs (Refer item 3.11 for hazardous job) and provide facilities for the same.

3.11 Job Hazard Analysis

(a) It should be ensured that a safe work procedure exists for all the hazardous jobs as mentioned hereunder and the requirements of the safety procedures are ensured at the work sites. Job hazard analysis (JHA) should form a part of such safe work procedures. A checklist based on JHA should be prepared. This checklist should be crosschecked by the line managers and verified by safety officer.

Typical list of jobs requiring job hazard analysis (this list is illustrative only and not exhaustive) is as follows:

(i) Excavation

- (a) Blasting including under water blasting
- (b) Earth and stone removal/backfilling/dumping of earth/stones
- (c) Any excavation more than 1.8 m depth.

(ii) Work at height (working beyond 3.5 meters above ground)

- (a) Erection and dismantling of scaffolding, platforms, shuttering/ de-shuttering work
- (b) Dome work, rod bending, construction of chimney and cooling towers
- (c) Working on tower crane.

(iii) Materials and material handling

(A) Critical equipment handling e.g.

- (a) Calandria
- (b) Steam generators
- (c) Turbine generator components
- (d) Diesel generator set
- (e) Generator stator
- (f) End shields
- (g) Fuelling machines components
- (h) Heat transport pumps etc.

(B) Hazardous chemical handling e.g.

- (a) Acids and alkalis
- (b) Chlorine

(c) Hydrazine

(d) Morpholine

(e) Freon

(f) Ammonia

(g) LPG

(C) Movement of heavy material by crane

(D) Movement of tractor trolley on slopes

(E) Manual lifting of heavy material to height

(F) Erection of heavy machinery, equipment.

(iv) Electrical connection

(a) Field connection for electrical installation

(b) Installation of lighting fixtures

(c) Charging of electrical system

(i) Charging of transformer, switch yard, switch gears

(ii) Working near high voltage lines

(iii) Use of portable electrical tools.

(v) Equipment/structural erection work

(a) Material handling

(b) Loading and unloading

(c) Transportation of material from one place to other

(d) Steel fabrication and erection

(e) Cleaning and maintenance of batching plant equipment.

(vi) Finishing/painting work

(a) Painting at height

(b) Painting in confined space.

(vii) Other specific work

(a) Work with pneumatic tools/compressed air

(b) Work on pressure vessels/lines

(c) Work in the vicinity of steam lines

(d) Work in high enthalpy area

(e) Work in high noise area

(f) Work in confined space including tunnels & trenches

(g) Work in isolated area (away from main site)

(h) Radiography work

(i) Work related to welding, gas cutting, grinding

(j) Working near conveyor, rotating machine

(k) Leak detection testing.

3.12 Reward and Reprimand

(a) It is important to acknowledge and encourage good health and safety performance and suitably reprimand repeated violations, non-conformances and poor health and safety performances. Project specific reward and reprimand system shall be prepared as a part of the project health and safety plan.

(b) To motivate the employees and organisation to work safely measures can be implemented based on the suitability. Selection and rewarding for the following categories may be considered on regular basis:

(i) Safest workmen

(ii) Safest supervisor

(iii) Safest area

(iv) Safest contractor, etc.

(v) Contractors and employees may be rewarded when the project achieves significant million man-hours without any lost time injury.

(c) Unsatisfactory health and safety performance in the form of repeated violations, frequent adverse incidents and accidents shall be dealt with firmly. Depending on the seriousness of the violation the following options shall be considered:

(i) Issue of violation memorandum and obtaining written commitment for safe working

(ii) Suspension or termination of the employee from the present work

(iii) Suspension or termination of contract in case of construction agency

(iv) Imposition of penalty to the construction agency.

(d) When penalties are imposed due records shall be maintained in a transparent manner. The main contractor shall be responsible wherever he deploys sub-contractor/petty contractor/piece rate contractor. The funds thus accrued may be spent in the form of rewarding employees for their sincere efforts towards improving the health and safety performance.

4. WORK SPECIFIC SAFETY SAFETY MEASURES

4.1 General

(a) The occupier should ensure that safety precautions are taken during the execution of awarded work and work areas are maintained safe at all times. At the end of each shift and at all times when the work is suspended, it should be ensured that the work area is left safe in such a way that no materials and equipment that can cause damage to existing property, personal injury or interfere with the other works of the project or station are left in an unsafe manner.

(b) The occupier should ensure to provide and maintain all lights, guards, fencing, warning signs, caution boards and other safety measures and provide for vigilance as and when necessary for the protection of workers and for the safety of others. The caution boards should also have appropriate symbols.

(c) Adequate lighting facilities such as floodlights, hand lights and area lighting should be provided at the site of work, storage area of materials and equipment and temporary access roads within the working area.

(d) All works should be planned so as to avoid interference with other facilities, works of other contractors or sub-contractors at the site. In case of any interference, necessary coordination should be ensured for safe and smooth working.

(e) It should be ensured that the instructions given by the safety officer or his designated nominee regarding safety precautions, protective measures, housekeeping requirements, etc. are complied with. The safety officer with due intimation to engineer-in-charge should have the right to stop the work, if in his opinion, proceeding with the work will lead to an unsafe and dangerous condition. Engineer-in-charge should arrange to get the unsafe condition rectified and/ or provide appropriate protective equipment.

(f) Engineer-in-charge should ensure that each job with a hazard whether small or big is intimated to the safety officer of the facility well before it is taken up.

(g) The facility should be fully responsible for non-compliance of any of the safety measures or requirements, implications, injuries, fatalities, dangerous occurrences and compensation arising out of such situations or incidents.

(h) Maximum duty hours of an individual should be as per the Factories Act 1948 or its latest amendment.

(i) Illumination levels should be as per the statutory requirements.

4.2 Rock Blasting

(a) All blasting operations should be carried out on the basis of procedures approved by Head, industrial safety and engineer-in-charge. All works in this connection should be carried out as per BIS specification/code (IS 4081: 1986. Title:- Safety code for blasting and related drilling operations (First Revision)). Barricades, warning signs etc. should be placed on the roads/open area.

(b) Blasting permit should be obtained from Head, industrial safety at least one day before the blasting operation and precautions mentioned there in shall be ensured by the engineer-in-charge before blasting operation.

(c) The blaster should have a licence from competent authority under Explosive Rules, 1983 for blasting work. It should also be ensured that he knows about the risks involved.

(d) Blasting should be done under the supervision of competent engineer/ supervisor.

(e) Blasting in the open site should only be carried out during fixed hours every day/fixed day in the week between sunrise and sunset. Residents of adjacent area should be informed in advance about the blasting schedule.

(f) No blasting should be undertaken during thunderstorm.

(g) Necessary precaution should be taken to ensure the stability/integrity/ safety of the adjacent structure by limiting the peak particle velocity.

(h) No loose material, such as tools, drilling equipment, etc. should be left on the surface to be blasted. Proper muffling arrangement of the blasting area should be ensured to avoid flying of blasted material.

(i) Authorised blaster should personally ensure that all the personnel/ equipment has been removed from the blasting area before the blasting operations.

(j) Blasting area should be free of detonating gas, inflammable objects, sparking or damaged wiring system, stray currents and static electricity.

(k) All electrical lines in blasting area should be de-energised.

(l) Entry of unauthorised personnel should be prevented by displaying warning signs.

(m) In case of misfire, no person should be allowed to approach the blasting site unless it is inspected and cleared by a competent engineer/supervisor.

(n) Explosives and blasting material should be stored only in clean, dry, well-ventilated, suitably constructed bullet/ magazine which should be fire resistant and securely locked. Stock book should be kept accurate and maintained. Licence should be obtained for storage of explosive as per the Explosives Act, 1884.

(o) Blasting caps, electric blasting caps or primers and detonators should not be stored in the same box, container or room with other explosives.

(p) Precautions against lightening should be provided in accordance with Indian Electricity Rules, 1956 (amended in 2000).

(q) The explosives should be transported in specially designed vehicles bearing a special sign or inscription entitled 'DANGER - EXPLOSIVES'. Also detonators separated from other explosive should be transported in a separate compartment.

4.3 Excavation, Trenching and Earth Removal

(a) Before taking up excavation work, necessary permission should be obtained from the engineer-in-charge with reference to existing underground services.

(b) The engineer-in-charge of the works should exercise full care to ensure that no damage is caused by him or his workmen, during the operation/excavation etc., to the existing water supply, sewerages, power or telecommunication lines or any other services or works. He should provide and erect before construction, substantial barricades, guardrails, and warning signs around the work area. He should also furnish, place and maintain adequate warning lights, display board, signals etc., as required.

(c) All trenches 1.2 m or more in depth should at all times be supplied with at least one ladder for every 30 m along the trench. Ladders shall extend from bottom of the trench to at least 1m above the surface of the ground.

(d) The sides of the trench/pit in soil, which are 1.2 m or more in depth should be stepped back to give suitable slope (angle of repose) or securely held by timber bracing or appropriate shoring/support, to avoid the danger of soil slides from collapsing. The excavated material should not be placed within 1.5 m or half of the depth of the pit whichever is more from edges of the trench/pit. Cutting should be done from top to bottom. Under no circumstances mining or under-cutting should be done.

(e) Workers should not be exposed to the danger of being buried by excavated material or collapse of shoring. Measures to prevent dislodgment of loose or unstable earth, rock or other material from falling into the excavation by proper shoring shall be ensured.

(f) The stability and safety of the excavation, adjacent structures, services and other works should be ensured.

(g) All excavated area should be fenced off by suitable railing and installation of caution board to warn the persons from slipping or/ falling into the excavation pit/ mound.

(h) All excavated areas shall have an illumination level of at least 20 lux for night work and a red danger light shall be displayed at prominent place near the excavation site to warn approaching traffic and men.

(i) For removal of earth from an earth mound/excavated heap a written permission should be obtained from the engineer-in-charge of the work. As far as practical, earth should be removed mechanically. Wherever manual removal of earth is involved, earth should be removed from the top by maintaining a slope equal to the angle of re-pose of the earth. Such work should be constantly supervised to ensure that no under-cutting is done and to ensure that no person is trapped.

(j) Dumping of excavated soil should be done at a specified area under proper supervision with respect to signaling, illumination and safety clearance.

(k) It should be ensured that at a construction site of a building or other construction work, every vehicle or earth moving equipment is equipped with a) silencers, b) tail lights, c) power and hand brakes, d) reversing alarm e) search light for forward and backward movement, which are required for the safe operation of such vehicle or earth moving equipment and f) the cab of the vehicle or earth moving equipment is kept at least one meter from the adjacent face of a ground being excavated. g) indicator etc.

(l) It should be ensured that when a crane or shovel is traveling, the boom of such crane or shovel is in the direction of such travel and the bucket or scoop attached to such crane or shovel is raised and without load, except when it is traveling downhill.

(m) Before loading or unloading power trucks or trailers attached to tractors, the brakes should be applied and if vehicle is on a sloping ground, the wheels should be blocked. Handcart should not be used for the transfer of construction/erection materials in the construction

area. However if the exigency demands urgent transfer of light materials a small handcart may be permitted with the prior approval of the engineer-in-charge.

(n) It should be ensured that at a construction site of a building or other construction work:

(i) All transport or earth moving equipment and vehicles are inspected at least once in a week by responsible persons and in case any defect is noticed in such equipment or vehicle, it is immediately taken out of service.

(ii) Safe gangways are provided for to and fro movement of building workers engaged in loading and unloading of lorries, trucks, trailers and wagons.

(iii) All earth moving equipment, vehicles or other transport equipment be operated only by such persons who are adequately trained and possess such skills as required for safe operation of vehicles or other transport equipment.

(iv) Trucks and other equipment are not loaded beyond their safe carrying capacity, which should be clearly marked on such trucks and other equipment.

(v) No unauthorised person rides the transport equipment employed in such work.

(o) It should be ensured at a construction site of a building or other construction work that:

(i) A shovel or an excavator whether operated by steam or electric or by internal combustion used for such work is constructed, installed, operated, tested and examined as required under any law for the time being in force and the relevant national standards.

(ii) Buckets or grabs of power shovels are propped to restrict the movement of such bucket or grabs while being repaired or while the teeth of such bucket or grabs are being changed.

(p) It should be ensured at a construction site of a building or other construction work that:

(i) An operator of a bulldozer before leaving – applies the brakes, lowers the blade and ripper and puts the shift lever into neutral.

(ii) A bulldozer is parked on level ground at the close of the work.

(iii) The blade of a bulldozer is kept low when such bulldozer is moving uphill.

(iv) Bulldozer blades are not used as brakes except in an emergency.

(q) It should be ensured at a construction site of a building or other construction work that:

(i) A tractor and a scraper are joined safely at the time of its operation

(ii) The scraper bowls are propped while blades of such scraper are being replaced.

(iii) A scraper moving downhill is driven in low gear.

(r) It should be ensured at a construction site of a building or other construction work that:

(i) Before a road roller is used on the ground, such ground is examined for its bearing capacity and general safety, especially at the edges of slopes such as embankments on such grounds.

(ii) A roller is not moved down hill with the engine out of gear.

(s) Vehicle carrying excavated material should have proper cover over the driver's cabin.

4.4 Safe Means of Access/Platforms

(a) Adequate safe means of access and exit should be provided for all work places, at all elevations.

(b) Suitable scaffolds should be provided for workmen for all works that cannot be done safely from the ground, or from solid platform except such short duration work that can be done safely from ladders. Bamboo/wooden scaffolding should not be permitted.

(c) Where the platform for working is more than 3.5 m above ground, the width of the platform should be minimum 1 m.

(d) Ladder should be of rigid construction having sufficient strength for the intended loads. Wooden/bamboo/rope ladders should not be permitted. All ladders should be maintained in good condition. The ladders should be fixed to the ground or rigid platforms. An additional person should be engaged for holding the ladder, if ladder is not securely fixed. Ladder shall be extended from floor to at least one meter above the platform.

(e) A portable ladder should be given an inclination not steeper than 1 in 4 (1 horizontal and 4 vertical). Ladders should not be used for climbing while carrying materials in hands. While climbing both the hands should be free.

(f) Any working platform on scaffolding or staging more than 3.5 m above the ground or floor should have a guard rail attached, bolted, braced at least 1 m high above the floor or platform of such scaffolding or staging along with mid-rail.

(g) The planks used for any working platform should not project beyond the end supports to a distance exceeding four times the thickness of the planks used. The planks should be rigidly fixed at both ends to prevent sliding, slipping or tilting. The thickness of the planks should be adequate to take load of men and materials and should not collapse. Plywood or packing wood should not be used as planks.

(h) The guardrail should extend along the entire exposed length of the scaffolding with only such opening as may be necessary for the delivery of materials. Standard railing should have posts not more than 2 m apart and an intermediate rail halfway between the floor or platform of the scaffolding and the top rail. Such scaffolding or staging should be so fastened as to prevent it from swaying from the building or structure. Scaffolding and ladder should conform to IS 3696 (Part 1): 1987 and (Part II): 1996.

(i) Working platforms of scaffolds should have toe boards at least 15 cm in height to prevent materials from falling down.

(j) A sketch of the scaffolding proposed to be used should be prepared and approval by the engineer-in-charge obtained prior to start of erection of scaffolding. All scaffolds should be examined by engineer-in-charge before use.

(k) Working platform, gangways and stairways should be so constructed that they should not sag unduly or unequally and if the height of the platform or gangway or stairway is more than 3.5 m above ground level or floor level. They should have adequate width for easy movement of persons and materials and should be suitably guarded.

(l) No single portable ladder should be used for access to a height of more than 4.5 m. For ladders up to 3m in length the width between styles (side bars)/width in the ladder should in no case be less than 300 mm. For longer ladders this width should be increased by at least 20 mm for each additional meter of length. Step/rungs spacing should be uniform and should not exceed 300 mm. Portable ladder should be used only for access to work place. In case work place is higher than 4.5 meters, pre-fabricated steel staircase should be used.

4.5 Work at Height

(a) Person to work at height should be medically fit and should have height pass issued by safety section. (Appendix A Part A, B and C). Safety training should be imparted before working at height.

(b) Safety work-permit system for working at height should be obtained from industrial safety section.

(c) At elevated places, secure access and foothold should be provided. Adequate and safe means of access and exit should be provided at all work places for all elevations. Means of access may be portable or fixed ladder, ramp or a stairway. The use of crosses, braces or framework, as a means of access to the working platform should not be permitted.

(d) Linear movement at height should be reduced to minimum. In case of such movement provision for anchoring the safety belt should be made.

(e) Where barricades cannot be installed, a safety net of adequate strength should be installed close to the level at which there is a danger of fall of personnel/fall of objects.

(f) In case where 'work at height' is on asbestos roof, crawling board, roof ladder should be used to walk across the asbestos roof.

4.6 Electrical Safety

(a) All electrical installations shall comply with the appropriate statutory requirements given below and shall be subject to approval of the electrical engineer and safety officer.

(i) The Electricity Act, 2003

(ii) The Indian Electricity Rules 1956 (as amended in 2000)

(iii) The National Electricity Code 2008

(iv) Atomic Energy (Factories) Rules, 1996

(v) Other relevant rules of statutory bodies and power supply authority

(vi) Relevant standards of BIS

In addition to the above statutory provisions, the clauses indicated in this document shall also be complied.

(b) It shall be the responsibility of the user seeking temporary power supply to indicate in writing, if any of the clauses (requirements noted in above regulations and in this document) are conflicting with each other and for which the user cannot decide the course of action regarding safe installation, commissioning, operation, maintenance and decommissioning of the electrical installations.

(c) The electrical engineer and safety officer of the facility providing temporary power supply shall interpret the concerned conflicting clauses and approve in writing the safe course of action.

(d) The Application Form-1 (Form-1A, 1B and 1C) as mentioned in Appendix-B should be submitted by the user for getting the temporary power supply.

(e) After installation of temporary electrical panels, wiring works by the user, certificates as per Form-1D (Appendix-B) should be submitted to the provider.

(f) Certificate of safety officer and authorisation of electrical engineer for energisation of temporary power supply should be filled as per Form-1E (Appendix-B).

4.7 Material Handling and Lifting Machines and Tackles

(a) It should be made compulsory to supervise jobs like lifting/placing/loading/unloading/carrying/transporting etc. of heavy material by qualified supervisor having knowledge about hazards involved and precautions to be taken for such job.

(b) The line managers should ensure that the material handling equipment used is adequate to handle the load.

(c) Manual pulling of heavy equipment and trolley loaded with heavy material is not to be permitted.

(d) Stacking and handling of heavy materials should be done on a firm ground to prevent settlement.

(e) No lifting machine and no chain, rope or lifting tackle, except a fiber rope or fiber rope sling, shall be taken into use in any factory for the first time in that factory unless it has been tested and all parts have been thoroughly examined by a competent person. A certificate of such a test and examination specifying the safe working load or loads and signed by the person making the test and the examination has been obtained and is kept available for inspection.

(f) Use of lifting machines and tackles should conform to relevant BIS requirements [IS 13367 (Part 1): 1992 Reaffirmed 2003, IS 4573: 1982 (Reaffirmed 2000) and IS 13834 (Part 1): 1994 Reaffirmed 2003 etc. The accessories and the attachments, anchorages and supports etc. should be ensured in healthy conditions by regular inspections at defined frequencies.

(g) Every rope used in hoisting or lowering materials or as a means of suspension should be of good quality and adequate strength and free

from any defect. This should be ensured by regular inspection as per IS 2762: 1982- Specification for wire rope slings and sling legs (first revision).

(h) Every crane operator or lifting appliance operator should be authorised. No person under the age of 18 years should be in charge of any hoisting machine or give signal to an operator of such machine.

(i) In case of every lifting machine (and of every chain, ring, hook, shackle, swivel and pulley block used in hoisting or as a means of suspension) the safe working load should be ascertained and clearly marked. In case of a lifting machine having a variable safe working load, each safe working load and the conditions under which it is applicable should be clearly indicated. No part of any machine should be loaded beyond the safe working load except for the purpose of testing. This should be approved by the engineer-in-charge and head, industrial safety.

(j) In case of facilities machines, the safe working load should be notified by the engineer-in-charge. As regards the contractor's machines, the contractor should declare the safe working load of the machine to the engineer-in-charge whenever he brings any machinery to site of work and get it verified by the engineer-in-charge, supported by a valid test certificate by the competent person.

(k) Thorough inspection and load testing of lifting machines and tackles should be done in the presence of competent person at least once in every 12 months and records of such inspections and testing should be maintained.

(l) No mobile crane should be allowed to move under live high-tension power transmission line.

(m) While lifting loads, cranes should be located on level ground.

(n) A thorough load analysis should be carried out before using cranes in tandem.

(o) Motors, gear transmission, couplings, belts, chain drives and other moving parts of hoisting appliances should be provided with adequate safeguards. Hoisting appliances should be provided with such means, which will reduce the risk of any part of a suspended load becoming accidentally displaced or lowered.

(p) It should be ensured that the cabin of the lifting machine in outdoor service:

(i) is made of fire resistant material,

(ii) has a suitable seat, a footrest and protection from vibration,

(iii) affords the operator an adequate view of the area of operation,

(iv) affords the operator adequate protection against the weather, and

(v) is provided with fire extinguisher.

4.8 Welding and Gas Cutting

(a) Welding and gas cutting operations should be done by qualified and authorized persons only.

(b) Safety work permit should be obtained (wherever necessary like presence of flammable or combustible material etc.) before flame cutting/welding is taken up.

(c) Welding and gas cutting should not be carried out in places where flammable or combustible materials are kept and where there is danger of explosion due to presence of gaseous mixtures. In case the requirement cannot be avoided, specific approval and procedure should be ensured and adequate precautions should be taken.

(d) Welding and gas cutting equipment including hoses and cables should be maintained in good condition.

(e) Barriers should be erected to protect other persons from harmful rays from the work. When welding or gas cutting is done in elevated positions, precautions should be taken to prevent sparks or hot metal falling below on persons or combustible materials.

(f) Suitable type of protective clothing consisting of fire resistant gauntlet gloves, leggings, boots and aprons should be provided to workers as protection from heat and hot metal splashes. Face shields with filter glasses of appropriate shade should be worn.

(g) Adequate ventilation should be provided while welding, brazing and cutting the metals like zinc, brass, bronze, galvanised or lead coated material.

(h) Welding and gas cutting on drums, barrels, tanks or other containers should be taken up only after ascertaining that they have been emptied, cleaned thoroughly and made free of flammable material.

(i) Fire safety measures should be available as required near the location of welding/cutting operations.

(j) Flash back arrestor should be provided with gas cutting and gas welding sets.

(k) For electric (Arc) welding the following additional safety precautions should be taken:

(i) When electrical welding is undertaken the return lead of welding machine should be directly connected to the job invariably.

(ii) Provision must be in place in electric welding machine to prevent physical contact with live parts.

(iii) The welding cables and power cables should be routed separately to avoid entanglement.

(iv) The electric welding set should have suitable earth connections. There should be an electrical isolation device in the input power supply side on the welding machine.

(l) Double gauges should be used for all gas cylinders used for cutting/ welding. Pressure gauges/regulators should be in healthy condition.

4.9 Rotary Cutters/Grinders

(a) All portable cutter/grinders should be provided with the wheel guard in position.

(b) Grinding wheels of specified diameter only should be used on all grinders in order to limit the prescribed peripheral speed.

(c) In pedestal grinder, the gap between tool rest and grinding wheel should be maintained less than 3 mm.

(d) Goggle/face shield should be used during grinding operation.

(e) No grinding wheel should be used after its expiry date.

(f) Ear muff/ear plug should be used during the welding/cutting jobs.

(g) Portable appliances, which are powered by single phase AC supply, shall be provided with three-core cable and three pin plug, otherwise the whole body should be double insulated.

(h) Safety work permit should be obtained (wherever necessary like presence of flammable or combustible material etc.) before grinding is taken up.

(i) Fire safety measures should be available as required near the location of grinding operations.

4.10 Concrete Mixing Equipment

(a) Cement bags should be stacked on wooden planks in dry and leak proof area, 150 mm to 200 mm from the floor and 450 mm away

from walls. Height of the stack should not be more than 15 bags or 1.5 meters which ever is lower. Width of the stack should not be more than 4 bags or 3 meters. Lateral loading of the walls of the storage room by stacking should not be permitted. Stacking of the bags should not be used as a working platform.

(b) Shuttering and supporting structures should be of adequate strength and approved by engineer-in-charge. This should be ensured before concrete is poured.

(c) If the mixer has a charging skip the operator should ensure that the workmen are out of danger before the skip is lowered.

(d) Adequate walking platforms (as per the AERB directives) are to be provided in the reinforcement area to ensure safe walking for pouring concrete on the roof.

(e) When workmen are working/cleaning the inside of the drum of mixer, the power of the mixer should be switched off and "Do not operate" tag should be provided. The plant operation and cleaning of mixing pan should be carried out as per equipment supplier's instructions.

(f) Interlocks between the cover and the mixer rotor shall be established to ensure that the agitator does not start when the cover is in open condition.

(g) It should be ensured that moving parts of the elevators, hoists, screens, bunkers, chutes and grouting equipment used for concrete work and of other equipment used for storing and transporting of ingredients of concrete are securely fenced to avoid contact of workers with such moving parts.

(h) It should be ensured that screw conveyors used for cement, lime and other dusty material are completely enclosed.

(i) Workers engaged for handling bulk cement in a confined place should be provided with tight fitting goggle, approved respirators and protective clothing, which will fit snugly around the neck, wrist and ankles.

(j) The following should be ensured for every pipe carrying pumped concrete:

    (i) The scaffolding carrying a pipe for pumped concrete should be strong enough to support such pipe at a time when such pipe is filled with concrete or water or any other liquid and to bear safely all the building workers who may be on such scaffold at such time.

(ii) Securely anchored at its end point and each curve on it.

(iii) Provided with an air release valve near the top of such pipe; and securely attached to a pump nozzle by a bolted collar or other adequate means.

(k) The following should be ensured while using the electric vibrators in concreting work at a construction site of a building or other construction work such that:

(i) Such vibrators are earthed.

(ii) The leads of such vibrators are heavily insulated.

(iii) The current is switched off when such vibrators are not in use.

(l) For obtaining a clearance for first pour of concrete and regular operation of ready mix concrete (RMC) plant, checklist given in Appendix-C shall be submitted to AERB along with the application for clearance.

4.11 Painting

(a) Appropriate breathing air respirators should be provided for use by the workers when paint is applied in the form of spray, or a surface having lead paint is dry rubbed or scraped.

(b) Only the quantity of paint, thinner and polish required for the day's work should be kept at the work spot. Excess storage should not be permitted at the work spot.

(c) Smoking, open flames or sources of ignition should not be allowed in places where paints, varnish, thinner and other flammable substances are stored, mixed or used. A caution board, with the instructions written in national language and regional language, 'SMOKING - STRICTLY PROHIBITED' should be displayed in the vicinity where painting is in progress or where paints are stored. Symbols should also be used on caution boards.

(d) All electrical equipment of paint storage room should be of explosion proof design. Suitable fire extinguishers/sand buckets should be kept available at places where flammable paints are stored, handled or used.

(e) When painting work/hot resin mix is done in a closed room or in a confined space, adequate ventilation should be provided and ensured. In addition, suitable respirators should be provided. No portable electric light or any other electric appliance of voltage exceeding

24 volts should be permitted for use inside any confined space. Walkie-talkie or other means of communication should be provided. Rescue arrangement like full body harness with lifeline, tripod with pulley and extra BA sets should be available.

(f) The workers should use PVC gloves and/or suitable barrier creams to prevent the skin contact with Epoxy resins and their formulations used for painting.

4.12 Demolition

(a) Before any demolition work is commenced and also during the progress of the work, all roads and open area adjacent to the work site should either be closed or suitably cordoned. Appropriate warning signs should be displayed for cautioning approaching persons/ vehicles.

(b) Before demolition operations begin, it should be ensured that all the service lines are de-energized.

(c) Persons handling demolition operations shall use appropriate PPE.

(d) All demolition operations should be carried out with safe and duly approved procedures which shall include following but not limited to:

(i) No masonry/material should be permitted to fall in such masses or volume or weight so as to endanger the structural stability of any floor or structural support.

(ii) No wall, chimney or other structure or part of a structure is left unguarded in such a condition that it may fall, collapse or weaken due to wind pressure or vibration.

(iii) No floor, roof or other part of the building should be overloaded with debris or materials as to render it unsafe.

(e) After the demolition, the debris and other materials collected should be disposed safely and not permitted to be dropped freely.

(f) Entries to the demolition area shall be restricted to authorised persons wearing safety helmets and safety shoes.

4.13 Traffic

(a) All the vehicles moving at sites should conform and comply with the requirements of Motor Vehicles Act, 1988 and the Rules made there under. All the drivers/operators of vehicles should possess valid driving license as per Motor Vehicles Act, 1988 or its latest amendment.

(b) The facility should conduct operations so as to interfere as little as possible with the use of existing roads at or near locations where the work is being performed. When interference to traffic is inevitable such as road cutting or transit unloading of heavy equipment etc. notice of such interference should be given to the engineer-in-charge and safety officer well in advance with the details of start of the work and time required.

(c) A cleaner/assistant must be available for all heavy vehicles whenever vehicles move forward as well as in the reverse direction. All vehicles should be fitted with proper reverse horns, back view mirrors and indicator signals.

(d) Facility should ensure that the assessment of the driver's visual ability is carried out as per Rule 55 of the Atomic Energy (Factories) Rules, 1996/guidelines of advisory committee on occupational health (ACOH), AERB or as per the latest amendments in statutes.

(e) Effective speed breakers with yellow stripes on the roads to regulate the speed at the vulnerable points should be installed. Effective barricading with adequate caution signs should be placed to warn the vehicle drivers whenever the jobs are carried out on the road.

(f) All vehicles moving at the site should have roadworthiness certificate issued by the concerned authority.

(g) Special limit boards and caution boards indicating turns should be installed wherever necessary.

(h) In general, the following maximum speed limits should be specified and implemented. Vehicles speed limits should be as per Motor Vehicle Act or 20 Km/h. Extra precautions and care should be exercised particularly during heavy material/equipment movements.

(i) Safety awareness programmes should be conducted for all the drivers of the light, medium and heavy vehicles.

4.14 Work in Radiation Area

The facility should follow the stipulated procedure under Atomic Energy Radiation Protection Rules, 2004 and AERB safety manual on 'Radiation Protection for Nuclear Facilities' (AERB/NF/SM/O-2) regarding work in the radiation area and other works related with radiography.

4.15 Work in and Around Water Bodies

(a) When work is done at a place where there is risk of drowning, all necessary rescue equipment such as life buoys and life jackets should be provided and kept ready for use.

(b) All necessary steps shall be taken for prompt rescue of any person in danger and adequate provision should be made for prompt first-aid treatment of all injuries likely to be sustained during the course of the work. Proper record of entry/exit to and from water bodies shall be maintained on shift basis and search operation shall be conducted as soon as any person is detected to be missing.

(c) Caisson Work

(i) Safe means of access should be provided to the place of work in the caisson and adequate means should be provided to safely reach the top of caisson in the event of inrush of water

(ii) The work relating to construction, positioning, modification or dismantling of caisson shall be done under the supervision of a responsible person

4.16 Fire Safety

(a) All provisions for fire safety shall be complied as per AERB safety standard on 'Fire Protection Systems for Nuclear Facilities' [AERB/NF/SS/FPS (Rev. 1)].

(b) All necessary precautions should be taken to prevent outbreak of fires at the construction site. It should be ensured that all hot work is carried out under valid work permit.

(c) Combustible materials such as wood, cotton waste, oil, coal, paints, chemicals etc., should be segregated and kept to the required bare minimum quantity at work place.

(d) Containers of paints, thinners and allied materials should be stored in a separate room which should be well ventilated and free from excessive heat, sparks, flame or direct rays of the sun. The containers of paint should be kept covered or properly fitted with lid and should not be kept open except while using.

(e) Adequate number of trained persons from approved fire training centre required to extend fire safety coverage should be ensured.

(f) Fire extinguishers as approved by the engineer-in-charge/in-charge of fire station/safety-in-charge should be located at the construction site at appropriate places.

(g) Adequate number of trained workmen in fire fighting who can operate fire extinguishers should be ensured.

(h) Portable fire extinguishers with periodic inspection, maintenance and re-filling complying with the mandatory requirements should be ensured.

(i) Availability of adequate water for fire fighting should be ensured.

(j) Implementation of the provisions of various statutory licenses for storing gas cylinders, petroleum products, explosives etc. as per the relevant acts and rules should be ensured wherever required.

4.17 Environmental Safety

Relevant provisions of the state/central statutory authority regarding environment protection should be adhered to.

4.18 Public Protection

The Facility should make necessary provisions to protect the public. He should be bound to bear the expenses in defense of every action or other proceedings at law that may be brought by any person for injury sustained owing to neglect of any precaution required to be taken to protect the public. He should pay for the any such damage and cost which may be awarded in any such suit, action or proceedings to any such person, or the amount, which may be fixed as a compromise by any such person.

4.19 Safety of Visitors

(a) Visitors for the project shall be given health and safety induction before they are allowed in to the construction project. It shall include the minimum PPE to be used, hazards and risks at the work area, restricted areas of entry, emergency response arrangements, etc.

(b) Visitors shall always be accompanied by one of the employees of the project site.

(c) Visitors shall not be allowed in the hazardous areas unless they are competent and trained to work in such areas.

4.20 Housekeeping

(a) It should be recognised that a proper place for everything and everything in its place is maintained for a good housekeeping.

(b) The material required for immediate use only should be brought to the designated workplace and stacked properly and labeled suitably.

(c) All work spots, site office and surroundings should all times be kept clean and free from debris, scrap, concrete muck, surplus materials and unwanted tools and equipment. A day-to-day collection and disposal of scraps/debris should be done safely at designated place.

(d) Electrical cables, leads and hoses should be so routed as to allow safe traffic by all concerned. Cable should be preferably supported on the brackets fixed along the wall to maintain safe access. Wherever

routing on the floor cannot be avoided, care should be taken to ensure mechanical protection of these cables and safe access is not disturbed.

(e) No material on any work place should be so stacked or placed or disposed off as to cause danger, inconvenience or damage to any person or environment.

(f) All unused scaffoldings, surplus/scrap materials and equipment/ systems like temporary electrical panels etc. should not be allowed to accumulate and shall be removed from the premises at the earliest.

(g) Accumulation of water/oil spillages on the floor or any other workplace should be avoided.

(h) Proper aisle space marking should be provided in all workplaces.

4.21 Other Statutory Provisions

Notwithstanding the clauses in the above subsections, there is nothing in these clauses to exempt the Facility from the provisions of any other act or rules in force in the Republic of India. In particular, all operations involving the transport, handling, storage and use of explosives should be as per the standing instructions and conform to the Indian Explosives Act, 1884 and the Explosives Rules, 1983. Handling, transport, storage and use of compressed gas cylinders and pressure vessels should conform to the Gas Cylinder Rules 2004 and Static and Mobile Pressure Vessels (Unfired) Rules 1981. In addition, The Indian Electricity Act 2003 and Indian Electricity Rules 2005, the Atomic Energy Act, 1962, the Radiation Protection Rules, 2004, the Atomic Energy (Factories) Rules, 1996 and AERB safety manual on 'Radiation Protection for Nuclear Facilities' (AERB/NF/SM/O-2) should be complied with.

5. PERSONAL PROTECTIVE EQUIPMENT

5.1 General

Although the primary approach in any safety effort is that the hazard to the workmen should be eliminated or controlled by engineering methods rather than protecting the workman through use of personal protective equipment (PPE). Engineering methods could include design change, substitution, ventilation, mechanical handling, atomisation etc. Under those situations when it is not possible to introduce any effective engineering methods for controlling hazards, it is necessary that workman use appropriate type of PPE. For example, in construction work there is the possibility of a hand tool, a bolt, or some loose material to fall from an elevated level and striking the head of workman working below. It is therefore necessary that construction worker wear a safety helmet. It is for such situations, both the Factories Act 1948 and the Atomic Energy (Factories) Rules, 1996 have provisions for use of appropriate type of PPE.

It is thus recognised that use of PPE is an important and necessary consideration in the development of a safety programme. Once the safety professional decides that PPE is to be used by workmen, it is essential to select right type of PPE and management should ensure that workman uses it and also PPE is correctly maintained.

5.2 Personal Protective Equipment (PPE)

(a) All personal protective equipment as considered necessary should be made available for the use of the persons employed on the site and maintained in a condition suitable for immediate use. Also adequate steps should be taken by engineer-in-charge to ensure proper use of PPE.

(b) All the PPEs in use should be as per relevant IS standards as referred in the AERB safety guidelines on 'Personal Protective Equipment' (AERB/SG/IS-3).

(c) All persons employed at the construction site should use safety helmets. Safety helmet should be with BIS mark and should have its headband with back support and chin strap.

(d) Workers employed on mixing asphaltic materials, cement and lime mortars should use protective goggles, protective foot wears, hand gloves and respirators as required.

(e) Persons engaged in welding and gas-cutting works should use suitable welding face shields. The persons who assist the welders should use suitable goggles. Protective goggles should be worn while chipping and grinding.

(f) Stonebreakers should use protective goggles. They should be seated at sufficiently safe distances from one another.

(g) Safety goggles should be of shatterproof type and with zero power.

(h) Persons engaged in or assisting in shot blasting operations and cleaning the blasting chamber should use suitable gauntlets, overalls, shatterproof and dust-proof goggles and self contained breathing apparatus set.

(i) All persons working at heights more than 3.5 m above ground or floor and exposed to risk of falling down should use full body harness safety belts, unless otherwise protected by cages, guard railings, etc. In places where the use of safety belts is not feasible, suitable net of adequate strength fastened to substantial supports should be used.

(j) When workers are employed in sewers and inside manholes that are in use, it should be ensured that the manholes are opened and are adequately ventilated at least for an hour. After it has been well ventilated, the atmosphere inside the space should be checked for the presence of any toxic gas or oxygen deficiency by a competent person and recorded in the register before the workers are allowed to get into the manholes. A pilot team should enter the area donning self contained breathing apparatus (SCBA). The manholes opened should be cordoned off with suitable railing and provided with warning signals or caution boards to prevent accidents. There should be proper illumination in the night. Depending upon the work situation, the facility should provide PPE including the SCBA as recommended by Head, industrial safety.

6. MEDICAL MANAGEMENT

6.1 General

(a) The facility management/contractor shall make arrangements for the first aid and medical services for the injured or ill persons for prompt attention or aid.

(b) The arrangement can be made by the contractor or an agreement can be in vogue with the facility .

(c) The medical facilities at first-aid centre shall be adequate to immediately cater to the injured based on the hazard potential and probable severe injuries.

(d) The first aid centre shall be provided with the adequate equipment and medicines for catering to the site requirements. The first aid centre shall be manned depending on the working hours/on round the clock shift basis. The services of at least one qualified medical practitioner (medical officer) shall be made available by the Facility management/contractor.

6.2 Medical Facilities

(a) Medical facilities conforming to the provisions of the Atomic Energy (Factories) Rules, 1996 should be provided at all work sites.

(b) The requisite medical facilities in the form of a well-equipped first aid centre manned by qualified nursing personnel should be provided at all work sites. Contractor may avail this facility as per terms and conditions of the contract.

(c) In addition, well-maintained first aid boxes should be kept at each location of the work by the Facility/contractor and availability of the personnel trained in first aid should be ensured.

(d) A manned and equipped ambulance should be available at work site during the working hours/on round-the-clock shift basis.

(e) It should be ensured by the occupier that occupational health monitoring of contract workers is carried out as per provisions of the Factories Act 1948 as per the latest amendment and the stipulations/directions given by Atomic Energy Regulatory Board from time to time.

(f) Display of emergency contact numbers of important persons and hospitals and route map of site shall be maintained at designated places.

6.3 Medical Management of Serious Injuries

(a) In case of serious injuries, the injured should be shifted to the nearest first-aid centre at site immediately. The opinion of medical officer/ certifying surgeon should be sought immediately for medical management.

(b) After providing the first aid treatment the injured should be shifted to designated medical facility of the site/hospital for further medical assistance, in an ambulance along with a nursing attendant.

(c) The doctor at the medical facility of the site/hospital attending the case shall assess the extent of injuries and render immediate medical aid. If the situation warrants trauma/special care the injured shall be shifted to the referral hospital, having all the requisite facilities for specialised treatment in ambulance along with a medical attendant.

(d) A list of such referral hospitals for specialised medical management facilities for the injured persons should be available with the project management/Head, industrial safety and Head, medical services of the site for ready reference.

APPENDIX-A

APPLICATION FOR HEIGHT PASS

PART- A

Group/Section: _____

Agency: _____

1. Applicant's Name : _____
2. Facility address : _____
3. Residential address : _____
4. Age : _____
5. Sex : _____
6. Height : _____
7. Gate Pass No. : _____
8. Name of contractor/agency with whom engaged at present : _____
9. Height pass required for work at _____ m. Height
10. Description of present job : _____
11. Previous experience of working at height :

S.No.	Name of the Employer	Duration of Employment	Work Experience
1.			
2.			

12. Does the applicant suffer from any of the following ailments? (If yes details to be given):

    (a) Blood pressure _____ (b) Epilepsy _____

    (c) Flat foot _____

    (d) Frequent headache or reeling sensation _____

    (e) Mental depression _____ (f) Limping gait _____

    (g) Aerofobia _____

Declaration:

I hereby declare that the above information furnished by me is true and correct. I shall always wear the safety belt and tie the life-line whenever working at unguarded heights of 3 m and above. I shall not misuse the height pass issued to me or transfer it to any other person. I shall never come to duty or work at height/depth under the influence of alcohol/drugs.

Date: Name:

Sign:

(Applicants name and signature or loss time injury (L.T.I) incase he cannot sign. In case of LTI an authorised person shall explain each point/item to the individual and certify on that behalf below the LTI)

I certify that I am satisfied with the above certification of the individual for the application of height pass and request for issue of height pass to him.

Name :

Sign :
(Agency Concerned)

Countersigned by:

Section Head (Facility)

PART- B

MEDICAL FITNESS CERTIFICATE

Certified that I, Dr. _____ have examined Shri _____ _____ aged _____ on (date) _____ who has signed below in my presence. General & physical examinations of Shri. _____ _____ do not reveal any abnormality. He does not suffer from any acute/ chronic skin disease or any contagious or infectious disease. His eye sight is normal with/without glasses. In my opinion, Shri _____ is physically and mentally fit for working at height.

Details of examinations are given below:

Personal attributes:

1. Height: _____
2. Chest: _____
3. Weight: _____
4. Hearing: _____
5. Sight: _____
6. Skin: _____
7. Heart beating: _____

Medical aspects:

1. Urine: _____
2. Blood pressure: _____
3. Epilepsy: _____
4. Flat foot: _____
5. Frequent headache or reeling sensation: _____
6. Mental depression: _____
7. Limping gait: _____
8. Aerophobia: _____

Name:

Sign :

Rubber Stamp of
Medical Practitioner
with Reg. No.

Signature of workman:

PART-C

INDUSTRIAL SAFETY SECTION

(Considering the above medical certificate, the applicant has appeared on the following practical tests conducted by industrial safety section and the results are given below (strike off whichever is in-applicable)

(a) Wearing a safety belt and tying the rope knot : Pass/fail

(b) Walking over a horizontal structure at 3 m. height wearing a safety belt : Pass/fail

(c) General physique (OK/Not OK)

The above applicant's performance in the above tests has been satisfactory/ unsatisfactory due to the following.

So I certify and issue this height pass to Shri _____ with Registration No. _____ in the height pass register. This is valid for one year from the date of issue i.e. up to _____

Date:

Name:

Sign.:
Scientific Assistant (Safety)

Safety Officer

APPENDIX-B

FORM - 1

APPLICATION FOR TEMPORARY POWER SUPPLY AND USE OF ELECTRICITY AT WORK SITE DURING CONSTRUCTION

[Prescribed under clause 4.6(d)]

1.	Name and address of user.	
2.	Reference of tender or work order (if applicable)	:
3.	Name & designation of tender/work order issuing authority.	:
4.	Power supply application number†	:
5.	Name and designation of tender/work order/work supervising authority (engineer-in-charge).	:
6.	Expected date of commencement of temporary supply	:
7.	Expected date of decommissioning of temporary supply	:
8.	Voltage level (LV/MV/HV)	
9.	Type of connection (1Ph/3Ph)	
10.	Connected load (Kw)	
11.	Maximum demand (KVA)/Power factor	
12.	Single line diagram* of proposed power distribution scheme along with equipment data sheet (downstream installation after point of connection).	Enclosed (Form-1A)/Not enclosed
13.	Name of overall supervisor and available qualified Staff	Enclosed (Form-1B)/Not enclosed
14.	Auxiliary equipment data sheet (meters, fire extinguisher, first aid box etc)	Enclosed (Form-1C/Not enclosed
15.	Name and designation of provider's representative to whom the application is addressed.	:
16.	Name and designation of authorized signatory of user, who had submitted this application	:

† Power supply application number shall be different for same user with multiple applications for temporary supply

* All the drawings and tables shall be signed by user's representative indicated against 16 above.

Signature of authorised signatory of user

Signed endorsement of work order supervising authority indicated against 5 above.

FORM - 1A

EQUIPMENT DATA SHEET FOR OBTAINING TEMPORARY POWER SUPPLY AND USE OF ELECTRICITY AT WORK SITE DURING CONSTRUCTION

(Prescribed against item-12 of form-1)

Name and address of user:

Power supply application Number:

Amendment No:-

References:- Single line diagram (SLD) of the power distribution scheme with all equipment details (Attach the SLD)

1. Identity	2. Type	3. Make & model	4. Manufacturer's S.No	5. Fixed/ Portable	6. Size	7. Last used date	8. Last test date	9. Latest test data	10. Rating

Signature of authorised signatory of user

Explanation of column headers:

1. Identity:- Identification mark/number/tag of equipment in single line drawing and layout drawing. Every equipment in single line drawing and layout drawing shall have suitable identification mark/number/tag.
2. Type:- Cable/CB/MCB/MCCB/ELCB/transformer/lightning arrestor/earthing station/ earthing connection/motor/lighting fixture/switch/fuse/switch, socket box etc.
3. Make and model:- manufacturer's name and corresponding model no.
4. Manufacturer's S. No:- serial number and date in name plate if available. Else NA
5. Fixed/portable:- Equipment is installed/laid/anchored to surface or portable.
6. Size:- depending upon type of equipment and as desired by provider representative e.g. length for cables or all dimensions if heavy equipment like transformer.
7. Last used date. date of last use else NEW
8. Last test date. latest test date by user or by manufacturer if NEW
9. Latest test data:- IR, HV, resistance, functional test data depending upon the type of equipment as desired by provider's representative.
10. Rating:- name plate rating of equipment like voltage, current, power (apparent, active, reactive), IP of enclosure, size(cable cross section) etc. depending upon the type of equipment and as desired by provider's representative.

FORM - 1B

STAFF DATA SHEET FOR OBTAINING TEMPORARY POWER SUPPLY AND USE OF ELECTRICITY AT WORK SITE DURING CONSTRUCTION
(Prescribed against item-13 of form-1)

Name and address of user:

Power supply application Number:
Amendment No:-

1. Name	2. Address	3. Tel.No.	4. Responsibility	5. Certification detail	6. Resucitation training	7. Expe-rience	8. Other relevant training	9. Signature

Signature of authorised signatory of user

Explanation of column headers:

1. Name:- Name of agency/person
2. Address:-
3. Tel No:- regular, alternate and emergency telephone numbers
4. Responsibility:- whether responsible for installation, operation, maintenance, overall supervision etc. overall supervisor shall be indicated specifically.
5. Certification detail:- (a) type of certification e.g wire man license, electrical supervisor license, electrical contractor license, diploma in electrical engineering, degree in electrical engineering etc. (b) certifying agency e.g. state PWD, central PWD, CEA, name of college/university etc. (c) certificate/license number with date. (d) valid up to date or next renewal date must for contractor/supervisor license.
6. Artificial resuscitation training:- indicate YES/NO if the staff is trained to apply artificial resuscitation technique.
7. Experience.:- number of years of experience.
8. Other relevant training :- any other training in electrical/safety course. Indicate name of training, duration (days/months), training providing agency.
9. Signature:- original signature of individual.

FORM - 1C

AUXILIARY EQUIPMENT DATA SHEET FOR OBTAINING TEMPORARY POWER SUPPLY AND USE OF ELECTRICITY AT WORK SITE DURING CONSTRUCTION
(Prescribed against item-14 of form-1)

Name and address of user:

Power supply application Number:
Amendment No:-

Reference:- Layout drawing No. / _____

1. Identity	2. Type	3. Make and model	4. Manufacturer's S. No	5. Fixed/ Portable	6. Size	7. Last used date

Signature of user's representative

Explanation of column headers:

1. Identity:- identification mark/number/tag of equipment in layout drawing.
2. Type:- earthing rod/megger/multi meter/earth resistance meter/fire extinguisher/s and bucket/first aid box/resuscitation chart/rubber mat etc.
3. Make and model:- manufacturer's name and corresponding model no.
4. Manufacturer's S. No:- serial number and date in name plate if available. Else NA
5. Fixed/portable:- equipment is installed/laid/anchored to surface or portable.
6. Size:- depending upon type of equipment and as desired by provider representative.
7. Last used date. NEW for new equipment. NA for passive devices like chart/mat etc.

FORM-1D

[Prescribed under clause 4.6(e)]

Name of user agency **Power supply application number:-**

CERTIFICATE BY THE LICENSED ELECTRICAL CONTRACTOR

Certified that subject installations have been carried out by us or checked by us and is in accordance with I.E. Rules. The documents submitted with subject temporary power supply application (Form-1) is verified by us and the complete installation confirms to these documents.

We shall periodically inspect/check the installation so that no unsafe situation arises during use of this temporary power supply system. We understand that for the entire duration of existence of this temporary power supply system we shall be responsible for any unsafe installation, operation, maintenance, testing of the same which results into any loss of life or material. We shall immediately report to the provider's representative and ensure de-energisation of supply if any unsafe situation arises during use of this temporary power supply system.

Signature of the authorised signatory of licensed electrical contractor

Rubber seal of licensed electrical contractor

Date

CERTIFICATE BY THE USER

Certified that my/our installations have been carried out in accordance with the I.E. Rules and that I/We have employed competent agency/staff to handle the installations which is strictly as per the staff data sheet submitted in Form-1B.

We understand that for the entire duration of existence of this temporary power supply system we shall be responsible for any unsafe installation, operation, maintenance, testing of the same which results into any loss of life or material. We shall immediately report to the provider's representative and ensure de-energisation of supply if any unsafe situation arises during use of this temporary power supply system.

Signature of the authorised signatory of user

Name of signatory

Date

FORM -1E

[Prescribed under clause 4.6(f)]

CERTIFICATE BY THE SAFETY OFFICER

Certified that I have inspected the electrical installation referred here in after satisfying myself about the safe condition of the installation, I hereby recommend that the service connection be given to the contractor.

Signature of the safety officer

Name:

Date:

AUTHORISATION BY THE ELECTRICAL ENGINEER

The subject power supply application along with completed installation, necessary certificates (as per Form-1 of Appendix-B) is scrutinised by us. The proposal found to be in order and the installation can be energised on _____ in presence of your designated overall supervisor as indicated in Form-1B. Enclosed herewith the test report data sheet Form-1F. You are requested to carry out the periodic testing of equipment and submit the test report periodically as per this form.

Signature of the electrical engineer
of provider

Name of signatory

Date

FORM - 1F

TEST/MAINTENANCE REPORT DATA SHEET OF EQUIPMENTS OF TEMPORARY POWER SUPPLY SYSTEM AT WORK SITE DURING CONSTRUCTION
(Prescribed against form-1E)

Name and address of user:

Power supply application Number:
Amendment No:-

1. Identity	2. Type	3. Last tested date	4. Next due date of any test	5 Frequency of IR test	6 Frequency of HV test	7. Frequency of earth resistance test	8. Other tests

Signature of electrical engineer of provider

Explanation of column headers:

1. Identity:- identification mark/number/tag of equipment in single line drawing and layout drawing. Every equipment in single line drawing and layout drawing shall have suitable identification mark/number/tag.
2. Type:- Cable/ CB/ MCB/ MCCB/ ELCB/transformer/lightning arrestor/earthing station/ earthing connection/motor/lighting fixture/switch/fuse/switch, socket box etc.
3. Last test date: - latest test date indicated in Form-1A.
4. Next due date of any test:- as worked out by frequency of tests indicated in subsequent columns.
5. Frequency of IR test:- required frequency depending upon type of equipment and location of installation. NA if not required after installation.
6. Frequency of HV test:- required frequency depending upon type of equipment and location of installation. NA if not required after installation.
7. Frequency of earth resistance test:- required frequency depending upon type of equipment and location of installation. NA if not required after installation.
8. Other tests: - name and description of any other essential tests/maintenance activity and required frequency depending upon type of equipment and location of installation. NA if not required after installation.

APPENDIX-C

CHECKLIST FOR OPERATION OF READY MIX CONCRETE (RMC) PLANT

(To be submitted to AERB along with application for construction consent and a copy to be retained by site)

(Verifiable documents like supplementary checklists, work sheets, spread sheets etc. should be maintained for each item of the checklist wherever relevant)

Serial No.	Points to be Checked	Remarks
1. 0	**Prior to Installation of the RMC Plant**	
1.1	Whether acceptance report on healthiness of the pre-identified critical plant equipment like concrete mixer, pumps, programmable logic controllers, conveyors, etc. prior to installation available ?	
1.2	Whether approval for the location of the plant site after evaluation and review by project management available ?	
1.3	Whether review of the vendor documents like operation and maintenance manual, vendor specifications, safety manual, etc. of contractor carried out by project management ?	
1.4	Whether job hazard analysis reports, erection procedures, checklists for critical activities available ? Are the operators aware of it ?	
1.5	Whether adequate number of line managers/supervisors/ operators for carrying out the jobs safely are identified and availability is ensured ?	
1.6	Whether safety surveillance requirements of construction activities both by contractor and facilities clearly spelt out?	
1.7	Whether adequate work control measures like construction permit, safety work permit system, height pass system, etc. for safe job performance are available ?	
1.8	Whether any facilities officer is assigned the responsibility of the RMC Plant ?	
2.0	**Commissioning/Operation of RMC Plant**	
2.1	Whether reports on healthiness of material handling equipment like hoists, belt conveyors, buckets, hoses, including electrical equipment etc. are available ?	

APPENDIX-C (CONTD.)

CHECKLIST FOR OPERATION OF READY MIX CONCRETE (RMC) PLANT

Serial No.	Points to be Checked	Remarks
2.2	Whether machine guards for pulleys, power shafts, rollers, etc. are available ?	
2.3	Whether availability of safe operating procedures, emergency procedures, process diagrams, power supply diagrams, details of interlocks, operation & maintenance manual (provided by supplier/vendor) ensured ?	
2.4	Whether adequate number of qualified, trained and experienced operators for safe operation of the plant including mechanism/method of operational control and command available ?	
2.5	Whether periodic surveillance programme for equipment, logics, interlocks, process parameters, trips, noise and illumination levels, etc. and measures to take corrective actions are available ?	
2.6	Whether periodic checks are carried out to ensure display of all interlocks and warning signals in PLC monitor ?	
2.7	Whether operations control measures like log sheets, work permits, procedures, instruction sheets, by-passing/jumpering trips, etc. are available ?	
2.8	Whether access to medical first-aid box & fire extinguishers, etc. available ?	
3.0	**Operating/Working Areas**	
3.1	Control Room	
3.1.1	Whether adequate information on process equipment and parameters, logics and control available ?	
3.1.2	Whether clear view of the plant from the control room to check entry of personnel into operating areas is available ?	
3.1.3	Whether availability of distinct window panels to distinguish process parameters, alarms and trips are verified ?	
3.1.4	Whether audio alarm is available in the field to give warning prior to starting of concrete mixer & conveyor belt ?	
3.1.5	Whether relevant operating and maintenance documents available and accessible ?	

APPENDIX-C (CONTD.)

CHECKLIST FOR OPERATION OF READY MIX CONCRETE (RMC) PLANT

Serial No.	Points to be Checked	Remarks
3.1.6	Whether operational controls preventing re-setting of operational parameters, trips by-passing, logic changes, etc. are available in control room ?	
3.1.7	Whether operational data and information logged chronologically indicating the status of equipment running & shutdown, maintenance works planned and taken up.	
3.1.8	Whether means of communication between operator and control room are available ?	
3.2	**Aggregates Storage/Handling Areas**	
3.2.1	Whether aggregates/materials stored separately in suitable weatherproof enclosures ?	
3.2.2	Whether routes for movement of vehicles clearly defined ?	
3.2.3	Whether reverse horns, rear view mirror, etc. on all dumpers/ trailers/trucks are provided ?	
3.2.4	Whether machine guards for rotating/moving/conveying machines available in place ?	
3.2.5	Whether engineered noise control measures available in the crushing areas ?	
3.2.6	Whether usage of ear muffs for ear protection in noisy areas enforced ?	
3.2.7	Whether trip/emergency stop switch/pull cord mechanisms, etc. to the moving/rotating equipment like belt conveyors, crushers etc. are available and healthy ?	
3.2.8	Whether adequate dust control measures in working areas available ?	
3.2.9	Whether adequate illumination is provided in the working areas ?	
3.2.10	Whether safety/warning sign boards available to prevent persons approaching operating crushers/belt conveyors etc ?	
3.3	**Storage Hoppers/Silos**	
3.3.1	Whether suitable access with handrails to reach to the top of hoppers/silos provided ?	

APPENDIX-C (CONTD.)

CHECKLIST FOR OPERATION OF READY MIX CONCRETE (RMC) PLANT

Serial No.	Points to be Checked	Remarks
3.3.2	Whether proper walk ways with guard railing to access to different storage areas available ?	
3.3.3	Whether measures to prevent clogging of equipment like air fluidiser, etc. are available ?	
3.3.4	Whether controls and safety measures for feeders like belt conveyors to the silos/hoppers, etc. is available ?	
3.3.5	Whether dust suppression and noise control measures are in place ?	
3.3.6	Whether safety measures to enter into silos/hoppers for operation/maintenance requirements.	
3.3.7	Whether safe access for sampling locations/areas and procedure for collecting the samples are available ?	
3.4	**Concrete Mixer Areas**	
3.4.1	Whether safe access and working platform in mixing area provided ?	
3.4.2	Whether safe condition of the mixers, pumps, etc. used in the areas is ensured ?	
3.4.3	Whether proper identification tags for equipment, pipelines etc. are available ?	
3.4.4	Whether safe condition of the electrical equipment like local push buttons, panels, cables etc. ensured ?	
3.4.5	Whether adequate illumination in the working areas is ensured ?	
3.4.6	Whether interlocks of Mixers are in healthy state ?	
3.4.7	Whether sand bin is provided with electro-mechanical vibrator for easy material flow ?	
3.4.8	Whether warning signals to prevent persons approaching operating mixers in place ?	
3.4.9	Whether proper storage of admixtures to prevent freezing and availability of material safety data sheets for admixtures and other chemicals are ensured ?	
3.4.10	Whether collection trays have been provided under overhead conveyor belt to prevent fall of material ?	

APPENDIX-C (CONTD.)

CHECKLIST FOR OPERATION OF READY MIX CONCRETE (RMC) PLANT

Serial No.	Points to be Checked	Remarks
3.4.11	Whether the mixing cylinder/drum has emergency manual discharge facility ?	
4.0	**Electrical Safety**	
4.1	Whether proper isolating switches/isolators are provided for all equipment in the field as well as in control room ?	
4.2	Whether proper grounding/earthing arrangement for all electrical installations metallic structures and panel boards provided and recording of earth pit resistance values planned ?	
4.3	Whether fuses of adequate rating are available to limit overloading of circuits ?	
4.4	Whether earth leakage circuit breakers in all circuits are provided and tested periodically to ensure their healthiness ?	
5.0	**Particulate Emissions**	
5.1	Whether provisions of measurement of particulate emissions are available ?	
5.2	Whether actions to be taken in case of more visual emissions are available ?	
5.3	Whether methods to prevent/control spread of dust in working areas available ?	
6.0	**General Requirements**	
6.1	Whether emergency services like fire station, first aid, hospital etc accessible ?	
6.2	Whether specific line staff/supervisors for carrying out routine, special and emergency works with certain instructions and communications identified and trained ?	
6.3	Whether do's and don'ts while handling refrigerants like ammonia and admixtures used in concrete mixing displayed promptly ?	
6.4	Whether the use of personal protective equipment like helmet, safety belt, self contained breathing apparatus/canister, hand gloves, apron, face shield, safety shoes, gumboots etc. has been ensured ?	

APPENDIX-C (CONTD.)

CHECKLIST FOR OPERATION OF READY MIX CONCRETE (RMC) PLANT

Serial No.	Points to be Checked	Remarks
6.5	Whether emergency procedures to be followed during ammonia leaks, fires, etc. are available ?	
6.6	Whether fire extinguishers are available at various critical locations ?	

PART-B

CONTROL OF WORKS
(CONTRACTORS)

7. INTRODUCTION

7.1 General

The Department of Atomic Energy(DAE) through its constituent units execute various site works either by their own manpower or by manpower of various outside agencies. The nature of contracts with outside agencies can be works contracts, engineering procurement contracts, purchase contracts, minor fabrication contracts etc. These site works involve entire gamut of conventional industrial activities like excavation, rock blasting, earth handling, construction, material handling, fabrication, installation, operation, maintenance etc. of nuclear or conventional plants/facilities. This is a challenging responsibility for the contractor due to the complexity of problems like quality of workforce (which may be unskilled, illiterate, migratory) available for labor-intensive jobs, lack of coordination among agencies at site, lack of safety awareness among concerned authorities, time schedules of project etc. As a principal employer, facility management shall be responsible to ensure health and safety of all personnel engaged for the work. In this process, the contractor through his established measures shall ensure that the guidelines are implemented. However the facility management shall monitor the compliance with the provisions outlined in the guidelines through periodic supervision and review. Any accidental injury or loss of life is detrimental to the facility as well as the society. This 'guidelines' covers the safety organisation and the safety management system requirements in sections two and three. The work specific safety precautions are covered in section four. The requirements relating to personal protective equipment and medical management are covered in sections 5 and 6.

7.2 Objective

This 'guidelines' has a basic framework of industrial safety organisation, safety management systems, safe work procedures to maintain a safe working environment for all personnel and to prevent any unsafe condition/act endangering the life of personnel engaged for industrial activities. The major objectives of this 'guidelines' are:

(i) To create awareness among workers about industrial hazards and safe working procedures.

(ii) To lay down safe work procedures and systems to be followed for different type of industrial activities.

(iii) To establish a robust safety management system.

(iv) To protect the health and ensure the safety of the workers from industrial activities.

7.3 Scope

This ‘guidelines’ is essential for implementation and assurance of conventional safety in areas such as industrial, chemical, electrical, fire, environmental and is applicable for all works executed through contracts, like engineering procurement contract, minor fabrication contract etc. Where the execution of work is envisaged in radiation controlled area or involves handling and fabrication of any nuclear material, additional precautions noted in relevant AERB safety documents on radiation protection shall also be applicable.

8. SAFETY ORGANISATION

8.1 General

(a) Construction projects have significant health and safety hazards, which need to be managed systematically since the project inception stage to achieve incident- free completion of jobs. Contractor should have well-defined safety organisation which helps in effective implementation of safety management systems and ensures health and safety of workers.

(b) The top management of contractor should assure that all the provisions of relevant Acts & Rules are conformed to.

(c) Safety organisation should carry out safety surveillance, safety training, safety enforcement measures, safety audit etc. related to all works to fulfill the overall safety requirements of this 'guidelines'.

(d) Safety functionaries should be exclusively assigned with the work related to protection of health and safety of workers.

(e) IS: 18001: 2007 gives detailed requirements of health and safety management system requirements. IS: 15793 gives requirements of good practices for managing environment, occupational health and safety legal compliance. This 'guidelines' prescribes requirements in addition to IS: 18001:2007 and IS: 15793 and gives guidelines on implementing these specific to a construction project.

(f) The requirements prescribed in various central and state regulations including *Building and other Construction Workers (Regulation of Employment and Conditions of Service) Act*, 1996 and rules framed thereunder with respect to managing health and safety in construction projects, shall be complied with.

8.2 Organisational Structure for Safety Management

(a) The Contractor shall deploy qualified and experienced line management personnel for supervising the jobs to be carried out safely by workers. In order to oversee the industrial and fire safety aspects during execution of hazardous jobs (listed out in para 9.11) by the contractors, at least one safety supervisor with the qualifications and experience mentioned in Table -2 shall be in place irrespective of the man power deployed by the contractor.

(b) The qualification, experience and the minimum number of safety professionals to be deployed by contractor shall be as per the following table:

TABLE-2 : QUALIFICATION, EXPERIENCE AND NUMBER OF SAFETY PROFESSIONALS FOR CONSTRUCTION PROJECTS

Category of safety person	Mandatory requirement	Qualification
Safety officer	One in each shift (minimum) up to 1000 workers. If number of workers in a shift (including contractor's workers) exceeds 1000, additionally one safety officer should be deployed for every 1000 workers or part thereof.	Degree in engineering/ technology and diploma in industrial safety with minimum two years of experience or Diploma in engineering with diploma in industrial safety with minimum 6 years experience or A recognised degree in physics or chemistry and has practical experience of working in a factory in a supervisory capacity for a period of not less than 5 years. Not withstanding the provision contained in the above criteria any person who (i) possesses a recognised degree or diploma in engineering or technology and has had experience of not less than five years in a department of the central or state government which deals with the administration of the Factories Act, 1948 or the Dock Workers (safety, health and welfare) Act, 1986 (54 of 1986) or (ii) Possesses a recognised degree or diploma in engineering or technology and has had experience of not less than 5 years, fulltime on training, education, consultancy, or research in the field of accident prevention in industry or in any institution, shall also be eligible for appointment as a safety officer:

TABLE-2 : QUALIFICATION, EXPERIENCE AND NUMBER OF SAFETY PROFESSIONALS FOR CONSTRUCTION PROJECTS (CONTD.)

Category of safety person	Mandatory requirement	Qualification
		Provided that competent authority may, subject to such condition as it may specify, grant exemption from the requirement of this sub rule if in its opinion, a suitable person possessing the necessary qualification and experience is not available for appointment.
Safety supervisor	One in each shift (minimum) up to 500 workers or One Supervisor for any hazardous job (listed in para 9.11) if, carried out by Contractor irrespective of number of workers. If number of persons working in a shift (including the contractors' workers) exceeds 500, additionally one safety supervisor should be deployed for every 500 workers or part thereof.	Diploma in engineering and diploma in industrial safety

9. SAFETY MANAGEMENT

9.1 General

The construction agencies (contractors) shall be asked to submit a project specific health and safety plan (construction safety management plan) proposing the methodology for managing health and safety and their capability in completing the project in a safe manner.

9.2 Safety Policy

(a) The facility and the construction agency jointly or separately shall have a written statement prescribing the health and safety policy of the organisation. The health and safety policy conveys the management commitment and intent of the organisation towards health and safety, its organisation and arrangements to ensure that the set objectives are met. It also provides a framework for establishing, maintaining and periodically reviewing health and safety objectives and targets.

(b) Health and safety policy shall meet the requirements of *Building and other Construction Workers (Regulation of Employment and Conditions of Service) Act*, 1996 and IS 18001.

(c) The policy shall be communicated to all stakeholders through display and other means. The policy shall be displayed in local language(s) which may be understood by majority of the workmen.

9.3 Safety Plan

(a) A project specific health and safety plan shall be developed by the contractor and approved by the facility. On approval by the facility, health and safety plan shall be reference document for implementation, control and monitoring of health and safety aspects of the project by the Contractor.

(b) Project health and safety plan shall describe how the project specific health and safety objectives and targets shall be achieved. It shall define the road map for achieving the standards that an organisation lays down for itself so that efforts can be coordinated, synergized and monitored.

(c) Health and safety plan shall explain the means of establishing a positive health and safety culture at the project site. Health and safety plan shall identify and enumerate the control measures to mitigate the risks to the project completion arising out of health and safety issues so that the project is allowed to proceed without interruption and executed as per schedule.

Salient aspects that may be covered in the project health and safety plan are:

(i) Project specific health and safety objectives, targets and programmes in line with health and safety policy.

(ii) Hazard identification and risk assessment

(iii) Meeting legal and other requirements

(iv) Health and safety organisation

(v) Resources, roles, responsibility and authority

(vi) General health and safety rules

(vii) Health and safety requirements to be followed by sub-contractors

(viii) Operation control procedure

(ix) Activities requiring work permit system and its procedure

(x) Management of traffic safety inside the project

(xi) Access control of employees

(xii) Safety of visitors

(xiii) Management of critical activities such as work at height, material handling, working with plant and machinery, etc.

(xiv) Safe handling of chemicals, explosives, gas cylinders, electrical equipment etc.

(xv) Ensuring the competency and awareness of the workmen

(xvi) Fire prevention and fire fighting plan

(xvii) Emergency preparedness and response plan

(xviii) Traffic management plan

(xix) Training matrix

(xx) Personal protective equipment matrix

(xxi) Health and safety performance monitoring measures such as inspection and audit

(xxii) Incident reporting and investigation procedure

(xxiii) Proactive and reactive indicators of health and safety

(xxiv) Reward and reprimand for health and safety performance

(xxv) Checklist and formats.

(xxvi) Health monitoring plan for employees/workers exposed to hazardous jobs.

(d) The risk control measures identified shall meet the provisions of *Building and other Construction Workers (Regulation of Employment and Conditions of Service) Act*, 1996, other legislations and provisions of various safety related standards.

(e) Procedures shall be established for timely recording and reporting of information required for continual improvement of health and safety performance.

Internal reporting procedures shall cover:

(i) Incident reporting

(ii) Non-conformance reporting

(iii) Health and safety performance reporting

(iv) Hazard identification reporting

External reporting shall cover

(i) Statutory reporting requirements

The recording of reporting of health and safety performance shall be clearly documented in the health and safety plan.

9.4 Roles, Responsibility and Authority

(a) Contractor shall define, document and communicate the roles, responsibilities and authorities of all personnel who manage, perform and verify activities having an effect on health and safety risks. It shall also include subcontractors and visitors.

(b) The line management personnel who are responsible for execution of activities are directly responsible for health and safety in the work under their control.

(c) Health and safety group and health and safety officers are responsible for guiding the top management of their own organisation on health and safety issues and facilitating the implementation of health and safety in the project site. For duties and responsibilities of health and safety officers refer Atomic Energy (Factories) Rules-1996.

(d) Health and safety supervisors shall be engaged to assist the health and safety officers in performing their duties.

(e) Management shall provide adequate resources essential to effectively manage the health and safety management system requirements of the project.

9.5 Design and Engineering

(a) Design drawings, construction methodology and plans shall be reviewed to determine whether any additional risks may arise during the construction due to the features in the design or methodology.

Attention shall be paid to:

(i) Providing permanent hooks and loops for tying safety slings of workers

(ii) Providing holes or such arrangements to the structure to which safe working platforms and safety nets can be connected

(iii) Laying permanent slings, grab rails/bars to be used by the workers

(iv) Permanent provision for attaching railings

(v) Provision for alternative access to the trapped or distressed workers

(vi) Provision for communication

(vii) Design facilitating barricading of the area around work site without causing hindrance to building functional activities

(viii) Durability of such safety related permanent design integrated elements

(ix) Other safety practices required for the type of woks involved

(x) Significant risks from construction materials, which cannot be avoided in the design.

(b) Analysis of design and integration of safety measures, as described above, should be undertaken as value engineering through multi-stakeholder consultation, necessarily involving designers, owner/ client, operation/maintenance management and construction agency.

(c) While need for special work methodology and enabling infrastructure is considered to make conditions safe for construction, attention shall also be drawn to the safety during maintenance operations (including inspections which may be necessary before project commissioning as well as maintenance).

(d) It shall also be ascertained whether it would be feasible (within the time and cost considerations) to erect necessary temporary enabling infrastructure. If, in the due assessment by the project manager, it is established that the design, as proposed, would continue to be unsafe during construction and maintenance operations unless special enabling infrastructure is created and work procedures specifically drawn, the design shall be reviewed.

9.6 Construction Planning

(a) Prior to the start of construction work, detailed planning shall be carried out which may include:

(i) Identifying aspects of design that have bearing on health and safety during construction stage.

(ii) While scheduling the various activities of the construction, allowing adequate time to carry work in accordance with health and safety requirements.

(iii) Reviewing the proposed work method of various activities, identifying health and safety hazards of activities in the project and assessment of the risk level.

(iv) When the risk level is unacceptable, taking additional control measures including revision of the work methodology so that identified risk is at ALARP (As Low as Reasonably Practicable) level.

(v) Planning and establishing the facilities for implementation of health and safety such as workmen training facility, health centre for medical check-up and first aid, access control of employees, etc.

(vi) Ensuring that the temporary establishments at project site such as site offices, workmen camps, toilets, canteens and rest sheds, etc. are created meeting the requirements of the relevant statutes and standards.

(b) Facility shall ensure that the construction agency has understood the challenges and has planned to meet the project specific health and safety requirement through appropriate competencies.

(c) Health and safety measures need proper coordination by the construction agency and such efforts of the construction agency shall be reviewed, monitored and appropriately guided by the facility.

(d) In respect of sub-contractors, project manager of the construction agency shall ensure that the sub-contractors meet the health and safety requirements of the project. Health and safety control and monitoring shall be established specific to the needs of the project.

9.7 Safety Communication

(a) Procedures shall be established to communicate significant hazards and risks to and from employees and other interested parties. The health and safety hazards and risks may be communicated in the following ways:

(i) Sharing of accidents case studies which occurred in the project site as well in other similar projects

(ii) Safety induction and orientation training

(iii) Health and safety posters and displays

(iv) Health and safety campaigns and competition involving the employees

(v) Sharing of results of the audits, inspections and other monitoring systems

(vi) Establishing a system for collecting feedback on health and safety from employees and other interested parties

(vii) Tool box meeting

(vii) Safety signage.

(b) Health and safety communications addressed to workmen shall preferably be in local language(s) understandable by majority of the workmen.

(c) The facility and construction agency shall jointly endeavour to promote a positive health and safety culture at the project. Top management of the organisations should exhibit a visible management commitment and felt leadership towards health and safety. This shall be achieved by participating in health and safety programmes such as:

(i) Project health and safety committee meeting

(ii) Health and safety walk down

(iii) Including health and safety in all performance review meetings

(iv) Exhibiting a safe behaviour while at site.

(d) The top management should clearly communicate that it considers safety as core value and it shall not allow it to get compromised. Such messages when it reaches down the level in the organisation enable to create a positive health and safety culture.

9.8 Safety Monitoring Programme

(a) The objective of the safety surveillance programme should address assurance of effective implementation of safety measures in execution of works. Following surveillance programme should be in place at sites. The safety organisation should monitor, maintain record and follow up for corrective actions.

(b) The surveillance programme should consist of identification of safety related deficiencies and status of corrections thereof, the implementation of protective measures, the safe work practices, human behavior etc.

(c) Specific surveillance should be ensured with respect to testing of equipment, portable power tools, electrical equipment and tools, hand tools, surveillance of material handling equipment, transport equipment, earth moving equipment, gas cylinders, stores, etc. to comply with various statutory requirements.

(d) Surveillance on safety awareness and training compliance including induction training, on the job training and refresher training, job specific pre-job briefing, job hazard analysis, etc. as per facility's guidelines should be ensured.

(e) Safety related deficiencies (SRDs) shall be detected by any employees/worker of construction agency and communicated to the line manager for corrective actions. The corrective action shall be monitored and records shall be maintained.

(f) Systematic updating of SRDs attended and pending should be made available by the contractor for verification of facility.

(g) The health and safety performance monitoring and measurement procedures shall provide for:

  (i) Both qualitative and quantitative measures appropriate to the project

  (ii) Monitoring the extent to which project health and safety objectives are met

  (iii) Proactive measures of compliance that measures compliance with health and safety plan, operational control procedures and legislation

  (iv) Reactive measures of performance to monitor accidents, ill health, near misses and non-conformances

  (v) Monitoring dangerous occurrences

  (vi) Fire occurrences

  (vii) First aid injuries.

(h) Health and safety inspections shall be preferably conducted by a team of the concerned engineer, health and safety officer and area in-charge of the contractor.

(i) The type of inspections that shall be carried out and the frequency shall be decided during the planning stage and documented in the project health and safety plan. The health and safety inspections should include:

(i) General site health and safety inspection

(ii) Electrical safety inspection

(iii) Plant and machinery inspection

(iv) Health and hygiene inspection

(v) Scaffolding safety inspection.

(vi) Portable tools and tackles

(vii) Lifting tools and tackles

(viii) Fire equipment inspections

(ix) Illumination level and noise level monitoring

(j) Status of health and safety implementation shall be measured and monitored by several proactive indicators which include the following:

(i) Compliance level of project health and safety plan

(ii) Compliance level of health and safety observations with in the target date

(iii) Implementation status of training plan

(iv) Implementation status of corrective and preventive actions

(v) Compliance level of pre-employment medical checks and periodic medical checkups

(vi) Compliance level of legal and other requirements

(vii) Percentage of activities for which detailed project specific risk assessment is conducted.

(k) Procedures shall be established to report, investigate and analyze incidents. The procedures shall involve:

(i) Members of the incident investigation team

(ii) Agencies to be reported in case of incidents

(iii) Time period within which incidents need to be reported

(iv) Methodology for investigation and determining the root cause of accidents.

These procedures shall form a part of the project health and safety plan and monitored on a regular basis for its effectiveness.

(l) All incidents including near miss cases, accidents and dangerous occurrences shall be thoroughly investigated, direct and root causes determined and corrective action planned. Incidents may be analysed covering the following ways to prepare and implement an effective prevention plan:

(i) Body part injured

(ii) Age of the victims

(iii) Time of accidents

(iv) Causes of accidents

(v) Nature of injury.

For detailed guidelines on analysis of incidents and computation of injury rate refer IS 3786.

(m) The following reactive health and safety indicators should be used to measure and monitor the health and safety performance of the project site:

(i) Number of near miss cases

(ii) Number of first aid cases

(iii) Lost time injury frequency rate

(iv) Lost time injury severity rate.

(n) The health and safety performance of subcontractors shall be monitored on a regular basis and necessary directive and support shall be given to achieve the set health and safety objectives and targets.

(o) All accidents leading to property damage/personnel injuries/fatal accident/near miss and dangerous occurrence should be reported to the facility's engineer-in-charge immediately

(p) All 'near-miss' accidents should also be recorded/reported and investigated and recommendations arising out should be implemented on priority.

9.9 Training/Orientation

(a) It shall be ensured that all employees are competent to perform the assigned work safely on the basis of appropriate education, training or experience. The competency requirements of different categories of employees shall be mapped and procedures shall be implemented to ensure that those deployed meet the competence requirements.

(b) The objective of health and safety training shall be to equip the employee with necessary knowledge and skill to perform the work assigned to him in a safe manner, to foster continual improvement and to imbibe safety culture.

(c) Preferably, the training should be carried out away from the working place of the participants to ensure focused attention on the training for both trainer as well as trainees.

(d) After completion of training due procedure shall be followed for obtaining the feedback from the participants on the effectiveness of the training. Effectiveness of training imparted shall be monitored for continual improvement and necessary corrections in implementation.

(e) The training/orientation programme should be implemented to meet the mandatory requirements. [Rule 43(2) (m) of the Atomic Energy (Factories) Rules 1996]. The training should be phased as follows:

(f) Induction cum orientation training should include the overall safety aspects of the work and give a general overview of the various hazards, the particular activities and the do's and don'ts. As a part of training, workers should also be given demonstrations on use of personal protective equipment, first aid and fire-fighting equipment, fire mock drills, other emergency preparedness etc.

(g) The line manager along with the safety representative should conduct pre-job briefing on day-to-day basis prior to specific hazardous jobs. This will make the workers aware of the hazards and the precautions to be taken.

(h) Refresher training should be imparted to each worker at least once in a year.

(i) A training schedule should be prepared by the construction agency and communicated to facility for concurrence.

(j) Records of training, demonstration and pep talk should be maintained.

9.10 Permit to Work System

(a) Activities requiring permit to work shall be decided before starting the construction and shall be suitably documented in the project health and safety plan. Some of the activities which shall require permit to work are:

(i) Excavation

(ii) Entry into confined spaces

(iii) Electrical work (HV/LV)

(iv) Opening manholes, covers and grills

(v) Blasting operation

(vi) Hot work

(vii) Work on plant and machinery and other power driven equipment

(viii) Working at height

(ix) Working at night

(b) The contractor should establish a permit to work system for any other hazardous activity, which it feels necessary to be controlled administratively for safe execution.

(c) Contractor should obtain valid safety work permit before carrying out any hazardous job and shall maintain a copy of it with him through out the period of his work. Record of safety work permit should be maintained in a systematic manner. All the safety conditions and requirements stipulated in the safety work permit should be ensured strictly.

(d) Contractor should ensure that only authorized personnel are deployed for hazardous works/jobs (refer item 3.11 for hazardous job) and provide facilities for the same.

9.11 Job Hazard Analysis

(a) It should be ensured by contractor that a safe work procedure exists for all the hazardous jobs as mentioned hereunder and the requirements of the safety procedures are ensured at the work sites. Job hazard analysis (JHA) should form a part of such safe work procedures. A checklist based on JHA should be prepared. This checklist should be crosschecked by the line managers and verified by safety officer.

Typical list of jobs requiring job hazard analysis (This list is illustrative only and not exhaustive) is as follows:

(i) Excavation

(a) Blasting including under water blasting

(b) Earth and stone removal/backfilling/dumping of earth/ stones

(c) Any excavation more than 1.8 m depth.

(ii) Work at height (working beyond 3.5 meters above ground)

(a) Erection and dismantling of scaffolding, platforms, shuttering/de-shuttering work

(b) Dome work, rod bending, construction of chimney and cooling towers

(c) Working on tower crane.

(iii) Materials and material handling

(A) Critical equipment handling e.g.

(a) Calandria

(b) Steam generators

(c) Turbine generator components

(d) Diesel generator set

(e) Generator stator

(f) End shields

(g) Fuelling machines components

(h) Heat transport pumps etc.

(B) Hazardous chemical handling e.g.

(a) Acids and alkalis

(b) Ammonia

(c) Chlorine

(d) Freon

(e) Hydrazine

(f) Hydrogen sulphide

(g) LPG

(h) Morpholine

(C) Movement of heavy material by crane

(D) Movement of tractor trolley on slopes

(E) Manual lifting of heavy material to height

(F) Erection of heavy machinery, equipment.

(iv) Electrical connection

(a) Field connection for electrical installation

(b) Installation of lighting fixtures

(c) Charging of electrical system

(d) Charging of transformer, switch yard, switch gears

(e) Working near high voltage lines

(f) Use of portable electrical tools.

(v) Equipment/structural erection work

(a) Material handling

(b) Loading and unloading

(c) Transportation of material from one place to other

(d) Steel fabrication and erection

(e) Cleaning and maintenance of batching plant equipment.

(vi) Finishing/painting work

(a) Painting at height

(b) Painting in confined space.

(viii) Other specific work

(a) Work with pneumatic tools/compressed air

(b) Work on pressure vessels/lines

(c) Work in the vicinity of steam lines

(d) Work in high enthalpy area

(e) Work in high noise area

(f) Work in confined space including tunnels and trenches

(g) Work in isolated area (away from main site)

(h) Radiography work

(i) Work related to welding, gas cutting, grinding

(j) Working near conveyor, rotating machine

(k) Leak detection testing.

9.12 Reward

(a) To motivate the employees and organisation to work safely measures can be implemented based on the suitability. Selection and rewarding for the following categories may be considered on regular basis:

(i) Safest workmen

(ii) Safest supervisor

(iii) Safest area

(iv) Safest sub-contractor, etc.

(v) Sub-contractors and employees may be rewarded when the project achieves significant million man-hours without any lost time injury.

10. WORK SPECIFIC SAFETY MEASURES

10.1 General

(a) The contractor should ensure that safety precautions are taken during the execution of awarded work and work areas are maintained safe at all times. At the end of each shift and at all times when the work is suspended, it should be ensured that the work area is left safe in such a way that no materials and equipment that can cause damage to existing property, personal injury or interfere with the other works of the project or station are left in an unsafe manner.

(b) The contractor should ensure to provide and maintain all lights, guards, fencing, warning signs, caution boards and other safety measures and provide for vigilance as and when necessary for the protection of workers and for the safety of others. The caution boards should also have appropriate symbols.

(c) Adequate lighting facilities such as floodlights, hand lights and area lighting should be provided at the site of work, storage area of materials and equipment and temporary access roads within the working area.

(d) All works should be planned so as to avoid interference with other facilities, works of other contractors or sub-contractors at the site. In case of any interference, necessary coordination should be ensured for safe and smooth working.

(e) It should be ensured that the instructions given by the safety officer or his designated nominee regarding safety precautions, protective measures, housekeeping requirements, etc. are complied with. The safety officer with due intimation to line manager should have the right to stop the work, if in his opinion, proceeding with the work will lead to an unsafe and dangerous condition. Line manager should arrange to get the unsafe condition rectified and/or provide appropriate protective equipment.

(f) Contractor should ensure that each job with a hazard whether small or big is intimated to the Head, industrial safety of the facility well before it is taken up.

(g) The contractor should be fully responsible for non-compliance of any of the safety measures or requirements, implications, injuries, fatalities, dangerous occurrences and compensation arising out of such situations or incidents.

(h) Maximum duty hours of an individual should be as per the Factories Act 1948 or its latest amendment.

(i) Illumination levels should be as per the statutory requirements.

10.2 Rock Blasting

(a) All blasting operations should be carried out on the basis of procedures approved by Head, industrial safety and engineer-in-charge. All works in this connection should be carried out as per BIS specification/code (IS 4081: 1986. Title:- Safety code for blasting and related drilling operations (First Revision)). Barricades, warning signs etc. should be placed on the roads/open area.

(b) Blasting permit should be obtained from Head, Industrial Safety at least one day before the blasting operation and precautions mentioned there in shall be ensured by the engineer-in-charge before blasting operation.

(c) The blaster should have a licence from competent authority under Explosive Rules, 1983 for blasting work. It should also be ensured that he knows about the risks involved.

(d) Blasting should be done under the supervision of competent engineer/ supervisor.

(e) Blasting in the open site should only be carried out during fixed hours every day/fixed day in the week between sunrise and sunset. Residents of adjacent area should be informed in advance about the blasting schedule.

(f) No blasting should be undertaken during thunderstorm.

(g) Necessary precaution should be taken to ensure the stability/integrity/ safety of the adjacent structure by limiting the peak particle velocity.

(h) No loose material, such as tools, drilling equipment, etc. should be left on the surface to be blasted. Proper muffling arrangement of the blasting area should be ensured to avoid flying of blasted material.

(i) Authorized blaster should personally ensure that all the personnel/ equipment has been removed from the blasting area before the blasting operations.

(j) Blasting area should be free of detonating gas, inflammable objects, sparking or damaged wiring system, stray currents and static electricity.

(k) All electrical lines in blasting area should be de-energised.

(l) Entry of unauthorized personnel should be prevented by displaying warning signs.

(m) In case of misfire, no person should be allowed to approach the blasting site unless it is inspected and cleared by a competent engineer/supervisor.

(n) Explosives and blasting material should be stored only in clean, dry, well-ventilated, suitably constructed bullet/magazine which should be fire resistant and securely locked. Stock book should be kept accurate and maintained. Licence should be obtained for storage of explosive as per the Explosives Act, 1884.

(o) Blasting caps, electric blasting caps or primers and detonators should not be stored in the same box, container or room with other explosives.

(p) Precautions against lightening should be provided in accordance with Indian Electricity Rules, 1956 (amended in 2000).

(q) The explosives should be transported in specially designed vehicles bearing a special sign or inscription entitled 'DANGER-EXPLOSIVES'. Also detonators separated from other explosive should be transported in a separate compartment.

10.3 Excavation, Trenching and Earth Removal

(a) Before taking up excavation work, necessary permission should be obtained from the engineer-in-charge with reference to existing underground services.

(b) The Line manager of the works should exercise full care to ensure that no damage is caused by him or his workmen, during the operation/excavation etc., to the existing water supply, sewerages, power or telecommunication lines or any other services or works. He should provide and erect before construction, substantial barricades, guardrails, and warning signs around the work area. He should also furnish, place and maintain adequate warning lights, display board, signals etc., as required.

(c) All trenches 1.2 m or more in depth should at all times be supplied with at least one ladder for every 30 m along the trench. Ladders shall extend from bottom of the trench to at least 1 m above the surface of the ground.

(d) The sides of the trench/pit in soil, which are 1.2 m or more in depth should be stepped back to give suitable slope (angle of repose) or securely held by timber bracing or appropriate shoring/support, to avoid the danger of soil slides from collapsing. The excavated material should not be placed within 1.5 m or half of the depth of the pit whichever is more from edges of the trench/pit. Cutting should

be done from top to bottom. Under no circumstances mining or under-cutting should be done.

(e) Workers should not be exposed to the danger of being buried by excavated material or collapse of shoring. Measures to prevent dislodgment of loose or unstable earth, rock or other material from falling into the excavation by proper shoring shall be ensured.

(f) The stability and safety of the excavation, adjacent structures, services and other works should be ensured.

(g) All excavated area should be fenced off by suitable railing and installation of caution board to warn the persons from slipping or/ falling into the excavation pit/ mound.

(h) All excavated areas shall have an illumination level of at least 20 lux for night work and a red danger light shall be displayed at prominent place near the excavation site to warn approaching traffic and men.

(i) For removal of earth from an earth mound/excavated heap a written permission should be obtained from the engineer-in-charge of the work. As far as practical, earth should be removed mechanically. Wherever manual removal of earth is involved, earth should be removed from the top by maintaining a slope equal to the angle of re-pose of the earth. Such work should be constantly supervised to ensure that no under-cutting is done and to ensure that no person is trapped.

(j) Dumping of excavated soil should be done at a specified area under proper supervision with respect to signaling, illumination and safety clearance.

(k) It should be ensured that at a construction site of a building or other construction work, every vehicle or earth moving equipment is equipped with (a) silencers, (b) tail lights, (c) power and hand brakes, (d) reversing alarm (e) search light for forward and backward movement, which are required for the safe operation of such vehicle or earth moving equipment and (f) the cab of the vehicle or earth moving equipment is kept at least one meter from the adjacent face of a ground being excavated. (g) indicator etc.

(l) It should be ensured that when a crane or shovel is traveling, the boom of such crane or shovel is in the direction of such travel and the bucket or scoop attached to such crane or shovel is raised and without load, except when it is traveling downhill.

(m) Before loading or unloading power trucks or trailers attached to tractors, the brakes should be applied and if vehicle is on a sloping

ground, the wheels should be blocked. Handcart should not be used for the transfer of construction/erection materials in the construction area. However if the exigency demands urgent transfer of light materials a small handcart may be permitted with the prior approval of the Engineer-in-charge.

(n) It should be ensured that at a construction site of a building or other construction work:

(i) All transport or earth moving equipment and vehicles are inspected at least once in a week by responsible persons and in case any defect is noticed in such equipment or vehicle, it is immediately taken out of service.

(ii) Safe gangways are provided for to and fro movement of building workers engaged in loading and unloading of lorries, trucks, trailers and wagons.

(iii) All earth moving equipment, vehicles or other transport equipment be operated only by such persons who are adequately trained and possess such skills as required for safe operation of vehicles or other transport equipment.

(iv) Trucks and other equipment are not loaded beyond their safe carrying capacity, which should be clearly marked on such trucks and other equipment.

(v) No unauthorised person rides the transport equipment employed in such work.

(o) It should be ensured at a construction site of a building or other construction work that:

(i) A shovel or an excavator whether operated by steam or electric or by internal combustion used for such work is constructed, installed, operated, tested and examined as required under any law for the time being in force and the relevant national standards.

(ii) Buckets or grabs of power shovels are propped to restrict the movement of such bucket or grabs while being repaired or while the teeth of such bucket or grabs are being changed.

(p) It should be ensured at a construction site of a building or other construction work that:

(i) An operator of a bulldozer before leaving - applies the brakes, lowers the blade and ripper and puts the shift lever into neutral.

(ii) A bulldozer is parked on level ground at the close of the work.

(iii) The blade of a bulldozer is kept low when such bulldozer is moving uphill.

(iv) Bulldozer blades are not used as brakes except in an emergency.

(q) It should be ensured at a construction site of a building or other construction work that:

(i) A tractor and a scraper are joined safely at the time of its operation

(ii) The scraper bowls are propped while blades of such scraper are being replaced.

(iii) A scraper moving downhill is driven in low gear.

(r) It should be ensured at a construction site of a building or other construction work that:

(i) Before a road roller is used on the ground, such ground is examined for its bearing capacity and general safety, especially at the edges of slopes such as embankments on such grounds.

(ii) A roller is not moved down hill with the engine out of gear.

(s) Vehicle carrying excavated material should have proper cover over the driver's cabin.

10.4 Safe Means of Access/Platforms

(a) Adequate safe means of access and exit should be provided for all work places, at all elevations.

(b) Suitable scaffolds should be provided for workmen for all works that cannot be done safely from the ground, or from solid platform except such short duration work that can be done safely from ladders. Bamboo/wooden scaffolding should not be permitted.

(c) Where the platform for working is more than 3.5 m above ground, the width of the platform should be minimum 1 m.

(d) Ladder should be of rigid construction having sufficient strength for the intended loads. Wooden/bamboo/rope ladders should not be permitted. All ladders should be maintained in good condition. The ladders should be fixed to the ground or rigid platforms. An additional person should be engaged for holding the ladder, if ladder is not securely fixed. Ladder shall be extended from floor to at least one meter above the platform.

(e) A portable ladder should be given an inclination not steeper than 1 in 4 (1 horizontal and 4 vertical). Ladders should not be used for climbing while carrying materials in hands. While climbing both the hands should be free.

(f) Any working platform on scaffolding or staging more than 3.5 m above the ground or floor should have a guard rail attached, bolted, braced at least 1.0 m high above the floor or platform of such scaffolding or staging along with mid-rail.

(g) The planks used for any working platform should not project beyond the end supports to a distance exceeding four times the thickness of the planks used. The planks should be rigidly fixed at both ends to prevent sliding, slipping or tilting. The thickness of the planks should be adequate to take load of men and materials and should not collapse. Plywood or packing wood should not be used as planks.

(h) The guardrail should extend along the entire exposed length of the scaffolding with only such opening as may be necessary for the delivery of materials. Standard railing should have posts not more than 2 m apart and an intermediate rail halfway between the floor or platform of the scaffolding and the top rail. Such scaffolding or staging should be so fastened as to prevent it from swaying from the building or structure. Scaffolding and ladder should conform to IS 3696 (Part I): 1987 and (Part II): 1996.

(i) Working platforms of scaffolds should have toe boards at least 15 cm in height to prevent materials from falling down.

(j) A sketch of the scaffolding proposed to be used should be prepared and approval by the engineer-in-charge obtained prior to start of erection of scaffolding. All scaffolds should be examined by engineer-in-charge before use.

(k) Working platform, gangways and stairways should be so constructed that they should not sag unduly or unequally and if the height of the platform or gangway or stairway is more than 3.5 m above ground level or floor level, they should have adequate width for easy movement of persons and materials and should be suitably guarded.

(l) No single portable ladder should be used for access to a height of more than 4.5 m. For ladders up to 3m in length the width between styles (side bars)/width in the ladder should in no case be less than 300 mm. For longer ladders this width should be increased by at least 20 mm for each additional meter of length. Step/rungs spacing should be uniform and should not exceed 300 mm. Portable ladder should be used only for access to work place. In case work place is higher than 4.5 meters, pre-fabricated steel staircase should be used.

10.5 Work at Height

(a) Person to work at height should be medically fit and should have height pass issued by safety section. (Appendix-D Part A, B and C). Safety training should be imparted before working at height.

(b) Safety work-permit system for working at height should be obtained from industrial safety section.

(c) At elevated places, secure access and foothold should be provided. Adequate and safe means of access and exit should be provided at all work places for all elevations. Means of access may be portable or fixed ladder, ramp or a stairway. The use of crosses, braces or framework, as a means of access to the working platform should not be permitted.

(d) Linear movement at height should be reduced to minimum. In case of such movement provision for anchoring the safety belt should be made.

(e) Where barricades cannot be installed, a safety net of adequate strength should be installed close to the level at which there is a danger of fall of personnel/fall of objects.

(f) In case where 'work at height' is on asbestos roof, crawling board/ roof ladder should be used to walk across the asbestos roof.

10.6 Electrical Safety

(a) All electrical installations shall comply with the appropriate statutory requirements given below and shall be subject to approval of the Electrical Engineer and Safety Officer.

(i) The Electricity Act, 2003

(ii) The Indian Electricity Rules 1956 (as amended in 2000)

(iii) The National Electricity Code 2008

(iv) Atomic Energy (Factories) Rules, 1996

(v) Other relevant rules of Statutory Bodies and power supply authority

(vi) Relevant standards of BIS

In addition to the above statutory provisions, the clauses indicated in this document shall also be complied.

(b) It shall be the responsibility of the user seeking temporary power supply to indicate in writing, if any of the clauses (requirements

noted in above regulations and in this document) are conflicting with each other and for which the user cannot decide the course of action regarding safe installation, commissioning, operation, maintenance and decommissioning of the electrical installations.

(c) The electrical engineer and safety officer of the agency providing temporary power supply shall interpret the concerned conflicting clauses and approve in writing the safe course of action.

(d) The application Form-1 (Form-1A, 1B and 1C) as mentioned in Appendix-E should be submitted by the user for getting the temporary power supply.

(e) After installation of temporary electrical panels, wiring works by the user, Certificates as per Form-1D (Appendix-E) should be submitted to the provider.

(f) Certificate of safety officer and authorization of electrical engineer for energisation of temporary power supply should be filled as per Form-1E (Appendix-E).

10.7 Material Handling and Lifting Machines and Tackles

(a) It should be made compulsory to supervise jobs like lifting/placing/ loading/unloading/carrying/transporting etc. of heavy material by qualified supervisor having knowledge about hazards involved and precautions to be taken for such job.

(b) The line managers should ensure that the material handling equipment used is adequate to handle the load.

(c) Manual pulling of heavy equipment and trolley loaded with heavy material is not to be permitted.

(d) Stacking and handling of heavy materials should be done on a firm ground to prevent settlement.

(e) No lifting machine and no chain, rope or lifting tackle, except a fiber rope or fiber rope sling, shall be taken into use for the first time in that factory unless it has been tested and all parts have been thoroughly examined by a competent person. A certificate of such a test and examination specifying the safe working load or loads and signed by the person making the test and the examination has been obtained and is kept available for inspection.

(f) Use of lifting machines and tackles should conform to relevant BIS requirements [IS 13367 (Part 1): 1992 Reaffirmed 2003, IS 4573: 1982 (Reaffirmed 2000) and IS 13834 (Part 1): 1994 Reaffirmed 2003 etc. The accessories and the attachments, anchorages and

supports etc. should be ensured in healthy conditions by regular inspections at defined frequencies.

(g) Every rope used in hoisting or lowering materials or as a means of suspension should be of good quality and adequate strength and free from any defect. This should be ensured by regular inspection as per IS 2762: 1982- Specification for wire rope slings and sling legs (first revision).

(h) Every crane operator or lifting appliance operator should be authorized. No person under the age of 18 years should be in charge of any hoisting machine or give signal to an operator of such machine.

(i) In case of every lifting machine (and of every chain, ring, hook, shackle, swivel and pulley block used in hoisting or as a means of suspension) the safe working load should be ascertained and clearly marked. In case of a lifting machine having a variable safe working load, each safe working load and the conditions under which it is applicable should be clearly indicated. No part of any machine should be loaded beyond the safe working load except for the purpose of testing. This should be approved by the engineer-in-charge and Head, Industrial Safety.

(j) In case of facilities machines, the safety of the machines shall be ensured by the Engineer-in-charge. As regards the Contractor's machines, the contractor should declare the safety of the machine to the Engineer-in-charge whenever he brings any machinery to site of work and get it verified by the engineer-in-charge, supported by a valid test certificate by the competent person.

(k) Thorough inspection and load testing of lifting machines and tackles should be done in the presence of competent person at least once in every 12 months and records of such inspections and testing should be maintained.

(l) No mobile crane should be allowed to move under live high-tension power transmission line.

(m) While lifting loads, cranes should be located on level ground.

(n) A thorough load analysis should be carried out before using cranes in tandem.

(o) Motors, gear transmission, couplings, belts, chain drives and other moving parts of hoisting appliances should be provided with adequate safeguards. Hoisting appliances should be provided with such means, which will reduce the risk of any part of a suspended load becoming accidentally displaced or lowered.

(p) It should be ensured that the cabin of the lifting machine in outdoor service:

(i) is made of fire resistant material,

(ii) has a suitable seat, a footrest and protection from vibration,

(iii) affords the operator an adequate view of the area of operation,

(iv) affords the operator adequate protection against the weather, and

(v) is provided with fire extinguisher.

10.8 Welding and Gas Cutting

(a) Welding and gas cutting operations should be done by qualified and authorized persons only.

(b) Safety work permit shall be obtained (wherever necessary like presence of flammable or combustible material etc.) before flame cutting/welding is taken up.

(c) Welding and gas cutting should not be carried out in places where flammable or combustible materials are kept and where there is danger of explosion due to presence of gaseous mixtures. In case the requirement cannot be avoided, specific approval and procedure should be ensured and adequate precautions should be taken.

(d) Welding and gas cutting equipment including hoses and cables should be maintained in good condition.

(e) Barriers should be erected to protect other persons from harmful rays from the work. When welding or gas cutting is done in elevated positions, precautions should be taken to prevent sparks or hot metal falling below on persons or combustible materials.

(f) Suitable type of protective clothing consisting of fire resistant gauntlet gloves, leggings, boots and aprons should be provided to workers as protection from heat and hot metal splashes. Face shields with filter glasses of appropriate shade should be worn.

(g) Adequate ventilation should be provided while welding, brazing and cutting the metals like zinc, brass, bronze, galvanised or lead coated material.

(h) Welding and gas cutting on drums, barrels, tanks or other containers should be taken up only after ascertaining that they have been emptied, cleaned thoroughly and made free of flammable material.

(i) Fire safety measures should be available as required near the location of welding/cutting operations.

(j) Flash back arrestor should be provided with gas cutting and gas welding sets.

(k) For electric (Arc) welding the following additional safety precautions should be taken:

(i) When electrical welding is undertaken the return lead of welding machine should be directly connected to the job invariably.

(ii) Provision must be in place in electric welding machine to prevent physical contact with live parts.

(iii) The welding cables and power cables should be routed separately to avoid entanglement.

(iv) The electric welding set should have suitable earth connections. There should be an electrical isolation device in the input power supply side on the welding machine.

(l) Double gauges should be used for all gas cylinders used for cutting/ welding. Pressure gauges/regulators should be in healthy condition.

10.9 Rotary Cutters/Grinders

(a) All portable cutter/grinders should be provided with the wheel guard in position.

(b) Grinding wheels of specified diameter only should be used on all grinders in order to limit the prescribed peripheral speed.

(c) In pedestal grinder, the gap between tool rest and grinding wheel should be maintained less than 3 mm.

(d) Goggle/face shield should be used during grinding operation.

(e) No grinding wheel should be used after its expiry date.

(f) Ear muff/ear plug should be used during the welding /cutting jobs.

(g) Portable appliances, which are powered by single phase AC supply, shall be provided with three-core cable and three pin plug, otherwise the whole body should be double insulated.

(h) Safety work permit should be obtained (wherever necessary like presence of flammable or combustible material etc.) before grinding is taken up.

(i) Fire safety measures should be available as required near the location of grinding operations.

10.10 Concrete Mixing Equipment

(a) Cement bags should be stacked on wooden planks in dry and leak proof area, 150 mm to 200 mm from the floor and 450 mm away from walls. Height of the stack should not be more than 15 bags or 1.5 meters which ever is lower. Width of the stack should not be more than 4 bags or 3 meters. Lateral loading of the walls of the storage room by stacking should not be permitted. Stacking of the bags should not be used as a working platform.

(b) Shuttering and supporting structures should be of adequate strength and approved by engineer-in-charge. This should be ensured before concrete is poured.

(c) If the mixer has a charging skip the operator should ensure that the workmen are out of danger before the skip is lowered.

(d) Adequate walking platforms are to be provided in the reinforcement area to ensure safe walking for pouring concrete on the roof.

(e) When workmen are working/cleaning the inside of the drum of mixer, the power of the mixer should be switched off and 'Do not operate' tag should be provided. The plant operation and cleaning of mixing pan should be carried out as per equipment supplier's instructions.

(f) Interlocks between the cover and the mixer rotor shall be established to ensure that the agitator does not start when the cover is in open condition.

(g) It should be ensured that moving parts of the elevators, hoists, screens, bunkers, chutes and grouting equipment used for concrete work and of other equipment used for storing and transporting of ingredients of concrete are securely fenced to avoid contact of workers with such moving parts.

(h) It should be ensured that screw conveyors used for cement, lime and other dusty material are completely enclosed.

(i) Workers engaged for handling bulk cement in a confined place should be provided with tight fitting goggle, approved respirators and protective clothing, which will fit snugly around the neck, wrist and ankles.

(j) The following should be ensured for every pipe carrying pumped concrete:

  (i) The scaffolding carrying a pipe for pumped concrete should be strong enough to support such pipe at a time when such pipe is filled with concrete or water or any other liquid and to bear safely all the building workers who may be on such scaffold at such time.

(ii) Securely anchored at its end point and each curve on it.

(iii) Provided with an air release valve near the top of such pipe; and securely attached to a pump nozzle by a bolted collar or other adequate means.

(k) The following should be ensured while using the electric vibrators in concreting work at a construction site of a building or other construction work such that:

(i) Such vibrators are earthed.

(ii) The leads of such vibrators are heavily insulated.

(iii) The current is switched off when such vibrators are not in use.

10.11 Painting

(a) Appropriate breathing air respirators should be provided for use by the workers when paint is applied in the form of spray, or a surface having lead paint is dry rubbed or scraped.

(b) Only the quantity of paint, thinner and polish required for the day's work should be kept at the work spot. Excess storage should not be permitted at the work spot.

(c) Smoking, open flames or sources of ignition should not be allowed in places where paints, varnish, thinner and other flammable substances are stored, mixed or used. A caution board, with the instructions written in national language and regional language, 'SMOKING - STRICTLY PROHIBITED' should be displayed in the vicinity where painting is in progress or where paints are stored. Symbols should also be used on caution boards.

(d) All electrical equipment of paint storage room should be of explosion proof design. Suitable fire extinguishers / sand buckets should be kept available at places where flammable paints are stored, handled or used.

(e) When painting work/hot resin mix is done in a closed room or in a confined space, adequate ventilation should be provided and ensured. In addition, suitable respirators should be provided. No portable electric light or any other electric appliance of voltage exceeding 24 volts should be permitted for use inside any confined space. Walkie-talkie or other means of communication should be provided. Rescue arrangement like full body harness with lifeline, tripod with pulley and extra BA sets should be available.

(f) The workers should use PVC gloves and/or suitable barrier creams to prevent the skin contact with Epoxy resins and their formulations used for painting.

10.12 Demolition

(a) Before any demolition work is commenced and also during the progress of the work, all roads and open area adjacent to the work site should either be closed or suitably cordoned. Appropriate warning signs should be displayed for cautioning approaching persons/ vehicles.

(b) Before demolition operations begin, it should be ensured that all the service lines are de-energized.

(c) Persons handling demolition operations shall use appropriate PPE.

(d) All demolition operations should be carried out with safe and duly approved procedures which shall include following but not limited to:

(i) No masonry/material should be permitted to fall in such masses or volume or weight so as to endanger the structural stability of any floor or structural support.

(ii) No wall, chimney or other structure or part of a structure is left unguarded in such a condition that it may fall, collapse or weaken due to wind pressure or vibration.

(iii) No floor roof or other part of the building should be overloaded with debris or materials as to render it unsafe.

(e) After the demolition, the debris and other materials collected should be disposed safely and not permitted to be dropped freely.

(f) Entries to the demolition area shall be restricted to authorized persons wearing safety helmets and safety shoes.

10.13 Traffic

(a) All the vehicles moving at sites should conform and comply with the requirements of Motor Vehicles Act, 1988 and the Rules made thereunder. All the drivers /operators of vehicles should possess valid driving license as per Motor Vehicles Act, 1988 or its latest amendment.

(b) When the construction work causes interference with traffic such as road cutting or transit unloading of heavy equipment etc. notice of such interference should be given to the engineer-in-charge and Head, industrial safety well in advance with the details of start of the work and time required.

(c) A cleaner/assistant must be available for all heavy vehicles whenever vehicles move forward as well as in the reverse direction. All vehicles should be fitted with proper reverse horns, back view mirrors and indicator signals.

(d) Facility shall ensure that the assessment of the driver's visual ability is carried out as per Rule 55 of the Atomic Energy (Factories) Rules, 1996/guidelines of advisory committee on occupational health (ACOH), AERB or as per the latest amendments in statutes.

(e) Effective speed breakers with yellow stripes on the roads to regulate the speed at the vulnerable points should be installed. Effective barricading with adequate caution signs should be placed to warn the vehicle drivers whenever the jobs are carried out on the road.

(f) All vehicles moving at the site should have roadworthiness certificate issued by the concerned authority.

(g) Special limit boards and caution boards indicating turns should be installed wherever necessary.

(h) In general, the following maximum speed limits should be specified and implemented. Vehicles speed limits should be as per Motor Vehicle Act or 20 Km/h. Extra precautions and care should be exercised particularly during heavy material/equipment movements.

(i) Safety awareness programmes should be conducted for all the drivers of the light, medium and heavy vehicles.

10.14 Work in Radiation Area

The facility shall follow the stipulations under Atomic Energy (Radiation Protection) Rules, 2004 and AERB Safety Manual on 'Radiation Protection for Nuclear Facilities'[AERB/NF/SM/O-2 (Rev.4)] with regard to work in the radiation area and other works related with radiography, etc.

10.15 Work in and Around Water Bodies

(a) When work is done at a place where there is risk of drowning, all necessary rescue equipment such as life buoys and life jackets should be provided and kept ready for use.

(b) All necessary steps shall be taken for prompt rescue of any person in danger and adequate provision should be made for prompt first-aid treatment of all injuries likely to be sustained during the course of the work. Proper record of entry/exit to and from water bodies shall be maintained on shift basis and search operation shall be conducted as soon as any person is detected to be missing.

(c) Caisson Work

(i) Safe means of access should be provided to the place of work in the caisson and adequate means should be provided to safely reach the top of caisson in the event of inrush of water.

(ii) The work relating to construction, positioning, modification or dismantling of caisson shall be done under the supervision of a responsible person.

10.16 Fire Safety

(a) Provisions prescribed in the AERB safety standard on 'Fire Protection Systems for Nuclear Facilities', [AERB/NF/SS/FPS (Rev. 1)] shall be complied.

(b) All necessary precautions should be taken to prevent outbreak of fires at the construction site. It should be ensured that all hot works are carried out under valid work permit.

(c) Combustible materials such as wood, cotton waste, oil, coal, paints, chemicals etc., should be segregated and kept to the required bare minimum quantity at work place.

(d) Containers of paints, thinners and allied materials should be stored in a separate room which should be well ventilated and free from excessive heat, sparks, flame or direct rays of the sun. The containers of paint should be kept covered or properly fitted with lid and should not be kept open except while using.

(e) Adequate number of trained persons from approved fire training centre required to extend fire safety coverage should be ensured.

(f) Fire extinguishers as approved by the engineer-in-charge/in-charge of fire station/safety in-charge should be located at the construction site at appropriate places.

(g) Adequate number of trained workmen in fire fighting who can operate fire extinguishers should be ensured.

(h) Portable fire extinguishers with periodic inspection, maintenance and re-filling complying with the mandatory requirements should be ensured.

(i) Availability of adequate water for fire fighting should be ensured.

(j) Implementation of the provisions of various statutory licenses for storing gas cylinders, petroleum products, explosives etc. as per the relevant Acts and Rules should be ensured wherever required.

10.17 Environmental Safety

Relevant provisions of the state/central statutory authority regarding environment protection should be adhered to.

10.18 Public Protection

The Contractor should make necessary provisions to protect the public. He should be bound to bear the expenses in defense of every action or other proceedings at law that may be brought by any person for injury sustained owing to neglect of any precaution required to be taken to protect the public. He should pay for the any such damage and cost which may be awarded in any such suit, action or proceedings to any such person, or the amount, which may be fixed as a compromise by any such person.

10.19 Safety of Visitors

(a) Visitors for the project shall be given health and safety induction before they are allowed in to the construction project. It shall include the minimum PPE to be used, hazards and risks at the work area, restricted areas of entry, emergency response arrangements, etc.

(b) Visitors shall always be accompanied by one of the employees of the project site.

(c) Visitors shall not be allowed in the hazardous areas unless they are competent and trained to work in such areas.

10.20 Housekeeping

(a) It should be recognized that a proper place for everything and everything in its place is maintained for a good housekeeping.

(b) The material required for immediate use only should be brought to the designated workplace and stacked properly and labeled suitably.

(c) All work spots, site office and surroundings should all times be kept clean and free from debris, scrap, concrete muck, surplus materials and unwanted tools and equipment. A day-to-day collection and disposal of scraps/debris should be done safely at designated place.

(d) Electrical cables should be so routed as to allow safe traffic by all concerned. Cable should be preferably supported on the brackets fixed along the wall to maintain safe access. Wherever routing on the floor cannot be avoided, care should be taken to ensure mechanical protection of these cables and safe access is not disturbed.

(e) No material at any work place should be so stacked or placed or disposed off as to cause danger, inconvenience or damage to any person or environment.

(f) All unused scaffoldings, surplus/scrap materials and equipment/ systems like temporary electrical panels etc. should not be allowed to accumulate and shall be removed from the premises at the earliest.

(g) Accumulation of water /oil spillages on the floor or any other workplace should be avoided.

(h) Proper aisle space marking should be provided in all workplaces.

10.21 Other Statutory Provisions

Notwithstanding the clauses in the above subsections, there is nothing in these clauses to exempt the contractor from the provisions of any other Act or Rules in force in the Republic of India. In particular, all operations involving the transport, handling, storage and use of explosives should be as per the standing instructions and conform to the Indian Explosives Act, 1884 and the Explosives Rules, 1983. Handling, transport, storage and use of compressed gas cylinders and pressure vessels should conform to the Gas Cylinder Rules 2004 and Static and Mobile Pressure Vessels (Unfired) Rules 1981. In addition, The Indian Electricity Act 2003 and Indian Electricity Rules 2005, the Atomic Energy Act, 1962, the Radiation Protection Rules, 2004, the Atomic Energy (Factories) Rules, 1996 and AERB safety manual on 'Radiation Protection for Nuclear Facilities' [AERB/NF/SM/O-2 (Rev.4)] should be complied with.

11. PERSONAL PROTECTIVE EQUIPMENT

11.1 General

Although the primary approach in any safety effort is that the hazard to the workmen should be eliminated or controlled by engineering methods rather than protecting the workman through use of personal protective equipment (PPE). Engineering methods could include design change, substitution, ventilation, mechanical handling, atomization etc. Under those situations when it is not possible to introduce any effective engineering methods for controlling hazards, it is necessary that workman use appropriate type of PPE. For example, in construction work there is the possibility of a hand tool, a bolt, or some loose material to fall from an elevated level and striking the head of workman working below. It is therefore necessary that construction worker wear a safety helmet. It is for such situations, both the Factories Act 1948 and the Atomic Energy (Factories) Rules, 1996 have provisions for use of appropriate type of PPE.

It is thus recognized that use of PPE is an important and necessary consideration in the development of a safety programme. Once the safety professional decides that PPE is to be used by workmen, it is essential to select right type of PPE and construction agency should ensure that workman uses it and also PPE is correctly maintained.

11.2 Personal Protective Equipment (PPE)

(a) All personal protective equipment as considered necessary should be made available for the use of the persons employed on the site and maintained in a condition suitable for immediate use. Also adequate steps should be taken by line manager to ensure proper use of PPE.

(b) All the PPEs in use should be as per relevant IS standards as referred in the AERB safety guidelines on 'Personal Protective Equipment' (AERB/SG/IS-3).

(c) All persons employed at the construction site should use safety helmets. Safety helmet should be with BIS mark and should have its headband with back support and chin strap.

(d) Workers employed on mixing asphaltic materials, cement and lime mortars should use protective goggles, protective foot wears, hand gloves and respirators as required.

(e) Persons engaged in welding and gas-cutting works should use suitable welding face shields. The persons who assist the welders should use suitable goggles. Protective goggles should be worn while chipping and grinding.

(f) Stonebreakers should use protective goggles. They should be seated at sufficiently safe distances from one another.

(g) Safety goggles should be of shatterproof type and with zero power.

(h) Persons engaged in or assisting in shot blasting operations and cleaning the blasting chamber should use suitable gauntlets, overalls, shatterproof and dust-proof goggles and self contained breathing apparatus set.

(i) All persons working at heights more than 3.5 m above ground or floor and exposed to risk of falling down should use full body harness safety belts, unless otherwise protected by cages, guard railings, etc. In places where the use of safety belts is not feasible, suitable net of adequate strength fastened to substantial supports should be used.

(j) When workers are employed in sewers and inside manholes that are in use, it should be ensured that the manholes are opened and are adequately ventilated at least for an hour. After it has been well ventilated, the atmosphere inside the space should be checked for the presence of any toxic gas or oxygen deficiency by a competent person and recorded in the register before the workers are allowed to get into the manholes. A pilot team should enter the area donning self contained breathing apparatus (SCBA). The manholes opened should be cordoned off with suitable railing and provided with warning signals or caution boards to prevent accidents. There should be proper illumination in the night. Depending upon the work situation, the contractor should provide PPE including the SCBA as recommended by Head, industrial safety.

12. MEDICAL MANAGEMENT

12.1 General

(a) The contractor shall make arrangements for the first aid and medical services for the injured or ill persons for prompt attention or aid.

(b) The arrangement can be made by the contractor or an agreement can be in vogue with the facility.

(c) The medical facilities at first-aid centre shall be adequate to immediately cater to the injured based on the hazard potential and probable severe injuries.

(d) The first-aid centre shall be provided with the adequate equipment and medicines for catering to the site requirements. The first-aid centre shall be manned depending on the working hours / on round the clock shift basis. The services of at least one qualified medical practitioner (medical officer) shall be made available by the contractor.

12.2 Medical Facilities

(a) Medical facilities conforming to the provisions of the Atomic Energy (Factories) Rules, 1996 should be provided at all work sites.

(b) The requisite medical facilities in the form of a well-equipped first aid centre manned by qualified nursing personnel should be provided at all work sites. Contractor may avail this facility as per terms and conditions of the contract.

(c) In addition, well-maintained first-aid boxes should be kept at each location of the work by the contractor and availability of the personnel trained in first aid should be ensured.

(d) A manned and equipped ambulance should be available at work site during the working hours/on round-the-clock shift basis.

(e) It should be ensured by the facility that occupational health monitoring of contract workers is carried out as per provisions of the Factories Act 1948 as per the latest amendment and the stipulations/directives given by Atomic Energy Regulatory Board from time to time.

(f) Display of emergency contact numbers of important persons and hospitals and route map of site shall be maintained at designated places.

12.3 Medical Management of Serious Injuries

(a) In case of serious injuries, the injured should be shifted to the nearest first-aid centre at site immediately. The opinion of medical officer/ certifying surgeon should be sought immediately for medical management.

(b) After providing the first aid treatment the injured should be shifted to designated medical facility of the site/hospital for further medical assistance, in an ambulance along with a nursing attendant.

(c) The doctor at the medical facility of the site/hospital attending the case shall assess the extent of injuries and render immediate medical aid. If the situation warrants trauma/special care the injured shall be shifted to the referral hospital, having all the requisite facilities for specialized treatment in ambulance along with a medical attendant.

(d) A list of such referral hospitals for specialised medical management facilities for the injured persons should be available with the project management/Head, industrial safety and Head, medical services of the site for ready reference.

APPENDIX-D

APPLICATION FOR HEIGHT PASS

PART- A

Group/Section: _____

Agency: _____

1. Applicant's name : _____
2. Facility address : _____
3. Residential address : _____
4. Age : _____
5. Sex : _____
6. Height : _____
7. Gate Pass No. : _____
8. Name of contractor/agency with whom engaged at present : _____
9. Height pass required for work at _____ m. Height
10. Description of present job : _____
11. Previous experience of working at height : _____

S.No.	Name of the employer	Duration of employment	Work experience
1.			
2.			

12. Does the applicant suffer from any of the following ailments ? (If yes details to be given):

(a) Blood pressure _____ (b) Epilepsy _____

(c) Flat foot _____

(d) Frequent headache or reeling sensation _____

(e) Mental depression _____ (f) Limping gait _____

(g) Aerofobia _____

Declaration:

I hereby declare that the above information furnished by me is true and correct. I shall always wear the safety belt and tie the life-line whenever working at unguarded heights of 3 m and above. I shall not misuse the height pass issued to me or transfer it to any other person. I shall never come to duty or work at height/depth under the influence of alcohol/drugs.

Date: Name:

Sign:

(Applicants Name and Signature or loss time injury (L.T.I) in case he cannot sign. In case of LTI an authorised person shall explain each point/item to the individual and certify on that behalf below the LTI)

I certify that I am satisfied with the above certification of the individual for the application of height pass and request for issue of height pass to him.

Name :

Sign:
(Agency Concerned)

Countersigned by:

Section Head (Facility)

PART-B

MEDICAL FITNESS CERTIFICATE

Certified that I, Dr. _____ have examined Shri._____ _____ aged _____ on (date) _____ who has signed below in my presence. General and physical examinations of Shri._____ do not reveal any abnormality. He does not suffer from any acute/chronic skin disease or any contagious or infectious disease. His eye sight is normal with/without glasses. In my opinion, Shri._____ is physically and mentally fit for working at height.

Details of examinations are given below:

Personal attributes:			**Medical aspects:**		
1.	Height	: _____	1.	Urine	: _____
2.	Chest	: _____	2.	Blood pressure	: _____
3.	Weight	: _____	3.	Epilepsy	: _____
4.	Hearing	: _____	4.	Flat foot	: _____
5.	Sight	: _____	5.	Frequent headache or reeling sensation:	_____
6.	Skin	: _____	6.	Mental depression:	_____
7.	Heart beating:	_____	7.	Limping gait	: _____
			8.	Aerophobia	: _____

Name:

Signature of workman

Signature and Rubber Stamp of Medical Practitioner with Reg. No.

PART-C

INDUSTRIAL SAFETY SECTION

(Considering the above medical certificate, the applicant has appeared on the following practical tests conducted by industrial safety section and the results are given below (strike off whichever is in-applicable)

(a) Wearing a safety belt and tying the rope knot : Pass/fail

(b) Walking over a horizontal structure at 3 m. height wearing a safety belt : Pass/fail

(c) General physique (OK/Not OK)

The above applicant's performance in the above tests has been satisfactory/ unsatisfactory due to the following.

So I certify and issue this height pass to Shri. _____ with Registration No. _____ in the height pass register. This is valid for one year from the date of issue i.e. up to .....

Date:

Name:

Signature

Scientific Assistant (Safety)

Safety Officer

APPENDIX-E

FORM - 1

APPLICATION FOR TEMPORARY POWER SUPPLY AND USE OF ELECTRICITY AT WORK SITE DURING CONSTRUCTION
[Prescribed under clause 10.6(d)]

1.	Name and address of user.	
2.	Reference of tender or work order (if applicable)	:
3.	Name and designation of tender/work order issuing authority.	:
4.	Power supply application number†	:
5.	Name and designation of tender/work order/work supervising authority (engineer-in-charge).	:
6.	Expected date of commencement of temporary supply	:
7.	Expected date of decommissioning of temporary supply	:
8.	Voltage level (LV/MV/HV)	
9.	Type of connection (1Ph/3Ph)	
10.	Connected load (Kw)	
11.	Maximum demand(KVA)/Power factor	
12.	Single line diagram* of proposed power distribution scheme along with equipment data sheet (downstream installation after point of connection).	Enclosed (Form-1A)/Not enclosed
13.	Name of overall supervisor and available qualified Staff	Enclosed (Form-1B)/Not enclosed
14.	Auxiliary equipment data sheet (meters, fire extinguisher, first aid box etc)	Enclosed (Form-1C/Not enclosed
15.	Name and designation of provider's representative to whom the application is addressed.	:
16.	Name and designation of authorised signatory of user, who had submitted this application	:

† Power supply application number shall be different for same user with multiple applications for temporary supply

* All the drawings and tables shall be signed by user's representative indicated against 16 above.

Signature of authorised signatory of user

Signed endorsement of work order supervising authority indicated against 5 above.

FORM - 1A

EQUIPMENT DATA SHEET FOR OBTAINING TEMPORARY POWER SUPPLY AND USE OF ELECTRICITY AT WORK SITE DURING CONSTRUCTION

(Prescribed against item-12 of form-1)

Name and address of user:

Power supply application Number:

Amendment No:

References:- Single line diagram (SLD) of the power distribution scheme with all equipment details (attach the SLD)

1. Identity	2. Type	3. Make and model	4. Manufacturer's S.No	5. Fixed/ Portable	6. Size	7. Last used date	8. Last test date	9. Latest test data	10. Rating

Signature of authorised signatory of user

Explanation of column headers:

1. Identity:- Identification mark/number/tag of equipment in single line drawing and layout drawing. Every equipment in single line drawing and layout drawing shall have suitable identification mark/number/tag.
2. Type:- Cable/CB/MCB/MCCB/ELCB/transformer/lightning arrestor/earthing station/ earthing connection/motor/lighting fixture/switch/fuse/switch, socket box etc.
3. Make and model:- manufacturer's name and corresponding model no.
4. Manufacturer's S. No:- serial number and date in name plate if available. Else NA
5. Fixed/portable:- Equipment is installed/laid/anchored to surface or portable.
6. Size:- depending upon type of equipment and as desired by provider representative e.g. length for cables or all dimensions if heavy equipment like transformer.
7. Last used date. date of last use else NEW
8. Last test date. latest test date by user or by manufacturer if NEW
9. Latest test data:- IR, HV, resistance, functional test data depending upon the type of equipment as desired by provider's representative.
10. Rating:- name plate rating of equipment like voltage, current, power (apparent, active, reactive), IP of enclosure, size (cable cross section) etc. depending upon the type of equipment and as desired by provider's representative.

FORM - 1B

STAFF DATA SHEET FOR OBTAINING TEMPORARY POWER SUPPLY AND USE OF ELECTRICITY AT WORK SITE DURING CONSTRUCTION
(Prescribed against item-13 of form-1)

Name and address of user:

Power supply application Number:
Amendment No:-

1. Name	2. Address	3. Tel.No.	4. Responsibility	5. Certification detail	6. Resucitation training	7. Expe-rience	8. Other relevant training	9. Signature

Signature of authorised signatory of user

Explanation of column headers:

1. Name:- Name of agency/person
2. Address:-
3. Tel No:- regular, alternate and emergency telephone numbers
4. Responsibility:- whether responsible for installation, operation, maintenance, overall supervision etc. overall supervisor shall be indicated specifically.
5. Certification detail:- (a) type of certification e.g wire man license, electrical supervisor license, electrical contractor license, diploma in electrical engineering, degree in electrical engineering etc. (b) certifying agency e.g. state PWD, central PWD, CEA, name of college/university etc. (c) certificate/license number with date. (d) valid up to date or next renewal date must for contractor/supervisor license.
6. Artificial resuscitation training:- indicate YES/NO if the staff is trained to apply artificial resuscitation technique.
7. Experience.:- number of years of experience.
8. Other relevant training :- any other training in electrical/ safety course. Indicate name of training, duration (days/months), training providing agency.
9. Signature:- original signature of individual.

FORM - 1C

AUXILIARY EQUIPMENT DATA SHEET FOR OBTAINING TEMPORARY POWER SUPPLY AND USE OF ELECTRICITY AT WORK SITE DURING CONSTRUCTION
(Prescribed against item-14 of form-1)

Name and address of user:

Power supply application Number:
Amendment No:-

Reference:- Layout drawing No. / _____

1. Identity	2. Type	3. Make and model	4. Manufacturer's S. No	5. Fixed/ Portable	6. Size	7. Last used date

Signature of user's representative

Explanation of column headers:

1. Identity:- identification mark/number/tag of equipment in layout drawing.
2. Type:- earthing rod/megger/multi meter/earth resistance meter/fire extinguisher/s and bucket/first aid box/resuscitation chart/rubber mat etc.
3. Make and model:- manufacturer's name and corresponding model no.
4. Manufacturer's S. No:- serial number and date in name plate if available. Else NA
5. Fixed/portable:- equipment is installed/laid/anchored to surface or portable.
6. Size:- depending upon type of equipment and as desired by provider representative.
7. Last used date. NEW for new equipment. NA for passive devices like chart/mat etc.

FORM -1D

(Prescribed under clause 4.6(e)]

Name of user agency **Power supply application number:-**

CERTIFICATE BY THE LICENSED ELECTRICAL CONTRACTOR

Certified that subject installations have been carried out by us or checked by us and is in accordance with I.E. Rules. The documents submitted with subject temporary power supply application (Form-1) is verified by us and the complete installation confirms to these documents.

We shall periodically inspect/check the installation so that no unsafe situation arises during use of this temporary power supply system. We understand that for the entire duration of existence of this temporary power supply system we shall be responsible for any unsafe installation, operation, maintenance, testing of the same which results into any loss of life or material. We shall immediately report to the provider's representative and ensure de-energisation of supply if any unsafe situation arises during use of this temporary power supply system.

Signature of the authorised signatory of licensed electrical contractor

Rubber seal of licensed electrical contractor

Date

CERTIFICATE BY THE USER

Certified that my/our installations have been carried out in accordance with the I.E. Rules and that I/We have employed competent agency/staff to handle the installations which is strictly as per the staff data sheet submitted in Form-1B.

We understand that for the entire duration of existence of this temporary power supply system we shall be responsible for any unsafe installation, operation, maintenance, testing of the same which results into any loss of life or material. We shall immediately report to the provider's representative and ensure de-energisation of supply if any unsafe situation arises during use of this temporary power supply system.

Signature of the authorised signatory of user

Name of signatory

Date

FORM -1E

[Prescribed under clause 10.6(f)]

CERTIFICATE BY THE SAFETY OFFICER

Certified that I have inspected the electrical installation referred here in after satisfying myself about the safe condition of the installation, I hereby recommend that the service connection be given to the contractor.

Signature of the safety officer

Name:

Date:

AUTHORISATION BY THE ELECTRICAL ENGINEER

The subject power supply application along with completed installation, necessary certificates (as per Form-1 of Appendix-E) is scrutinised by us. The proposal found to be in order and the installation can be energised on _____ in presence of your designated overall supervisor as indicated in Form-1B. Enclosed herewith the test report data sheet Form-1F. You are requested to carry out the periodic testing of equipment and submit the test report periodically as per this form.

Signature of the electrical engineer
of provider

Name of signatory

Date

FORM - 1F

TEST/MAINTENANCE REPORT DATA SHEET OF EQUIPMENTS OF TEMPORARY POWER SUPPLY SYSTEM AT WORK SITE DURING CONSTRUCTION
(Prescribed against form-1E)

Name and address of user:

Power supply application Number:
Amendment No:-

1. Identity	2. Type	3. Last tested date	4. Next due date of any test	5 Frequency of IR test	6 Frequency of HV test	7. Frequency of earth resistance test	8. Other tests

Signature of electrical engineer of provider

Explanation of column headers:

1. Identity:- Identification mark/number/tag of equipment in single line drawing and layout drawing. Every equipment in single line drawing and layout drawing shall have suitable identification mark/number/tag.
2. Type:- Cable/CB/MCB/MCCB/ELCB/transformer/lightning arrestor/earthing station/ earthing connection/motor/lighting fixture/switch/fuse/switch, socket box etc.
3. Last test date: - latest test date indicated in Form-1A.
4. Next due date of any test:- as worked out by frequency of tests indicated in subsequent columns.
5. Frequency of IR test:- required frequency depending upon type of equipment and location of installation. NA if not required after installation.
6. Frequency of HV test:- required frequency depending upon type of equipment and location of installation. NA if not required after installation.
7. Frequency of earth resistance test:- required frequency depending upon type of equipment and location of installation. NA if not required after installation.
8. Other tests:- name and description of any other essential tests/maintenance activity and required frequency depending upon type of equipment and location of installation. NA if not required after installation.

BIBLIOGRAPHY

1. The Atomic Energy (Factories) Rules, 1996
2. The Building and Other Constructions Workers' (Regulation of Employment and Conditions of Service) Central Rules, 1998
3. Regulatory control of the use of contractors by operating organisations (Peer discussions on regulatory practices), IAEA, 2000
4. Bureau of Indian Standards, Guidelines for construction project management: Part 5 Health and Safety Management, Draft copy, 2011
5. Indian Standard 3696(Part 1), Safety code of scaffolds and ladders: Part 1 Scaffolds, 1987
6. Indian Standard 3696(Part 2), Safety code of scaffolds and ladders: Part 2 Ladders, 1991
7. Indian Standard 3764, Code of safety for excavation work (first revision), 1992
8. Indian Standard 4014(Part 2), Code of practice for steel tubular scaffolding: Part 2 Safety regulations for scaffolding, 1967.
9. Indian Standard 4081, Safety code for blasting and related drilling operations (First Revision), 1986
10. Indian Standard 4130,Safety code for demolition of buildings (second revision), 1991
11. Indian Standard 4138, Safety code for working in compressed air (first revision), 1977
12. Indian Standard 4756, Safety code for tunnelling work (first revision), 1978
13. Indian Standard 4912, Safety requirements for floor and wall openings, railings and toe boards (first revision), 1978
14. Indian Standard 5121, Safety code for piling and other deep foundations, 1969
15. Indian Standard 5916, Safety code for construction involving use of hot bituminous materials, 1970
16. Indian Standard 7293, Safety code for working with construction machinery, 1974
17. Indian Standard 7969, Safety code for handling and storage of building materials, 1975

18. Indian Standard 8989, Safety code for erection of concrete framed structures, 1978

19. Indian Standard 10067, Material constants in building works, 1982

20. Indian Standard 10291, Safety code for dress divers in civil engineering works, 1982

21. Indian Standard 13415, Code of safety for protective barriers in and around, 1992

22. Indian Standard 13416(Part 1), Recommendations for preventive measures against hazards at workplaces: Part 1 Falling material hazards prevention, 1992

23. Indian Standard 13416(Part 2), Recommendations for preventive measures against hazards at workplaces: Part 2 Fall prevention, 1992

24. Indian Standard 13416(Part 3), Recommendations for preventive measures against hazards at workplaces: Part 3 Disposal of debris, 1994

25. Indian Standard 13416(Part 4), Recommendations for preventive measures against hazards at workplaces: Part 4 Timber structure, 1994

26. Indian Standard 13416(Part 5), Recommendations for preventive measures against hazards at workplaces: Part 5 Fire protection, 1994

27. Indian Standard 13430, Code of practice for safety during additional construction and alteration to existing buildings, 1992

LIST OF PARTICIPANTS

EXPERT COMMITTEE FOR REVIEW OF 'GUIDELINES' ON CONTROL OF WORKS

Dates of meeting:	July 9, 2007	July 23, 2007
	September 3, 2007	October 3, 2007
	October 17, 2007	February 22, 2008
	April 4, 2008	April 23, 2008
	May 6, 2008	May 13, 2008
	June 18 & 19, 2008	August 4, 2008
	May 12, 2010	

Members of Sub Committee:

Shri P.B. Kulkarni (Chairman)	:	BARC (Former)
Shri Sushil Kumar	:	DGFASLI
Shri D.K. Jain	:	NPCIL
Shri N. Nagaich	:	NPCIL
Shri P. Lahiri	:	BARC
Shri N. Prasad	:	NPCIL
Shri K. Ramprasad	:	AERB
Shri A.K. Tandle	:	BARC
Shri T.V. Sudhikumaran	:	NPCIL
Shri S.R. Bhave (Member Secretary)	:	AERB

Invitees:

Dr. P.K. Sinha	:	NPCIL (Former)
Shri D. Das	:	AERB

Contributors:

Shri R. Bhattacharya	:	AERB
Shri.S. Sounderarajan	:	BARC
Shri.S.R. Bhave	:	AERB
Shri S. Chockalingam	:	AERB

ADVISORY COMMITTEE ON INDUSTRIAL AND FIRE SAFETY (ACIFS)

Dates of meeting	:	July 6, 2009 August 4, 2009 November 30, 2009 February 22, 2010 March 26, 2010 April 29, 2010 July 30, 2010 September 21, 2010

Member ACIFS:

Shri S.K. Mukherjee (Chairman)	:	HPCL, Mumbai (Former)
Shri R.K. Gupta	:	HPCL, Mumbai
Shri M.P. Mahajan	:	HWB (Former)
Shri H.S. Ahluwalia	:	NFC (Former)
Shri S.K. Ghosh	:	BARC
Shri S.E. Kannan	:	AERB (Former)
Shri N.K. Agarwal	:	NPCIL (Former)
Shri P.K. Ghosh	:	AERB (Former)
Shri R. Bhattacharya	:	AERB
Shri K. Ramprasad (Member-Secretary)	:	AERB

PROVISIONAL LIST OF REGULATORY DOCUMENTS ON INDUSTRIAL AND FIRE SAFETY

Reference No.	Title	Year of Publication
AERB/NF/FPS (Rev. 1)	Fire Protection Systems for Nuclear Facilities	2010
AERB/NRF/SG/IS-1 (Rev. 1)	Control of Works	2012
AERB/SG/IS-2	Preparation of Safety Report of Industrial Plants other than Nuclear Power Plants in the Department of Atomic Energy	2001
AERB/SG/IS-3	Personal Protective Equipment	004
AERB/SG/IS-4	Guidelines for Pre-employment Medical Examination and fitness for Special Assignment	2005
AERB/SG/EP-3	Preparation of Site Emergency Preparedness Plans for Non-nuclear Installations.	2000
AERB/SG/EP-4	Preparation of Off-site Emergency Preparedness Plans for Non-nuclear Installations.	2000
AERB/SG/D-4	Fire Protection in Pressurised Heavy Water Reactor Based Nuclear Power Plants	1999
AERB/SM/IS-1	Manual on Database Management for Accidents/ Diseases Happening due to Occupation and Implementation of the same in the Department of Atomic Energy	1991

AERB SAFETY GUIDELINES NO. AERB/NRF/SG/IS-1 (Rev. 1)

Published by **:** Atomic Energy Regulatory Board
Niyamak Bhavan, Anushaktinagar
Mumbai - 400 094
INDIA.

BCS