

"Schedule of the quantity" cum "Unprice bid format"						
Name of the work:- "Balance Signalling & Telecommunication (S&T) Modification Works" at TWS, Mainpuri site, Allahabad Division.						
Tender Ref no. T0AYX00077 dated:10.12.2025						
Item No.	Item Description	Unit	Qty	Rate in Rs.	Amount in Rs.	Weightage %
1	Installation, termination, wiring, testing and commissioning of point machine	per machine	1			1.536251
2	Erection & wiring of shunt signal post.	nos.	1			0.431997
3	Modification of existing PA system to suit RE requirement	nos.	2			18.688415
4	Supply and Installation of cable termination pannel fitted with 6 nos. of 32 way U link feed pannel along U links complete and mounting arrangement	nos.	9			3.904697
5	Supply & Installation of Maintenance free earthing and bonding system as per RDSO.	no.	5			15.376441
6	Supply & installation of Location box (Full case) along with internal accessories and painting to mount different S&T equipments.	no.	3			6.033045
7	Supply of 3x0.7 and 16/0.2 multi strand flexible wire red, black and others (wiring material),	meter	500			0.886279
8	Wiring in existing Full Location Boxes	no.	3			1.692146
9	Supply of all consumables, charging, wiring and in new Full Location Boxes	no.	3			1.865701
10	Painting, Letter writing, Numbering of termination particulars over all Indoor & Outdoor Gears at Complete STATION including LC gate.	per station	1			3.914532
11	Laying of indoor Signaling cable on ladder, dressing, and terminating the same on Old and New CT rack, wherever required, to patch the Old Outdoor Signaling cable in new installation.	per station	1			2.445570
12	Laying of signaling / power / cables of various sizes.	Km	0.9			0.473899
13	Installation of Conventional earth pit including earth connection to S&T installation by suitable means(Ms flat/copper wire) as required. (Earth pipe supplied by BHEL)	nos.	10			1.751447
14	Supply and Installation of RCC Enclosure for Earth Pit	nos	10			0.738325
15	Supply and Installation of RCC Enclosure cover for Earth Pit	nos	10			0.369166
16	Excavation of trench 0.35m width 1.2m deep in all categories of soil such as black cotton / hard soil / murrum / soft rock mixed with boulders etc., as per cable route plan. Filling the trench with earth to the level of surrounding ground after laying cables.	km	0.9			11.827174
17	Modification in works, drawing & submission of as built drawing	unit	1			28.064915
	Total amount in Rs. (Excluding GST)					100.00
	Bidder to confirm having quoted their price in BHEL NIC portal (https://eprocurebhel.co.in) in the manner described in below, by writing "QUOTED" here					
Note						
1	Bidder no need to quote the price here, lumsum Price quoted by bidder in (excel sheet) price bid format in BHEL NIC portal (https://eprocurebhel.co.in) shall be cosidered as the total price of this tender SOQ. Rate and amount against each line item shall be derived from the corresponding weightage assigned against each line item of this SOQ.					
2	The rate and amount are inclusive of all applicable taxes, except for the GST. For details of taxes, clause no. 13.0 of the SCC will be					
3	Details of SOQ items shall be read in conjunction with the corresponding specifications, drawings and other tender terms.					