## 810050/2022/PSO PENTEL XLPE POWER CABLES FOR 2x660MW KHURJA TG T

1.1KV, Al conductor, XLPE insulated, Galvanised Steel Round/Formed Wire Armoured for multi-core cables (Non Magnetic Hard drawn Aluminium Round/Formed Wire Armoured conforming to H4 grade for single core cables), INNER SHEATH: Extruded PVC compound conforming to type ST2 of IS: 5831 for multicore cable & for single core cables, OVERALL SHEATH: Extruded FRLS PVC compound conforming to type ST2 of IS: 5831 & black in colour.

S. No.	ITEM CODE	CABLE SIZE [No. of cores - Cross section Area (sq.mm)]	UNIT	QUANTITY (Metre)	DRUM LENGTH
1	507-28220-A	1C - 300- AL ARMOURED	MTR	6000	1000
2	507-28007-A	1C - 630- AL ARMOURED	MTR	25500	750
3	507-28041-A	3C - 150- AL ARMOURED	MTR	2250	750
4	507-28045-A	3C - 240- AL ARMOURED	MTR	5250	750
5	507-28085-A	3.5C - 240-AL ARMOURED	MTR	2250	750
6	507-28027-A	2C - 95- AL ARMOURED	MTR	7500	750
7	507-28037-A	3.5C - 95- AL ARMOURED	MTR	2250	750
8	507-28051-A	3C - 95- AL ARMOURED	MTR	1500	750
9	507-28035-A	3.5C - 50- AL ARMOURED	MTR	22500	750
10	507-28049-A	3C - 50- AL ARMOURED	MTR	3000	750
11	507-28011-A	2C - 10- AL ARMOURED	MTR	2250	750
12	507-28039-A	3C - 10- AL ARMOURED	MTR	13500	750
13	507-28053-A	4C - 10- AL ARMOURED	MTR	2250	750
14	507-28017-A	2C - 25- AL ARMOURED	MTR	1500	750
15	507-28047-A	3C - 25- AL ARMOURED	MTR	16500	750
16	507-28031-A	3.5C - 25- AL ARMOURED	MTR	8250	750
17	507-28124-A	2C-16 AL ARMOURED	MTR	2250	750
18	507-28157-A	1CX120 - AL ARMOURED	MTR	5250	750
19	507-28154-A	1CX35 - AL ARMOURED	MTR	27000	750

1.1KV, Cu conductor, XLPE insulated, Galvanised Steel Round Armoured for multi-core cables, INNER
 B) SHEATH: Extruded PVC compound conforming to type ST2 of IS: 5831 for multicore cable. OVERALL SHEATH: Extruded FRLS PVC compound conforming to type ST2 of IS: 5831 & black in colour.

S. No.	ITEM CODE	CABLE SIZE [No. of cores - Cross section Area (sq.mm)]	UNIT	QUANTITY (Metre)	DRUM LENGTH
--------	-----------	---	------	---------------------	----------------

## 810050/2022/PSOPENTEL XLPE POWER CABLES FOR 2x660MW KHURJA TG T

1	507-28015-A	2C - 2.5- CU ARMOURED	MTR	81000	750
2	507-28043-A	3C - 2.5- CU ARMOURED	MTR	109500	750

#### **NOTES:**

- The standard drum length shall be 750/1000 meters as indicated above. Tolerance on individual drum length shall be  $\pm 5\%$ .
- Overall tolerance on total dispatched quantity of each size shall be (-) 2% and (+) 0% except where the total ordered quantity is one single drum length of 750/1000m, in which case it shall be -5% to 0%. Cables consumed for testing and inspection shall be to bidder's account.
- For each individual cable size, one short length of not less than 200m may be accepted only in the final drum length to complete the supply (except where the total ordered quantity is one single drum length of 750/1000m). The overall tolerance limits stipulated above shall continue to apply (in case short lengths are accepted).
- In case of the quantities cleared by BHEL for manufacturing are manufactured and offered for inspection by successful bidder in more than one batch, BHEL reserves the right to witness type testing on all batches without any price implications.
- Unit price of cables quoted by bidder shall be inclusive of type test charges. No separate charges shall be payable for type tests.
- 6 For any clarification please refer technical specification no.PE-TS-475-507-E002.(Rev-0)

#### **VOLUME-II**

## 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

# FOR LT XLPE POWER CABLE

SPECIFICATION NO: PE-TS-475-507-E002

REVISION: 00

(LVISION, 00



## BHARAT HEAVY ELECTRICALS LIMITED POWER SECTOR PROJECT ENGINEERING MANAGEMENT NOIDA, UP (INDIA) – 201301

### 81005<mark>0/202<del>2/PS-PEM-EL</del></mark>



## TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES

## 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

SPECIFICATION NO. PE-TS-475-507-E002		
VOLUME II		
SECTION		
REVISION 00	DATE: 11.03.2022	
SHEET 1 OF 1		

#### **CONTENTS**

<u>S. NO</u> .	<u>DESCRIPTION</u>	NO. OF SHEETS
1.	CONTENTS	01
2.	SECTION - I	
	COMPLIANCE CERTIFICATE	01
	SPECIFIC TECHNICAL REQUIREMENTS	01
	DATA SHEET-A	03
	DATA SHEET-C	03
3.	SECTION - II	
	STANDARD TECHNICAL SPECIFICATION	02
	QUALITY PLAN (ALONGWITH ANNEXURE A TO QP)	19
	TYPICAL DRAWING OF CABLE DRUM PACKING	01
	TOTAL NO. OF SHEETS=	34
		34
	(INCLUDING COVER/ SEPARATOR SHEETS)	



## TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES

## 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

SPECIFICATION NO. PE-TS- 475-507-E002			
VOLUME II			
SECTION I			
REVISION 00	DATE: 11.03.2022		
SHFFT 1 of 1			

#### **COMPLIANCE CERTIFICATE**

The bidder shall confirm compliance to the following by signing/ stamping this compliance certificate and furnishing same with the offer.

- 1. The scope of supply, technical details, construction features, design parameters etc. shall be as per technical specification & there are no exclusion/ deviation with regard to same.
- 2. There is no deviation with respect to specification other than those furnished in the 'schedule of deviations'.
- 3. Only those technical submittals which are specifically asked for in NIT to be submitted at tender stage shall be considered as part of offer. Any other submission, even if made, shall not be considered as part of offer.
- 4. Any comments/ clarifications on technical/ inspection requirements furnished as part of bidder's covering letter shall not be considered by BHEL, and bidder's offer shall be construed to be in conformance with the specification.
- 5. Any changes made by the bidder in the price schedule with respect to the description/ quantities from those given in 'BOQ-Cum-Price schedule' of the specification shall not be considered (i.e., technical description & quantities as per specification shall prevail).

BIDDER'S STAMP & SIGNATURE	

81005<mark>0/202<del>2/PS-PEM-EL</del></mark>



## TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES

2X660MW KHURJA TG AN	D
ASSOCIATED PACKAGES	,

SPECIFICATION N	O. PE-TS-475-507-E002
VOLUME II	
SECTION I	
REVISION 0	DATE: 11.03.2022
	VOLUME II SECTION I

## <u>SECTION – I</u> <u>SPECIFIC TECHNICAL REQUIREMENTS</u>



## TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES

## 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

SPECIFICATION NO. PE-TS-475-507-E002		
VOLUME II		
SECTION I		
REVISION 0	DATE: 11.03.2022	
SHEET 1 OF 1		

#### 1.0 SCOPE OF ENQUIRY

- 1.1 Design, Manufacture, Inspection and Testing at Manufacturer's works, proper packing and delivery to site of LT XLPE Power Cable conforming to this specification.
- 1.2 It is not the intent to specify herein all the details of design & manufacture of material. However, the material shall conform in all respects to high standard of design, engineering & workmanship and shall be capable of performing in continuous commercial operation at site condition.
- 1.3 General technical requirements of the LT XLPE Power cables are indicated in Section-II & Datasheet-A. Project specific technical/ quality requirements / changes are listed in Section-I.
- 1.4 The stipulation of Data Sheet-A shall prevail in case of any conflict between the stipulations of Data Sheet-A & Section-II.
- 1.5 The documents shall be in English Language and MKS system of units.

#### 2.0 BILL OF QUANTITIES

Quantity requirements shall be as per 'BOQ-cum-price schedule' as part of NIT.

#### 3.0 SPECIFIC TECHNICAL REQUIREMENTS

S.No.	Reference Clause No. of Section- II	Specific Requirement/ Change
1.	3.1	BHEL Standard Quality Plan (PE-QP-999-507-E002) shall be read as "QP. NO. 0000-999-QOE-S-041, REV-01".  Additionally, The QP. NO. 0000-999-QOE-S-041 REV-01 shall be read in conjunction with Annexure B (Quality Assurance & Inspection). However, Type testing on cables shall be conducted as per attached BHEL QP (PE-QP-999-507-E002, R02) along with Annexure-A to QP

#### 4.0 DRAWINGS & DOCUMENTS TO BE SUBMITTED

- 4.1 After placement of order, documents shall be submitted for BHEL & customer's approval as specified in NIT.
- 4.2 Drawings/documents shall be submitted through Document Management System (DMS).

Note: NTPC Standard Quality Plan as enclosed in the technical specification is for reference and same shall be finalized during detailed engineering in consultation with NTPC without any price implication to BHEL. The finalized QP during detailed engineering is to be appended with cover sheet bearing document number and description as stated above. The signed and stamped copy of the same shall be submitted to BHEL without making any changes in the contents of the document.

### 810050/<del>2022/PS-PEM-EL</del>



#### TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

DOCUMENT TITLE

SPECIFICATION NO. PE-TS- 475-507-E002			
VOLUME II			
SECTION I			
REVISION 00	DATE: 11.03.2022		
SHEET 1 OF 3			

#### DATA SHEET-A

1.0	Type of Cable	Flame Retardant Low Smoke halogen (FR-LSH)
2.0	Standard applicable in general(Latest amendment to be referred if any)	IS:7098 (Part-1), IS:8130, IS:5831, IS:10810, IS:3975, ASTMD:2843, ASTMD:2863, IEC-754-1, IEC:60332 (Part-1), IEC:60332-3-23, IEEE:60383
3.0	Voltage Grade	1.1kV
5.0	Voltage Grade	1.1KV
4.0	Number of cores, cross sectional area of conductors and quantities	As per BOQ-Cum-Price Schedule
5.0	FAULT CHARACTERISTICS	
	Fault Level	50kA RMS
	Fault Clearing Time	1.0 sec
6.0	CONDUCTOR	
(a)	Material	Aluminium (With Tensile strength more than 100N/sq.mm.)
(α)	Grade and Class	Stranded, Compacted, H2, Class 2
(h)		IS: 8130
(b)	Standard Applicable	Aluminium
(d)	Min. number and diameter of strands for main	Circular/ Shaped – as per IS As per Table-2 of IS: 8130
(u)	and neutral conductor [Neutral conductor cross section w.r.t main conductor shall be as per Table-2 of IS: 7098 (Part-1)]	AS per Table-2 of 13. 0130
	1	
7.0	INSULATION	
(a)	Material	Cross-Linked Polyethylene(XLPE)
(b)	Standard Applicable	IS: 7098 (Part-1)
(c)	Continuous withstand temperature	90°C
(d)	Short-circuit withstand temperature	250°C
(e)	Method of application	By extrusion; sleeve extrusion not permitted.
(f)	Nominal Thickness of insulation	As per IS: 7098 (Part-1)
8.0	CORE IDENTIFICATION	Cores of the cables shall be identified by colouring of insulation. Following colour scheme shall be adopted: 1 core - Red, Black, Yellow or Blue 2 core - Red & Black 3 core - Red, Yellow & Blue 4 core - Red, Yellow, Blue and Black For reduced neutral conductors, the core shall be black
9.0	INNER SHEATH	
(a)	Material	Extruded PVC Type ST-2
(a) (b)	Standard Applicable	IS: 7098 (Part-1) & IS: 5831
(c)	Colour	Black
	Whether FR-LSH	
(d)	WHEHE FK-LOH	No

#### 810050/<del>2022/PS-PEM-EL</del>



#### TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES 2X660MW KHURJA TG AND

DOCUMENT TITLE

SPECIFICATION NO. PE-TS- 475-507-E002

VOLUME II

SECTION I

REVISION 00 DATE: 11.03.2022

SHEET 2 OF 3

		OCIATED PACKAGES	SHEET 2 OF 3		
	ASSI	OCIATED FACINAGES			
(e)	Inner sheath applicable	for single core cable V	es		
		•			
(f)	Fillers		cceptable		
(g)	Material of fillers (if pern		ame as inner sheath (Material of filler to be compatible with at of inner sheath)		
(h)	Method of application				
(1)	Multi-core cables:				
(i)	With fillers		ressure/ Vacuum extruded		
(ii)	Without fillers	ı	ressure extruded		
(2)	Single-core cables:	N	OT APPLICABLE		
10.0	ARMOUR				
(a)	Applicable	Y	es (As specified in BOQ cum price schedule)		
(b)	Material:		/herever armouring is applicable		
(i)	Single core cables		on Magnetic Hard drawn Aluminium Round/Formed Wire H4		
(1)	Single core cables		rade to IS: 8130 (as specified in BOQ cum price schedule)		
(ii)	Multi-core cables				
(iii)	Standard Applicable		imension as per IS: 7098 (Part-1) Table-6 and tolerance on mension as per IS:3975		
(c)	Minimum Coverage	9	0%		
(d)	Gap between armour wi	res SI	hall not exceed one armour wire space		
			(No cross-over/ over-riding)		
(e)	Breaking load of joint		5 % of normal armour		
(f)	Paint on joint		nc rich paint shall be applied on armour joint surface of G.S. ire / formed wire		
	<del>,</del>	<u>,                                      </u>			
11.0	OUTERSHEATH				
(a)	Material		VC Type ST2 as per IS: 5831		
(b)	Colour		lack		
(c)	Whether FR-LSH		es		
(d)	Method of application		xtruded		
(e)	Thickness of outer shea		s per Table-8 of IS: 7098 (Part-1)		
(f)	Marking	ar W M m 'E Pi @	able size (cross section area and no. of cores), voltage grade and Reference IS @ 5m (by embossing)  /ord "XLPE", "FR-LSH" @ 5m (by embossing) anufacturer's name and/ or trade name, and year of anufacture @ 5m (by embossing)  BHEL' and 'CUSTOMER' name @ 5m (by embossing) rogressive sequential marking of length of the cable in metres  o 1m (by embossing/ printing)  ne embossing shall be progressive, automatic, in line and arking shall be legible and indelible.		
12.0	FR-LS CHARACTERIS	TICS			
(a)	Oxygen index	I M	in 29 (As per IS 7098-I /ASTMD 2863)		

#### 810050/<del>2022/PS-PEM-</del>EL



#### TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

DOCUMENT TITLE

SPECIFICATION NO. PE-TS- 475-507-E002
VOLUME II
SECTION I
REVISION 00 DATE: 11.03.2022
SHEET 3 OF 3

(c)	Acid gas generation	Max. 20% by weight (As per IS 7098-I /IEC-60754-1)
(d)	Smoke density rating	Max. 60% (As per IS 7098-I /ASTM D 2843)
(e)	Flammability Test	
(i)	Flammability test for single cable	YES
(1)	Training test for single easie	As per IEC-60332 Part-1
(ii)	Flammability test for bunched cables	YES
()	Training test for parieties easies	As per IEC-60332 Part-3-23, CAT-B
(iii)	Flammability test as per IEEE: 60383	YES
(iv)	As per Swedish Chimney test SEN-SS-424-1475-F3	YES
(f)	Special Tests	
1.	Hydrolytic Stability Test	No/ Refer Cl. 3.4 of Sec-II
II.	Ultraviolet Radiation Test	No/ Refer Cl. 3.4 of Sec-II
	Olivariote Hadiation 1000	Trof trofor on our or occur
13.0	Anti-rodent and Termite repulsion Test	YES
14.0	Anti-Fungal Test	No
1 1.0		1.00
15.0	TOLERANCE ON OUTER DIAMETER	+ 2mm
10.0	TOLLIA WOL ON OUTER BITWIETER	<u> </u>
16.0	MINIMUM BENDING RADIUS	
(a)	Single core cables	15 x O.D.
(b)	Multi core cables	12 x O.D.
(6)	Wall core cables	12 A O.D.
17.0	SAFE PULLING FORCE	
(a)	Aluminium conductor cable	30 N/ sq. mm.
(b)	Copper conductor cable (if applicable)	50 N/ sq. mm
(b)	Copper conductor cable (ii applicable)	50 W 5q. 111111
18.0	CABLE DRUMS	
(a)	Type of Drum	Wooden as per IS 10418
(b)	Standard drum length	750m (±) 5% / 1000m (±) 5%. (as specified in BOQ-Cum- Priced Schedule)
(c)	Painting	Entire surface to be painted
(d)	Outermost Layer	To be covered with waterproof polyethylene
(e)	Construction details	Clause no 4.2 of Section-II of this technical specification
(f)	Particular details on Drum	Clause no 4.2 of Section-II of this technical specification.  The surface of the drum and the outer most cable layer shall be covered with water proof cover. Both the ends of the cables shall be properly sealed with heat shrinkable PVC/ rubber caps secured by 'U' nails so as to eliminate ingress of water during transportation, storage and erection. Wood preservative antitermite treatment shall be applied to the entire drum. Wooden drums shall comply with IS: 10418.
(g) 19.0	Cable packing  Sea Worthy packing	Please refer Clause no 4.2 of Section-II of this technical specification. It may be noted that the outer most cable layer shall be covered with water proof cover polythene followed by complete drum covering with wooden plank of suitable thickness across flanges. (Refer typical drawing of cable drum packing, attached in section -II)  No



#### DOCUMENT TITLE

## TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

SPECIFIC	SPECIFICATION NO. PE-TS-475-507-E002				
VOLUME	VOLUME II				
SECTION	SECTION I				
REV NO. 00 DATE 11.03.2022					
SHEET	1	OF	3		

#### **DATASHEET C**

## GUARANTEED TECHNICAL PARTICULARS (TO BE SUBMITTED BY SUCCESSFUL BIDDER)

S.No.		Unit	Description
Α	GENERAL	-	
1	Name of manufacturer	-	
2	Place of Manufacture	-	
3	Current rating of cables conforms to	-	
4	Short circuit rating conforms to	-	
5	Formula for calculating short circuit current for different duration	-	
6	Permissible conductor temperature		
	(a) Maximum continuous rating	deg. C	
	(b) Short circuit rating	deg. C	
7	(a) Installation Conditions at site		
	i) Ambient air temperature	deg. C	
	ii) Ground temperature	deg. C	
	iii) Depth of laying of cables buried in ground	cm	
8	CHARACTERISTICS OF FRLS SHEATH		
	(a) Oxygen index	%	
	(b) Temperature index	deg. C	
	(c) Acid gas generation	%	
	(d) Smoke density rating	%	
9	CABLE DRUMS		
	(a) Type & construction	-	
	(b) Standard drum length	Mtr	
	(c) Tolerance on drum length	%	
В	INFORMATION TO BE FILLED IN FOR EACH SIZE CABLE IN THE FORM OF TABLE		
1	No. of cores x size	No. x sq.mm	
2	Voltage grade (Uo/U)	kV	
3	Base current ratings (*) based on SI. (A) 7.0		
	(a) In air	Amp	
	(b) In ground	Amp	
	(c) ducts	Amp	
NAME OF	VENDOR		<u>'</u>

NAME OF VENDOR					
				REV.	
NAME	SIGNATURE	DATE	SEAL		



#### DOCUMENT TITLE

#### TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

SPECIFICATION NO. PE-TS-475-507-E002				
VOLUME II				
SECTION I				
REV NO. 00 DATE 11.03.2022				
SHEET 2 OF 3				

(a) D.C. resistance of conductor at 20 deg C (main / neutral) (b) A.C. resistance of conductor at 90 deg. C (main / neutral) (c) Reactance of cable at Normal frequency (d) Electrostatic capacitance of cable at normal frequency (d) Electrostatic capacitance of cable at normal frequency (d) Electrostatic capacitance of cable at normal frequency (a) Material type (b) Grade (c) No & dia of wires in each core before stranding (d) Shape  7 INSULATION (a) Material (b) Nominal thickness (main / neutral) (c) Minimum thickness (main / neutral) (d) Minimum volume resistivity at 27 deg. C (e) Minimum volume resistivity at 90 deg. C  NINERSHEATH (a) Material (b) Whether FRLS (c) Thickness (min.) (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour  7 ARMOUR (a) Material (b) Type of armour (c) Sizel dimensions (Nominal dia of wire) (d) Minimum no. of round if formed wires (f) Gap between armour wirelstrip (g) Breaking load of joint (h) Maximum resistivity of GS formed / Round wire (i) Maximum resistivity of GS formed / Round wire (ii) Maximum resistivity of Aluminium round wire (iii) Whether FRLS (iii) Maximum resistivity of Aluminium round wire (iii) Whether FRLS	4	Short circuit rating for 1 sec duration	kA	
(c) Reactance of cable at Normal frequency (d) Electrostatic capacitance of cable at normal frequency (d) Electrostatic capacitance of cable at normal frequency (e) Material type (f) Grade (c) No & dia of wires in each core before stranding (d) Shape 7 INSULATION (a) Material (b) Nominal thickness (main / neutral) (d) Minimum thickness (main / neutral) (d) Minimum volume resistivity at 27 deg. C (e) Minimum volume resistivity at 90 deg. C  NNFRSHEATH (a) Material (b) Whether FRLS (c) Thickness (min.) (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour  9 ARMOUR (a) Material (b) Type of armour (c) Sized dimensions (Nominal dia of wire) (d) Minimum no. of round / formed wires (e) Minimum coverage (f) Gap between armour wire/strip (g) Breaking load of joint (f) Maximum resistivity of Aluminium round wire (f) Maximum resistivity of Aluminium round wire Ohm-cm  10 OUTERSHEATH (a) Material (b) TypeSized dimensions (Nominal dia of wire) (f) Maximum resistivity of Aluminium round wire Ohm-cm OUTERSHEATH (a) Material	5	(a) D.C. resistance of conductor at 20 deg C (main / neutral)	ohm/km	
(d) Electrostatic capacitance of cable at normal frequency		(b) A.C. resistance of conductor at 90 deg. C (main / neutral)	ohm/km	
CONDUCTOR		(c) Reactance of cable at Normal frequency	ohm/km	
(a) Material type (b) Grade (c) No & dia of wires in each core before stranding (d) Shape 7 INSULATION (a) Material (b) Nominal thickness (main / neutral) (c) Minimum thickness (main / neutral) (d) Minimum volume resistivity at 27 deg. C (e) Minimum volume resistivity at 90 deg. C  Nom-cm  8 INNERSHEATH (a) Material (b) Whether FRLS (c) Thickness (min.) (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour  9 ARMOUR (a) Material (b) Type of armour (c) Size/ dimensions (Nominal dia of wire) (d) Minimum no. of round / formed wires (e) Minimum coverage (f) Gap between armour wire/strip (g) Breaking load of joint (h) Maximum resistivity of GS formed / Round wire (i) Maximum resistivity of Aluminium round wire Ohm-cm  10 OUTERSHEATH (a) Material		(d) Electrostatic capacitance of cable at normal frequency	μF/km	
(b) Grade  (c) No & dia of wires in each core before stranding  (d) Shape  7 INSULATION  (a) Material  (b) Nominal thickness (main / neutral)  (c) Minimum thickness (main / neutral)  (d) Minimum volume resistivity at 27 deg. C  (e) Minimum volume resistivity at 90 deg. C  Nom-cm  8 INNERSHEATH  (a) Material  (b) Whether FRLS  (c) Thickness (min.)  (d) Method of application for multi-core cables  (e) Type and shape of fillers (if used)  (f) Colour  9 ARMOUR  (a) Material  (b) Type of armour  (c) Size/ dimensions (Nominal dia of wire)  (d) Minimum no. of round / formed wires  (e) Minimum coverage  (f) Gap between armour wire/strip  (g) Breaking load of joint  (h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  10 OUTERSHEATH  (a) Material	6	CONDUCTOR		
(c) No & dia of wires in each core before stranding (d) Shape  7 INSULATION  (a) Material (b) Nominal thickness (main / neutral) (c) Minimum thickness (main / neutral) (d) Minimum volume resistivity at 27 deg. C (e) Minimum volume resistivity at 90 deg. C  8 INNERSHEATH (a) Material (b) Whether FRLS (c) Thickness (min.) (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour  9 ARMOUR  (a) Material (b) Type of armour (c) Size/ dimensions (Nominal dia of wire) (d) Minimum no. of round / formed wires (e) Minimum coverage (f) Gap between armour wire/strip (g) Breaking load of joint (h) Maximum resistivity of GS formed / Round wire (i) Maximum resistivity of GS formed / Round wire (i) Maximum resistivity of Aluminium round wire Ohm-cm  10 OUTERSHEATH (a) Material  - COUTERSHEATH (a) Material		(a) Material type	-	
(d) Shape		(b) Grade	-	
7 INSULATION  (a) Material (b) Nominal thickness (main / neutral) (c) Minimum thickness (main / neutral) (d) Minimum volume resistivity at 27 deg. C (e) Minimum volume resistivity at 90 deg. C  8 INNERSHEATH (a) Material (b) Whether FRLS (c) Thickness (min.) (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour  9 ARMOUR  (a) Material		(c) No & dia of wires in each core before stranding	no x mm	
(a) Material (b) Nominal thickness (main / neutral) (c) Minimum thickness (main / neutral) (d) Minimum volume resistivity at 27 deg. C (e) Minimum volume resistivity at 90 deg. C  NNERSHEATH (a) Material (b) Whether FRLS (c) Thickness (min.) (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour  9 ARMOUR (a) Material		(d) Shape	-	
(b) Nominal thickness (main / neutral) mm (c) Minimum thickness (main / neutral) mm (d) Minimum volume resistivity at 27 deg. C Ohm-cm (e) Minimum volume resistivity at 90 deg. C Ohm-cm  8 INNERSHEATH (a) Material (b) Whether FRLS (c) Thickness (min.) mm (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour 9 ARMOUR (a) Material (b) Type of armour (c) Size/ dimensions (Nominal dia of wire) mm (d) Minimum no. of round / formed wires No. (e) Minimum coverage % (f) Gap between armour wire/strip (g) Breaking load of joint (h) Maximum resistivity of GS formed / Round wire Ohm-cm (i) Maximum resistivity of Aluminium round wire Ohm-cm  10 OUTERSHEATH (a) Material	7	INSULATION		
(c) Minimum thickness (main / neutral) mm  (d) Minimum volume resistivity at 27 deg. C (e) Minimum volume resistivity at 90 deg. C  8  INNERSHEATH (a) Material (b) Whether FRLS - (c) Thickness (min.) (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour  9 ARMOUR  (a) Material - (b) Type of armour (c) Size/ dimensions (Nominal dia of wire) (d) Minimum no. of round / formed wires (e) Minimum coverage (f) Gap between armour wire/strip (g) Breaking load of joint (h) Maximum resistivity of GS formed / Round wire (i) Maximum resistivity of Aluminium round wire  10 OUTERSHEATH (a) Material -  OUTERSHEATH (a) Material -		(a) Material	-	
(d) Minimum volume resistivity at 27 deg. C (e) Minimum volume resistivity at 90 deg. C  8  INNERSHEATH (a) Material (b) Whether FRLS (c) Thickness (min.) (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour  9 ARMOUR (a) Material (b) Type of armour (c) Size/ dimensions (Nominal dia of wire) (d) Minimum no. of round / formed wires (e) Minimum coverage (f) Gap between armour wire/strip (g) Breaking load of joint (h) Maximum resistivity of GS formed / Round wire  10 OUTERSHEATH (a) Material  - Ohm-cm		(b) Nominal thickness (main / neutral)	mm	
(e) Minimum volume resistivity at 90 deg. C  NNERSHEATH (a) Material (b) Whether FRLS (c) Thickness (min.) (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour  9 ARMOUR  (a) Material - (b) Type of armour - (c) Size/ dimensions (Nominal dia of wire) (f) Gap between armour wire/strip (g) Breaking load of joint (h) Maximum resistivity of GS formed / Round wire (i) Maximum resistivity of Aluminium round wire  OuterSHEATH (a) Material  - OUTERSHEATH (a) Material  - Ohm-cm  Ohm-cm		(c) Minimum thickness (main / neutral)	mm	
8 INNERSHEATH (a) Material (b) Whether FRLS (c) Thickness (min.) (d) Method of application for multi-core cables (e) Type and shape of fillers (if used) (f) Colour  9 ARMOUR  (a) Material (b) Type of armour (c) Size/ dimensions (Nominal dia of wire) (d) Minimum no. of round / formed wires (e) Minimum coverage (f) Gap between armour wire/strip (g) Breaking load of joint (h) Maximum resistivity of GS formed / Round wire (i) Maximum resistivity of Aluminium round wire  10 OUTERSHEATH (a) Material			Ohm-cm	
INNERSHEATH (a) Material - (b) Whether FRLS - (c) Thickness (min.) mm  (d) Method of application for multi-core cables - (e) Type and shape of fillers (if used) - (f) Colour -  9 ARMOUR  (a) Material - (b) Type of armour - (c) Size/ dimensions (Nominal dia of wire) mm  (d) Minimum no. of round / formed wires No.  (e) Minimum coverage (f) Gap between armour wire/strip - (g) Breaking load of joint - (h) Maximum resistivity of GS formed / Round wire Ohm-cm  10 OUTERSHEATH (a) Material -  -  -  -  -  -  -  -  -  -  -  -  -		(e) Minimum volume resistivity at 90 deg. C	Ohm-cm	
(a) Material - (b) Whether FRLS (c) Thickness (min.) mm (d) Method of application for multi-core cables - (e) Type and shape of fillers (if used) - (f) Colour (f) Colour - (a) Material - (b) Type of armour - (c) Size/ dimensions (Nominal dia of wire) mm (d) Minimum no. of round / formed wires No. (e) Minimum coverage / (f) Gap between armour wire/strip - (g) Breaking load of joint - (h) Maximum resistivity of GS formed / Round wire Ohm-cm (i) Maximum resistivity of Aluminium round wire Ohm-cm OUTERSHEATH (a) Material	8	INNEDCHEATH		
(b) Whether FRLS - (c) Thickness (min.) mm  (d) Method of application for multi-core cables - (e) Type and shape of fillers (if used) - (f) Colour -  ARMOUR  (a) Material - (b) Type of armour - (c) Size/ dimensions (Nominal dia of wire) mm  (d) Minimum no. of round / formed wires No.  (e) Minimum coverage (f) Gap between armour wire/strip - (g) Breaking load of joint - (h) Maximum resistivity of GS formed / Round wire Ohm-cm  OUTERSHEATH (a) Material -  OUTERSHEATH  (a) Material -  -  -  -  -  -  -  -  -  -  -  -  -			-	
(d) Method of application for multi-core cables  (e) Type and shape of fillers (if used)  (f) Colour  9 ARMOUR  (a) Material  - (b) Type of armour  - (c) Size/ dimensions (Nominal dia of wire)  (d) Minimum no. of round / formed wires  No.  (e) Minimum coverage  (f) Gap between armour wire/strip  - (g) Breaking load of joint  - (h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material			-	
(e) Type and shape of fillers (if used)  (f) Colour  ARMOUR  (a) Material  (b) Type of armour  (c) Size/ dimensions (Nominal dia of wire)  (d) Minimum no. of round / formed wires  (e) Minimum coverage  (f) Gap between armour wire/strip  (g) Breaking load of joint  (h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material		(c) Thickness (min.)	mm	
(f) Colour  ARMOUR  (a) Material  - (b) Type of armour  - (c) Size/ dimensions (Nominal dia of wire)  (d) Minimum no. of round / formed wires  (e) Minimum coverage  (f) Gap between armour wire/strip  (g) Breaking load of joint  - (h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material		(d) Method of application for multi-core cables	-	
9 ARMOUR  (a) Material  (b) Type of armour  (c) Size/ dimensions (Nominal dia of wire)  (d) Minimum no. of round / formed wires  No.  (e) Minimum coverage  (f) Gap between armour wire/strip  (g) Breaking load of joint  -  (h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material		(e) Type and shape of fillers (if used)	-	
(a) Material  (b) Type of armour  (c) Size/ dimensions (Nominal dia of wire)  (d) Minimum no. of round / formed wires  (e) Minimum coverage  (f) Gap between armour wire/strip  (g) Breaking load of joint  (h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material		(f) Colour	-	
(b) Type of armour  (c) Size/ dimensions (Nominal dia of wire)  (d) Minimum no. of round / formed wires  (e) Minimum coverage  (f) Gap between armour wire/strip  (g) Breaking load of joint  (h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material	9	ARMOUR		
(c) Size/ dimensions (Nominal dia of wire) mm  (d) Minimum no. of round / formed wires No.  (e) Minimum coverage %  (f) Gap between armour wire/strip -  (g) Breaking load of joint  (h) Maximum resistivity of GS formed / Round wire Ohm-cm  (i) Maximum resistivity of Aluminium round wire Ohm-cm  OUTERSHEATH  (a) Material		(a) Material	-	
(d) Minimum no. of round / formed wires  (e) Minimum coverage  (f) Gap between armour wire/strip  (g) Breaking load of joint  (h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material		(b) Type of armour	-	
(e) Minimum coverage %  (f) Gap between armour wire/strip -  (g) Breaking load of joint -  (h) Maximum resistivity of GS formed / Round wire Ohm-cm  (i) Maximum resistivity of Aluminium round wire Ohm-cm  OUTERSHEATH  (a) Material -		(c) Size/ dimensions (Nominal dia of wire)	mm	
(f) Gap between armour wire/strip  (g) Breaking load of joint  (h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material  -		(d) Minimum no. of round / formed wires	No.	
(g) Breaking load of joint  (h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material  -		(e) Minimum coverage	%	
(h) Maximum resistivity of GS formed / Round wire  (i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material  -		(f) Gap between armour wire/strip	-	
(i) Maximum resistivity of Aluminium round wire  Ohm-cm  OUTERSHEATH  (a) Material  -		(g) Breaking load of joint	-	
10 OUTERSHEATH (a) Material -		(h) Maximum resistivity of GS formed / Round wire	Ohm-cm	
(a) Material -		(i) Maximum resistivity of Aluminium round wire	Ohm-cm	
	10	OUTERSHEATH		
(b) Whether FRLS		(a) Material	-	
		(b) Whether FRLS	-	

NAME OF VENDOR					
				REV.	
NAME	SIGNATURE	DATE	SEAL		



## TECHNICAL SPECIFICATION FOR

#### TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

SPECIFICATION NO. PE-TS-475-507-E002
VOLUME II
SECTION I
REV NO. 00 DATE 11.03.2022
SHEET 3 OF 3

	(c) Minimum thickness	mm	
	(d) Colour	-	
	(e) Method of application	-	
11	DIAMETERS		
	(a) Diameter of insulated conductor	mm	
	(b) Cable diameter under armour	mm	
	(c) Cable diameter over armour	mm	
	(d) Overall diameter of cable	mm	
	(e) Tolerance on overall diameter	(±) mm	
12	Ovality	mm	
13	Minimum bending radius	x O.D	
14	Safe Pulling Force	N/mm <sup>2</sup>	
15	Weight of cable	kg./km	
16	Dimension of drum	mm	
17	Shipping weight (approx.)	kg	
18	Cable marking on outer sheath	-	
19	Marking on drum	-	

(\*) For single core cables, the continuous current rating shall be furnished separately for armour earthed at one end and at both ends.

NAME OF VENDOR					
				REV.	
NAME	SIGNATURE	DATE	SEAL		



## TECHNICAL SPECIFICATION FOR LT XLPE POWER CABLES

2X660MW KHURJA TG AND ASSOCIATED PACKAGES

SPECIFICATION N	O. PE-TS-475-507-E002
VOLUME II	
SECTION II	
REVISION 0	DATE: 11.03.2022

## SECTION-II STANDARD TECHNICAL REQUIREMENTS



## TECHNICAL SPECIFICATION FOR LT XLPE Power Cable

## 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

SPECIFICATION N	O. PE-TS-475-507-E002
VOLUME II	
SECTION II	
REVISION 00	DATE: 11.03.2022
Sheet 1 of 2	

#### 1.0 CODES AND STANDARDS

- 1.1 The material shall comply with all currently applicable safety codes and statutory regulations of India as well as of the locality where the material is to be installed.
- 1.2 The design, material, construction, manufacture, inspection and testing of LT XLPE POWER Cable shall conform to the latest revision of relevant standards as per Data Sheet-A.
- 1.3 In case of conflict between the applicable reference standard and this specification, this specification shall govern.

#### 2.0 TECHNICAL REQUIREMENTS

2.1 LT XLPE POWER Cable shall be supplied as per technical particulars specified in Data Sheet – A.

#### 3.0 QUALITY ASSURANCE, TESTING & INSPECTION

- 3.1 Bidder shall confirm compliance with the BHEL Standard Quality Plan (PE-QP-999-507-E002, Rev-02) as attached with the specification without any deviations. At contract stage (project specific), the successful bidder shall submit the same QP for BHEL/ ultimate customer's approval. In case bidder has reference QP agreed with ultimate customer, same can be submitted for specific project after award of contract for BHEL/ultimate customer's approval. There shall be no commercial implication to BHEL on account of minor changes in QP during contract stage.
- 3.2 All materials shall be procured, manufactured, inspected and tested by vendor/ sub-vendor as per approved quality plan.
- 3.3 Type testing, routine / acceptance testing and special testing requirements shall be as per Annexure –A to QAP. Charges for all these tests for all the equipments & components shall be deemed to be included in the bid price (except UV Radiation & Hydraulic Stability test).
- 3.4 The charges of UV Radiation test & Hydrolytic Stability test (if applicable) shall be reimbursed extra at actual against original money receipt of Govt. Lab. (CPRI/ ERDA etc).
- 3.5 Cost of cables consumed for testing shall be to bidder's account.

#### 4.0 PACKING

- 4.1 Cables shall be supplied in non-returnable drums. Material of cable drums shall be wooden.
- 4.2 For wooden drums, all wooden parts shall be manufactured from seasoned wood treated with copper napthenates / zinc napthenates (refer IS: 401) and anti-termite. The surface of the drum and the outer most cable layer shall be covered with water proof cover. Both the ends of the cables shall be properly sealed with heat shrinkable PVC/ rubber caps secured by 'U' nails so as to eliminate ingress of water during transportation, storage and erection. Dimensions of wooden drums shall be as per IS 10418. All ferrous parts shall be treated with suitable rust protective



## TECHNICAL SPECIFICATION FOR LT XLPE Power Cable

## 2X660MW KHURJA TG AND ASSOCIATED PACKAGES

SPECIFICATION N	O. PE-TS-475-507-E002
VOLUME II	
SECTION II	
REVISION 00	DATE: 11.03.2022
Sheet 2 of 2	

finish or coating to avoid rusting during transit and storage. BIS certification mark shall be stamped on each cable drum.

4.3 Each drum shall carry manufacturer's name, purchaser's name, address and contract no., item no. & type, size & length of cable and net gross weight stencilled on both sides of drum. A tag containing same information shall be attached to the leading end of the cable. An arrow & suitable accompanying wording shall be marked on one end of the reel indicating the direction in which it should be rolled.

na	add Item	1.1 KV Power (XLPE	STAT	NDADD OHATE	TV DI AN (CON	FOR MIG TO	Lon No sees see	1				4-9-1-1	As	11 2 11
AIT		VC) Insulated FRLS	COI	NDARD QUALI DE: IS 1554 PART TECHNICA	I Y PLAN (CON F1 , IS 7098 Part L SPECIFICATI	-I AND NTPC	QP. NO. 0000-999- QOE- S-041 REV-01 DATE: 2 \( \sqrt{1} \sqrt{20} \)\( \sqrt{20} \)\( \sqrt{20} \)\( \sqrt{20} \)	REVIEWED AMAN PANDEY RAJESH SHARMA S K LAL	Quan a	8:11:18	8	31	K O	ED BY
SI.	Component	Characteristics	Class	Type of check	Quantu	Quantum of check Reference Document Acceptance Recent Norms For				1	Agen	1011	1	Remarks
No	& Operations			1875	M	C/N	E TORNUS DE GERMAN	ACCOUNT OF THE PARTY OF THE PAR	Format	D	M	C	N	Remarks
1	2	3	4	5	6		7	8	9	(22)	10			11
nstru	ctions: 1) Cabl	manufacturer to maintain	records to	show co-relation	of raw materials	to finished cables	i,e raw material batch/ lot no. shou	ld be traceable to the		3193				
()	L) Cubi	Brought out Items	all quality	y control records is	dentified as per al	II QP stages enum	erated below whether it is identified	for NTPC verification	on or witness	or not		Money		
.01	Aluminum	1.Make	MA	Verify	100%		MANUFACTURER APPROVED SOURCES	MANUFACTUR ER APPROVED SOURCES	QCR		V	-	-	
		2. Resistivity	МА	Elect	As per Cable Mnfr Std.	=	1S5082	IS5082	-do		P	34		
1.02	PVC / XLPE/comp ound for	1. Make	MA	Verify	do	100%	MANUFACTURER APPROVED SOURCES	MANUFACTUR ER APPROVED SOURCES	do		v	V	-	
	insulation	2. Type/ Grade	MA	Verify	100%	100%	NTPC ADS	NTPC ADS	do		v	v	V	Low House
		3. All acceptance test as per manufacturer norms including thermal stability test for PVC insulation	MA	Verify	As per manufacturer norms	As per manufacturer norms	NTPC ADS	NTPC ADS	do		v	v	v	Refer note 1
03	PVC Compound for Inner sheath	1. Make	MA	Verify	do	do	MANUFACTURER APPROVED sources	MANUFACTUR ER APPROVED sources	do	0	v	V	V	
	Siedui	2. Type/ Grade	MA	Verify	do	do	NTPC ADS	NTPC ADS	do		V	V	V	
.04	Steel wire / Formed Wire ( As applicable )	1. Make	МА	Verify	do	do	MANUFACTURER APPROVED sources	MANUFACTUR ER APPROVED sources	do		v	v	V	
	-групологе ј	2. Dimension	MA	Meas	1 sample from each size / lot	CMEN	NTPC APPROVED DATA SHEET & IS 3975	NTPC APPROVED DATA SHEET & IS 3975	do		P			
05	NI G	3. All acceptance tests as per IS 3975	MA	Verify	As per IS 3975	156	IS 3975	IS 3975	Supplier TC		v	V		
05	PVC compound for Sheath	1. Make	МА	Verfy	As per manufacturer norms	100%	MANUFACTURER APPROVED sources	MANUFACTUR ER APPROVED sources	QCR		V	V	***	
	1	2. Type / Grade	MA	Verify	100%	100%	NTPC ADS	NTPC ADS			v	ν	v	

Page 1 of 9

LEGEND:- \*RECORDS, IDENTIFIED WITH "TICK" UNDER COLUMN "D" SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION.
-M:MANUFACTURER/SUPPLIER, C:MAIN SUPPLIER, N:NTPC, P:PERFORM W:WITNESS,V:VERFICATION AS APPROPRIATE, CHP: NTPC SHALL IDENTIFY IN COLUMN "N" AS "W" FORMAT NO:QS-01-QAI-P-10/F3-R1

্যন্ত		: 1.1 KV Power (XLPE VC) Insulated FRLS s	STANI	DARD QUALITY E: IS 1554 PART 1, TECHNICAL S	PLAN (CONFOI , IS 7098 Part-I A PECIFICATION	ND NTPC	QP. NO. 0000-999- QOE- S-041 REV-01 DATE : Page 2 of 9	REVIEWED AMAN PANDEY RAJESH SHARM S K LAL	1 R. Ster		- //	AP 3 A	PROVI	ਰ ਵੇ\
SI.	Component	Characteristics	Class	Type of check	Quantum	of check	Reference Document	Acceptance	Record		Ac	ency		Remarks
No	& Operations				М	C/N		Norms	Format	D*	M	Ć	N	Tromans.
1	2	3	4	5	6		7	8	9		10			11
		All acceptance test as per manufacturer norms	MA	Verify	As per manufacturer norms	As per manufactu rer norms	NTPC ADS	NTPC ADS	QCR		V	V	V	Refer note 1
		4. Thermal Stability	MA	Chem	One sample / Batch	(875)	NTPC ADS	NTPC ADS	QCR		P			
		5. Oxygen Index	MA	Chem	do	900 S	NTPC ADS/ IS 10810 Part 58	NTPC ADS/ IS 10810 Part 58	do		P		THE S	
		6. Acid Gas Emission	MA	Chem	One sample / Batch	58	NTPC ADS / IEC60754	NTPC ADS / IEC60754	QCR		P		-	
1.06	Wooden Drum	1. Dimension	MI	Meas	Manuf. Std.		IS 10418	IS10418	do		Р			
		2. Anti termite treatment	MI	Chem	Cable manuf.	<u>~~</u>	CABLE MANUF, STD.	CABLE MANUF, STD.	COC		V	V	V	COC from drum manuf.
1.07	Steel Drum	1. Dimension	MI	Meas	do	-	do	do	QCR		P			Thunds.
		2. Surface finish	MI	Meas	do		do	do	do-	and the same	P			
В		age Inspection									-			
2.01	Wire Drawing	1.Surface finish	MA	Visual .	One sample/Settin g of each size	-	SHOULD BE SMOOTH & FREE FROM SCRATCHES	SHOULD BE SMOOTH & FREE FROM SCRATCHES	QCR		P	-		
		Wire Diameter	MA	Meas	do	<u></u>	NTPC ADS	NTPC ADS	do-		P			
		3. Tensile test	CR	Mech	do	do	do	do	do		Р	V	V	Refer Sl. No.3.03(iii)
		Wrapping test	CR	Mech	do	do	do	do	do		P	V	V	do
2.02	Bunching /	1. No. of wires	MA	Meas	do		NTPC ADS	NTPC ADS	do-		P	-2-	- 24	
	stranding	2.Dia of wire	MA	Meas	-do	1	do	do	do		P		-	
		3. Dimension of Conductor	MA	Meas	do		do	do	do		P	-		
8		4.Direction of lay	MA	Visual	do		do-	do	do		P	20.8	0015	
		5.Records of strand breakage / welding during conductor stranding	МА	Verify	do	<b>2-</b>	IS 8130	IS8130	do		P		**	
1		6.Surface finish	MA	Visual	do	•	do	do	do		Р			8-5
		7. DC Resistance	CR	Meas	do	2	IS8130/NTPC ADS	IS8130/ NTPC ADS	do		P	**		
2.03	Insulation extrusion	Surface finish	MA	Visual	One sample/Settin g of each size	3	NTPC spec	SHOULD BE SMOOTH, NO POROSITY IS PERMITTED.	QCR		P	77.1		XLPE/ PVC compound shall b preferably loaded in to extruder by suction method.

LEGEND:- \*RECORDS, IDENTIFIED WITH "TICK" UNDER COLUMN "D" SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION.
-M:MANUFACTURER/SUPPLIER, C:MAIN SUPPLIER, N:NTPC, P:PERFORM W:WITNESS, V:VERFICATION AS APPROPRIATE, CHP: NTPC SHALL IDENTIFY IN COLUMN "N" AS "W"
FORMAT NO:QS-01-QAI-P-10/F3-R1

ਹਜ਼ M	मिन्से Item: & P cable	1.1 KV Power (XLPE VC) Insulated FRLS s	CODE	OARD QUALITY : IS 1554 PART 1 TECHNICAL S	PLAN (CONFOR , IS 7098 Part-I AT SPECIFICATION)	ND NTPC	QP. NO. 0000-999- QOE- S-041 REV-01 DATE:	REVIEWED AMAN PANDEY			. /		KOL	ED BY
		a:					Page 3 of 9	RAJESH SHARMA S K LAL DINESH KUMAR	1.			AT Dt.	W.	ed 6
SI. No	Component & Operations	Characteristics	Class	Type of check	Quantum o	of check C/N	Reference Document	Acceptance Norms	Record Format	D*	Agen	C	N	Remarks
1	2	3	4	5	6		7							
1		2.Colour of cores	MA	Visual	One sample/Settin g of each size	8 <b>-</b> 81	NTPC ADS	8 NTPC ADS	9 QCR		10 P			11
		3.Thickness	CR	Meas	do	-	NTPC ADS	NTPC ADS	do		P	207		
		4.Spark Test	CR	Elect	100%	100%	CABLE MANUF. STD.	No FAILURE	do		P	V	V	1.Spark test failure record is to be verified. 2.Core repairing not permitted
		5. Hot Set	CR	Mech	One sample/Settin g of each size	-	IS 7098- Part I	IS 7098- Part I	do		P	-	See	Sample is to be taken from both top & bottom end
2.04	Laying up	1. Core sequence	MA	Visual	do		IS 1554 (Part I) & IS 7098- Part I	IS 1554 (Part I) & IS 7098- Part I	do		P	(max)		top to obtain one
		2. Direction of lay	MA	Visual	do	/	-do-	do	do		P			
		Dia over laid up core	MA	Meas	do	***	NTPC ADS	NTPC ADS	do		P	1922		
2.05	Inner Sheath	1.Colour	MA	Visual	-do	ä	do	do	do		P	-		
		2. Surface Finish	MA	Visual	100%	E	NTPC SPECIFICATION	FISH EYE, BLOW HOLE NOT PERMITTED	do	34	P			
		3.Thickness	MA	Meas	One sample/Settin g of each size	<u> </u>	NTPC ADS	NTPC ADS	do		P	155		5
		4.Dia over inner sheath	MI	Meas	do	800-8	do	do	do		P	-		
2.06	Armouring (	1.Dimension	MA	Meas	do		do	do	do		P			
	As Applicable)	2.No. of wires / strip	MA	Meas.	do	ā	do	do	do		P			
		3. Direction of lay	MA	Visual	do	D##H	IS 1554 (Part 1) & IS 7098- Part I	IS 1554 (Part 1) & IS 7098- Part I	QCR		P			T.

শ্ল		1.1 KV Power (XLPE VC) Insulated FRLS		DARD QUALITY : IS 1554 PART 1, TECHNICAL S		ND NTPC	QP. NO. 0000-999- QOE- S-041 REV-01 DATE :	REVIEWED AMAN PANDEY	manin				K OJI	D BY
							Page 4 of 9	RAJESH SHARMA S K LAI	Lundy	and the same	k	A <sub>l</sub> Dt.,	Co X	A S
SI. No	Component &	Characteristics	Class	Type of check	Quantum o	of check C/N	Reference Document	Acceptance Norms	Record Format	D*	Agend	y C	N	Remarks
-	Operations 2								5.723353890		Parker.		538 Satore	
	2	3 4.Coverage & Quality of armouring	MA	Meas,	6 100%	<b></b>	Min. area of coverage of armouring gap between amour wires / for exceed one amour wire/ formed wirbe no cross over/ over riding of a wire. Zn rich paint shall be appl surface of G.S. Wire /formed wire. amour wire joint shall not be less that wire / formed wire. (As per NTPC sp	med wires shall not e space & there shall amour wire / formed lied on amour joint The breaking load of an 95% of that amour	9 QCR		10 P		2	11
		5 Dia over armouring	MA	Meas.	One sample/Settin g of each size	-	NTPC ADS		do		P	-		<u> </u>
2.07	Outer Sheath	Surface finish	МА	Visual	Visual 100% Pimple, Fish Eye, permitted. Repairing		Pimple, Fish Eye, Burnt particle permitted. Repairing on outer sheat per NTPC specification)	es, Blow Hole not h not permitted. (As	do		P		\$000E	PVC FRLS compound shall be preferably loaded in to extruder by suction method.
		2.Colour of sheath	MA	Visual	One sample/Settin g of each size	Maria	NTPC ADS	NTPC ADS	do		P	-	*	
		3. Dia over outer sheath	MA	Meas	do	-	NTPC ADS	NTPC ADS	do		P		1570	
		4.Thickness of outer sheath	CR	Meas	do	7	do	do	do		P	2	<u> </u>	
		5. Embossing quality	MA	Visual	100%	•	Drum No.,IS1554-I & IS7098-1, grade & Words "FRLS" at ever embossed. Embossing shall be at marking shall be legible & indel specification)	y 5 meter is to be atomatic, in line & lible. (As per NTPC	do		Р		E	Drum No. on Cable may be embossed/printed
		6. Sequencial marking	MA	Visual	Full length	229	Sequencial marking of length of cal one meter is to be embossed / pr printing shall be progressive, au marking shall be legible & indelib specification) In addition, Drum No. is also to be full cable length	inted. Embossing / itomatic, in line & le. ( A s per NTPC	do		P		-	
C 3.01	Finished Cabl Type test	All type tests as per	CR	Doc.	1000/	1000/	NITTO CRECIEIO ATION (NITTO	L	000 100 P		- n			
3.01	reports clearance from NTPC	NTPC specification	CK	Doc.	100%	100%	NTPC SPECIFICATION / NTPC ADS / IS 1554 (Partl) & IS 7098- Part I	NTPC SPECIFICATION / NTPC ADS / IS 1554 (Partl) & IS	do	~	P	v	V	

553	Engineering							7098- Part I			1		Lerna	
ত্র্	श्रीमी Item:	1.1 KV Power (XLPE VC) Insulated FRLS	STANI	DARD QUALITY : IS 1554 PART 1, TECHNICAL S	PLAN (CONFOR IS 7098 Part-1 A PECIFICATION)	ND NTPC	QP. NO. 0000-999- QOE- S-041 REV-01 DATE: Page 5 of 9	RAJESH SHARMA	200				K OJI	HA T
SI.								DINESH KUMAR	1			4. 3	~ 0	
No	Component & Operations	Characteristics	Class	Type of check	Quantum e M	of check C/ N	Reference Document	Acceptance Norms	Record Format	D*	Agend	C	N	Remarks
1	2	3	4	5	6		7	8	9		10		L	11
3.02	Routine Tests	High Voltage test at room temperature	CR	Elect	100%	100%	NTPC ADS / IS 1554 (Part I) & IS 7098- Part I	NTPC ADS / IS 1554 (Part I) & IS 7098- Part I	Test certific ate	1	P	W	V	Refer note 2
		2.Conductor Resistance	CR	Elect	100%	100%	NTPC ADS / IS 1554 (Part I) & IS 7098- Part I	NTPC ADS / IS 1554 (Part I) & IS 7098- Part I	Test certific ate	1	P	W	V	Refer note 2
3.03	Acceptance T									573795-111				
3.03 (i)	Construction of finished Cable	1. OD of Cable	MA	Meas.	Each type & si as per samplin 1554 ( Part 1) Part	g plan of IS & IS 7098-	NTPC ADS	NTPC ADS	do	~	P	w	W	
		2. Laying of core	CR	Visual	do		NTPC ADS / IS 1554 (Part I) & IS 7098- Part I	NTPC ADS / IS 1554 (Part I) & IS 7098- Part I	do	~	P	W	W	
		3. Core Identification	CR	Visual	do		do	do	do	<b>V</b>	P	w	W	
		4. Colour of outer sheath	МА	Visual	Each type & si as per samplin 1554 ( Part 1) Part	g plan of IS & IS 7098-	NTPC ADS	NTPC ADS	do	~	P	w	W	
		5. Inner sheath thickness	CR	Meas	- do		do	do	do	~	P	w	W	
		6. Inner sheath colour	MA	Visual	- do	23	- do -	- do -	do	1	P	w	w	
3.03 (ii)	Armour wires/ Formed wires ( if	1.Dimensions	CR	Meas	do	<b>A=</b> 3	NTPC ADS /IS1554(Partl)/IS3975	NTPC ADS /IS1554(PartI) /IS3975	do	~	Р	W	w	
	applicable)	2. No. of wires/ formed wire	CR	Mech	do	-	do	do	do	<b>V</b>	P	W	W	
		3. Tensile test	CR	Mech	do		do-	do	do	1	P	v	V	
		4. Elongation test	CR	Mech	do	-41	do	do	do	/	P	V	V	
		5. Torsion test ( for round wires only)	CR	Mech	Each type & si as per samplin 1554 ( Part 1) Part	g plan of IS & IS 7098- I	do	do	do	~	P	V	V	
	8	6. Wrapping test	CR	Mech	do		do	do	do	1	P	V	V	
	10 10	7. Resistance test	CR	Mech	do		do	do-	do-	1	P	v	v	

LEGEND:- \*RECORDS, IDENTIFIED WITH "TICK" UNDER COLUMN "D" SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION.
-M:MANUFACTURER/SUPPLIER, C:MAIN SUPPLIER, N:NTPC, P:PERFORM W:WITNESS,V:VERFICATION AS APPROPRIATE, CHP: NTPC SHALL IDENTIFY IN COLUMN "N" AS "W"
FORMAT NO:QS-01-QAI-P-10/F3-R1

VAI:		1.1 KV Power (XLPE VC) Insulated FRLS		IS 1554 PART 1,	PLAN (CONFORMING TO IS 7098 Part-1 AND NTPC PECIFICATION)	QP. NO. 0000-999- QOE- S-041 REV-01 DATE:	REVIEWED AMAN PANDEY				APPR K	K OJI	11.83
					7.	Page 6 of 9	RAJESH SHARMA S K LAL JUNESH KUMAR	Liste	مست	Tale of the same o	774		(3)
SI. No	Component & Operations	Characteristics	Class	Type of check	Quantum of check M C/N	Reference Document	Acceptance Norms	Record Format	D*	Agend	C	N	Remarks
1	2	3	4	5	6	7	8	9		10		<u> </u>	11
	-	8.Mass of Zinc coating	CR	Meas	do	do	do	do	1	P	V	V	11
		9. Uniformity of Zinc Coating	CR	Chem.	Each type & size of cables as per sampling plan of IS 1554 (Part 1) & IS 7098- Part I	NTPC ADS /IS1554(Partl)/IS3975	NTPC ADS /IS1554(PartI) /IS3975	Test certific ate	~	P	V	V	,
		10.Adhesion test	CR	Mech	do	do	do-	do	1	P	V	V	
		11.Freedom from defects	CR	Visual	do	do	do	do	1	P	V	V	
3.03	Conductor												
(iii)		1.Resistance Test	CR	Elect	do	do	do	do	~	P	W	W	
		2.Tensile test ( For aluminum conductor only )	CR	Mech	Each type & size of cables as per sampling plan of IS IS 1554 (Part I)/7098(Part- 1)	NTPC ADS/ IS 8130	NTPC ADS/IS 8130	do	*	P	W	w	Test report of manufacturer to be reviewed as per SI No. 2.01 for Tensile test & wrapping test ( for Aluminum ) in case this test is not applicable for cable under inspection as per IS 8130 cl. 6.2
		3.Wrapping test (For aluminum conductor only)	CR	Mech	do	do	do	-do	1	Р	P	w	do
3.03 (iv)	PVC / XLPE Insulation & PVC Sheath	1.Thickness of insulation & sheath	CR	Meas.	do-	NTPC ADS/ IS 1554(Partl) & IS 7098-Part I	NTPC ADS/ IS 1554(PartI) & IS 7098-Part I	do	~	P	W	W	

	Item Powe PVC FRL	er (XLPE & ) Insulated S cables	(CON	FORMING TO 7098 Part-I AN SPECIFI	UALITY PLAN CODE: IS 1554 PART D NTPC TECHNICAL CATION)	QP. NO. 0000-999- QOE- S-041 REV-01 DATE: Page 7 of 9	REVIEWED AMAN PANDEY RAJESH SHARM/ S K LAL	dimanun		San Susai		COJ	DBY
SI. No	Operations	Characteristics	Class	Type of check	Quantum of check M C/ N	Reference Document	Acceptance Norms	Record Format	D*	Agenc	C	N	Remarks
1	2	3	4	5	6	7	8	9		10			11
		2.Tensile strength & elongation at break of insulation & outer sheath	CR	Mech	Each type & size of cables as per sampling plan of IS IS 1554 (Part 1)/IS7098(Part-1)	NTPC ADS/ IS 1554(Partl) & IS 7098 Part I	NTPC ADS/ IS 1554(Partl) & IS 7098 Part I	Test Certific ate	√.	P	W	W	-11
		3.Tensile strength & clongation of PVC at break of insulation & outer sheath (Ageing Test )	CR	Mech	One sample per batch of offered lot irrespective of sizes	do	do	do	¥	P	V	V	MTR for Ageing Test of the offered to shall be ventied
		3a. Tensile strength & clongation of XLPE at break of insulation (Ageing Test)	CR	Mech	do	NTPC ADS/ IS 7098 Part I	NTPC ADS/ IS 7098 Part I	do	1	P	V	V	MTR for Ageing Test of the offered lot shall be verified
		4. Insulation resistance (Volume resistivity method)	CR	Elect	Each type & size of cables as per sampling plan of IS 1554 ( Part 1) & IS 7098- Part I	do	NTPC ADS/ IS 1554(Partl) & IS 7098 Part I	do		P	W	W	
		5.High voltage test at room temperature	CR	Elect	Each type & size of cables as per sampling plan of IS 1554 ( Part 1) & IS 7098- Part 1	do	do	do	1	P	w	W	ā
		6.Thermal stability on PVC Insulation and outer sheath	CR	Chem	One sample of each offered lot of all offered sizes	-do	do	do	~	Р	W	W	
		7. Hot Set Test (for XLPE Insulation only)	CR	Elect	Each type & size of cables as per sampling plan of IS 1554 ( Part 1) & IS 7098- Part I	NTPC ADS/ IS 1554(Partl) & IS 7098 Part I	do	do	~	P	w	W	
		8.Oxygen index Test on outer sheath	CR	Chem	One sample of each offered lot of all offered sizes	NTPC ADS / IS10810 Part 58	NTPC A.D.S / IS10810 Part 58	Test certific ate	1	P	W	W	Refer Note 3

ু ব	Item: & PV cables	1.1 KV Power (XLPE C) Insulated FRLS		DARD QUALITY E: IS 1554 PART 1, TECHNICAL S		ND NTPC	QP. NO. 0000-999- QOE- S-041 REV-01 DATE: Page 8 of 9	REVIEWED AMAN PANDEY RAJESH SHARMA S K LAL	1	مسو		1/3	K OJI	DBY Oved O
SI.	Component &	Characteristics	Class	Type of check	Quantum o	f chack	Reference Document	DINESH KUMAR	-			S. Carlo	10	1107/
No	Operations		Cias	Type of check	M	C/N	Reference Document	Acceptance Norms	Record Format	D*	Agen	C	N	Remarks
1	2	3	4	5	6		7	8	9	-	10	- 002	20000-00	11
		9.Smoke density rating test on outer sheath	CR	Chem	do-	*	NTPC ADS & ASTMD2843	NTPC ADS	-do	1	P	W	W	Refer Note 3
		10.Acid gas generation test on outer sheath	CR	Chem	do-	**	NTPC ADS & IEC 60754-1	'NTPC ADS	Test Certific ate	1	P	W	w	Refer Note 3
		11.Flammability test on completed cable	CR	Chem	Refer Note 4	Refer Note 4	NTPC ADS & IEC 60332 Part-3 ( Category-B)	NTPC ADS	do	1	P	W	w	
		12.Surface finish & length measurement.	CR	Visual & Meas	100% (COC from Manufacturer to be submitted for surface finish as per specification's requirement)	one length of each offered lot of 50 drums of all sizes	(1) IS1554-1 & IS7098-1, Cable sit Words "FRLS" at every 5 meter Embossing shall be automatic, in lin legible & indelible. (2) Sequential reable in meter at every one meter printed. Embossing / printing slautomatic, in line & marking shall be	is to be embossed.  e & marking shall be marking of length of is to be embossed / mall be progressive.	do	~	P	w	W	Pimple, Fish Eye, Burnt particles, Blow Hole etc. no permitted. Repairing on oute sheath not permitted.
		13. Sequence of cores armour coverage, gap between two consecutive armour/ formed wire	CR	Visual & Meas	One length of each size	One length of each size	Min. area of coverage of armouring gap between armour wires / for exceed one armour wire/ formed wirbe no cross over/ over riding of arwire. Zn rich paint shall be applisurface of G.S. Wire /formed wire	med wires shall not e space & there shall mour wire / formed	do-	9 🗸	P	w	w	
4	Packing	1. Scaling	MA	Visual	100%	100%	(1)IS1554(Part-I) & IS 7098-Part I (2 drum and the outer most cable layers water proof cover. (3) Both the enc properly sealed with heat shrinkable secured by "U" nails.	hall be covered with	QCR	~	P			
4.01	Identification	NTPC Sealing	MA	Visual	100%	100%	Scaling shall be visible		QCR	_	P	v	v	

'ম্ম	Po PV FF	m: 1.1 KV wer (XLPE & 'C) Insulated RLS cables	(CONI	ANDARD QI FORMING TO C 7098 Part-I AND SPECIFIC	CODE: IS 15 NTPC TEC CATION)	554 PART CHNICAL	QP. NO. 0000-999- QOE- S-041 REV-01 DATE: Page 9 of 9	REVIEWED AMAN PANDEY RAJESH SHARMA S K LAL DINESH KUMAR	A = C	1. 	110	PPROVI	l'es
SI. No	Componen & Operations		Class	Type of check	Quantum M	of check C/ N	Reference Document	Acceptance Norms	Record Format		Agency M C N		Remarks
1	2	3	4	5	6	/I	7	8	9		10		11
		not carrying out age be one sample /bate	ing test :h)	, then cable ma	nufacturer	is to carry	report of compound manufact out ageing test & test repor	t is to be review	red (qu	antum o	of age	ing te	st sample sha
	2)	internal test report a 2(b) In case of m	are to be anufact Contract	e verified by NT turers / suppl or on 100% ba	PC at the ier WHO I	time of fin	lied cables in the past throal inspection.  T SUPPLIED cables in the to manufacturer internal test	past through (	Corpora	te Cent	:re:- R	coutine	Test are to I
	3)	to be carried out  2. For Acid Gas of to be carried out  3. For Oxygen In carried out with of the test option of retesting	with co General with co dex tes condition results g the sa	nditioning of ion test: if the nditioning of t: if the test re oning of sampl without cond amples after co	samples as test result samples as sult withoutes as per s itioning do onditioning	s per stand t without s per stand ut conditi standard a conot meet g as per s		er conditioning 0% of the maxi er conditioning the minimum sp ditioning shall pecified value,	shall be mum sp shall be ecified be final the mar	e final for ecified to the final for accordance to the for accordance to the first for accordance for accordanc	or according to a control or according to a	ceptar e, then ceptar etestin nce/rej ny exe	nce/rejection , retesting is nce/rejection ng is to be lection.
	4)	more than 30 mm,	lubbing	to be done for	cables hav	ing similar	n equal to 30 mm, any size o ODs. les having similar ODs.	f cable may be o	lubbed t	ogether.	For c	ables	where OD is
LEG	END:		nufac	turer's inte	rnal pla		uality control record lard, MI: minor, MA: r				, CA	BLE	MANUF

CLAUSE NO.

एनरीपीसी NTPC

#### QUALITY ASSURANCE



#### **LT Power Cables**

Attributes / Characteristics  Item / Components / Sub System Assembly	Make, Type & T.C as per relevant standard	Dimension/surface finish	Mechanical properties	Chemical Composition	Spark Test(as applicable)	Electrical properties	Hot Set Test/ Eccentricity & Ovality	Lay length & Sequence	Armour coverage, cross over, looseness, gap between two wires	Sequential marking/ Batch marking/ surface finish/ cable length	T.S & elongation before & after ageing on outer sheath & insulation	Thermal stability	Anti termite coating on wooden	Constructional requirements feature as per NTPC specification	Routine & Acceptance Tests as per relevant standard & NTPC specification	FRLS Tests
Aluminum (IS-8130) Y YYY Y																
XLPE Compound (IS-7098) Y Y YY Y																
PVC insulation Compound (IS: 5831) Y Y Y Y																1
FRLS PVC Compound	YY	Y	Y	Y												
(IS-5831, ASTM-D2843, IS10810( Part 58), IEC-60754 Part-1)																
Extrusion & curing /Manufacturing of Core	Y Y	v	Y													
(PVC/XLPE)	1 1		1													
Core Laying Y																
Armour wire/strip Y YY																
Inner sheath Y Y																
Armouring Y Y									_							
Outer Sheathing Y Y																
Power Cable (Finished) (IS-5831, ASTM-D2843,	Y	ΥY	YY	Y	ΥY											
IS10810( Part 58), IEC-60754 Part-1, IEC 60332																
part III cat B)																
Wooden drum(IS-10418) /Steel Drum Y YY																,

#### Notes

- 1. This is an indicative list of tests / checks. The manufacturer is to furnish a detailed Quality Plan indicating the practice and procedure along with relevant supporting documents.
- 2. Make of all major Bought out items will be subject to NTPC approval.

KHURJA SUPER THERMAL POWER PROJECT (2X660 MW) TURBINE GENERATOR AND ASSOCIATED PACKAGES	TECHNICAL SPECIFICATION SECTION-VI, PART-B BID DOC NO.: THDC/RKSH/CC-9915-371	SUB-SECTION-E-16 LT POWER CABLE	PAGE 1 OF 4
---	---	------------------------------------	----------------

CLAUSE NO.

एनटीपीसी NTPC

#### **QUALITY ASSURANCE**



ROUTINE TESTS Follow	ving routine tests shall be carried out on ea Ch drum of finished cables for all types (PVC / XLPE insulated) & sizes.
1) Conductor Resistar	nce test
2) High voltage test	
ACCEPTANCE TESTS	Following Acceptance tests shall be carried out on each size of each type (PVC / XLPE insulated) of cables, in the offered lot.
A) For Conductor (as pe	r sampling plan mentioned in IS: 1554 / 7098)
1)	Annealing test (Copper)
2)	Tensile Test ( Aluminum)
3)	Wrapping Test ( Aluminum)
4)	Resistance test
B) For Armour Wires / For 1.	ormed Wires ( If applicable ) (as per sampling plan mentioned in IS: 1554 / 7098)  Measurement of Dimensions
2.	Tensile Tests
3.	Elongation Test
4.	Torsion Test For Round wires only
5.	Wrapping Test
6.	Resistance Test
7.	Mass of Zinc coating test For G S wires / Formed wires only
8.	Uniformity of Zinc coating For G S wires / Formed wires only
9.	Adhesion test For G S wires / Formed wires only
10.	Freedom from surface defects
C ) For PVC / XLPE insu	lation & PVC Sheath (as per sampling plan mentioned in IS: 1554 / 7098)
1)	Test for thickness
2)	Tensile strength & Elongation before ageing (for tests after ageing see "D")
3)	Hot set test (For XLPE insulation)
D) Ageing test:	

KHURJA SUPER THERMAL POWER PROJECT
(2X660 MW)
TURBINE GENERATOR AND ASSOCIATED PACKAGES

TECHNICAL SPECIFICATION SECTION-VI, PART-B BID DOC NO. : THDC/RKSH/CC-9915-371

SUB-SECTION-E-16 LT POWER CABLE PAGE 2 OF 4

				T						
Criter	I .			Requirements Rea						
PVC insulation & outer sheath:	Samples as per releving size of cables in the tested for tensile structure (before ageing). Testesting shall prefers a computerized matches will be corresponding value to the testing shall prefers a computerized matches will be corresponding value.	offered lot, shall rength & elongat nsile & elongati ably be done with chine. ompared with s mentioned in the tepted by NTPC.	meet the criteria  ion  on th	The size which has negative deviation report values will laccelerated ageing shall be aged in air temperature of 130 hours and tested for elongation.  Acceptance norms	from type test be put on test. The samples oven at 0°c+/- 2°c for 5 or TS &	In case the size does not meet the requirement in accelerated ageing test then all sizes (which had met the criteria) will be put on ageing test as per IS.				
	These values of Ten Elongation (before a within +/ - 15% of the values of Type Test that test values shou minimum values industandard).	ngeing) should be the corresponding report. (Please n ld be more than	meet the criteria ote the	Every size will be as per IS.	put on ageing test					
XLPE insulation	Samples as per relev	vant IS, from eac	h size of cables in the offe	ered lot,will be put o	on ageing test as per	IS.				
		out on complete	d cables as ner IS on eac	1	(DVC / VI DE : au					
E) Following	tests will be carried a		leted cables as per IS on each size of each type (PVC / XLPE insulated)							
	tests will be carried (					llated)				
E) Following 1) 2)	tests will be carried o	Insulati	on resistance test (Volum ltage test			llated)				
1) 2)		Insulation High vo	on resistance test (Volun ltage test	ne resistivity method	1)	llated)				
1) 2) <b>F) Following</b>		Insulation High vo	on resistance test (Volum ltage test	ne resistivity method	& types)	llated)				
1) 2) <b>F) Following</b> 1)		Insulation High vo	on resistance test (Volum ltage test  size of offered lot (complete stability test on PVC ins	orising of all sizes &	& types)	llated)				
1) 2)  F) Following 1  2)		out on only one Therma Oxygen	on resistance test (Volumentage test)  size of offered lot (complete test)  stability test on PVC instance index test on outer sheath	orising of all sizes &	& types)	llated)				
1) 2)  F) Following (1) 2) 3)		out on only one Therma Oxygen Smoke	on resistance test (Volum ltage test  size of offered lot (complete stability test on PVC instance index test on outer sheath density rating test on outer	orising of all sizes & ulation and outer short respectively.	& types)	llated)				
1) 2)  F) Following 1 1) 2) 3) 4)	tests shall be carried	out on only one Therma Oxygen Smoke Acid ga	esize of offered lot (complete test)  I stability test on PVC instance index test on outer sheath density rating test on outer segmentation test on outer	prising of all sizes & ulation and outer short r sheath sheath	& types)					
1) 2)  F) Following 1 1) 2) 3) 4) G) Flammabi	tests shall be carried	out on only one Therma Oxygen Smoke Acid ga  0332 - Part- 3 (	esize of offered lot (complete stability test on PVC instability rating test on outer sheath density rating test on outer segmentation test on outer Category-B) on complete	prising of all sizes dulation and outer short sheath sheath ed cables as per followers.	& types)					
1) 2)  F) Following 1 1) 2) 3) 4) G) Flammabi	tests shall be carried	out on only one Therma Oxygen Smoke Acid ga  0332 - Part- 3 (composite sampli	Itage test  size of offered lot (complete stability test on PVC instability test on outer sheath density rating test on outer segmentation test on outer category-B) on completing i.e. irrespective of size:	prising of all sizes & ulation and outer short sheath sheath cables as per followed to the cables of one	types) eath  llowing sampling p	lan:				
1) 2)  F) Following 1 1) 2) 3) 4) G) Flammabi	tests shall be carried	out on only one Therma Oxygen Smoke Acid ga  0332 - Part- 3 (composite sampli	esize of offered lot (complete stability test on PVC instability rating test on outer sheath density rating test on outer segmentation test on outer Category-B) on complete	prising of all sizes & ulation and outer short sheath sheath cables as per followed to the cables of one	types) eath  llowing sampling p	lan:				

	एनशिपीशी NTPC		QUALITY ASSURANCE		
		with cove For toge toge take	alated, unarmoured XLPE insulated) will be to the IEC. All sizes of PVC & XLPE insulated ered. one particular type, cables with OD less than either in touching formation while cables with either leaving a gap equal to OD of cable haven as nominal overall diameter as per NTPC a	ed, armoured & unarmoured con or equal to 30 mm shall be con OD greater than 30 mm shalling least diameter. Cable OD approved datasheet.	cables shall be lubbed l be clubbed
	ing tests shall be o		gth of each size of each type (PVC / XLPE	,	
1)		arm	astructional / dimensional check, surface finis our coverage, Gap between two consecutive king, drum / Batch (outer sheath extrusion by	armour wires / formed wires,	Sequential
2)		Mea	asurement of Eccentricity & Ovality		

	MANUFACT	URER/ BIDDER		ST	ANDARD QUALITY PLA	AN	SPEC. NO	PE-TS-4	75-5	07-E002	DATE:
बी एच इ		NAME & ADDRESS	_		NTPC					002, REV 02.	
mil	E		PROJ	<b>ECT:</b> 2X66	OMW KHURJA TG &	ASSOCIATED	PP NO.:				
77			ITEM: LT XLPE POWER CABLE SYSTEM: CABLE SECTION					I			SHEET 10 OF 12
	COMPONENTS & OPERATIONS	CHARACTERSTICS		TYPE OF CHECK	QUANTUM OF CHECK			FORMAT		AGENCY	REMARKS
1	2	3	4	5	6 M C/N	7	8	9	* D	** M C N	
T					IVI C/IN				D	W   C  N	
o F	inal Inspection										
	Final Inspection EXTERNAL)										

4.0	Final Inspection (EXTERNAL)													
		6 Type Tests												
		6. Type Tests (Refer Note-H)	CR	Physical & Electrical Tests	Sample #	Sample #	#	- #	TEST REPORT	1	P	w	W	# REFER ANNEXURE-A TO QP

	BHEL						DDER/ SUPPLIER		FOR CUSTOMER REVIEW & APPROVAL					
	ENGINEERING			QUALITY		Sign & Date		Doc No:						
	Sign & Date	Name	9	Sign & Date	Name	Seal			Sign & Date	Name	Seal			
Prepared by:	July 03.201	VIKAS KUMAR SINGH	Checked by:	INTER OF THE	KUNAL GANDHI			Reviewed by:						
Reviewed by:	Maurich		Reviewed by:	المرازا	RITESH KUMAR JAISWAL			Approved by:						
	18 03	W		(913)	2020									

	MANUFACT	URER/ BIDDER	1	ST	ANDARD QUA	ALITY PL	AN	SPEC. NO	PE-TS-	475-	507-E	002	DATE:
ीएच ई	एन SUPPLIER N	NAME & ADDRESS	CUST	OMER: NT	PC			QP NO.: P	E-QP-999	-507-E	E002, RI	EV 02.	
			PROJ	<b>ECT:</b> 2X66	OMW KHURJ	A TG &	ASSOCIATED	P 6 NO.:					
			ITEM	LT XLPE PO	WER CABLE		SYSTEM: CAB	LE SECTION:	II .				SHEET 11 OF 12
1		OLLA DA OTEROTION	101.40	T-05-05	TO LLANTING	-	IDEEEDE VOE	14005574110	TEODA A	- 05			
	COMPONENTS & OPERATIONS	CHARACTERSTICS		TYPE OF CHECK	QUANTUM ( CHECK	JF		ACCEPTANC E NORMS	FORMA'		AGEN	CY	REMARKS
1	2	3	1	5	6		7	8	9	*	**		
			4	9	M	C/N	7 '	0	9	D	M	CN	

5.0	Packing	End sealing / Polythene wrapping	MA	Visual	100%	100%	Appd. Datasheet	Appd. Datasheet	-do-	1	Р	w	

#### NOTES:

- A. Joints in conductors & armour shall be as permitted by IS:8130 & IS:7098-I respectively.
- B. No repair of core insulation permitted.
- C. Cable ends shall be sealed.
- D. Record of raw material, process & all stages shall be certified by Vendors QC and are liable to audit check by purchaser.
- E. Fillers/dummy cores etc. Shall be as per BHEL specification.
- F. Wherever extent of check for stage is mentioned as 'sample' & not defined in QP, the same shall be as per vendors sampling plan agreed by purchaser.
- G. Vendor shall furnish compliance certificate to the inspection agency confirming the packing as per IS/ BHEL specification.
- H. For lists of routine tests, acceptance tests & type tests refer annexure to QAP.
- I. Cable manufacturer to maintain records to show co-relation of raw materials to finished cables i.e. raw material batch/ lot no. should be traceable to the final cable drum number or batch no.
- J. Cable manufacturer to maintain all quality records identified as per all QP stages enumerated below whether it is identified for BHEL verification or witness or not.
- K. BHEL reserves the right to perform repeat test, if required.
- L. Photographs of cable to be despatched shall be sent to BHEL purchase group for review prior to issue of mdcc.
- M. Project specific QP to be prepared in line with this standard QP.
- N. In case of export jobs, sea worthy packing as per BHEL technical specification shall be carried out.

#### LEGENDS:

	BHEL					BII	DDER/ SUPPLIER	FOR CUSTOMER REVIEW & APPROVAL						
	ENGINEERING		4	QUALITY		Sign & Date		Doc No:						
	Sign & Date	- Name		Sign & Date	Name	Seal			Sign & Date	Name	Seal			
Prepared	July 03.2020	VIKAS KUMAR	Checked by:		KUNAL			Reviewed						
by:	12,18.00	SINGH		Antono 3/20	GANDHI			by:						
Reviewed	Marrish	MANISH	Reviewed	81	RITESH KUMAR			Approved			A COLUMN TO A STATE OF THE PARTY OF THE PART			
by:	18/03/	SHUKLA	by:	144	JAISWAL			by:						
	10/05/	40		1913/2	070				OR OTHER DESIGNATION OF THE PERSON NAMED IN COLUMN 1					

	MANUFACT SUPPLIER			STA	NDARD QUA	LITY PLA	N	SPEC. NO.:					DATE:	<del>37</del> 81
बीएच इ			CUSTOMER: NTPC QP NO.: PE-QP-999-507-E002, REV 02.  PROJECT 2X660MW KHURJA TG & ASSOCIATED PKG PO NO.:				02.							
-77			ITEM:	LT XLPE POV	VER CABLE		SYSTEM: CABI	LE SECTION: I	ı				SHEET 1	2
	COMPONENTS & OPERATIONS	CHARACTERSTICS			QUANTUM C	)F			FORMAT RECORD		AGENCY	′	REMARK	s
1	2	3	4	5	6 M	C/N	7	8	9	* D	** M C	N		

\*RECORDS, IDENTIFIED WITH "TICK"(√) SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION,

\*\* M: SUPPLIER/ MANUFACTURER/ SUB-SUPPLIER, B: MAIN SUPPLIER/ BHEL/ THIRD PARTY INSPECTION AGENCY, C: CUSTOMER,

P: PERFORM, W: WITNESS, V: VERIFICATION, AS APPROPRIATE

MA: MAJOR, MI: MINOR, CR: CRITICAL

D: DOCUMENTATION

		BI	HEL		
	ENGINEERING			QUALITY	
	Sign & Date	Name		Sign & Date	Name
Prepared by:	Juan 8.03. 200	VIKAS KUMAR SINGH	Checked by:	West of	KUNAL GANDHI
Reviewed by:	Marrish	MANISH SHUKLA	Reviewed by:	Testal.	RITESH KUMAR JAISWAL

1	BI	DDER/ SUPPLIER
٦	Sign & Date	
	Seal	
2		

	FOR CUSTOMER REVIEW & APPROVAL					
Doc No:						
	Sign & Date	Name	Seal			
Reviewed by:						
Approved						
by:						

0



ANNEXURE-A TO QP	CUSTOMER: NTPC	PROJECT TITLE 2X660MW KHURJA TG	SPECIFICATION NUMBER: PE-TS-475-507-E002	R
	BIDDER/VENDOR:	QUALITY PLAN NUMBER: PE-QP- 999-507-E002, R02	SPECIFICATION TITLE:	
SHEET 1 OF 3	SYSTEM: CABLE	ITEM: LT XLPE POWER CABLE	DOC. NO.	

#### TYPE/ ACCEPTANCE/ ROUTINE TEST REQUIREMENTS

#### A. Type Test Conduction:

- 1. Tests for which "T" is indicated in the 'Test Conduction Required As' column below shall be conducted as Type Test.
- 2. Sampling:
  - a) Type test to be conducted on one size of cable for every lot and type of cable (CU/AL conductor)
  - b) FRLS & Flammability Test to be conducted only on one sample/ lot.
- **B.** Acceptance Test Conduction:
- 1. Tests for which "A" is indicated in the 'Test Conduction Required As' column below shall be conducted as Acceptance tests.
- Sampling: Sampling for acceptance tests shall be as per Appendix-B (Clause 15.2.2) of IS: 7098 Part-I.
- 3. Flammability Test to be conducted only on one sample/ lot.
- C. Routine Test Conduction:
- 1. Tests for which "R" is indicated in the 'Test Conduction Required As' column below shall be conducted as Routine tests.
- D. Tests listed in S.No-7.0 & 8.0 shall be conducted only on one sample / lot.


Note: LOT shall be considered as per IS: 7098 Part-I, appendix-B.

<u>S. No.</u>	TEST	APPLICABLE FOR	TEST CONDUCTION REQUIRED AS	REFERENCE STANDARD	REMARKS
1.0	Tests for Conductor				
I.	Annealing test	For copper conductor only	T, A	IS 10810 Pt 1	Internal in process Test Report to be furnished for acceptance test
II.	Tensile test	For aluminium conductor only (Not applicable for compacted circular or shaped conductor)	T, A	IS 10810 Pt 2	
III.	Wrapping test	For aluminium conductor only (Not applicable for compacted circular or shaped conductor)	T, A	IS 10810 Pt 3	
IV.	Resistance test	For Al/Cu	T, A, R	IS 10810 Pt 5	-1-1-1

		1	BHEL		
E	NGINEERIN	4G		QUALITY	
	Sign & Date	Name		Sign & Date	Name
Prepared by:	18.03.2020	VIKAS KUMAR SINGH	Checked by:	140000	KUNAL GANDHI
Reviewed by:	Marin	MANISH SHUKLA	Reviewed by:	टिनेश	RITESH KUMAR

ign & Date	
eal	

FOR CUSTOMER REVIEW & APPROVAL				
Doc No:				
	Sign & Date	Name	Seal	
Reviewed by:				
Approved by:				



<u>S. No.</u>	TEST	APPLICABLE FOR	TEST CONDUCTION REQUIRED AS	REFERENCE STANDARD	REMARKS
2.0	Tests for Armour Wires/Strips				
I.	Measurement of dimensions	Applicable for Aluminium wire & GS wire/Strip	T,A	IS 10810 Pt 36	
II.	Tensile test	Applicable for Aluminium wire & GS wire/Strip	T, A	IS 10810 Pt 37	
III.	Elongation at break test	Applicable for GS wire/Strip only	T, A	IS 10810 Pt 37	
IV.	Torsion test	For GS round wire only	T, A	IS 10810 Pt 38	
٧.	Winding / Adhesion Test	For GS strip only	T, A	IS 10810 Pt 39	
VI.	Resistivity test	Applicable for Aluminium wire & GS wire	T, A	IS 10810 Pt 42	
VII.	Uniformity of Zinc coating test	For G. S. wires/Strip only	T, A	IS 10810 Pt 40	
VIII.	Mass of Zinc coating test	For G. S. wires/Strip only	T, A	IS 10810 Pt 41	
IX.	Wrapping Test	Applicable for Aluminium wire & GS wire	T, A	IS 10810 Pt 3	
3.0	Physical Tests for XLPE Insulation & PVC sheath				
1.	Test for thickness	Applicable for XLPE insulation, PVC inner sheath & PVC outer sheath	T, A	IS 10810 Pt 6	
11.	Tensile strength and elongation test at break	Applicable for XLPE insulation & PVC outer sheath			
(a)	Before ageing		T, A	IS 10810 Pt 7	
(b)	After ageing		T, A	IS 10810 Pt 7	
III.	Ageing in air oven	Applicable for XLPE insulation & PVC outer sheath	Т	IS 10810 Pt 11	
IV.	Loss of mass in air oven test	For PVC outer sheath only	Т	IS 10810 Pt 10	
٧.	Hot deformation test	For PVC outer sheath only	T	IS 10810 Pt 15	
VI.	Heat shock test	For PVC outer sheath only	T	IS 10810 Pt 14	
VII.	Shrinkage test	For XLPE insulation & PVC outer sheath only	Т	IS 10810 Pt 12	
VIII.	Thermal stability test	For PVC outer sheath only	T	IS 10810 Pt 60	
IX.	Hot set test	For XLPE insulation only	T, A	IS 10810 Pt 30	
X.	Water absorption (gravimetric) test	For XLPE insulation only	Т	IS 10810 Pt 33	
4.0	Improved Fire performance (FR-LSH) Tests				

		1	BHEL		
E	NGINEERIN	IG		QUALITY	
	Sign & Date	Name		Sign & Date	Name
Prepared by:	July 2.2020	VIKAS KUMAR SINGH	Checked by:	West 11	KUNAL GANDHI
Reviewed by:	Manuel	MANISH SHUKLA	Reviewed by:	िक्स	RITESH KUMAR

BIDDER/SU	JPPLI
Sign & Date	
Seal	

FOR CU	STOMER REVI	EW & AP	PROVAL
Doc No:			
	Sign & Date	Name	Seal
Reviewed by:			
Approved by:			



S. No.	TEST	APPLICABLE FOR	TEST CONDUCTION REQUIRED AS	REFERENCE STANDARD	REMARKS
l.	Oxygen index test	For PVC outer sheath only	T, A	IS 10810 Pt 58 / ASTMD 2863/ NES 715-I	Applicable for Inner Sheath
II.	Smoke density test	For PVC outer sheath only	T	IS 10810 Pt 63 / ASTMD 2843	also, if the
III.	Acid gas generation test	For PVC outer sheath only	T, A	IS 10810 Pt 59 / IEC-754-1	indicated in Datasheet-A
IV.	Temperature Index Test	For PVC outer sheath only	T	IS 10810 Pt 64 / ASTMD 2863	
5.0	Flammability Tests			7.011115 2.000	
I.	Flammability test for bunched cables	For complete cable	Т	IS 10810 Pt 62/ IEC-60332 (Part-3-23-Cat-B	Test & Category
11.	Flammability test for single cable	For complete cable	T,A	IS: 10810 Pt 61 / IEC:60332 Part-1	applicable as indicated in
111.	Swedish chimney test	For complete cable	A	SEN SS 424 1475 (Class F3)	Datasheet-A
IV.	Flammability test	For complete cable	A	IEEE: 60383	
111					
6.0	Electrical Tests	- 11			
l.	High Voltage Test	For complete cable	T, A, R	IS 10810 Pt 45	
II.	Insulation Resistance Test (Volume resistivity method)	For complete cable	T, A	IS 10810 Pt 43	
7.0	Anti-rodent and Termite Repulsion test	For PVC outer sheath only	А	Refer Note	Test applicable if
8.0	Anti-Fungal Test	For PVC outer sheath only	A		indicated in Datasheet-A
9.0	Special Tests				
l.	Hydrolytic Stability Test	For complete cable	**	ASTM D 3137:81	Test applicable if
11.	Ultraviolet Radiation Test	For complete cable	**	BS EN ISO 4892- 2	indicated in Datasheet-A

\*\* These tests shall be conducted on one sample for the entire contract and duration of these tests shall be 14 days.

Note: A few chipping of the PVC compound is slowly ignited on a porcelain dish or cubicle in a muffle furnace at about 60-degree C. The resulting ignited ash is boiled with a little ammonium acetate solution (10%). Place a drop of aqueous sodium sulphide solution on a thick filter paper and allow soaking. Touch the spot with a drop of above extract. A black spot indicates

the presence of lead, the anti-termite and rodent compound.

BHEL					BIDDER/ SUPPLIER	FOR	FOR CUSTOMER REVIEW & APPROVAL			
E	NGINEERIN	NG .		QUALITY		Sign & Date	Doc No:			
	Sign & Date	Name		Sign & Date	Name	Seal		Sign & Date	Name	Seal
Prepared by:	Just 18.03.20	VIKAS KUMAR SINGH	Checked by:	/ 1 1	KUNAL GANDHI		Reviewe by:	d		
Reviewed by:	Manish	MANISH SHUKLA	Reviewed by:	Petri	RITESH KUMAR		Approve by:	d		





#### PRE-QUALIFICATION REQUIRMENTS OF LT XLPE POWER CABLE FOR 2X660MW KHURJA TG & ASSOCIATED PACKAGES

PE-PQ-475-507-E002

REVISION NO. 0 DATE 27/04/2022

SHEET NO. 1 OF 1

	E: Supply: YES; Erection & Commissioning: NO;
1.0	Vendor should be a manufacturer of LT power cables.
2.0	Availability of test reports of tests on LT XLPE FRLS power cables to establish in- house capability to carry out all routine, type & acceptance tests as per relevant IS/international standards (except UV radiation & hydrolytic stability test which can be conducted at Govt. lab/ Govt. approved independent lab).
3.0	Capacity of manufacturing 100 km of LT power cables per month.
4.0	Manufactured and supplied at least one (1) km of FRLS cables.
5.0	Manufactured and supplied LT Power cable sizes of minimum 240 sq. mm for 3/3.5 core and minimum 630 sq. mm for single core cable
6.0	Manufactured and supplied at least 300 km of LT Power cables in one or more orders and at least 60 km in one single order.
7.0	Minimum two (2) nos. purchase orders for LT XLPE power cable shall be submitted which should not be more than five (5) years old from the date of techno- commercial bid opening for establishing continuity in business.

#### NOTES:

- 1. Consideration of bidder's offer is subject to NTPC approval.
- 2.Bidder to submit all supporting documents in English. If documents submitted by bidder are in language other than English, a self-attested English translated document should also be submitted.
- 3. Notwithstanding anything stated above, BHEL reserves the light to assess the capabilities and capacity of the bidder/collaborators to perform the contract, should the circumstances warrant such assessment in the overall interest of BHEL.
- 4. After satisfactory fulfillment of all the above criteria requirement, offer shall be considered for further evaluation as per NIT and all the other terms of the tender.

PREPARED BY

NAME:MANU SINGH
DESIGNATION:
DY MANAGER

CHECKED BY

REVIEWED BY

NAME: DESIGNATION:
NAME: CHECKED BY

NAME: WAR NAME: DESIGNATION:
DESIGNATION: DESIGNATION: DGM

REVIEWED BY

NAME: DESIGNATION: DGM

DESIGNATION: DGM

APPROVED BY

DESIGNATION: DGM

DESIGNATION: DGM