

**( Cover page for Price Bid )**

**Issued to:** \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_



**BHARAT HEAVY ELECTRICALS LIMITED**  
**RAMACHANDRAPURAM :: HYDERABAD-32**  
**TOWNSHIP ADMINISTRATION**

**TENDER DOCUMENTS (PRICE BID)**

**Name of the work : Additions & alterations to electrical points in non-residential buildings in township.**

**Tender Notice : HY/TA/E/OT-01/2011-12, Dt. 10.05.2011; Item No. 02**

**INDEX**

**1. Schedule 'A' : Schedule of rates and approximate quantities**

**SIGN. OF TENDERER**

**ISSUING OFFICER**

**Address:**

**Phone No.** \_\_\_\_\_

**BHARAT HEAVY ELECTRICALS LIMITED**  
**RAMACHANDRAPURAM :: HYDERABAD - 32**  
**(TOWNSHIP ADMINISTRATION)**  
**ELECTRICAL DEPARTMENT**  
**SCHEDULE - 'A'**

**Tender No.: HY/TA/E/OT-01/2011-12**  
**Date : 10.05.2011**  
**Item No.: 02**

**Additions & Alterations to Electrical points to Non-Residential Buildings in Township.**

<b>Sl. No.</b>	<b>Nature of work</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
<b>(1)</b>	<b>(2)</b>	<b>(3)</b>	<b>(4)</b>	<b>(5)</b>	<b>(6)</b>
	<b>WIRING</b>				
1	Supply & Wiring with 2run 1.5sq.mm (22/.3mm) PVC insulated multistranded copper conductor cable L&T / Finolex make run together with single run 1 sq mm PVC insulated multistranded copper conductor for earth continuity in concealed / surface rigid with PVC conduit pipe of 25mm dia ;1.5 mm thick (Sudhakar make) through MS junction box. Wiring includes supply and fixing of 5A, 250V ceiling rose / PVC holder Anchor make on teak wood / PVC round block and 6A 250V piano type switch Anchor / Icon make on hylam sheet of thickness 3mm preferably white with suitable MS box for control of light, fan, bell and exhaust fan point; all complete as directed by engineer in charge.	Each	220	742.00	163,240.00
2	Supply & wiring with 1.5 sq.mm (22/.3mm) PVC insulated multi stranded copper conductor cable L & T / Finolex make together run with single run of 1 sq.mm PVC insulated multi stranded copper conductor for earth continuity run in concealed surface rigid PVC conduit pipe 25mm dia, 1.5mm thick (sudhakar make) through MS junction box. supply and fixing of 1 no. brass holder, 2 nos. 6A,250V two way piano type/flush type switches Anchor / Icon Make on Hylam sheet of thickness 3mm preferably white with suitable MS box for control from two sides for stair case light points; all complete as directed by engineer in charge	Each	20	1,213.00	24,260.00

<b>Sl. No.</b>	<b>Nature of work</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
<b>(1)</b>	<b>(2)</b>	<b>(3)</b>	<b>(4)</b>	<b>(5)</b>	<b>(6)</b>
3	Supply & wiring with 2 run 1.5 sq.mm (22/.3mm) PVC insulated multi stranded copper conductor cable L&T / Finolex make run together with 1 sq. mm PVC insulated multi stranded copper conductor for earth continuity run in concealed surface rigid PVC conduit pipe 25mm dia / 1.5 mm thick (sudhakar make) and supply & fixing of 2/3 pin flush mounted multipurpose 6A, 250 V piano type switch and socket Anchor / Icon make on Hylam sheet of thickness 3mm preferably white with suitable MS box for separate socket; all complete as directed by engineer in charge.	Each	55	541.00	29,755.00
4	Supply & fixing and connecting of, 2/3 pin flush mounted multipurpose 6A, 250 V piano type switch and socket Anchor / Icon make with internal connection 1.5sq.mm wire for control to be fixed on common switch board; all complete as directed by engineer in charge.	Each	72	66.00	4,752.00
5	Supply of 25mm dia 1.5mm thick PVC pipe of sudhakar make (ISI mark) and fixing as concealed / surfaced to wall / ceiling with all required accessories including massonary work and labour charges etc.; all complete as directed by engineer in charge	Mtr.	20	49.00	980.00
<b>RUN OF MAINS</b>					-
6	Supply & run of with 2.5 Sqmm PVC insulated Multistranded copper conductor cable of L&T /Finolex make run together with single run of 1.0 sq.mm PVC insulated multistranded copper conductor for earth continuity, run in concealed / surfaced rigid PVC conduit pipe 25 mm dia, 1.5 mm thick (sudhakar make) with all required accessories for single phase two wires run of mains; all complete as directed by Engineer-in-charge.	Rmt	360	124.00	44,640.00
7	Supply & run of with 4.0 Sqmm PVC insulated Multistranded copper conductor cable of L&T /Finolex make run together with single run of 1.5 sq.mm PVC insulated multistranded copper conductor for earth continuity, run in concealed / surfaced rigid PVC conduit pipe 25 mm dia, 1.5 mm thick (sudhakar make) with all required accessories for single phase two wires run of mains; all complete as directed by Engineer-in-charge.	Rmt	180	153.00	27,540.00

Sl. No.	Nature of work	Unit	Qty	Rate	Amount
(1)	(2)	(3)	(4)	(5)	(6)
8	Supply & run of with 4.0 Sqmm PVC insulated Multistranded copper conductor cable of L&T /Finolex make run together with single run of 1.5 sq.mm PVC insulated multistranded copper conductor for earth continuity, run in concealed / surfaced rigid PVC conduit pipe 25 mm dia, 1.5 mm thick (sudhakar make) with all required accessories for three phase four wires run of mains; all complete as directed by Engineer-in-charge.	Rmt	120	231.00	27,720.00
9	Supply & run of with 6.0 Sqmm PVC insulated Multistranded copper conductor cable of L&T /Finolex make run together with single run of 1.5 sq.mm PVC insulated multistranded copper conductor for earth continuity, run in concealed / surfaced rigid PVC conduit pipe 25 mm dia, 1.5 mm thick (sudhakar make) with all required accessories for single phase two wires run of mains; all complete as directed by Engineer-in-charge.	Rmt	100	206.00	20,600.00
10	Supply & run of with 6.0 Sqmm PVC insulated Multistranded copper conductor cable of L&T /Finolex make run together with single run of 1.5 sq.mm PVC insulated multistranded copper conductor for earth continuity, run in concealed / surfaced rigid PVC conduit pipe 25 mm dia, 1.5 mm thick (sudhakar make) with all required accessories for three phase four wires run of mains; all complete as directed by Engineer-in-charge.	Rmt	50	335.00	16,750.00
	<b>ACESSORIES</b>				-
11	Supply and fixing of 250V, 6A ceiling rose of Anchor / Icon make; as directed by Engineer-in-charge.	Each	30	39.00	1,170.00
12	Supply and fixing of PVC slant / batten/ pendant holder Roma make. ( Catalog no. 30125, 30114, 30103 )	Each	50	57.00	2,850.00
13	Supply and fixing of Ding dong bell of Anchor / Icon make; as directed by Engineer-in-charge.	Each	10	118.00	1,180.00
14	Supply and fixing of Musical bell of Anchor / Icon make; as directed by Engineer-in-charge.	Each	4	263.00	1,052.00
15	Supply and fixing of 250V, 6A piano type switch of Anchor / Icon make; as directed by Engineer-in-charge.	Each	10	32.00	320.00

<b>Sl. No.</b>	<b>Nature of work</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
<b>(1)</b>	<b>(2)</b>	<b>(3)</b>	<b>(4)</b>	<b>(5)</b>	<b>(6)</b>
16	Supply of 250V, 6A flush type socket of Anchor / Icon make; as directed by Engineer-in-charge.	Each	10	26.00	260.00
17	Supply and fixing of 250V, 16A switch or socket of Anchor / Icon make; as directed by Engineer-in-charge.	Each	20	77.00	1,540.00
18	Supply and fixing of 7" x 4" M.S Box with Hylam sheet of thickness 3mm preferably white with 16A Switch and 16A socket (or switch cum socket) of Anchor / Icon make; complete as directed by Engineer-in-charge.	Each	40	190.00	7,600.00
19	Supply and fixing of 250V, 6A, 3-pin plug tops of Anchor / Icon make; as directed by Engineer-in-charge.	Each	20	43.00	860.00
20	Supply and fixing of 250V, 16A, 3-pin plug tops of Anchor / Icon make; as directed by Engineer-in-charge.	Each	10	60.00	600.00
	<b>HYLAM SHEET &amp; M.S. BOXES</b>				-
21	Supply, cutting and fixing of hylam sheet with thicknes 3mm preferably white on MS boxes.	S.ft.	20	103.00	2,060.00
22	Supply and fixing of 8" x 10" MS Boxes	Each	10	104.00	1,040.00
23	supply and fixing of 10" x 12" MS Boxes	Each	5	125.00	625.00
	<b>DECOLAM BOARD</b>				-
24	supply and fixing of 7" x 4" decolam board	Each	20	40.00	800.00
25	supply and fixing of 8" x 10" decolam board	Each	15	53.00	795.00
26	supply and fixing of 10" x 12" decolam board	Each	10	69.00	690.00
	<b>TEAK WOOD BOARDS</b>				-
27	Supply and fixing of teak wood round block	Each	50	15.00	750.00
28	Supply and fixing of 10" x 12" teak wood board	Each	10	47.00	470.00
29	Supply and fixing of 12" x 15" teak wood board	Each	5	72.00	360.00
	<b>MAINSWITCHES, FUSES &amp; FUSE D.B.</b>				-
30	Supply and fixing of 32A, 250V Porcelain rewirable fuse unit reputable make	Each	10	121.00	1,210.00
31	Supply and fixing of 32A, 415V Porcelain rewirable fuse unit reputable make	Each	10	141.00	1,410.00
32	Supply and fixing of 63A, 415V Porcelain rewirable fuse unit reputable make	Each	20	220.00	4,400.00
33	Supply, fixing and connecting of 250V, 32A Double Pole Iron Clad Main Switch with porcelain rewirable fuse units; complete as directed by Engineer-in-charge.	Each	2	898.00	1,796.00

<b>Sl. No.</b>	<b>Nature of work</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
<b>(1)</b>	<b>(2)</b>	<b>(3)</b>	<b>(4)</b>	<b>(5)</b>	<b>(6)</b>
34	Supply, fixing and connecting of 415V, 32A Triple Pole Iron Clad Main Switch; complete as directed by Engineer-in-charge.	Each	2	937.00	1,874.00
35	Supply, fixing and connecting of 415V, 63A Triple Pole Iron Clad Main Switch; complete as directed by Engineer-in-charge.	Each	2	2,044.00	4,088.00
36	Supply, fixing and connecting of 250V, 16A, 1-phase 8-way porcelain fuses distribution board having metallic sheet steel enclosure; complete as directed by Engineer-in-charge.	Each	5	588.00	2,940.00
	<b>ISOLATORS, MCBs &amp; MCB D.B.</b>				-
37	Supply of 6A-32A MCB's of MDS make.	Each	36	210.00	7,560.00
38	Supply of 250V, 40/63A, 2-pole isolators (MCB) of MDS make.	Each	3	959.00	2,877.00
39	Supply of 415V, 63A, 4-pole isolators (MCB) of MDS make.	Each	5	1,852.00	9,260.00
40	Supply of 415V, 80/100A, 4-pole isolators (MCB) of MDS make.	Each	3	2,072.00	6,216.00
41	Supply, fixing and connecting of 1-phase 6-way single door MCB Distribution Box with 6A-32A MCB's and 40/63A isolator of MDS make; complete as directed by Engineer-in-charge.	Each	3	2,646.00	7,938.00
42	Supply, fixing and connecting of 1-phase 8-way double door MCB Distribution Box with 6A-32A MCB's and 40/63A isolator of MDS make; complete as directed by Engineer-in-charge.	Each	3	3,866.00	11,598.00
43	Supply, fixing and connecting of 3-phase 4-way double door MCB Distribution Box with 6A-32A MCB's and 40/63A isolator of MDS make; complete as directed by Engineer-in-charge.	Each	1	6,072.00	6,072.00
44	Supply, fixing and connecting of 3-phase 6-way double door MCB Distribution Box with 6A-32A MCB's and 40/63A isolator of MDS make; complete as directed by Engineer-in-charge.	Each	1	7,850.00	7,850.00
45	Supply, fixing and connecting of 3-phase 8-way single door MCB Distribution Box with 6A-32A MCB's and 80/100 A isolator of MDS make; complete as directed by Engineer-in-charge.	Each	3	7,707.00	23,121.00

<b>Sl. No.</b>	<b>Nature of work</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
<b>(1)</b>	<b>(2)</b>	<b>(3)</b>	<b>(4)</b>	<b>(5)</b>	<b>(6)</b>
46	Providing of earthing arrangement comprising of 100 mm inner dia, 3 mm thick GI pipe buried upto a minimum depth of 3.0 mtrs including filling the earth pit with homogenous layers of coke/charcoal, salt & sand etc. as required conforming to IS:3043. Suitable length of 8 SWG bare copper conductor to be bolted at bottom of the pipe and run around the pipe upto the surface connection point ( Copper conductor included as separate item ). The earth pit to be provided with brick masonry chamber with hinged cover and watering arrangement; complete in all respects, as directed by Engineer-in-charge.	Set	3	3,111.00	9,333.00
47	Supply and fixing of Copper flat / bare conductor.	Kg.	6	559.00	3,354.00
48	Supply and installation of 20A single phase MCB box with 20A metal clad plug-socket of Legrand / MDS make for termination of cable for AC point.	Each	12	1,077.00	12,924.00
	<b>M.S. ITEMS</b>				-
49	Supply & fixing of angular iron frame in wall with 1/1.6 mm MS sheet on top with hinges & all four sides with screws. Necessary red-oxide / grey painting as directed by engineer in charge.	Kg.	12	112.00	1,344.00
50	Supply, fabrication & fixing of MS sheet cupboards made of sheet 1.6mm thick with single/double shutter and mechanical locking arrangements. The cupboards shall be given 2 coats of red-oxide paint and finished with necessary general purpose quick drying oil paint of suitable shade, etc. complete as directed by engineer in charge.	Kg.	24	184.00	4,416.00
	<b>SERVICE CONNECTIONS &amp; MAINS</b>				-
51	Supply & fixing of one run of 2x6 Sq.mm (twin core WPTC) PVC insulated sheathed weather proof AL. Conductor cable payal / gold model make 1100V grade together run with 7/18 SWG GI bearer wire outside building and concealed / surface in rigid PVC conduit inside the building including necessary clips insulation tape etc., for single phase service tapping as directed by engineer incharge	Mtr.	145	45.00	6,525.00
52	Supply & fixing of one run of 2x10 Sq.mm (twin core WPTC) PVC insulated (WPTC) sheathed weather proof AL. Conductor cable payal/gold model make 1100V grade together run with 7/18 SWG GI bearer wire outside building and concealed /surface in rigid PVC conduit inside the building including necessary clips insulation tape etc., for single phase service tapping as directed by engineer in charge.	Mtr.	145	54.00	7,830.00

Sl. No.	Nature of work	Unit	Qty	Rate	Amount
(1)	(2)	(3)	(4)	(5)	(6)
53	Supply & fixing two run (4 wires) of 2x10 Sq.mm (twin core WPTC) PVC insulated sheathed weather proof AL. Conductor cable Payal/gold model make 1100V grade together run with 7/18 SWG GI bearer wire outside building and concealed/surface in rigid PVC conduit 32mm dia 2mm thickness inside the building including necessary clips insulation tape etc., for single phase service tapping as directed by engineer incharge.	Mtr.	50	92.00	4,600.00
	<b>SERVICE OF MAINS SUPPORTING MATERIALS</b>				-
54	Supply & fixing of guy insulator of 80x50mm. One guy insulators to be fixed at either ends of the GI wire supporting the service connection cable.	No.	20	44.00	880.00
55	Supply & grouting in wall 32mm dia GI pipe (class B) at the building end for entry of service tapping to building. One end of the pipe should have threaded for fixing bends.	Mtr.	10	226.00	2,260.00
56	Supply & fixing of GI bends 32mm dia for fixing of 25mm/32mm dia GI pipe for arresting entry of rain water into the pipe . Also suitable size of PVC/Rubber bushes should be provided at the entry of the point of pipe/bend.	Each	6	82.00	492.00
57	supply & fixing of rigid conduit PVC pipe 35mm dia and 1.5 thick (sudhakar make) on surface/concealed including bends.	Rmt.	12	68.00	816.00
58	Supply & fixing of Steel support wire 7/20 SWG with tape and new link clips to the existing weather proof wire only in case of breaking of GI wire.	Mtr.	20	11.00	220.00
59	Supply & fixing of bus bar insulators with necessary screw etc..	Each	20	22.00	440.00
60	Supply & fixing of 3 x25mm copper flat for bus bar with necessary screw etc..	Kg.	6	527.00	3,162.00
	<b>METERS</b>				-
61	Supply, fixing and connecting of 3 phase 5Amp/100Amp – 415V C.T meter	Each	1	2,990.00	2,990.00
62	Supply, fixing and connecting of 3 phase 5Amp/100Amp-415V C.T.coil	Each	6	143.00	858.00
63	Supply of energy meter lead seals	Kg.	4	506.00	2,024.00
64	supply of enery meter lead wire	Kg.	2	143.00	286.00
	<b>B.C / S.C / Halogen bulbs</b>				-
65	Supply of B.C. bulbs 200watts	Each	5	24.00	120.00
66	Supply of bulk head fitting with cast aluminium enamel painted body with water light clear glass  with wire guard hinged with lock & key arrangement etc complete of best Indian make.	Each	5	416.00	2,080.00

Sl. No.	Nature of work	Unit	Qty	Rate	Amount
(1)	(2)	(3)	(4)	(5)	(6)
67	Supply and fixing and connection of porcelain holder 2/3 pin holder 5A-250V reputable make	Each	5	43.00	215.00
68	Supply of Hylogen bulbs 500watt	Each	10	109.00	1,090.00
69	Supply of Hylogen bulbs 1000watt	Each	10	132.00	1,320.00
70	Supply of spot light 500W	Each	4	385.00	1,540.00
71	Supply of spot light 1000W	Each	6	517.00	3,102.00
	<b>TUBE LIGHT</b>				-
72	Supply of Tube light starters / starter base / side holder / side holder base / Rotary type holder reputed make.	Each	100	17.00	1,700.00
73	Supply of Tube light 20 watt bulb	Each	6	47.00	282.00
74	Supply of Tube light 40 watt / 36watts bulb	Each	30	51.00	1,530.00
75	Supply of Tube light 80 watt / 65watts bulb	Each	5	132.00	660.00
76	supply of 20W/40W copper choke phillips make	Each	20	143.00	2,860.00
77	supply of 80w /65w copper chock reputable make	Each	5	374.00	1,870.00
	<b>C.F.L LIGHTING</b>				-
78	Supply of CFL (bulb) 9W/11 watts Bajaj / Philips as directed by engineer in charge	Each	10	88.00	880.00
79	Supply of CFL (bulb)14W/18 watts Bajaj / Philips as directed by engineer in charge	Each	10	182.00	1,820.00
80	Supply of tube light choke 9 watts/11 watts phillips /B=55make as directed by engineer incharge	Each	2	175.00	350.00
81	Supply of tube light choke 14 watts/18watts phillips /B=55make as directed by engineer incharge	Each	2	220.00	440.00
82	Supply and fixing of FMS 200/111 , 1xPL s 11 watts (mirror light), switch, starters complete with all accessories inclusive of PF correction capacitor, together with tube light for engg. Hostel philphs make	Each	2	624.00	1,248.00
83	supply and fixing recess mounted luminaire of model no. FBS 450/236 D6 AG HF Philphs make	Each	2	5,012.00	10,024.00
84	Supply fixing of CFL lamp PL-L 36W only bulbs Philps make	Each	10	189.00	1,890.00
85	Supply and fixing of decoratvie CFL luminaire for wall mounting FL 800/320 with 20 W bulb philphs make.	Each	3	669.00	2,007.00
	<b>SPECIAL ITEMS FOR NON RESDENTIAL BUILDINGS</b>				-

Sl. No.	Nature of work	Unit	Qty	Rate	Amount
(1)	(2)	(3)	(4)	(5)	(6)
86	Cleaning of switch boards/ switches/ shades/ fittings with detergent powder, wherever it is necessary.	Each	120	26.00	3,120.00
87	supply & fixing of tubular type heating element suitable for 50 Ltrs / 90 Ltrs water heaters 3 hole /triangular disc type / non-threaded type as per samples given as directed by engineer in charge .	Each	12	440.00	5,280.00
88	Supply & fixing of thermostat 30 °C to 90 °C adjustable and suitable for 25Lts to 90Lts.	Each	8	230.00	1,840.00
89	Servicing of storage type water heaters(geyser). Work involves cleaning, replacement, dismantling & refixing.	Each	6	193.00	1,158.00
90	Removal of MS rod from ceiling and fixing of 4'/5' tube light fitting to down rods with suitable MS clamps to provide ceiling rose on Teakwood round block ( The work includes dismantling of fittings removal of existing gutties, clamps, bolts & nuts.) as directed by engineer in charge	Each	25	182.00	4,550.00
91	Supply of emergency lamp dry cell 6 Volts 10 AH rechargable maintenance free battery as directed by engineer in charge.	Each	12	510.00	6,120.00
92	Supply of 12way - 30Amps., 600 V Bakelite with brass terminal connectors as directed by engineer incharge	Each	6	154.00	924.00
93	Supply of micro phone cable 3 core reputable make	Mtr.	60	30.00	1,800.00
94	Providing of series lights for buildings on special occasions like indenpence day , Republic Day at buildings like Main Check post, ED's Bunglow and other palces whererver required etc. (10000 bulbs of series lights is considered-1 unit)	Each	60	330.00	19,800.00
	<b>EXCAVATION OF CABLE TRENCHES</b>				-
95	Earth work excavation for cable trenches of size 0.6m width & 0.9m deep in all soils except rocky, cutting of floor & roads & refill. (2.10.1.1)	Rmt.	300	71.00	21,300.00
96	Supply & spreading of sand cushion 5cm thick alround the cable & laying rough shahabad stone	Rmt.	300	89.00	26,700.00
97	Providing and fixing GI pipes complete with GI fittings and clamps including cutting and making good the walls etc. (internal work)				-
a	50mm dia. GI pipe (medium) (CPWD p-210 20.2.1.6)	Rmt.	20	343.00	6,860.00
b	100mm dia GI pipe (medium) (dept. supply) (BHEL misc. external water supply work)	Rmt.	20	32.00	640.00

Sl. No.	Nature of work	Unit	Qty	Rate	Amount
(1)	(2)	(3)	(4)	(5)	(6)
98	Providing and laying in position cement concrete of specified grade excluding the cost of carrying and shuttering etc1:5:10	Cu.M	3	2,080.00	6,240.00
99	Laying of PVC insulated PVC sheathed steel armoured Al conductor cable & connecting to switch and pole ( both sides ) ( cable supplied dept.)				-
a	1.5sq.mm/2.5sq.mm to 16 sq.mm	Rmt.	25	13.00	325.00
b	25 sq.mm to 70 sq.mm cable	Rmt.	300	19.00	5,700.00
100	Laying of AL conductor PVC insulated PVC sheathed, steel armoured cables following sizes				-
a	3 / 3 <sup>1</sup> / <sub>2</sub> core 120 to 225 sq.mm HT/LT cables	Rmt.	60	26.00	1,560.00
b	3 <sup>1</sup> / <sub>2</sub> core 50 to 95 sq.mm	Rmt.	50	19.00	950.00
c	3 <sup>1</sup> / <sub>2</sub> core 25 to 35 sq.mm	Rmt.	50	15.00	750.00
d	2 / 3 / 4 core 2.5 to 16 sq.mm	Rmt.	85	13.00	1,105.00
101	Supply& crimping of copper lugs of following sizes				-
a	16 sq.mm	Each	12	14.00	168.00
b	25 sq.mm	Each	25	17.00	425.00
c	35 sq.mm	Each	20	30.00	600.00
d	50 sq.mm	Each	20	39.00	780.00
e	70 sq.mm	Each	20	47.00	940.00
f	95 sq.mm	Each	20	55.00	1,100.00
g	120 sq.mm	Each	20	85.00	1,700.00
			<b>TOTAL ... ..</b>		<b>709,686.00</b>

**Note:- The tenderers are required to quote their tender value on %age basis at excess or less or on par with estimated value.**

Tender %	Figures	words
Excess		
Less		
Estimate rate only		

Sl. No.	Nature of work	Unit	Qty	Rate	Amount
(1)	(2)	(3)	(4)	(5)	(6)

**Conditions :**

1	A <b>penalty of 0.5%</b> of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.
2	The rates quoted for the items of work shall be inclusive of taxes ( excluding sales tax & service tax ) and duties levied by Central / State Govt. Organisations as well as local authorities.
3	<b>Sales tax &amp; Service tax will be extra if applicable for this contract.</b> Taxes if paid by the contractor with respect to this work will be reimbursed by BHEL on production of documentary evidence for having paid the taxes by the contractor.
4	If the contractor has not quoted the <b>%age clearly</b> , it is considered as incomplete tender and tender cannot be accepted.
5	All BHEL general conditions of contract and special conditions enclosed to this document are applicable to this work.
6	In case there is any difference in the quoted % age between figures and words, the resultant higher tender value will be taken for evaluation of tender priority and while awarding, lower tender value will be taken and this should be binding on the contractor.
7	The department reserves the right to cancel the work without assinging any reasons therefor.
8	The billing is done as per the units specified and completion to the satisfaction of Engineer-in-charge.
9	The quantities shown above are approximate and liable for variation.
10	Conditional offers are not acceptable.
11	All the bills of the contractors will be cleared subject to the production of clearance certificate by the contractors in respect of compliance of all statutory requirement, issued by IR section of BHEL-HR department.