

EXTENSION NOTICE AND QUERIES/CLARIFICATION TO THE FOLLOWING NIT

REFURBISHMENT OF OIL RIG(F6100) AT ONGC-SIBSAGAR9ASSAM) (TENDER NO: PSER : PUR :ONG-S921 :08 DATED: 29/04/2008)

QUERIES RAISED BY INTENDED BIDDER AND CORRESPONDING REPLY ARE ATTACHED HEREWITH. ALSO PLEASE BE INFORMED THAT DUE DATE OF TENDER SUBMISSION IS EXTENDED UPTO 15=00 HRS ON 22-05-08

-
-

QURIES RAISED BY INTENDED BIDDER

NIT NO: PSER:PUR:ONG-S921:08 DT:29-04-08

In Scope of work, Annexure-I at page no.1 you have mentioned that the drill site being the remote areas around Sibsagar, accommodation, provision & transportation for workmen deployed has to be arranged within the scope of work of successful Bidder. Successful Bidder has to complete all the jobs at drill site including supply of any fabricated materials etc. as detailed free of cost at drill site.

- Agree to provide the above facility to our crews. But for your people, whether the above facilities are required? – Please clarify.

Detail Scope:

Rig Mechanical Sl.No. AA at point no.1:

- That supply of items as per BHEL drawings duly fabricated, cleaned, painted by application of one coat primer with two coats of **Hi build EPOXY paint**. These shall be supplied free at drill site where the rig will be commissioned.
- But you mentioned under scope of work – Rig Mechanical at page no.3 that painting of Mast and substructure items which are blast cleaned and repaired by one coat primer and two coats of **EPOXY paint** as per BHEL specification. The paint material/consumables including power/T&P & accessories are within the scope of bidder.

Contd-2-

From the above, it is seen that in first paragraph, you are asking **Hi-build EPOXY** & 2nd paragraph you are asking **only EPOXY paint**. It is confusing us to quote the rate – Please specify clearly.

- **Rig Mechanical Sl.No. CC:**

Installation of equipments: Following equipments are to be installed under guidance of BHEL, Hyderabad expert (Installation means placement of equipments on the skid/ supports etc, do necessary modification or fabrication and fitting with the end equipments. All T&Ps like diesel, welding generator with operator and consumables, accessories, workmen etc. as required, is to provide within the scope of successful bidder. Epoxy painting material with primer & consumables for painting of skids and pipelines fabricated shall be within the scope of successful bidder. However all other material e.g. pipe lines / fittings/angel / channels etc. including electrodes which will go permanently into the equipments except those are specifically mentioned will be provided by BHEL/ ONGC free of cost).

Kindly specify clearly the approximate quantity of materials that will be supplied by BHEL and supplied by the bidder so that we can access and quote the rates accordingly.

- **Under page no. 3 of point no.6:** Installation of BHEL supplied items at site while rig is erected at site. Modification if necessary is to be carried out within the scope to install the fabricated/repaired items. Any minor jobs carried out at drill site are within the scope.

Kindly tell us the name of the items supplied by BHEL at site while rig is erected. Specify the actual nature and extent of minor modification job to be carried out. Unless you not clearly defined us the minor modification jobs both qualitatively and quantitatively, it becomes difficult to calculate the probable cost involved for the job.

- **At Annexure-II, Page no.14 – Tentative List of T&Ps:**

- i) Sl. No. 36: Wooden planks.
- ii) Sl. No.37: Wooden Racks for stores.
- iii) Sl. No.40: Rubber Mats for electrical welding.

Kindly clarify the approximate quantity of the above materials so that we can access and quote the rate.

- **At Annexure-III, Page no.15 – Tentative List of Consumables:**

- i) Sl. No. 5 : Welding Electrode
- ii) Sl. No. 6 : Gas cutting consumables (Oxygen/DA) as required.
- iii) Sl. No. 7 : Tarpaulins
- iv) Sl. No. 9 : Cleaning consumable e.g. petrol, diesel, CCL4, acetone etc.

We request you kindly to specify the approximate quantity of your requirement of the above consumables so that we can access & loaded in our quoted rate.

- **At page No.11: Note:** The arrangement of required workmen with provisions, commutation of workmen to & from repair yard & drill site, arranging power, portable water required for workmen or, during execution, compliance to statutory requirements and obtaining such clearance or permissions from any authorities so required, transportation for supply, arranging, providing during execution any raw material, finished goods, equipment, consumables, accessories etc. as required is within the scope of successful bidder.
 - a) **Arranging power:** Please tell us clearly specify what type of Power is required at sites so that we can ascertain the cost and loaded in our quoted rate.
 - b) **Potable water:** Please specify the approximate quantity of potable water required to be supplied from the beginning to the end of the contract.
 - c) **Transportation for items:** please clarify whether the transportation facility is required on daily basis or occasionally. Please also specify the approximate quantity or weight of the raw materials/ finished goods required to be transported during execution.

POINTWISE REPLY TO THE QUERIES RAISED
NIT NO: PSER: PUR: ONG-S921:08 DT:29-04-08

Pg 1/2

- Annexure-I Pg 1 of Tender enquiry :- For BHEL personnel no such facility is required to be provided.
- Under Detail scope against painting:- Painting is EPOXY as per BHEL Standard HY0674162 Rev-01
- Rig Mechanical SL.NO. CC :of Annexure-I of NIT :- Modifications may be necessary in the form of cutting , removal of any local obstructions on the skid while placing the equipments , changing of route of air/water lines which if obstruct placement of equipments etc. BHEL will supply materials including welding electrodes which will go permanently into the equipments / system. The successful bidder has to provide within scope necessary workmen , T&Ps , paint material etc. to carry out these jobs as described in the NIT
- Page No.- 3 ,Point no 6 :- Same as above
- Annexure-II Page no 14:- Tentative list of T&Ps
Wooden planks & racks: - Wooden planks are required for support of various equipments under refurbishment and racks for storing various materials at site during execution. These are to be provided within scope on returnable basis. Bidders to assess the requirement.

Bidders to assess the requirement of Rubber mats for safety during various welding jobs .

- Annexure-III Page no 15:- Tentative list of consumables

Welding electrode:- BHEL will provide except where successful bidder has to provide within scope as specifically mentioned in NIT (e.g.- for supply items in Table in Annexure-I etc.)

Gas cutting consumables:- Requirement maximum is Oxygen 450 Cylinders and DA 150 Cylinders.

Tarpaulins :- Required to provide on returnable basis for covering various equipments under refurbishment at site during rain

Cleaning consumables :- Cleaning consumables e.g.- petrol/diesel/acetone etc.. These are required for cleaning of various components during fitting , during NDT of weld joints and cleaning of various electrical fittings during assembly is to be provided within the scope.

- Page -11 Note:- Arranging power:- Site Illumination power will be made available to the successful bidder by ONGC .For rig equipments operation, commissioning, trial run, mast hoisting , well spudding and drilling , power will be provided by ONGC . However, power for any motor driven T&Ps if mobilised by successful bidder for execution of job is to be arranged by the successful bidder within scope.
- Potable water :- Potable water (in sealed bottle) is to be provided to BHEL personnel within scope at drill site 5 Litres per day per head for maximum five person for 105 days only during site execution .
- Transportation :- Transportation of rig equipments and ONGC materials , BHEL personnel are not included within scope. However, successful bidder has to include within scope the transportation his own equipments , T&Ps, Consumables , supply items including workmen to be mobilised to rig refurbishment yard and drill site for execution of job.