

Section VI: Part B I – Mechanical

NTPC Limited

(A Government of India Enterprise)



LOT 1A PROJECTS

PART – B (DETAILED TECHNICAL SPECIFICATION)

SUB-SECTION-I-M (MECHANICAL SYSTEM)

SECTION – VI

TECHNICAL SPECIFICATION FOR

FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE



BIDDING DOCUMENT NO. : CS-0011-109(1A)-2



PART - B (DETAILED TECHNICAL SPECIFICATION)
SUB-SECTION-I-M (MECHANICAL SYSTEM)



LOT-IA PROJECTS
FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE

TECHNICAL SPECIFICATION
SECTION-VI
BID DOCUMENT NO.: CS-0011-109(1A)-2



SUB-SECTION-I-M1

FLUE GAS DESULPHURISATION SYSTEM



LOT-IA PROJECTS
FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE

TECHNICAL SPECIFICATION
SECTION-VI
BID DOCUMENT NO.: CS-0011-109(1A)-2

CLAUSE NO.	TECHNICAL REQUIREMENTS												
	 FLUE GAS DESULPHURIZATION (FGD) SYSTEM 1.00.00 GENERAL The design/specifications/sizing of various plants/systems/equipment offered for Flue Gas Desulphurisation (FGD) System shall comply with the requirements detailed hereinafter: 1.01.00 System Description The Flue Gas Desulphurisation (FGD) System shall be based on Wet Limestone Forced Oxidation process. The FGD system shall be installed downstream of the Induced Draft (ID) fans (Employer's scope). The flue gas shall be drawn from air preheater outlets of the balanced draft, pulverised coal fired Steam Generator and guided through adequately sized duct work into the specified number of independent gas streams of each Electrostatic Precipitators. The flue gas after the Electrostatic Precipitators shall be led to the suction of the ID fans. The flue gas temperature may approach the economiser outlet temperature of about 300°C in case the regenerative airpreheaters fails to operate. The Contractor shall take this aspect into account while designing the Flue Gas Desulphurisation (FGD) System. 1.02.00 Service Conditions The Steam Generators, being provided by Employer, are designed to burn pulverised coal having properties as indicated in Sub-section-II-A (Project Information), Part-A, Section-VI. Also HFO/HPS/LSHS and LDO shall be used during startup and at low loads for warm up and flame stabilization as specified in respective Project Information Chapter. The design of Steam Generator shall not call for any oil support for flame stabilization beyond 40 % BMCR load when firing any coal. Further, the frequency and duration for startup and low loads operation may be quite long during the first year of unit commissioning and operation. The Steam Generator has been designed for cyclic/two shift operation. Expected numbers of Steam Generator start-ups during 25 years of design life are as follows: <table border="1"> <thead> <tr> <th></th><th>Type of Starts</th><th>Number of Starts</th></tr> </thead> <tbody> <tr> <td>a.</td><td>Hot start (after 8 hours of unit shut down)</td><td>4000</td></tr> <tr> <td>b.</td><td>Warm start (after 36 hours of unit shut down)</td><td>1000</td></tr> <tr> <td>c.</td><td>Cold start (after 72 hours of unit shut down)</td><td>150</td></tr> </tbody> </table> The Contractor, shall take into account the entire characteristics of expected combination of fuels to be fired and the expected numbers of Steam Generator start-		Type of Starts	Number of Starts	a.	Hot start (after 8 hours of unit shut down)	4000	b.	Warm start (after 36 hours of unit shut down)	1000	c.	Cold start (after 72 hours of unit shut down)	150
	Type of Starts	Number of Starts											
a.	Hot start (after 8 hours of unit shut down)	4000											
b.	Warm start (after 36 hours of unit shut down)	1000											
c.	Cold start (after 72 hours of unit shut down)	150											
	<table border="1"> <tr> <td>LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE</td><td>TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2</td><td>PART-B SUB-SECTION-I-M1 (FGD)</td><td>PAGE 1 OF 51</td></tr> </table>	LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 1 OF 51								
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 1 OF 51										

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC	
1.03.00	Design Criteria	 	
1.03.01	The Flue Gas Desulphurisation (FGD) System shall be designed to meet all the conditions specified above. Representative coal and ash analysis for the expected coal and oil are given in Sub-section-II-A (Project Information), Part-A, Section-VI for each project. The FGD system and all the associated auxiliaries shall be designed to comply with the requirements stipulated under 'Guarantee Point' and 'Design Point' conditions indicated in Sub-Section-V, Part-A, Section-VI of the Technical Specification for the respective projects. The values indicated for FGD sizing shall be considered as minimum design criteria. These shall be modified to more conservative values if Contractor experience warrants the same. However, no credit shall be given to the Contractor for this during evaluation of the bids. Utilization of these values in no way relieves the Contractor of his responsibility to meet all the guarantee requirements. The Contractor shall also furnish along with his offer the detailed calculations and data along with his Bid to establish as to how the Bidder will meet the efficiency requirements both at design and guarantee point as specified in FGD sizing criteria.		
1.03.02	The FGD system shall be installed downstream of the ID fans and shall be based on wet Limestone Forced Oxidation Process. The FGD system shall be designed to achieve the required SO₂ capture without the use of oxalic acid or any other additives. The FGD System shall be designed so as to be in operation whenever the Steam Generator is in operation. However, provision shall be made by the Contractor for facilitating operation of unit with emergency FGD bypass. This shall also facilitate the online maintenance of absorber system and associated equipment's. The arrangement of the flue gas system shall allow complete isolation of the absorber from the gas side, with the unit in operation. For this purpose. Motorized Guillotine type gates has be provided at (i) hot gas inlet to Booster Fans, (ii) Outlet of Booster Fans and (iii) in the bypass duct (common Flue Gas Duct going towards the existing Chimney). Further, Quick opening Bi-plane motorized/pneumatic damper along with 2x100% seal air fans shall be provided in the by-pass duct by the Contractor. The same shall also be taken into account while designing the control & logics for the FGD System.		
1.03.03	The wet absorber system shall be designed to maintain the required SO ₂ removal.		
1.03.04	In order to be compatible to all possible modes of operation, the design of the FGD plant shall enable short start-up times, compatible with load changes in the Steam Generator and shall ensure reliable mode of continuous operation.		
1.03.05	The flue gas desulphurization plant (FGD) shall be designed to be operated with limestone as specified in Sub-Section-V, Section-VI of the Technical Specification.		
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
1.03.06	The FGD and the ancillary facilities shall be suitable for unlimited operation with all transients and at any load point between the minimum and maximum load point of the Steam Generator. Further, the FGD plant shall be suitable for an unlimited operation at any pollutant concentrations between minimum and maximum without exceeding the emission values of SO ₂ emission of less than 100 mg/Nm ₃ (6% O ₂ dry).			
1.03.07	In case of failure of the SG and ancillary equipment, the FGD plant shall be brought automatically to the off-load operation without restriction by the current load case by suitable measures.			
1.03.08	In case of a power failure all items of equipment (e.g. minimum one agitator in absorber and limestone slurry tank, flue gas damper upstream & downstream of FGD, Process water pump & lube oil system of Booster Fan & Ball Mill) which may cause irreversible damage to the FGD System shall be connected to the emergency power supply system to be provided by the Contractor. Bidder shall furnish a list of all such Auxiliaries in their bid proposal.			
1.03.09	In case of shutdown and outage periods, draining and flushing of limestone slurry and gypsum slurry pipe work, tanks and all other items being in contact with limestone slurry or gypsum slurry shall be possible without restriction and without necessity of extensive or unusual preparation and activity. Draining and flushing which are required even during short time outages or an emergency shutdown shall be started automatically and by remote control from the Control Room.			
1.03.10	All items or equipment which are subject to wear, abrasion or failure (e.g. nozzles, pumps, pipe work, etc.) shall be designed and installed for easy replacement, repair and maintenance.			
1.03.11	The design and the construction shall be performed so as to avoid stress corrosion cracking, galvanic or other types of corrosion. Especially when using two different alloys, appropriate measures shall be taken to avoid corrosion. This is subject to approval by the Employer.			
1.03.12	All items of equipment including flue gas ducts, expansion joints, etc. shall be designed considering thermal and mechanical strength as a function of the maximum temperature which might occur in case of a failure of any upstream equipment.			
1.03.13	Waste water which might be generated during flushing and cleaning procedures of the equipment (e.g. lime slurry bins, pipes, trucks, etc.) shall be collected in sump and shall possibly be reused in the wet absorber.			
1.04.00	Justification of Proposed Design			
1.04.01	All the design procedures, systems, and components proposed shall have already been adequately developed and have demonstrated good reliability under similar or more arduous conditions elsewhere.			
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	 PAGE 3 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
1.04.02	The Bidder shall submit with the offer, comprehensive information on how the L/G ratio, mass balance, spray nozzle cone angle, spray nozzle arrangement, limestone consumption etc. of the proposed design has been arrived at. The Contractor shall also submit alongwith the offer, a detailed write up on the proposed design features with recent design modifications, if any, and their specific advantages over the previous designs.	
1.05.00	Statutory Approval The engineering, design, supply and installation of FGD system and the associated auxiliaries shall comply with the applicable safety code and regulation of the locality where the system is being installed.	
1.06.00	Location & Layout Requirements	
1.06.01	The Contractor shall offer the best design to accommodate the Flue Gas Desulphurisation (FGD) System and Lime stone & Gypsum handling & storage system within the confines of the space available. The location of FGD System and associated facilities shall be decided by the Bidder after visiting the Project site.	
1.07.00	Capital Overhaul of FGD System Employer envisages to carryout the capital overhaul of units once in three (3) years. The design and materials for various equipments/auxiliaries etc. shall be selected by the Contractor keeping in view the above requirement of the Employer, such that no major repairs/replacements, requiring shutdown of the unit, are needed in between the capital overhauls.	
1.08.00	Maintenance	
1.08.01	The Contractor shall provide adequate handling facilities & approach as for carrying out on-line and off-line maintenance of the FGD system and its auxiliaries. In order to carry out on-line maintenance, it shall be possible to readily disassemble, repair and reassemble the equipment supplied in the shortest period.	
1.09.00	Noise level The equivalent weighted average of sound level measured at a distance of 1.5 m above floor level in each elevation and one meter horizontally from the base of any equipments furnished and installed under these specifications, expressed in decibel to a reference of 0.0002 microbar, shall not exceed 85 dB(A).	
2.00.00	EQUIPMENTS AND SYSTEMS SPECIFICATIONS Specified hereafter are the minimum acceptable functional requirements of the Employer, and all components, equipments and systems for the Flue Gas	
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	 TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD)

CLAUSE NO.	TECHNICAL REQUIREMENTS			एनटीपीसी NTPC																		
	Desulphurisation System shall be designed to cater to these requirements. Compliance to various stipulations of the Technical Specifications, functional requirements of Employer and utilization of various parameters and their values in the specification by the Contractor shall in no way relieve the Contractor of his responsibilities to meet all guarantee requirements or of providing completely safe and reliable operating equipment/systems. The complete FGD system and the associated auxiliaries shall be designed by the standard industrial practices. The FGD system shall be designed to achieve the required SO₂ capture without the use of oxalic acid or any other additives. Only field proven materials for similar application shall be used for the system. The complete installation of liners shall be made under the supervision of the liner supplier as per their guidelines. In the execution of the welds contractor must ensure that welding material has same corrosion resistance as the actual plate surface. Alloy to carbon steel welds must either be hidden behind a covering strip of alloy material, or be executed by a special welding procedure ensuring the same quality at the weld surface as the alloy lining. All welding which shall be in the contact with process fluids shall be executed under the supervision of the designer/manufacturer.																					
3.00.00	FLUE GAS SYSTEM																					
3.01.00	The entire flue gas system, flue gas ducts, absorber etc. shall be designed to meet the following conditions:																					
	<table border="1"> <tbody> <tr> <td data-bbox="396 1058 461 1184">1.</td> <td data-bbox="461 1058 915 1184">Design internal pressure at 67% yield strength (mm wc)</td> <td data-bbox="915 1058 1386 1184">+660 and -150 mmwc or maximum conceivable head of Booster fan (if provided), whichever is higher</td> </tr> <tr> <td data-bbox="396 1184 461 1289">2.</td> <td data-bbox="461 1184 915 1289">Design Inlet Gas Temperature (deg.C)</td> <td data-bbox="915 1184 1386 1289">150</td> </tr> <tr> <td data-bbox="396 1289 461 1415">3.</td> <td data-bbox="461 1289 915 1415">Short temp excursion temperature of inlet gas (for approx. fifteen (15) minutes at a time) (deg. C)</td> <td data-bbox="915 1289 1386 1415">300</td> </tr> <tr> <td data-bbox="396 1415 461 1478">4.</td> <td data-bbox="461 1415 915 1478">Inlet Dust Burden in Gas (mg/Nm³)</td> <td data-bbox="915 1415 1386 1478">200</td> </tr> <tr> <td data-bbox="396 1478 461 1583">5.</td> <td data-bbox="461 1478 915 1583">Maximum flue gas velocity through the Absorber (M/sec)</td> <td data-bbox="915 1478 1386 1583">Not more than 4 m/s at Design Point Conditions</td> </tr> <tr> <td data-bbox="396 1583 461 1688">6.</td> <td data-bbox="461 1583 915 1688">Recirculation Slurry pH</td> <td data-bbox="915 1583 1386 1688">Not less than 5.5 under all operating conditions</td> </tr> </tbody> </table>			1.	Design internal pressure at 67% yield strength (mm wc)	+660 and -150 mmwc or maximum conceivable head of Booster fan (if provided), whichever is higher	2.	Design Inlet Gas Temperature (deg.C)	150	3.	Short temp excursion temperature of inlet gas (for approx. fifteen (15) minutes at a time) (deg. C)	300	4.	Inlet Dust Burden in Gas (mg/Nm ³)	200	5.	Maximum flue gas velocity through the Absorber (M/sec)	Not more than 4 m/s at Design Point Conditions	6.	Recirculation Slurry pH	Not less than 5.5 under all operating conditions	
1.	Design internal pressure at 67% yield strength (mm wc)	+660 and -150 mmwc or maximum conceivable head of Booster fan (if provided), whichever is higher																				
2.	Design Inlet Gas Temperature (deg.C)	150																				
3.	Short temp excursion temperature of inlet gas (for approx. fifteen (15) minutes at a time) (deg. C)	300																				
4.	Inlet Dust Burden in Gas (mg/Nm ³)	200																				
5.	Maximum flue gas velocity through the Absorber (M/sec)	Not more than 4 m/s at Design Point Conditions																				
6.	Recirculation Slurry pH	Not less than 5.5 under all operating conditions																				
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 5 OF 51																			

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC
3.02.00	Design	
3.02.01	The flue gas ducts shall be sized and designed to meet all the criteria as specified in Cl. No 16.00.00 this subsection.	
3.02.02	All ducts with operating temperature above 60°C shall be insulated in accordance with cl. No. 17.00.00 of this sub section.	
3.02.03	The duct layout shall ensure that there is no accumulation of acid mist on the duct floor.	
3.02.04	The duct to Absorber inlet shall be made of Carbon steel of minimum 7mm thickness. The duct to Absorber inlet shall be made of Carbon steel of minimum 7mm thickness. The duct from Absorber outlet to bypass duct shall be made of Carbon steel of minimum 7mm thickness with 2 mm (minimum) thickness lining / cladding / wall paper of Alloy C276 / Alloy 59 or better material.	
3.02.05	In addition to the base offer as described above, the bidder may also submit an alternate offer for a different material / lining of duct from Absorber outlet to stack, if the bidder has previous experience of the same. The bidder should have supplied a similar design of duct in previous installations for similar application. Bidder shall indicate the applicable price implication for such an alternate offer in the relevant Bid Proposal sheet. The Bidder shall also furnish details of the previous installations of such system and bring out all the technical features of the system proposed. Bidder to note that application of lining material in the ducts shall be carried out under the supervision of designer/manufacture. Bidder to note that application of lining material in the duct shall be carried out under supervision of Designer/Manufacturer.	
3.02.06	Wherever required, expansion joints of proven design shall be provided in the ducts to take care of differential expansion in the system. The material chosen for expansion joints shall suitable for the duty conditions and the corrosive atmosphere of the FGD system and shall be field proven for similar applications. The expansion joints shall be guaranteed for faultless material and workmanship, for a minimum guaranteed life of not less than 20000 hrs. of operation. During Guarantee period any defects noticed in the expansion-joints due to faulty material and workmanship shall be rectified by the Contractor free of cost.	
3.02.07	The Contractor, shall take into account the entire characteristics of expected combination of fuels to be fired, for the complete load range of operation and the expected numbers of Steam Generator start-ups while designing the Chimney flue liner. The chimney flue liner cladding shall be made of 2 mm thick Titanium (Grade 2 as per ASME SB265) or C-276 alloy over 8 mm thick (minimum) mild steel base metal of flue liner. Cladding shall be done to achieve the required quality as per ASTM B 898-11. External surface of chimney flue liner projecting over the chimney roof shall be wrapped with 2 mm thick Titanium / C-276 sheet over insulation.	
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2 PART-B SUB-SECTION-I-M1 (FGD) PAGE 6 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
	The stack shall be designed as per the latest guidelines of EPRI Wet Stack Design Guide. The design of wet ducts and stacks system shall consider the Stack liquid discharge (SLD), Corrosion/chemical attack, Condensate collection system and its drainage etc. 3.03.00 Gates & Dampers 3.03.01 The arrangement of the flue gas system shall allow complete isolation of the absorber from the gas side, with the unit in operation. Guillotine gate type damper shall be provided by the Contractor before the suction of each Booster fan. A gas tight, motor operated Guillotine gate shall be provided by the Contractor at the outlet of each Booster fan. A gas tight, motor operated Guillotine gate shall be provided by the Contractor in the bypass duct (flue gas duct connecting the existing chimney). 3.03.02 All gates/dampers shall be designed to withstand the operating flue gas temperature without distortion. 3.03.03 There shall not be any backlash, play, etc. with linkage mechanism, actuator and final control element. 3.03.04 Thermal expansion of ducting shall not produce stress in louvers, linkage arrangement etc. 3.03.05 Outlet dampers of seal air fans shall be pneumatically operated, suitable for remote manual operation. 3.03.06 All pneumatically operated interlocked dampers actuators shall be provided with solenoid valves. 3.03.07 A quick acting biplane damper shall be provided by the Contractor in the bypass duct (flue gas duct connecting the existing chimney) for quick opening to allow bypass to come into operation in case of emergency. The damper shall be capable of quick opening during emergency conditions within a time of 10-20 secs. Bidder should indicate the required opening time for bypass damper for emergency operating condition. 3.03.08 All the gates shall be designed for tight shut off. The Guillotine gate type dampers mentioned at Clause No. 3.03.01 above shall have a guaranteed gas tightness efficiency (on flow) of not less than 99.95% along the duct as well as from the duct to atmosphere or from atmosphere to the duct, depending on the pressure in both the damper open and damper closed condition without the use of seal air fans of the damper. The bypass damper shall have a guaranteed gas tightness efficiency (on flow) of not less than 99.5% and 100% leak tight with seal air fans under operation. The gas tightness shall be demonstrated at shop for minimum one type of damper of each type and size. 3.03.09 The dampers shall be pneumatically operated and controlled from the control room. Provision shall be made for giving signal automatic bypass controls of the absorber in case of failure of the absorber spray system or the GGH. The dampers shall have provision for manual operation, through a hand wheel. The force required for manual operation of the gate shall not exceed 35 kg (max.) at the rim of the hand wheel.			
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 7 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS													
3.03.10	The isolating gates shall be provided with locking devices to permit locking in fully closed position.													
3.03.11	Pressurization Fans: - All gates shall be provided with 2x100% pressurization fans to achieve 100% sealing efficiency. - The location and scheme for pressurization system shall be subject to Employer's approval.													
3.03.12	All gates shall be designed to withstand the operating air and flue gas temperature without distortion.													
3.03.13	All guillotine gates shall be located in horizontal duct to avoid fly ash build up when in closed position and shall be of top entry type.													
4.00.00	BOOSTER FAN:													
4.01.00	The Booster Fans shall be located downstream of the ID Fans (Induced Draft Fans) in the inlet duct to Absorber shall be capable of handling the pressure drop in the FGD system & ducting and wet stack of 150 m height also considering the exit loss from wet stack over the entire load range with any one or both Booster fans in operation in conjunction with one or both ID fan in operation while firing the specified range of fuels. Additionally a pressure loss of 100 mm wcl (excluding margin) shall be built up in booster fan design criteria as mentioned below to take care of pressure loss due to future installation of De-Nox system. Booster Fans shall be sized such that they satisfy the criteria stipulated below.													
4.01.01	<table border="1"> <thead> <tr> <th>S.N.</th><th>Description</th><th>Booster Fan</th></tr> </thead> <tbody> <tr> <td>1</td><td>Type of fans</td><td>Constant speed, axial type.</td></tr> <tr> <td>2</td><td>No. of fans per unit</td><td>Two</td></tr> <tr> <td>3</td><td>Fan sizing criteria with all the following conditions occurring together :</td><td>Booster Fan to be sized for one (1) Booster Fan stream in operation taking into account following factors occurring</td></tr> </tbody> </table>		S.N.	Description	Booster Fan	1	Type of fans	Constant speed, axial type.	2	No. of fans per unit	Two	3	Fan sizing criteria with all the following conditions occurring together :	Booster Fan to be sized for one (1) Booster Fan stream in operation taking into account following factors occurring
S.N.	Description	Booster Fan												
1	Type of fans	Constant speed, axial type.												
2	No. of fans per unit	Two												
3	Fan sizing criteria with all the following conditions occurring together :	Booster Fan to be sized for one (1) Booster Fan stream in operation taking into account following factors occurring												
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		 TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2												
PART-B SUB-SECTION-EM1 (FGD)		 POWER Senior Marketing PAGE 8 OF 51												

CLAUSE NO.	TECHNICAL REQUIREMENTS
4.02.00	together; (i) Flue Gas Flow through fan 920 m³/sec for all 800 MW units 724 m³/sec for 660 MW units of Mouda, Tanda , Nabinagar STPP & Barh-I 802 m³/sec for 660 MW units of Meja 893 m³/sec for 660 MW units of Solapur 297 m³/sec for 250 MW units of Nabinagar TPP (ii) Power supply frequency 47.5 Hz (iii) Pressure at Booster Fan suction 0 mmWc (iv) Gas temperature (degree Celsius) 150 The fans shall also fulfill following sizing criteria in addition to those mentioned at clause 4.02.01 above Each fan to be sized with following conditions occurring together. (i) No. of fans in operation 2 (ii) Flue gas flow through each fan 727 m³/sec for all 800 MW units 600 m³/sec for 660 MW units of Mouda, Tanda , Nabinagar & Barh-I 645 m³/sec for 660 MW units
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2 PART-B SUB-SECTION-I-M1 (FGD) PAGE 9 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	of Meja 678 m³/sec for 660 MW units of Solapur 237 m³/sec for 250 MW units of Nabinagar TPP (iii) Margin over flow 20% (iv) Margin over pressure requirement 44% over the calculated value (v) Power supply frequency 50 Hz (vi) Pressure at Booster Fan suction 0 mmWc (viii) Gas temperature (degree Celsius) 150 (viii) Flue gas control Blade pitch control Note to 4.02.01 & 4.02.02: Booster fan shall have a minimum stall margin of 10% over the Design duty points. 4.02.01 Both fans shall operate with highest possible efficiency which shall be nearly equal at the Guarantee point flow and test block points. 4.03.00 Fan components along with servo/blade pitch control mechanism shall be designed to withstand and continuously operate with the maximum air or flue gas temperature that these fans will be required to handle. Fan component shall also be designed to withstand the excursions in flue gas temperature up to 300 degree Celsius, which may persist for about 30 minute duration. Such temperature excursion will not inhibit the safe and smooth operation of fans or cause any damage or increased maintenance. 4.04.00 The construction of Booster fans shall also comply with following requirements	
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	  PART-B SUB-SECTION-1-M1 (FGD) PAGE 10 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC
4.05.00	DESCRIPTION Booster Fans Type of fan blades stream lined, aerofoil shaped section Blade material Nodular Cast Iron or High Wear Resistant Steel with or without Hard coating as per the proven practice of the fan manufacturer Fan rotational speed 600 rpm (max.) Air/Flue gas flow blade pitch control Fan critical speed not less than 125% of fan maximum operating speed Fan component design* to withstand torsional stresses three (3) times the normal full load motor torque at all speeds Fan casing material thickness Abrasion and wear resistant, high BHN steel having minimum 8.0mm thickness or 12mm mild steel with liner of thickness 10mm (min.) Fan Housing design for shut off head of fan *Note : (a) Contractor shall submit detailed calculations, for Employer's approval, to confirm compliance with above requirements for all fan components, specifically for fan shafts, impeller hubs and impeller as a whole. Areas of high stress concentration and residual stresses, like welded attachments shall be avoided on the fan rotor/shafts. Combined static, dynamic as well as residual stresses shall be demonstrated to be within allowable limits. These fan components shall last the life of the plant with such combined stresses present in them. (b) Although employer envisages to install highly efficient electrostatic precipitator to control particulate emission, however. Bidder shall select the Booster fan components such as blades, hubs, casing etc. to encounter the high dust burden of the order of 250 mg/Nm³. The minimum wear life of Booster fan components shall not be less than 25000 hours of operation from the date of commissioning. Fan Bearings (a) Bearing shall be provided with oil bath to prevent damage in case of complete loss of plant auxiliary power when the fans must coast down	
	LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2 PART-B SUB-SECTION-I-M1 (FGD) PAGE 11 OF 51	



range of
generating


CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC
	(c) Vibration For mounting of vibration pads/pickups (in the Employer's scope) flat surfaces shall be provided, both in X & Y directions, by the Contractor on the bearing housing in such a way, so that welding/screwing of the pads shall be possible. (d) Bearing metal temperature monitoring Shall be possible from remote as well as locally, using atleast 2 nos. of duplex platinum RTD's (100 ohms at 0 deg. C) per bearing	
4.08.00	The fans shall be suitable for parallel operation and sharing the load capacity over the entire range of operation without hunting. Pulsation shall be avoided by suitable design of fans and	
4.09.00	Fan Casing : (a) The fan casing shall be split to provide easy removal of the fan hub/impeller for replacement and repairs. (b) The sections shall have gasket joints to ensure airtight sealing. (c) Access doors shall be provided in each suction chamber casing and diffuser.	
4.10.00	Drain Connection: Drain connections shall be provided at bottom most point of the fan housing to the nearest trench.	
5.00.00	ABSORBER The unit shall be provided with an independent/dedicated absorber.	
5.01.00	The contractor may offer either a spray type absorber, with single or multiple levels of spray, or an absorber with gas bubbling through the slurry, as per Bidders/Colaborator's proven practice. Only proven system in successful operation in previous installations supplied by the contractor shall be offered. A Spray System (if offered) (i) The contractor shall provide spray system and minimum spray levels required to meet the stipulated guarantee and design requirement. The spray system (including slurry recirculation pump & nozzles) shall be sized to achieve a desired L/G ratio required to meet the guarantees SO₂ removal efficiency, with redundancies specified	
 LOT-1A PROJECTS *FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD) PAGE 13 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS		
	under this clause. (ii) In case the contractor offers an absorber with multiple levels of spray nozzles, each spray level shall be provided with independent 2x100% pumps. Alternatively, the contractor may offer a spare spray level with each spray level served by an independent 100% capacity pump. In case the contractor offers a single level of spray, one number of standby pump of the same capacity & head as the working slurry recirculation pumps shall be provided. The contractor shall provide spray system / spray levels only as per his proven practice, which should be in successful operation elsewhere. (iii) The slurry recirculation pumps shall have a minimum margin of 10% on flow and 10% on frictional head, over the actual requirement for meeting the guarantee and design point conditions. All slurry recirculation pumps including motors shall be of the same size and type. (iv) The slurry recirculation pumps shall have motor driven knife gate valve at pump suction and discharge side. (v) The slurry recirculation pumps shall be wear-resistant and equipped with flushing devices to prevent sedimentation and shall be designed and installed in a manner to allow easy replacements, repair and maintenance. The slurry recirculation pumps shall be equipped with oil level indication, coupling guard and collecting equipment for leakage, made of resistant material. Single mechanical seals with automatic flushing with a connection for additional manual flushing shall be provided. (iv) The slurry pumps shall also comply with the requirements stipulated in Clause 8.00.00 of this sub-section. (v) Sufficient redundancy, as per the proven practice of the contractor, shall be provided in the spray nozzles. Minimum 10% spare nozzles shall be provided at each level. B Bubbling Type Absorber (i) In case the bidder offers an absorber with gas bubbling through the slurry, the complete gas distribution system to the slurry shall be in bidder's scope. No re-circulating pump and spray header and nozzles shall be required in such case. However, 2x 100% Cooling Pumps instead of Slurry Recirculation shall be provided. The spray headers & piping for cooling pump discharge shall be made of Alloy 59 or C276 and nozzles shall be made of Silicon Carbide or ceramic or equivalent having a minimum guaranteed life of 20,000 hrs. The Cooling Pumps shall be installed inside a building.		
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	  PART-B SUB-SECTION-I-M1 (FGD)	PAGE 14 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
5.02.00	The sparger and gas riser tubes shall be made proven material which shall have a minimum life of 5 years.			
	Minimum 10% redundancy, shall be provided in the Sparger Tubes.			
	Absorber Recirculation Tank			
	Sufficient number of agitators, as per the proven practice of the contractor, shall be provided for thorough mixing of the re-circulating slurry. In case the Contractor's Absorber includes side entry agitators, the contractor shall offer and demonstrate mixing arrangement such that n-1 number of agitators are sufficient to avoid the slurry settlement in the absorber tank in case of one agitator under breakdown (n-total no. of working agitators). In case vertical agitators in Absorber are offered, one complete mechanical assembly of agitator shall be supplied as warehouse spare for each Absorber.			
	Absorber Oxidation Systems			
5.03.01	The contractor may offer either a grid type oxidation system or a sparge jet oxidation system or lance type or air rotary sparge system or jet air sparger system for oxidation of sulfite sludge to sulfates, or any other proven system as per the practice of the FGD vendor.			
5.03.02	The oxygen required for oxidation shall be supplied by 2x100% oxidation air blowers for each absorber. The compressor/blower shall be sized to supply at least 2.5 times the stoichiometric air requirement for spray tower process & at least 4.0 times the stoichiometric air requirement for Bubbling Type process or the actual requirement, whichever is higher, under the following condition, all occurring simultaneously. The natural oxidation of sulfite by residual oxygen in flue gas shall not be considered for this purpose.			
	Load	Design point Flow		
	Flow	Minimum 2.5 times for spray tower process & 4.0 for Bubbling Type process the stoichiometric requirement		
	Head	For spray tower process actual requirement considering choking/ blockage of minimum 10% of the oxidation nozzles / sprayers or minimum 8500 mmwc whichever is higher.		
		For Bubbling Type process actual requirement considering choking/ blockage of minimum 10% of the oxidation nozzles / sprayers or minimum 3500 mmwc		
	LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	 PAGE 15 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS एनटीपीसी NTPC										
	whichever is higher. Margin on Head 10% under above conditions. Ambient Conditions 45°C / 60% RH. 5.03.03 Oxidation nozzles / spargers shall have a minimum redundancy of 10% or as per the contractor's proven practice whichever is maximum. 5.03.04 The oxidation system shall be complete with a quenching system to cool down heated oxidation air in order to prevent any scaling or buildup that could occur at the sparger tips due to localized evaporation of recycled slurry. 5.04.00 Gypsum Bleed Pump Each absorber shall be provided with 2x100% Gypsum Bleed Pumps for supply of gypsum slurry to Gypsum Dewatering system. Each Gypsum bleed pump shall be sized to bleed-off the gypsum slurry from the absorber with slurry solid concentration not exceeding 30%, under the following conditions, all occurring simultaneously: <table data-bbox="462 997 1356 1312"> <tr> <td>Load</td><td>Design point</td></tr> <tr> <td>Flow</td><td>100% of gypsum produced at Design point condition</td></tr> <tr> <td>Head</td><td>As per system requirement</td></tr> <tr> <td>Margins</td><td>Flow – 15%</td></tr> <tr> <td></td><td>Head – 20%</td></tr> </table> The pumps shall be designed to meet the stipulations of Clause No.9.00.00 of this Sub-Section. Provision shall also be provide in the Gypsum Bleed Pumping system by provision of tap off, valves etc. for pumping the gypsum bleed to alternate source. 5.05.00 Emergency Spray System An emergency cooling system for automatic spray of quenching water for a sufficient time (minimum 15 min) at the inlet to the absorber, in case the gas temperature exceeds the design temperature due to failure of upstream equipment's shall be provided to protect the FGD and all other sensitive downstream equipment against high flue gas temperatures. The water shall be supplied from an elevated tank (emergency water tank) installed near to the absorber. The tank volume and the	Load	Design point	Flow	100% of gypsum produced at Design point condition	Head	As per system requirement	Margins	Flow – 15%		Head – 20%
Load	Design point										
Flow	100% of gypsum produced at Design point condition										
Head	As per system requirement										
Margins	Flow – 15%										
	Head – 20%										
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	 TECHNICAL SPECIFICATION SECTION 4.1 BID DOCUMENT NO.: CS-0044-109(1A)-2  PART-B SUB-SECTION-I-M1 (FGD) PAGE 16 OF 51										

CLAUSE NO.	TECHNICAL REQUIREMENTS	
5.06.00 5.06.01 5.06.02 5.06.03 5.06.04 5.06.05 5.06.06	injection lances/nozzles shall be designed to protect the inlet duct and the lining of the absorber. The inlet duct shall be sloped towards the absorber. Design The design and arrangement of the absorber shall be field proven for successful long-term operation in conjunction with a coal fired power plant. The design of flue gas ducts and inlet and outlet hoods of the FGD as well as guide vanes and baffle plates shall ensure a homogeneous flue gas flow with respect to the distributions of: (i) temperature (ii) velocity (iii) dust content (iv) slurry injection and distribution. The above shall be proven by two phase Computational Fluid Dynamics simulations (liquid and gas). The scope of modelling shall include flue gas path inside the absorber vessel including inlet and outlet duct. Homogeneity shall be ensured, if the deviation from average is less than $\pm 10\%$. Further, in the Absorber outlet hood no internals such as guide vanes and baffle plates shall be allowed. The fabrication of the absorber vessel shall follow common practice as there shall be no longitudinal seams located behind any attachment or obstruction which would prevent inspection of the welds. Nozzles, access ways, and their reinforcements shall not be located in or on any seam. Inaccessible gaps or hollow beams shall be avoided. The absorber shell shall be designed for pressure loads, piping forces and moments, wind and seismic loads and all other loads imposed on the absorber. Bracing and reinforcement shall be adequate to prevent deflection and vibration. Internal supports for mist eliminator sections, etc. shall be designed to withstand the flooded weight of the supported section. The absorber and its structural supports shall be designed for the maximum operating loads including design positive & negative internal pressure, static head, external attachment loads (such as exerted by piping) wind load using the allowable stresses permitted by the applied standards. It shall be possible to reach the SO₂ emission guarantees, at Guarantee point condition, with at least one spray level continuously out of service (in case the absorber is equipped with several spray levels) or one spare pump continuously out of service. Three stage chevron type Mist Eliminators (ME) made of polysulfone or stainless steel shall be provided at the exit of the absorber. Provision shall be made for continuous washing of both ends of the first & second stage and the front section of the third stage of mist eliminators. Wash water arrangement shall also be provided at the back end of the second stage of mist eliminator. If the mist eliminator washing system is designed for cyclic washing of different sections, all the valves required for cycling shall be motorized or pneumatically operated. The automatic valve for the spray system shall be easily accessible on a platforms close to the mist eliminator.	
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD) PAGE 17 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC	
	Entrained slurry shall be collected by mist eliminators downstream of the slurry spray system to avoid carry-over of slurry to the stack. The ME system shall be equipped with washing and drain provisions, where drains are directed into the absorber. Washing provisions shall include external and internal piping systems with replaceable nozzles, water pressure booster pumps (if required) complete with all piping, valves, instrumentation and controls. The mist eliminator wash piping/header shall be constructed of rubber lined carbon steel or glass fiber reinforced plastics. Polypropylene or PVC is also acceptable for mist eliminator wash headers provided Contractor or its Collaborator has proven experience for the same. Ease of replace ability and placement of the mist eliminator on maintenance platforms is an important requirement. The ME shall be designed to allow for efficient cleaning in process. Test ports shall be provided downstream of the mist eliminator to enable performance testing. The mist eliminator system shall be capable of withstanding high velocity spray water jets typically employed during manual cleanings. The ME shall be constructed in individual cells. The design shall safely avoid ME vibration and/or humming. The individual cells shall be sized so that no more than two maintenance personnel are needed to handle them manually when they are fully scaled or plugged, and the cells shall be capable of passing through the access doors for the mist elimination section. Easy access for placement and replacement of the mist eliminator shall be incorporated in the design of the mist eliminator arrangement and the absorber vessel. Walkways shall be arranged and also measures shall be taken as appropriate to permit the internal components to be disassembled and reassembled during repairs without the necessity for time-consuming preparatory work. The headroom shall have a height of more than 2200 mm. The mist eliminator support beams shall be designed to act as maintenance walkways approximately 300 mm wide and shall allow for a minimum 500 Kg/m² load. The support beam/walkways shall provide personnel access to all mist eliminator modules, wash headers and wash nozzles. Adequate number of viewing ports with flushing devices connected to automatically operating washing system shall be delivered at following locations: (i) upstream of 1st stage (ii) between 1st and 2nd stage (iii) downstream of 2nd stage. (iv) downstream of 3rd stage The regular flushing shall be done in a defined time sequence. 5.06.07 The absorber oxidation tank shall be provided with an over flow line (for spray tower process) complete with sealing pot, over flow and drain line. The absorber over flow shall be taken to a sump in the absorber region, from where the slurry shall be pumped back to the absorber by a sump pump. 5.06.08 Materials used shall be suitable for the chemistry of the absorber process and resist abrasion from any particulate contained in the incoming flue gas and from the		
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION IV BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD)	PAGE 18 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	particulate of desulphurization process.	
5.06.09	All equipment located in the gas path or connected to such equipment shall be designed to withstand the maximum inlet gas temperature fluctuations. There shall be no damage whatsoever to any equipment as a result of these fluctuations.	
5.06.10	The raw gas inlet duct of the absorber shall be equipped with a flushing device of the side walls and the ground, which shall operate continuously as well as intermittently.	
5.06.11	The absorber vessel shall be made of minimum 7 mm thick carbon steel. The absorber oxidation tank, absorber tower & absorber outlet duct shall be provided with 2 mm (minimum) thickness lining / cladding / wall paper of Alloy C276 / Alloy 59 or better material.	
5.06.12	The material of process equipments of flue gas desulphurization system shall be appropriate for the chloride content and pH level at which the process is to operate.	
5.06.13	All internal members shall be lined with minimum 2 mm Alloy 59/ C276 . All metallic fasteners which are provided inside the absorber/absorber wet-dry interface ducting shall be of Alloy 59/ C276.	
5.06.14	The absorber wet-dry interface shall be made of solid Alloy 59 or C276 of minimum 6 mm thickness.	
5.06.15	The other bridges (supports) shall be lined with minimum 2 mm Alloy 59/ C276.	
5.06.16	Lining material and technical application requirements shall be furnished by manufacturer experienced with similar FGD plants. Proof of such experience shall be provided by the Contractor.	
5.06.17	The spray headers (if provided) and air supply headers shall be made of FRP or Carbon Steel with rubber lining (minimum 10 mm natural rubber lining), corrosions and erosion resistant in the inner and outer side (Silicon Carbide coating on metal/FRP surface exposed to slurry). Optionally ceramic coating is also acceptable provided bidder/Collaborator has proven experience for the same. The slurry spraying system shall be made of material resistant to erosion and corrosion. During the lifetime of the plant, only the nozzles shall be replaced. The distribution system of the slurry shall be hydraulically optimized. The spray nozzles shall be of silicon carbide or ceramic or equivalent having a minimum guaranteed life of 20,000 hrs. The design of the spray nozzles shall be such that rapid wear, encrustation and plugging are avoided. Nozzle pipes and slurry spray nozzles shall be with bolted flanged connections. Nozzle pipes shall be installed easily to be removed partially through absorber modules.	
5.06.18	In case the absorber is equipped with several spray levels they shall be designed as follows:	
	LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	PART-B SUB-SECTION-I-M1 (FGD)
	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PAGE 19 OF 51


CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC	
	(i) The last spray level upstream the mist eliminator shall be operated only in counter-flow. (ii) Depositions at downstream spray level and mist eliminator by co-flow injection of slurry shall be avoided. (iii) The spray lances shall be equipped with bars for installation of scaffolding without any offset. The spray levels shall be designed for a load of min. 500 kgf/m². (iv) A flushing device of the spray levels with water shall be installed. Flushing shall take place if spray levels are out of operation.		
5.06.18	The absorber shall be self-supported from the bottom to suit site conditions. Absorbers which are externally supported from the structure are also acceptable provided Bidder or its Technology Collaborator has proven experience of supplying such Absorbers which are operating for more than 5 years. The absorber shall have adequate stiffening arrangement on the external side. Internal stiffeners shall be used only where it is not possible to provide proper external stiffening with approval of employer.		
5.06.19	It should be possible to build platforms inside the absorber for access to all parts of the absorber during maintenance. In case the contractor offers a multiple spray level design, minimum distance of 1.5 m shall be maintained between individual spray levels. Arrangement shall be properly designed to facilitate access for maintenance and replacement of spray nozzles.		
5.06.20	The spray piping, mist eliminators and its supporting structure shall be designed to carry sufficient load during maintenance.		
5.06.21	The bottom of the absorber sump shall be designed so that there will be an easy entrance for a man with a wheelbarrow. Therefore the arrangement and dimensions of the inspection door of the absorber at ground level shall be designed to allow for this. The bottom of the absorber sump shall be designed in such a way that complete drainage of the absorption liquid/slurry is possible and is accessible without damage of lining/rubber.		
5.06.22	In case of Spray Tower System, Suction screens shall be installed inside the Absorber vessel to protect the Slurry recirculation pumps. In case Bubbling type, suction strainers shall be installed at the suction side of Gas Cooling Pumps. For the agitators a flushing system for start ups shall be provided.		
5.06.23	It should be possible to discharge the absorber sump into the emergency drain tank within 2 hours.		
5.06.24	At the head of the absorber two manholes shall be provided to reduce the draught of the stack during outage.		
5.06.24	Equipment's required for internal & external inspection shall be furnished by the contractor in brand new condition. List of all such items shall be furnished along with the Bid. The formation of agglomeration, deposition & caking shall be avoided. For		
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD) PAGE 20 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	areas, where this might occur, (e.g. mist eliminators, spray levels) the Contractor shall submit a cleaning procedure including the required safety measures as part of the inspection concept.	
6.00.00	LIMESTONE GRINDING AND SLURRY PREPARATION SYSTEM	
6.01.00	Type	
	A common limestone and slurry preparation system is envisaged for each project. Contractor shall supply wet limestone grinding and slurry preparation system complete with all auxiliaries and slurry storage tank of proven design.	
6.02.00	Limestone Silo:	
6.02.01	The Contractor shall provide 2X100% Limestone storage silos each silo having minimum 24 hours storage capacity equivalent to the requirements of FGD system of all the units operating at Design point. The storage silo shall be complete with supporting steel structure, platforms, staircase, air canons power operated gates, gravimetric feeders, level switches, air relief devices, etc..	
6.02.02	The storage silos and hopper cones shall be fabricated of minimum 10 mm thick carbon steel with a SS lining of grade SS304 of minimum 4 mm thickness in the complete cones to ensure reliable discharge of material. The design of storage silos shall conform to IS 9178 (Part 1 to 3). The storage silo shall be capable of feeding the limestone by means of gravimetric feeder to the wet ball mills. The top of the unloading hopper shall be equipped with a grate to protect the downstream equipment from gravel lumps or tramp waste.	
6.02.03	Each Silo shall be provided with sufficient no. of level transmitters.	
6.02.04	Each silo shall be provided with minimum 3nos. of air canons at necessary location, capable of removing the jamming/clogging/blockage in the silos.	
6.02.05	For dust free operation each silo should be provided with a covering arrangement and a self cleaning bag filter system of suitable capacity containing blower, automatic/on-load cleaning system, etc.	
6.02.06	For each silo facilities shall be provided for unloading the bunker, through feeder, to a truck at ground level, along with all necessary chutes and diversion chutes.	
6.02.07	Lime stone silo with hopper may be fabricated at factory in segments, transported and welded at site.	
6.03.00	Bunker Shut-off Gates	
6.03.01	A bunker outlet chute shall be provided for feeding limestone from bunker to the feeder. The size of the opening chute shall be sufficient to ensure proper flow of the limestone. There shall be no reduction of section in the bunker outlet chute from	
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD) PAGE 21 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC	
	bunker to feeder. The inlet chute shall be provided with suitable poke doors/holes in order to remove jamming/blockage. A motorized bunker shut-off gate shall be provided at the inlet to each feeder.		
6.03.02	All parts of the gate in contact with limestone shall be of stainless steel construction.		
6.03.03	The shut-off gates and its actuator shall ensure 100% closing of the gate even with 'bunker full of limestone'.		
6.03.04	Facility shall be provided to open/close the bunker outlet gate, through actuator, from remote as well as local.		
6.03.05	In addition, a hand wheel with proper access shall also be provided for manual operation of the gate. The force at the rim of the hand wheel shall not exceed 35 kg with bunker full of coal.		
6.03.06	For each bunker facilities shall be provided for unloading the bunker, through feeder, to a truck at ground level, along with all necessary chutes and diversion chutes.		
6.04.00	Gravimetric Feeders		
6.04.01	Gravimetric feeders shall be sized to meet 110% of the maximum mill capacity.		
6.04.02	The limestone feeder belt shall be of seamless rubber construction. It should be possible to adjust the belt tension from outside without opening the feeder body.		
6.04.03	All parts in contact with limestone except belt shall be of stainless steel construction.		
6.04.04	The feeder shall have adequate instrumentation to detect 'loss of flow'.		
6.04.05	The feeder shall have a motor/pneumatic operated gate at the outlet.		
6.05.00	Wet Ball Mill		
6.05.01	There shall be 2X100% tube mills for grinding of limestone. Each mill shall be sized to meet 110% of the maximum limestone requirement of all the units in a project operating under the following conditions, all occurring together.		
	(i) Load	Design point flow	
	(ii) Flow	110% of limestone requirement of two absorbers at Design point	
	(iii) Input Limestone Size	1" (max.)	
	(iv) Output Fineness	Output Fineness 90% or higher (as per the requirement of absorber) through 325 mesh (for spray tower process) OR 90% or higher (as per	
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 22 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	the requirement of the absorber) through 200 mesh (for bubbling process) (v) Mill Wear Part Near Guaranteed Wear Part Life. Conditions (vi) Limestone bond 13 (min) index(kWh/sh.T)	
6.05.02	All integral auxiliaries of the mills like hydro-cyclones, separator tank & mill circuit pumps shall be sized to meet the above conditions. A 100% stand-by pump shall be provided for the mill circuit pump.	
6.05.03	The mill hydro-cyclone set shall have sufficient redundancy. A minimum 10% spare hydro-cyclone shall be provided in each set of hydro-cyclone. Hydro-cyclones shall be of modular construction. It shall be possible to remove and replace individual hydro-cyclone with the set in service. Individual isolation valve shall be provided for each hydro-cyclone for this purpose. The hydro-cyclone shall be of proven design and shall be provided with replaceable rubber lining. The hydro-cyclone shall be provided with replaceable rubber lining of thickness 12 mm for the feed chamber and 12 mm for the overflow launder.. The liners shall have a minimum wear life of not less than 7000 hrs.	
6.05.04	All parts of the mill including mill body, trunnion, hydro-cyclones, integral pipes, mill circuit pumps and other parts in contact with limestone slurry shall be provided with replaceable rubber wear liners. The wear liners or wear parts shall have a minimum guaranteed wear life of not less than 8000 hrs without reversal of the liners. The guaranteed capacity and fineness of the mill shall not be affected within the guaranteed life of the mil wear parts.	
6.05.05	The material of the balls shall be chosen to ensure that the balls do not lose their original shape and to ensure minimum ball consumption. The contractor shall also guarantee ball consumption per ton of limestone throughput. The contractor shall furnish the minimum ball diameter below which the balls shall be replaced.	
6.05.06	Facility shall be provided for on-load loading of steel balls to the mill.	
6.05.07	The ball mill shall be driven by a motor through a peripheral gear/ central drive system. An auxiliary motor shall also be provided for inching of mills after trip and during maintenance.	
6.05.08	The lube oil system shall have 100% stand-by arrangement for lube oil pumps and oil coolers of each circuit with independent pump / cooler. Wherever required duplex oil filters shall be provided.	
6.05.09	The mill auxiliaries like separator tanks, mill circuit pump, hydro-cyclones and all connecting pipes handling limestone slurry shall have replaceable rubber linings.	
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD) PAGE 23 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS		एनटीपीसी NTPC
6.06.00	Limestone Slurry Preparation / Storage Tank		
6.06.01	The contractor shall provide two (2 nos.) slurry storage tank, common for all mills. Each tank shall be sized to meet 12 hours continuous limestone requirement of all the units operating at Design point. For tank volume calculation, solid concentration (by weight) in the slurry shall be assumed, not more than 20% or actual required whichever is lower.		
6.06.02	The storage tanks shall be equipped with sufficient number of agitators, to avoid settling of limestone, as per the proven practice of the supplier. The agitators shall be designed to meet the requirements stipulated in Cl. No. 11.00.00 of this Sub-Section.		
6.06.03	The limestone mill circulation tanks shall be installed indoor beneath the hydro cyclone stations. The slurry storage tank shall be located outdoor.		
6.06.04	The slurry preparation tank shall be CS construction with replaceable chlorobutyl/bromobutyl rubber lining of minimum 5 mm thickness.		
6.07.00	Limestone Slurry Supply Pumps & Piping		
6.07.01	2x100% centrifugal type limestone slurry pump shall be provided for each unit. Each limestone slurry pump shall be sized to supply the limestone requirement of one (1 no.) unit, under the following conditions all occurring together.		
	(i)	Load	Design point
	(ii)	Flow	110% of one absorber requirement with the limestone requirement at Design point.
	(iii)	Head	As per system requirement.
	(iv)	Margins	Flow 10% (minimum) Heads 15% (minimum)
	(v)	Solids Concentration	Max. 30% by weight or actual as per suppliers practice, whichever is minimum.
6.07.02	The limestone slurry pumps shall be designed to meet the requirements stipulated in Cl. No.8.00.00. of this Sub-Section.		
6.07.03	The limestone slurry pipes shall be sized to minimize erosion and avoid settling of the limestone at part load operation. The slurry pipes shall be lined with replaceable wear resistant natural rubber lining of minimum 10 mm thickness. Additional thickness of 2 mm in rubber lining shall be provided at bends.		
6.07.04	Automatic flushing equipment for all lime slurry pumps and pipes shall be supplied.		
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	Central Heavy Electricals Ltd. Sector Marketing PART-B SUB-SECTION-I-M1 Page 20 of 51 NEW DELHI FGDI एनटीपीसी NTPC POWER SUPPLYING CO. PVT. LTD.



CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC
7.00.00	GYPSUM DEWATERING SYSTEM	
7.01.00	A common gypsum dewatering system for all the units operating at Design point is envisaged. Contractor shall supply a two stage gypsum dewatering system, consisting of a primary stage of sets of hydro-cyclones and secondary stage of vacuum belt filters for dewatering of gypsum from absorber up to less than 10% moisture. All the equipments supplied shall be proven design with previous installations for similar capacities.	
7.02.00	The Contractor shall provide 2x100% gypsum dewatering system with each stream sized to dewater 110% of the maximum gypsum produced by all the units operating at Design point. All other stipulations with respect to sizing and design of the dewatering system, auxiliaries and other systems shall be in line with this specification.	
7.03.00	Primary Dewatering Hydro-cyclones	
7.03.01	Each set of primary dewatering hydro-cyclone shall be sized to dewater the gypsum slurry produced by the unit operating at Design point with an additional 10% margin. The outlet water content in the gypsum shall be as per the requirement of the vacuum belt filters.	
7.03.02	Each set of primary hydro-cyclone shall be provided with 10% spare hydro-cyclones. The capacity defined in the previous clause shall be met with spare hydro-cyclones out of service.	
7.03.03	The primary hydro-cyclone shall be installed directly above the belt filters. The overflow of the hydro-cyclones shall be taken to Hydro-cyclone Waste Water tank via secondary hydro-cyclone feed tank and secondary waste water hydrocyclone as shown in the relevant tender drawing.	
7.03.04	Hydro-cyclones shall be of modular construction. It shall be possible to remove and replace individual hydro-cyclone with the set in service. Individual isolation valve shall be provided for each hydro-cyclone for this purpose.	
7.03.05	The hydro-cyclone shall be of proven design. The primary hydro-cyclone shall be made up of polyurethane or urethane materials. It shall be possible to remove and replace individual hydro-cyclone with the set in service. Individual isolation valve shall be provided for each hydro-cyclone for this purpose. The feed chamber shall be provided with a minimum rubber lining thickness of 12mm. The liners shall have a minimum wear life of not less than 7000 hrs.	
7.04.00	Vacuum Belt Filters	
7.04.01	Each vacuum belt filter shall be sized to meet the following requirements, all occurring together, with an inlet solid concentration of not more than 45% or outlet of hydro-cyclones whichever is minimum:	
GEN ERATING CO. PVT. LTD. NTPC LOT-1A PROJECTS FUELS GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	Heavy Electricals Ltd. Sector Marketing New Delhi - 110048 PART-B SUB-SECTION-I-M1 (FGD) PAGE 25 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	a. Capacity 110% of gypsum produced by Absorbers of all the units operating at Design point. b. Outlet Moisture 10% max. c. Gypsum Purity 90% (minimum) d. Chloride content < 100 ppm	
7.04.02	The vacuum belt filter shall be proven design in operation for similar capacities. The filter cloth shall be polyester or polypropylene as per the proven design of the supplier and shall be guaranteed for a minimum life of not less than 7000 hrs.	
7.04.03	The complete frame of the filter and all parts in contact with gypsum shall be made of corrosion resistant material or shall be provided with corrosion resistant liners of proven design.	
7.04.04	In case, the contractor offers a design with an underlying belt for carrying the filter cloth, the same shall be endless, factory vulcanized rubber belts. The belt shrouds and the sealing belts shall provide a leak tight arrangement to prevent overflow of gypsum slurry. The sealing belt shall have minimum life of not less than 7000 hrs.	
7.04.05	The vacuum box shall ensure tight sealing with the belt/cloth and shall be of proven design.	
7.04.06	The belt filter shall have an automatic cloth tracking mechanism and shall be provided with all required instrumentation as per the supplier's proven practice. The belt filter shall have an automatic cloth tensioning mechanism.	
7.04.07	The filter shall be provided with minimum 2 stages of cake washing for removing impurities in the gypsum. For cake washing only clarified water shall be used. For this purpose, one (1) clarified water storage tank (minimum 1 hr storage) shall be provided along with 2x100 cake washing pumps for each Vacuum Belt Filter. One stage of cloth washing arrangement shall also be provided along with 2x100 cloth washing pumps for each Vacuum Belt Filter.	
7.04.08	The filtrate from gypsum slurry and from cake washing shall be taken to a common or separate vacuum receiver tank(s) as per the proven practice of the supplier. Each belt filter shall have an independent vacuum pump.	
7.04.03	Gypsum cake from each belt filter shall be discharged through a hopper onto belt conveyor being provided by the Employer.	
7.04.04	A 2 m (min.) wide platform shall be provided around each belt filter for easy approach & maintenance. Handling facilities for replacement of heavy components	
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC
	of the belt shall also be provided.	
7.05.00	Vacuum System	
7.05.01	The filtrate from each belt filter, cake washing & cloth washing shall be taken to a common or separate receiver tank(s) as per the supplier's proven practice.	
7.05.02	Each belt filter shall be provided with an independent vacuum pump sized to meet the requirements of the belt filter operating at its maximum capacity. An additional margin of 10% (min.) over the above capacity shall be provided for each vacuum pump.	
7.05.03	The vacuum pump shall be of low speed liquid ring type of proven design. The design of the vacuum pumps shall avoid cavitations under all operating conditions. The seals shall be of proven design.	
7.05.04	Silencers shall be provided, if required, to limit the noise level to values stipulated elsewhere in this specification.	
7.05.05	The vacuum receiver and pump internals shall be suitably lined to protect against the corrosive environment. The material selected for vacuum pumps & vacuum receivers shall be proven for similar application.	
7.05.06	Each vacuum receiver tank(s) shall be provided with slide plate type pneumatic vacuum breaker. The plate shall be stainless steel with a min. thickness of 3 mm.	
7.06.00	Filtrate System	
7.06.01	Water from vacuum receiver tank(s) and the secondary waste water hydrocyclone underflow shall be taken to a common filtrate tank for recirculation to the absorber tanks.	
7.06.02	2x100% horizontal centrifugal pumps shall be provided for recirculation of filtrate water to absorber. 2x100% horizontal centrifugal pumps shall be provided for wash water requirements of belt filter. Alternatively, wash water pump may take suction from the vacuums receiver tanks. Each pump shall be provided with 100% standby in such a case.	
7.06.03	The pump shall be capable of pumping of filtrate water with solid concentration of not less than 10% & particle lumps of 6-7mm. A 10% margin shall be provided in each of the pump.	
7.07.00	Waste Water System	
7.07.01	The overflow of the primary hydro-cyclones shall be taken to a secondary hydrocyclone feed tank for feeding the secondary waste water hydro-cyclones.	
7.07.02	The secondary hydrocyclone feed tank shall be sized to provide a minimum storage	
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD) PAGE 27 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	of 1 hr of primary hydro-cyclone overflow with all the units operating at Design Point and no outflow from the tank.	
7.07.03	2x100% horizontal centrifugal pumps shall be provided to feed the secondary hydro-cyclones.	
7.07.04	Each set of hydro-cyclone shall be sized to process the maximum discharge from the secondary hydro-cyclone feed pumps. A minimum 10% spare hydro-cyclones shall be provided in each set. Secondary Hydro-cyclones shall be of modular construction and of proven design. The secondary hydro-cyclone shall be made up of polyurethane or urethane materials. It shall be possible to remove and replace individual hydro-cyclone with the set in service. Individual isolation valve shall be provided for each hydro-cyclone for this purpose.	
7.07.05	The secondary waste water underflow shall be taken to the adequately sized filtrate tank, while the overflow shall be taken to a waste water Tank.	
7.07.06	1x100% Waste water tank shall be provided (in projects where separate Zero Liquid Discharge system for waste water treatment is not in the scope of the contractor) which shall be sized for 8 hrs storage of waste water with all the units operating at Design point and no out flow from the tank. The Waste water Tank shall be complete with Agitator, level transmitters etc. The waste water collection tank shall be of Steel construction with rubber lining. 2x100% horizontal centrifugal pumps shall be provided for pumping the waste water from waste water tank at required pressure to waste water terminal point as indicated in Sub-section IV, Part A, Section VI of the Technical Specification. The material of Casing and impeller shall be rubber lined Cast Iron (IS:210 Gr FG260). Shaft and Shaft Sleeves shall be Stainless Steel-410.	
7.07.07	All piping, valves & instrumentation upto the employer's terminal point shall be in the contractor's scope. Contractor shall provide the complete lime dosing system (in projects where separate Zero Liquid Discharge system for waste water treatment is not in the scope of the contractor) to correct the pH of the waste water by lime (83% purity) dosing shall be provided and after mixing of the effluent (using re-circulation system of the pumping system), the effluent shall be discharged once the waste water has been neutralized to desired pH. A pH monitor shall be provided at the discharge of the pumps for measurement and control. Complete lime storage, feeding & dosing system shall be in contractor scope. The complete waste water neutralization system shall be automated and controlled from the control room.	
7.07.07	Contractor shall provide 2x 100% Lime Neutralization tanks (in projects where separate Zero Liquid Discharge system for waste water treatment is not in the scope of the contractor) which shall be of minimum 8 hr capacity made of carbon steel with rubber lining along with 2x100% Lime storage silos. The tanks shall be provided with SS dissolving basket, Agitator of SS construction, drain, over flow and dosing connection, level transmitters, Agitators etc. The storage silos and hopper cones shall be fabricated of minimum 10 mm thick carbon steel with a SS lining of grade SS304 of minimum 4 mm thickness in the complete cones to ensure reliable discharge of material. The design of storage silos shall confirm to IS 9178 or any	
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	



CLAUSE NO.	TECHNICAL REQUIREMENTS		
8.01.00	This Clause covers the design, manufacture and erection of all slurry pumps for the FGD system including the Absorber slurry recirculation pumps, Gypsum bleed pumps, Limestone slurry feed pumps, Mill circuit pumps and any other pump handling slurries.		
8.02.00	The Contractor shall offer only proven design in successful operation in similar application at previous installations. The design, manufacture, installation and testing of the pumps shall follow the latest applicable Indian / International (ASME / EN / Japanese) Standards.		
8.03.00	The pumps shall be designed for continuous operation. The pump shall be single stage centrifugal type capable of delivering the rated flow at rated head with margins as specified in the respective clauses. The slurry concentration in the pump shall not exceed 30% by weight except for Mill circuit slurry pumps for which the slurry concentration in the pump shall not exceed 55% by weight.		
8.04.00	All the slurry pumps shall be provided with motorized suction and discharge valves. In addition, flushing water lines with motorized valves shall be provided for each pump for automatic flushing of the pump after each shut down. The flushing water for the pumps shall be taken from the process water supply		
8.05.00	The pump casing should be radially split to allow easy removal of impeller.		
8.06.00	All the pump wear parts in contact with the slurry shall be provided with replaceable rubber/elastomer liners suitable for the fluid handled. The Bidder can also offer an hi chrome alloy line pump if the Bidder has previous experience of the same for similar applications. The material used by the contractor shall be proven in previous installations.		
8.07.00	For absorber recirculation service a Silicon carbide impeller and SiC lining for casing can also be accepted if the manufacturer has supplied a similar pump for a previous installation for similar service.		
8.08.00	The material and thickness of the liners shall ensure a minimum service life of 2 years before replacement. All the wear parts of the pump shall be guaranteed for a minimum wear life of not less than 14000 hrs.		
8.09.00	The design of the shaft shall ensure that the operating speed is at least 20% above the critical speed of the shaft.		
9.10.00	The pump shall be provided with seals of proven type and shall be designed for minimization of seal water consumption. The shaft shall be supported on heavy duty ball/roller bearings.		
9.00.00	VERTICAL SUMP PUMPS		
9.01.00	Contractor shall provide sumps of adequate capacity in the each absorber area, limestone grinding area and gypsum dewatering area for containing the overflow		
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD)	 PAGE 30 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
	from the respective systems. Contractor shall make arrangements for pumping the drainage water back to the respective system with vertical sump pumps. Agitators shall also be provided to avoid settling of solids in the sump. Adequate redundancy in line with the standard practice adopted by the bidder shall be provided. This Clause covers the design, manufacture and erection of all vertical sump pumps for the FGD system.			
9.02.00	The contractor shall offer only proven design in successful operation in similar application at previous installations. The design, manufacture, installation and testing of the pumps shall follow the latest applicable Indian / International (ASME / EN / Japanese) Standards.			
9.03.00	The pumps shall be designed for continuous operation. The pump shall be single stage centrifugal type with semi open or open impeller. The pump impeller shall be cantilever type and shall not be supported below the base plate for easy withdrawal.			
9.04.00	The pump shall deliver the rated flow at rated head with margins as specified in the respective clauses. The pump shall be capable of pumping of filtrate water with solid concentration upto 10% & particle lumps of 6-7mm. Sump pumps handling slurry shall be designed with a maximum concentration of 30% solid by weight.			
9.05.00	The material chosen for the pump components shall be suitable for the fluid handled and shall be proven in similar application.			
9.06.00	The pumps shall not be supported below the base plate level for easy withdrawal without entering the sump.			
10.00.00	SLURRY & PROCESS WATER TANKS			
10.01.00	All the slurry tanks (Slurry Tanks, Filtrate Tank, Secondary hydro cyclone feed tank, vacuum receiver tank, Waste water Tank, Lime Neutralization tanks etc.) shall be designed, fabricated, erected and tested in accordance with the IS:803, latest edition. Additional Corrosion allowance of 3mm on the minimum tank shell thickness as calculated by IS:803, latest edition shall be provided by the Contractor. Tanks shall be made from IS:2062 quality mild steel plates of tested quality. The tanks shall be of welded construction. Interior surface of the tanks shall lined with replacable chlorobuty/bromobutyl rubber lining of minimum 5 mm thickness and the outside surface shall be coated with paint as approved by the Employer. The Tanks shall be provided with drain, manholes, over flow & inlet level control valves etc. Coarse-screen(s) at suction-side of these pumps shall be provided.			
11.00.00	AGITATORS			
11.01.00	Agitators shall be supplied in tanks and vessels to prevent caking and settlement of particles out of the slurry, e.g. in the absorber vessel, limestone mill recycle tanks, limestone slurry tank, Auxiliary Absorbent tank, and sumps etc.			
11.02.00	All agitators shall be designed for continuous operation unless otherwise specified.			
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	 PAGE 31 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	Horizontal agitators shall be used for Absorber. Vertical agitators can also be used for Absorber, if it is only the standard & proven practice of the Contractor for the offered Absorber design. In other vessels and tanks vertical agitators are also acceptable if they are of proven make and the Bidders standard practice which can be proven by means of suitable references. The design of the agitators shall be of proven type. 11.03.00 Standard type agitators with suitable characteristics shall be used wherever practical. The agitators shall be complete with motor, gearbox, agitator shaft, coupling, safety guards, mechanical seal (for side entry agitators), impeller, support legs, agitator mounting flange including bolts nuts and gasket etc. 11.04.00 All agitator parts and accessories in contact with the stirred fluid shall be constructed of materials specifically designed for the conditions and nature of the stirred fluid and be resistant to erosion and corrosion. 11.05.00 The material for the shaft (which is continuously in contact with slurry) and agitator blades of the Absorber Agitators shall be made with Alloy 926 or better material. For Agitators in other tanks, agitator blades shall be made with Alloy 926 or better material & shaft can be rubber lined. This does not release the Contractor of the responsibility for selecting the correct materials. 11.06.00 Each agitator and its associated equipment shall be arranged in such a manner as to permit easy access for operation, maintenance and agitator removal without interrupting plant operation. It shall be possible to remove the sealing devices of the Agitators of the absorber vessel without having to drain completely the absorber. 11.07.00 To prevent mechanical blocking load start-up after standstill of pumps, piping and agitators for slurries shall be applied with C-hose connection. 11.08.00 Lifting lugs and eyes and other special tackle shall be provided as necessary to permit easy handling of the agitators and their components. 11.09.00 Static and dynamic (as far as applicable) balancing of all agitators shall be carried out after assembly. 11.10.00 All agitator parts and components shall be designed and calculated for fatigue life, considering maximum bending loads, induced by fluctuating hydraulic forces and torsional loads, based on the installed motor power. For side entry agitators the alternating bending moment resulting from impeller and shaft weight has to be considered additionally. 11.11.00 All exposed moving parts shall be covered by guards. 11.12.00 Side entry agitator shall be flange mounted. 11.13.00 The shape of the impeller blades of side entry agitators shall be designed to avoid wear on the impellers which will affect the agitator performance as specified for a minimum period of 2 years of continuous operation under design conditions for the range of coal & limestone specified in the specification. In order to avoid excessive wear impeller tip speeds must not exceed 12 m/s. 11.14.00 Belt drives (if applied) shall be properly designed to provide a minimum lifetime of 2 years under design conditions	
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD)  PAGE 32 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
12.00.00	SLURRY LINES AND VALVES			
12.01.00	Slurry pipes shall be designed to keep the velocity above the settling velocity under all operating conditions. The contractor may provide a recirculation line with motorized isolation valve for the above purpose.			
12.02.00	All the pipes handling slurry shall be provided with replaceable rubber lining of proven quality. The Contractor can provide slurry pipes of size lower than 3" made up of FRP material (silicon carbide coating on slurry exposed surface) if it has previous experience of providing the same.			
12.03.00	The isolation valves provided in all the slurry lines shall be of knife gate type/butterfly type unless specifically mentioned. Motorized actuators shall be provided for valves requiring frequent operation as indicated in the relevant scheme.			
12.04.00	The valves shall be of proven type and the contractor shall submit a detailed valve schedule for employer's approval. Reference list for previous installations for similar application shall also be furnished to the employer.			
12.05.00	Bidder shall provide all necessary arrangements for purging & flushing of all the process pipelines, equipments etc.			
13.00.00	PROCESS WATER STORAGE TANKS & PUMPS			
13.01.00	Two (2) Process water Storage tanks (each tank catering to the requirements of all the units operating at Design Point) along with two numbers of 2x100 % Booster water pumps, if required, (Each pump catering to the process water requirements of all the units operating at Design Point) along with all necessary piping, valves, control & instrumentation to feed the clarified water shall be provided by the Contractor. Process water Storage level shall be automatically controlled at operating level by controlling the water flow from the makeup water from terminal point. The process water storage tank shall be designed to store 15 minutes of total maximum water required for the entire FGD process (including absorber system and mist eliminator washing system, limestone grinding and slurry preparation system and gypsum dewatering system, etc.) for the units operating at Design point. All the process water storage tanks shall be designed, fabricated, erected and tested in accordance with the IS:803, latest edition. Additional Corrosion allowance of 1.50 mm on the minimum tank shell thickness as calculated by IS:803, latest edition shall be provided by the bidder. Tanks shall be made from IS:2062 quality mild steel plates of tested quality. The tank shall receive water supplied (as identified in Subsection titled "Terminal points" in Part-A of Technical Specification) by Employer. The Tanks shall be provided with drain, manholes, over flow & inlet level control valves etc.			
13.02.00	2x100% Process Water Pumps shall be provided for each unit connected to each of the Process water Storage tanks along with all necessary piping, valves, control &			
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 33 OF 51



CLAUSE NO.	TECHNICAL REQUIREMENTS		
	instrumentation. Each pump catering to process water requirement of one unit. The capacity of the pumps shall be such that it shall meet the maximum process water requirement of each unit. A further 10% margin shall be provided over the above capacity for all the above pumps.		
13.03.00	2x100% Mist Eliminator Wash Water Pump for each unit connected to each of the Process water Storage tanks along with all necessary piping, valves, control & instrumentation shall be provided by the Contractor. Alternatively, Contractor can use process water pumps for mist eliminator washing if it is the standard & proven practice of the Contractor or its Technology Collaborator. Each pump shall cater to maximum mist washing requirement of one unit. The capacity of the pumps shall be such that the total capacity of working pumps is sufficient to meet the maximum wash water requirements of mist eliminators of the absorber. A further 10% margin shall be provided over the above capacity for all the above pumps.		
13.03.04	Two (2) clarified water Storage tanks along with two numbers of 2x100 % clarified Booster water pumps from terminal point shall be provided by the Contractor. The two tanks shall be interconnected with an isolation valve.		
13.03.05	2x100% clarified water Pumps connected to each of the clarified water Storage tanks for each dewatering stream. Each pump catering to clarified water requirement of each dewatering stream.		
13.03.06	The type of pumps shall be horizontal centrifugal type designed for continuous operation with semi open or closed impeller. Casing, Gland and Stuffing Box shall be of 2.5 Ni Cast Iron to IS:210 Grade FG 260 or equivalent. Impeller, Wearing rings (as applicable) shall be of Stainless Steel -316 grade and Shaft & Shaft sleeves shall be of SS-410 grade. Pump re-circulation line shall be provided for pumping system. Pumps shall be provided with accessories such as Y-type suction strainers, Coupling guard, drain plugs, vent valves etc.		
13.03.07	All the Process water tanks (Process water Storage tanks, Clarified water tank, Emergency water storage tanks etc.) shall be designed, fabricated, erected and tested in accordance with the IS:803, latest edition. Additional Corrosion allowance of 3mm on the minimum tank shell thickness as calculated by IS:803, latest edition shall be provided by the Contractor. Tanks shall be made from IS:2062 quality mild steel plates of tested quality. The tanks shall be of welded construction. Interior surface of the tanks shall lined with replacable chlorobuty/bromobutyl rubber lining of minimum 4 mm thickness or with vinly ester based flake glass lining of minimum 3 mm thickness and the outside surface shall be coated with paint as approved by the Employer. The Tanks shall be provided with drain, manholes, over flow & inlet level control valves etc.		
14.00.00	APPROACH and Handling Facilities	 	
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109/1A1-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 34 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
14.01.00	Proper approach shall be provided for access to all equipments during normal operation and maintenance. Unless otherwise specified, platforms, staircase and ladders shall follow the stipulations specified elsewhere in this specification.	
14.02.00	Equipments requiring monitoring during regular operation shall be approachable from the ground floor through staircase. Staircase with minimum width of 1200 mm shall be provided for approach to elevated structures at 5m height from the nearest platform. Below this height a vertical ladder with minimum clear width of 600 mm may also be acceptable.	
14.03.00	Platform with a minimum clear width of 1000 mm shall be provided all around the lowest absorber spray levels and mist eliminators. Similar platforms shall be provided at subsequent elevations if they are more than 3000 mm apart from each other. An adequately sized manhole with platform (min. 2 sq. m) shall be provided above each spray level. Ladders/staircase shall be provided for the access to the platform.	
14.04.00	The absorber slurry recirculation pumps, gypsum bleed pumps and limestone feed pumps shall be mounted on the ground level. Suitable approach and platforms shall be provided for all the valves required during regular operation.	
14.05.00	A 1500 mm space shall be provided around all pumps, except absorber recirculation pumps, where a 2000 mm space shall be provided.	
14.06.00	Platform with a minimum width of 1500 mm shall be provided all around the pulverizers and feeders. Approach along with suitable platforms shall be provided for ball loading hoppers.	
14.07.00	A 1000 mm wide platform with suitable approach shall be provided around each hydro-cyclone.	
14.08.00	A 2000 mm wide floor/platform shall be provided all around each belt filter.	
14.09.00	Contractor shall provide motorized hoists and trolleys for all items requiring maintenance and weighing 500 kg or more. All auxiliary structures, monorails, runway beams for all lifting tackles, hoists etc., are included in Contractor's scope of supply. Access ladders with suitable platform shall also be provided for approach to all motorized hoists/trolleys mounted on their runway beams for the maintenance of hoists/trolleys. Items weighing more than 50 kg and required to be replaced for maintenance shall be provided with manual hoists/trolleys with runway beams/supporting structure etc.	
14.10.00	The regular basement floor is not acceptable in FGD area. Further local Pits/trenches shall be avoided as far as possible.	
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2 PART-B SUB-SECTION-I-M1 (FGD) PAGE 35 OF 51		

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC	
14.11.00	Handling arrangement of milling system, Booster fans, Slurry recirculation pumps, oxidation blower, belt feeder system etc. complete with crane/monorail along with removal space for maintenance shall be provided by the Contractor.		
14.12.00	Approach for removal of equipment for maintenance shall be provided.		
14.13.00	All other safety requirements as per the Factories Act, National Electricity code shall be complied with while developing Layout.		
14.14.00	Cable trenches/slits, if unavoidable, shall be provided with adequate cushioning of sand and the same shall be covered with PCC.		
14.15.00	Each Equipment room shall be provided with alternate exits in case of fire/accidents as per requirements of Factories Act and Statutory bodies/insurance companies.		
14.16.00	Minimum Headroom (free height) under all floors, ducts, walkways and stairs shall be 2.50 M.		
14.17.00	Inter-connecting pipes/cables between various facilities of FGD plant shall be routed on the steel trestles to be provided by the Contractor. The clear head room for the same shall be minimum 8 M.		
15.00.00	ELEVATORS		
15.01.00	Elevators shall be designed based on following criteria : (i) Type of service One (1) no. Passenger cum goods elevator per Absorber & for Mill Building (ii) Design/construction/installation codes (a) Latest edition of IS:14665 (All parts) AND also meeting any additional requirements of IS:4666, IS:1860 and IS:3534. (b) Any other equivalent code, subject to Employer's approval. Load carrying capacity (iii) 1000 kg (minimum). (iv) Rated speed 1.0 m/s. (v) Total Travel As per FGD supplier's recommendations subject to Employer's approval.		
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 36 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनडीपीसी NTPC
	(vi) Number of floors to be served As per requirement and subject to Employer's approval (vii) Entrance As per requirement and subject to Employer's approval (viii) Entrance and platform size As per design/installation codes at (ii) above (ix) Drive/motor As per Electrical Specifications. (x) Method of control As per Electrical Specifications. (xi) Machine room and lift Shaft Pressurized dust proof or Airconditioned machine room as per the requirement of lift manufacturers. (xii) Position of machine room Directly above the lift shaft. (xiii) Power Supply As detailed in Electrical Specification	
15.02.00	Landing doors of the elevators shall have fire resistance of at least one hour. These doors shall also be smoke tight as far as possible.	
15.03.00	Construction of the elevators shall specifically meet all requirements of the codes indicated at Cl. 15.01.00 (ii) and shall have following additional features: (i) Flooring of Cabin : 6 mm thick Checkered Plate flooring. (ii) Design, Construction and finish of car & car door : Car inside enclosure including inner side of door shall be of stainless steel plate of grade SS:304 of bright finish. (iii) Car entrance and landing doors : As per BS:476 (Part 20 & 22) (iv) Door construction : Hollow metal construction from 16 guage thick steel sheet spray painted. (v) Signals : Car position informer in car both visual and audio, hall position indicator at all floors, telltale lights at all floors, battery operated alarm bell and emergency light with suitable battery, charger & controls.	
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD) PAGE 37 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	(vi) Type of Indicators : Soft touch keys and digital luminous display in car operating panel and on all floors landings. (All fixtures in stainless steel face plates).	
15.04.00	Technical requirements of Electrical items shall be as per details given in Electrical Sub-Section, Part-B.	
15.05.00	Provide sound reducing material below machines in machine room.	
15.06.00	Provide special corrosion resistant treatment on all elevator components. The protective treatment shall be subject to Employer's approval.	
15.07.00	Elevators shall have provisions to meet following operational requirements: (i) Selective collective, automatic operation with or without operator through illuminated push button station located inside the lift car. (ii) Power operated with automatic opening/closing car and landing doors. (iii) Two push buttons, one for upward movement and the other for downward movement at each intermediate landing, and one push button at each terminal landing shall be provided in order to call the car. (iv) Push buttons shall be fixed in the car for holding the doors open for any length of the time required.	
15.08.00	Fireman's switch shall be provided for each elevator.	
16.00.00	DUCT WORK AND DAMPERS :	
16.01.00	Duct Work	
16.01.01	Sizing Criteria :	
	1. Allowable velocities in the duct work. Maximum gas velocity shall be 15 m/sec at Design point condition.	
16.01.02	Loads for Duct and Structure Design The duct design shall take into account following loads all occurring together: 1. Wind loads as specified. 2. Dead weight including weight of insulation, lining, wash water and the vertical live load.	 
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD) PAGE 38 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS						
	एनटीपीसी NTPC 3. Ash load : All ducts to be designed for one tenth of duct full of ash. The ash density for the purpose of loading shall be at least 1300 kg/m³. 4. Expansion joint reaction. 5. Seismic Load 6. The following minimum load factors shall be applied to the design loads: Temperature (Deg.C) : 27 38 93 149 205 260 316 321 Load Factor : 1.00 1.02 1.12 1.1 1.25 1.29 1.34 1.4 9 2 <tr><td>16.01.03</td><td> Duct Design Pressure All flue gas ducts shall also be designed for ± 660 mm w.g., or maximum conceivable pressure of the relevant fans, whichever is higher at 67% of yield strength of material </td></tr> <tr><td>16.01.04</td><td> Duct Slope All ducts shall have a sufficient slope with respect to horizontal so that any chance of accumulation of ash particles or water in the duct can be avoided under all normal/abnormal operating conditions. The inlet duct shall be sloped towards the absorber. </td></tr> <tr><td>16.01.05</td><td> Type of duct construction: The duct shall be of rectangular cross-section and shall be of all welded construction. For rectangular ducts following requirements shall be complied with: a) Minimum 7 mm thick steel plates for gas ducts & Duct stiffening shall be by means of rolled sections of duct material. b) A corrosion allowance of 1.5 mm shall be considered for stress calculation for the flue gas ducting. c) Duct stiffening shall be by means of rolled sections. No internal stiffeners shall be used for ducts from Absorber outlet to chimney inlet. </td></tr>	16.01.03	Duct Design Pressure All flue gas ducts shall also be designed for ± 660 mm w.g., or maximum conceivable pressure of the relevant fans, whichever is higher at 67% of yield strength of material	16.01.04	Duct Slope All ducts shall have a sufficient slope with respect to horizontal so that any chance of accumulation of ash particles or water in the duct can be avoided under all normal/abnormal operating conditions. The inlet duct shall be sloped towards the absorber.	16.01.05	Type of duct construction: The duct shall be of rectangular cross-section and shall be of all welded construction. For rectangular ducts following requirements shall be complied with: a) Minimum 7 mm thick steel plates for gas ducts & Duct stiffening shall be by means of rolled sections of duct material. b) A corrosion allowance of 1.5 mm shall be considered for stress calculation for the flue gas ducting. c) Duct stiffening shall be by means of rolled sections. No internal stiffeners shall be used for ducts from Absorber outlet to chimney inlet.
16.01.03	Duct Design Pressure All flue gas ducts shall also be designed for ± 660 mm w.g., or maximum conceivable pressure of the relevant fans, whichever is higher at 67% of yield strength of material						
16.01.04	Duct Slope All ducts shall have a sufficient slope with respect to horizontal so that any chance of accumulation of ash particles or water in the duct can be avoided under all normal/abnormal operating conditions. The inlet duct shall be sloped towards the absorber.						
16.01.05	Type of duct construction: The duct shall be of rectangular cross-section and shall be of all welded construction. For rectangular ducts following requirements shall be complied with: a) Minimum 7 mm thick steel plates for gas ducts & Duct stiffening shall be by means of rolled sections of duct material. b) A corrosion allowance of 1.5 mm shall be considered for stress calculation for the flue gas ducting. c) Duct stiffening shall be by means of rolled sections. No internal stiffeners shall be used for ducts from Absorber outlet to chimney inlet.						

GENERATING UNIT

LOT-1A PROJECTS
FLUE GAS DESULPHURISATION (FGD)
SYSTEM PACKAGE

TECHNICAL SPECIFICATION
SECTION-VI
BID DOCUMENT NO : CS-0011-109/1A/2

PART-B
SUB-SECTION-I-M1
(EGD)

PAGE 39 OF 51



LOT-1A PROJECTS
FLUE GAS DESULPHURISATION (FGD)
SYSTEM PACKAGE

TECHNICAL SPECIFICATION
SECTION-VI
BID DOCUMENT NO.: CS-0011-109(1A)-2

PART-B
SUB-SECTION-I-M1
(FGD)

PAGE 39 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS		
16.01.06	Insulation & Lagging a) Thermal insulation shall be applied to all air/gas ducts to comply with the requirements of as specified at clause no 18.00.00 of this chapter. b) Acoustic insulation shall be used, if required, in gas ducts to restrict the noise level to specified values.		
16.01.07	Specific Requirements a) The stiffeners provided on the ducts walls shall be of such a design and layout that no rainwater can accumulate on the duct surfaces. b) The flanges at the bolted joints shall have adequate stiffeners to avoid damages to the flanges. c) All necessary wall boxes and floor collars shall be provided where the ductwork pass through walls, floor and roof. d) The floor collars shall be fitted with a high combing to prevent water and dust falling through the hole. e) The ductwork shall be fitted with a steel hood to cover the opening. f) Weatherproof flashing shall also be provided wherever necessary. g) The configuration and design of ducts shall be coordinated with the pulveriser parts removal requirement. h) Air and gas ducts shall not counter internal bracings, which cause excessive pressure drop. i) Duct plates shall be designed for one-way beam action over stiffeners and considered fully continuous over all supports. j) Bidder to ensure proper draining facilities for the complete system including proper drainage of acidic fluids from the ducts so as to avoid any accumulation of acidic fluids. k) The deflection of the plate, assumed continuous, shall be less than one-half the plate thickness.		
16.01.08	Duct Work Structure a) Ductwork sections between expansion joints shall be investigated with regard to their ability to transmit loads to supports. Care shall be exercised to identify uplift condition.		
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD)	 PAGE 40 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	b) Internal stiffeners: (i) Duct shape shall be maintained by providing internal stiffening elements at or near supports. However, these internal stiffeners shall be used, if and only if, it is not possible to provide external stiffeners. (ii) Internal stiffening elements shall consist of trusses, preferably comprised of extra-strong steel pipes (min. dia. 76.2 mm) acting in conjunction with external stiffeners. Such internal stiffeners for the flue gas duct between boiler and ESP shall be provided with erosion protection shields. (iii) The number of internal trusses shall be limited to the minimum required for structural integrity and shaped so as to offer least resistance to gas flow and to minimize the accumulation of fly ash in the bottom of duct. (iv) Conceptual data of internal stiffeners of the ducting shall be furnished along with the offer. (v) All the detailed design data shall be furnished to the Employer before the duct support column foundation data submission. c) Corner angles shall be used on all inside corners of all ducts to provide adequate continuity. d) Inside welds of corner angles to duct plate shall be continuous and seal welded. Where inside surface of ducts will be coated, welds shall be full throat. e) Field welding and all connections of bracing (stiffening elements) to stiffeners shall be well designed in order to develop full strength of the members. The gusset plates shall be of 10 mm minimum thickness. f) The duct, plates, trusses, stiffeners, bracings and ductwork shall be designed as structures in accordance with relevant Indian Standards. g) All openings in ducts shall be reinforced for all design loads. h) Ductwork supports may be hangers or sliding bearing, guides and anchorages. A coefficient of sliding friction of 10% can be used with self-lubricated plates such as "LUBRITE" or "MECHANITE", a coefficient of sliding friction of not less than 35% shall be used for steel-on-steel contact. The allowable bearing stress for self-lubricated plates shall be 70 Kg/sq.cm.	
	LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2 PART-B SUB-SECTION-I-M1 (FGD) PAGE 41 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS		एन टी पी सी NTPC
16.01.09	Fabrication Requirements a) Fabrication shall be as per IS specification for Design, fabrication and erection of 'Structural Steel for Building. b) Welding shall be in accordance with Section IX of ASME code. c) Ducts shall be strength welded and seal welded to produce a gas tight duct. Alignment holes shall be provided in mating flange sections. d) Ducting shall be detailed and fabricated in a few pieces as practical, taking into account, shipping and erection considerations. e) Materials improperly detailed or fabricated necessitating extra work during erection on field, shall be the responsibility of the Contractor.		
17.00.00	THERMAL INSULATION AND CLADDING		
17.01.00	Thermal Insulation along with aluminum cladding shall be provided for all the equipments/surfaces having skin temperature more than 60degree Celsius. The specification of the insulation including type, density, thickness, heat conductivity and finish shall be designed based on criteria specified below. The insulation thickness shall be designed based on following criteria.		
	Criteria	Design Conditions	
	(i) Ambient Temperature	45°C	
	(ii) Surface wind velocity	0.25 m/sec.	
	(iii) Emissivity of Aluminium	0.2	
	(iv) Cladding surface temperature	60°C (max.)	
	(v) Thermal conductivity of insulation material	Not less than the Maximum values as per IS:8183	
	(vi) Pipe/Equipment wall temperature design temperature	Maximum	fluid
	(vii) Overall heat transfer coefficient and insulation thickness	To be calculated as per ASTM C 680-89	
	However, the minimum insulation thickness, however, shall not be less than 75 mm		
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	भारत भारी बिजली शक्ति लिमिटेड Power Sector Marketing PART-B SUB-SECTION-I-M1 (FGD) भारत भारी बिजली शक्ति लिमिटेड NTPC PAGE 42 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS एनटीपीसी NTPC												
17.02.00	Material and application of insulation material, protective cladding, wire mesh etc. shall be conforming to latest edition of following codes: (a) IS:8183 (b) IS:3677 (c) IS:3144 (d) IS: 14164 (e) IS:280 (f) ASTM-B 209												
17.03.00	Insulation material for all equipments, ducting, etc. shall conform to following requirements: <table border="0"> <thead> <tr> <th>Parameters</th><th>Requirement</th></tr> </thead> <tbody> <tr> <td>(i) Material</td><td> (a) Lightly resin bonded mineral wool of best grade conforming to IS:8183. (Hand made mattresses is not acceptable). Material shall be rock wool only. Slag wool or slag wool inclusion shall not be accepted. (b) Lightly resin bonded glass wool mattress, having density 64 Kg/m³ (min.), self stitched in shop can also be accepted for temperature less than 400°C. </td></tr> <tr> <td>(ii) Bulk density of lightly resin bonded mineral rock wool mattresses</td><td> (a) For use upto 400°C - 100 Kg/m³ (b) For use above 400°C - 150 Kg/m³ </td></tr> <tr> <td>(iii) Physical requirements -</td><td></td></tr> <tr> <td colspan="2">Following shall be met by testing as per relevant clauses of IS:3144.</td></tr> <tr> <td>(a) Shot content</td><td>5% by weight (maxm.), size of any shot not to exceed 5 mm in diameter</td></tr> </tbody> </table>	Parameters	Requirement	(i) Material	(a) Lightly resin bonded mineral wool of best grade conforming to IS:8183. (Hand made mattresses is not acceptable). Material shall be rock wool only. Slag wool or slag wool inclusion shall not be accepted. (b) Lightly resin bonded glass wool mattress, having density 64 Kg/m³ (min.), self stitched in shop can also be accepted for temperature less than 400°C.	(ii) Bulk density of lightly resin bonded mineral rock wool mattresses	(a) For use upto 400°C - 100 Kg/m³ (b) For use above 400°C - 150 Kg/m³	(iii) Physical requirements -		Following shall be met by testing as per relevant clauses of IS:3144.		(a) Shot content	5% by weight (maxm.), size of any shot not to exceed 5 mm in diameter
Parameters	Requirement												
(i) Material	(a) Lightly resin bonded mineral wool of best grade conforming to IS:8183. (Hand made mattresses is not acceptable). Material shall be rock wool only. Slag wool or slag wool inclusion shall not be accepted. (b) Lightly resin bonded glass wool mattress, having density 64 Kg/m³ (min.), self stitched in shop can also be accepted for temperature less than 400°C.												
(ii) Bulk density of lightly resin bonded mineral rock wool mattresses	(a) For use upto 400°C - 100 Kg/m³ (b) For use above 400°C - 150 Kg/m³												
(iii) Physical requirements -													
Following shall be met by testing as per relevant clauses of IS:3144.													
(a) Shot content	5% by weight (maxm.), size of any shot not to exceed 5 mm in diameter												



LOT-1A PROJECTS
FLUE GAS DESULPHURISATION (FGD)
SYSTEM PACKAGE

TECHNICAL SPECIFICATION
SECTION-VI
BID DOCUMENT NO.: CS-0011-109(1A)-2

PART-B
SUB-SECTION-I-M1
(FGD)

PAGE 43 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC
	(b) Bulk density To comply with 16.03.00(i) & (ii) above. (c) Weight gain by moisture absorption 2% (maxm.) (d) Sulphur Content Not exceeding 0.6% (e) Alkalinity as percentage of Na₂O Not exceeding 0.6% (f) Maximum oil content Not exceeding 0.3% by weight (g) Total carbon content Not exceeding 0.3% by weight (h) Settlement Nil (When tested as per Cl. 21.1 & 21.2 of IS:3144) (i) Handability Fully handable, without any lump formation and disintegration of material (k) Loss of weight after combustibility test Not exceeding 5% by weight	
17.04.00	The Insulation mattress shall be rated incombustible when tested by the method prescribed in clause 15 of IS:3144 and shall meet the requirement of the Mercantile Marine department, Lloyd's Register of shipping, underwriter, fire hazards codes and other International standards.	
17.05.00	In addition to requirements as mentioned above, insulation material (and protective covering) shall: (a) Be fresh, incombustible, rust proof, non hygroscopic, (b) Be capable of withstanding continuously and without deterioration the maximum temperature to which they will be subjected. (c) Not react chemically, either to itself or with other components. (d) Not sustain any fungi, or vermin and must not pose health hazards.	
18.06.00	The Mineral wool shall:	
LOT-IA PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
	(a) Pass standard combustibility test both immediately after application and after subjected to maximum operating temperature for not less than 100 hrs. (b) Not suffer permanent deterioration as a result of contact with moisture due to condensation and shall be free from objectionable odor. (c) Not cause corrosion of the surface being insulated or of cladding on it under normal site conditions. (d) Not suffer any quality deterioration under specified service conditions (both cold/hot face temp.) of use.			
17.07.00	The use of insulation of finishing materials containing asbestos in any form is not permitted.			
17.08.00	Insulation mattress/section shall be supplied in thickness of 25,40,50 and 75 mm. Insulation of higher thickness shall be made up in multiple layers using mattress/slabs of thickness specified above. However, if the required thickness is such that by using above mattress/slabs the calculated thickness is not achieved, the mattress/slabs in increment of 5 mm shall be acceptable for outer layers. The min. thickness however, shall not be less than 25 mm and number of layers shall be minimum and innermost layer shall be thickest.			
17.09.00	Sheathing Material Sheathing material for all insulated surfaces, equipments, piping etc. confirming to ASTM B-209-1060 temper H-14 or IS:737 Gr 19000/H2, shall be provided. The thickness of aluminium sheathing to be used shall be 22 SWG (0.71mm).			
17.10.00	Binding and lacing wires shall be 20 SWG Galvanised Steel wire			
17.11.00	All Straps and bands shall be Galvanized Steel. Bands shall be 20 mm wide and 0.6 mm thick. For securing Aluminum sheathing material, stainless steel or anodized aluminum bands shall be used.			
17.11.01	Screws shall be of galvanized steel, check headed, self tapping type. Above 400 degree Celsius temperature, screws shall be stainless steel.			
17.12.00	Hexagonal wire mesh netting shall be 10-13 mm aperture and atleast 0.56mm diameter conforming to following Galvanized Steel wire.			
17.12.01	Non metallic components like 3 mm thick mill board, aluminum pigment sealant, white glass cloth, insulating cement, neoprene washer shall be provided.			
17.13.00	Application of Insulation			
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 45 OF 51	

CLAUSE NO.	TECHNICAL REQUIREMENTS		
17.13.01	General (a) All surfaces to be insulated shall be cleaned of all foreign materials such as dirt, grease, rust etc. and shall be dry before the application of insulation. (b) Before applying the insulation the contractor shall check that all instrument tapping, clamps, lugs and other connections on the surface to be insulated have been properly installed as per the relevant erection drawing. (c) All flanged joints shall be insulated only after the final tightening and testing. (d) The insulation shall be applied to all surfaces when they are at ambient temp. Ample provision shall be made for the maximum possible thermal movement and the insulation shall be applied so as to avoid breaking/telescoping due to alternate periods of expansion and contraction. (e) All cracks voids and depressions shall be filled with finishing cement, suitable for the equipment operating temp. so as to form a smooth base for the application of cladding.		
17.13.02	All the refractory and insulation materials required for complete field application of insulation, cladding etc. covered under these documents and specifications shall be furnished with the equipment. They shall conform to the requirements of the various relevant ISI standards or other approved equivalents. All items such as insulating cement, sealing material, insulation material, screws, washers, etc., needed to complete the work in the course of the application of insulation and refractory shall be furnished. All insulating materials shall be chemically inert in both the dry and wet state and shall withstand the full working temperature conditions to which they are exposed without any deterioration. The gas ducts shall be insulated with mineral wool block or mineral wool blanket and all other equipment operating at elevated temp. not enclosed in the boiler casing shall be insulated with calcium silicate blocks, mineral wool blocks or mineral wool blanket insulation.		
17.13.03	Application on Piping (a) All vertical pipes shall be provided with the suitable insulation supports to prevent collapsing/crushing of insulation due to its self weight. Support rings shall be provided on all vertical piping with a difference in elevation of 4 meter or above, and there shall not be more than 3 m straight length between support rings. (b) Longitudinal joints of insulation mattress sections of horizontal piping shall be on the bottom or at the sides of the pipe.	 	
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 46 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS			
	(c) When more than one layer of insulation mattress/section is required on piping the circumferential joints on adjacent layers shall be staggered by at least 150 mm and longitudinal joints shall be staggered by at least 50 mm. (d) The mattress type insulation shall be formed to fit the pipe and applied with the mattress edges drawn together at the longitudinal joints and secured by lacing wire. Pipe section insulation shall be fitted on pipe using binding wires. (e) Where insulation is applied in two or more layers each layer of mattress shall be backed with hexagonal wire mesh. For the first layer of insulation and in case of single layer insulation, hexagonal wire mesh shall be provided on both the surface of the mattress. For pipe sections, the sections shall be held in place by binding wires without any wire mesh. (f) The ends of all wire loops shall be firmly twisted together with pliers, bent over and carefully pressed into the surface of the insulation. Any gap in the insulation shall be filled with loose mineral wool or finishing cement. (g) Insulation mattress/section ends shall be terminated at a sufficient distance from the flanges to facilitate removal of bolts. (h) The insulation shall be held in place by fastening over with binding wire for insulation surface with diameter upto and including 550 mm and with metal bends for insulation surfaces with diameter over 550 mm. The fastening shall be done at intervals of 250 mm except where specified otherwise. The ends of the binding wires shall be hooked and embedded in the insulation. The straps shall be mechanically stretched and fastened with metallic clamping seals of the same materials as the strap. (i) Insulation for application on bends and elbows shall be cut into mitred segments, sufficiently short to form a reasonably smooth internal surface. After the application of insulation material place, insulating cement shall be applied as required to obtain a smooth surface. (j) Weather hoods shall be provided for insulated piping passing through floors/walls. (k) All pipe attachments coming on horizontal pipes, inclined pipes and bends shall be insulated along with pipe such that there will be no insulation applied to hanger rod and the component connecting hanger rod to pipe attachment. All pipe attachments exposed to weather shall be provided with weather proof covering. (l) Upstream of all drain lines and the lines connected to steam traps, shall be insulated upto and including first isolating valve for heat conservation. Rest			
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 47 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS		
17.13.04	of such lines such as downstream of the drain valves, traps etc. and other lines such as safety valve discharges, vents, etc. shall be insulated for personnel protection. Application on Valves and Fittings (a) All valves fittings and specialties shall be insulated with the same type and thickness of insulation as specified for the connected piping with the special provisions and or exceptions as given below. (b) All valves and flanges shall be provided with removable box type of insulation covered with box fabricated from aluminium sheets of thickness same as the connected pipe cladding. Adjoining pipe insulation shall be bevelled back to permit removal bolts and nuts or bands. The portion of the valve which can not be covered by box type insulation shall be filled by loose insulating material of packing density at least equal to that of the insulating material of adjoining pipe. The insulation for valves/flanges shall be applied after the finishing has been applied over the connected piping. The cladding shall be applied in such a manner that the bonnet flange can be exposed easily without disturbing the complete insulation and cladding. (c) Flanges on lines having temperature upto and including 150 deg.C shall not be insulated. (d) Union shall not be insulated. (e) Expansion joints, metallic or rubber, shall not be insulated unless otherwise specifically indicated. (f) Safety valves shall be insulated.		
17.14.00	While applying mineral wool blanket insulation: (a) Provide expended metal or hexagonal wire mesh on both sides for single layer mattress and on first layer in case of multilayer insulation. Subsequent layers of multilayer insulation to have only one side wire netting. (b) The edges of adjacent blankets to be leased together, by appropriate lacing wire as per Clause 16.08.00. (c) Any gap between joints between insulation layers shall be filled by loose mineral wool confirming to IS:3677. (d) All insulation to be secured by 1.63 mm dia wire netting over blankets with ends of wire tightly twisted, and pressed in to insulation surface		
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 48 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
17.15.00	(e) Impelling pins shall be placed on centers not exceeding 300 mm. Flue Gas ducts with external stiffeners shall have first layer of insulation between the stiffeners and a second layer of insulation over stiffeners so that stiffeners are also insulated and a level surface is achieved. Other requirements are same as given in Clause 18.09.00.			
17.16.00	Application of Metal Cladding All insulated surfaces of the FGD shall be provided with metal cladding in accordance with the following requirements. (a) All insulation procedure of metal cladding shall have prior approval of the Owner. (b) All insulated surfaces of FGD shall be covered with aluminium cladding. (c) Cladding for FGD components are to be finished with plain aluminium sheeting of thickness not less than the values specified. Wherever an inner casing plate is necessary to effect a gas tight enclosure, the plate shall be of mild steel of required thickness, but not less than four (4) mm suitably stiffened and supported. (d) Cladding on straight surfaces shall be finished with aluminium sheeting of at least 20 SWG thicknesses suitably pressed along diagonals to form diamond shape or otherwise formed. (e) Cladding for insulated circular surfaces will be constructed from aluminium sheets of thickness not less than 20 SWG. (f) Weather proof flashings shall be installed where the panels intersect with columns and at other similar joints.			
17.17.00	Application All metal cladding shall be fabricated and installed to ensure a neat appearance and no open ended sections of cladding shall be left uncovered. The following provisions shall also be complied with: (a) All closures, flashings and seals required shall be provided and installed. (b) An asphalt and craft paper moisture barrier shall be provided to the aluminium cladding for all out door applications. Such moisture barriers shall be fixed to the inner surface of the cladding or shall be cemented to the outside surface of the insulation before application of cladding.			
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE		TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	PART-B SUB-SECTION-I-M1 (FGD)	PAGE 49 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	(c) All the used in the out door cladding shall be provided with Neoprene washers. (d) All openings and joints in outdoor cladding for piping connections, supports or access shall be suitably flashed and weather-proofed. Where such flashings or weather-proofing can not effectively control the entry of moisture, then such openings and joints shall be weather-proofed by application of aluminium pigmented sealer. (e) Cladding on the top surfaces of the FGD, duct work and equipment shall be suitably reinforced to prevent damage by personnel walking thereon.	
17.18.00	Protection of Equipment during insulation application All equipment and structure shall be suitably protected from damage while applying insulation. After completion all equipment and structures shall be thoroughly cleaned of insulating materials which might have fallen on them.	
18.00.00	TYPE TEST	
18.01.00	Full scale type tests using actual equipment shall be conducted by the Contractor for the equipment mentioned in the subsequent clauses below:	
18.01.01	Full range and full scale performance testing shall be conducted at shop on one number each of the following Fans as per BS 848, Part-1: (a) Booster Fan The performance testing at shop shall be conducted using actual fans	
18.01.02	Leak tightness testing of dampers for each type and size of damper at shop to demonstrate the guaranteed gas tightness efficiency (on flow). The minimum guaranteed gas tightness efficiency of dampers shall not be less than that indicated in clause no. 3.03.08 of this Sub-Section.	
18.02.00	The Bidder shall indicate the charges for each of these type tests separately in the relevant price schedule of Bid Proposal Sheet (BPS) and the same shall be considered for the evaluation of the Bids. The type test charges shall be paid only for the test(s) actually conducted successfully under this contract and upon certification by the Employer's Engineer.	
18.03.00	The type tests shall be carried out in presence of the Employer's representative. Contractor shall inform the Employer about his readiness for conducting the type test and issue such notice to the Employer 30 days in advance, along with schedule of the type tests. The Contractor shall obtain the Employer's approval for the type test procedure before notifying the Employer about his readiness for conducting the type	
LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD)  PAGE 50 OF 51

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
18.04.00	test. The type test procedure shall clearly specify the test set-up, instruments to be used, procedure, acceptance norms, recording of different parameters, interval of recording, precautions to be taken etc. for the type test(s) to be carried out. Irrespective of the requirement of conducting the type tests under this contract, The Contractor shall submit the reports of the type tests carried out for the equipments listed above in clause no. 18.01.00 and These reports should be for the tests conducted on the equipment for the model / type / size / rating to those proposed to be supplied under this contract and the test(s) should have been either be conducted at an test facility/shop/independent laboratory or should have been witnessed by a client. The Employer reserves the right to waive conducting of any or all of the specified type tests under this contract, in which case the type test charges shall not be payable for the type tests waived by the Employer.			
18.05.00	All acceptance and routine tests as per the specification and relevant standards shall be carried out. Charges for these shall be deemed to be included in the equipment price.			
 LOT-1A PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE	TECHNICAL SPECIFICATION SECTION-VI BID DOCUMENT NO.: CS-0011-109(1A)-2	 PART-B SUB-SECTION-I-M1 (FGD)	PAGE 51 OF 51	