



ISG-Bengaluru

1 X 250 MW NSPCL Rourkela PP-II Expansion Project
Technical Enquiry Specification of Ash Handling System Main Package

Addendum-02 to Specification No.
IS-4-ES- 708-300-M001

Addendum-02 to Specification No. IS-4-ES- 708-300-M001

1 X 250 MW NSPCL Rourkela PP-II Expansion Project
Technical Enquiry Specification of Ash Handling System Main Package

BHARATH HEAVY ELECTRICALS LTD
INDUSTRIAL SYSTEMS GROUP
Bangalore

	Prepared By	Checked by	Approved by
Mechanical	Ragavan S	Amit Gupta	Tirupati Rao R



ISG-Bengaluru

1 X 250 MW NSPCL Rourkela PP-II Expansion Project
Technical Enquiry Specification of Ash Handling System Main Package

Addendum-02 to Specification No.
IS-4-ES- 708-300-M001

Sl.No	Reference Document/ Page/ Clause/Sl. No	Existing	Revised as
1.	Addendum-01 to specification IS-4-ES- 708-300-M001 Page 1 of 5 Sl. No. 5	Clause 4.2 Sl. No B.2 ECONOMIZER BYPASS HOPPER ASH REMOVAL SYSTEM	Bidder shall quote optional price for items mentioned in Sl. No. B.2 (9 to 16) of clause 4.2 for effective evacuation of ash from Economizer-bypass hoppers to Bottom ash hopper
2.	Specification no. IS-4-ES- 708-300-M001 Page 15 of 40 Clause 4.4 Sl. No D.2	Eco to SCR hopper (Eco-SCR) Ash Removal System	Bidder shall quote for optional price for items mentioned in Sl. No. D.2 (11 to 21) of Clause 4.4 for effective evacuation of ash from ash from Eco-SCR hoppers to IA silo.
3.	IS-4-ES- 708-300-M001 Page 17 of 40 Clause 4.4.12.1	--	Supply of one set of Slurrification system (Capacity 90 TPH on dry fly ash basis) below each IA silo upto Ash slurry sump including adopters, knife gate valves, spool pieces, wetting unit, slurry pipes, water piping and valves, fittings etc.-Quantity 1 Lot Bidder shall quote optional price for the above.