| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | एनदेवीसी NTPC | | |
|---------------|------------------------|-------------------------|--|------------------------------|------------------|--------------------------------|--------------------|
| | 7 | Accuracy | ±1% of span | ± 1% of spar | <u> </u> | ± 2% | |
| | 8 | Scale | Linear, 270° arc graduated in metric units | Linear, 270 graduated in | | Linear verti | cal |
| | 9 | Range selection | Shall cover 125% of max. operating press | Shall cover of max. ope temp | erating | Shall of Operating I | over max. evel. |
| | 10 | Over range | 125% of FSD | 125% of FSD |) | - | |
| | 11 | Housing | Weather and dust proof as per IP-55 | Weather and proof as per | | CS/304 SS | leak proof |
| | 12 | Zero/span adjustment | Provided | Provided | | | |
| | 13 | Identification | Engraved with servi | ice legend or la | aminate | ed phenolic n | ame plate |
| | 14 | Accessories | Blow out disc, siphon, snubber, pulsation dampener, chemical seal (if required by process) gauge isolation valve | SS Thermowel | I | for transpar and drain | per CS/Alloy |
| | Note | s:- | | | | | |
| | | | auges will be provious and feed water servi | | ations | involving ste | am and water |
| | | | s shall not be more mm overlapping sha | | | e vessel is h | nigher, multiple |
| | seals entire | shall be provide | uids are corrosive, v d. Parts below the d ne diaphragm shall b | diaphragm sha | all be re | emovable for | cleaning. The |
| | | | | | | | |
| FLUE GAS DESI | JLPHURIS | , , | TECHNICAL SPECIFI SECTION-VI, PAR BID DOCUMENT NO.: CS | ₹Т-В | MEAS | TION-III-C2 URING IMENTS | PAGE 13 OF 34 |

| CLAUSE NO. | | TECHNICAL REQUIREMENTS | | | | | |
|------------|---|--|---|---|--|--|--|
| 5.00.00 | PROCESS ACTI | JATED SWITCHES | | | | | |
| | FEATURES | ESSENTIA | L/MINIMUM RE | EQUIREMENTS | | | |
| | | Pressure/ Draft Switches/ DP Switches | Temperature switches | Level switches | | | |
| | Sensing Element | Piston actuated for high pressure and diaphragm or bellows for low pr./ vacuum | Vapor pressure sensing, liquid filled bellow type with SS bulb and capillary (5 m minimum, to suit application) | Capacitance types, float type, conductivity type, RF type, Ultrasonic type as per suitability to the application. | | | |
| | Material | 316 SS | Bulb 316 SS/ capillary 304 SS | 316 SS | | | |
| | End connection | ½ inch NPT (F) | ½ inch NPT (F) | Manufacturer standard | | | |
| | Over range/ proof pressure | 150% of maximum operating pr. | - | 150% of maximum operating pr. | | | |
| | Repeatability | +/- 0.5% of full range | | | | | |
| | No. of contacts 2 No.+2NC. SPDT snap action dry contact | | | | | | |
| | Rating of contacts | 60 V DC, 6 VA (or more if required by DDCMIS) | | | | | |
| | Elect. Connection | Plug in socket. | | | | | |
| | Set point adjustment | Provided over full range. | | | | | |
| | Dead band adjustment | Adjustable/ fixed as p | er requirement o | of application. | | | |
| | Enclosure | Weather and dust pro | oof as per IP-55, | metallic housing. | | | |
| | Accessories | Siphon, snubber, chemical seal, pulsation dampeners as required by process | of All mounting accessories | | | | |
| | Mounting | Suitable for enclosure/ rack mounting or direct mounting | Suitable for rac mounting direct mounting | or | | | |
| | | | | | | | |
| | JLPHURISATION (FGD) | TECHNICAL SP SECTION-V BID DOCUMENT N | | SUB-SECTION-III-C2 MEASURING PAGE 14 OF 34 INSTRUMENTS | | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | एनदीपीसी NTPC | |
|---------------|--|---|--|---------------------------------|------------------|--|
| | Power Supply (wherever required) | As pe | r Contractor's Standard practice. | | | |
| | Notes :- | | | | | |
| | 1) Where diaphrag | 1) Where the process fluids are corrosive, viscous, solid bearing or slurry type, diaphragm seals shall be provided. Parts below the diaphragm shall be removable for cleaning. The entire volume above the diaphragm shall be completely filled with an inert liquid suitable for the application. | | | | |
| | sensor r | nateriaĺ | oressure switches for very low p other than SS316 in case of any ard product of the manufacture fo | technical limitation a | and the offered | |
| | | | an be upto + <i>i-</i> 1% of full range ir v pressure/DP range. | n case of switches v | vith diaphragm | |
| | be as p | er syst | ns of switches for air conditioning em manufacturer's standards. T orting documents for establishing | he manufacturer sh | nall submit the | |
| 6.00.00 | SOLENOID VAL | VES | | | | |
| | Solenoid valves s | hall fulf | īll the following requirements: - | | | |
| | a) Type 2/3/4 way SS 316/ forged brass (depending on the application subject to Employer's approval during detailed engg.) | | | | | |
| | b) Power su | ipply 24 | V DC. | | | |
| | c) Plug in co | onnecto | r connection. | | | |
| | d) Insulation | n : Clas | s "H" | | | |
| 7.00.00 | Limit switches | | | | | |
| | Contact ratin | g shall | be silver plated with high conduct be sufficient to meet the requi minimum of 60V, 6VA rating. Pro | irement of Fire alarr | m Control | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| FLUE GAS DESU | JLPHURISATION (FGD) | | TECHNICAL SPECIFICATION SECTION-VI, PART-B | SUB-SECTION-III-C2 MEASURING | PAGE 15 OF 34 | |

BID DOCUMENT NO.: CS-0011-109(1)-2

SYSTEM PACKAGE

INSTRUMENTS

HUMIDITY SENSOR

Sensor : Capacitance type

Accuracy : +/-3% R.H

Range : 0-100% R.H

Output : 4-20 ma

Time constant : 2 mins.

Output from the sensor is to be connected to respective control system. Contractor can also provide combined instrument for measurement of humidity and temperature subject to Employer's approval during detailed engineering. In all such cases, 4-20 ma outputs, each for temperature and humidity measurements are to be provided.

TEMPERATURE / HUMIDITY INDICATOR

Sensor : RTD for(Pt 100) for temperature

: Capacitance Type for Humidity (specs for humidity and temperature shall

be as mentioned above)

Display : Combined enclosure with two three digit seven segments LED display

with decimal point after two digits. LED height shall be 4 inches, clearly

legible from a distance of at least 10 meters.

Range : 0-60 Deg C for temperature.

: 0-95.0 % for Relative Humidity.

Accuracy : Better than +/_0.5 % for Temperature

: Better than +/_2.5 % for Relative Humidity

Mounting : Table Top/ wall mounting.

Power supply

: 240 V AC, 50 Hz.

Output : 4-20 mA signal each for temperature.

One Set of output signal is to be connected to respective control system. Apart from displaying the temperature/humidity values on indicator.

| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | |
|--------------------|---|--|--|--|--|
| 1.00.00 | GENERAL: | | | | |
| 1.01.00 | Actuators shall be designed for valve operation to ensure proper function in accordance with specifications given below and complying to EN15714-2 or equivalent. All standards, specifications and codes of practice referred to herein shall be the latest editions including all applicable official amendments and revisions. | | | | |
| 1.02.00 | This sub-section of specification is applicable for following types of electric actuators: | | | | |
| 1.02.01 | Modulating duty electric actuators: | | | | |
| | These shall be provided as per standard practice of OEM of equipment, meeting other requirements of specifications. For specifications of Blade pitch actuators, refer clause no. 5.00.00 of this chapter. | | | | |
| 1.02.02 | Electric actuators for valves/ dampers/ gates (other than covered in 1.02.01): | | | | |
| | These actuators shall be Non-Intrusive type electric actuators. The interface of these actuators with DDCMIS shall be of two types viz. with Hardwired interface and with Fieldbus interface. The common requirements of both these type of actuators are specified at clause 2.00.00, specific requirements of Non-Intrusive hardwired actuators are specified at clause 3.00.00 and specific requirements of Non-Intrusive fieldbus actuators are specified at clause 4.00.00. The applications where these two types of actuators are to be provided is specified in Part-A of Technical Specifications. | | | | |
| 2.00.00 | COMMON REQUIREMENTS FOR NON INTRUSIVE ELECTRIC ACTUATORS | | | | |
| 2.01.00 | TYPE: | | | | |
| 2.01.01 | The actuators shall have integral starters with built in SPP (Single Phasing Preventer). 415 V, 3 phase 3 wire power supply shall be given to the actuator from switch board as applicable through a switch fuse unit. Control voltage of the motor starter shall be 110 V AC / 24 V DC, derived suitably from 415V power supply. | | | | |
| 2.01.02 2.02.00 | The actuators shall be Non- Intrusive electric actuator. All actuator settings including torque, limit shall be possible without opening the actuator cover and LCD indication shall be available integral to actuator body. RATING: | | | | |
| | (a) Supply Voltage & frequency: 415V +/- 10%, 3 Phase, 3 Wire & 50HZ +/-5%. | | | | |
| | (b) Sizing: | | | | |
| | | | | | |
| | Open/Close at rated speed against designed differential pressure at 90% of rated voltage. | | | | |
| | For ON/OFF type: Three successive open-close operations or 15 minutes, whichever is higher. | | | | |
| | For inching type: 150 starts per hour or required cycles, whichever is higher. | | | | |
| 2.03.00 | CONSTRUCTION: | | | | |
| | (a) Enclosure: | | | | |
| | Totally enclosed weatherproof, minimum IP-68 degree of protection. | | | | |
| | (b) Manual Wheel: | | | | |
| | Shall disengage automatically during motor operation. | | | | |
| | | | | | |
| | TECHNICAL SPECIFICATIONS SULPHURISATION (FGD) SECTION – VI, PART-B ELECTRIC ACTUATORS 1 OF 4 | | | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS である。 | | | |
|------------|---|--|--|--|
| 2.04.00 | MOTOR: | | | |
| | (a) Type: | | | |
| | Squirrel cage induction motor suitable for Direct On Line (DOL)starting. | | | |
| | (b) Enclosure: | | | |
| | Totally enclosed, self-ventilated. | | | |
| | (c) Insulation | | | |
| | Class F. Temperature rise 70 Deg C. over 50 Deg C ambient. (d) Bearings: | | | |
| | Double shielded, grease lubricated antifriction. | | | |
| | (e) Earth Terminals: | | | |
| | Two | | | |
| | (f) Protection: | | | |
| | Single Phasing Protection, Over heating protection through Thermostat (as applicable) and wrong phase sequence protection shall be provided over and above other protection features standard to bidder's design. Suitable means shall be provided to diagnose the type of fault locally. | | | |
| 2.05.00 | POSITION/TORQUE TRANSMITTER: | | | |
| | The Position/ Limit measurement shall be done using absolute encoders which will give information of position/ limit in both the directions. Electronic measurement of torque shall be provided. | | | |
| 2.06.00 | LOCAL OPERATION: | | | |
| | It shall be possible to operate the actuator locally also. Lockable local/remote selection shall be provided on the actuator. | | | |
| 2.07.00 | LCD DISPLAY: | | | |
| | A local LCD display shall be provided to give information regarding actuator alarms, status and valve position indications as a minimum in local. | | | |
| 2.08.00 | WIRING: | | | |
| | Suitable voltage grade copper wire. | | | |
| 2.09.00 | TERMINAL BLOCK: | | | |
| | For power cables, the grade of TBs shall be minimum 650V. | | | |
| 2.10.00 | ACCESSORIES: | | | |
| | All required accessories (if applicable) for calibration / settings/ configuration of various parameters of actuator shall be provided. For quantities, please refer Part A of technical specifications. | | | |
| | TECHNICAL SPECIFICATIONS SULPHURISATION (FGD) SECTION – VI, PART-B BID DOC. NO.: CS-0011-109(1A)-2 SUB-SECTION-IIIC-8 ELECTRIC ACTUATORS 2 OF 4 | | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | |
|------------|--|--|--|--|--|
| | | | | | |
| 2.11.00 | SIL CERTIFICATION: All actuators shall be certified for SIL 2 or better. | | | | |
| 3.00.00 | SPECIFIC REQUREMENTS FOR NON INTRUSIVE HARDWIRED ACTUATORS | | | | |
| 3.01.00 | INTERFACES: | | | | |
| | For ON-OFF and INCHING type actuators interface with the control system shall be through hardwired signal only. | | | | |
| | (a) Open/Close command, open/ close status and disturbance monitoring signal (common contact for Overload, Thermostat, control supply failure, L/R selector switch at local & other protections operated) shall be provided hardwired. | | | | |
| | (b) The actuator shall be able to accept open/close command at 24V DC with max. 2.5VA load from control system. Accordingly suitable isolated interface in the actuator shall be provided. | | | | |
| | (c) Open/close command termination logic shall be suitably built inside actuator. | | | | |
| | (d) For typical wiring diagram Refer Tender Drawing No. 0000-999-POI-A-063 (Except plug & socket connector, if not applicable) | | | | |
| 3.02.00 | TERMINAL BOX: | | | | |
| | Suitable terminals/ connectors, integral to actuator, for terminating instrumentation & power cables shall be provided. Necessary glands for power cables and instrumentation cables shall be provided. | | | | |
| 3.03.00 | TRAINING: | | | | |
| | Contractor shall provide training on Non-Intrusive hardwired Electric Actuator for Employer's personnel. The duration of the training shall be as elaborated in Part-C, Section-VI of technical specifications. | | | | |
| 4.00.00 | SPECIFIC REQUIREMENTS FOR NON INTRUSIVE FIELDBUS ACTUATORS | | | | |
| 4.01.00 | INTERFACES: | | | | |
| | For ON-OFF and INCHING type actuators interface with the control system shall be through fieldbus network. | | | | |
| | (a) Open/ close commands, open/ close feedback status, disturbance signal etc. shall be available to the Control System through the fieldbus network along with diagnostics. The detailed diagnostics including the actuator operating data shall be available to the DDCMIS through the fieldbus network. | | | | |
| | (b) All actuators shall be Foundation Fieldbus/ Profibus compatible. However the exact protocol shall be based on finalized protocol of DDCMIS. If Profibus DP protocol is envisaged then actuator shall have two (redundant) Profibus DP ports for connecting the redundant Profibus DP cables. That is if one profibus cable is cut or not working/ not available, then complete actuator functionality shall be available through the second redundant cable without any manual intervention. | | | | |
| | (c) Open/close command termination logic shall be suitably built inside actuator. | | | | |
| | TECHNICAL SPECIFICATIONS SULPHURISATION (FGD) SECTION – VI, PART-B BID DOC. NO.: CS-0011-109(1A)-2 TECHNICAL SPECIFICATIONS SUB-SECTION-IIIC-8 ELECTRIC ACTUATORS 3 OF 4 | | | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS |
|------------|---|
| 4.02.00 | TERMINAL BOX: Suitable terminals/ connectors, integral to actuator, for terminating fieldbus cables and power cables shall be provided. Necessary glands for power cables and armored fieldbus cables shall be provided. |
| | |
| | |

| FLUE GAS DESULPHURISA SYSTEM PACKAG | TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS-0011-109(1A)-2 | SUB-SECTION-IIIC-8 ELECTRIC ACTUATORS | PAGE 4 OF 4 |
|--|---|--|----------------|

| CLAUSE NO. | SCOPE OF SUPPLY & SERVICES (다음대회 NTPC |
|------------|---|
| | |
| 12.00.00 | Fieldbus based Non-Intrusive Electrical Actuators with integral starters along with associated accessories etc. shall be supplied on as required basis for Valves / Dampers to meet the functional and the other specification requirements specified elsewhere in the Technical specification. For detailed specification refer chapter "Electric Actuator", Part B, Section-VI. These actuators shall comply the common requirements of actuators as specified at clause 2.00.00 and specific requirements of Non-Intrusive fieldbus actuators as specified at clause 4.00.00. Specific requirements of Non-Intrusive hardwired actuators specified in clause no. 3.00.00 are not applicable for this project. For Blade pitch actuators specification clause no. 5.00.00 shall be complied. |
| | TECHNICAL SPECIFICATION PHURISATION (FGD) SYSTEM PACKAGE TECHNICAL SPECIFICATION SECTION – VI, PART-A BID DOC. NO.:CS-0011-109(4)-9 SUB-SECTION-III-C C&I SYSTEM PAGE 18 OF 21 |

| CLAUSE NO. | SCO | PE OF SUPPLY & SERVICES | S | एनरीपीमी NTPC | |
|------------|--|---|---------------------------------|------------------|--|
| | complying to specification | quires any additional power ation requirements, then requ e provided by the contractor. | | • | |
| | The protocol of fieldbus based non-intrusive electric actuators shall be matching with fieldbus protocol of FGD System DDCMIS, and the same shall be subject to Employer's approval. For erection and commissioning of above specified actuators, qualified and experienced engineers of actuator manufacturer shall be deputed at site. After successful commissioning of actuators, minimum one qualified and experience engineer of main package supplier/ actuator manufacturer shall be continuous available at site up to completion of defect liability period (warranty) of actuators, for troubleshooting and maintenance of actuators and proper interfacing with DDCMIS Qualified and experienced engineers indicated above shall have expertise in a aspects of non-intrusive actuators along with fieldbus protocol and interfacing with DDCMIS. | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | DT-4 PROJECTS PHURISATION (FGD) SYSTEM PACKAGE | TECHNICAL SPECIFICATION SECTION – VI, PART-A BID DOC. NO.:CS-0011-109(4)-9 | SUB-SECTION-III-C C&I SYSTEM | PAGE 19 OF 21 | |



SUB-SECTION-II-E19

VFD

LOT-4 PROJECTS
FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE

TECHNICAL SPECIFICATION
SECTION-VI
BID DOCUMENT NO.: CS-0011-109(4)-9

| CLAUSE NO. | | TECHNICAL REQUIREMENT | s | एनहीपीमी NTPC | | | |
|--------------|---|--|---|---|--|--|--|
| | | VFD | | | | | |
| 1.00.00 | | | | | | | |
| 1.00.00 | GENERAL | | | | | | |
| | provided under this applicable official ar standards. In case standards, etc.) refe | acture, erection, testing and p specification shall comply w mendments and revisions as of conflict between this s rred herein, the former shall p codes and standards. | rith the latest edition ir on date of award of th pecification and code | ncluding all le following (IS Code, | | | |
| 2.00.00 | CODES AND STAN | DARDS | | | | | |
| | HT breaker | | IEC:60056 | | | | |
| | DC reactor | | IEC 60289 | | | | |
| | Transformers | | IS:2026, IEC | D: 60076 | | | |
| | | | IEC 61378 | | | | |
| | Bushing | | IS: 2099, IEC | 60137 | | | |
| | Adjustable Speed | Electrical Power Drive System | ns IEC 61800 | | | | |
| | Semiconductor co | nverters–General requiremen | s IEC 60146 | | | | |
| | IEEE Recommend | ded practices and requirement | s | | | | |
| | for harmonic contr | rol in electrical power systems | IEEE 519 | | | | |
| | Degrees of protect | tion provided by enclosures (I | P Code) IEC 60529 | IEC 60529 | | | |
| | Electrostatic immu | unity test | IEC1000-4-2 | | | | |
| | Fast transient imn | IEC1000-4-4 | | | | | |
| | | | | Γ | | | |
| FLUE GAS DES | -4 PROJECTS SULPHURISATION (FGD) IEM PACKAGE | TECHNICAL SPECIFICATION SECTION - VI, PART-B BID DOC NO : CS-0011-109(4)-9 | SUB-SECTION II-E-19 VFD | PAGE 1 OF 15 | | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | | |
|--------------|--|---|---|--|--|--|
| | Surge immunity te | est | IEC1000-4-5 | | | |
| | High-voltage sv | r; Pt.102: Alternatin | g current 62271-102 | | | |
| | | chgear and controlgear; Pt.20 or rated voltages above 1 | | | | |
| | AC electricity met | ers | IS: 722 | | | |
| | Metal oxide surge | arrestor without gap for AC | C system IEC: 60099-4 IEC: 60947-7-1 | | | |
| | Terminal blocks fo | or copper conductors | onductors IEC: 60947-7-1 | | | |
| | Dry transformer | IS: 11171 | IS: 11171 | | | |
| | Motor | | IEC 60034-18-41 &42, IEC60034 / NEMA 30 & 31, | | | |
| | Contactor/Switche | es/Fuses etc. | IEC:60947, IS | IEC:60947, IS: 13947 | | |
| | Harmonics & EM | compatibility | IEEE:519/IEC | IEEE:519/IEC: 61000 | | |
| | VFD | | IEC: 60034/ I | EC: 61800 | | |
| | considered if they c superior to standard the standard(s) adop | ing with other internationally ensure performance and co is listed above. In such a capted, furnish a copy in Englishe as on date of opening of comparison. | nstructional features ed se, the Bidder shall clea n of the latest revision a | quivalent or arly indicate mendments | | |
| FLUE GAS DES | -4 PROJECTS SULPHURISATION (FGD) TEM PACKAGE | TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 | SUB-SECTION II-E-19 VFD | PAGE 2 OF 15 | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | | |
|-------------|--|--|---------------|----------------------------|------------|--|
| 3.00.00 | OPERATING CONE | OPERATING CONDITIONS | | | | |
| 3.01.00 | For the purpose of design of equipment/systems, an ambient temperature of 50 deg. Centigrade and also relative humidity of 95% at 40 deg. Celsius shall be considered. | | | | | |
| 3.02.00 | All equipment shall be suitable for rated frequency of 50 Hz with a variation of +3% & -5%, and 10% combined variation of voltage and frequency unless specifically brought out in the specification. | | | | | |
| 3.03.00 | The auxiliary AC voltage supply arrangement shall have 11/6.6/3.3kV and 415V systems (as applicable). It shall be designed to limit voltage variations as given below under worst operating condition: | | | | | |
| | 1. 11kV/ 3.3 kV | 1. 11kV/ 3.3 kV/ 6.6 KV : +/- 6% | | | | |
| | 2. 415V | : - | +/- 10% | | | |
| | Note: The Voltage level mentioned above is the Nominal Voltage available at the input of the VFD System from the MCC/ Switchgear/transformer, based on the system requirement/Availability. | | | | | |
| | The voltage level for | the VFD output to | be fed to m | notor shall be as follows | :- | |
| | 1. Upto 400 kW | I | : 415\ | //690V, Low Voltage, Tl | nree Phase | |
| | | | AC | | | |
| | 2. Above 400k\ | W and upto 700 KV | V : 690\ | /, Low Voltage, Three F | hase AC | |
| | 3. Above 700K | W | : Med | ium Voltage | | |
| | 415 V or 690 V may be termed as MV VI | From here onwards in the specifications all the VFD Systems consisting of eithe 415 V or 690 V may be termed as LV VFD while the higher rated VFD System shabe termed as MV VFD. If nothing is mentioned than the Clause is applicable for both the LV and the MV VFD until deliberated otherwise. | | | | |
| 4.00.00 | SYSTEM DESCRIP | TION | | | | |
| | Type of drive | 3-Phase SGCT/ IE | | yristor / Multi Stage IG | BBT / IGCT | |
| | Type of Cooling of | VFD Naturally | air cooled/fo | orced air cooled/Liquid | cooled | |
| | Converter Type | Full wave | diode rectif | fier/active front end type | ; | |
| | Inverter Type | Thyristor/ | IGBT/IGCT | /SGCT/IEGT | | |
| FLUE GAS DE | LOT-4 PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 SUB-SECTION II-E-19 VFD 3 OF 15 | | | | | |

| CLAUSE NO. | | TECHNICAL REQUIREMENT | rs (| एनदीपीसी NTPC | |
|---|--|---|---|------------------------|--|
| 5.00.00 | GENERAL REQUIR | EMENTS | | | |
| 5.01.00 | modern proven desi shall be either Curre | Medium Voltage VFD : The Variable frequency drive (VFD) system shall be of a modern proven design for similar applications in power plants/industry. The system shall be either Current Source Inverter (CSI) or Voltage Source Inverter (VSI) type with minimum eighteen (18) pulse design. | | | |
| 5.02.00 | modern proven desi shall be either Curre with minimum Twelv | FD: The Variable frequency gn for similar applications in ent Source Inverter (CSI) or vec (12) pulse design. For drive ing all other requirements. | power plants/industry. T /oltage Source Inverter | he system (VSI) type | |
| 5.03.00 | The system shall be fully digital, PLC/Microprocessor based, energy efficient, and shall provide very high reliability, high power factor, low harmonic distortion and low vibration and wear and noise. It shall be easy to install in minimum time and expense and no special tools shall be required for routine maintenance. | | | on and low | |
| 5.04.00 | The offered equipment shall be with state of art technology and proven field track record. No prototype equipment shall be offered. | | | field track | |
| 5.05.00 | The VFD manufacturer shall ensure the proper coordination of their VFD with the Driven Motor and the supply system. All the Motors which are to be driven by VFDs will be of Inverter duty type. Also these motors shall comply the requirements stipulated in IEC: 60034-18-41 and IEC: 60034-18-42 as applicable. The VFD operation shall have no inherent detrimental impact on the Motors/ cables & supply system. | | | | |
| 6.00.00 | TECHNICAL AND OPERATIONAL REQUIREMENTS | | | | |
| 6.01.00 | complete speed tor supply voltage and | e designed to deliver the motor que characteristics of the di frequency variation. The sys he operational duty of the driv | iven equipment, with vitem shall be suitable for | worst input | |
| 6.02.00 | The overload capacity of the controller shall be 150% of the rated current of the motor for one minute for constant torque applications and 110% of rated current for one minute for variable torque applications at rated voltage. If the motor load exceeds the limit, the drive shall automatically reduce the frequency and voltage to the motor to guard against overload. | | | current for motor load | |
| 6.03.00 | _ | shall be designed to operate to suit characteristics of the | | • | |
| | a. Variable torque ch | nanging as a function of speed | l. | | |
| | b. Constant torque o | ver a specific speed range. | | | |
| | c. Constant power o | ver a specific speed range. | | | |
| FILIE CAS DESILI DULIDISATION (ECD) SECTION = VI PART-B | | PAGE 4 OF 15 | | | |

| CLAUSE NO. | | TECHNICAL REQUIREMENT | rs | एनदीपीमी NTPC |
|--------------|--|---|----------------------------|------------------|
| | d. Any other as spec | rified in data-sheet | | |
| 6.04.00 | VFDs shall comply with the latest edition of IEEE 519 & IEC 61000 for both individual as well as total harmonic voltage and current distortion limits. The Voltage and Current limits shall be applicable at the Point of Common Coupling (PCC), which shall be the MCC/ Switchgear/ from which the VFD system is fed. | | | |
| 6.05.00 | | nce shall be verified by the fie thout VFDs operation. | eld measurements of ha | irmonics at |
| 6.06.00 | transient mechanica | ole of withstanding the therm I torque, resulting from short or internal fault shall be limited | circuit. Any damage res | ulting from |
| 6.07.00 | The system shall be suitable to maintain speed variation within range 10-110% or as per the requirement of driven equipment with speed set accuracy of +1% of rated maximum speed and steady state regulation of +0.5% of rated speed as per system requirement. | | | |
| 6.08.00 | The VFD System shall maintain a power factor of 0.95 (minimum) (for LV VFD system) and 0.9 (minimum) (for MV VFD system) in the entire operating range. | | | |
| 6.09.00 | Maximum allowable audible noise from the VFD system will be 85 dB (A) at a distance of one meter under rated loaded with all cooling fan operating conditions. | | | |
| 6.10.00 | All the circuit compo | All the circuit components shall be suitably protected against over voltages, surges, lightning etc. | | |
| 6.11.00 | The panels shall be designed to provide easy access to hardware, to facilitate replacement of cards in case of any failure. | | | |
| 6.12.00 | All the VFDs for part interchangeability of | icular application shall be of s components. | ame design so as to ens | sure 100 % |
| 6.13.00 | message in complet | ed warning and fault protection te English words or Standard essages shall be stored in the | English abbreviations. | |
| 6.14.00 | | hall be placed in air condition / are designed to operate in cceptable. | | |
| 6.15.00 | The 3-Phase Thyristor/IGCT/SGCT/ multistage IGBT/IEGT based VFD system shall have minimum number of components to ensure very high reliability. The input side converter shall have 3-Phase Diode/Thyristor bridge configuration modular type and inverter shall be of 3-Phase Thyristor/IGCT/SGCT/multi stage IGBT/IEGT type, using Pulse Width Modulation or better technique for generating near sine wave output to motor. | | | |
| 6.16.00 | Fiber optic cable connection shall be provided preferably to ensure high network reliability. | | | gh network |
| FLUE GAS DES | -4 PROJECTS SULPHURISATION (FGD) FEM PACKAGE | TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 | SUB-SECTION II-E-19 VFD | PAGE 5 OF 15 |

| CLAUSE NO. | | TECHNICAL REQUIREMENT | rs (| एनहीपीसी NTPC | |
|--|---|---|-----------------|------------------|--|
| 7.00.00 | VFD COMPATIBILIT | TY WITH THE MOTOR | | | |
| 7.01.00 | MV VFD output current waveform, as measured at the motor, shall be inherently sinusoidal at nominal loads, with a total harmonic current and voltage distortion within acceptable/standard limits. VFD with transformers on output side are not acceptable. | | | | |
| 7.02.00 | , , | The system design shall not have any inherent output harmonic resonance in the operating speed range. | | | |
| 7.03.00 | regardless of cable the motor cable dist constraints if the cal by the VFD manufa | VFD shall provide stable operation of motor from high-voltage dv/dt stress, regardless of cable length to motor. The vendor shall clearly state the limitations in the motor cable distance in his proposal. However, due to system requirements & constraints if the cable length becomes critical, filters/ chokes etc. shall be provided by the VFD manufacturers as an integral part of the VFD to mitigate the reflected wave effect of harmonics. | | | |
| 8.00.00 | BYPASS ARRANGI | EMENT (OPTIONAL, IF SPEC | CIFIED) | | |
| 8.01.00 | The VFD System shall have an optional feature to run the motor under bypass arrangement for operation of Motor with VFD bypassed. During starting (under rated conditions) the motor will be switched on in VFD Mode to limit the starting current and after gaining speed, the load would be switched over to bypass mode. | | | | |
| 8.02.00 | | Comprehensive motor protection scheme for protection and control for operation VFD during bypass mode shall be finalized during detailed engineering. | | | |
| 9.00.00 | STANDBY VFD ARRANGEMENT (OPTIONAL, IF SPECIFIED) | | | | |
| 9.01.00 | A Common standby arrangement with auto/manual switchover shall be provided in case of failure of any VFD in a group of drives. Complete protection, interlocks & control required shall be provided in the changeover module. | | | | |
| 10.00.00 | EFFICIENCY | | | | |
| 10.01.00 | efficiency shall be n rated load and spee harmonic filters and fans and output filter | Efficiency (Drive only) shall be minimum 98% for both MV VFD and LV VFD. Overall efficiency shall be minimum 96.5% for LV VFD and minimum 94 % for MV VFD at rated load and speed. Overall Efficiency evaluation shall include input transformer, harmonic filters and power factor correction (if applicable), VFD converters, cooling fans and output filter, as applicable in the system. Auxiliary controls, such as internal VFD control boards, cooling fans/pumps. | | | |
| 10.02.00 | In absence of valid test report, a factory test shall be performed at the VFD manufacturer's facility verifying the efficiencies. Manufactures who are supplying Drive and transformer from different locations, efficiency test will be conducted separately for Drive and transformer. | | | | |
| 11.00.00 | COOLING SYSTEM | | | | |
| 11.01.00 | The VFD shall be designed to operate indoor under temperature range of 0 deg C to 50 deg C and relative humidity of 95 %(at 40 deg C). | | | 0 deg C to | |
| LOT-4 PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 SUB-SECTION II-E-19 VFD OF 05 06 0F 15 | | | PAGE 6 OF 15 | | |

| CLAUSE NO. | | TECHNICAL REQUIREMENT | rs | एनहीपीसी NTPC | |
|---|---|--|--|----------------------|--|
| 11.02.00 | VFD manufacturer to primarily offer Air cooled Design. However in case of large ratings, liquid cooled drives may be accepted subject to employer's approval. In case of liquid cooled system, there shall be no necessity of continuous water supply system (Closed Loop System). | | | | |
| 11.03.00 | minimum heat load i with ventilation ducts Air Conditioning & Manufacturer shall for | In case of Air cooled design, the VFD Cooling system shall be such that it puts minimum heat load inside the room and preferably throw the hot air outside the room with ventilation ducts. The Cooling system shall be designed in such a way that the Air Conditioning & Ventilation Air requirements are kept to minimum. The VFD Manufacturer shall furnish the data regarding heat load, air flow requirements during the detailed engineering. | | | |
| 11.04.00 | Air cooled VFDs shall be provided with cooling fans mounted integral to the VFD/ enclosure. The VFD shall include air-flow pressure switches and temperature detectors to monitor proper operation of the air cooling system. If the fan fails, the system must generate the alarm/trip for the fan failure. | | | | |
| 12.00.00 | TRANSFORMER: | | | | |
| 12.01.00 | Type: Outdoor Mineral oil filled ONAN type or Indoor natural air-cooled Dry type, Three phase unit, rectifier/converter duty type transformer. | | | | |
| 12.02.00 | All other components | s, technical parameters shall b | e as per applicable IEC | /IS. | |
| 12.03.00 | Enclosure for Dry Type Transformer (as applicable) | | | | |
| | Enclosure shall be of a tested quality sheet steel of minimum thickness 2 mm & shall also accommodate cable terminations. The housing door shall be interlocked such that it should be possible to open the door only when transformer is off. The enclosure shall be provided with lifting lugs and other hardware for floor mounting. | | | | |
| 12.04.00 | Core | Shall be High grad oriented Laminations. | de non-ageing cold ro silicon | olled grain steel | |
| 12.05.00 | Winding conductor | Shall be electrolytic g Windings shall be of | | | |
| 12.06.00 | Winding temperature Indicator (WTI) | Shall be Platinum res detector in each limb | sistance type temperatu | re | |
| 12.07.00 | Thermistors | Shall be embedded contacts for remote a | in each limb with alarm annunciation. | and trip | |
| 12.08.00 | Temperature rise: | Winding temperature r | ise shall be as per appli | cable IEC. | |
| | | | | | |
| | | | | | |
| FILIE GAS DESUI DUUDISATION (EGD) SECTION – VI PART-B | | PAGE 7 OF 15 | | | |

| CLAUSE NO. | | TECHNICAL REQUIREMENT | rs | एनहीपीमी NTPC | |
|--------------|--|---|----------------------------|------------------|--|
| 13.00.00 | POWER CONVERTER: | | | | |
| 13.01.00 | The static power converter shall consist of a line side converter for operation as a rectifier and a load side power converter for operation as a fully controller inverter. Power converter shall be fast switching, most efficient and low loss type. | | | | |
| 13.02.00 | | The converter shall be coordinated with the transformers. The converter shall be able to withstand a three phase short circuit current until interrupted by normal breaker operation. | | | |
| 13.03.00 | l - | Adequate short circuit and over voltage protection shall be provided for the converter and inverter system. | | | |
| 13.04.00 | | All power converter devices shall include protective devices, snubber networks and dv/dt networks as required. | | | |
| 13.05.00 | The current rating of the converter's semi-conductor components shall not be less than 120% of the nominal current flowing through the elements at full load of the VFD through the whole speed range. If the parallel connection of semiconductor is applied, the above current rating shall not be less than 140% of the above values. | | | | |
| 13.06.00 | All power diodes shall be of silicon type with minimum VBO rating at 2.5 times the rated operating voltage. | | | | |
| 13.07.00 | The power converter circuit shall be designed so that motor can be powered at its full nameplate rating continuously without exceeding its rated temperature rise nor reducing its service factor due to harmonic currents generated by the inverter operation. The conversion devices and associated heat sinks shall be assembled such that individual devices can be replaced without requiring the use of any special precautions / tools. | | | | |
| 13.08.00 | | of the electronic component ns shall be provided to preven es. | | | |
| 14.00.00 | OUTPUT FILTER (A | AS APPLICABLE): | | | |
| 14.01.00 | Output/ dv/dt filter shall be provided, if required. It shall be an integral part of the VFD system and included within the VFD enclosure. It shall inherently protect motor from high voltage dv/dt stress. | | | | |
| 15.00.00 | DC LINK CAPACITO | OR (AS APPLICABLE): | | | |
| 15.01.00 | Capacitor shall be of self-healing film or electrolytic type having high life time. The capacitor shall be an integral part of VFD system. DC link Capacitors shall have | | | | |
| FLUE GAS DES | -4 PROJECTS SULPHURISATION (FGD) FEM PACKAGE | TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 | SUB-SECTION II-E-19 VFD | PAGE 8 OF 15 | |

| CLAUSE NO. | TE | ECHNICAL REQUIREMENT | rs | एनरीपीसी NTPC |
|-------------|---|--|----------------------------|----------------------------|
| | | nich shall be capable of red r is disconnected from the s ple currents. | | |
| 16.00.00 | AC/DC Reactor (As a | pplicable) | | |
| | earth fault contin | e, air cored, self cooled, indo uously. nal Class 155(F), temperatu | •• | ithstanding ermal class |
| | · | not exceed value specified i | n NEMA TR-1. | |
| 17.00.00 | VFD PANEL REQUIR | EMENTS | | |
| 17.01.00 | Enclosure frames and load bearing members shall be fabricated using suitable mild steel structural sections or pressed and shaped cold-rolled sheet steel of thickness 2.0 mm. Frames shall be enclosed in cold-rolled sheet steel of thickness 1.6 mm. Doors and covers shall also be of cold rolled sheet steel of thickness 1.6 mm. Stiffeners shall be provided wherever necessary. The gland plate thickness shall be 3.0 mm for hot / cold-rolled sheet steel and 4.0 mm for non-magnetic material. In case dry type transformer is provided inside VFD panels, the enclosure and in its frame thickness shall be same as indicated in this para. | | | |
| 17.02.00 | The cable entry shall be from the bottom of the panel and a removable bolted undrilled gland plate. | | | |
| 17.03.00 | All Panels shall be of dust-proof and vermin-proof construction and shall be provided with a degree of protection of IP: 3X or better for MV VFD and IP: 4X or better for LV VFD as per IS/IEC 60947 | | | |
| 17.04.00 | Enclosures must be designed to avoid harmonic and inductive heating effects and to shield any outside equipment from interference, enclosing and shielding the complete to eliminate any radio frequency interference. The construction of the panel shall provide effective protection against electromagnetic emissions. | | | |
| 17.05.00 | Each panel shall be p and variable setting the | provided with illuminating lar ermostat. | mp, space heater with s | switch fuse |
| 17.06.00 | panels to ensure that m | g air filters and fans/pumps s naximum temperature inside liable and continuous operat | the cubicle is within | |
| 18.00.00 | PAINTING | | | |
| | Paint shade shall be a | s follows | | |
| | a) VFD transfor | , | , legend in black letter | |
| | reactor enclosur b) Motors | re : RAL 5012 (Blue) | | |
| FLUE GAS DE | -4 PROJECTS SULPHURISATION (FGD) TEM PACKAGE | TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 | SUB-SECTION II-E-19 VFD | PAGE 9 OF 15 |

| CLAUSE NO. | | TECHNICAL REQUIREMENT | rs | एनदीपीसी NTPC |
|--------------|--|---|-----------------------------------|------------------|
| | c) VFD Panels | : Front and rear pasides in blue (RA | anels in Grey (RAL9002 L 5012) |). End pane |
| 19.00.00 | HT SWITCHGEAR | | | |
| 19.01.00 | | irements of HT switchgear of Technical specifications. | shall be as per chap | oter of HT |
| 20.00.00 | MOTORS | | | |
| 20.01.00 | VFD shall be used to drive three (3) phase squirrel cage inverter duty Induction motor with VPI insulation (Resin poor) suitable for VFD application. These motors shall be provided with insulated bearing on at least one side for motor frame size above 250 frame. | | | |
| 20.02.00 | | Motors shall also meet the requirements mentioned in subsection for motors, relevant portions of the specifications for driven equipment and relevant IS/IEC. | | |
| 20.03.00 | Motor shall be suitable for operation with a solid state power supply consisting of an adjustable frequency inverter for speed control & shall be suitable for the current waveforms produced by the power supply including the harmonics generated by the drive. | | | |
| 20.04.00 | Motor insulation shall Vpeak and dv/dt limi | ll be designed to accept the ap ts as per IEC-61800. | oplied voltage waveform | , within the |
| 20.05.00 | | shall coordinate with the motor given load application and the | | |
| 20.06.00 | | of motor shall be as stipulated Part-B of technical specificatio | | Motors and |
| 21.00.00 | LT & HT CABLES | | | |
| 21.01.00 | Contractor's scope s Motors. | shall also include LT and HT ca | ables suitable for VFD s | ystem and |
| 22.00.00 | CONTROL AND PE | RFORMANCE REQUIREMEN | NTS | |
| 22.01.00 | The VFD to provide an automatic current limiting feature to control motor currents during startup and provide a "soft start" torque profile for the motor load combination. Current and torque limit adjustments shall be provided to limit the maximum VFD output current and the maximum torque produced by the motor. | | | |
| 22.02.00 | It shall be possible to vary the speed of the drive and control it in either Local or Remote mode. Local / Remote selection shall be done from VFD panel unless otherwise specified. | | | |
| FLUE GAS DES | LOT-4 PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 TECHNICAL SPECIFICATION SUB-SECTION II-E-19 VFD 10 OF | | | |

| CLAUSE NO. | | TECHNICAL REQUIREMENTS | | | | |
|--|--|---|--|------------------|--|--|
| 22.03.00 | Provision shall be k system parameters t | ept for exchange of informati hru PLC/DDCMIS. | ion between different V | FD control | | |
| | 1 | ace for (MV) VFD shall have o) in the VFD room and a color n control room. | | • | | |
| | Parameter Monitorin | g: -Input and output voltage of a linput and output current of a Motor speed and output power from 1 Torque and Output power transformer if applicable a Output kWhr of Drive a Transformer (if applicable a Ambient temperature and local/remotors.) | of Drive equency of Drive ver of Drive system e) temperature for alarm | ` | | |
| 22.04.00 | Drive shall be equipped with a front mounted operator console panel consisting of a backlit alphanumeric display and a keypad with keys for parameterization and adjusting parameter. Control panel shall be operable with password for changing the protection setting, safety interlock etc. | | | zation and | | |
| 22.05.00 | Operator console/Main Control Card shall have facility / port to connect external hardware such as Lap-Top etc. Console shall have facility for upload and download of all parameter settings from one drive to another drive for start up and operation. | | | d download | | |
| 22.06.00 | User-friendly licensed software for operation and fault diagnostic shall be loaded in the drive system panel before commissioning. | | | | | |
| 23.00.00 | PROTECTION FEATURES | | | | | |
| 23.01.00 | | shall incorporate adequate pro operly coordinated for the driv | | | | |
| | i) Converter transform high protection. | mer: short circuit, over current | , earth fault & winding to | emperature | | |
| | ii) Incoming and outo | joing line surge protection. | | | | |
| | iii) Under / over volta | ge protection | | | | |
| | iv) Phase loss, pha protection. | se reversal, overload, negati | ve phase sequence, lo | ocked rotor | | |
| | v) Instantaneous Ov | er current & Earth fault protec | tion | | | |
| | vi) Converter/Inverte | r module failure indication. | | | | |
| | vii) Over frequency/s | peed protection. | | | | |
| LOT-4 PROJECTS FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 TECHNICAL SPECIFICATION SUB-SECTION II-E-19 VFD 11 OF 15 | | | | PAGE 11 OF 15 | | |

| CLAUSE NO. | | TECHNICAL REQUIREMENTS | | | | |
|--------------|--|--|----------------------------|------------------|--|--|
| | viii) Ventilation failure | e indication & alarm. | | | | |
| | ix) Over temperature | of VFD | | | | |
| | x) Bearing temperatu | ure protection. | | | | |
| | xi) System earth faul | t protection. | | | | |
| | xii) Speed reference | loss protection. | | | | |
| 23.02.00 | Under VFD Bypass Motor shall remain a | Mode (if applicable) all the epplicable. | lectrical protections rela | ated to the | | |
| 24.00.00 | CONTROL FEATUR | RES | | | | |
| 24.01.00 | | Following controls shall be provided as a part of the Operator Control Panel or through separate switches on the front panel door. | | | | |
| | i) Start / stop (in loca | i) Start / stop (in local/remote mode) | | | | |
| | ii) Speed control (Ra | ii) Speed control (Raise / lower) | | | | |
| | iii) Acknowledge/Accept/ Test Push Button for annunciation | | | | | |
| | iv) Auto / Manual / T | est Mode select | | | | |
| | v) Emergency stop | | | | | |
| | vi) Trip-Remote Brea | aker | | | | |
| 25.00.00 | DIAGNOSTIC FEAT | URES | | | | |
| 25.01.00 | | de a microprocessor/PLC bas trol functions and displays fau | | | | |
| 25.02.00 | Fault diagnostic shall be built into the system to supervise the operation and failure of the system. The information regarding failure of any of the system including shut down of the system shall be available. It shall be possible to retrieve the record of events prior to tripping of the system or de-energization. Auxiliary supply to the system components or to the electronics (firmware) for the diagnostics / display shall be taken care of by the manufacturer for this purpose. | | | | | |
| 26.00.00 | SERVICEABILITY / | MAINTAINABILITY | | | | |
| 26.01.00 | Power Component Accessibility: All power components in the converter sections shall be designed for rack-out accessibility for ease of maintenance and to minimize repair downtime. | | | | | |
| FLUE GAS DES | -4 PROJECTS SULPHURISATION (FGD) TEM PACKAGE | TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 | SUB-SECTION II-E-19 VFD | PAGE 12 OF 15 | | |

| CLAUSE NO. | | TECHNICAL REQUIREMENT | rs | एनहीपीमी NTPC |
|---|---|---|------------------|---|
| 26.02.00 | Marking / Labeling: Sleeve type wire marker tags or other acceptable means of permanent identification shall be applied to power and control wiring. Individual labels shall be provided for all major components of the VFD system. | | | |
| 27.00.00 | STORAGE AND PR | ESERVATION | | |
| 27.01.00 | equipments to be installation and com long periods before | The Contractor shall be responsible for the storage and preservation of all the equipments to be supplied under the VFD System, till the time of successful installation and commissioning. The equipment should be suitable for storage for long periods before installation. Contractor should take adequate measures to ensure that no damage happens to the VFD System due to storage and preservation. | | |
| 28.00.00 | TESTS | | | |
| 28.01.00 | ROUTINE TESTS | | | |
| | | routine tests as envisaged in nall be deemed to be included | | carried out. |
| 28.02.00 | TYPE TESTS | | | |
| 28.02.01 | The Contractor shall carry out the type tests as listed in this specification on the equipment to be supplied under this contract. The bidder shall indicate the charges for each of these type tests separately in the relevant schedule and the same shall be considered for the evaluation of the bids. The type tests charges shall be paid only for the test(s) actually conducted successfully under this contract and upon certification by the employer's engineer. | | | |
| 28.02.02 | The type tests shall be carried out in presence of the employer's representative, for which minimum 15 days' notice shall be given by the Contractor. The Contractor shall obtain the employer's approval for the type test procedure before conducting the type test. The type test procedure shall clearly specify the test set—up, instruments to be used, procedure, acceptance norms, recording of different parameters, interval of recording, precautions to be taken etc. for the type test(s) to be carried out. | | | Contractor conducting st set–up, of different |
| 28.02.03 | In case the Contractor has conducted such specified type test(s) within last ten years as on the date of bid opening, he may submit during detailed engineering the type test reports to the Employer for waival of conductance of such test(s). These reports should be for the tests conducted on the equipment similar to those proposed to be supplied under this contract and test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client. The Employer reserves the right to waive conducting of any or all the specified type test(s) under this contract. In case type tests are waived, the type test charges shall not be payable to the Contractor. | | | |
| 28.02.04 | Further the Contractor shall only submit the reports of the type tests as listed in "LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED" and carried | | | |
| FILIE CAS DESILI DULIDISATION (ECD) SECTION = VI PART-B | | | PAGE 13 OF 15 | |

| CLAUSE NO. | | TECHNICAL REQUIREMENT | -s | एनहीपीसी NTPC |
|--------------|--|--|----------------------------|------------------|
| | out within last ten years from the date of bid opening. These reports should be for the test conducted on the equipment similar to those proposed to be supplied under this contract and the test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client. However if the Contractor is not able to submit report of the type test(s) conducted within last ten years from the date of bid opening, or in the case of type test report(s) are not found to be meeting the specification requirements, the Contractor shall conduct all such tests under this contract at no additional cost to the Employer either at third party lab or in presence of client/Employers representative and submit the reports for approval. | | | |
| 28.03.00 | LIST OF TYPE TESTS TO BE CONDUCTED | | | |
| | The following type tests shall be conducted under this contract for MV VFD | | | |
| | filters etc at moto ii) Temperature rise iii) Noise level | | m including transformer | / Harmonic |
| 28.04.00 | LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED | | | |
| | The following type to | est reports shall be submitted f | for VFD Panels' | |
| | 1) VFD panels (Fo | r LV VFD) | | |
| | i. Rated Currer | nt/ Output | | |
| | ii. Temperature | rise test | | |
| | iii. Noise level te | est | | |
| | iv. Power Loss I | Determination Test | | |
| | v. Power factor | measurement. | | |
| | vi. Degree of Pr | otection Test | | |
| | vii. EMC Test | | | |
| | | ansient SWC tests as per A -2008 / IEC 61800 | NSI / IEEE C37.901-2 | 2002 / IEC |
| | 2) VFD panels (Fo | r MV VFD) | | |
| | i. Rated Currer | nt/ Output | | |
| FLUE GAS DES | -4 PROJECTS SULPHURISATION (FGD) FEM PACKAGE | TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 | SUB-SECTION II-E-19 VFD | PAGE 14 OF 15 |

| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | |
|-------------|--|--|--|--|--|
| | ii. Current Sharing | | | | |
| | iii. Voltage Division | | | | |
| | iv. Power Loss Determination Test | | | | |
| | v. Power factor measurement. | | | | |
| | vi. Degree of Protection Test | | | | |
| | vii. The Fast transient SWC tests as per ANSI / IEEE C37.901-2002 / IEC 60255-22-04-2008 / IEC 61800 | | | | |
| | 3) AC/DC Reactor | | | | |
| | i. Lightning impulse test(If applicable) | | | | |
| | ii. Heat run test | | | | |
| | iii. Short time current test(If applicable) | | | | |
| | iv. Noise level test | | | | |
| | 4) Transformers (In case of non integrated type) | | | | |
| | As per requirements mentioned in subsection for Transformer chapter in technical specifications. | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| FLUE GAS DE | -4 PROJECTS SULPHURISATION (FGD) TEM PACKAGE TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO : CS-0011-109(4)-9 TEM PACKAGE TECHNICAL SPECIFICATION SUB-SECTION II-E-19 VFD 15 OF 15 | | | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | एनदीपीमी NTPC | |
|------------|---|--|---|------------------|--|
| 1.00.00 | CONTROL DESK & PA | CONTROL DESK & PANELS | | | |
| 1.01.00 | GENERAL | | | | |
| 1.01.01 | All control desk, panels, LVS panel etc. shall be furnished fully wired with necessary provision for convenience outlets, internal lighting, grounding, ventilation, space heating, anti-vibration pads, internal piping & accessories as required for completeness of the system. | | | | |
| 1.01.02 | be finalised application cabinets shall be seale single for inside room propagation of fire. Suf | All panels, desks, cabinets shall be free standing type & have bottom / top entry for cables to be finalised application wise during detailed engineering stage. The bottom of desk & cabinets shall be sealed with bottom plate, compression cable glands (double for field and single for inside rooms) and fire proof sealing material to prevent ingress of dust and propagation of fire. Sufficient number of power receptacles with disconnect switches shall be installed within all panels/desk. | | | |
| 1.01.03 | smooth enamel painted microns for sheet thick | Exterior steel surface shall be sand blasted, ground smooth, filled, primed, sanded and smooth enamel painted to give a good finish subject to minimum paint thickness of 65-75 microns for sheet thickness of 3 mm and 50 microns for sheet thickness of 2mm. The exact color shall be finalised during detailed engineering. | | | |
| 1.01.04 | The design shall conform to the EN ISO 11064 (Ergonomical design of control room), Part-1,2 and 3. | | | | |
| 2.00.00 | CONTROL DESK & PANEL | | | | |
| 2.01.00 | GENERAL | | | | |
| 2.01.01 | Control Desk etc. shall | The exact dimensions, material, construction details, grounding, general arrangement etc. of Control Desk etc. shall be as per the actual requirement and shall be finalised during detailed engineering and subjected to Employer's Approval. | | | |
| 2.01.02 | For control desk mounted instruments/ devices etc., which are to be powered from UPS, all required conversion of interface equipments / accessories to make such devices compatible with UPS supply shall be provided. All necessary hardware like Input switches/ fuse unit for each feeder as well as switch fuse unit for each instrument/ device on the power supply line shall be provided. From UPS, redundant feeders shall be provided with suitably rated MCB and provision of fast auto changeover of UPS feeders. | | | | |
| 2.02.00 | Control Desk (CD) | | | | |
| 2.02.01 | Control desk shall be Modular, non-welded construction free standing table top type with front & back cover constructed of 1.6 mm thick CRCA steel plates. The tabletop of the control desk shall be arc-shaped for mounting TFT monitors & mice. The work surface of control desk shall be 30mm thick with the top 12mm of Acrylic Solid Surface (ASS) and the remaining 18mm of laminated medium density fiber board. Work surface shall be made of two different colors at same level and seamlessly joined in each section. The structure frame shall consist of extruded aluminum top and bottom horizontal beams and vertical support tensioned together to form an integrated, finished curvilinear shaped frame. Vertical & Horizontal supports, minimum 2.5mm and 2mm thick respectively, have to be provided for the structure frame. Extreme side legs shall be illuminated type and should complete the | | | | |
| | SULPHURISATION (FGD) EM PACKAGE | TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS-0011-109(1A)-2 | SUB-SECTION-IIIC-9 CONTROL DESK & PANELS | PAGE 1 OF 3 | |

| CLAUSE NO. | - | TECHNICAL REQUIREMENT | rs | एनदीपीसी NTPC | |
|----------------------|---|--|---|------------------|--|
| | management system. trays shall be provided | sthetics of the desk. It shall Telephone sets shall be mounted I on the CD. The exact profile of ised during detailed engineering | on the control desk. Slidi the desk, dimension and t | ng keyboard | |
| 2.02.02 | All operator monitors a | & mice shall be mounted on this | CD. | | |
| 2.02.03 | | The cabling / wiring between OWS & CPU's, power supply cables etc. shall be aesthetically routed and concealed from view. | | | |
| 2.03.00 | Internal Panel/Desk It | tems | | | |
| | Equipment and devices mounted within the panels/desk shall be mounted on suitable racks/brackets and shall be arranged for convenient access for adjustment and maintenance work. | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| FLUE GAS DES SYST | SULPHURISATION (FGD) EM PACKAGE | TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS-0011-109(1A)-2 | SUB-SECTION-IIIC-9 CONTROL DESK & PANELS | PAGE 2 OF 3 | |



| SPECIFICATION NO.: PE-SS -999- 145 -054A | | | |
|--|---|------------------|--|
| VOLUME II | В | | |
| SECTION D | | | |
| REV. NO. 03 | | DATE: 16-09-2013 | |
| SHEET | 1 | OF 6 | |

1.0 SCOPE

This specification covers the Design, Manufacture, Inspection and Testing at the manufacturer's works, proper packing for transportation and delivery to site, supervision, erection, and commissioning at site of Local Panels required for control and monitoring of the Auxiliary Plant & Equipment.

2.0 CODES AND STANDARDS

- 2.1 All the equipments specified herein shall comply with the requirements of the latest issue of the relevant National and International standards.
- 2.2 As a minimum requirement, the following standards shall be complied with:

a) IS-6005 : 1998 : Code of practice for phosphating of iron and steel.

b) IS-5 : 2007 : Colors for ready mixed paints and enamels.

c) IS-1248:2 003 : Direct Acting Indicating Analog Elec Measuring Instruments.
d) IS/IEC 60947:Part 1:2004 : Low Voltage switchgear & control gear: Part-I (General Rules)

e) IS-8828:1996 : Circuit breaker for household and similar installations.

f) IS-13947 (Part-I):1993 : Low Voltage switchgear & control gear : Part-I (General Rules)

g) ISA-18.1:1979 : Annunciator Sequences and Specification

h) NFPA-496:2003 : Purged & Pressurised Enclosure fo r Elect rical Equipment in

Hazardous Locations.

3.0 TECHNICAL REQUIREMENTS

- 3.1 Panel Construction
- 3.1.1 The local panels shall house the secondary instruments, annunciation system, Single lo op controller, Control switches / push buttons, indicating lamps/LED cluster, relays, timers and other devices required for operation and monitoring of the equipment locally.
- 3.1.2 The panels shall be of free standing type either welded construction on angle iron (minimum section of 50 x 50 x 4 mm) structure or folde d con struction by she et m etal formation depending upon the equipments to be mounted on it. The panels shall be robustly built and stiffeners as necessary shall be provided.
- 3.1.3 The panel shall be suitably reinforced to ensure adequate support for all instruments mounted thereon. All welds on exposed panel surfaces shall be ground smooth.
- 3.1.4 The salient features of construction shall be:

Sheet material: Cold rolled sheet steel Frame thickness: Not less than 3.0mm

Enclosure thickness: Not less than 2.5 mm for load bearing sections (Mounted with instruments)

1.6 mm for doors and Not less than 2.0 mm for others

Gland plate thickness: 3.0mm

Base channel: ISMC 100 with anti-vibration mounting & foundation bolts.

- 3.1.5 The panel shall be provided with rear doors with integral lockable handle. The door when locked shall be held at mi nimum three places. The door width shall not be more than 550mm. The doors shall be provided with suitable stiffeners to prevent buckling. The handle shall be on the right side of the door. The door shall be remov able type with conceal ed hinges to facilit ate maintenance work. Suitable pocket inside the door shall be provided with suitable glass windows, as per the requirement.
- 3.1.6 Suitable neoprene gasket shall be provided on all doors and removable covers. Suitable ventilation system along with louvers shall be provided at bottom and top of the doors covered with removable wire mesh.

Page 295 of 532



| SPECIFICATION NO.: PE-SS -999- 145 -054A | | | | |
|--|---|--|----|-----------------|
| VOLUME II | В | | | |
| SECTION D | | | | |
| REV. NO. 03 | | | DA | ΓE : 16-09-2013 |
| SHEET | 2 | | OF | 6 |

- 3.1.7 The class of protection shall be in accordance with IP-42 unless otherwise specified in the data sheet A (No. PES-145-54A-DS1-0).
- 3.1.8 All steel surf aces shall be cle aned by sand / pellet blasting, treated for pickling, de greasing and phosphating etc. by seven tank method. The planel shall have a high quality finish and appearance. The panel shall be painted with two coats of primer followed by two coats of epoxy / synthetic enamel based final paint of color shade and finish as given in data sheet-A (No. PES-145A-DS1-0). Minimum thickness of the paint shall be 85 microns for external paint and 70 microns for internal paint.
- 3.1.9 The cable glands of the required size and type as given in data sheet-A (No. PES-145A-DS1-0) shall be supplied alongwith the Panel.
- 3.1.10 All operable and indicating devices shall be mounted on the front of the panel while aux. Relays / timers MCBs etc. required for re alization of control I ogics shall be mo unted on a mounting plate inside the panel. Auxiliary relays and timers etc. shall be grouped according to the control function. No operable or indicating devices shall be mounted below 750 mm and above 1800 mm (w.r.t. finished ground level). The devices shall be located in such a way so as to ensure easy access for operation / maintenance.
- 3.1.11 Single / dual control power supply feeders of voltage class as specified in data sheet-A (No. PES-145A-DS1-0) shall be provided by the purchaser. In case redundant power supply feeders are provided then auto changeover unit shall be mounted on the pan el are in the panel supplier's scope. Whe re DC control power supply is specified an additional 24 0V, 50 Hz AC supply feeder for powering of space heater and lighting shall be provided by the purchaser. Suitable arrangement shall be provided in side the panel to receive and terminate the power supply feeder(s). For this purpose MCBs of suitable current rating shall be provided by the vendor. A suppressory relay along with a pilot lamp to indicate control supply 'ON' shall be provided on the panel. Any other power supply required for the operation of the devices mounted in the panel shall be arranged by the vendor.
- 3.1.12 The internal wiring shall be carried out with 1100 volt grade PV C insulated copper multi strand wire / flexible of 1.5mm2 si ze. AC & DC wires shall be k ept separate from each other. Separate colou red wires to be used for AC and DC circuits. All wire s shall be p roperly numbered and identified with ferrules as per the Control scheme / wiring diagram. Wires shall be routed and run through PVC troughs.
- 3.1.13 Terminal blocks shall be clip on type, 1100 volts grade. Separate terminal blocks shall be used for AC & DC circuits. The terminals shall be suitable for terminating 0.5 mm2 to 2.5mm2 external cables. The TB points in terminal block shall be cage clamp type / screw type. The terminal for ammeters shall be provided with removable links for shorting CTs. Each terminal strip shall be provided with identification strip. The terminal shall not be mounted below 250 mm height from fini shed floor. The panel shall have ten (20) percent spare terminal.
- 3.1.14 The interior of each panel shall be suitably illuminated through fluorescent lamps / tube lights with shrouded cover of minimum 15W operable on 240V 50 Hz AC power supply through panel door switch. A 15 Amp. 3-pin Power receptacle shall be provided.
- 3.1.15 Suitable space heaters operable on 240 Volts 50 Hz AC power system shall be provided at the panel bottom. These shall be designed to maintain the panel temperature five (5) deg. C above the ambient temperature during maintenance shutdown. Suitable isolating and control devices comprising of MCB, thermostat etc. shall be provided for the space heater.
- 3.1.16 The panel shall be provided with a copper earth bus of 25 x 6 mm size running throughout the width of the panel. It shall be terminated internally with 10 mm bolts at extreme ends for connection to; main station earth. The panel mounted equipments / devices shall be connected to earth bus through green coloured PVC insulated stranded copper conductor of 2.5 mm2 size.
- 3.1.17 Local Panel shall be provided with main name plate of 150 mm x 40 mm size having inscription of 20 mm height. The individual devices on the panels shall be as provided with separate name plate with inscription of 3 mm height. The instrument / devices shall be provided with stick on label plates inside the panel. The material of the main and individual labels shall be three (3) ply 3 mm thick Traffolyte



| SPECIFICATION NO.: PE-SS -999- 145 -054A | | | |
|--|---|------------------|--|
| VOLUME II | В | | |
| SECTION D | | | |
| REV. NO. 03 | | DATE: 16-09-2013 | |
| SHEET | 3 | OF 6 | |

Sheet / 2 mm Anodised Aluminium Plate. The inscriptio n shall be with white letters on bl ack background on traffolyte sheet. The labels shall be fixed by self tapping non-rusting screws.

- 3.1.18 Vendor shall furnish electric load and he at load list (in case panel is to be placed in ac environ ment) of each panel.
- 3.2 Hazardous Area Panel Requirement
- 3.2.1 The Local Panel lo cated in ha zardous are a shall be pressurized as per NF PA-496 requirements to render it no n-hazardous. Alarms shall be p rovided for lo cal and rem ote annu nciation when pressurisation falls below 2.5 mm of water column. Protection shall be of type Z of NFPA-496. It shall not be possible to swit ch ON the power of purged section unless it is purged a sper the recommendation of NFPA-496. Vendor must provide a protective device on the panel to protect the panel from over pressurisation.
- 3.2.2 Vendor shall supply pressurisation kit consisting of valves, restriction orifices, dual filter regulation, pressure gauges, pressure switches, rotameter etc. Pressurisation kit shall be surface mounting on a metal board and located outside the local panel. Pressurisation kit shall further consist of sole noid valve flow switch, timer blow off safety device etc., so as to make purging fully automatic. However final start shall be manual. Panel protection against over pressure to be provided as per NFPA-496.
- 3.2.3 Pressurised local control panel pressurization kit assembly design shall provide minimum leakage flow through the Local Control Panel. Panel venting shall be as per NFPA-496.
- 3.2.4 All components in the local panel like in dicating instruments, push buttons switches, lamps etc., which are required to be energized without panel pressurization or before completion of purge cycle shall be explosion proof as per NEMA-7 & suitable for area classification.
- 3.2.5 All push butt ons et c. req uiring frequent operation during machine running shall have go od positive sealing. Weatherproof housing or cover to be provided wherever necessary. Vendor shall provide pressurisation bypass switch outside explosion proof enclosure of pressurized panel with lam pindication. This shall be used only during maintenance. All hinges, screws, other non-painted metallic parts shall be of stainless steel material.
- 3.2.6 Provision to switch off manually all types of power shall be provided in the panel. In a ddition, it shall also be possible to switch off power circuits / components which are powered from motor control centre or control room manually in case of pressurization failure. All such cables from MCC and main control room shall be terminated in explosion proof boxes (NEMA-7).
- 3.3 Control & Monitoring devices
- 3.3.1 Instruments like Indicators, recorders, single loop controllers etc. as applicable and specified elsewhere for the plant / equipment shall be supplied and mounted on the panel.
- 3.3.2 Alarm Annunciator System

It shall be solid state discrete facia type having a sequence of ISA-S18.1A or as specified, opaque facia windows of 70 mm x 50 mm size, havin g two (2) lamps per window, and hooter of 10W, and provision for re peat g roup alarm at remote. The ann unciator shall be provided with ten (10) percent spare windows or minimum two (2) windows along with electronics.

3.3.3 Relay s

The relays shall be electromagnetic type suitable for specified control supply. Its contact configuration and rating shall be suitable for the specified control function. However minimum contact rating shall be 5 Amp AC & 2 Amp DC as applicable. There shall be ten (10) percent spare contacts.

3.3.4 Timers

The timers shall be ele ctronic type suit able for specified control supply. Its contact configuration and rating shall be suitable for the specified control function. However, minimum contact rating shall be 5 Amp AC & 2 Amp DC as applicable.



| SPECIFICATION NO.: PE-SS -999- 145 -054A | | | |
|--|---|------------------|--|
| VOLUME II | В | | |
| SECTION D | | | |
| REV. NO. 03 | | DATE: 16-09-2013 | |
| SHEET | 4 | OF 6 | |

3.3.5 Control / Selector Switches

Switches shall be Rotary Cam type with minimum of 5 Amps AC & 2 Amp DC continuous current rating. Selector switches shall be stay put type while control switches shall be spring-return-to-neutral type. Contact configuration and rating shall be as per the control function requirement. The switches shall be lockable type wherever specified. Each switch shall be provided with engraved plates indicating the switch position / functions.

3.3.6 Push Buttons / Indicating Lights

The push buttons shall be momentary action self-resetting type, however stop P.B. for unidire ctional drives shall be provided with manual reset facility. Its contact configuration & rating shall be as required for the control function but minimum 2 NO + 2 NC of 5 Amp. AC rating. It shall have round coloured projecting tab and engraved escutcheon plate / inscription plate. Colour coding of push buttons shall be as under:

RED Motor OFF / Valve CLOSE YELLOW Alarm acknowledge Left Hand Side GREEN Motor ON / Valve OPEN BLACK Lamp test Right Hand Side

Indicating lights shall be suitable for direct connections a cross specified power supplies. It shall be fitted with built in resistance to prevent circuit tripping on shorting of lamp filament. It shall be fitted with LED cluster type lamp replaceable from front.

GREEN Motor OFF / Valve CLOSED condition AMBER Motor tripped Left Hand Side RED Motor ON / Valve OPEN condition WHITE Normal / healthy Right Hand Side

3.3.7 Ammeters

Ammeter shall be 9 6 x 96 mm si ze, 90 deg. d eflection, 1.5% accuracy, 1 Amp. CT o perated or with 4-20mA input and Flush mounting type as called for in the dat a sheet-A (No. PES-145-54A-DS1-0). Ammeters for motors shall have six (6) times folded scale at upper end to enable motor starting current indication

3.3.8 Miniature Circuit Breaker (MCB)

These shall be instantaneous magnetic trip type for short circuit in addition to current time inverse delayed thermal trip feature for over current protection. The housing of MCB shall be made of nonignitable, high impact material. It shall have minimum short circuit rating of 9 KA for AC Voltages and 4 KA for DC Voltages.

3.3.9 Makes of various instruments / devices shall be as given below

1. Alarm Annunciators : Procon / IIC Ammeters : AEP / IMP

Control / Selector Switches
 Push Buttons / Indicating Lamps
 Alsthom / Kaycee / Siemens / L&T
 Siemens / L&T / Teknic / Alsthom

5. Auxiliary Relays : Jyoti / Siemens / L&T / OEN

Timers
L&T / Alsthom / Bhartiya Cutler Hammer
MCBs
S&S Power Engg. / Indo Asian / MDS

8. Terminal Blocks : Jyoti / Elmex

4.0 TESTING AND INSPECTION

2.

- 4.1 The bidder shall adopt suitable quality assurance program to ensure that the equipments offered will meet the specification requirements in full.
- 4.2 BHEL's standard Quality Plan for L CP is enclosed with the specification. The bidder shall furnish his acceptance to BHEL's QP and submit the signed and stamped copy of QP along with the offer.



| SPECIFICATION NO.: PE-SS -999- 145 -054A | | | |
|--|---|------------------|--|
| VOLUME II | В | | |
| SECTION D | | | |
| REV. NO. 03 | | DATE: 16-09-2013 | |
| SHEET | 5 | OF 6 | |

- 4.3 The vendor shall conduct the following tests as a minimum requirement:
- 4.3.1 Routin e Tests
 - 1. High Voltage (H.V.)
 - 2. Insulation Resistance (I.R.)
 - 3. Functio nal
- 4.3.2 Type Tests
 - 1. Enclosure Class Test



| SPECIFICATION NO.: PE-SS -999- 145 -054A | | | |
|--|---|------------------|--|
| VOLUME II | В | | |
| SECTION D | | | |
| REV. NO. 03 | | DATE: 16-09-2013 | |
| SHEET | 6 | OF 6 | |

5.0 SPARES AND CONSUMABLES

5.1 Commissioning Spares and consumables

The bidder shall supply all commissioning spares and consumables 'as required' during Start-up, as part of the main equipment supply.

5.2. Mandato ry Spares

The bid der shall offer alo ngwith m ain offer, the Ma ndatory Spa res as spe cified elsewhe re in the specification. The Man datory Spares offered shall be of the same m ake and type as the main equipment.

5.3. Re commended Spares

The bi dder shall f urnish a li st of Recomme nded S pares indi cating the no rmal service expectancy period and freque ncy of repla cement; quantities recommended for 3 years operation alongwith unit rate again st each item to enable BHEL/BHEL's Custome r to place a separate order later, if required.

6.0 DRAWINGS AND DOCUMENTS

- 6.1 The bidder shall furnish the following documents in required number of copies along with the bid:
 - 1. Data Sheet no. PES-145A-DS1-0
 - 2. General Arrangement Drawing.
 - 3. Catalogue and technical information for instruments and devices.
 - 4. Quality Plan.
- 6.2 The vend or shall furnish the followin g documents in required number as agreed after the award of contract:
 - 1. Data Shee No. PES-145A-DS2-0
 - 2. GA Drawing indicating layout of instruments, construction details, foundation details, cable gland plate alongwith cable glands and all details mentioned in this specification.
 - 3. Control Schematic Diagram along with grouping of different terminals for various functions.
 - 4. Catalogue and technical information for instruments and devices with selected options clearly marked.
 - 5. O&M Manuals.
 - 6. "As Built" Drawing.
 - 7. CDs.


7.0 MARKING AND PACKING

7.1 Panel with all instruments / devices mounted on it shall be suitably packed & protected for the entire period of despatch, storage and erection against impact, abrasion, corrossion, incidental damage due to vermin, sunlight, high temperature, rain moisture, humidity, dust, sea-water spray (where applicable) as well as rough handling and delays in Transit and storage in open.

8.0 APPLICABLE DATA SHEET FORMS

This document shall be read with one or more of the following data sheet forms:

Data sheet A&B for Local Panels
 Data sheet no. PES-145A-DS1-0
 Data sheet C for Local Panels
 Data sheet no. PES-145A-DS2-0



FORMAT FOR SERIAL INTERFACE BETWEEN DCS SYSTEM & FOREIGN DEVICE

| 1 | | | | DCS (Engg.) | Range | | _ | | _ | _ | | | | | |
|-----------------------------|--------------------------------|------------------------|---|-------------|-------|-----|------------|--------------------------------------|----------------------------------|-------------------|----------------|-------------------------|------------------------|--------|------------------------|
| (Maximum (Maximum 15 Char.) | (Maximum of 32 (Note-1) Char.) | Point Type (Note-1) | _ | Max | ΑË | lax | Engg. Unit | Alarm Engg. Unit Requirement (Y / N) | Alarm Priority (URGENT/HI/LO) | Alarm SetPoint | Required (Y/N) | Data Format (Note-3) | Device ID (Address) | Modbus | Register Type (Note-4) |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |

1. Data type (AI/AO/DI/DO) shall be specified with respect to DCS.
2. For Digital points (IOs) please indicate the alarm state.
3. Data FormaSIGN16, USIGN16, SIGN32, USIGN32, FLOAT32, LONG32, BOOL, LOGIC
4. Function code: 1-Coil Status, 2-Input Status, 3-Holding Register, 4- Input Register, 5-Force single Coil, 6-Preset Single Register.

| | Che | eklist for Serial Communication between DCS System and Foreign Device | - |
|------|--|--|---------------------------------|
| | | | |
| Α | Device Specific : | | |
| SN | Parameters | Options available | Remarks if any |
| 1 | Model No.& Make of Device | | |
| 2 | Communications Link Options | ☐ Multidrop ✓ Peer to Peer ☐ N/w topology attached | |
| 3 | Protocol Mode (Device is a) | ☐ Master ☐ Slave ☐ Master/Slave | |
| 4 | Protocol | □ RTU □ ASCII □ Other | |
| 5 | Master | System maxDNA Other | |
| 6 | Redundancy Requirements | Yes / No | |
| 7 | Dist.bet.DCS System & Device* | □ Feet □ Meters | |
| В | Electrical Specific : | | |
| 1 | Interface Type | ☐ RS232 ☐ RS422 ☐ RS485 | |
| | Wiring at Device end | 2 Wire 4 Wire | |
| | Transmission Channel | ☐ Half Duplex ☐ Full Duplex | |
| | Baud Rates (bps) | □ 1200 □ 2400 □ 4800 □ 9600 □ 19200 | |
| 5 | Databits | □ 8 □ 7 | |
| 6 | Stopbits | □1 □2 | |
| 7 | Parity | ✓ None ☐ Odd ☐ Even | |
| | H/w & Software Handshake | ☐ Yes ☐ No | |
| 9 | Response Timeout time (Sec) | □ Configurable timeout | |
| | Data Formats Supported | □ Boolean □ Real □ Char □ Sn.Int □ UnSn.Int | |
| 11 | Transmission mode | ☐ Asynchronous ☐ Synchronous | |
| _ | Annication Considers | | |
| | Application Specific : * | ☐ Data Acquisition ☐ Data Acquisition & Control | |
| - | Primary Function* | Download parameter sets | |
| 2 | Analog Points to read | Nos. Details attached Details not attached | |
| | Analog Points to write | Nos. Details attached Details not attached | |
| | Digital Points to read | Nos. Details attached Details not attached | |
| | Digital Points to write | Nos. Details attached Details not attached | |
| | Memory / Flag Points to read | Nos. Details attached Details not attached | |
| | Memory / Flag Points to write | Nos. Details attached Details not attached | |
| | | 1100. | |
| | Hardware Specific : | ☑ Boolean cable ☐ Twisted pair cable | |
| | Cable type | Ev. EN | |
| | Cable Details Enclosed | | |
| 3 | Any specific Converter required | Yes No Details enclosed | |
| E | Device Documents : | | |
| 1 | Manufacturer's Documents* | ☐ Tech., Spec. ☐ Operating Manual | |
| | | | |
| *No | otes: | | |
| A6: | To identify converter requirement as | nd cable length. | |
| c. 1 | Or no 1 to 7 are required to be furnic | had for interface; such as Tagnama Description point type modbus/Pagistar) add | roop Ell roppe 9 dovice address |

 $\textbf{C:} \ Sr.no.1 \ to \ 7 \ are \ required \ to \ be \ furnished \ for \ interface: such \ as \ Tagname, Description, point \ type, modbus (Register) \ address, EU, range \ \& \ device \ address.$

C1: What is the primary purpose of the communication link?

E1: Reqd. Contents: This document must provide an overview of the device including its intended use.(a general tech,communication & electrical details)



C&I SPECIFICATION FOR HVAC SYSTEM

SECTION: C SUB SECTION: C&I

INSTRUMENTATION CABLE INTERCONNECTION AND TERMINATION PHILOSOPHY

| CLAUSE NO. | | | TECHNICAL F | REQUIREMENT | rs | एनटीपीसी NTPC |
|--------------|--|-----------------------------------|--|---|---|----------------------------|
| 1.00.00 | | | | | /ER SUPPLY CABLE, N MATERIAL (CABLE \$ | |
| 1.01.00 | Genera | al requirement | s | | | |
| 1.01.01 | shall c docume furnish | onform to this ents and the la | s specification, atest edition of t d services requ | Employer appro | d electrical field construct oved detail engineering dards & guidelines. The oleteness of the work ide | drawings & Bidder shall |
| 1.01.02 | and in: | strumentation | | es/systems inclu | all instrumentation cable uded under Contractor's | |
| 1.01.03 | | | | | entation cables are reque provided by Contractor. | ired due to |
| 1.01.04 | periphe | erals etc. (unde | r Contractor's sc | ope) are also to t | cables for c pe furnished by the Contra | onnection of actor. |
| 1.01.05 | branch | cable trays/sul | b-trays, support | s, flexible condui | rdware from the main trun ts, cable glands, lugs, pu this specification. | |
| 1.01.06 | furnishe | ed by contracto | | d basis within his | required basis, the same s quoted lump sum price | |
| 2.00.00 | SPECII | FICATION OF | INSTRUMENTA | TION CABLE | | |
| 2.01.00 | Comm | on Requireme | nts | | | |
| | S. No. | Property | | Requirement | | |
| | 1 Operating Voltage 225 V (peak value) | | | | | |
| | 2. Codes and s | | and standard All instrumentation cables shall comply with V 0815, VDE 0207, Part 4, Part 5, Part 6, VDE VDE 0472, SEN 4241475, ANSI MC 96.1, IS-10810 (latest editions) and their amendme read along with this specification. | | | DE 0816, , IS-8784, |
| | 3. | Continuous o | peration | | for Type-C cables & he eg C for all other type of c | |
| | | | | | | |
| FLUE GAS DES | SULPHURISA Tem Packa | | SECTION | SPECIFICATION -VI, PART-B NO.:CS-0011-109(1A)-2 | SUB-SECTION-III-C4 INSTRUMENTATION CABLES | PAGE 1 OF 13 |

| CLAUSE NO. | | TE | CHNICAL RI | EQUIREMEN | ітѕ | एनशेषीसी NTPC |
|--------------|-------------------------|--------------------------------------|--|-----------------------|---|---|
| | S. No. | Property | | Requirement | : | |
| | 4. | Marking :- a.Pro to be provided a | | | sequential markíng heath. | of length in meters |
| | | b.Marking to rea for Type-C cable | | provided at e | very 5 meters on ou | iter sheath except |
| | | | ı material, con | ductor's size, | number of pairs, vo | lude manufacturer's oltage rating, type of |
| | 5. | Allowable Tolera | | +/- 2 mm (ma sheet | ximum) over the de | clared value in data |
| | 6. | Variation in dian | neter | Not more than cable. | 1.0 mm throughou | it the length of |
| | 7. | Ovality at any ci | ross-section | Not more than | 1.0 mm | |
| | 8. | CAGE-CLAMP | suitability | To be provide | •d | |
| | 9. | Color | | The outer she | eath shall be of blue | color. |
| | 10. | Others | | Repaired cab | les shall not be acc | eptable. |
| 2.02.00 | Specifi | c Requirements | | | | |
| | | fication rements | Type-A cable | Type-B cable | Type F & G cable | Type-C cable |
| | A. CO | NDUCTORS | | • | | • |
| | Cross section area | | 0.5 sq. mm | | | |
| | Condu | ıctor material | ANSI type KX | ANSI type SX | Annealed bare copper | ANSI type KX |
| | Coloui | r code | Yellow-Red | Black-Red | As per VDE-815 | Yellow-Red |
| | Condu | ıctor Grade | As per ANSI | MC 96.1 | Electrolytic | As per ANSI MC 96.1 |
| | No & | dia of strands | | 7: | L x0.3 mm (nom) | 1 |
| | No. of | Pairs | 2 | 2 | 2/4/8/12/16/ / 48 | /24 2 |
| | | | | | , 10 | |
| | | | 1 | I | L | ı |
| FLUE GAS DES | SULPHURISA TEM PACKA | | TECHNICAL SE SECTION-V BID DOCUMENT NO | /I, PART-B | SUB-SECTION-I INSTRUMENTATION 1-2 | |

| CLAUSE NO. | TE | CHNICAL RI | EQUIREME | ENTS | एनदीपीसी NTPG |
|------------|---|---|-----------------|----------------------------------|--|
| | Specification Requirements | Type-A cable | Type-B cable | Type F & G cable | Type-C cable |
| | Max. conductor loop resistance per Km (in ohm) at 20 deg. C | As per ANSI | MC 96.1 | 73.4 | As per ANSI MC 96.1 |
| | Reference Standard | As per ANSI | MC 96.1 | VDE : 0815 | As per ANSI MC 96.1 |
| | B. INSULATION | | | | |
| | Material | E | xtruded PVC | type YI 3 | Teflon (i.e. extruded FEP) |
| | Thickness in mm (Min/Max) | | 0.25/0. | 35 | 0.4 / 0.50 (nominal) |
| | Volume Resistivity (Min) in ohm-cm | 1 x 10 ¹⁴ at 2 | 20 deg. C & · | 1x10 ¹¹ at 70 deg. C. | 2.8x 10 ¹⁴ at 20 deg. C & 2x10 ¹¹ at 205 deg. C. |
| | C. PAIRING & TWISTIN | IG | | | |
| | Max. lay of pairs (mm) | | | 50 | |
| | Single layer of binder tape on each pair provided | Each core pr number or N binder tape t provided on | umbered o be | Yes | Each core printed with number or Numbered binder tape to be provided on each pair |
| | Bunch (Unit Formation) for more than 4P | N.A To be provid | | To be provided | N.A |
| | Conductor /pair identification as per VDE0815 | N.A. To be provid | | To be provided | N.A. |
| | D. SHIELDING | | | | |
| | Type of shielding | | | Al-Mylar tape | |
| | Individual pair shielding | N | lo | To be provided for F-type cable | No |
| | Minimum thickness of Individual pair shielding | No | | 0.028mm (28 micron) | No |
| | SULPHURISATION (FGD) ITEM PACKAGE | TECHNICAL SP SECTION-V BID DOCUMENT NO | I, PART-B | SUB-SECTION- INSTRUMENTATION | |

| CLAUSE NO. | TE | CHNICAL RI | EQUIREME | ENTS | एनशेवीमी NTPC | |
|------------|---|--|-----------------|------------------------------------|----------------------------|--|
| | Specification Requirements | Type-A cable | Type-B cable | Type F & G cable | Type-C cable | |
| | Overall cable assembly shielding | | | To be provided | | |
| | Minimum thickness of Overall cable assembly shielding | | | 0.055 mm (55 micron |) | |
| | Coverage / Overlapping | | | 100% / 20% | | |
| | Drain wire provided for individual shield | N.A | | Yes (for F-type) Size- 0.5 sqmm | N.A. | |
| | | | | No of strands-7 | | |
| | | | , | Annealed Tin coated copper | | |
| | Drain wire provided for overall shield | Yes, Size- 0.3mm,Anne | | nm,No of strands- ated copper | 7,Dia of strands- | |
| | E. FILLERS (if applical | ble) | | | | |
| | Non-hygroscopic, flame retardant | | | To be provided | | |
| | F. OUTER SHEATH | | | | | |
| | Material | Extruded PV properties | C compound | d YM1 with FRLS | Teflon (i.e. extruded FRP) | |
| | Minimum Thickness at any point | 1.8 mm | | 0.4 mm | | |
| | Nominal Thickness at any point | | >1.8 m | ım | 0.5 mm | |
| | Resistant to water, fungus, termite & rodent attack | | | Required | | |
| | Minimum Oxygen index as per ASTMD- 2863 | | 29 % | 's | N.A. | |
| | Minimum Temperature index as per ASTMD- 2863 | | 250 de | g.C | N.A. | |
| | <u> </u> | | | | | |
| | SULPHURISATION (FGD) FEM PACKAGE | TECHNICAL SP SECTION-V BID DOCUMENT NO | I, PART-B | SUB-SECTION-I INSTRUMENTATION | • | |

| CLAUSE NO. | TE | CHNICAL RE | EQUIREMEN | тѕ | एनरीपीसी NTPC |
|--|--|--|------------------------------|---|-----------------------------|
| | Specification Requirements | Type-A cable | Type-B cable | Type F & G cable | Type-C cable |
| | Maximum Acid gas generation by weight as per IEC-60754-1 | | 20% | | N.A. |
| | Maximum Smoke Density Rating as per ASTMD-2843 | when the res | ults of smoke | g light absorption | N.A. |
| | Reference standard | VE |)E207 Part 5,\ | /DE-816 | VDE207 Part 6 ASTM D2116 |
| | G. Electrical Parameters | | | | |
| | Mutual Capacitance Between Conductors At 0.8 Khz (Max.) | 200 r | nF/km | 120 nF/km for F type | 200 nF/km |
| | , K G. G KIIZ (WIGX.) | | | 100 nF/km for G- type | |
| | Insulation Resistance (Min.) | | 10 | 00 M Ohm/Km | |
| | Cross Talk Figure (Min.) At 0.8 Khz | 60 | dB | 60 dB | 60dB |
| Characteristic Impedance (Max) Khz | | | A. | 320 OHM FOR F-TYPE 340 OHM FOR G- TYPE | N.A. |
| | Attenuation Figure At 1 Khz (Max) | N. | A. | 1.2 db/km | N.A. |
| | H. COMPLETE CABLE | | | | |
| | Complete Cable assembly | | Swedish Chir N-SS 4241475 | nney test as per class F3. | N.A. |
| | | • | | | |
| | SULPHURISATION (FGD) TEM PACKAGE | TECHNICAL SP SECTION-V BID DOCUMENT NO | I, PART-B | SUB-SECTION-II INSTRUMENTATION | |

| CLAUSE NO. | | TECHNICAL RE | EQUIREMEN | TS | एनदीपीर NTPC |
|------------|--|--------------------|-------------------------------|---|---|
| | Specification Requirements | Type-A cable | Type-B cable | Type F & G cable | Type-C cable |
| | Flammability | | ammability as unction to this | per IEEE-383 read specification | As per manufacturer's standard subject to employer's approval |
| | I. CABLE DRUM | | | | |
| | Туре | from season | | um (wooden drum to rom defects with wo teel drum. | |
| | Length | 1000 m <u>+</u> 5% | 6 for up to & in | cluding 12 pairs | |
| | | 500 m <u>+</u> 5% | for above12 p | pairs | |
| | Note: Heat resistant instrumentation cable shall be Teflon and cal | as specified abo | ve, except that | at insulation and ou | iter sheath mater |
| | instrumentation cable | as specified abo | ve, except that | at insulation and ou | iter sheath mater |

TECHNICAL SPECIFICATION
SECTION-VI, PART-B
BID DOCUMENT NO.:CS-0011-109(1A)-2

FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE SUB-SECTION-III-C4
INSTRUMENTATION CABLES

PAGE

6 OF 13

| CLAUSE NO. | | TECHNICAL REQUIRI | EMENT | S | | एनटीपीसी NTPC |
|------------|---|---|---------------------------------|--|---|--|
| 3.07.00 | Penetration of water re | esistance and impact resi | stance s | hall be as p | er IEC standaı | rd. |
| 4.00.00 | SPCIFICATION OF C | ONTROL & POWER SU | PPLY C | ABLES | | |
| | Refer Electrical sub-se | ections | | | | |
| 5.00.00 | INSTRUMENTATION | CABLE INTERCONNEC | TION A | ND TERMIN | NATION PHILO | DSOPHY |
| | signals by large scale (where large concent switchgear) is done a | tion philosophy to be add use of field mounted Gro ration of signals are av and consequently cable rmination to be followed a | up Junc ailable, with hig | tion Boxes e.g. valves her numbe | (JBs) at strateg limit & torqu r of pairs are | gic locations le switches, extensively |
| | TABLE A: CABLE TEI | RMINATION TO BE FOLL | OWED | | | |
| | Арр | olication | Т | ype Of Teri | mination | Type Of Cable |
| | FROM (A) | TO (B) | END A | ١ | END B | Gubio |
| | Valves/dampers drives (Integral Junction box) | Marshalling / Marshalling – cum Termination Cubicle / local group JB | Plug ir conne | | Post mount cage clamp type. | G |
| | Transmitters, Process Actuated switches mounted in LIE/LIR | Integral Junction box of LIE/LIR | Plug ir conne | | Cage clamp (Rail mount) type. | F,G |
| | RTD heads | Local junction box | Plug ir conne | | Cage clamp (Rail mount) type. | F |
| | Thermocouple | Local junction box / CJC box (if applicable) | Plug ir conne | | Cage clamp (Rail mount) type. | A, B, C* |
| | Other Field mounted Instrumen | Local JB / Group JB | Plug ir conne | | Cage clamp (Rail mount) type. | F,G |
| | RTD | Temperature transmitter | Plug ir conne | | Screwed, Cage clamp type | F |
| | Thermocouple | Temperature transmitter | Plug ir conne | | Screwed, Cage clamp type | A, B, C* |
| | Local Junction box, Temperature Transmitter, Int. Junction box of LIE LIR/ MCC/SWGR | Group JB | Cage ((Rail n type. | | Cage clamp (Rail mount) type. | F,G |
| | SULPHURISATION (FGD) | TECHNICAL SPECIFICAT SECTION-VI, PART-B BID DOCUMENT NO.:CS-0011 | | | CTION-III-C4 TATION CABLES | PAGE 7 OF 13 |

| _ | | | _ | | |
|---|----|----|---|----|----|
| C | LΑ | us | Έ | NO |)_ |

TECHNICAL REQUIREMENTS



| Appli | cation | Type Of Ter | mination | Type O |
|--|---|---------------------------------------|--|---|
| FROM (A) | TO (B) | END A | END B | Cable |
| Local Junction box, Temperature Transmitter, Int. Junction box of LIE/ LIR/ Group JB / MCC/SWGR | Marshalling / Marshalling – cum Termination Cubicle | Cage clamp (Rail mount) type. | Cage clamp (Post mounted) type. | F,G |
| Marshalling cubicle/ Termination Cabinet | Electronic system cabinet | Cage clamp (Post mounted) type. | Plug-in connector / other system as per Mfr.'s Standard | Internal wiring |
| Marshalling/ Termination System Cabinets | UCD mounted equipments | Cage clamp (Post mounted) type. | Plug in connector / Cage clamp type (rail mounted). | F,G (with plug-in connec or at one end) |
| DDCMIS/PLC cabinets | PC, Printers etc. | Plug in connector | Plug in connector | Mfr.'s Standa |

- be as per manufacturer's standard.
- 2 For analog signals, individual pair shielding & overall shielding & for Binary signals, only overall shielding of instrumentation cables shall be provided.
- $_3$ * For high temperature applications only.
- 4 . For connection between field/JB and DDCMIS marshalling cabinet Minimum 4 pair instrumentation cable shall be used.
- 5 All the spare cores of instrumentation cable have to be terminated in Marshalling cabinets/ DCS panel end.
- 6 Not used.

6.00.00

TERMINAL BLOCKS

6.01.00

All terminal blocks shall be rail mounted/post mounted, cage clamp type with high quality non-flammable insulating material of melamine suitable for working temperature of 105 deg. C. The terminal blocks in field mounted junction boxes, temperature transmitters, instrument enclosures/racks, etc., shall be suitable for cage clamp connections. The terminal blocks in Control Equipment Room logic/termination/marshalling cubicles shall be suitable for post

| FLUE GAS DESULPHURISATION (FGD) SYSTEM PACKAGE | TECHNICAL SPECIFICATION SECTION-VI, PART-B BID DOCUMENT NO.:CS-0011-109(1A)-2 | SUB-SECTION-III-C4 INSTRUMENTATION CABLES | PAGE 8 OF 13 | |
|---|---|--|-----------------|--|
|---|---|--|-----------------|--|

| CLAUSE NO. | TECHNICAL REQUIREMENTS |
|------------|--|
| | mounted cage clamp connection at the field input end. The exact type of terminal blocks to be provided by the Bidder and the technical details of the same including width etc. shall be subject to Employer's approval. |
| 6.02.00 | All the terminal blocks shall be provided complete with all required accessories including assembly rail, locking pin and section, end brackets, partitions, small partitions, transparent covers, support brackets, distance sleeves, warning label, marking, etc. |
| 6.03.00 | The marking on terminal strips shall correspond to the terminal numbering on wiring diagrams. At least 20% spare unused terminals shall be provided everywhere including local junction boxes, instrument racks/enclosures, termination/marshalling cabinets, etc. All terminal blocks shall be numbered for identification and grouped according to the function. Engraved labels shall be provided on the terminal blocks. |
| 6.04.00 | For terminating each process actuated switches, drive actuators, control valves, Thermocouple, RTD, etc. in Local Junction Boxes, etc, refer Drg no. 0000-999-POI-A-065. |
| 6.05.00 | The terminal blocks shall be arranged with at least 100 mm clearance between two sets of terminal blocks and between terminal blocks and junction box walls. |
| 7.00.00 | INTERNAL PANELS/ SYSTEM CABINETS WIRING |
| 7.01.00 | Internal panel/cabinet wiring shall be of multi-stranded copper conductor with FRLS PVC insulation without shield and outer sheath meeting the requirements of VDE 0815. |
| 7.02.00 | All internal wires shall be provided with tag and identification nos. etched on tightly fitted ferules at both ends. All wires directly connected to trip devices shall be distinguished by one additional red colour ferrule. |
| 7.03.00 | All external connection shall be made with one wire per termination point. Wires shall not be tapped or spliced between terminal points. |
| 7.04.00 | All floor slots of desk/panels/cabinets used for cable entrance shall be provided with removable gasketed gland plates and sealing material. Split type grommets shall be used for prefabricated cables. |
| 7.05.00 | All the special tools as may be required for solder less connections shall be provided by Bidder. |
| 7.06.00 | Wire sizes to be utilised for internal wiring. |
| | (i) Current (4-20 mA), low voltage signals (48V); 0.5 Sq.mm. Ammeter/Voltmeter circuit, control switches etc. for electrical system. |
| | (ii) Power supply and internal illumination. 2.5Sq.mm. minimum (shall be as per load requirement.) |
| | I Control of the cont |
| | |
| | |
| | |
| | TECHNICAL SPECIFICATION SUB-SECTION-III-C4 PAGE INSTRUMENTATION CABLES 9 OF 13 TEM PACKAGE BID DOCUMENT NO.:CS-0011-109(1A)-2 |

| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | | | | | |
|------------|--|--|--|--|--|--|--|--|--|
| 8.02.00 | Cables shall be segregated as per IEEE Std422. In vertically stacked trays, the higher voltage cable shall be in higher position and instrumentation cable shall be in bottom tier of the tray stack. The distance between instrumentation cables and those of other system shall be as follows: | | | | | | | | |
| | From 11 kV/6.6 kV/3.3 kV tray system - 914 mm | | | | | | | | |
| | From 415V tray system - 610 mm | | | | | | | | |
| | From control cable tray system - 305 mm | | | | | | | | |
| 8.03.00 | Cables shall terminate in the enclosure through cable glands. All cable glands shall be properly gasketed. Sealing (to prevent ingress of dust entry and propagation of fire) shall be provided for all floor slots used for cable entrance. Compression cable glands (double for armoured and single for other cables) shall be provided. | | | | | | | | |
| 8.04.00 | Not in use | | | | | | | | |
| 8.05.00 | The cables emanating from redundant equipment/devices shall be routed through different paths. The above segregation of cables & wiring for redundant equipments/devices shall be in accordance with IEEE-Std-422. | | | | | | | | |
| 9.00.00 | CABLE LAYING AND ACCESSORIES | | | | | | | | |
| 9.01.00 | CABLE LAYING | | | | | | | | |
| | Cables shall be laid strictly in line with cable schedule. | | | | | | | | |
| | 2 Identification tags for cables. | | | | | | | | |
| | Indelible tags to be provided at all terminations, on both sides of wall or floor crossing, on each conduit/duct/pipe entry/exit, and at every 20 m in cable trench/tray. | | | | | | | | |
| | 3 Cable tray numbering and marking. | | | | | | | | |
| | To be provided at every 10m and at each end of cable way & branch connection. | | | | | | | | |
| | 4 No jointing is permissible for Instrumentation cables. For other cables Jointing for more than 250 Meters run of cable shall be permitted. | | | | | | | | |
| | 5 Buried cable protection | | | | | | | | |
| | With concrete slabs; Route markers at every 20 Meters along the route & at every bend. | | | | | | | | |
| | 6 Road Crossings | | | | | | | | |
| | Cables to pass through buried high density PE pipes encased in PCC. At least 300 mm clearance shall be provided between | | | | | | | | |
| | - HT power & LT power cables, | | | | | | | | |
| | - LT power & LT control/instrumentation cables, | | | | | | | | |
| | TECHNICAL SPECIFICATION SUB-SECTION-III-C4 PAGE SULPHURISATION (FGD) SECTION-VI, PART-B INSTRUMENTATION CABLES 10 OF 13 TEM PACKAGE BID DOCUMENT NO.:CS-0011-109(1A)-2 | | | | | | | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS |
|------------|--|
| | Spacing between cables of same voltage grade shall be in accordance with the derating criteria adopted for cable sizing. |
| | 7 Segregation (physical isolation to prevent fire jumping) |
| | a All cable associated with the unit shall be segregated from cables of other Units. |
| | b Interplant cables of station auxiliaries and unit critical drives shall be segregated in such a way that not more than half of the drives are lost in case of single incident of fire. |
| | 8 Cable clamping |
| | All cables laid on trays shall be neatly dressed up & suitably clamped/tied to the tray. For cables in trefoil formation, trefoil clamps shall be provided. |
| | 9 Optical fiber cables (OFCs) : |
| | Outside Building Area - to be laid necessarily inside GI conduit with support from cable tray/Trestle structure |
| | Inside Building Area – to be laid on separate cable sub-trays |
| | While buried- in separate burried trench approx.1.0 meter depth, to be laid in 2" rodent proof HDPE conduits covered with sand, brick, laid breadth-wise and soil along the pipe line route by contractor; |
| | While crossing roads - to be laid in GI/ rodent proof HDPE conduits with sand filling at bottom and sand, soil filling at top with cement concrete; |
| | While crossing canals/river- to be laid in rodent proof HDPE conduits within hume pipe. |
| | 10 Laying of Network Cable (UTP/STP) : |
| | Out side Building Area- to be laid necessarily inside GI conduits with support from cable tray / Trestle structure. |
| | Inside Building Area- to be laid necessarily inside GI conduits on separate cable sub-trays. |
| 9.02.00 | Bidder shall supply and install all cable accessories and fittings like Light Interface Units, Surge suppressors, Opto isolators, Interface Converters, Fibre Optic Card Cage, Fibre Optic Line Driver, Repeater / Modem (for Optical Fibre Cables), cable glands, grommets, lugs, termination kits etc. on as required basis. |
| 9.03.00 | Cables, which terminate in cabinets of draw out sections shall have sufficient cable coiled in the bottom of the cabinet to permit full withdrawal of draw out sections without disconnecting the cables. When prefabricated cables with factory connectors on both ends are longer than required, the excess cable shall be coiled in the bottom of one or both termination cabinets. |
| 9.04.00 | The Bidder shall be responsible for proper grounding of all equipment under this package. Further, proper termination of cable shields shall be verified and the grounding of the same shall be coordinated so as to achieve grounding of all instrumentation cable shields at same potential. This shall be completed prior to system tests. |
| | TECHNICAL SPECIFICATION SUB-SECTION-III-C4 PAGE INSTRUMENTATION CABLES 11 OF 13 TEM PACKAGE BID DOCUMENT NO.:CS-0011-109(1A)-2 |

| CLAUSE NO. | | TE | ECHNICAL REQUIREMENT | rs | एनशैपीसी NTPC | | | | | | | |
|--------------|--|---|---|--|---|--|--|--|--|--|--|--|
| 9.05.00 | The Contractor shall take full care while laying / installing cables as recommended by cable manufacturers regarding pulling tensions and cable bends. Cables damaged in any way during installation shall be replaced at the expense of the Contractor. | | | | | | | | | | | |
| 10.00.00 | FIELD | FIELD MOUNTED LOCAL JUNCTION BOXES | | | | | | | | | | |
| | (i) | No. of ways | 12/24/36/48/64/72/96/128 v | vith 20% spares terminals. | | | | | | | | |
| | (ii) | Material and Thickness | d 4mm thick Fiberglass Reinf | orced Polyester (FRP). | | | | | | | | |
| | (iii) | Туре | Screwed at all four corner synthetic rubber. | s for door. Door gasket | shall be of | | | | | | | |
| | (iv) | Mounting clamps and accessories | - | vs, glands required for ere | | | | | | | | |
| | (v) | (v) Type of terminal Rail mounted cage-clamp type suitable for conductor size up blocks 2.5 mm ² . A M6 earthing stud shall be provided. | | | | | | | | | | |
| | (vi) | (vi) Protection Class IP: 55 minimum for indoor & IP-65 minimum for outdoo applications. | | | | | | | | | | |
| | (vii) | (vii) Grounding To be provided. | | | | | | | | | | |
| | (viii) | (viii) Color RAL 7035 | | | | | | | | | | |
| 11.00.00 | COND | UITS | | | | | | | | | | |
| 11.01.00 | JB's. A in acco surface zinc ch fire an | all rigid conduits, of ordance with IS: 99 es shall have conti oromate. Flexible of | ally used for interconnecting occuplings and elbows shall be 537 Part-I (1980) and Part-II (1 inuous zinc coating with an oveconduit shall be heat resistant cted for the areas of Mills,Drun | hot dipped galvanised rig 981). The conduit interior ercoat of transparent enan terne coated steel with | id mild steel and exterior nel lacker or , water leak, | | | | | | | |
| | | | cations, water leak, fire and rure reting of flexible conduit sha | | | | | | | | | |
| 11.02.00 | fitting | shall be used w | hall conform to the requiremen ith steel conduit. All flexible d fittings shall be compatible w | conduit fittings shall be | liquid tight, | | | | | | | |
| 11.03.00 | provide equipn shall b | ed as required by nent with which the e sealed and gas | ion proof, dust proof and other these specifications and shows they are installed. Fittings instance keted. Hazardous area fitting or the area classification. | nall be consistent with th alled outdoors and in dar | e area and np locations | | | | | | | |
| 11.04.00 | | | e double locknuts on all cor lings. Water tight conduit unior | | | | | | | | | |
| FLUE GAS DES | SULPHURIS | | TECHNICAL SPECIFICATION SECTION-VI, PART-B BID DOCUMENT NO.:CS-0011-109(1A)-2 | SUB-SECTION-III-C4 INSTRUMENTATION CABLES | PAGE 12 OF 13 | | | | | | | |


| CLAUSE NO. | | TECHNICAL REQUIREMENT | rs | एनटीपीसी NTPC |
|------------|---|---|---|---------------------------|
| | utilised for all the app eliminated from condu | lication which shall be exposed tits. | to weather. Moisture pock | ets shall be |
| 11.05.00 | Conduits shall be secu | rely fastened to all boxes and ca | binets. | |
| 12.00.00 | CABLE SUB-TRAY & | SUPPORT | | |
| 12.01.00 | JBs and the main c Contractor. It is the a | nd the supporting system, to be able trays and the same shall ssembly of sections and associant the cable from the equipment of e). | l be furnished and insta ated fittings forming a rig | lled by the id structural |
| 12.02.00 | | able sub-trays shall be used for om falling objects, welding spark, and solidly grounded. | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | SULPHURISATION (FGD) TEM PACKAGE | TECHNICAL SPECIFICATION SECTION-VI, PART-B BID DOCUMENT NO.:CS-0011-109(1A)-2 | SUB-SECTION-III-C4 INSTRUMENTATION CABLES | PAGE 13 OF 13 |



C&I SPECIFICATION FOR HVAC SYSTEM


SECTION: C SUB SECTION: C&I

INSTRUMENT STUB DETAILS



PRESSURE CONNECTIONS ON VERTICAL PIPES

FOR TENDER PURPOSE ONLY NTPC LIMITED COVERNMENT OF INDIA ENTERPRISE) KNGINEKRING DIVISION ਓਸਟੀ ਧੀਸ਼ੀ NTPC PROJECT TYPICALTHERMAL POWER PROJECT MLE INSTRUMENT SOURCE CONNECTION DETAILS FIRST ISSUE REV. NIDESIGN CHKD. W E C CLI ARCH, APFD. DATE SIZE SCALE REV. NO. DRG. NO. 0000-999-POI-A-035 DESCRIPTION Α N.T.S. CLEARED Page 320 of 532 A4




- 1. MATERIAL OF THE BOSS AND NIPPLE SHALL BE THE SAME AS THE PIPE INTO WHICH IT IS WELDED AND CONFIRM TO ANSI B 16.11.
- 2. THE LENGTH OF THE NIPPLE SHOULD BE 250mm.
- 3. THE OTHER END OF THE NIPPLE SHALL BE SOCKET WELDED WITH 1" GLOBE VALVE OF MATERIAL AS PER ANSI B 16.1.
- 4. TWO ISOLATED VALVES ARE TO BE USED FOR PRESSURE = >40 Kg/Cm2.
- 5. EDGE HOLE MUST BE CLEAN AND SQUARE OR ROUNDED SLIGHTLY (1/64" RADIUS) FREE FROM BURRS, WIRE EDGES OR OTHER IRREGULARITIES.
- 6. ORIENTATION OF TAP WILL BE VARY WITH TYPE OF PROCESS FLUID AND NATURE OF RUN OF THE PIPE.
- 7. ACTIVITIES TO BE COMPLETED AT THE SHOP, WELD THE COUPLING (OR BOSS) ON THE PIPE AND DRILL PRESSURE CONNECTION HOLE (SAME AS I D OF NIPPLE) IN THE PIPE IN ALLIGNMENT WITH HOLE IN THE COUPLING.
- 8. ALL DIMENSIONS ARE IN mm UNLESS OTHERWISE STATED.

FOR TENDER PURPOSE ONLY

| | | | | | | | | | | | | | ਸ਼ਹੀਧੀਸੀ NTPC | NTPCLIMITED (A GOVERNMENT OF NOM ENTERPRISE) ENGINEERING DIVISION |
|------|-------------|-------|----------|-------|---|---|------|-------|-----|-------|----------|------------------|------------------|---|
| | | | | | | | | | | | | PROJECT | TYF | PICALTHERMAL POWER PROJECT |
| | | | | | | | | | | | | TITLE | INST | RUMENT SOURCE CONNECTION DETAILS |
| Α | FIRST ISSUE | | <u> </u> | | | | | T.G. | | | Q1,D4,19 | | | |
| REV. | DESCRIPTION | DRAWN | DESIGN | CHKD. | ¥ | Ε | ¢ | | | APFD. | | | SCALE | ORG. NO. 0000-999-POI-A-035 REV. NO. |
| | | | | | | | CLEA | ED by | age | 321 | of 5 | β2 ^{A4} | N.T.S. | Sh-2 of 14 |

PRESS. MEASUREMENT




NOTES:-

- THIS TYPE OF PRESSURE CONNECTON SHALL BE PROVIDED FOR PRESSURE MEASUREMENTS IN AIR AND FLUE GAS DUCT/FURNACE.
- 2. DIMENSIONS ARE INDICATIVE ONLY.


FOR TENDER PURPOSE ONLY

| | | | | | | | | | | | | | ਸ਼ਰੀ ਧੀਸ਼ੀ NTPC | NTPCLIMITED (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION |
|------|-------------|---|---|-------|---|---|-----------|------|---|--------------|----------|---------------|--------------------|---|
| | | | | | | | | | | | | PROJECT | TYF | PICALTHERMAL POWER PROJECT |
| A | FIRST ISSUE | | ļ | | | | | T,G. | | | 21,04,16 | TITLE | INST | RUMENT SOURCE CONNECTION DETAILS |
| AEV. | DESCRIPTION | _ | - | снкв. | ¥ | Ε | C CLEA | | I | APFD. 322 | | suze 32 A4 | SCALE N.T.S. | DRG. NO. 0000-999-POI-A-035 Sh-3 Of 14 REV. NO. |

TEMP. MEASUREMENT



- THIS TYPE OF THERMOWELL INSTALLATION IS SUITABLE FOR THE PROCESS PIPE OF 2" NPS AND SMALLER.
- 2. FOR STEAM SERVICE THIS TYPE OF THERMOWELL INSTALLATION 90' BEND MAY BE USED ONLY IN VERTICAL PLANE.
- 3. THE LENGTH OF THE LARGER PIPE SECTION SHALL BE MINIMUM 150mm (IT MUST BE GREATER THAN THERMOWELL LENGTH).



NOTES:-

- INCLINED INSTALLATION OF THERMOWELL SHALL BE APPLICABLE FOR 4" AND SMALLER LINE SIZE BUT LIMITED TO MIN. 3" LINE SIZE.
- 2. FOR 2" AND SMALLER LINE SIZE NECESSARY EXPANDER OF MIN. 3" SIZE OF MAIN PIPING SPECIFICATION SHALL BE USED.
- THIS TYPE OF INSTALLATION IS APPLICABLE FOR HORIZONTAL AND VERTICAL PIPE SECTION.
- 4. FOR STEAM SERVICES EXPANDER SECTION MAY BE USED ONLY IN VERTICAL RUN.
- 5. THE EXPANDER SECTION SHALL BE OF ADEQUATE LENGTH (ATLEAST 3-4 TIMES DIA OF THE MAIN PROCESS PIPE AT BOTH SIDE OF THE INSTALLED THERMOWELL).

FOR TENDER PURPOSE ONLY NTPCLIMITED (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION एन ही पी ਸੀ NTPC TYPICALTHERMAL POWER PROJECT PROJECT (SG PACKAGE) MLE INSTRUMENT SOURCE CONNECTION DETAILS FIRST ISSUE REV. CHKD. 44 E C CLI ARCH, APFD. DATE SIZE SCALE REV. NO. 0000-999/102-POI-A-035 DESCRIPTION Α N.T.S. CLEARED Page 323 of 532 A4

reproduced by any means without the wrilten permission.

CORPORATION LTD.


POWER

NATIONAL THERMAL

o o

This document is the property No part of this document will

TEMP. MEASUREMENT



NOTES:-

- 1. FLOW INSTALLATION OF THERMOWELL SHALL BE APPLICABLE FOR 4" AND SMALLER LINE SIZE BUT LIMITED TO MINIMUM 3" LINE SIZE.
- 2. FOR 2" AND SMALLER LINE SIZE NECESSARY EXPANDER OF ELBOW FORM (AS SHOWN) OF MINIMUM 3" SIZE SHALL BE USED.
- ELBOW EXPANDER SECTION IN HORIZONTAL PLANE MAY BE USED FOR LIQUID SERVICES. ONLY STEAM SERVICES EXPANDER SECTION MAY BE USED IN VERTICAL PLAN.


FOR TENDER PURPOSE ONLY

NTPC LIMITED

COMERNMENT OF INDIA ENTERPRISE)

ENGINEERING DIVISION ਓਸਟੀ ਧੀਸ਼ੀ NTPC PROJECT TYPICALTHERMAL POWER PROJECT TITLE INSTRUMENT SOURCE CONNECTION DETAILS FIRST ISSUE REV. DRG. NO. 0000-999-POI-A-035 DESIGN CHKD. W E C CAI ARCH, APPD, DATE SIZE SCALE REV. NO. DESCRIPTION Α CLEARED Page 324 of 532 A4 N.T.S.

TEMP. MEASUREMENT




NOTES:-

- THIS TYPE OF TEMPERATURE BOSS SHALL BE USED FOR THE PROCESS PRESS EQUAL/ABOVE 40 Kg/Cm2(g).
- THE MATERIAL OF THE BOSS SHOULD BE SIMILAR TO THAT OF PIPING MATERIAL OF SPECIFICATION.
- ALL WELD TO BE TESTED IN ACCORDANCE WITH APPLICABLE CODES BY MANUFACTURER.
- 4. MATERIAL OF THE THERMOWELL SHALL BE OF 316SS.
- THERMOWELL SHALL BE DRILLED BARSTOCK TYPE.
- INTERNAL BORE OF THE THERMOWELL SHOULD BE SELECTED BASED ON THE NORMAL SIZE OF THE SENSING ELEMENT AS PER ASME,PTC-19.3.
- 7. THE BOTTOM DIAMETER OF THE THERMOWELL TYPICALLY SHOWN HERE SHALL BE SUBJECT TO VARIATION BASED ON THE INTERNAL BORE OF THERMOWELL AND THICKNESS OF THERMOWELL MATERIAL TO WITHSTAND THE PROCESS PRESS.AND TEMP.,AS PER ASME,PTC-19.3.
- 8. THE TYPE OF TAPERED THERMOWELL SHALL BE USED FOR LIQUID VELO-CITIES UP TO 92M.P.S.(300F.T.P.S.).
- THERMOWELL WITH THE INSULATION LAG EXTENSIONS SHALL BE USED WHEREVER APPLICABLE.
- 10. ACTIVITIES TO BE COMPLETED AT THE SHOP. WELD THE BOSS ON THE PIPE AND DRILL THE HOLE IN THE PIPE IN ALLIGNMENT WITH HOLE IN THE BOSS. PROVIDE INTERNAL THREAD AS PER IS:554 TO MATCH WITH THE THERMOWELL EXTERNAL THREAD.
- ALL DIMENSIONS ARE IN MM UNLESS OTHERWISE STATED.
- 12. WILL BE SUITABLE TO MATCH THE STUB DIMENSIONS AS PER RC 11/2
- 13. THE "U" & "L" DIMENSIONS SHALL BE BE SELECTED BASED ON PARTICULAR APPLICATION AND THE SAME SHALL BE SUBJECT TO OWNER'S APPROVAL DURING DETAILED ENGINEERING.
- 14. ALL DIMENSIONS ARE INDICATIVE ONLY.

FOR TENDER PURPOSE ONLY

N T P C LIMITED ਦਾ ਹੀ ਧੀ ਸੀ NTPC faterprese) MERMENT OF INDIA ENTERS ENGINEERING DIVISION PROJECT TYPICALTHERMAL POWER PROJECT MLE INSTRUMENT SOURCE CONNECTION DETAILS FIRST ISSUE REV. CHKOL W E C CLI ARCH. APPOL DATE SIZE SCALE DRG. NO. 0000-999-POI-A-035 REV. NO. DESCRIPTION Α N.T.S CLEARED Page 325 of 532 A4




NOTES:-

- 1. THIS TYPE OF TEMPERATURE BOSS IS APPLICABLE FOR THE PROCESS PRESSURE/TEMPERATURE BELOW 40 kg/Cm2(g)/400°C
- 2. FOR PRESSURE TIGHT JOINTS THE BOSS SHOULD HAVE INTERNAL TAPERED PIPE THREAD Rc 1 AS PER IS:554. THE LENGTH OF THREAD ENGAGEMENT SHOULD BE AS PER ABOVE STANDARD.
- PIPES HAVING PROBABILITY OF PROLONGED VIBRATION SEAL WELDING MAY BE DONE ALL AROUND AFTER TIGHTENING THERMOWELL WITHIN THE BOSS.
- 4. SEE NOTES-2 TO 14 OF DRG. NO. 0000-999-POI-A-035, Sh-6 Of 14.

FOR TENDER PURPOSE ONLY NTPCLIMITED GOVERNMENT OF INDIA ENTERS ENGINEERING DIVISION एन ही पी ਸੀ NTPC PROJECT TYPICALTHERMAL POWER PROJECT MLE INSTRUMENT SOURCE CONNECTION DETAILS FIRST ISSUE REV. DESIGN CHKD. W E C CM ARCH, APFD. DATE SIZE SCALE ORG. NO. 0000-999-POI-A-035 REV. NO. DESCRIPTION Α N.T.S. CLEARED Page 326 of 532 A4

TEMP. MEASUREMENT




NOTES:-

- THIS TYPE OF TEMPERATURE CONNECTIONS SHALL BE PROVIDED FOR TEMPERATURE MEASUREMENT IN AIR AND FLUE GAS DUCT.
- 2. MATERIAL OF THERMOWELL SHALL BE OF 316SS.
- 3. EXTERNAL CONNECTION SHALL BE OF SLIP ON FLANGED TYPE AND THERMOWELL DESIGN SHALL BE AS PER ASME.PTC-19.3 (REFER NOTES 9&10 OF DRG.NO. 0000-999-POI-A-035, Sh-6 Of 14).
- 4. BIDDER TO SUPPLY AND INSTALL THE COUNTER FLANGED AND THERMOWELL (ALONG WITH TEMP. ELEMENT).
- 5. ALL DIMENSIONS ARE INDICATIVE ONLY.


FOR TENDER PURPOSE ONLY

ਓਸਟੀ ਧੀਸ਼ੀ NTPC NTPCLIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
ENGINEERING DIVISION PROJECT TYPICALTHERMAL POWER PROJECT MLE INSTRUMENT SOURCE CONNECTION DETAILS A FIRST ISSUE REV. DESIGN CHKD. W E C CLI ARCH, APFD. DATE SIZE SCALE REV. NO. DRG. NO. 0000-999-POI-A-035 DESCRIPTION Α N.T.S. CLEARED Page 327 of 532 A4

LEVEL MEASUREMENT



- THIS TYPE OF PROCESS CONNECTION SHALL BE USED FOR LEVEL GAUGE AND EXTERNAL CAGE TYPE FLOAT OR DISPLACER OPERATED LEVEL SWITCH.
- 2. FOR GAUGES 3/4" NIPPLE ALONG WITH 3/4" SW SOURCE VALVE AND FOR SWITCHES 1" NIPPLE ALONG WITH 1" SW SOURCE VALVE SHALL BE PROVIDED AS PROCESS CONNECTION.
- SOURCE CONNECTION ON VESSEL SHOULD NOT BE LOCATED AT PLACES SUBJECTED TO INTERFACE AND TURBULENCE FROM INLETS AND OUTLETS.
- IF LOWER CONNECTION IS TAKEN FROM BOTTOM OF THE VESSEL THEN THE NIPPLE MUST BE 100 mm TO 150 mm ABOVE THE BOTTOM OF THE VESSEL.




NOTES:-

- THIS TYPE OF PROCESS CONNECTION SHALL BE PROVIDED FOR TANK LEVEL MEASUREMENT OF VISCOUS OR CORROSIVE LIQUID USING FLUSH DIAPHRAGM/WAFER TYPE LEVEL TRANSMITTER.
- 2. WELDING OF MATCHING FLANGE TO GATE VALVE SHALL BE DONE BY BIDDER.

FOR TENDER PURPOSE ONLY

| | | | | | | | | | | | | | एਜ ਹੀ ਧੀ ਸੀ NTPC | NTPC LIMITED (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION |
|-------------|--------------|-----------|--------|-------|---|---|------|--------|-----|-----|----------|---------|---------------------|--|
| | | | | | | | | | | | | PROJECT | TYF | PICALTHERMAL POWER PROJECT |
| Α | FIRST ISSUE | Mark Mark | + | | | | | T.G. | | | 21.08.12 | TITLE | INST | RUMENT SOURCE CONNECTION DETAILS |
| REV. NO. | DESCRIPTION | DRAWN | DESIGN | CHKD. | м | E | ¢ | | | | DATE | | SCALE | DRG. NO. 0000-999-POI-A-035 REV. NO. |
| | 323331111011 | | | | | | CLEA | RED BY | age | 328 | of s | 32 A4 | N.T.S. | Sh-13 Of 14 A |

LEVEL MEASUREMENT



NOTES:-

- THIS TYPE OF PROCESS CONNECTION SHALL BE USED FOR DISPLACER TYPE LEVEL TRANSMITTER.
- SOURCE CONNECTION ON VESSEL SHOULD NOT BE LOCATED AT PLACES SUBJECTED TO INTERFACE AND TURBULENCE FROM INLETS AND OUTLETS.
- 3. IF LOWER CONNECTION IS TAKEN FROM BOTTOM OF THE VESSEL THEN THE NIPPLE MUST BE 100 mm TO 150 mm ABOVE THE BOTTOM OF THE VESSEL.

FOR TENDER PURPOSE ONLY


NTPCLIMITED एन टी पी ਸੀ NTPC OVERNMENT OF INDIA ENTERPRISE)
ENGINEERING DIVISION PROJECT TYPICALTHERMAL POWER PROJECT TITLE INSTRUMENT SOURCE CONNECTION DETAILS REV. FIRST ISSUE C C&I ARCH. APPD. DATE DESIGN CHKD. M Е SIZE SCALE DRG. NO. 0000-999-POI-A-035 REV. NO. DESCRIPTION Α CLEARED Page 329 of 5 32 A4 N.T.S.





C&I SPECIFICATION FOR HVAC SYSTEM


SECTION: C SUB SECTION: C&I


| INSTRUMENT INSTALLATION DRAWING | J |
|---------------------------------|---|
|---------------------------------|---|














| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | | | | | | | | |
|------------|--|---|--------------------------------|--|--------------------------|--|--|--|--|--|--|--|
| | | PROCESS CO | NNECTION A | ND PIPING | | | | | | | | |
| 1.00.00 | PROCESS CONNECT | PROCESS CONNECTION PIPING | | | | | | | | | | |
| 1.01.00 | Impulse Piping System | The Contractor shall provide, install and test all required material for completeness of Impulse Piping System and Air Piping System as per the requirements of this Sub-Section on as required basis for the connection of all instruments and control equipments of entire plant. | | | | | | | | | | |
| 1.01.01 | IMPULSE PIPING, TUBING, FITTINGS, VALVES AND VALVE MANIFOLDS | | | | | | | | | | | |
| 1.01.02 | numbers. The size of & Flue Gas application | All impulse pipes shall be of seamless type conforming to ANSI B36.10 for schedule numbers. The size of impulse pipe shall be ½" for Steam & Water Application and ¾" for Air & Flue Gas applications. The rating of material of impulse pipes, tubes, fittings, valves and their installation thereof shall conform to the latest edition of standards as per following table: | | | | | | | | | | |
| | Impulse Pipes, Tubes | (Material, Rating) | ANSI B31.1, | ANSI B31.1a, ANSI/ISA 7 | 7.70 | | | | | | | |
| | Valves (Material, Pr. C | lass, Size) | ASTM A182 | /ASTM A105 as per ASME | 16.34 | | | | | | | |
| | | Fittings (Size, Rating, Material) ANSI B31.1, ANSI B31.1a, ASME B16.11-2009 | | | | | | | | | | |
| | Installation Schemes | | BS 6739-20 | 09, ANSI/ISA 77.70 | | | | | | | | |
| 1.01.03 | manifold and then to instrument. The source shut-off (primary process root valve) and blow down valve shall be of 1/2 inch size globe valve type for all applications except for air and flue gas service wherein no source shut-off valves are to be provided. Two root valves are to be used wherever pressure is more than 40 Kg/cm² or Temp>280 °C. The end connections of valves shall be of socket welded type. Typical installation scheme of DP Transmitter (inside LIE/LIR) mounted below instrument source point is indicated in Drg. No. 0000-999-POI-A-036. Same scheme with necessary changes shall be applied for other instruments. The valve manifolds of 316 SS with pressure rating suitable for intended application shall be provided as given below: | | | | | | | | | | | |
| | | on/Measurement | e prossure tre | namittara/pragaura guitab | • | | | | | | | |
| | | | | ansmitters/pressure switch pressure transmitter/ switch | | | | | | | | |
| | | al Pressure, Flow ar | | | | | | | | | | |
| | For Pr./D.P gauges, to instrument in Fluid/Air | | | provided on each impulsovely . | e line to the | | | | | | | |
| 2.00.00 | AIR SUPPLY PIPING | | | | | | | | | | | |
| 2.01.01 | accessories required to be provided. This will | for instrument air fo Linclude as a mini | or the various mum air supp | egulator, purge rotameter pneumatic devices/ instru ply to pneumatically opera ent purging requirements o | ments shall ated control | | | | | | | |
| 2.02.00 | | or all transmitters | of mill, dirty a | ided for continuous and ir and flue gas applicatio | | | | | | | | |
| 2.03.00 | suitable sizes for all output to actuators) c | pneumatic equipmon | ents/actuators 31.1 and 31 | associated fittings (screw (including supply air, sig 3 standard. All other air s d outside as per IS-1239, | nal air and supply lines | | | | | | | |
| | SULPHURISATION (FGD) FEM PACKAGE | TECHNICAL SPE SECTION-VI, BID DOCUMENT NO.: C | PART-B | SUB-SECTION-III-C3 PCP | PAGE 1 OF 4 | | | | | | | |

| CLAUSE NO. | | TECHNICAL REQUIREMENT | rs | एनटीपीसी NTPG | | | | |
|------------|---|--|---|---|--|--|--|--|
| | galvanized inside and per ASA B16.11 of rat accumulation of conde | ttings for air supply line shall be outside, screwed as per ASA Ba ting 3000 lbs. Air supply piping s ensed water within the pipe. The supported properly by clamps or s | Dimensions of fittings shall be adequately sloped air supply headers, sub-h | shall be as to prevent | | | | |
| 2.04.00 | provided by a well des 1" GI Pipe sub-header regulator set with mo | e air supply to each equipment/ igned air distribution scheme cor feeding ½" pipe at each equipmounting accessories shall be pexcept for Ash Handling Systemate each location. | mprising of 2" GI Pipe Hea nent/device. Instrument ai provided for each pneum | ider feeding r filters cum latic device | | | | |
| 2.05.00 | screw rising stem, scre | s in the air supply line shall be gowed female ends as per ASA Be stainless steel, body rating 150 | 2.1. Valve bonnet shall be | union type | | | | |
| 2.06.00 | pneumatic device requested max. Inlet pressure. The air set shall have 2-income. | cum regulator set with mountin iiring air supply. The filter regulat ne filter shall be of size 5 microns ch size pressure gauge and built e as per the requirement to be fir | tors shall be suitable for 1 s and of material sintered in filter housing blowdowr | 0-kg/ sq.cm bronze. The n valve. The | | | | |
| 3.00.00 | INSTALLATION AND ROUTING | | | | | | | |
| 3.01.01 | All instrument piping, tubing and its accessories shall be supported in a safe manne prevent excessive vibrations and anchored sufficiently to prevent undue strain on connect equipment. Impulse piping shall be supported at an interval not exceeding 1.5 meters. slope of the impulse pipe form the process connection to the instrument shall be as ANSI/ISA 77.70 latest edition and BS 6739-2009. All impulse piping shall be installed permit free movement due to thermal expansion. Wherever required expansion loops is be provided. | | | | | | | |
| | all flow measurement i 120 Deg. C. Colour co | all be provided for all level measurements in steam and water se t in steam services and for flow measurements in water services coding of all impulse pipes shall be done by the Contractor in lir ng followed for the parent pipes. | | | | | | |
| 4.00.00 | SHOP AND SITE TES | TS | | | | | | |
| 4.01.01 | test as per requireme | ork performed as per this Sub-se- ents of Sub-section-IIIE-04 (Qu his Sub-section and Employer ap | ality Assurance & Inspe | ction) other | | | | |
| 4.01.02 | Hydrostatic and Pneun and shall conform to A | natic leakage tests shall be perfo NSI B31.1. | rmed on all pipes, tubing a | and systems | | | | |
| 5.00.00 | LOCAL INSTRUMENT | FENCLOSURE AND RACKS | | | | | | |
| | contract shall be su enclosures in case of covered areas. The G | hes etc. for FGD system and oth itably grouped together and m open areas of the plant and (ii) A of LIE with purging indicated in ntractor. The GA of LIR shall be | ounted inside (i) local in In local instrument racks the Drg. No. 0000-999-Po | nstruments in case of OI-A-036 is | | | | |
| | SULPHURISATION (FGD) FEM PACKAGE | TECHNICAL SPECIFICATION SECTION-VI, PART-B BID DOCUMENT NO.: CS-0011-109(1A)-2 | SUB-SECTION-III-C3 PCP | PAGE 2 OF 4 | | | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS |
|------------|---|
| | The internal layout shall be such that the impulse piping/ blow down lines are accessible from back side of the enclosure / rack and the transmitters etc. are accessible from from side for easy maintenance. Bulkheads, especially designed to provide isolation from process line vibration shall be installed on instrument enclosures/racks to meet the process sensing line connection requirement. Vibration dampeners shall be installed for each enclosure / rack. The Degree of Protection of LIE and JB of LIE/LIR shall be IP-55. |
| | The enclosures shall be constructed of 3 mm sheet plate and shall be of modular construction with one or more modules and two end assemblies bolted together to form an enclosure. Double inter locking doors shall be provided. The doors shall be the three-point locking type constructed of not less than 1.6 mm thick steel. Doors shall have concealed quick removal type pinned hinges and locking handles. Door locks shall accept the same key. |
| | The instrument racks shall be free standing type constructed of suitable 5 mm thick channe frame of steel and shall be provided with a canopy to protect the equipment mounted in racks from falling objects, water etc. The canopy shall not be less than 3 mm thick steel and extended beyond the ends of the rack. |
| | Enclosures/Racks shall be reinforced as required to ensure true surface and to provide adequate support for instruments and equipment mounted therein. Centre posts or any member which would reduce access shall not be provided. |
| | Contractor shall provide not more than three variants for LIE/LIR with respect to max. no transmitters mounted in each LIE/LIR. |
| 5.01.00 | ENCLOSURE / RACKS FOR DUAL I/P TEMPERATURE TRANSMITTERS |
| | All Dual Input temperature transmitters for FGD system and other system being provided under the contract shall be suitably grouped together and mounted inside (i Enclosures in case of open areas of the plant and (ii) Racks in case of covered areas Integral JB shall be provided with each Enclosure and Rack. |
| | The internal layout shall be such that the transmitters are accessible from both front and back side of the enclosure / rack for easy maintenance. |
| | Enclosure/ Racks shall be of robust and rugged design. Vibration dampeners shall be installed for each enclosure / rack. The Degree of Protection of Enclosure and JB shall be IP-55. |
| | Enclosure and Racks shall be free standing type. |
| | Enclosures/Racks shall be reinforced as required to ensure true surface and to provide adequate support for instruments and equipment mounted therein. |
| | Contractor shall provide not more than five variants for Enclosure/ Rack with respect to max. no. transmitters mounted in each Enclosure/ Rack. However, the maximum number o Transmitters that can be grouped in one Enclosure/ Rack shall be decided during detain Engineering. |

| FLUE GAS DESULPHURISATION (F | GD) |
|------------------------------|-----|
| SYSTEM PACKAGE | |

TECHNICAL SPECIFICATION
SECTION-VI, PART-B
BID DOCUMENT NO.: CS-0011-109(1A)-2

SUB-SECTION-III-C3 PCP PAGE 3 OF 4





C&I SPECIFICATION FOR HVAC SYSTEM


SECTION: C SUB SECTION: C&I


SIGNAL EXCHANGE BETWEEN DRIVES & DCS

DDCMIS INTERFACE WITH LT MCC (LT)










DCS INTERFACE FOR AHUS VFD(VFD-AC) START COMMAND VFD-AC PANEL STOP COMMAND BINARY OUTPUT BY PASS ON COMMAND ON FEED BACK **BINARY** FAULT INPUT FEED BACK DCS **OWS** BYPASS ON FEED BACK BUS SPEED REFERENCE (4-20mA) ANALOG OUTPUT SPEED FEED BACK (4-20mA) ANALOG **INPUT** 4pX0.5Sqmm 'F-TYPE'








C&I SPECIFICATION FOR HVAC SYSTEM


SECTION: C SUB SECTION: C&I


DRIVE & INSTRUMENT INTERFACE DIAGRAM

















- NOTE :- 1) ABOVE IS THE TYP, DRG, MOUNTED TEMP TRANSMITTER FRO T/C APPLICATION. EXACT TYPE OF TEMP TRANMITTERS SHALL BE AS PER PART-A OF SPECIFICATION.
 - 2) THE EXACT GROUPING OF TEMP TXs SHALL BE FINISHED DURING DERAILED ENGG. STAGE.
 - 3) AFTER GLADDING OF T/C CABLES ON JB. THE CABLE PAIR OF FIRST ELEMENT WILL BE DIRECTLY CONNECTED TO TT AND THE CABLE PAIR OF SECOND ELEMENT SHALL BE WIRED TO INPUT TBs FOR FUTURE USE.
 - A) DIEASE NOTE THAT THIS CONFICURATION IS SHOWN FOR SINCLE INDUT ON PAIL

FOR TENDER PURPOSE ONLY

| | | 4) PLEASE NOTE THAT THIS CONFIG MOUNTED TT. FOR DUAL INPUT 1 | | | | | | | | | RAIL | | | | FOR TENDER PURPOSE C | INLY | | | | |
|--|---------|---|--------------|--------|-------|---|------|---------------|--------|-------|------|----------|---------------------------|-------|---|----------|--|--|--|--|
| CONNECTED DIRECTLY TO TT WITHOUT INPUT TBs. HOWEVER 5 NOS OF INPUTS TBs ARE TO PROVIDED FOR EACH T/C FOR FUTURE USE. | | | | | | | | | | | | | | | NTPCLIMITED (A COVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION | | | | | |
| | | | | | | | | | | | | | PROJECT | | TYPICAL THERMAL POWER PROJECT | | | | | |
| Ī | 8 | CABLING OF 2ND RTD CHANGED TO MATCH COLOR CODE | Made | | | | | | | | | 21.08.12 | TOTLE | | INTERFACING OF FIELD INSTRUMENTS | | | | | |
| | Α | FIRST ISSUE | 40 <u></u> 6 | 1 | | | | | | | | 29.04.06 | | TYPIC | CAL T/C CONNECTION WITH TEMP TXs IN JI | Bs | | | | |
| 1 | REV.NO. | | DRAWN | DESIGN | CHKD. | м | E | c | C&I | ARCH. | APPD | DATE | SIZE | SCALE | DRG. NO. | REV. NO. | | | | |
| 1 | | DESCRIPTION | | | | | CLEA | rege Regen | 357 of | 532 | | | A3 NTS 0000-999-POI-A-065 | | | | | | | |
| _ | | | | | | | | | | | | | | | SH 15 OF 15 | | | | | |



C&I SPECIFICATION FOR HVAC SYSTEM

SECTION: C SUB SECTION: C&I

QUALITY ASSURANCE-INSTRUMENTS, LCP & TYPE TEST REQUIREMETS



| MEASURING INSTRUMENTS (PRI | MAR | Y A | ND S | EC | ONDA | ARY) | | | |
|--|----------------|-------------------------------|---------------------------------------|------------------|------------------------------|--------------------------|--------------------------------------|---------------|-----------------------------|
| TESTS | | | | | | | | | |
| ITEMS | Dimensions (R) | Make, Model, Type, Rating (R) | ≺ Process / Electrical connection (R) | ≺Calibration (R) | ≺ Test as per standard(R) | nsulation Resistance (R) | BR Certification (if applicable)(R) | Hydro Test(R) | Material Test certificate ® |
| 1. PR Gauge (IS-3624) | Υ | Υ | | | | | | | |
| 2. Temp. Gauge (BS-5235) | Υ | Υ | Υ | Υ | Υ | | | | |
| 3. Pr./D.P.Switch(BS-6134) | Υ | Υ | Υ | Υ | Υ | Υ | | | |
| 4. Electronic Transmitter(IEC-60770) | Υ | Υ | Υ | Υ | Υ | Y | | | |
| 5. Temp. Switch | Υ | Υ | Υ | Υ | Υ | Υ | | | |
| 6. Recorder(IS-9319/ANSI C-39.4) | Υ | Υ | Υ | Υ | Υ | Υ | | | |
| 7. Vertical indicators | Υ | Υ | Υ | Υ | | Υ | | | |
| 8. Digital Indicators | Υ | Υ | Υ | Υ | | Υ | | | |
| 9. Integrators | Υ | Υ | Υ | Υ | | | | | |
| 10. Electrical Metering Instrument (IS-1248) | Υ | Υ | Υ | Y | Υ | Υ | | | |
| 11. Transducer (IEC-688) | Υ | Υ | Υ | Υ | Υ | Υ | | | |
| 12. Thermocouples (IEC - 754 / ANSI-MC-96.1) | Y | Υ | Υ | Υ | Υ | Υ | | | |
| 13. RTD(IEC-751) | Υ | Υ | Υ | Υ | Υ | Υ | | | |
| 14. Thermowell | Υ | | Υ | | | | Υ | Υ | Υ |
| R-Routine Test A- Acceptance Te | st | • | <u>Y – T</u> | est a | applic | able | _ | | |

: Note: 1) Detailed procedure of Environmental Stress Screening shall be as per Quality Assurance Programme in General Technical Conditions. Requirement of test and procedure (if required) finalized during QP finalization

2) This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the Practices and Procedure adopted along with relevant supporting documents.



| MEASURING INSTRU | JME | NTS | (PR | IMA | RY A | AND | SEC | ONI | DAR | Y) | | |
|--|----------------|-------------------------------|-------------------------------------|-----------------|---------------------------------|------------------|-----------------------------|------------------------------|---------------------------|-------------------------------------|----------------|-------------------------------|
| TESTS | | | | | | | | | | | | |
| ITEMS | Dimensions (R) | Make, Model, Type, Rating (R) | Process / Electrical connection (R) | Calibration (R) | Requirement as per standard (R) | WPS approval (A) | Non-destructive testing (R) | Calculation for accuracy (R) | Insulation Resistance (R) | IBR Certification as applicable (R) | Hydro test (R) | Material test certificate (A) |
| 15. Cold junction compensation box | Υ | Υ | Υ | Υ | | | | | Υ | | | |
| 16. Orifice plate(BS-1042) | Υ | Υ | Υ | Y * | Υ | Y ** | Y ** | | | Υ | Y ** | Υ |
| 17. Flow nozzle(BS-1042) | Υ | Υ | Υ | Y * | Υ | Υ | Υ | | | Υ | Υ | Y |
| 18. Impact head type element | Υ | Υ | Υ | | | | | Υ | | | | Y |
| 19. Level transmitter/float type switch | Υ | Υ | Υ | Υ | | | | | Υ | Y | Υ | Y |
| 20. Analysers | Υ | Υ | Υ | Υ | | | | | | | | |
| 21. Dust emission monitors | Υ | Υ | Υ | Υ | | | | | | | | |
| *Calibration to be carried out | | | | | | | | | | | | |
| on one flow element of each type and size if calibration | | | | | | | | | | | | |
| carried out as type test same | | | | | | | | | | | | |
| shall not be repeated. | | | | | | | | | | | | |
| ** If applicable | | | | | | | | | | | | |
| R-Routine Test A- Accepta | ance | Tes | t | | | Y | — Те | est a | pplic | able | | |

Note: 1) Detailed procedure of Environmental Stress screening test shall be as per Quality Assurance Programme in General Technical Conditions.

Requirement of test and procedure (if required) finalized during QP finalization

2) This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the Practices and Procedure adopted along with relevant supporting documents.

| FLUE GAS DESULPHURISATION SYSTEM |
|----------------------------------|
| PACKAGE |



| Pro | ces | s, C | onr | 1ec1 | tion | & p | oipiı | ng F | OR | C8 | l S' | YST | ЕМ | S | | | |
|---------------------------------------|----------|--|-------------|-------------------------|---|---------------------|----------|----------------------------|-----------|---|--------------------------------|---------------------------|----------|--------------------|--|---|--|
| ITEMS | Visual @ | GA, BOM, Layout of component & construction feature® | Dimension ® | Paint Shade/thickness ® | Flattening, flaring, hydrotest, hardness check as per ASTM standard | Component Ratings ® | Wiring ® | Make, Model, Type, Rating® | IR & HV ® | Review of TC for instrument/devices (R) | Accessability of TBs/Devices ® | Illumination, grounding ® | Tubing ® | Leak/Hydro test(A) | Chemical/physical properties of material (A) | Proof pressure test, Dismantling & reassembly test, Hydrulic impulse and vibration test (R) | Tests as per standards & specification |
| Local Instrument enclosure | Υ | Υ | Υ | Υ | | Υ | Υ | Υ | Υ | Υ | Υ | Υ | Υ | Υ | | | |
| Local instruments racks | Υ | Υ | Υ | Υ | | Υ | Υ | Υ | Υ | Υ | Υ | Υ | Υ | Υ | | | |
| Junction Box | Υ | Y | Υ | Y * | | Υ | | Y | Υ | | | | | | | | |
| Gauge Board | Υ | Υ | Υ | Υ | | Υ | | Υ | | Υ | | | Υ | Υ | | | |
| Impulse pipes and tubes | Υ | | Υ | | Υ | | | Υ | | | | | | | Υ | | |
| Socket weld fittings ANSI B- 16.11 | Υ | | Υ | | | | | Υ | | | | | | | Υ | | Υ |
| Compression fittings | Υ | | Υ | | | | | Υ | | | | | | Υ | Υ | Υ | |
| Instrument valves & Valve manifolds | Y | | Y | | | | | Υ | | | | | | Y | Υ | | |
| Copper tubings ASTM B75 | Υ | | | | | | | Υ | | | | | | | | | Υ |

^{*-}applicable for painted junction boxes.

Note: R-Routine Test A- Acceptance Test Y – Test applicable

Note: This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the Practices and Procedure adopted alongwith relevant supporting documents.

| FLUE GAS DESULPHURISATION SYSTEM PACKAGE TECHNICAL SPECIFICATION SUB-SECTION-V-QC2 PAGE PROCESS CONNECTION 1 OF 1 PIPING | | SECTION - VI, PART-B | PROCESS CONNECTION | PAGE 1 OF 1 |
|---|--|----------------------|--------------------|----------------|
|---|--|----------------------|--------------------|----------------|



| INSTRUMENTATION CABLE | . | | | | | | | | | | | | | | |
|--|------------------------------|----------------------|-------------------------------|---------------------------------------|---|-------------------------|------------------------------|--------------------------------|------------------------|---------------------------------|--|--------------------|--|---|----------------------------|
| ITEMS | Conductor Resistance ® & (A) | High Voltage ® & (A) | Insulation Resistance ® & (A) | Constructional detail, dimensions (A) | Outer-Sheathe/core marking, end sealing (A) | Thermal Stability (A) + | Visual, Surface finish (A) + | Electrical Parameters ** (A) + | Persulphate Test (A) + | Overall/Coverage/Continuity (A) | Swidesh chimney Test (SS-4241475) (A) ++ | FRLS Test * (A) ++ | Tensile & Elongation before & after aging (A) ++ | Vol. Resistivity. at room & Elevated Temp. (A) ++ | Spark test report review ® |
| 1. Instrument cable twisted and shielded | | | | | | | | | | | | | | | |
| Conductor(IS-8130) | Υ | | | Υ | ļ., | | Υ | | | | | Щ | | | |
| Insulation(VDE-207) | | | | Υ | Υ | Υ | Υ | | | | | Щ | Υ | | Υ |
| Pairing/Twisting | | | | Υ | Υ | | Υ | | | | | | | | |
| Shielding | | | | Υ | | | Υ | | | Υ | | | | | |
| Drain wire | Υ | | | Υ | | | Υ | | Υ | Υ | | | | | |
| Inner Sheath | | | | Υ | Υ | Υ | Υ | | | | | Υ | Υ | | |
| Outer Sheath | | | | Υ | Υ | Υ | Υ | | | | | Υ | Υ | | |
| Over all cable | Υ | Υ | Υ | Υ | Υ | | Υ | Υ | | | Υ | | | Υ | |
| Cable Drums(IS-10418) | | | | Y | | | Υ | | | | | | | | |

Note: High Temp. cables shall be subjected to tests as per VDE-207(Part-6) Compensating cables shall be checked for Thermal EMF/Endurance test as per IS 8784.

Note: This is an indicative list of tests/checks. The manufacture is to furnish a detailed Quality Plan indicating his practice & Procedure along with relevant supporting documents during QP finalization for all items.

Note: ® - Routine Test A - Acceptance Test Y - Test Applicable

Note: Sampling Plan for Acceptance test shall be as per IS 8784 (As applicable)

- * FRLS Tests: Oxygen / Temp Index (ASTM D-2863), Smoke Density Rating (ASTM D 2843), HCL Emission (IEC-754-1)
- ** Characteristic Impedance, Attenuation, Mutual Capacitance, Cross Talk (As applicable)
- + Sample size will be One No. of each size/type per lot.
- ++ Sample size will be One No. sample for complete lot offered irrespective of size/type.

| FLUE GAS DESULPHURISATION SYSTEM PACKAGE TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC. NO CS-0011-109(1A)-2 SUB-SECTION-V-QC3 INSTRUMENTATION 1 OF 1 |
|---|
|---|



CONTROL DESK, PLC PANEL, SMOKE DETECTOR, FIRE ALARM & CONTROL SYSTEM

| TESTS | | | | | | | | | / <u>^</u> | | | - | | | |
|---|----------|--------------------------------|--------------|--------------------------------|------------------------|---------------------------------|----------|-----------|--|---------------------------------|----------------|------------|---------|-----------------|-----------------|
| | | | | | | | | | Review of TC for instruments/ Devices/ Recorders, Indicators/ osaic Items/ Transducers ® | | | Element | | | |
| | | onents ® | | esion ® | | Type ® | | | nts/ Device Isducers ® | ⊗ S; | | Control | | | |
| | | comp | | s/Adh | 8 | ake/ | | | trumer s/ Trar | Device | | for | | * @ | € |
| | | GA, BOM ,Lay Out of components | s ® | Paint Shade/Thickness/Adhesion | Alignment of Section ® | Component Rating/ Make / Type ® | | | TC for instosaic Items | Accessibility of TBS/ Devices ® | 8 ر | Check | | r IEC 1131 | per Std ® & (A) |
| ITEMS | Visual ® | GA, BOM | Dimensions ® | Paint Shac | Alignment | Componer | Wiring ® | IR & HV ® | Review of Indicators/ | Accessibili | Illumination ® | Functional | Mimic ® | Test as per IEC | Test as pe |
| 1. Control Desk | Υ | Υ | Υ | Υ | Υ | Υ | Υ | Υ | Υ | Υ | Υ | Υ | Υ | | |
| 2. Annunciation/ Control/ PLC Panel | Y | Y | Υ | Υ | | Υ | Υ | Υ | Y | Y | Y | | | Υ | Υ |
| 3.Smoke Detectors (UL-268,EN-54 PT-7), Heat Detectors(UL-521/EN 54 PT- 5) Annunciation/ Control Panel (UL -864, EN-54, PT- 2) | | | | | | Chin | | | | | | h a II | | | Y |

- Note: 1) Detailed procedure of Environmental Stress Screening test shall be as per Quality Assurance Programme in General Technical Conditions
 - 2) This is an indicative list of test/ checks. The manufacturer is to furnish a detailed quality plan indicating the Practice and Procedure alongwith relevant supporting documents.
 - *Applicable for PLC
 - Y Test Applicable , ® Routine Test (A) Acceptance Test

| FLUE GAS DESULPHURISATION SYSTEM PACKAGE | TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC. NO CS-0011-109(1A)-2 | SUB-SECTION-V-QC4 CONTROL DESK, PLC PANEL, SMOKE DETECTOR, | PAGE 1 OF 1 |
|--|--|--|----------------|
| PACRAGE | BID DOC. NO CS-0011-109(1A)-2 | FIRE ALARM & CONTROL SYSTEM | |



| ELECTR | ICA | L AC | TU | IOTA | R WI | ТНІ | NTE | GRA | LS | TAR | TER | | |
|---|-------|-------------------|---------------|---------------------|---|-------------------------|--|--------------------------|---|---|--------------|------------------|--|
| Test/Attributes Characteristics Characteristics ITEM/ COPONENT/ SUB SYSTEM ASSEMBLY/ TESTING ELECTRICAL ACTUATOR WITH INTEGRAL | RPM ® | No Load Current ® | IR & HV Test® | Mounting Dimension® | All routine Test as per Standard & Specification® | Correct Phase Sequence® | Operation & Setting of limit Switch/Torque Switch® | Stall Torque/Current (A) | Hand Wheel operation/ Auto de clutch function (A) | Function of Aux. like Potentiometer, space heater, position indicator | EPT output ® | Grease leakage ® | Local/ Remote (Open-Stop-Close) Operation® Safety check (Single phasing, Phase correction, Tripping etc.) (A) |
| STARTER(IS 9334) Motor | Υ | Υ | Y | Υ | Υ | | | | | | | | |
| Final Testing | Ϋ́ | Ϋ́ | Ϋ́ | Y | Y | Υ | Υ | Υ | Y | Υ | Υ | Υ | Υ |

Note: 1) Detailed procedure of Environmental Stress Screening test shall be as per Quality Assurance Programme in General Technical Conditions. Requirement of test and procedure finalized during QP finalization

2) This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the practices and procedure adopted along with relevant supporting documents.

® - Routine Test (A) - Acceptance Test Y - Test applicable

TECHNICAL SPECIFICATION SECTION - VI, PART-B BID DOC. NO CS-0011-109(1A)-2 SUB-SECTION-V-QC7 ELECTRICAL ACTUATOR WITH INTEGRAL STARTERS

PAGE 1 OF 1



| | VFD MO | DULE SQ | E_28 | |
|---|-----------------------------------|------------------------------------|---|--|
| ATTRIBUTES / CHARACTERISTICS | Visual & Dimensional checks | Make / Type / Rating etc. | Final Inspectio n as ISS / IEC | Remarks |
| ITEMS/COMPONENTS, SUB SYSTEM ASSEMBLY | | | | |
| HT Breaker (IEC 56) | Y | Y | Υ | |
| DC Reactor | Υ | Y | , | For details refer table for DC Reactor |
| Transformer | Υ | Y | | For details refer table for Transformer |
| Motor | Υ | Y | | For details refer separate table for Motor |
| VFD Panel | Υ | Y | | For details refer table for VFD |

Note: 1) This is an indicative list of tests/checks. The manufacture is to furnish a detailed Quality

Plan indicating the practices & Procedure followed alongwith relevant supporting documents during QP finalisation.

2) Make of all major Bought Out Items will be subject to NTPC approval.

LOT-IA PROJECTS
FLUE GAS DESULPHURISATION
SYSTEM PACKAGE

TECHNICAL SPECIFICATION SECTION - VI, PART-B BID DOC. NO CS-0011-109(1A)-2 SUB-SECTION-V-QE13 VFD MODULE PAGE 1 OF 5



| | DC | REA | CTOR | | | | | |
|---|--------|-------------|------------------------|----------------------------|----------------------------|-----------------------------|---------------------------------|-------------|
| ATTRIBUTES / CHARACTERISTICS ITEMS/COMPONENTS, SUB SYSTEM ASSEMBLY | Visual | Dimensional | Mech. & Chem. Property | Electrical Characteristics | Pretreatment by Seven Tank | Painting by Stove Enameling | Final Inspection as per IS-2026 | Welding/NDT |
| Winding Material (Aluminium) | Y | Y | Y | Y | | 300 E 1 | | |
| Insulation Material | Y | Υ | | Y | | | | |
| Sheet Steel | Υ | Υ | Y | | | 1 | | |
| Winding | Υ | Υ | | Y | | | | |
| Fabrication of Enclosures | Υ | Y | | | Υ | Y | | Υ |
| Assembly | Υ | Υ | | | | | | |
| Routine Tests | Y | Y | | | | | Y | |

Note: 1) This is an indicative list of tests/checks. The manufacturer to furnish a detailed Quality Plan indicating their practice & procedure along with relevant supporting documents during QP finalisation for all items.

2) All major Bought Out Items will be subject to NTPC approval.

| LOT-IA PROJECTS |
|---------------------------|
| FLUE GAS DESULPHURISATION |
| SYSTEM PACKAGE |

TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC. NO CS-0011-109(1A)-2 SUB-SECTION-V-QE13 VFD MODULE PAGE 2 OF 5



| | 1 | TRANS | SFOR | MER | 2 | (OIL F | FILLI | ED) | | | | | |
|--|-----------------------------|-----------------------|---------------------|--------------------|----------------------|------------------------|----------------------|--------------|---|---|-------|-----------------------------------|--------------|
| Attributes / Characteristics | 1 | | | | | | | | No. | / 0 | | st | |
| Items/Components | Visual & Dimensional Checks | Mechanical properties | Electrical strength | Thermal properties | Chemical Composition | Compatibility with oil | NDT / DPT / MPI / UT | Ageing Test. | Voltage Ratio, Vector Group & Polarity, Magnetic Balance Test | Make / Type / Rating / Model / TC General Physical Inspection. | 8 PQR | Routine Test as per relevant test | Routine Test |
| Sub Systems | Visu | Mec | Elec | The | Che | Con | NDI | Age | Volt | Mak Gen | WPS | Ron | Rou |
| Tank, H.V. & L.V. Cable Box / Flange throat | Y | Y | | | | | Υ | | | | | | |
| Conservator / Radiator / Cooler / Pipes | Y | Y | | | | | Υ | | | | | | |
| Copper Conductor (IS:191) | Y | Υ | Y | | Y | | | | | | | | |
| Insulating Material | Y | Υ | Y | Υ | Υ | Υ | | | | | | | |
| CRGO Lamination & Built Core | Y | Υ | Y | | Y | Υ | | | | | | | |
| Bushing / Insulator (IS:2544 / 5621) | Y | Y | | | | | | | | Υ | | Y | |
| Gasket | Y | | | | Y | Υ | | Y | | | | Y | |
| Transformer Oil (IS:335 / IEC296) | | | | | | | | | | | | Y | |
| Off-Circuit Tap Changer | Y | | | | | | | | | Y | | | |
| Core Coil Assembly & Pre-tanking | Y | | | | | | | | Υ | | | | |
| Marshalling Box | Y | Υ | | | | | Υ | | | | | Υ | |
| WTI, OTI, MOG, PRD, Breather, Terminal Connector, Bucholz Relay, Globe & Gate Valve, | Y | | | | | | | | | Y | | | |
| Welding (ASME Sect-IX) | Y | | | | | | | | | | Y | | |
| Complete Transformer (IS:2026/ IEC-60076) | Y | | | | | | | | | | | | Y |

Note: 1) This is an indicative list of tests / checks. The manufacturer is to furnish a detailed Quality Plan indicating the practice and procedure along with relevant supporting documents.

2) All major Bought Out Items will be subject to NTPC approval.

| LOT-IA PROJECTS FLUE GAS DESULPHURISATION SYSTEM PACKAGE | TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC. NO CS-0011-109(1A)-2 | SUB-SECTION-V-QE13 VFD MODULE | PAGE 3 OF 5 |
|--|--|----------------------------------|----------------|
|--|--|----------------------------------|----------------|



DRY TYPE TRANSFORMER

| \ Attributes / | | DIVI | | | | 1401 0 | | | | | 7 | |
|--|----------------------------|-----------------------|---------------------|--------------------|---------------------|----------------|--|---|-----------|---------------------------------------|---|--------------|
| Characteristics | | | | | | | | | | | g | |
| Items/Components Sub Systems | Visual & Dimensional check | Mechanical properties | Electrical strength | Thermal Properties | Chemical Properties | NDT / DP / MPI | Voltage Ratio, Vector Group & Polarity | Make / Type / Rating / Model /TC / General Physical Inspection | WPS & PQR | Routine Test as per relevant standard | Measurement of capacitance & tan delta between winding | Routine Test |
| | > | 2 | ш | | O | _ | > | 20 | > | IT. | 2 0 | IF |
| Enclosure door, H.V. & | V | Y | | | | | | Y | | | | |
| L.V. Cable Box / Flange Throat | Υ | Y | | | | | | Y | | | | |
| | V | V | V | _ | V | | | | | | | |
| | 1 | Y | Y | \/ | | | | | | | | |
| Insulating Material | Y | | | Y | Y | | | x x | | | | |
| CRGO Lamination & Built Core | Y | | | | | | | | | | | |
| Bushing /Insulator (IS:2544 / 5621) | Y | | | | | | | Y | | Υ | | |
| Gasket | Y | | | | | | | Y | | Υ | | |
| Off-Circuit Tap Changer | Y | | | | | | | Y | | | | |
| Core Coil Assembly | Υ | | | | | | Υ | | | | | |
| Marshalling Box | Y | | | | | | 110 | | | Υ | 7 | |
| WTI, Thermister, Terminal Connector | Y | | | | | | | Y | | | | |
| | | | | | | | | | Υ | | | |
| Complete Transformer (IS:11171 / IEC 60076) | Y | | | | | | | | | | Υ | Y |
| Bushing /Insulator (IS:2544 / 5621) Gasket Off-Circuit Tap Changer Core Coil Assembly Marshalling Box WTI, Thermister, Terminal Connector Welding Complete Transformer | Y Y Y Y | Y | Y | Y | Y | | Y | Y | Y | Υ | Y | |

Notes: 1) This is an indicative List of test/checks. The manufacturer is to furnish a detailed Quality Plan indicating his practice and procedure along with relevant supporting documents during QP finalization for all item.

2. All major Bought out Items will be subject to NTPC approval.

LOT-IA PROJECTS
FLUE GAS DESULPHURISATION
SYSTEM PACKAGE

TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC. NO CS-0011-109(1A)-2 SUB-SECTION-V-QE13 VFD MODULE PAGE 4 OF 5



VFD PANEL

| Attributes Characteristics | | | - A | | | | std. | | | | | _ | | |
|---|-----------------------|-----------------------|---------------------|---------------------|-------------------------------|-------|------------------------|-------------------------|-----------------------------|-------------------------------|--|--|---------------------------|-------------------------------|
| Item Components Sub System Assembly | Electrical Properties | Mechanical Properties | Chemical Properties | Dimensions / Finish | Type/ Rating/Functional check | HV/IR | e test as per relevant | Constructional Features | IS:6005, Seven tank process | Paint finish/ shade/thickness | Mountings / BOM/ Make, Completeness | Interlock Functional & Operation Testing / Simulation check | Degree of Protection Test | Final testing as per Relevant |
| Sheet Steel (IS-513) | | Υ | Y | Υ | | | | | | - | | | | |
| Aluminum / Copper Bus- bar(IS-5082/IS-613/IS-1987) | Υ | Υ | Y | Υ | | | | | | | | | | |
| Support Insulator (BS- 2782/IEC-660/IS-10912) | Υ | Υ | Υ | Υ | | | | | | | | | | |
| Control / Selector Switch(IS- 6875) | | | | | Y | Y | Υ | | | | | | | |
| Contactor/ MCB(IS-13947) | | | | | Υ | Y | Υ | | | | | | | |
| O/L Protection relays(IS-3231) | | | | | Υ | | Υ | | | | | | | |
| C.T /V.T/ Indicating Meter(IS- 2705/3156/1248) | | | | | Υ | Y | Y | | | | | | | |
| Fuse/ Fuse carrier(IS-13703) | | | | | Υ | Y | Υ | | | | | | | |
| Terminals/lugs/pvc wires(IS- 13947//IS-694) | Υ | | | Υ | Υ | Y | Υ | | | | | | | |
| Timers(IS-3231) | | | | | Υ | Υ | Y | | | | | | | |
| Push Button/ Lamp/ (IS-6875) | | | | | Υ | Υ | Υ | | | | | | | |
| Control Transformer (IS- 12021) | | | | | Y | Y | Y | | | | | | | |
| Mimic, Annunciater | | | | | Υ | | Υ | | | | | | | |
| GASKET(IS-11149) | | Υ | Υ | Υ | Υ | | Υ | | | | | | | |
| Fabrication | | | | | Ť | | | Υ | | | | | | |
| Pretreatment & Painting | | | | | | | | r-sdall | Υ | Υ | | | | |
| VFD panel | | | | | | | | | | Y | Υ | Υ | Υ | Υ |

NOTE:

- This is an indicative list of Test/ Checks. The manufacturer to furnish a detailed Quality Plan indicating the practice and procedure along with relevant supporting documents.
- 2. All major Bought Out Items will be subject to NTPC approval.

| LOT-IA PROJECTS |
|---------------------------|
| FLUE GAS DESULPHURISATION |
| SYSTEM PACKAGE |

TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC. NO CS-0011-109(1A)-2 SUB-SECTION-V-QE13 VFD MODULE PAGE 5 OF 5

| | MANUFACTURER/ BIDDER/ SUPPLIER | STANDARD QUALIT | Y PLAN | SPEC. NO: | DATE: |
|------------|--------------------------------|---------------------|-------------|----------------------------|---------|
| बी एच ई एल | NAME & ADDRESS | CUSTOMER: | | QP NO.: PE-QP-999-145-1056 | DATE: 0 |
| | | PROJECT: | | PO NO.: | DATE: - |
| | | ITEM: LOCAL CONTROL | SYSTEM: C&I | SECTION: C | SHEET 1 |

| SL. NO. | COMPONENT & OPERATIONS | CHARACTERISTICS | CLASS | TYPE OF CHECK | C | NTUM OF ECK | REFERENCE DOCUMENT | ACCEPTANC E NORMS | FORMAT OF RECORD | | , | \GEN | CY | REMARKS |
|------------|------------------------------|----------------------|-------|-------------------|------------|-------------------|---------------------------|---------------------------|--------------------------------|---|-----|------|----|---------|
| 1 | 2 | 3 | 4 | 5 | | 6 | 7 | 8 | 9 | * | | ** | | |
| | | | | | M | C/N | | 0 | 3 | D | M | С | N | |
| | RAW MATERIAL | | | | | | | | | | | | 1 | |
| 1.0 | Sheet Steel (CRCA & HR) | Chemical Composition | MA | Chemical analysis | Samp le | Samp le | IS:1079 IS:513 | IS:1079 IS:513 | Test Certificate | 1 | P/W | V | | |
| | | 2. Bend Test | CR | Mech. test | Samp le | Samp le | IS:1079 IS:513 | IS:1079 IS:513 | Test Certificate | 1 | P/W | V | | |
| | | 3. Surface finish | MA | Visual | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | P/W | | | |
| | | 4. Waviness | МА | Visual | 100% | 10% | Manufacturing Standard | No Waviness | Inspection Report | 1 | P/W | | l | |
| | | 5. Thickness | MA | Measuremen | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 🗸 | P/W | V | | |
| | | 6. Mill marking | MA | Visual | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | ٧ | P/W | ٧ | | |
| 2.0 | Flats / Angles / Channels | 1. Dimensions | MA | Measuremen | Samp le | Samp | IS:2062 | IS:2062 | Test Certificate | 1 | P/W | | | |
| | Chameis | 2. Surface Defects | MA | Visual | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | P/W | | | |
| | | 3. Straightness | MA | Measuremen | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection | 1 | P/W | | | |
| | | 4. Mill marking | MA | τ Visual | 100% | 10% | IS:2062 | IS:2062 | Report Inspection Report | 1 | P/W | V | | n |

| | BHEL | | | | | | | | | | |
|---------------------|-------------|-----------------|--------------|--------------|------------------|--|--|--|--|--|--|
| ENGINEERING QUALITY | | | | | | | | | | | |
| | Sign &.Date | Name | | Sign & Date | Name | | | | | | |
| Prepared by: | trall 12020 | CHETAN MALIK | Checked by: | x-y-do Johan | KUNDAN PRASAD | | | | | | |
| Reviewed by: | Portaba2 | RK RAINA | Reviewed by: | 1421 | RK JAISWAL | | | | | | |
| | 74/21 | | | رط عامه. | | | | | | | |

| | BIC | DER/ SUPPLIER |
|---|-------------|---------------|
| | Sign & Date | |
| 1 | Seal | |
| | | |
| | Pa | ge 370 of 532 |

| | FOR CUSTOMER REVIEW & APPROVAL | | | | | | |
|--------------|--------------------------------|------|------|--|--|--|--|
| Doc No: | | | | | | | |
| | Sign & Date | Name | Seal | | | | |
| Reviewed by: | | | | | | | |
| Approved by: | | | | | | | |

DATE: 07.02.2020

SHEET 1 OF 9

DATE: --

| बीएच ई एल |
|-----------|
| mbles |
| |

| MANUFACTURER/ BIDDER/ SUPPLIER | STANDARD QUALIT | Y PLAN | SPEC. NO: | DATE: |
|--------------------------------|------------------------------|-------------|----------------------------|------------------|
| NAME & ADDRESS | CUSTOMER: | | QP NO.: PE-QP-999-145-I056 | DATE: 07.02.2020 |
| | PROJECT: | | PO NO.: | DATE: |
| | ITEM: LOCAL CONTROL PANEL | SYSTEM: C&I | SECTION: C | SHEET 2 OF 9 |

| SL. NO. | COMPONENT & OPERATIONS | CHARACTERISTICS | CLASS | TYPE OF CHECK | C | NTUM PF ECK | REFERENCE DOCUMENT | ACCEPTANC E NORMS | FORMAT OF RECORE | - | A | GEN | CY | REMARKS |
|------------|--|---|----------------|---|--------------------------|-------------------------|---------------------------------------|---------------------------------------|------------------------|--------|-----|---------|----|-------------------------------|
| 1 | 2 | 3 | 4 | 5 | M | G/N | 7 | 8 | 9 | * D | M | ** C | N | |
| 3.0 | Cables / Wires | Visual / Surface defects | MA | Visual | 100% | 10% | IS:1554 or IS:694 | IS:1554 or IS:694 | Inspection Report | 1 | P/W | | | |
| 1 | | 2. IR and HV | МА | Electrical | 100% | 10% | IS:1554 or IS:694 | IS:1554 or IS:694 | Inspection Report | 1 | P/W | | | |
| | | Conductor a) Resistance b) Size c) Sheet colour | MA MA MA | Electrical Measuremen t Visual | 100% 100% 100% | 10% 10% 10% | IS:1554 or IS:694 | IS:1554 or IS:694 | Inspection Report | 1 | PW | | | - |
| | | Type / Routine Test Certificates | MA | Verification | 100% | 10% | IS:1554 or IS:694 | IS:1554 or IS:694 | Inspection Report | 1 | P/W | | | |
| 4.0 | Electrical Components like Annunciator | Verification at make and Type | CR | Visual | Samp le | Samp le | Approved Drg/Datasheet | Approved Drg/Datasheet | Test Certificate | 1 | P/W | | | , |
| | Transformers Lamps Switches | Verification of Test Certificates | CR | Scrutiny of Type / Routine T.Cs. | 100% | 10% | Relevant Indian Std & Catalogue | Relevant Indian Std & Catalogue | Inspection Report | 1 | P/W | | | |
| | PBs Contactors Relays | Operation / Functional check | CR | Electrical | Sampl e+ 100% @ | Sampl e+ 10% @ | Relevant Indian Std & Catalogue | Relevant Indian Std & Catalogue | Inspection Report | 1 | P/W | | | + for relay & contactors only |

| | BHEL | | | | | | | | | | |
|--------------|---------------------|-----------------|-----------------|-------------|------------------|--|--|--|--|--|--|
| | ENGINEERING QUALITY | | | | | | | | | | |
| | Sign & Date | Name | | Sign & Date | Name | | | | | | |
| Prepared by: | - Wall 19/12/2010 | CHETAN MALIK | Checked by: | X w w w w | KUNDAN PRASAD | | | | | | |
| Reviewed by: | 1/0//1/0// | RK RAINA | Reviewed by: | ועורוספים | RK JAISWAL | | | | | | |
| | 14/2/2 | | | | | | | | | | |

| | BID | DER/ SUPPLIER |
|---------------|-------------|---------------|
| 1 | Sign & Date | |
|] | Seal | |
| l | j | |
| $\frac{1}{2}$ | | |
| | Pa | ge 371 of 532 |

| FOR CUSTOMER REVIEW & APPROVAL | | | | | | |
|--------------------------------|-------------|------|------|---|--|--|
| Doc No: | | | | • | | |
| | Sign & Date | Name | Seal | | | |
| Reviewed by: | | | | | | |
| Approved by: | | | | | | |



| MANUFACTURER/ BIDDER/ SUPPLIER | STANDARD QUALIT | Y PLAN | SPEC. NO: | DATE: |
|--------------------------------|------------------------------|-------------|----------------------------|------------------|
| NAME & ADDRESS | CUSTOMER: | | QP NO.: PE-QP-999-145-I056 | DATE: 07.02.2020 |
| | PROJECT: | | PO NO.: | DATE: |
| | ITEM: LOCAL CONTROL PANEL | SYSTEM: C&I | SECTION: C | SHEET 3 OF 9 |

| SL. NO. | COMPONENT & OPERATIONS | CHARACTERISTICS | CLASS | TYPE OF CHECK | | NTUM OF ECK | REFERENCE DOCUMENT | ACCEPTANC E NORMS | FORMAT OF RECORD | | | AGEN | ICY | REMARKS |
|------------|--------------------------------------|----------------------------------|---------|------------------|------------|-------------------|---------------------------------------|---------------------------------------|------------------------|---|----|------|-----|--|
| 1 | 2 | 3 | 4 | 5 | | 6 | 7 | 8 | 9 | * | | ** | | |
| | | | <u></u> | ļ | M | C/N | | | ļ | D | M | C | N | |
| | Timers, Space Heaters, Thermostat, | 4. I.R. | MA | Electrical | 100% | 10% | Relevant Indian Std & Catalogue | Relevant Indian Std & Catalogue | Inspection Report | 1 | PW | | | @ for all components except relays & contactors. |
| | Indicating meters etc. | 5. H.V. | MA | Electrical | 100% | 10% | Relevant Indian Std & Catalogue | Relevant Indian Std & Catalogue | Inspection Report | 1 | PW | | | d comacions. |
| | | 6. Calibration | MA | Electrical | 100% | 10% | Relevant Indian Std & Catalogue | Relevant Indian Std & Catalogue | Inspection Report | 1 | PW | V | | |
| | | 7. Pick up / Drop off Voltage | MA | Electrical | 100% | 10% | Relevant Indian Std & Catalogue | Relevant Indian Std & Catalogue | Inspection Report | 1 | PW | | | |
| 5.0 | Misc. Components like Gaskets. | Verification of Type / Make | MA | Visual | Samp | Samp | Manufacturing Standard | Manufacturing Standard | Test Certificate | 1 | PW | | | |
| | Terminal Blocks etc. | 2. Surface defects | MA | Visual | Samp le | Samp le | Manufacturing Standard | Manufacturing Standard | Test Certificate | 1 | PW | | | |
| | | 3. IR / HV on Terminal Blocks | MA | Electrical | Samp | Samp le | Manufacturing Standard | Manufacturing Standard | Test Certificate | 1 | PW | | | |
| | IN PROCESS INSPECTION | | | | | | | | | | | | | |

| | BHEL | | | | | | | | | | |
|-----------------------------------|---------------------------------------|----------|-----------------|-------------|---------------|------------------|--|--|--|--|--|
| | ENGINEERING QUALITY | | | | | | | | | | |
| Sign & Date Name Sign & Date Name | | | | | | | | | | | |
| Prepared by: | ليسلا | 4/2/2020 | CHETAN MALIK | Checked by: | X=100/00/2012 | KUNDAN PRASAD | | | | | |
| Reviewed by: | Reviewed RK RAINA Reviewed RK JAISWAL | | | | | | | | | | |

| | | DER/ SUPPLIER |
|---|-------------|---------------|
| | Sign & Date | |
| | Seal | |
| | | |
| 4 | | |
| 1 | Pa | ge 372 of 532 |
| _ | | |

| [| FOR CUSTOMER REVIEW & APPROVAL | | | | | | | | |
|--------------|--------------------------------|------|------|--|--|--|--|--|--|
| Doc No: | | | • | | | | | | |
| | Sign & Date | Name | Seal | | | | | | |
| Reviewed by: | | | | | | | | | |
| Approved by: | | | | | | | | | |

| बी एच ई एल | MANUFACTURER/ BIDDER/ SUPPLIER | STANDARD QUALIT | SPEC. NO: | | | | | |
|------------|--------------------------------|---------------------------|----------------------------|------------|--|--|--|--|
| MICUS CIT | NAME & ADDRESS | CUSTOMER: | QP NO.: PE-QP-999-145-I056 | | | | | |
| | | PROJECT: | | PO NO.: | | | | |
| | | ITEM: LOCAL CONTROL PANEL | SYSTEM: C&I | SECTION: C | | | | |

| SL. NO. | COMPONENT & OPERATIONS | | CHARACTERISTICS | CLASS | TYPE OF CHECK | C | NTUM OF ECK | REFERENCE DOCUMENT | ACCEPTANC E NORMS | FORMAT OF RECORD | | OF | | OF | | OF | | OF AGE | | CY | REMARKS |
|------------|------------------------------------|----|-------------------------------|-------|-------------------|------|-------------------|---------------------------|---------------------------|------------------------|--------|-----|---------|----|--|----|--|--------|--|----|---------|
| 1 | 2 | | 3 | 4 | 5 | M | 6 M C/N | 7 8 | 9 | 9 | * D | М | ** C | N | | | | | | | |
| 6.0 | Blanking / Bending / Forming | 1. | Dimensions | MI | Measuremen t | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | PW | | | | | | | | | |
| | , and the second | 2. | Surface defects after bending | MA | Visual | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | P/W | | | | | | | | | |
| 7.0 | Nibbling / Punching | 1. | Cutout Sizes | МІ | Measuremen t | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | ٧ | P/W | | | | | | | | | |
| | | 2. | Deburring | MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | | | | | | | | | |
| | ASSEMBLY | | | | | | | | | | | | | | | | | | | | |
| 8.0 | Frame Assembly & Sheet fixing | 1. | Dimensions | MA | Measuremen t | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | | | | | | | | | |
| | | 2. | Alignment | MA | Measuremen t | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | | | | | | | | | |
| | | 3. | Welding Quality | MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | | | | | | | | | |
| | | 4. | Surface defects | MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | | | | | | | | | |

| BHEL | | | | | | | | | |
|-----------------|-------------|-----------------|----------------|---------------|------------------|--|--|--|--|
| _ | ENGINEERIN | G | QUALITY | | | | | | |
| | Sign & Date | Name | | Sign & Date | Name | | | | |
| Prepared by: | Jan Jan | CHETAN MALIK | Checked by: | X-rugan Helye | KUNDAN PRASAD | | | | |
| Reviewed by: | O posson | RK RAINA | Reviewed by: | किया | RK JAISWAL | | | | |
| | Jab I | | | , , | | | | | |

| | BIDDER/ SUPPLIER | | | | | | | |
|---|------------------|---------------|--|--|--|--|--|--|
| | Sign & Date | | | | | | | |
| | Seal | | | | | | | |
| | | | | | | | | |
| ' | | | | | | | | |
| | Pa | ge 373 of 532 | | | | | | |

| | FOR CUSTOMER REVIEW & APPROVAL | | | | | | | | |
|--------------|--------------------------------|------|------|--|--|--|--|--|--|
| Doc No: | | | | | | | | | |
| | Sign & Date | Name | Seal | | | | | | |
| Reviewed by: | | | | | | | | | |
| Approved by: | | | | | | | | | |

DATE:

DATE: --

DATE: 07.02.2020

SHEET 4 OF 9



| MANUFACTURER/ BIDDER/ SUPPLIER | STANDARD QUALIT | Y PLAN | SPEC. NO: | DATE: |
|--------------------------------|------------------------------|-------------|----------------------------|------------------|
| NAME & ADDRESS | CUSTOMER: | | QP NO.: PE-QP-999-145-I056 | DATE: 07.02.2020 |
| | PROJECT: | | PO NO.: | DATE: |
| | ITEM: LOCAL CONTROL PANEL | SYSTEM: C&I | SECTION: C | SHEET 5 OF 9 |

| SL. NO. | COMPONENT & OPERATIONS | CHARACTERISTICS | CLASS | TYPE OF CHECK | C | NTUM DF ECK | REFERENCE DOCUMENT | ACCEPTANC E NORMS | FORMAT OF RECORD | | OF AGENCY | | CY | REMARKS |
|------------|----------------------------|---|-------|----------------------|------------------|-------------------|---------------------------|---------------------------|------------------------|----------|-----------|---------------|----|---------|
| 1 | 2 | 3 | 4 | 5 | | 6 | 7 | 8 | 9 | * D | | ** | | |
| 9.0 | Pre-treatment and Painting | Pretreatment Process | MA | Visual | M 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | √ | P/W | <u>с</u> v | N | |
| | | Process parameters like bath temp. concentration etc. | MA | Measuremen t | Perio dic | Perio dic | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | P/W | V | | |
| | | 3. Dipping / Removal Time | MA | Measuremen t | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | P/W | V | | |
| | | Surface quality after every dip | MA | Visual | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | PW | V | | |
| | | Primer after phosphating | MA | Visual, Thickness | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | ٧ | PW | V | | |
| | | 6. Putty Application & Rubbing after primer | MA | Visual | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | P/W | v | | |
| | | 7. Paint first coat | MA | Visual, Thickness | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | P/W | V | | |

| | BHEL | | | | | | | | | | |
|--------------|------------|----------|-----------------|--------------|------|--------------------|-------|------------------|--|--|--|
| | ENG | INEERIN | G | QUALITY | | | | | | | |
| | Sign & | Date | Name | | Sign | 1 & | Date | Name | | | |
| Prepared by: | لموستكر | 4/2/2020 | CHETAN MALIK | Checked by: | XA | Jan 1 | HOUND | KUNDAN PRASAD | | | |
| Reviewed by: | Por | 220 | RK RAINA | Reviewed by: | टि | रे दे <u>१५</u> | 4 | RK JAISWAL م | | | |
| | [d] Strain | | | | | | | | | | |

| | | BIDDER/ SUPPLIER | | | | | | | | | |
|---|--------|------------------|---------------|--|--|--|--|--|--|--|--|
| 7 | Sign 8 | & Date | | | | | | | | | |
|] | Seal | | | | | | | | | | |
| 1 | | | | | | | | | | | |
| 4 | | | | | | | | | | | |
| ١ | | Pa | ge 374 of 532 | | | | | | | | |
| _ | | | | | | | | | | | |

| | FOR CUSTOMER REVIEW & APPROVAL | | | | | | | |
|-----------------|--------------------------------|------|------|--|--|--|--|--|
| Doc No: | | | | | | | | |
| | Sign & Date | Name | Seal | | | | | |
| Reviewed by: | | | | | | | | |
| Approved by: | | | | | | | | |



| | MANUFACTURER/ BIDDER/ SUPPLIER | STANDARD QUALITY | PLAN | SPEC. NO: | DATE: | | |
|--|--------------------------------|------------------------------|-------------|----------------------------|------------------|--|--|
| | NAME & ADDRESS | CUSTOMER: | | QP NO.: PE-QP-999-145-I056 | DATE: 07.02.2020 | | |
| | , | PROJECT: | | PO NO.: | DATE: | | |
| | | ITEM: LOCAL CONTROL PANEL | SYSTEM: C&I | SECTION: C | SHEET 6 OF 9 | | |

| SL. NO. | COMPONENT & OPERATIONS | CHARACTERISTI | CS CLASS | TYPE OF CHECK | QUANTUM OF CHECK | | REFERENCE DOCUMENT ACCEPTANC E NORMS | | FORMAT OF RECORD | | AGENCY | | | REMARKS |
|------------|------------------------|---|----------|---|------------------------|-----|--------------------------------------|---------------------------|------------------------|---|--------|----|---|---------|
| 1 | 2 | 3 | 4 | 5 | | 6 | 7 | 8 | 9 | * | | ** | | |
| 1 | 2 | | 4 | 5 | M | C/N | <u>'</u> | 0 | 9 | D | M | С | N | |
| | | 8 Putty Application Rubbing after firs of paint | | Visual | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | P/W | V | | |
| | | 9. Paint second coa | nt MA | Visual, Thickness, Scratch test Colour adhesion | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | ٧ | P/W | V | | |
| 10. | Panel Wiring | 1. Wiring Layout | MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | | | |
| | | Wiring Termination (Crimped Lugs) | on MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | | | |
| | | 3. Ferrule numbers | MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | | | |
| | | 4. Colour of wiring | MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | ٧ | | |
| | | 5. Size of Conducto | or MA | Measuremen t | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | ٧ | | |
| 11. | Component Mounting | Correct compone | ents MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | ٧ | P/W | | | |
| | | 2. Fixing | MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | | | |

| | BHEL | | | | | | | | | | | | |
|--------------|-----------------|-----------------|--------------|-------------|------------------|--|--|--|--|--|--|--|--|
| | ENGINEERIN | IG | QUALITY | | | | | | | | | | |
| | Sign & Date | Name | | Sign & Date | Name | | | | | | | | |
| Prepared by: | touch 19/2/1020 | CHETAN MAĻIK | Checked by: | A7/4/01200 | KUNDAN PRASAD | | | | | | | | |
| Reviewed by: | 0000 | RK RAINA | Reviewed by: | हिर्म । | RK JAISWAL | | | | | | | | |
| | Japi | | | | | | | | | | | | |

| | BID | DER/ SUPPLIER |
|---|-------------|----------------|
| | Sign & Date | |
| | Seal | |
| ı | | |
| - | | |
| | Pa | age 375 of 532 |
| _ | | |

| | FOR CUSTOMER REVIEW & APPROVAL | | | | | | | | | | |
|-----------------|--------------------------------|------|------|---|--|--|--|--|--|--|--|
| Doc No: | | | | | | | | | | | |
| | Sign & Date | Name | Seal | | | | | | | | |
| Reviewed by: | | | | ! | | | | | | | |
| Approved by: | | | | | | | | | | | |

| | MANUFACTURER/ BIDDER/ SUPPLIER | STANDARD QUALIT | Y PLAN | SPEC. NO: | | |
|------------|--------------------------------|---------------------|----------------------------|------------|--|--|
| बी एच ई एल | NAME & ADDRESS | CUSTOMER: | QP NO.: PE-QP-999-145-I056 | | | |
| | | PROJECT: | | PO NO.: | | |
| | | ITEM: LOCAL CONTROL | SYSTEM: C&I | SECTION: C | | |

| SL. NO. | COMPONENT & OPERATIONS | | CHARACTERISTICS | CLASS | TYPE OF CHECK | QUANTUM OF CHECK | | REFERENCE DOCUMENT | ACCEPTANC E NORMS | FORMAT OF RECORD | | AGENCY | | | REMARKS |
|------------|------------------------|----|---|-------|------------------|------------------------|-----|---------------------------|---------------------------|------------------------|----|--------|----------|---|---|
| 1 | 2 | | 3 | 4 | 5 | 6 7 | | 8 | 9 | * | ** | | | | |
| | | | · · · · · · · · · · · · · · · · · · · | | | М | C/N | | | | D | M | С | N | |
| | FINAL TESTING | | | | | | | | | | | | | | · |
| 12. | Final Inspection | 1. | Workmanship | MA | Visual | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | P/W | w | | |
| | | 2. | Component layout (neatness, accessibility & safety) Mounting / Proper fixing of all components | MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | * | | At Random by BHEL, based on 100 % internal test reports by |
| | | 3. | Components identification Marking / Name plates | MA | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | w | | Mfr. |
| | | 5. | Dimensions | MA | Measuremen t | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | W | | |
| | | 6. | Door functioning | MA | Functional | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | PW | w | | At Random by BHEL, based on 100 % |
| | | 7. | Paint Shade | CR | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | PW | w | | internal test reports by Mfr. |

| | BHEL | | | | | | | | | | | | |
|--------------|-------------|-----------------|--------------|---------------|------------------|--|--|--|--|--|--|--|--|
| | ENGINEERIN | G | QUALITY | | | | | | | | | | |
| | Sign & Date | Name | | Sign & Date | Name | | | | | | | | |
| Prepared by: | 19/2/2020 | CHETAN MALIK | Checked by: | Xu day al 200 | KUNDAN PRASAD | | | | | | | | |
| Reviewed by: | 02/2/20 | RK RAINA | Reviewed by: | 14/2/20 | RK JAISWAL | | | | | | | | |
| | July | | | • • | | | | | | | | | |

| | | DER/ SUPPLIER |
|----|-------------|---------------|
| | Sign & Date | |
| | Seal | |
| | | |
| ┩ | | |
| ۱- | Pa | ge 376 of 532 |
| _ | | l . |

| | FOR CUSTOMER REVIEW & APPROVAL | | | | | | | | | | | |
|--------------|--------------------------------|------|------|---|--|--|--|--|--|--|--|--|
| Doc No: | | | | | | | | | | | | |
| | Sign & Date | Name | Seal | _ | | | | | | | | |
| Reviewed | | | | | | | | | | | | |
| by: | | | | | | | | | | | | |
| Approved by: | | | | | | | | | | | | |

DATE:

DATE: --

DATE: 07.02.2020

SHEET 7 OF 9

| बीएचई एल |
|----------|
| militar |
| |

STANDARD QUALITY PLAN SPEC. NO: DATE: MANUFACTURER/ BIDDER/ SUPPLIER NAME & ADDRESS CUSTOMER: QP NO.: PE-QP-999-145-I056 DATE: 07.02.2020 PROJECT: PO NO.: --DATE: --ITEM: LOCAL CONTROL SYSTEM: C&I **SECTION:** C SHEET 8 OF 9 **PANEL**

| SL. NO. | COMPONENT & OPERATIONS | CHARACTERISTICS | CLASS | TYPE OF CHECK | QUANTUM OF CHECK | | REFERENCE DOCUMENT | ACCEPTANC E NORMS | FORMAT OF RECORD | | AGENCY | | | REMARKS |
|------------|------------------------|---------------------------|-------|---------------------|------------------------|------------|---|---|--------------------------|--------------|--------|---|---|---------|
| 1 | 2 | 3 | 4 | 5 | | 6 | 7 | 8 | 9 | * | ** | | · | |
| • | <u> </u> | <u> </u> | | | M | C/N | <u> </u> | <u> </u> | | D | M | С | N | |
| | | 8. Paint Thickness | CR | Measuremen t | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | W | | |
| | | Workmanship of Gaskets | MA | Visual | 100% | 10% | Manufacturing Standard | Manufacturing Standard | Inspection Report | 1 | P/W | w | | |
| | | 10. Wiring Layout | МА | Visual | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | w | | |
| | | 11. Wire Termination | MA | Pulling manually | Samp le | Samp le | | Firm termination | Inspection Report | 1 | PW | w | | |
| | | 12. Continuity | MA | Electrical | 100% | 10% | | Continuity OK | Inspection Report | 1 | P/W | w | | |
| | | | | | | | | | | | | | | |
| 13. | TYPE TEST | Degree of Protection | CR | Mech. Protection | Samp le | Samp le | Approved Drg/Datasheet | Approved Drg/Datasheet | Type Test Certificate | 1 | P/W | V | | |
| | | | | | | | Relevant IS- 13947 Part-1, IS-2148. | Relevant IS- 13947 Part-1, IS-2148. | | | | | | |
| 14 | ROUTINE TEST | IR before & after HV Test | CR | Electrical | 100% | 10% | Approved Drg/Datasheet Relevant IS. | Approved Drg/Datasheet Relevant IS. | Inspection Report | 1 | P/W | w | | |

| BHEL | | | | | | | | |
|--------------|----------------|-----------------|----------------|-------------------|------------------|--|--|--|
| | ENGINEERIN | G | QUALITY | | | | | |
| | Sign & Date | Name | | Sign & Date | Name | | | |
| Prepared by: | Tuel 11/2/1020 | CHETAN MALIK | Checked by: | KAN GON ON JOVO | KUNDAN PRASAD | | | |
| Reviewed by: | 0/1000 | RK RAINA | Reviewed by: | fertal 142tran | RK JAISWAL | | | |
| | 14/17 | | | | | | | |

| BIDDER/ SUPPLIER | | | | | | | |
|------------------|--|--|--|--|--|--|--|
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| FOR CUSTOMER REVIEW & APPROVAL | | | | | | |
|--------------------------------|-------------|------|------|--|--|--|
| Doc No: | | | | | | |
| | Sign & Date | Name | Seal | | | |
| Reviewed by: | | | | | | |
| Approved by: | | | | | | |

| बीएच ईएल | MANUFACTUF NAME & ADDF |
|----------|---------------------------|
| BHEL | |

| MANUFACTURER/ BIDDER/ SUPPLIER NAME & ADDRESS | STANDARD QUALIT | Y PLAN | SPEC. NO: | DATE: |
|--|------------------------------|-------------|----------------------------|------------------|
| | CUSTOMER: | | QP NO.: PE-QP-999-145-I056 | DATE: 07.02.2020 |
| | PROJECT: | | PO NO.: | DATE: |
| | ITEM: LOCAL CONTROL PANEL | SYSTEM: C&I | SECTION: C | SHEET 9 OF 9 |

| SL. NO. | COMPONENT & OPERATIONS | CHARACTERISTICS | CLASS | TYPE OF CHECK | | QUANTUM OF CHECK REFERENCE DOCUMENT | | | | | , | \GEN | ICY | REMARKS |
|------------|------------------------|-----------------------------|-------|------------------|------|-------------------------------------|---|---|----------------------|---|-----|------|-----|---------|
| 4 | 2 | 3 | 1 | 5 | 1 | 6 | - | | 9 | * | | ** | | |
| 1 | | 3 | 4 | 5 | M | C/N | 7 8 | | D | М | С | N | | |
| 15 | FUCTIONAL TEST | Control Logic Operation | CR | Electrical | 100% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | PW | w | | |
| | | 2. Instrument Calibration | CR | Electrical | 10% | 10% | Approved Drg/Datasheet | Approved Drg/Datasheet | Inspection Report | 1 | P/W | w | | |
| | | 3. Temperature rise | CR | Electrical | 100% | 10% | Approved Drg/Datasheet Relevant IS. | Approved Drg/Datasheet Relevant IS. | Inspection Report | 1 | P/W | w | | |

NOTES:

- 1. Customer's specification for painting shall be included in the technical specification. In the absence of Customer's spec. for painting, vendor to obtain BHEL's approval on their painting specification / procedure.
- 2. Copies of all TC's (Test Certificates) for components shall be submitted to BHEL for verification and acceptance.
- 3. BHEL reserves the right to conduct repeat tests, if required.

LEGENDS:

*RECORDS, INDENTIFIED WITH "TICK"(1) SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION, D: DOCUMENTATION,

** M: SUPPLIER/ MANUFACTURER/ SUB-SUPPLIER, C: MAIN SUPPLIER/ BHEL/ THIRD PARTY INSPECTION AGENCY, N: CUSTOMER,

P: PERFORM, W: WITNESS, V: VERIFICATION, AS APPROPRIATE

MA: MAJOR, MI: MINOR, CR: CRITICAL

| BHEL | | | | | | | | |
|---------------------|-------------|------------|----------|-------------|------------|--|--|--|
| ENGINEERING QUALITY | | | | | | | | |
| | Sign & Date | Name | | Sign & Date | Name | | | |
| Prepared | - alle | CHETAN | Checked | X7 y WONDO | KUNDAN | | | |
| by: | 14/2/2020 | MALIK | by: | Ar Schlon. | PRASAD | | | |
| Reviewed | 1741 | DIV DAINIA | Reviewed | 100 | RK JAISWAL | | | |
| by: | 14/2/2020 | | by: | 14/2/2 | 220 | | | |

| | BIDDER/ SUPPLIER | | | | | | |
|---|------------------|-----------------|--|--|--|--|--|
| | Sign & Date | | | | | | |
|] | Seal | | | | | | |
| | | | | | | | |
| 4 | | | | | | | |
| | | Page 378 of 532 | | | | | |
| ┚ | | | | | | | |

| | FOR CUSTOMER REVIEW & APPROVAL | | | | | |
|--------------|--------------------------------|------|------|--|--|--|
| Doc No: | | | | | | |
| | Sign & Date | Name | Seal | | | |
| Reviewed by: | | | | | | |
| Approved by: | | | | | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS एनरीपीसी NTPC | | | | | | |
|--------------|---|--|--|--|--|--|--|
| 1.00.00 | TYPE TEST REQUIREMENTS | | | | | | |
| 1.01.00 | General Requirements | | | | | | |
| 1.01.01 | The Contractor shall furnish the type test reports of all type tests as per relevant standards and codes as well as other specific tests indicated in this specification. If the bidder proposes a different standard/code from that indicated at clause no 2.01.00 and at table 3.00.00, same is acceptable provided the equivalence of the proposed standard is established by the bidder. A list of such tests are given for various equipment in table titled 'TYPE TEST REQUIREMENT FOR OTHER C&I SYSTEMS' at the end of this chapter and under the item "Special Requirement for Solid State Equipments/Systems". | | | | | | |
| | (a) Out of the tests listed, the Bidder/ sub-vendor/ manufacturer is required to conduct certain type tests specifically for this contract (and witnessed by Employer or his authorized representative) even if the same had been conducted earlier, as clearly indicated subsequently against such tests. | | | | | | |
| | (b) For the rest, submission of type test results and certificate shall be acceptable provided. | | | | | | |
| | The same has been carried out by the Bidder/ sub-vendor on exactly the same model /rating of equipment. | | | | | | |
| | ii. There has been no change in the components from the offered equipment & tested equipment. | | | | | | |
| | iii. The test has been carried out as per the latest standards alongwith amendments as on the date of Bid opening. | | | | | | |
| | (c) In case the approved equipment is different from the one on which the type test had been conducted earlier or any of the above grounds, then the tests have to be repeated and the cost of such tests shall be borne by the Bidder/ sub-vendor within the quoted price and no extra cost will be payable by the Employer on this account. | | | | | | |
| 1.01.02 | The schedule of conduction of type tests/ submission of reports shall be submitted and finalized during pre-award discussion. | | | | | | |
| 1.01.03 | For the type tests to be conducted, Contractor shall submit detailed test procedure for approval by Employer. This shall clearly specify test setup, instruments to be used, procedure, acceptance norms (wherever applicable), recording of different parameters, interval of recording precautions to be taken etc. for the tests to be carried out. | | | | | | |
| 1.01.04 | The Bidder shall indicate in the relevant BPS schedule, the cost of the type test for each item only for which type tests are to be conducted specifically for this project. The cost shall only be payable after conduction of the respective type test in presence of authorize representative of Employer. If a test is waived off, then the cost shall not be payable. | | | | | | |
| 2.00.00 | SPECIAL REQUIREMENT FOR SOLID STATE EQUIPMENTS/ SYSTEMS | | | | | | |
| 2.01.00 | The type test reports which are to be submitted for each of the C&I systems(indicated in clause 2.01.01) shall be as indicated below: | | | | | | |
| | i) Surge Withstand Capability (SWC) for Solid State Equipments/ Systems | | | | | | |
| | All solid state systems/ equipments shall be able to withstand the electrical noise | | | | | | |
| FLUE GAS DES | 4 PROJECTS SULPHURISATION (FGD) TEM PACKAGE TECHNICAL SPECIFICATION SECTION – VI, PART-A BID DOC. NO.:CS-0011-109(4)-9 Page 379 of 532 SUB-SECTION-IIIC-6 TYPE TEST REQUIREMENTS | | | | | | |

| CLAUSE NO. | | TECHNICAL REQU | JIREMENTS | | एनरीपीमी NTPG | | | | | |
|------------|-----------|---|--|---|---|--|--|--|--|--|
| | | and surges as encountered in actual service conditions and inherent in a power plant. All the solid state systems/ equipments shall be provided with all required protections that needs the surge withstand capability as defined in ANSI / IEEE C37.90.1 Hence, all front end cards/ devices which receive external signals like Analog input & output modules, Binary input & output modules etc. including power supply, data highway, data links shall be provided with protections that meets the surge withstand capability as defined in ANSI / IEEE C37.90.1. Complete details of the features incorporated in electronics systems to meet this requirement, the relevant tests carried out, the test certificates etc. shall be submitted along with the proposal. As an alternative to compliance to ANSI / IEEE C37.90.1, the system shall comply to IEC-61000-4-4, IEC-61000-4-5 and IEC-61000-4-18. | | | | | | | | |
| | ii) | Dry Heat test as per IEC-60068-2-2 of | or equivalent. | | | | | | | |
| | iii) | Damp Heat test as per IEC-60068-2- | 30 or IEC-60068-2 | 2-78 or equivaler | nt. | | | | | |
| | iv) | Vibration test as per IEC-60068-2-6 | or equivalent. | | | | | | | |
| | v) | Electrostatic discharge tests as per II | EC 61000-4-2 or e | quivalent. | | | | | | |
| | vi) | Radio frequency immunity test as pe | r IEC 61000-4-6 o | equivalent. | | | | | | |
| | vii) | Electromagnetic Field immunity as pe | er IEC 61000-4-3 o | or equivalent. | | | | | | |
| | | | | | | | | | | |
| 2.01.01 | | Systems- | | | | | | | | |
| | SI. No | Item | Remark | Test To Be Specifically Conducted | NTPC's Approval Req. On Test Certificate | | | | | |
| | 1 | Control System of DDCMIS | | No | Yes | | | | | |
| | 2 | PLC, excluding its HMI | Not applicable for integral PLCs and PLCs which are governed by standard practice of OEM | No | Yes | | | | | |
| | 3 | VMS System (Applicable for each module of VMS) | | No | Yes | | | | | |
| | 4 | Main Turbine & BFP Drive Turbine TSI System (Applicable for each module of TSI System) | | No | Yes | | | | | |
| | 5 | Vibration Analysis System (Applicable for each module of Vibration Analysis System) | | No | Yes | | | | | |
| | <u> </u> | | | <u> </u> | | | | | | |

| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | | | |
|--------------|---|---|-------------------|---------------------------------------|----------------|--|--|
| | Auto synchron | Special modules like izer, Load transducer speed measurement | N | lo Y | 'es | | |
| | 7 Master Clock | | N | lo Y | ⁄es | | |
| | Note: Type Tests are to be eackage. | conducted only for the ite | ems, which are be | ing supplied as | a part of this | | |
| | S | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| FLUE GAS DES | 4 PROJECTS ULPHURISATION (FGD) EM PACKAGE | TECHNICAL SPECIFICA SECTION – VI, PART BID DOC. NO.:CS-0011-1 | -A TY | ECTION-IIIC-6 PE TEST JIREMENTS | PAGE 3 OF 8 | | |

Page 381 of 532

| CLAUSE NO. | TECHNICAL REQUIREMENTS | | | | | | |
|--------------|---|---------------------------|--|------------------------|---|---|--|
| 3.00.00 | TYPE TEST REQUIREMENT FOR OTHER C&I SYSTEMS | | | | | | |
| | SI. No | Item | Test Requirement | Standard | Test To Be Specifically Conducted | NTPC's Approval Req. On Test Certificate | |
| | Col 1 | Col 2 | Col 3 | Col 4 | Col 5 | Col 6 | |
| | 1 | Electronic transmitter | As per standard (col 4) | BS-6447 / IE 60770 | C- No | Yes | |
| | 2 | Instrumentation | n Cables Twisted & S | Shielded* | | | |
| | | -Conductor | Resistance test | VDE-0815 | No | Yes | |
| | | | Diameter test | IS-10810 | No | Yes | |
| | | | Tin Coating test (Persulphate test) | IS-8130 | No | Yes | |
| | | -Insulation | Loss of mass | VDE 0472 | No | Yes | |
| | | | Ageing in air ovens** | VDE 0472 | No | Yes | |
| | | | Tensile strength and elongation test before and after ageing** | VDE 0472 | No | Yes | |
| | | | Heat shock | VDE 0472 | No | Yes | |
| | | | Hot deformation | VDE 0472 | No | Yes | |
| | | | Shrinkage | VDE 0472 | No | Yes | |
| | | | Bleeding & blooming | IS-10810 | No | Yes | |
| | | -Inner sheath* | * Loss of mass | VDE 0472 | No | Yes | |
| | | | Heat shock | VDE 0472 | No | Yes | |
| | | | Cold bend/ cold impact test | VDE 0472 | No | Yes | |
| | | | Hot | VDE 0472 | No | Yes | |
| FLUE GAS DES | 4 PROJE SULPHUR EM PACE | ISATION (FGD) | TECHNICAL SPEC SECTION – VI, F BID DOC. NO.:CS-00 Page 382 of 5 | PART-A 011-109(4)-9 | SUB-SECTION-IIIC-6 TYPE TEST REQUIREMENTS | PAGE 4 OF 8 | |

| CLAUSE NO. | 1 | ECHNICAL REQ | UIREMENTS | | एनदीपीमी NTPC |
|-----------------|---|---|------------------------|---|------------------|
| | | deformation | | | |
| | | Shrinkage | VDE 0472 | No | Yes |
| | -Outer sheath | Loss of mass | VDE 0472 | No | Yes |
| | | Ageing in air ovens** | VDE 0472 | No | Yes |
| | | Tensile strength and elongation test before and after ageing** | VDE 0472 | No | Yes |
| | | Heat shock | VDE 0472 | No | Yes |
| | | Hot deformation | VDE 0472 | No | Yes |
| | | Shrinkage | VDE 0472 | No | Yes |
| | | Bleeding & blooming | IS-10810 | No | Yes |
| | | Colour fastness to water | IS-5831 | No | Yes |
| | | Cold bend/ cold impact test | VDE-0472 | No | Yes |
| | | Oxygen index test | ASTMD-2863 | No | Yes |
| | | Smoke Density Test | ASTMD-2843 | No | Yes |
| | | Acid gas generation test | IEC-60754-1 | No | Yes |
| | -fillers | Oxygen index test | ASTMD-2863 | No | Yes |
| | | Acid gas generation test | IEC-60754-1 | No | Yes |
| | -AL-MYLAR shield | Continuity test | | No | Yes |
| | | Shield thickness | | No | Yes |
| | | Overlap test | | No | Yes |
| FLUE GAS DESULF | ROJECTS PHURISATION (FGD) PACKAGE | TECHNICAL SPEC SECTION – VI, F BID DOC. NO.:CS-00 Page 383 of 5 | PART-A 911-109(4)-9 | SUB-SECTION-IIIC-6 TYPE TEST REQUIREMENTS | PAGE 5 OF 8 |

| CLAUSE NO. | TE | TECHNICAL REQUIREMENTS | | | | |
|-----------------|---|---|--|---|--|--|
| | -Over all cable | Flammability Test | IEEE 383 | No | Yes | |
| | | Swedish Chimney Test | SEN 42414 | 75 No | Yes | |
| | | Noise interference | IEEE Tra | ans- No | Yes | |
| | | Dimensional checks | IS 10810 | No | Yes | |
| | | Cross talk | VDE-0472 | No | Yes | |
| | | Mutual capacitance | VDE-0472 | No | Yes | |
| | | HV test | VDE-0815 | No | Yes | |
| | | Drain wire continuity | | No | Yes | |
| | conducted within report(s) are not shall conduct all works in presence Owner and subm | last Ten years from to be meeting such tests either the end of Owner's reports for a small be carried of d & outer sheather | om the date of ing the specifi in an indepen resentative un approval. ut as per VE ed cables | bid opening, or cation requirem dent laboratory nder this contra | t of the type test(s) in case the type test ents, the Contractor or at manufacturer's ct free of cost to the & ASTMD-2116 for | |
| | DC Power Supply 1)The Type Tes irrespective of the | t reports for offe | ered rectifier | module and th | () ne controller module | |
| | | Surge Withstand Capability(SWC) | (ANSI / C37.90.1)or (IEC-61000-4 and IEC-64-18). | -4-4, 4-5 | Yes | |
| | | Dry Heat Test | IEC-60068-2 or equivale | | Yes | |
| FLUE GAS DESULF | ROJECTS PHURISATION (FGD) PACKAGE | TECHNICAL SPEC SECTION - VI, I BID DOC. NO.:CS-00 Page 384 of 9 | PART-A 011-109(4)-9 | SUB-SECTION- TYPE TES' REQUIREMEI | T 6 OF 8 | |

| CLAUSE NO. | | - | TECHNICAL REQUIREMENTS | | | एनरीपीसी NTPC |
|---------------------|--------------------------------|---------------|--|---|--------------------------------------|-----------------------|
| | | | Damp Heat test | IEC-60068- or IEC-600 78 or equiv | 068-2· | Yes |
| | | | Vibration test | IEC-60068- or equivale | | Yes |
| | | | Electrostatic discharge test | IEC 6100 or equivale | 00-4-2 No nt | Yes |
| | | | Radio frequency immunity test | IEC-61000- or equivale | | Yes |
| | | | Electromagneti c field immunity | IEC 6100 or equiva | 00-4-3 No lent | Yes |
| | | | Degree of Protection | IS-13947 equivalent | oı No | Yes |
| | 4 | Battery ## | As per standard (col 4) | IS-10918 Cd Batterie | ` | Yes |
| | | | (**) | IS-1652 (Lead / Plante Batteries) | Acid No | |
| | 5 | | ole for each model a | | h similar PCB's | cards and controllers |
| | | _ | | • | tests conducted | d on individual PCB's |
| | | · | Surge Withstand Capability(SWC) | (ANSI / C37.90.1)o (IEC-61000- IEC-61000- and IEC-6 4-18). | r)-4-4, -4-5 | Yes |
| | | | Dry Heat Test | IEC-60068- or equivale | | Yes |
| | | | Damp Heat test | IEC-60068- or IEC-600 78 or equiv | 068-2· | Yes |
| | | | Vibration test | IEC-60068- or equivale | | Yes |
| FLUE GAS DES | 4 PROJE(ULPHURI EM PACK | ISATION (FGD) | TECHNICAL SPEC SECTION – VI, I BID DOC. NO.:CS-00 Page 385 of 5 | PART-A 011-109(4)-9 | SUB-SECTION TYPE TES REQUIREME | ST 7 OF 8 |

| CLAUSE NO. | | | TECHNICAL REQ | UIREMENT | S | एनशैपीसी NTPC |
|------------|----------------------------|--|--|---|--|---|
| | | | Electrostatic discharge test | IEC 6100 or equivaler | 00-4-2 No nt | Yes |
| | | | Radio frequency immunity test | IEC-61000- or equivaler | | Yes |
| | | | Electromagnetic field immunity | IEC 6100 or equival | 00-4-3 No lent | Yes |
| | | | Degree of protection test | IS-13947 | No | Yes |
| | | | Fuse Clearing Capability | Approved procedure | No | Yes |
| | | | Short Circuit current capability | IEC 60146- | 2 No | Yes |
| | 6 | Public Address | s System | | | |
| | | IP based system components | PA As per Standard | IEC 60268- | -16 No | Yes |
| | 7 | Control Valves | CV test | ISA 75.0 75.11 | 02& No | Yes |
| | 8 | Flow Noz Orifice plates | zle Calibration | ASME PTC BS 1042 | No | Yes |
| | latest should repres | IS-10918 carried I have been eith entative. The co | all submit for Employ d out within last ten y ner conducted at an omplete type test repo dimensions being ma | ears from the independent orts shall be | ne date of Bid op laboratory or in for any rating of | ening and the test(s) presence of owner's |
| | Note: | | | | | |
| | Type Tecka | | conducted only for th | e items, whic | ch are being sup | plied as a part of this |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| LOT- | 4 PROJE | | TECHNICAL SPECII SECTION – VI. P | | SUB-SECTION- | IIC-6 PAGE |



C&I SPECIFICATION FOR HVAC SYSTEM

SECTION: C SUB SECTION: C&I

MANDATORY SPARES

| CLAUSE NO. | MANDATORY SPARES (FOR EACH PROJECT) एन्हेंपीवी NTPC | | | | |
|------------|---|-------------------------|---|-------------------------------------|--|
| | | | | | |
| | 3.0 | Control & In | strumentation | | |
| | i) | Air-Condition | ing System | | |
| | 3.1 | Electronic Tr | ansmitters | | |
| | 3.1.1 | the measure | of all types and model no. (fo ement of Pressure, differentia v, level, temperature etc.) | I and model with more. (to be | whichever is |
| | 3.2 | Temperature | elements | | |
| | 3.2.1 | RTD's* | | 5% or 1 No. v more ** | which ever is |
| | 3.2.2 | Thermo well | | 5% or 1 No. v | which ever is |
| | | * (With head nipple) | assembly, terminal block and | | divided into on lengths in to main |
| | 3.3 | All types of L | ocal Indicators | proportion | be whichever be divided to anges in to main and to make, |
| | 3.4 | | | | of each type whichever is |
| | 3.5 | Relative Hun | nidity Sensors | 1 No. | |
| | 3.6 | Geyserstat | | 1 No. | |
| | 3.7 | Local Humid | ity/Temperature indicators | 2 Nos. each | |
| | Process Connection Piping (for Impulse Piping / Tubing, Sampling Piping / | | | | |
| FLUE GAS D | OT-4 PROJECT ESULPHURISA STEM PACKA | ATION (FGD) | TECHNICAL SPECIFICATION SECTION – VI, PART-A BID DOC. NO.:CS-0011-109(4)-9 | SUB-SECTION-VII MANDATORY SPARES | PAGE 15 OF 63 |

| CLAUSE NO. | | | MANDA | TORY SP | ARES | | | एनदीपीमी NTPC |
|------------|---|--|----------|--|----------|----|---|---|
| | 4.1 4.2 | Tubing an Applicable) Valves 2 way, 3way, | | | . • | as | 10% or 1 No. class, size whichever is m 10% or 1 No. class, size whichever is m | and model nore. of each type, and model |
| | 4.3 | Fittings | | | | | 10% or 1 No. class, size whichever is m | of each type, and model |
| | (II) | Ventilation S | ystem | | | | | |
| | 5.0 | Measuring I | nstrume | ents | | | | |
| | 5.1 | Pressure Ga | uge | | | | 1 No. (for pumps of UAF | centrifugal units). |
| | 5.2 | Level transm | itter | | | | 1 No. | |
| | 5.3 | Pressure trar | nsmitter | | | | 1 No. (for UAF | units) |
| | 6.0 | Process Co Piping / T Tubing an Applicable) | ubing, | | g Piping | | | |
| | 6.1 | Valves | | | | | 1 no. of each size and mode | |
| | 6.2 | 2 way valve ı | manifold | | | | 1 no. of each size and mode | |
| | 6.3 | Fittings | | | | | 1 no. of each size and mode | • • |
| | | | | | | | | |
| FLUE GAS D | OT-4 PROJECT ESULPHURIS, STEM PACKA | ATION (FGD) | s | HNICAL SPEC ECTION – VI, F OC. NO.:CS-00 | PART-A | M | SUB-SECTION-VII ANDATORY SPARES | PAGE 16 OF 63 |



C&I SPECIFICATION FOR HVAC SYSTEM

SECTION: C SUB SECTION: C&I

SUB VENDOR LIST

PACKAGE WISE REGISTERED SUPPLIER LIST (PERMANENT CATEGORY) AS ON 1/21/2021 3:05:28 PM

| SI No | Package Name | Supplier Name | Supplier Communication Address |
|-------|---------------------------------------|---|--|
| 1 | PRESSURE SWITCH/DIFF. PRESSURE SWITCH | Kaustubha Udyog, | S.No. 36/1/1, Sinhgad Road, Vadgaon Khurd, Near Lokmat Press, Pune, Phone- 020-24393577, Pincode : Email : pressure@vsnl.com, |
| 2 | PRESSURE SWITCH/DIFF. PRESSURE SWITCH | PRECISION MASS PRODUCTS PVT. LTD. | Mr. Nishit Patel/Mr. Anuj Verma Plot No.2306, Phase II, GIDC Chhatral Kalol Phone- 9999464663 Pincode : 382729 Email : sales@precisionmass.com |
| 3 | PRESSURE SWITCH/DIFF. PRESSURE SWITCH | SWITZER PROCESS INSTRUMENTS PVT. LTD. | Mr. V S Jayaprakash, 128, SIDCO North Phase, Ambattur Estates CHENNAI Phone- 044-26252017/2018 Pincode: 600050 Email: sales@switzerprocess.co.in |
| 4 | PRESSURE SWITCH/DIFF. PRESSURE SWITCH | DRESSER INDUSTRIES INC. | Mr. Nishit Patel/Mr. Anuj Verma Plot No.2306, Phase II, GIDC Chhatral Kalol Phone- 02764-233682 Pincode : 382729 Email : Nishit.patel@ashcroftindia.com |
| 5 | PRESSURE SWITCH/DIFF. PRESSURE SWITCH | SOR INC. | LARRY DEGARMO/Avdhesh Chandra, 14685 W. 105TH STREET LENEXA Phone- 09810905139, Pincode : 66215 Email : Ldegarmo@sorinc.com, avdhesh@sherman-india.com, |
| 6 | PRESSURE SWITCH/DIFF. PRESSURE SWITCH | GENERAL INSTRUMENTS CONSORTIUM | Mr. Amarendra Kulkarni 194/195, Gopi Tank Road, Off. Pandurang Naik Marg, Mahim Mumbai Phone- 9323195251 Pincode : 400016 Email : amarendra@general-gauges.com |
| 7 | PRESSURE SWITCH/DIFF. PRESSURE SWITCH | Barksdale GmbH, Germany | Michael Weileder Dorn Assenheimer, Strasse 27 Reichelsheim Phone+91-9999107840 Pincode : D-61203 Email : msingh@barksdale.de |
| 8 | PRESSURE SWITCH/DIFF. PRESSURE SWITCH | INDFOS INDUSTRIES LIMITED | B-20-21, INDUSTRIAL AREA, MEERUT ROAD, GHAZIABAD Phone- 0120-2712016 Pincode : Email : mktg@indfos.com |
| 9 | PRESSURE SWITCH/DIFF. PRESSURE SWITCH | INDFOS (INDIA) LIMITED | MR.L.C.VENKATRANGAN/MR.B.KANNAN New No.17, II Floor, Adwave Towers, Dr.Sevalia Shivaji Salai, T.Nagar Chennai Phone- +91 44 24353407 Pincode : 600017 Email : delhi@indfos.com |
| 10 | PRESSURE GAUGE/ DIFF.PRESSURE GAUGE | FORBES MARSHALL (HYD) LTD. | MR SAILESH PATALAY/MR. M K SRINIVASAN PLOT NO.A-19/2, & T-4/2, IDA, NACHARAM, HYDERABAD Phone-9849913704 Pincode: 500 076 Email: mksrinivasan@forbesmarshall.com |
| 11 | PRESSURE GAUGE/ DIFF.PRESSURE GAUGE | PRECISION MASS PRODUCTS PVT. LTD. | Mr. Nishit Patel/Mr. Anuj Verma Plot No.2306, Phase II, GIDC Chhatral Kalol Phone- 9999464663 Pincode : 382729 Email : sales@precisionmass.com |
| 12 | PRESSURE GAUGE/ DIFF.PRESSURE GAUGE | Baumer Technologies India Pvt. Ltd. | Mr. Shyam Warilani/Mr. V Suresh Babu 36, DAMJI SHAMJI INDUSTRIAL COMPLEX, OFFMAHAKALI CAVES ROAD, ANDHERI(E) MUMBAI Phone- +91 99589 25151 Pincode : 400093 Email : |
| 13 | PRESSURE GAUGE/ DIFF.PRESSURE GAUGE | H.GURU INSTRUMENTS (SOUTH INDIA) P. LTD | sales.in@baumer.com 32,INDUSTRIAL SUBURB YESWANTHAPUR BANGALORE Phone- 080-23370300, Pincode : 560022 Email : info@hgurusouth.com |
| 14 | PRESSURE GAUGE/ DIFF.PRESSURE GAUGE | H.GURU INDUSTRIES | Mr. G. D. Hazra/Mr. P. K. Mitra 10 B, HO-CHI-MINH SARANI, KOLKATA Phone- 033 2282 2463 / 1637 Pincode : 700071 Email : mquru@vsnl.net |
| 15 | PRESSURE GAUGE/ DIFF.PRESSURE GAUGE | GAUGE BOURDON INDIA PVT. LTD. | 194/195, Gopi Tank Road, Off Pandurang Naik Marg, Mahim Mumbai, Phone- 011-41607463, Pincode : 400016, Email : gicdelhi@general-gauges.com, |
| 16 | PRESSURE GAUGE/ DIFF.PRESSURE GAUGE | BOSE PANDA INSTRUMENTS PVT.LTD. | Mr. Partha Bose 44, Saheed Hemanta Kumar Bose, Sarani, Kolkata Phone- +91 33 2548 7220 Pincode : 700074 Email : parthabosebpi@gmail.com; bosepanda@vsnl.net |
| 17 | PRESSURE GAUGE/ DIFF.PRESSURE GAUGE | A.N. INSTRUMENTS PVT. LTD. | MARKETING DIVISION, 5th FLOOR, 59-B, CHOWRINGHEE ROAD, KOLKATA Phone- 24757784,22472509 Pincode : 700020 Email : anidel@bol.net.in |
| 18 | PRESSURE GAUGE/ DIFF.PRESSURE GAUGE | Nesstech Instruments Private Limited | 26/2, G Type, Global Industrial Park Near Nahuli Railway Crossing, Valvada Vapi Phone- 9920576002 Pincode : 396105 Email : sales@nesstech.co.in |
| 19 | PRESSURE GAUGE/ DIFF.PRESSURE GAUGE | SCIENTIFIC DEVICES (BOMBAY) PVT LTD, | Office no. 53, Shree Manoshi Complex, Plot No. 5 & 6, Sec-3, Ghansoli (East), Navi Mumbai, Phone- 9892230623, Pincode : 400 701, Email : sdbpl@vsnl.com |
| 20 | TEMPERATURE GAUGE | PRECISION MASS PRODUCTS PVT. LTD. | Mr. Nishit Patel/Mr. Anuj Verma Plot No.2306, Phase II, GIDC Chhatral Kalol Phone- 9999464663 Pincode : 382729 Email : sales@precisionmass.com |
| 21 | TEMPERATURE GAUGE | Baumer Technologies India Pvt. Ltd. | Mr. Shyam Warilani/Mr. V Suresh Babu 36, DAMJI SHAMJI INDUSTRIAL COMPLEX, OFFMAHAKALI CAVES ROAD, ANDHERI(E) MUMBAI Phone- +91 99589 25151 Pincode : 400093 Email : |
| 22 | TEMPERATURE GAUGE | H.GURU INSTRUMENTS (SOUTH INDIA) P. LTD | sales.in@baumer.com 32,INDUSTRIAL SUBURB YESWANTHAPUR BANGALORE Phone- 080- 23370300, Pincode : 560022 Email : info@hgurusouth.com |
| 23 | TEMPERATURE GAUGE | GAUGE BOURDON INDIA PVT. LTD. | 194/195, Gopi Tank Road, Off Pandurang Naik Marg, Mahim Mumbai, Phone- 011-41607463, Pincode: 400016, Email: gicdelhi@general-gauges.com, |
| 24 | TEMPERATURE GAUGE | H.GURU INDUSTRIES | Mr. G. D. Hazra/Mr. P. K. Mitra 10 B, HO-CHI-MINH SARANI, KOLKATA Phone- 033 2282 2463 / 1637 Pincode : 700071 Email : mguru@vsnl.net |
| 25 | TEMPERATURE GAUGE | GOA THERMOSTATIC INSTRUMENTS PVT.LTD. | FLAT -B , GF, HILL CROWN APTS., COLLEGE ROAD, MAPUSA Phone- Pincode : 403525 Email : gtilworks@pyro-electric.in |
| 26 | TEMPERATURE GAUGE | GOA INSTRUMENTS INDUSTRIES PVT.LTD., | D2/5, Mapusa Industrial Estate, Mapusa, Goa, Phone- 09326054551, Pincode: 403507, Email: sumukh@goainstruments.com, |
| 27 | TEMPERATURE GAUGE | A.N. INSTRUMENTS PVT. LTD. | MARKETING DIVISION, 5th FLOOR, 59-B, CHOWRINGHEE ROAD, KOLKATA Phone- 24757784,22472509 Pincode : 700020 Email : anidel@bol.net.in |
| 28 | TEMPERATURE GAUGE | FORBES MARSHALL (HYD) LTD. | MR SAILESH PATALAY/MR. M K SRINIVASAN PLOT NO.A-19/2, & T-4/2, IDA, NACHARAM, HYDERABAD Phone-9849913704 Pincode: 500 076 Email: mksrinivasan@forbesmarshall.com |

| 29 | LEVEL GAUGE | TOSHNIWAL BROTHERS PVT.LTD. | WORKS:TOSHNIWAL IND.PVT.LTD, INDUSTRIAL ESTATE MAKHUPURA, AJMER Phone- 441171 Pincode : 305002 Email : toshniwalprocess@gmail.com |
|----|--------------------|---|--|
| 30 | LEVEL GAUGE | BLISS ANAND PVT. LTD. | Mr. Vikas Anand/ Mr.RGRajan 92B & 93 B , IMT MANESAR Gurgaon Phone- 0124-4366000 TO 9 Pincode : 122001 Email : sales@blissanand.com |
| 31 | LEVEL GAUGE | SIGMA INSTRUMENTS CO. | Gopal Kannan/R Gopinath 201, ANANDRAJ INDUSTRIAL ESTATE, OFF.LBS MARG, SONAPUR LANE, BHANDUP (W) MUMBAI Phone+919821038162 Pincode: 400078 Email: sales@sigmainstruments.co.in |
| 32 | TEMP. ELEMENT | DETRIVE INSTRUMENTATION & ELECTRONICS LTD | 320, TV INDUSTIAL ESTATE, OFF.DR.A.BESANT ROAD, BEHIND GLAXO, WORLI, MUMBAI Phone- 24934125,24938403 Pincode : 400025 Email : trivtech@vsnl.com |
| 33 | TEMP. ELEMENT | Nesstech Instruments Private Limited | 26/2, G Type, Global Industrial Park Near Nahuli Railway Crossing, Valvada Vapi Phone- 9920576002 Pincode : 396105 Email : sales@nesstech.co.in |
| 34 | TEMP. ELEMENT | Thermal Instrument India Pvt. Ltd. | Mr. Raghavendra M. Kulkarni 194/195, Gopi Tank Road Behind Citylight Cinema, Mahim Mumbai Phone- 09322664709 Pincode : 400016 Email : ramk@giconindia.com |
| 35 | TEMP. ELEMENT | Baumer Technologies India Pvt. Ltd. | Mr. Shyam Warilani/Mr. V Suresh Babu 36, DAMJI SHAMJI INDUSTRIAL COMPLEX, OFFMAHAKALI CAVES ROAD, ANDHERI(E) MUMBAI Phone- +91 99589 25151 Pincode : 400093 Email : |
| 36 | TEMP. ELEMENT | PYRO ELECTRIC INSTRUMENTS GOA PVT.LTD. | sales.in@baumer.com M. D. BICHU/R. M. BICHU G.B, HILL CROWN APARTMENTS, COLLEGE ROAD, MAPUSA Phone- 9326114601 Pincode: 403507 Email: priyanka.marketing@pyro-electric.in |
| 37 | TEMP. ELEMENT | GAUGE BOURDON INDIA PVT. LTD. | 194/195, Gopi Tank Road, Off Pandurang Naik Marg, Mahim Mumbai, Phone- 011-41607463, Pincode : 400016, Email : gicdelhi@general-gauges.com, |
| 38 | TEMP. ELEMENT | GOA INSTRUMENTS INDUSTRIES PVT.LTD., | D2/5, Mapusa Industrial Estate, Mapusa, Goa, Phone- 09326054551, Pincode: 403507, Email: sumukh@goainstruments.com, |
| 39 | TEMP. ELEMENT | TOSHNIWAL INDUSTRIES PVT. LTD., | Industrial Estate, Makhupura, Ajmer, Phone- 9352009000, Pincode : 305002, Email : info@tipl.com, |
| 40 | TEMP. ELEMENT | SCIENTIFIC DEVICES (BOMBAY) PVT LTD, | Office no. 53, Shree Manoshi Complex, Plot No. 5 & 6, Sec-3, Ghansoli (East), Navi Mumbai, Phone- 9892230623, Pincode : 400 701, Email : sdbpl@vsnl.com |
| 41 | TEMP. ELEMENT | Tempsens Instrument (I) Pvt Ltd | MR. V.P.RATHI/MR. HEMANT RATHI B-188A ROAD NO.5 , M.I.A UDAIPUR Phone- 09352420069 Pincode : 313003 Email : info@tempsens.com |
| 42 | TRANSMITTERS | ABB INDIA LIMITED | MR. RAJIV GOVIL 14, MATHURA ROAD, FARIDABAD Phone- 09971085678 Pincode : 121003 Email : vipin.swami@in.abb.com |
| 43 | TRANSMITTERS | V. AUTOMAT & INTRUMENTS (P) LTD. | Mr. R. K. BASSI/Mr. PRAVEEN KUMAR F-61, OKHLA INDL.AREA, PH-1 NEW DELHI Phone- 9810005826 Pincode : 110 020 Email : sales@vautomat.com |
| 44 | TRANSMITTERS | Pune Techtrol Pvt. Ltd. | N.P.Khatan/Sudhakar Badiger S-18, MIDC Bhosari, Pune Phone- 9850560042 Pincode : 411 026 Email : ho@punetechtrol.com |
| 45 | TRANSMITTERS | YOKOGAWA INDIA LIMITED, | PLOT NO.96, ELECTRONICS CITY COMPLEX, HOSUR ROAD, BANGALORE, Phone- 080-41586000, Pincode : Email : uday.shankar@in.yokogawa.com, |
| 46 | TRANSMITTERS | TOSHNIWAL INDUSTRIES PVT. LTD., | Industrial Estate, Makhupura, Ajmer, Phone- 9352009000, Pincode: 305002, Email: info@tipl.com, |
| 47 | TRANSMITTERS | SBEM PVT. LTD. | MR.N.K. BEDARKAR/MR. VISHWANATH KARANDIK 39, ELECTRONIC CO.OP. ESTATE, PUNE SATARA ROAD PUNE, Phone- 912041030100 Pincode: 411009 Email: newdelhi@sbem.co.in |
| 48 | TRANSMITTERS | Endress + Hauser (India) Pvt. Ltd., | Mr. Prakash Vaghela 215-216, DLF Tower 'A', Jasola District Centre, New Delhi, Phone- 9717593001, Pincode : 110025, Email : prakash.vaghela@in.endress.com, |
| 49 | TRANSMITTERS | PANAM ENGINEERS | Mr. Santosh Shukla 203, Jaisingh Business,Parsiwada, Sahar road,Andheri(East), Mumbai, Phone- 9892179529, Pincode: 400099, Email: santosh@panamengineers.com, |
| 50 | TRANSMITTERS | Moore Industries International Inc. | Leonard.W. Moore/ Matt Moren 16650 Schoenborn St. North Hills Phone- +1 818 830 5548 Pincode : 91343 Email : mmoren@miinet.com |
| 51 | TRANSMITTERS | EMERSON PROCESS MANAGEMENT (INDIA) PVT.LTD. | Mr. Amit Paithankar/Vikram Raj Singh 206-210,BALARAMA BUILDING 2ND FLR. BANDRA EAST MUMBAI Phone- 9619121500 Pincode : 400051 Email: vikramraj.singh@emerson.com |
| 52 | TRANSMITTERS | NIVO CONTROLS PVT. LTD. | Mr. Praveen Toshniwal 104-115, Electronic Complex, Indore Phone- 0731-4081305 Pincode : 452010 Email : sales@nivocontrols.com |
| 53 | TRANSMITTERS | SIEMENS LIMITED | Dr. Armin Bruck/Sandeep Mathur 130, Pandurang Budhkar Marg Worli Mumbai Phone- 0124 383 7377 Pincode : 400018 Email : ankit.varshney@siemens.com |
| 54 | TRANSMITTERS | SMART INSTRUMENTS LTD, BRAZIL | Agents: Digital Electronic Ltd. 74/11 'C' Cross Road MIDC Andheri (East) MUMBAI Phone- 28208477 Pincode : 400093 Email : corp@delbby.rpgms.ems.vsnl.net.in |
| 55 | TRANSMITTERS | Honeywell Automation India Limited | Mr. Ritwij Kulkarni 917, INTERNATIONAL TRADE TOWER, NEHRU PLACE, NEW DELHI Phone- 9890200584 Pincode : 110019 Email : rajesh.chaudhary@honeywell.com |
| 56 | TEMPERATURE SWITCH | TOSHNIWAL BROTHERS PVT.LTD. | WORKS:TOSHNIWAL IND.PVT.LTD, INDUSTRIAL ESTATE MAKHUPURA, AJMER Phone- 441171 Pincode : 305002 Email : toshniwalprocess@gmail.com |
| 57 | TEMPERATURE SWITCH | DRESSER INDUSTRIES INC. | Mr. Nishit Patel/Mr. Anuj Verma Plot No.2306, Phase II, GIDC Chhatral Kalol Phone- 02764-233682 Pincode : 382729 Email : Nishit.patel@ashcroftindia.com |
| 58 | TEMPERATURE SWITCH | INDFOS (INDIA) LIMITED | MR.L.C.VENKATRANGAN/MR.B.KANNAN New No.17, II Floor, Adwave Towers, Dr.Sevalia Shivaji Salai, T.Nagar Chennai Phone- +91 44 24353407 Pincode : 600017 Email : delhi@indfos.com |
| | | | |

| 59 | TEMPERATURE SWITCH | SWITZER PROCESS INSTRUMENTS PVT. LTD. | Mr. V S Jayaprakash, 128, SIDCO North Phase, Ambattur Estates CHENNAI Phone- 044-26252017/2018 Pincode : 600050 Email : sales@switzerprocess.co.in |
|----|-------------------------------|---------------------------------------|--|
| 60 | TEMPERATURE SWITCH | SOR INC. | LARRY DEGARMO/Avdhesh Chandra, 14685 W. 105TH STREET LENEXA Phone- 09810905139, Pincode: 66215 Email: Ldegarmo@sorinc.com, avdhesh@sherman-india.com, |
| 61 | DIFFERENTIAL PRESSURE SWITCH | SOR INC. | LARRY DEGARMO/Avdhesh Chandra, 14685 W. 105TH STREET LENEXA Phone- 09810905139, Pincode : 66215 Email : Ldegarmo@sorinc.com, avdhesh@sherman-india.com, |
| 62 | JUNCTION BOX | K.S.INSTRUMENTS PVT.LTD. | S Raghavan No. 72, 3rd Main, 1st Stage Industrial Suburb, Yeshwanthpur Bangalore Phone- 9880385770 Pincode : 560022 Email : sales1@ksinstruments.net |
| 63 | JUNCTION BOX | SUCHITRA INDUSTRIES | NO-2,OPP-27 AECS LAYOUT 2ND STG REJAMAHALVILAS EXTN 2ND STG BANGALORE Phone- Pincode : Email : suchitra.industriesblr@amail.com |
| 64 | JUNCTION BOX | FLEXPRO ELECTRICALS PVT. LTD. | Mr. Dineshbhai Zaveri C-1/ 27&37, GIDC, Kabilpore, Navsari Phone- 02637-265140,265003 Pincode : 396424 Email : flexpro@flexproltd.com |
| 65 | JUNCTION BOX | Shrenik & Company, | Mr. Mitesh Shah/Mr. Pulin Shah 39 A/3 ,Panchratna Industrial Estate, Sarkhej-Bavla Road Ahmedabad Phone- 9825024921 Pincode : 382213 Email : sales@pustron.com, pulin@sumip.com |
| 66 | JUNCTION BOX | AJMERA INDUSTRIAL & ENGINEERING WORKS | JIGNESH MAHENDRA AJMERA DENA BANK BLDG.,SHREE NAGESH INDL. ESTATE,STATION ROAD, MUMBAI Phone- 022 67973578 Pincode: 400 088 Email: ajmera@ajmera.net, |
| 67 | INSTRUMENTS TUBE FITTINGS | VIKAS INDUSTRIAL PRODUCTS | imaimera@yahoo.com S.R.SINGH/NAVEEN SINGH B - 2, SECTOR - 6, NOIDA Phone- +91- 9810122070 Pincode : 201301 Email : naveensingh@vsnl.com |
| 68 | INSTRUMENTS TUBE FITTINGS | PRECISION ENGINEERING INDUSTRIES | K. SITARAM/ K. SRINIVAS 7,SIDHAPURA INDUSTRIAL ESTATE S.V. ROAD,GOREGAON(W) MUMBAI Phone- 022 42631700 Pincode : 400 062 Email : peiks@vsnl.com |
| 69 | INSTRUMENTS TUBE FITTINGS | AURA INCORPORATED | NIRAJ SHARAN/SUJIT KUMAR W-167A, GREATER KAILASH-II NEW DELHI Phone- 9810182430 Pincode : 110048 Email : niraj@aurainc.com |
| 70 | INSTRUMENTS TUBE FITTINGS | Fluid Controls Pvt. Ltd. | Sophie Y. Moochhala/Mayur Rajput J.V.PATEL, I.T.I CMPD, B.MADHUKAR MARG, ELPHINSTONE ROADSTN.(WR), MUMBAI Phone- (022) 43338000 Pincode: 400013 Email: sales@fluidcontrols.com |
| 71 | LEVEL SWITCH-CAPACITANCE TYPE | SIGMA INSTRUMENTS CO. | Gopal Kannan/R Gopinath 201, ANANDRAJ INDUSTRIAL ESTATE, OFF.LBS MARG, SONAPUR LANE, BHANDUP (W) MUMBAI Phone- +919821038162 Pincode : 400078 Email : |
| 72 | LEVEL SWITCH-CAPACITANCE TYPE | V. AUTOMAT & INTRUMENTS (P) LTD. | sales@sigmainstruments.co.in Mr. R. K. BASSI/Mr. PRAVEEN KUMAR F-61, OKHLA INDL.AREA, PH-1 NEW DELHI Phone- 9810005826 Pincode : 110 020 Email : sales@vautomat.com |
| 73 | LEVEL SWITCH-CAPACITANCE TYPE | SCIENTIFIC DEVICES (BOMBAY) PVT LTD, | Office no. 53, Shree Manoshi Complex, Plot No. 5 & 6, Sec-3, Ghansoli (East), Navi Mumbai, Phone- 9892230623, Pincode : 400 701, Email : sdbpl@vsnl.com |
| 74 | LEVEL SWITCH-CAPACITANCE TYPE | Pune Techtrol Pvt. Ltd. | N.P.Khatan/Sudhakar Badiger S-18, MIDC Bhosari, Pune Phone- 9850560042 Pincode : 411 026 Email : ho@punetechtrol.com |
| 75 | LEVEL SWITCH-CAPACITANCE TYPE | LEVCON INSTRUMENTS PVT. LTD. | Mr Shayak Gupta/Badal Jana Rajkamal', 7th floor, 13, Camac Street KOLKATA Phone- 0 33 2283 2766 Pincode : 700017 Email : b_jana@levcongroup.com |
| 76 | LEVEL SWITCH-CAPACITANCE TYPE | Baumer Technologies India Pvt. Ltd. | Mr. Shyam Warilani/Mr. V Suresh Babu 36, DAMJI SHAMJI INDUSTRIAL COMPLEX, OFFMAHAKALI CAVES ROAD, ANDHERI(E) MUMBAI Phone- +91 99589 25151 Pincode : 400093 Email : sales.in@baumer.com |
| 77 | LEVEL SWITCH-CONDUTIVITY TYPE | Sapcon Instrument Pvt Ltd. | 131, PALSHIKAR COLONY Contact Person- Mr. Ashwin (9826080207) INDORE Phone- +91-731-4085751, Pincode: 452004 Email: sales@sapconinstruments.com |
| 78 | LEVEL SWITCH-CONDUTIVITY TYPE | LEVCON INSTRUMENTS PVT. LTD. | Mr Shayak Gupta/Badal Jana Rajkamal', 7th floor, 13, Camac Street KOLKATA Phone- 0 33 2283 2766 Pincode : 700017 Email : b_jana@levcongroup.com |
| 79 | LEVEL SWITCH-CONDUTIVITY TYPE | BLISS ANAND PVT. LTD. | Mr. Vikas Anand/ Mr.RGRajan 92B & 93 B , IMT MANESAR Gurgaon Phone- 0124-4366000 TO 9 Pincode : 122001 Email : sales@blissanand.com |
| 80 | LEVEL SWITCH-CONDUTIVITY TYPE | V. AUTOMAT & INTRUMENTS (P) LTD. | Mr. R. K. BASSI/Mr. PRAVEEN KUMAR F-61, OKHLA INDL.AREA, PH-1 NEW DELHI Phone- 9810005826 Pincode : 110 020 Email : sales@vautomat.com |
| 81 | LEVEL SWITCH-CONDUTIVITY TYPE | HI-TECH SYSTEMS & SERVICES LTD. | Mr. Vikash Agrawal/Mr. Tarun Debnath 119, PARK STREET , KOLKATA Phone- 033-22290045 Pincode : 700016 Email : sandeep@hitech.in |
| 82 | LEVEL SWITCH-CONDUTIVITY TYPE | RAMAN INSTRUMENTS PVT.LTD. | Mr. N R Shenoy/Mr G B Vijh 8, First Floor.Plot : 160A Bait-Ush-Sharaf, 29th Road,Bandra(W) MUMBAI Phone- 09892331381 Pincode : 400050 Email : ramanbpl@vsnl.com |
| 83 | LEVEL SWITCH-CONDUTIVITY TYPE | SIGMA INSTRUMENTS CO. | Gopal Kannan/R Gopinath 201, ANANDRAJ INDUSTRIAL ESTATE, OFF.LBS MARG, SONAPUR LANE, BHANDUP (W) MUMBAI Phone+919821038162 Pincode: 400078 Email: sales@sigmainstruments.co.in |
| 84 | LEVEL SWITCH-CONDUTIVITY TYPE | SOR INC. | LARRY DEGARMO/Avdhesh Chandra, 14685 W. 105TH STREET LENEXA Phone- 09810905139, Pincode : 66215 Email : Ldegarmo@sorinc.com, avdhesh@sherman-india.com, |
| 85 | LEVEL SWITCH-FLOAT TYPE | Pune Techtrol Pvt. Ltd. | N.P.Khatan/Sudhakar Badiger S-18, MIDC Bhosari, Pune Phone- 9850560042 Pincode: 411 026 Email: ho@punetechtrol.com |
| 86 | LEVEL SWITCH-FLOAT TYPE | D.K. INSTRUMENTS PVT.LTD. | N.SIKDAR/ SUMIT SIKDAR 76/2, SELIMPUR RD DHAKURIA Kolkata Phone- 033-2415-1310. Pincode : 700031 Email : dkinst@vsnl.net |
| 87 | LEVEL SWITCH-FLOAT TYPE | V. AUTOMAT & INTRUMENTS (P) LTD. | Mr. R. K. BASSI/Mr. PRAVEEN KUMAR F-61, OKHLA INDL.AREA, PH-1 NEW DELHI Phone- 9810005826 Pincode : 110 020 Email : sales@vautomat.com |

| 88 | LEVEL SWITCH-FLOAT TYPE | SCIENTIFIC DEVICES (BOMBAY) PVT LTD, | Office no. 53, Shree Manoshi Complex, Plot No. 5 & 6, Sec-3, Ghansoli (East), Navi Mumbai, Phone- 9892230623, Pincode : 400 701, Email : sdbpl@vsnl.com |
|-----|---------------------------|---|--|
| 89 | LEVEL SWITCH-FLOAT TYPE | LEVCON INSTRUMENTS PVT. LTD. | Mr Shayak Gupta/Badal Jana Rajkamal', 7th floor, 13, Camac Street KOLKATA Phone- 0 33 2283 2766 Pincode : 700017 Email : b_jana@levcongroup.com |
| 90 | LEVEL SWITCH-FLOAT TYPE | GENERAL INSTRUMENTS CONSORTIUM | Mr. Amarendra Kulkarni 194/195, Gopi Tank Road, Off. Pandurang Naik Marg, Mahim Mumbai Phone- 9323195251 Pincode : 400016 Email : amarendra@general-gauges.com |
| 91 | LEVEL SWITCH-FLOAT TYPE | Baumer Technologies India Pvt. Ltd. | Mr. Shyam Warilani/Mr. V Suresh Babu 36, DAMJI SHAMJI INDUSTRIAL COMPLEX, OFFMAHAKALI CAVES ROAD, ANDHERI(E) MUMBAI Phone- +91 99589 25151 Pincode : 400093 Email : |
| 92 | LEVEL SWITCH-FLOAT TYPE | SBEM PVT. LTD. | sales.in@baumer.com MR.N.K. BEDARKAR/MR. VISHWANATH KARANDIK 39, ELECTRONIC CO.OP. ESTATE, PUNE SATARA ROAD PUNE, Phone- 912041030100 Pincode: 411009 Email: newdelhi@sbem.co.in |
| 93 | LEVEL SWITCH-FLOAT TYPE | SIGMA INSTRUMENTS CO. | Gopal Kannan/R Gopinath 201, ANANDRAJ INDUSTRIAL ESTATE, OFF-LBS MARG, SONAPUR LANE, BHANDUP (W) MUMBAI Phone+ +919821038162 Pincode: 400078 Email: sales@sigmainstruments.co.in |
| 94 | LEVEL SWITCH-FLOAT TYPE | SOR INC. | LARRY DEGARMO/Avdhesh Chandra, 14685 W. 105TH STREET LENEXA Phone- 09810905139, Pincode : 66215 Email : Ldegarmo@sorinc.com, avdhesh@sherman-india.com, |
| 95 | INSTRUMENTS PIPE FITTINGS | AURA INCORPORATED | NIRAJ SHARAN/SUJIT KUMAR W-167A, GREATER KAILASH-II NEW DELHI Phone- 9810182430 Pincode : 110048 Email : niraj@aurainc.com |
| 96 | INSTRUMENTS PIPE FITTINGS | PRECISION ENGINEERING INDUSTRIES | K. SITARAM/ K. SRINIVAS 7,SIDHAPURA INDUSTRIAL ESTATE S.V. ROAD,GOREGAON(W) MUMBAI Phone- 022 42631700 Pincode : 400 062 Email : peiks@vsnl.com |
| 97 | INSTRUMENTS PIPE FITTINGS | VIKAS INDUSTRIAL PRODUCTS | S.R.SINGH/NAVEEN SINGH B - 2, SECTOR - 6, NOIDA Phone- +91- 9810122070 Pincode : 201301 Email : naveensingh@vsnl.com |
| 98 | INSTRUMENTS PIPE FITTINGS | Fluid Controls Pvt. Ltd. | Sophie Y. Moochhala/Mayur Rajput J.V.PATEL, I.T.I CMPD, B.MADHUKAR MARG, ELPHINSTONE ROADSTN.(WR), MUMBAI Phone- (022) 43338000 Pincode : 400013 Email : sales@fluidcontrols.com |
| 99 | INSTRUMENT FITTINGS | HP VALVES & FITTINGS INDIA PVT. LTD. | S. Harichandran/P.S. Pandi B-11, Mugappair Industrial Estate, CHENNAI Phone- 044 26252537 Pincode: 600037 Email: sales@hpvalvesindia.com |
| 100 | INSTRUMENT FITTINGS | Arya Crafts & Engineering Pvt. Ltd. | Mr.Sanjay Brahman/Mr.Shyam Vazirani 102, Vora Industrial Estate No.4 Navghar, Vasai Road (E) Dist.Thane, Mumbai Phone-+91-250- 2392246 Pincode : 401210 Email : arya@aryaengg.com |
| 101 | INSTRUMENT FITTINGS | Perfect Instrumentation Control (India) Pvt. Ltd. | MD Hussain Shaikh/Shahanawaz Khan Gala No. 168, Loheki Chwal,216/ 218, Maulana Azad Rd. Nagpada Junction Mumbai Phone- 91-9324383121 Pincode : 400008 Email : |
| 102 | INSTRUMENT FITTINGS | FLUIDFIT ENGINEERS PVT. LTD. | shahanawaz.khan@perfectinstrumentation.com Mr. Abbas Bhola Potia Building No. 2, Office No. 3,292, Bellasis Road,Mumbai Central (East) Mumbai Phone- 9920044113 Pincode: 400008 Email: ab@fluidfitengg.com |
| 103 | INSTRUMENT FITTINGS | VIKAS INDUSTRIAL PRODUCTS | S.R.SINGH/NAVEEN SINGH B - 2, SECTOR - 6, NOIDA Phone- +91- 9810122070 Pincode : 201301 Email : naveensingh@vsnl.com |
| 104 | INSTRUMENT FITTINGS | PANAM ENGINEERS | Mr. Santosh Shukla 203, Jaisingh Business,Parsiwada, Sahar road,Andheri(East), Mumbai, Phone- 9892179529, Pincode : 400099, Email : santosh@panamengineers.com, |
| 105 | INSTRUMENT FITTINGS | Fluid Controls Pvt. Ltd. | Sophie Y. Moochhala/Mayur Rajput J.V.PATEL, I.T.I CMPD, B.MADHUKAR MARG, ELPHINSTONE ROADSTN.(WR), MUMBAI Phone- (022) 43338000 Pincode : 400013 Email : sales@fluidcontrols.com |
| 106 | INSTRUMENT FITTINGS | PRECISION ENGINEERING INDUSTRIES | K. SITARAM/ K. SRINIVAS 7,SIDHAPURA INDUSTRIAL ESTATE S.V. ROAD,GOREGAON(W) MUMBAI Phone- 022 42631700 Pincode : 400 062 Email : peiks@vsnl.com |
| 107 | INSTRUMENT FITTINGS | AURA INCORPORATED | NIRAJ SHARAN/SUJIT KUMAR W-167A, GREATER KAILASH-II NEW DELHI Phone- 9810182430 Pincode : 110048 Email : niraj@aurainc.com |
| 108 | INSTRUMENT FITTINGS | Comfit & Valve Pvt. Ltd. | Mr. Jeetu Jain/Mr. Vinay Sosa Survey No. 23/1, Part 2, Ahmedabad- Mehsana Highway Laxmipura, Nandasan Phone- 02764-267036/37 Pincode: 382705 Email: marketing@com-fit.com |


Notes:- 1.)The above Sub-Vendor list is tentative & reference only. However Sub-Vendor List is subject to BHEL/End user approval without any commercial /delivery implication. 2.)New Sub-Vendor if proposed by Vendor during contract stage shall subject to BHEL/end user approval without commercial/delivery implication.

| | DOCUMENT TITLE | | |
|-----------------------------|----------------|--------------------------|--|
| बीएचर्ड एत मिन्ना | | KKS NUMBERING PHILOSOPHY | |
| | | | |

KKS NUMBERING PHILOSOPHY

For identifying (tagging) an instrument / equipment in Power plant KKS numbering scheme is used. The purpose is to assign a unique number to every equipment in the power plant. For C&I equipment unique number are to be provided up to the signal level so that a unique number Input / Output exist in DCS for every signal.

Normally KKS number is a 10 digit alpha-numeric code and is typically split into the following:



First three digits indicate the Sub-System. The Code for the major system are given as per **Annexure-1**.

Fourth and Fifth digits are the **Numerical Keys at System Code Level** and used to distinguish between main systems having same Alpha Codes.

Sixth and Seventh digits are the **Equipment / Apparatus / Measuring Circuit Code**. The code of various Equipment / Apparatus / Measuring Circuit is shown in **Annexure-2**

Eight, Nine and tenth digits are the **Numerical Keys at Equipment / Apparatus / Measuring Circuit Code** and used to distinguish between various instruments in the same sub-group. Numerical keys at System / Equipment / Apparatus / Measuring Circuit is shown in **Annexure-3**.

**

KKS TAGS ARE PROVIDED IN THE P&ID FURNISHED BY VENDOR.HOWEVER, IF THE KKS NUMBER OF EQUIPMENT/INSTRUMENTS CHANGES,THE SAME SHALL BE FINALIZED DURING DETAILED ENGINEERING.



KKS NUMBERING PHILOSOPHY

ANNEXURE-1

List of System / Sub-System Codes used in Power Plant:

1) Refer the P&ID sheets.

ANNEXURE-2

Standard Equipment Codes:

| AA | Valves | including | drives | also | hand | operated |
|----|---------|-----------|---------|------|-------|----------|
| AA | v aives | meruanig | ulives. | aiso | Hallu | operateu |

AB Seclusions, Lock, Gates, Doors

AC Heat Exchanger

AE Turning, Driving, Lifting equipment AF Continuous conveyors, Feeders

AG Generator Units

AH Heating and Cooling Units

AK Pressing and Packaging equipment

AM Mixer, Stirrer

AN Blower, Air Pumps / Fans, Compressor Units

AP Pump Units

AT Purification, Drying, Filter

AV Combustion Equipment e.g. grates

Standard Apparatus Codes:

BB Vessels and Tank
BF Foundation

BG Boiler Heating Surfaces

BN Injector, Ejector

BP Flow and throughput limitation equipment (Orifice)

BQ Holders, Carrying Equipment, Support BR Piping, Ducts, Chutes, Compensator

BS Sound Absorber BU Insulations, Sheatings

Standard Measuring Circuits Codes:

CD Density

CE Electrical Quantities CF Flow, throughput

CG Distance, Length, Position

CK Time CL Level

| | DOCUMENT TITLE | | | |
|-------------------------------------|---|-------------------------------|----------------|-------------------|
| वी एच ई एत 11 भी है। | KKS NU | MBERING PHIL | OSOPHY | |
| ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, | | | | |
| CM CQ CS CT CY | Speed, V Tempera | (SWAS) relocity, Frequency | У | |
| | ANNE | XURE-3 | | |
| | Numer | ical Keys | | |
| A) Nur | nerical Keys at System Code Leve | el | | |
| i) | i) Use 10, 20, 30 To distinguish between main systems having same Alpha Codes. Examples: | | | |
| | a) Main Steam (Left) and Main Steam (Right) | | | |
| | b) BFP – A/B/C | | | |
| | c) ID Fan – A/B, FD Fan A/B, AH – A/B | | | |
| ii) | ii) For branch off from main system path having code say 10, keep the same alpha code and use 11, 12, 13 etc. Similarly for other branch off from main system path having code say 20, keep the same alpha code and use 21, 22, 23 etc and shall carry on further in the same way. | | | |
| iii) | iii) If the branch off from main system / sub system path is used for some other system, where different alpha codes can be applied, then in that case the said branch line will be designated by the alpha codes of the system to which it is providing the input. | | | |
| B) Nur | nerical keys at Equipment Code le | evel: | | |
| Fo | ere are three numerical keys allowing has been agreed upon come in sorting. Valves and Dampers Equipment Valves and Dampers Equipment Valves and Dampers Valves | nsidering present p | | |
| | Motorised (on/off duty) | - | <u>N1</u> 0 | N2 N3 01 to 50 |
| | Motorised (inching duty) | - | 0 | 51 to 99 |
| | Pneumatic (Control) | - | 1 | 01 to 50 |
| | Motorised (thyrestor Control) | - | 1 | 51 to 99 |
| | Sol. Operated - 2 01 to 99 | | | |

01 to 99

(Open / Close duty (Valves, NRVs, Gate)

Hydraulic

| DOCL | JMENT | TITI | F |
|------|--------------|------|---|
| | וווובועוכ | 1116 | ᆫ |



KKS NUMBERING PHILOSOPHY

| | NRV (Without actuation) | - | 4 | 01 to 99 |
|-----|--|--------|-----|----------|
| | Manual | - | 5 | 01 to 99 |
| | Manual | - | 6 | 01 to 99 |
| | Relief & Safety Valves | - | 7 | 01 to 99 |
| | Reserve | - | 8 | 01 to 99 |
| | Reserve | - | 9 | 01 to 99 |
| ii) | Field Instruments | | | |
| | Field Transmitters & Analog Signals | - | 0 | 01 to 99 |
| | Field Switches & Binary Signals | - | 1 | 00 to 99 |
| | PG Test Point | - | 4 | 00 to 99 |
| | Gauges | - | 5 | 00 to 99 |
| | Automatic Turbine Tester (ATT)-HWR | - | 2 | 00 to 99 |
| | (Reserved for protection Signals used by I | Hardwa | ar) | |
| | | | | |

Example of Numerical Key Usage:

In line with the philosophy adopted for Valves / Dampers /instruments etc. pumps and fans in the main systems (having different system code) can be numbered as AP/N100 and as AP/N101, 102, Where system code is same.



4x210 + 3x500 MW KAHALGOAN STPS, STG-I &II- FGD SYSTEM

HVAC SYSTEM TECHNICAL SPECIFICATION (MATERIAL HANDLING PORTION)

| SPECIFICATION No: PE-TS-481- (571-13000-A)-A001 (REV-0) | | |
|---|--|--|
| SECTION: I | | |
| SUB-SECTION: C-5 | | |
| REV. 00 | | |

SECTION: I

SUB-SECTION: C-5
TECHNICAL SPECIFICATION (MATERIAL HANDLING)