

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			<div>एनटीपीसी NTPC</div>
28.09.00	TRAINING REQUIRED IN MAN MONTH			
	Area	Engineering (Man months)	Erection (Man months)	O&M (Man months)
	Steam Turbine Generator and its Auxiliaries	5.5	8.0	21
	Steam Generator and its Auxiliaries	5.5	8.0	20.5
	Station C&I (Control and Instrumentation)	3.5	5.5	10
	Ash Handling Plant	2.0	3.0	5.0
	Coal Handling Plant	1.0	1.5	2.5
	UF Membranes, RO Membranes, ZLD, Chlorine Di Oxide (ClO2) generation & dosing system, Condensate Polishing Plant (CPU), CW Treatment System	0.2	0.3	0.5
	Electrical systems consisting of generators, Excitation systems, VFD, Motors, MV/LV switchgears, relays, SAS and Switchyard	4.5	3.5	9
	Total	22.2	29.8	68.5
29.00.00	SAFETY ASPECTS DURING CONSTRUCTION AND ERECTION			
	<p>In addition to the requirements given in Erection Conditions of Contract (ECC) the following shall also cover:</p> <p>i) Working platforms should be fenced and shall have means of access.</p> <p>ii) Ladders in accordance with Employer's safety rules for construction and erection shall be used. Rungs shall not be welded on columns. All the stairs shall be provided with handrails immediately after its erection.</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 56 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
30.00.00	<p><b>NOISE LEVEL</b></p> <p>The equivalent 'A' weighted sound pressure level measured at a height of 1.5 m above floor level in elevation and at a distance of one (1) meter horizontally from the nearest surface of any equipment/machine, furnished and installed under these specifications, expressed in decibels to a reference of 0.0002 microbar, shall not exceed 85 dBA except for</p> <ul style="list-style-type: none"> <li>i) Safety valves and associated vent pipes for which it shall not exceed 105 dBA-115 dBA.</li> <li>ii) Regulating drain valves in which case it shall be limited to 90 dBA-115 dBA.</li> <li>iii) Mill noise which will be limited to 85-90 dBA.</li> <li>iv) TG unit in which case it shall not exceed 90 dBA.</li> <li>v) For HP-LP bypass valves and other intermittently operating control valves, the noise level shall be within the limit of 90 dBA.</li> <li>vi) For BFP Motor Noise level shall be within the limit of 90 dBA.</li> </ul>			
31.00.00	<p><b>PACKAGING, TRANSPORTATION AND STORAGE</b></p> <p>All the equipments shall be suitably protected, coated, covered or boxed and crated to prevent damage or deterioration during transit, handling and storage at Site till the time of erection. While packing all the materials, the limitation from the point of view of the sizes of railway wagons available in India should be taken account of. The Contractor shall be responsible for any loss or damage during transportation, handling and storage at site due to improper packing and preservation. The Contractor shall ascertain the availability of Railway wagon sizes from the Indian Railways or any other agency concerned in India well before effecting despatch of equipment. Before despatch it shall be ensured that complete processing and manufacturing of the components is carried out at shop, only restricted by transport limitation, in order to ensure that site works like grinding, welding, cutting &amp; preassembly to bare minimum. The Employer's Inspector shall have right to insist for completion of works in shops before despatch of materials for transportation.</p> <p>In addition to above, the contractor shall take all necessary measures for storage of all electronic equipment / systems at site in a dust free Air conditioned space ensuring proper temperature &amp; humidity.</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 57 OF 119	


CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			<div>एनडीपीसी NTPC</div>
32.00.00	<b>ELECTRICAL EQUIPMENTS/ENCLOSURES</b>			
32.01.00	All electrical equipments and devices, including insulation, heating and ventilation devices shall be designed for ambient temperature and a maximum relative humidity, as specified elsewhere in the specifications.			
33.00.00	<b>INSTRUMENTATION AND CONTROL</b>			
	All instrumentation and control systems/ equipment/ devices/ components, furnished under this contract shall be in accordance with the requirements stated herein, unless otherwise specified in the detailed specifications.			
33.01.00	All instrument scales and charts shall be calibrated and printed in metric units and shall have linear graduation. The ranges shall be selected to have the normal reading at 75% of full scale.			
	All scales and charts shall be calibrated and printed in Metric Units as follows:			
	1. Temperature	-	Degree centigrade (deg C)	
	2. Pressure	-	Kilograms per square centimetre (Kg/cm <sup>2</sup> ). Pressure instrument shall have the unit suffixed with 'a' to indicate absolute pressure. If nothing is there, that will mean that the indicated pressure is gauge pressure.	
	3. Draught	-	Millimetres of water column (mm wc).	
	4. Vacuum	-	Millimeters of mercury gauge (mm Hg) or water column (mm Wcl).	
	5. Flow (Gas)	-	Tonnes/ hour	
	6. Flow (Steam)	-	Tonnes/ hour	
	7. Flow (Liquid)	-	Tonnes / hour	
	8. Flow base	-	760 mm Hg. 15 deg.C	
	9. Density	-	Grams per cubic centimetre.	
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C		GENERAL TECHNICAL REQUIREMENTS  PAGE 58 OF 119


CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			<div>एनडीपीसी NTPC</div>
33.02.00	All instruments and control devices provided on panels shall be of miniaturized design, suitable for modular flush mounting on panels with front draw out facility and flexible plan-in connection at rear.			
34.00.00	<b>ELECTRICAL NOISE CONTROL</b>  The equipment furnished by the Contractor shall incorporate necessary techniques to eliminate measurement and control problems caused by electrical noise. Areas in Contractor's equipment which are vulnerable to electrical noise shall be hardened to eliminate possible problems. Any additional equipment, services required for effectively eliminating the noise problems shall be included in the proposal. The equipment shall be protected against ESD as per IEC-61000-2. Radio Frequency interference (RFI) and Electro Magnetic Interference (EMI) protection against hardware damage and control system mal-operations/errors shall be provided for all systems as per EN-50082-2 (1995).			
35.00.00	<b>SURGE PROTECTION FOR SOLID STATE EQUIPMENT</b>  All solid state systems /equipment shall be able to withstand the electrical noise and surge as encountered in actual service conditions and inherent in a power plant and shall meet the requirements of surge protection as defined in ANSI C37.90.1-1989 on its suitable equivalent class of IEC 254-4. Details of the features incorporated and relevant tests carried out. The test certificates. etc. shall be submitted by the Bidder.			
36.00.00	<b>INSTRUMENT AIR SYSTEM</b>  The instrument air supply system as supplied by the Bidder for various pneumatic control & instrumentation devices like pneumatic actuators, power cylinders, E/P converters, piping / tubing etc.  Each pneumatic instrument shall have an individual air shut - off valve. The pressure regulating valve shall be equipped with an internal filter, a 50 mm pressure gauge and a built-in filter housing blow down valve.			
37.00.00	<b>TAPPING POINTS FOR MEASUREMENTS</b>  Tapping points shall include probes, wherever applicable, for analytical measurements and sampling.  For direct temperature measurement of all working media, one stub with internal threading of approved pattern shall be provided along with suitable plug and washer. The Contractor will be intimated about thread standard to be adopted.  The following shall be provided on equipment by the Bidder. The standard which is to be adopted, will be intimated to the Contractor.			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 59 OF 119




CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS	एनडीपीसी NTPC		
38.00.00	i) Temperature test pockets with stub and thermowell  ii) Pressure test pockets			
	<b>SYSTEM DOCUMENTATION</b>  The Bidder shall provide drawings, system overview & description, hardware/software details, technical literature, functional & hardware schemes, bill of material, parts list, interconnection diagrams, data sheets, erection/ installation/ commissioning procedures, instruction/ operating manuals, etc. for each of the C& I system / sub-systems/ equipment supplied under this package. The documentation shall include complete details of the C&I systems/ sub-systems/ equipment to enable review by Employer during detailed engineering stage and to provide information to plant personnel for operation & Maintenance (including quick diagnostics & trouble shooting) of these C&I systems/ sub-systems/ equipment at site. The minimum documentation requirements for C&I systems shall be as stipulated under C&I "Technical Data Sheets" Part of specifications. In addition to this, system documentation for DDCMIS shall include as a minimum to that specified elsewhere in the Technical Specification.  The exact format, submission schedule and contents of various documents shall be as finalised during detailed engineering stage.			
	38.01.00 Bill of material (instrument list) for all C&I equipment/ devices shall be furnished by the bidder in standard formats as approved by the Employer.			
39.00.00	<b>MAINTENANCE MANUALS OF ELECTRONIC MODULES</b>  The Contractor shall have to furnish two (2) sets of all maintenance manual of each and every electronic card/module as employed on the various systems and equipment including peripherals etc., offered by him. The Contractor will also have to furnish the data regarding the expected failure rate of various modules and other system components. Further, the contractor shall furnish a set of operating manuals which should include block diagrams, make, model/type, details wiring and external connection drawings etc. as required to do the testing and maintenance of the electronic modules.  Backup & Restoration Procedures of DDCMIS, Station LAN & Advance Process Control shall be provided.			
	40.00.00 <b>MAKE IN INDIA REQUIREMENTS</b>  a) The bidder shall follow Indian laws, regulations and standards. There shall not be any restriction in terms of compliance to codes & standards of foreign origin only. The compliance to equivalent/better Indian as well as other codes & standards, wherever available, shall also be acceptable.			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 60 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
<p>b)</p> <p>c)</p> <p>d)</p> <p>e)</p> <p>f)</p> <p>g)</p> <p>h)</p> <p>i)</p> <p>j)</p>	<p>The technologies/ products offered shall be environmentally friendly, consuming less energy, and safe, energy efficient, durable and long lasting under the prescribed operational conditions.</p> <p>The bidder/its sub vendor/supplier shall ensure supply of spares, materials and technological support for the entire life of the project.</p> <p>The bidder shall list out the products and components producing Toxic E-waste and other waste as specified. It shall have an Extended Producers Responsibility (EPR) so that after the completion of the lifecycle, the materials are safely recycled/ disposed of by the contractor and for this, the bidder has to establish recycling/disposal unit as specified.</p> <p>The equipment/ material sourced from foreign companies will be tested in accredited labs in India before acceptance wherever such facilities are available. The testing shall be carried out in accordance with MOP extant order/guidelines.</p> <p>The bidder shall have to furnish a certificate regarding cyber security/safety of the equipment/process to be supplied/services to be rendered as safe to connect.</p> <p>All applicable safety requirements shall be met. Regular safety audit shall be carried out by the manufacturer/ supplier.</p> <p>Wherever required, the foreign supplier shall establish fully functional service centers in India and shall keep spares/material locally for future needs of Employer.</p> <p>To protect the security, integrity and reliability of equipment in this package, it is essential to remove vulnerabilities arising out of the possibility of cyber-attack through malware/ Trojans etc. embedded in imported equipments. This requirement shall apply to any item imported for end use or to be used as a component, or as a part in manufacturing, assembling of any equipment or to be used in this package. Contractor shall comply all the requirements of Order No 25-11/6/2018-PG, dated 02/07/2020 (attached as <b>Appendix-I</b>), issued by Ministry of Power, Government of India and its subsequent amendments/revisions. Contractor shall furnish declaration of compliance of MOP order dated 02/07/2020 requirements with dispatch of equipment/ item. Further, Contractor shall furnish back up testing certificates, whenever Employer asks the same.</p> <p>All equipment/materials/parts/items required in this package which are domestically manufactured with sufficient domestic capacity as identified in Annexure-I of MOP order dated 16/11/2021 including its subsequent revisions (copy attached as <b>Appendix-II</b>) shall necessarily be sourced from the class-I local suppliers only as per the extant provisions of the Public Procurement (Preference to Make in India) Orders issued by DPIIT and MoP.</p> <p>Any violation w.r.t Make in India and minimum local content (MLC) requirements as specified shall be sole responsibility of the Bidder.</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 61 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS <div data-bbox="1284 113 1429 184" style="float: right;">  </div>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 62 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			<div>एनटीपीसी NTPC</div>
	<div>Appendix-I</div> <div>No.25-11/6/2018-PG Government of India Ministry of Power Shram Shakti Bhawan, Rafi Marg, New Delhi – 110001 Tele Fax: 011-23730264 *****</div> <div>Dated 02/07/2020</div> <div>ORDER</div> <div><p>Power Supply System is a sensitive and critical infrastructure that supports not only our <b>national defence, vital emergency services</b> including health, disaster response, <b>critical national infrastructure</b> including classified data &amp; communication services, defence installations and manufacturing establishments, logistics services but also the <b>entire economy</b> and the <b>day-to-day life</b> of the citizens of the country. Any danger or threat to Power Supply System can have catastrophic effects and has the potential to cripple the entire country. Therefore, the Power Sector is a <b>strategic and critical sector</b>.</p><p>The vulnerabilities in the Power Supply System &amp; Network mainly arise out of the possibilities of cyber attacks through malware / Trojans etc. embedded in imported equipment. Hence, <b>to protect the security, integrity and reliability of the strategically important and critical Power Supply System &amp; Network</b> in the country, the following directions are hereby issued :-</p><p>(1) All equipment, components, and parts imported for use in the Power Supply System and Network shall be tested in the country to check for any kind of embedded malware/trojans/cyber threat and for adherence to Indian Standards.</p><p>(2) All such testings shall be done in certified laboratories that will be designated by the Ministry of Power (MoP).</p><p>(3) Any import of equipment/components/parts from "prior reference" countries as specified or by persons owned by, controlled by, or subject to the jurisdiction or the directions of these "prior reference" countries will require prior permission of the Government of India</p><p>(4) Where the equipment/components/parts are imported from "prior reference" countries, with special permission, the protocol for testing in certified and designated laboratories shall be approved by the Ministry of Power (MoP).</p><p>This order shall apply to any item imported for end use or to be used as a component, or as a part in manufacturing, assembling of any equipment or to be used in power supply system or any activity directly or indirectly related to power supply system.</p><p>This issues with the approval of Hon'ble Minister of State for Power and New &amp; Renewable Energy (Independent Charge).</p><div><div></div><div>(Goutam Ghosh) Director Tel: 011-23716674</div></div><div>To: 1. All Ministries/Departments of Government of India (As per list) 2. Secretary (Coordination),Cabinet Secretariat 3. Vice Chairman, NITI Aayog 4. Comptroller and Auditor General of India 5. Chairperson, CEA 6. CMDs of CPSEs/Chairman of DVC &amp; BBMB/MD, EESL/DG, NPTI/DG, CPRI/DG, BEE/ 7. All ASs/JSs/EA, MoP</div><div>Copy: 1. PS to Hon'ble PM, Prime Minister's Office 2. PS to Hon'ble MOS(IC) for Power and NRE 3. Sr. PPS to Secretary(Power)</div></div>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 63 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			<div>एनटीपीसी NTPC</div>
	<div>Appendix-II</div> <div>No. A-1/2021-FSC-Part(5) Government of India Ministry of Power Shram Shakti Bhawan, New Delhi Dated: 16<sup>th</sup> November, 2021</div> <div>ORDER</div> <div>Subject: Public Procurement (Preference to Make in India) to provide for Purchase Preference (linked with local content) in respect of Power Sector.</div> <div>Reference: Department for Promotion of Industry and Internal Trade (DPIIT) Notification No. P-45021/2/2017-PP (BE-II) dated 16.09.2020.</div> <div>The Government of India, Department for Promotion of Industry and Internal Trade (DPIIT) issued Public Procurement (Preference to Make in India), Order 2017, for encouraging 'Make in India' and promoting manufacturing and production of goods and services in India with a view to enhancing income and employment. Subsequently, DPIIT vide order No. P-45021/2/2017-PP (BE-II) dated 4<sup>th</sup> June, 2020 and further vide order dated 16<sup>th</sup> September, 2020 have issued the revised Public Procurement (Preference to Make in India) Order 2017.</div> <div>2. In light of the Public Procurement (Preference to Make in India) Order 2017, this Ministry had notified purchase preference (linked with local content) for Hydro and Transmission sectors vide Order No. 11/05/2018-Coord dated 20.12.2018, for Thermal sector vide Order dated 28.12.2018 and for Distribution sector vide Order dated 17.03.2020. Further, a combined order dated 04.04.2020 was also issued in supersession of all previous orders to indicate equipment/material/components for which there was sufficient local capacity and competition and also to indicate conditions for including suitably in the tenders to be issued by the procurers. In furtherance of Para 19 of the DPIIT Notification No. P-45021/2/2017-PP(BE-II) dated 04.06.2020, Ministry of Power (MoP) issued a revised comprehensive Order dated 28.07.2020 (Annexure-I amended by order dated 17.09.2020).</div> <div>3. DPIIT Notification No. P-45021/2/2017-PP(BE-II) dated 16.09.2020 has further revised its order dated 04.06.2020. Therefore, in supersession of all the aforementioned orders including order No.10/1/2019-St.Th. (Part-II) dated 20.03.2020 issued by this Ministry, the following has been decided:</div> <div><div>i. For the purpose of this order, the definitions of various terms used in the order, and provisions relating to (i) Eligibility of 'Class-I local supplier'/'Class-II local supplier'/'Non-local suppliers' for different types of procurement, (ii) purchase preference (iii) exemption to small purchases and (iv) margin of purchase preference shall be the same as in DPIIT order dated 16.09.2020, referred to above and extracts of the same is given at <b>Appendix</b>.</div><div>ii. In procurement of all goods and services or works in respect of which there is sufficient local capacity and local competition as in <b>Annexure-I</b>, only "Class-I local supplier" shall be eligible to bid irrespective of purchase value. "Class-I local supplier" is a supplier or service provider whose goods, services or works offered for procurement meets the Minimum Local Content (MLC) as prescribed in Annexure-I of this order. "Class-II local supplier" means a</div></div> <div></div>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 64 OF 119	

supplier, as defined by DPIIT in its Order No. P-45021/2/2017-PP (BE-II) dated 16-09-2020.

- iii. In the procurement of all goods and services or works other than those listed in Annexure-I, only "Class-I local supplier" and "Class-II local supplier" as defined in the order of this Ministry herewith shall be eligible to bid in procurement undertaken by procuring entities, except when Global Tender Enquiry has been issued. In Global tender enquiries, "Non-local suppliers" shall also be eligible to bid along with "Class-I local suppliers" and "Class-II local suppliers". In procurement of all goods, services or works not covered by sub-para 3(ii) above, and with estimated value of purchases less than Rs. 200 crores, in accordance with Rule 161(iv) of GFR, 2017, Global Tender Enquiry(GTE) shall not be issued except with the approval of the competent authority as designated by Department of Expenditure.
- iv. For the purpose of this order, 'Works' means all works as per Rule 130 of GFR- 2017, and will also include 'turnkey works', Engineering, Procurement and Construction (EPC) contracts and service contracts including System Integrator (SI) contracts.
4. The list of items, in respect of which, local capacity with sufficient competition exists as per **Annexure-I**, will be reviewed at regular intervals with a view to increase number of items in this list and also to increase the MLC for each item, wherever it is less than 100%.
5. Purchase preference shall be given to local suppliers in accordance with **para 3A** of DPIIT Order dated 16.09.2020, and extracts of the same are given at **Appendix**.
6. Further, it has been decided to constitute a committee for independent verification of self-declarations and auditor's / accountant's certificates on random basis and in the case of complaints. The composition of the committee is given below:

Member (Planning), Central Electricity Authority (CEA)	Chairperson
Chief Engineer (PSETD), CEA	Member
Chief Engineer (HETD), CEA	Member
Chief Engineer (TETD), CEA	Member
Chief Engineer (DP&R), CEA	Member
As may be co-opted by CEA	External Expert
Chief Engineer (R&D), CEA	Convener

7. Further, it has also been decided to constitute a committee to examine the grievances in consultation with stakeholders and recommend appropriate actions to the Competent Authority in MoP. The composition of the Committee is given below:

Chairperson, CEA	Chairperson
Member (Hydro), CEA	Member





Member (Power System), CEA	Member
Member (Thermal), CEA	Convener

8. The complaint fee of Rs. 2 Lakhs or 1% of the value of the local item being procured (subject to maximum of Rs. 5 Lakhs), whichever is higher, shall be paid in the form of Demand Draft, drawn in favour of **PAO, CEA, New Delhi**. In case the complaint is found to be incorrect, the complaint fee shall be forfeited. In case, the complaint is upheld and found to be substantially correct, the deposited fee of the complainant would be refunded without any interest.

9. All other conditions, not stipulated in this order, shall be as laid down in the DPIIT's order No. P-45021/2/2017-PP (BE-II) dated 16.09.2020.

10. This order shall be applicable in respect of the procurement made by all attached or subordinate offices or autonomous bodies under the Government of India including Government Companies as defined in the Companies Act, and/or the States and Local Bodies making procurement under all Central Schemes/ Central Sector Schemes where the Scheme is fully or partially funded by the Government of India. The aforesaid orders shall also be applicable in respect of projects wherein funding of goods, services or works is by Power Finance Corporation (PFC) /Rural Electrification Corporation (REC) and any Financial Institution in which Government of India/ State Government share exists. This order shall be applicable to Tariff Based Competitive Bidding (TBCB) projects also. Procuring entities as defined in the DPIIT's Order dated 16.09.2020 are advised to revise their tender documents to fully comply with the said DPIIT's Order and the subsequent Orders that would be issued in this regard by DPIIT/ this Ministry from time to time.



11. All tenders for procurement by Central Government Agencies or the States and Local Bodies, as the case may be, have to be certified for compliance of the Public Procurement (Preference to Make in India) 'PPP-MII' Order by the concerned procurement officer of the Government Organization before uploading the same on the portal.

12. Exemption from meeting the stipulated local content is allowed as per clause 13 and 13A of PPP-MII Order dated 16.09.2020, if the manufacturer declares that the item is manufactured in India under a License from a foreign Manufacturer who holds Intellectual Property Rights (IPRs) and there is Transfer of Technology (ToT) with phasing to increase Minimum Local Content. For such items, if any CPSE under the administration of Ministry of Power requests exemption for any item, it shall be considered by Ministry of Power, on case to case basis.


13. In order to further encourage Make in India initiatives and promote manufacturing and production of goods and services in India, general guidelines as enclosed at **Annexure-II** may be adopted in an appropriate manner according to the circumstances by the procuring entities in their tendering process.


14. The procurers may specify the higher values of MLC than those specified in this Order in respect of goods, services or works covered in their tenders and award the weightage to the product of higher MLC for which they have to specify the criteria beforehand in their tender. The values given in Annexure-I are the minimum prescribed values for becoming a class-I local supplier for the products indicated therein.




CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS <div data-bbox="1284 113 1425 184" style="float: right;">  </div>		
	<p data-bbox="508 352 1247 405">15. This issues with the approval of Hon'ble Minister for Power and New &amp; Renewable Energy.</p> <div data-bbox="1101 384 1300 478" style="text-align: right;">  </div> <p data-bbox="841 457 1247 527" style="text-align: right;"> (S. Majumdar)  Under Secretary to the Government of India  Tele No. 011- 23356938 </p> <p data-bbox="508 527 540 548">To:</p> <ol data-bbox="508 552 1252 968" style="list-style-type: none"> <li>1. Secretary to Government of India (All Ministries/ Departments of Government of India) (As per list)</li> <li>2. Secretary (Coordination), Cabinet Secretariat</li> <li>3. CEO, NITI Aayog</li> <li>4. Chief Secretaries of all States/ UTs</li> <li>5. Comptroller and Auditor General of India</li> <li>6. Secretary, DPIIT, Chairman of Standing Committee for implementation of Public Procurement Order, 2017</li> <li>7. Director General, Bureau of Indian Standards (BIS)</li> <li>8. Joint Secretary, DPIIT, Member-Convener of Standing Committee for implementation of Public Procurement Order, 2017</li> <li>9. Chairperson, CEA</li> <li>10. CMDs of CPSEs, CMD NLC, Chairman of DVC/ BBMB/ EESL, DGs of BEE/ CPRI/ NPTI</li> <li>11. All Additional Secretaries/ JSs/ EA/ CE, Ministry of Power</li> </ol> <p data-bbox="508 999 597 1020">Copy to:</p> <p data-bbox="570 1024 1252 1066">Director (Technical), NIC with a request to publish the Order on the website of Ministry of Power</p>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 67 OF 119




CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			
	<p style="text-align: right;"><b>APPENDIX</b></p> <p><b><u>Extracts of important provisions contained in DPIIT Order No. P-45021/2/2017-PP (BE-II) dated 16-09-2020</u></b></p> <p>1. <b>Definitions (Para 2 of DPIIT order):</b></p> <p><b>'Local content'</b> means the amount of value added in India which shall, unless otherwise prescribed by the Nodal Ministry, be the total value of the item procured (excluding net domestic indirect taxes) minus the value of imported content in the item (including all customs duties) as a proportion of the total value, in percent.</p> <p><b>'Class-I local supplier'</b> means a supplier or service provider, whose goods, services or works offered for procurement, meets the minimum local content as prescribed for 'Class-I local supplier' under this Order.</p> <p><b>'Class-II local supplier'</b> means a supplier or service provider, whose goods, services or works offered for procurement, meets the minimum local content as prescribed for 'Class-II local supplier' but less than that prescribed for "Class-I Local supplier" under this Order.</p> <p><b>'Non-Local supplier'</b> means a supplier or service provider, whose goods, services or works offered for procurement, has local content less than that prescribed for 'Class-II local supplier' under this Order.</p> <p><b>'L1'</b> means the lowest tender or lowest bid or the lowest quotation received in a tender, bidding process or other procurement solicitation as adjudged in the evaluation process as per the tender or other procurement solicitation.</p> <p><b>'Margin of purchase preference'</b> means the maximum extent to which the price quoted by a 'Class-I local supplier' may be above the L1 for the purpose of purchase preference.</p> <p><b>'Nodal Ministry'</b> means the Ministry or Department identified pursuant to this order in respect of a particular item of goods or services or works.</p> <p><b>'Procuring entity'</b> means a Ministry or department or attached or subordinate office of, or autonomous body controlled by, the Government of India and includes Government companies as defined in the Companies Act.</p> <p><b>'Works'</b> means all works as per Rule 130 of GFR- 2017, and will also include 'turnkey works'.</p> <p>2. <b>Eligibility of 'Class-I local supplier'/ 'Class-II local supplier'/ 'Non-local suppliers' for different types of procurement (Para 3 of DPIIT order)</b></p> <p>(a) In procurement of all goods, services or works in respect of which the Nodal Ministry / Department has communicated that there is sufficient local capacity and local competition, only 'Class-I local supplier', as defined under the Order, shall be eligible to bid irrespective of purchase value.</p> <p>(b) Only 'Class-I local supplier' and 'Class-II local supplier', as defined under the Order, shall be eligible to bid in procurements undertaken by procuring entities, except when Global tender enquiry has been issued. In global tender enquiries, 'Non-local suppliers' shall also be eligible to bid along with 'Class-I local suppliers' and 'Class-II local suppliers'. In procurement of all goods, services or works, not covered by 3(a) above, and with estimated value of purchases less than Rs 200 crores, in accordance with Rule 161(iv) of GFR, 2017 Global tender enquiry shall not</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 68 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS <div data-bbox="1284 113 1422 180" style="float: right;">  </div>		
	<p>be issued except with the approval of competent authority as designated by Department of Expenditure.</p> <p>(c) For the purpose of this Order, works includes Engineering, Procurement and Construction (EPC) contracts and services include System Integrator (SI) contracts.</p> <p><b>3. Purchase Preference (Para 3A of DPIIT order)</b></p> <p>(a) Subject to the provisions of this Order and to any specific instructions issued by the Nodal Ministry or in pursuance of this Order, purchase preference shall be given to 'Class-I local supplier' in procurements undertaken by procuring entities in the manner specified here under.</p> <p>(b) In the procurements of goods or works, which are covered by para 3(b) of DPIIT Order No. P-45021/2/2017-PP(BE-II) dated 16-09-2021 and which are divisible in nature, the "Class-I local supplier" shall get purchase preference over 'Class-II local supplier' as well as 'Non-local supplier', as per following procedure:</p> <ol style="list-style-type: none"> <li>i. Among all qualified bids, the lowest bid will be termed as L1 If L1 is 'Class-I local supplier', the contract for full quantity will be awarded to L1.</li> <li>ii. If L1 bid is not a 'Class-I local supplier', 50% of the order quantity shall be awarded to L1. Thereafter, the lowest bidder among the 'Class-I local supplier' will be invited to match the L1 price for the remaining 50% quantity subject to the Class-I local supplier's quoted price falling within the margin of purchase preference, and contract for that quantity shall be awarded to such 'Class-I local supplier' subject to matching the L1 price. In case such lowest eligible 'Class-I local supplier' fails to match the L1 price or accepts less than the offered quantity, the next higher 'Class-I local supplier' within the margin of purchase preference shall be invited to match the L1 price for remaining quantity and so on, and contract shall be awarded accordingly. In case some quantity is still left uncovered on Class-I local suppliers, then such balance quantity may also be ordered on the L1 bidder.</li> </ol> <p>(c) In the procurements of goods or works, which are covered by para 3(b) of DPIIT Order No. P-45021/2/2017-PP(BE-II) dated 16-09-2021 and which are not divisible in nature, and in procurement of services where the bid is evaluated on price alone, the 'Class-I local supplier' shall get purchase preference over 'Class-II local supplier' as well as 'Non-local supplier', as per following procedure:</p> <ol style="list-style-type: none"> <li>iii. Among all qualified bids, the lowest bid will be termed as L1. If L1 is 'Class-I local supplier', the contract will be awarded to L1,</li> <li>iv. If L1 is not 'Class-I local supplier', the lowest bidder among the 'Class-I local supplier', will be invited to match the L1 price subject to Class-I local supplier's quoted price falling within the margin of purchase preference, and the contract shall be awarded to such 'Class-I local supplier' subject to matching the L1 price.</li> <li>v. In case such lowest eligible 'Class-I local supplier' fails to match the L1 price, the 'Class-I local supplier' with the next higher bid within the margin of purchase preference shall be invited to match the L1 price and so on and contract shall be awarded accordingly. In case none of the 'Class-I local supplier' within the margin of purchase preference matches the L1 price, the contract may be awarded to the L1 bidder.</li> </ol> <p>(d) "Class-II local supplier" will not get purchase preference in any procurement, undertaken by procuring entities.</p>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 69 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS <div data-bbox="1284 113 1425 184" style="text-align: right;">  </div>		
	<p>4. <b>Applicability in tenders where contract is to be awarded to multiple bidders</b> (<i>Para 3B of DPIIT order</i>)-  In tenders where contract is to be awarded to multiple bidders subject to matching of L1 rates or otherwise, the 'Class-I local supplier' shall get purchase preference over 'Class-II local supplier' as well as 'Non-local supplier', as per following procedure:</p> <p>a) In case there is sufficient local capacity and competition for the items to be procured, as notified by the Nodal Ministry, only 'Class-I local supplier' shall be eligible to bid. As such, the multiple supplier who would be awarded the contract, should be all and only 'Class-I local suppliers'.</p> <p>b) In other cases, 'Class-II local suppliers' and 'Non-Local suppliers' may also participate in the bidding process along with 'Class-I local supplier' as per provisions of this order.</p> <p>c) If 'Class-I local supplier' qualify for award of contract for at least 50% of the tendered quantity in any tender, the contract may be awarded to all the qualified bidders as per award criteria stipulated in the bid documents. However, in case 'Class-I local supplier' do not qualify for award of the contract for at least 50% of the tendered quantity, purchase preference should be given to the 'Class-I local supplier' over 'Class-II local supplier'/'Non-local suppliers' provided that their quoted rate falls within 20% margin of purchase preference of the highest quoted bidder considered for award of contract so as to ensure that the 'Class-I local suppliers' taken in totality or considered for award of contract for at least 50% of the tendered quantity.</p> <p>d) First purchase preference has to be given to the lowest quoting 'Class-I local supplier', whose quoted rates fall within 20% margin of purchase preference subject to its meeting the prescribed criteria for award of contract as also the constraints of maximum quantity that can be sourced from any single supplier. If the lowest quoting 'Class-I local supplier', does not qualify for purchase preference because of aforesaid constraints or does not accept the offered quantity, an opportunity may be given to next higher 'Class-I local supplier' falling within 20% margin of purchase preference, and so on.</p> <p>e) To avoid any ambiguity during bid evaluation process, the procuring entities may stipulate its own tender specific criteria for award of contract amongst different bidders including the procedure for purchase preference to 'Class-I local supplier' within the broad policy guidelines stipulate in sub-paras above.</p> <p>5. <b>Exemption of small purchases</b> (<i>Para 4 in DPIIT order</i>): Procurements where the estimated value to be procured is less than Rs. 5 lakhs shall be exempt from this Order. However, it shall be ensured by procuring entities that procurement is not split for the purpose of avoiding the provisions of this Order.</p> <p>6. <b>Minimum Local Content</b> (<i>Para 5 in DPIIT order</i>): The 'local content' requirement to categorize a supplier as 'Class-I local supplier' is minimum 50%. For 'Class-II local supplier', the local content requirement is minimum 20%. Nodal Ministry/Department may prescribe only a higher percentage of minimum local content requirement to categorize a supplier as 'Class-I local supplier'/'Class-II local supplier'. For the item for which Nodal Ministry/Department has not prescribed higher minimum local content notification under the order, it shall be 50% and 20% for 'Class-I local supplier'/'Class-II local supplier' respectively.</p>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 70 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
	<p>7. Vide DPIIT OM No. P-45021/102/2019-BE-IIPart(1) (E-50310) dated 4.03.2021 services such as transportation, insurance, installation, commissioning, training and after sales service support like AMC/CMC etc. shall not be considered as local value addition. Bidders offering imported products will fall under the category of Non- local suppliers. They can't claim themselves as Class-I local suppliers/Class-II local suppliers by claiming the services such as transportation, insurance, installation, commissioning, training and after sales service support like AMC/CMC etc. as local value addition.</p> <p>8. <b>Margin of Purchase Preference</b> (Para 6 of DPIIT order): The margin of purchase preference shall be 20%.</p> <p>9. <b>Specifications in Tenders and other procurement solicitations</b> (Para 10 of DPIIT order):</p> <ol style="list-style-type: none"> <li>Every procuring entity shall ensure that the eligibility conditions in respect of previous experience fixed in any tender or solicitation do not require proof of supply in other countries or proof of exports.</li> <li>Procuring entities shall endeavour to see that eligibility conditions, including on matters like turnover, production capability and financial strength do not result in unreasonable exclusion of 'Class-I local supplier'/ 'Class-II local supplier' who would otherwise be eligible, beyond what is essential for ensuring quality or creditworthiness of the supplier.</li> <li>Procuring entities shall, within 2 months of the issue of this Order review all existing eligibility norms and conditions with reference to sub-paragraphs 'a' and 'b' above.</li> <li><b>Reciprocity Clause:</b> <ol style="list-style-type: none"> <li>When a Nodal Ministry/Department identifies that Indian suppliers of an item are not allowed to participate and/ or compete in procurement by any foreign government, due to restrictive tender conditions which have direct or indirect effect of barring Indian companies such as registration in the procuring country, execution of projects of specific value in the procuring country etc. it shall provide such details to all its procuring entities including CMDs/CEOs of PSEs/PSUs, State Governments and other procurement agencies under their administrative control and GeM for appropriate reciprocal action.</li> <li>Entities of countries which have been identified by the nodal Ministry/Department as not allowing Indian companies to participate in their Government procurement for any item related to that nodal Ministry shall not be allowed to participate in Government procurement in India for all the items related to that nodal Ministry/Department, except for the list of items published by the Ministry/Department permitting their participation.</li> <li>The stipulation in (ii) above shall be part of all tenders invited by the Central Government procuring entities stated in (i) above. All purchase on GeM shall also necessarily have the above provisions for items identified by nodal Ministry/Department.</li> <li>State Governments should be encouraged to incorporate similar provisions in their respective tenders.</li> <li>The term 'entity' of a country shall have the same meaning as under the FDI Policy of DPIIT as amended from time to time.</li> </ol> </li> <li>Specifying foreign certification/ unreasonable technical specifications/ brands/ models in the bid document is restrictive and discriminatory practice against local</li> </ol>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 71 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS <div data-bbox="1284 113 1429 184" style="float: right;">  </div>		
	<p>suppliers. If foreign certification is required to be stipulated because of non-availability of Indian Standards and/ or for any other reason, the same shall be done only after written approval of Secretary of Department concerned or any other authority having been designated such power by the Secretary of the Department concerned.</p> <p>f. "All administrative Ministries/Departments whose procurement exceeds Rs. 1000 Crore per annum shall notify/ update their procurement projections every year, including those of PSEs/PSUs, for the next 5 years on their respective website."</p>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 72 OF 119

## Annexure-I

Sl. No.	Electrical Equipment for Generation, Transmission and Distribution sectors with sufficient local capacity and competition	Class-I Local Supplier (Minimum Local Content (%))
<b>(A) Common items for Transmission, Distribution and Generation Sector</b>		
1	Power Transformers (up to 765 kV, including Generator transformers)	60
2	Instrument Transformer (up to 765 kV)	60
3	Transformer Oil Dry Out System (TODOS)	60
4	Reactors up to 765 kV	60
5	Oil Impregnated Bushing (up to 400 kV)	60
6	Resin Insulated Paper (RIP) bushings (up to 145 kV)	50
7	Circuit Breakers (up to 765 kV AC - Alternating Current)	60
8	Disconnectors/Isolators (up to 765 kV AC)	60
9	Wave trap (up to 765 kV AC)	60
10	Oil Filled Distribution Transformers up to & including 33 kV [Cold Rolled Grain Oriented (CRGO)/Amorphous, Aluminium/Copper wound]	60
11	Dry Type Distribution Transformer upto and including 33 kV (CRGO/Amorphous, Aluminium/Copper wound )	60
12	Conventional Conductor	60
13	Accessories for Conventional conductors	60
14	High Temperature/High Temperature Low Sag (HTLS) conductors (such as Composite core, GAP, ACSS, INVAR, AL59) and Accessories	60
15	Optical ground wire (OPGW) – all designs	60
16	Fiber Optic Terminal Equipment (FOTE) for OPGW	50
17	OPGW related Hardware and Accessories	60
18	Remote Terminal Unit (RTU)	50
19	Power Cables and accessories up to 33 kV	60
20	Control cables including accessories	60
21	XLPE Cables up to 220 kV	60
22	Substation Structures	60
23	Transmission Line Towers	60
24	Porcelain (Disc/Long Rod) Insulators	60
25	Bus Post Insulators (Porcelain)	60
26	Porcelain Disc Insulators with Room Temperature Vulcanisation (RTV) coating	50
27	Porcelain Longrod Insulators with Room Temperature Vulcanisation (RTV) coating	50
28	Hardware Fittings for Porcelain Insulators	60
29	Composite/Polymeric Long Rod Insulators	60
30	Hardware Fittings for Polymer Insulators	60
31	Bird Flight Diverter (BFD)	60
32	Power Line Carrier Communication (PLCC) System (up to 800 kV)	60
33	Gas Insulated Switchgear (up to 400 kV AC)	60
34	Gas Insulated Switchgear (above 400 kV AC)	50
35	Surge/Lightning Arrester (up to 765 kV AC)	60
36	Power Capacitors	60
37	Packaged Sub-station (6.6 kV to 33 kV)	60
38	Ring Main Unit (RMU) (up to 33 kV)	60
39	Medium Voltage (MV) GIS Panels ( up to 33 kV)	60
40	Automation and Control System/Supervisory Control and data Acquisition (SCADA) System in Power System	50
41	Control and Relay Panel (including Digital/Numerical Relays)	50
42	Electrical Motors 0.37 kW to 1 MW	60
43	Energy Meters excluding smart meters	50
44	Control & power cables and Accessories (up to 1.1 kV)	60
45	Diesel Generating (DG) set	60



Sl. No.	Electrical Equipment for Generation, Transmission and Distribution sectors with sufficient local capacity and competition	Class-I Local Supplier (Minimum Local Content (%))
46	DC system (DC Battery & Battery Charger)	60
47	AC & DC Distribution Board	60
48	Indoor Air Insulated Switchgear (AIS) upto 33 kV	60
49	Poles (PCC, PSCC, Rolled Steel Joist, Rail Pole, Spun, Steel Tubular)	60
50	Material for Grounding/earthing system	60
51	Illumination system	60
52	Overhead Fault Sensing Indicator (FSI)	50
53	Power Quality Meters	50
54	Auxiliary Relays	50
55	Load Break Switch	50
<b>(B) Hydro Sector</b>		
56	Hydro Turbine & Associated equipment	
	a) Francis Turbine	60
	b) Kaplan Turbine	60
	c) Pelton Turbine	50
57	Main Inlet Valve & Associated Equipment	60
58	Penstock Protection Valve and Associated Equipment	60
59	Governing system & Accessories	60
60	Generator for Hydro Project & Associated Equipment	60
61	Static Excitation System	60
62	Workshop Equipment	60
63	Cooling Water System	60
64	Compressed Air System	60
65	Drainage/Dewatering System	60
66	Fire Protection System	60
67	Heating, Ventilation & Air Conditioning System (HVAC)	60
68	Oil Handling System	60
69	Mechanical Balance of Plant (BOP) Items	60
<b>(C) Thermal Sector</b>		
<b>Boiler Auxiliaries</b>		
70	Air Pre-Heater	60
71	Steam Coil Air Pre Heater (SCAPH)	60
72	Steam soot blowers [wall blowers & Long Retractable Soot Blower (LRSB)]	60
73	Auxiliary Steam Pressure Reducing & Desuperheating (PRDS)	60
74	Fuel oil system	60
75	Seal air Fan	60
76	Ducts and dampers	60
77	Duct expansion joints	60
78	Blowdown tanks	60
79	Coal burners and oil burners	60
80	Coal mills	60
81	Gear Box of Coal Mill	50
82	Coal feeders	60
83	Primary Air Fans	60
84	Forced Draft Fans	60
85	Induced Draft Fans	60
86	Forced Draft (FD)/Induced Draft (ID)/ Primary Air (PA) Fan Servo Motor Assembly	50
87	Tubes (Carbon Steel)	50
88	Steam pipes (Carbon Steel)	50
89	Steam drum	50
90	Separator	50
91	Selective Catalytic Reduction (SCR)	50

Sl. No.	Electrical Equipment for Generation, Transmission and Distribution sectors with sufficient local capacity and competition	Class-I Local Supplier (Minimum Local Content (%))
	<b>Electro-Static Precipitators (ESPs)</b>	
92	Casing	60
93	Electrodes	60
94	Rapping System	60
95	Hopper Heaters	60
96	Transformer Rectifiers	60
97	Insulators	60
	<b>Turbine &amp; Auxiliaries</b>	
98	Turbine (High Pressure/Intermediate Pressure/Low Pressure)	50
99	Condensate Extraction Pumps	60
100	Condenser On line Tube Cleaning System (COLTC)	60
101	Debris filters	60
102	Deaerator	60
103	Drain Cooler and Flash Tank	60
104	ECW Pump	50
105	Plate Heat Exchanger	50
106	Self- cleaning filters	50
107	Condensate Polishing Units (CPUs)	60
108	Chemical Dosing System	60
109	Oil Filter	60
110	Gland Steam Condenser	60
111	Oil Purifying Centrifuge	50
112	Water Cooled Condenser	50
113	Boiler Feed Pumps (BFPs)	50
	<b>Generator and Auxiliaries</b>	
114	Generator (including Seal Oil System, Hydrogen Cooling System, Stator water cooling system)	60
	<b>Electrical Works</b>	
115	Control and metering equipment	60
	<b>Control &amp; Instrumentation System (C&amp;I System)</b>	
116	Thermocouples	50
117	Measuring instruments [Resistance Temperature Detectors (RTDs)], Local gauges	50
118	Actuators (Pneumatic and conventional electric)	50
119	Interplant Communication/ Public Address (PA) system except IP based	50
	<b>Coal Handling Plant</b>	
120	Conveyors	60
121	Wagon Tippler	60
122	Side Arm Charger	60
123	Paddle feeder	60
124	Crushers & Screens	60
125	Dust suppression (dry fog & plain water) system	60
126	Air Compressors	50
127	Magnetic separators & metal detectors	60
128	Coal Sampling System	60
129	Stacker cum reclaimer	60
130	Belt weighing & monitoring system	60
131	Wheel & axle assembly (without bearings) for Bottom Opening Bottom Release (BOBR) Wagons	60
	<b>Ash Handling System</b>	
132	Clinker grinder	60
133	Water jet ejectors	60
134	Scraper chain conveyor	60
135	Dry fly ash vacuum extraction system	60
136	Pressure pneumatic conveying system	60




Sl. No.	Electrical Equipment for Generation, Transmission and Distribution sectors with sufficient local capacity and competition	Class-I Local Supplier (Minimum Local Content (%))
137	Ash water & ash slurry pumps	60
138	Compressors, air dryers & air receivers	50
139	Ash water recovery system	60
<b>Raw Water Intake &amp; Supply System</b>		
140	Travelling water screens	60
141	Raw water supply pumps	60
142	Valves, RE joints etc.	60
<b>Water Treatment System and Effluent Treatment System</b>		
143	Clarification plant	60
144	Filtration plant	60
145	Ultra filtration plant	50
146	Reverse Osmosis (RO) plant and its membrane	55
147	De-Mineralised water plant (DM Plant)	60
148	Chlorination plant	60
149	Chemical dosing system	60
150	Effluent Treatment Plant	60
<b>Circulating Water (CW) &amp; Auxiliary Circulating Water (ACW) System</b>		
151	CW & ACW Pumps	60
152	Butter Fly (BF) valves, Non-return Valves (NRVs) etc.	60
153	Rubber Expansion (RE) joints	60
154	Air release valves	60
<b>Cooling Towers (NDCT/ IDCT)-Natural-Draft and Induced Draft Cooling Tower</b>		
155	Water Distribution System	60
156	Spray nozzles	60
157	Packing	60
158	Drift eliminators	60
159	Cooling Tower (CT) Fans (for Induced Draft Cooling Towers IDCT)	60
160	Gear boxes, shafts & motors (for IDCT)	60
<b>Air Conditioning &amp; Ventilation System</b>		
161	Split & window air conditioners	60
162	Chilling/ condensing unit [upto 500 ton of refrigeration(TR)]	55
163	Air Handling Unit (AHU) and Fresh air unit	60
164	Cooling Towers	60
165	Air Washing Units (AWUs), axial fans, roof extractors	60
166	Ducts, louvers & dampers	60
<b>Flue Gas Desulphurization (FGD)</b>		
167	Spray Nozzles,	50
168	Spray header	50
169	Oxidation Blowers	50
170	Limestone wet Ball Mill	50
171	Slurry Handling Pumps for FGD system	50
172	Booster Fans for FGD system	50
173	Carbon Steel Ducts and Dampers for FGD	60
174	Storage Tanks and Silos	60
175	Process Water Pump for FGD system	50
<b>(D) Other Common Items</b>		
<b>Fire protection and detection system</b>		
176	Motor driven fire water pumps	60
177	Diesel engine driven fire water pumps	60
178	Hydrant system for the power plant.	60
179	High velocity water spray system	60
180	Medium velocity water spray system	60
181	Foam protection system	60
182	Inert gas flooding system	60

Sl. No.	Electrical Equipment for Generation, Transmission and Distribution sectors with sufficient local capacity and competition	Class-I Local Supplier (Minimum Local Content (%))
183	Fire tenders	60
184	Portable fire-extinguishers	60
185	Cranes, EOT cranes, gantry crane & chain pulley blocks etc.	60
186	Elevator	60

**(E) Minimum Local Content percentages in Engineering, Procurement & Construction (EPC) / Turnkey project**

In case the contract is awarded through the EPC route, the contractor should comply with the requirement of MLC for individual items as listed in Annexure-I and should purchase these items only from Class-I Local supplier. In addition, MLC for complete EPC project may also be prescribed as below:

	(1) Package Based Works	Minimum Local Content (%)
1	Boiler	60
2	TG System ( Water Cooled Condenser)	60
3	Ash Handling Plant	60
4	Coal Handling Plant	60
5	Electro-static Precipitator (ESP)	60
6	Circulating Water (CW) System	60
7	Cooling Tower	60
8	Water Treatment System	60
9	Air Conditioning System ( below 500TR)	60
10	Flue Gas Desulphurisation (FGD) System	60
11	Station Control & Instrumentation (C&I)	50
12	Hydro Power Projects (Electro-Mechanical Works)	60
	<b>Gas based generation</b>	
	<b>Overall Gas Turbine Package (on finished Product basis)</b>	
13	< 44 MW	60
14	44 – 145 MW	50
	<b>Overall Combined Cycle Gas Turbine (CCGT) Package (on finished Product basis)</b>	
15	< 44 MW	60
16	44 – 145 MW	60
17	> 150 MW	60
	<b>(2) Project as a whole</b>	
1	Works and service contracts in Power Sector	60
2	Transmission Line with Conventional conductors (ACSR, AAAC, AL-59 etc.)	60
3	Transmission Line with High temperature Low Sag (HTLS) conductors	60
4	HVAC Substation Air Insulated (AIS)	60
5	HVAC Substation Gas Insulated (GIS)	60
6	HVDC Substation	60
7	Distribution Sector	60

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS <div data-bbox="1284 113 1422 180" style="float: right;">  </div>		
	<div data-bbox="1203 327 1330 352" style="text-align: right;">Annexure-II</div> <p data-bbox="475 380 1330 428">General guidelines to be adopted selectively in an appropriate manner by the procuring entities in their tender documents.</p> <ol data-bbox="509 455 1336 1486" style="list-style-type: none"> <li>1. The bidder shall have to be an entity registered in India in accordance with law.</li> <li>2. The bids shall be in the language as prescribed by the tenderer/procurer.</li> <li>3. The bids shall be in Indian Rupees (INR) (in respect of local content only).</li> <li>4. Indian subsidiaries of foreign bidders shall have to meet the qualifying criteria in terms of capability, competency, financial position, past performance etc.</li> <li>5. The bidder shall follow Indian laws, regulations and standards.</li> <li>6. To be eligible for participation in the bid, foreign bidders shall compulsorily set up their manufacturing units on a long term basis in India as may be specified by the tenderer/ procurer.</li> <li>7. Similar or better technology than the technology offered in respect of material, equipment and process involved shall be transferred to India. Along with the transfer of technology, adequate training in the respective field shall also be provided.</li> <li>8. Country of origin of the equipment/material shall be provided in the bid.</li> <li>9. For supply of equipment / material from the country of origin other than India, the bidder shall submit performance certificate in support of satisfactory operation in India or a country other than the country of origin having climatic and operational conditions including ambient temperature similar to that of India for more than _____ years (to be specified by the procurer).</li> <li>10. The technologies/ products offered shall be environmental friendly, consuming less energy, safe, energy efficient, durable and long lasting under the prescribed operational conditions.</li> <li>11. The supplier shall ensure supply of spares, materials and technological support for the entire life of the project.</li> <li>12. The manufacturers/ supplier shall list out the products and components producing Toxic E-waste and other waste as may be specified. It shall have an Extended Producers Responsibility (EPR) so that after the completion of the lifecycle, the materials are safely recycled / disposed of by the Manufacturer/ supplier and for this, the Manufacturer/supplier along with procurer has to establish recycling / disposal unit or as may be specified.</li> <li>13. Minimum Local Content requirement for goods, services or works shall be in accordance with the conditions laid down in respective Order(s) of the sectors on Public Procurement (Preference to Make in India) to provide for purchase preference (linked with local content).</li> </ol>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 78 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			<div>एन टी पी सी NTPC</div>
	<div>14. The equipment/ material sourced from foreign companies may be tested in accredited labs in India before acceptance wherever such facilities are available.</div> <div>15. The Tender fee and the Bank Guarantee (BG) shall be in Indian Rupees only.</div> <div>16. The bidder shall have to furnish a certificate regarding cyber security/safety of the equipment/process to be supplied/services to be rendered as safe to connect.</div> <div>17. Applicable safety requirements shall be met. Regular safety audit shall be carried out by the manufacturer/ supplier.</div> <div>18. Statutory laws/regulations including the labour and environmental laws shall be strictly complied with during supply, storage, erection, commissioning and operation process. A regular compliance report shall be submitted to the procurer/appropriate Authorities.</div> <div>19. Formation of new joint venture in India shall be permitted only with the Indian companies.</div> <div>20. Tendering by the agent shall not be accepted.</div> <div>21. In case local testing is not considered necessary by the procurer, the original test report in the language prescribed by the procurer may be accepted. The translated test report shall not be accepted unless it is notarised.</div> <div>22. Certification/compliance as per the Indian Standards/ International Standards/ Indian Regulations/ specified Standards shall be mandatory, where ever applicable.</div> <div>23. Quality assurance of the product shall be carried out by the procurer or an independent third party agency appointed by the procurer. Manufacturing Quality Plan as approved by the procurer shall be followed by the manufacturer/supplier.</div> <div>24. Wherever required by the procurer, foreign supplier shall establish fully functional service centers in India and shall keep spares/material locally for future needs of utilities.</div> <div>25. Arbitration proceedings shall be instituted in India only and all disputes shall be settled as per applicable Indian Laws.</div>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 79 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			<div>एनटीपीसी NTPC</div>
	LIST OF CODES AND STANDARDS			
	Indian Standards	Title	International and Internationally recognised standards	
	IS:277	Galvanised steel sheets (plain or corrugated)		
	IS:655	Specification for metal air duct		
	IS:800	Code of practice for use of structural steel in general building construction	BS 449:1969 BS 5950 ASA A57, 1-1952	
	IS:807	Code of practice for design, manufacture, erection and testing (Structural portion) of cranes and hoists 6588 (Issued by Standards Association of Australia). DIN 120:1936 (Sheet 1) DIN 120:1936 (Sheet 2) 327 part-I, 1951 BS 466 part-II, 1960 BS 644:1960 BS 1757:1951 BS 2573:part-I:1960	Draft Revision of A.S. NO. CS.2 SAA Crane and Hoist code Doc:No. BU/4 Rev	
	IS:875	Code of practice for design loads (other than earthquake) for buildings and structures Leading standards (issued by Canadian Standard) DIN-1055-1955 (Issued by ASA)	National Building code of Canada (1953)-Part-IV  Design section 4.1	
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 80 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
	IS:1239 Part-I	Mild steel tubes	(ISO/R 65-1957) (ISO/R-64-1958) (ISO/R-65-1958) (BS 1387 : 1957)	
	IS:1239 Part-II	Mild steel tubulars and other wrought steel pipe fittings	BS 1387 : 1967 BS 1387 :1967 BS 1740 :1965	
	IS:2825	Code for unfired vessels		
	IS:1520	Horizontal centrifugal pumps for clear cold and fresh water		
	IS:1600	Code for practice for performance of constant speed IC Engines for general purpose		
	IS:1601	Specification for perform- ance of constant speed IC Engines for general Purpose		
	IS:1893	Criteria for earthquake resistant design of structures		
	IS1978-1971	Line Pipe April 1969.	API Standards 5L	
	IS:2254-1970	Dimensions of vertical shaft motor for pumps	IEC Pub 72-1 part I NEMA Pub MG 1 1954	
	IS:2266	Steel wire ropes for general engineering purposes	BS :302 : 1968	
	IS:2312	Propellant type Ventilation fans		
	IS:2365	Steel wire suspension ropes for lifts and hoists	BS : 1957	
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C		GENERAL TECHNICAL REQUIREMENTS  PAGE 81 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
	IS:3346	Method for the determination of thermal conductivity of thermal insulation materials (two slab guarded hot plate method)	DIN 52612 (Deutscher Normenausschuss) ASTM C 163-1964 (American Society of Testing and materials) ASTM C 167-1974 ASTM C 177-1963	
	IS:3354	Outline dimensions for electric lifts.		
	IS:3401	Silica gel		
	IS:3588	Specification for electrical axial flow fans		
	IS:3589	Electrically welded steel pipes for water, gas and sewage (200mm to 2000 mm Nominal Diametre)		
	IS:3677	Unbonded rock and slag wool for thermal insulation		
	IS:3815	Point hook with shank for general engineering purposes	BS 482 - 1968 Doc.:67/3 1284 (Revision of BS 2903) (Issued BS)	
	IS:3895	Specification for monocry-stallines semiconductor rectifier cells and stacks		
	IS:3963	Roof extractor unit		
	IS:3975	Mild steel wires, strips and tapes for armouring cables		
	IS:4503	Shell and tube type heat Exchanger		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C		GENERAL TECHNICAL REQUIREMENTS  PAGE 82 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनडीपीसी NTPC
	<p>IS:4540</p> <p>IS:4671</p> <p>IS:4736</p> <p>IS:4894</p> <p>IS:5456</p> <p>IS:5749</p> <p>IS:6392</p> <p>IS:6524 Part-I</p> <p>IS:7098</p> <p>IS:7373</p> <p>IS:7938</p> <p>ISO:1217</p> <p>ASHRAE-33 and air heating coils.</p> <p>ASHRAE-52-76 particle matter.</p>	<p>Specification for monory- stallines rectifire assembly equipment</p> <p>Expanded polystyrene for thermal insulation purpose</p> <p>Hot dip zinc coating on steel tubes</p> <p>Centrifugal fans</p> <p>Code of practice for testing of positive displacement type air compressors and exhauster (For Test Tolerance Only)</p> <p>Forged ramshorn hooks</p> <p>Steel pipe flanges</p> <p>Code of practice for design of tower cranes Static and rail mounted</p> <p>Cross linked Polyethylene insulated PVC sheathed cables</p> <p>Specification for wrought aluminium and aluminium sheet and strips</p> <p>Air receivers for compressed air installation</p> <p>Displacement compressor-Acceptance test</p> <p>Methods of testing for rating of forced circulation air cooling</p> <p>Air cleaning device used in general ventilation for removing</p>	<p></p> <p></p> <p></p> <p></p> <p></p> <p>Entwurf DIN 15402 Blett 1 Entwurf DIN 15402 BS 3017-1958</p> <p>BS 4504 : 1969</p> <p>BS 2799 : 1956</p> <p>Standard No. 1 to IPCEA (USA) Pub. No. 5-66-524</p> <p></p> <p></p> <p></p> <p></p>	
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C		GENERAL TECHNICAL REQUIREMENTS  PAGE 83 OF 119



CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS	एनडीपीसी NTPC		
	<p>ASHRAE-22-72      Method of testing for rating of water cooled refrigerant condensers.</p> <p>ASHRAE 23-67      Methods of testing for rating of positive displacement refrigerant compressors.</p> <p>ARI-450-6            Standard for water cooled refrigerant condensers.</p> <p>ARI-550              Standard for centrifugal water chilling packages.</p> <p>ARI-410              Standard for forced circulation air cooling and air heating coils</p> <p>ARI-430/435          Central station AHU/Application of Central Station AHU BS:848                Fans (Part-1,2)</p> <p>BS:400                Low carbon steel cylinders for the storage &amp; transport of permanent gases.</p> <p>BS:401                Low carbon steel cylinders for the storage &amp; transport of liquified gases.</p> <p>CTI Code             Acceptance test code for Water Cooling Tower. ACT-105</p> <p>ANSI-31.5            Refrigerant piping</p> <p>ASME-PTC-           Atmospheric Water Cooling Equipment 23-1958</p> <p>AMCA A-21C          Test Code for air moving devices</p> <p>API:618              Reciprocating Compressor for general refinery services.</p> <p>HYDRAULIC INSTITUTE STANDARDS.</p> <p>HYDRANT SYSTEM MANUALS OF TAC.</p> <p>TAC MANUALS OF SPRAY SYSTEM</p> <p>NFPA USA/ NSC UK/ UL USA/ FM USA STANDARDS.</p> <p>INDIAN EXPLOSIVES ACT.</p> <p>INDIAN FACTORIES ACT.</p> <p>STANDARD OF TUBULAR EXCHANGER MANUFACTURER'S ASSOCIATION.</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 84 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS	एनडीपीसी NTPC		
	<p><b>CODE AND STANDARD FOR CIVIL WORKS</b></p> <p>Some of the applicable Standards, Codes and references are as follows:</p> <p><b>Excavation &amp; Filling</b></p> <p>IS: 2720 (Part-II, IV TO VIII, XIV, XXI, XXIII, XXIV, XXVII TO XXIX, XL) Methods of test for soils-determination for water content etc.</p> <p>IS: 4701                      Code of practice for earth work on canals.</p> <p>IS: 9758                      Guidelines for Dewatering during construction.</p> <p>IS: 10379                    Code of practice for field control of moisture and compaction of soils for embankment and sub-grade.</p> <p><b>Properties, Storage and Handling of Common Building Materials</b></p> <p>IS: 269                      Specification for ordinary Portland cement, 33 grade.</p> <p>IS: 383                      Specification for coarse and fine aggregates from natural sources for concrete.</p> <p>IS: 432                      Specification for mild steel and (Parts 1&amp;2) medium tensile steel bars and hard-drawn steel wires for concrete reinforcement.</p> <p>IS: 455                      Specification for Portland slag cement.</p> <p>IS: 702                      Specification for Industrial bitumen.</p> <p>IS: 712                      Specification for building limes.</p> <p>IS: 808                      Rolled steel Beam channel and angle sections.</p> <p>IS: 1077                    Specification for common burnt clay building bricks.</p> <p>IS: 1161                    Specification of steel tubes for structural purposes.</p> <p>IS: 1363                    Hexagon head Bolts, Screws and nuts of production grade C.</p> <p>IS: 1364                    Hexagon head Bolts, Screws and Nuts of Production grade A &amp; B.</p> <p>IS: 1367                    Technical supply conditions for Threaded fasteners.</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 85 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS		<div>एनटीपीसी</div> <div>NTPC</div>	
	IS: 1489 (Part-I) (Part-II)	Specification for Portland-pozzolana cement: Fly ash based. Calcined clay based.		
	IS: 1542	Specification for sand for plaster.		
	IS: 1566	Specification for hard-drawn steel wire fabric for concrete reinforcement.		
	IS: 1786	Specification for high strength deformed bars for concrete reinforcement.		
	IS: 2062	Specification for steel for general structural purposes.		
	IS: 2116	Specification for sand for masonry mortars.		
	IS: 2386 (Parts-I to VIII)	Testing of aggregates for concrete.		
	IS: 3150	Hexagonal wire netting for general purpose.		
	IS: 3495 (Parts-I to IV)	Methods of tests of burnt clay building bricks.		
	IS: 3812	Specification for fly ash, for use as pozzolana and admixture.		
	IS: 4031	Methods of physical tests for hydraulic cement.		
	IS: 4032	Methods of chemical analysis of hydraulic cement.		
	IS: 4082	Recommendations on stacking and storage of construction materials at site.		
	IS: 8112	Specification for 43 grade ordinary portland cement.		
	IS: 8500	Medium and high strength structural steel.		
	IS: 12269	53 grade ordinary portland cement.		
	IS: 12894	Specification for Fly ash lime bricks.		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 86 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
	<p><b>Cast-In-Situ Concrete and Allied Works</b></p> <p>IS: 280                      Specification for mild steel wire for general engineering purposes.</p> <p>IS: 456                      Code of practice for plain and reinforced concrete.</p> <p>IS: 457                      Code of practice for general construction of plain &amp; reinforced concrete for dams &amp; other massive structures.</p> <p>IS: 516                      Method of test for strength of concrete.</p> <p>IS: 650                      Specification for standard sand for testing of cement.</p> <p>IS: 1199                     Methods of sampling and analysis of concrete.</p> <p>IS: 1791                     General requirements for batch type concrete mixers.</p> <p>IS: 1838 (Part-I)                     Specification for preformed fillers for expansion joints in concrete pavements and structures (non-extruding and resilient type).</p> <p>IS: 2204                     Code of practice for construction of reinforced concrete shell roof.</p> <p>IS: 2210                     Criteria for the design of reinforced concrete shell structures and folded plates.</p> <p>IS: 2438                     Specification for roller pan mixer.</p> <p>IS: 2502                     Code of practice for bending and fixing of bars for concrete reinforcement.</p> <p>IS: 2505                     General requirements for concrete vibrators, immersion type.</p> <p>IS: 2506                     General requirements for concrete vibrators, screed board type.</p> <p>IS: 2514                     Specification for concrete vibrating tables.</p> <p>IS: 2645                     Specification for Integral cement water proofing compounds.</p> <p>IS: 2722                     Specification for portable swing weigh batches for concrete. (single and double bucket type)</p> <p>IS: 2750                     Specification for Steel scaffolding.</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 87 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			<div>एनडीपीसी NTPC</div>
	IS: 2751	Code of practice for welding of mild steel plain and deformed bars for reinforced concrete construction.		
	IS: 3025	Methods of sampling and test waste water.		
	IS: 3366	Specification for Pan vibrators.		
	IS: 3370 (Part I to IV)	Code of practice for concrete structures for the storage of liquids.		
	IS: 3414	Code of practice for design and installation of joints in buildings.		
	IS: 3550	Methods of test for routine control for water used in industry.		
	IS: 3558 concrete.	Code of practice for use of immersion vibrators for consolidating concrete.		
	IS: 4014 (Parts I & II)	Code of practice for steel tubular scaffolding.		
	IS: 4326 of buildings.	Code of practice for earthquake resistant design and construction of buildings.		
	IS: 4461	Code of practice for joints in surface hydro-electric power stations.		
	IS: 4656	Specification for form vibrators for concrete.		
	IS: 4925	Specification for batching and mixing plant.		
	IS: 4990	Specification for plywood for concrete shuttering work.		
	IS: 4995 (Parts I & II)	Criteria for design of reinforced concrete bins for the storage of granular and powdery materials.		
	IS: 5256	Code or practice for sealing joints in concrete lining on canals.		
	IS: 5525	Recommendations for detailing of reinforcement in reinforced concrete work.		
	IS: 5624	Specification for foundation bolts.		
	IS: 6461	Glossary of terms relating to cement concrete.		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 88 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
	IS: 6494  IS: 6509  IS: 7861  IS: 9012  IS: 9103  IS: 9417  IS: 10262  IS: 11384  IS: 11504  IS: 12118  IS: 12200  IS: 13311 Part-1 Part-2  SP:23  SP: 24  SP: 34   <b>Precast Concrete Works</b>  SP: 7(PartVI/	Code of practice for water proofing of underground water reservoirs and swimming pools.  Code of practice for installation of joints in concrete pavements.  Code of practice for extreme weather concreting. (Parts I & II)  Recommended practice for shot concreting.  Specification for admixtures for concrete.  Recommendations for welding cold worked steel bars for reinforced concrete construction.  Recommended guidelines for concrete mix design.  Code of practice for composite construction in structural steel and concrete.  Criteria for structural design of reinforced concrete natural draught cooling towers.  Specification for two-parts poly sulphide.  Code of practice for provision of water stops at transverse contraction joints in masonry and concrete dams.  Method of non-destructive testing of concrete.  Ultrasonic pulse velocity.  Rebound hammer.  Handbook of concrete mixes  Explanatory Handbook on IS: 456-1978  Handbook on concrete reinforcement and detailing.   National Building Code- Structural design of prefabrication and Sec.7) systems building.		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 89 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनडीपीसी NTPC
	IS: 10297	Code of practice for design and construction of floors and roofs using precast reinforced/prestressed concrete ribbed or cored slab units.		
	IS: 10505	Code of practice for construction of floors and roofs using pre-cast reinforced concrete units.		
	<b>Masonry and Allied Works</b>			
	IS: 1905	Code of Practice for Structural Safety of Buildings-Masonry walls.		
	IS: 2212	Code of Practice for Brickwork.		
	IS: 2250	Code of Practice for Preparation and use of Masonry Mortar.		
	SP: 20	Explanatory handbook on masonry code.		
	<b>Sheeting Works</b>			
	IS:277	Galvanised steel sheets (plain or corrugated).		
	IS: 459	Unreinforced corrugated and semi-corrugated asbestos cement sheets.		
	IS: 513	Cold-rolled carbon steel sheets.		
	IS: 730	Specification for fixing accessories for corrugated sheet roofing.		
	IS: 1626	Specification for Asbestos cement building pipes and pipe fittings, gutters and gutter fittings and roofing fittings.		
	IS: 2527	Code of practice for fixing rain water gutters and down pipe for roof drainage.		
	IS: 3007	Code of practice for laying of asbestos cement sheets.		
	IS: 5913	Methods of test for asbestos cement products.		
	IS: 7178	Technical supply conditions for tapping screw.		
	IS: 8183	Bonded mineral wool.		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 90 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनडीपीसी NTPC
	IS: 8869  IS: 12093  IS: 12866  IS: 14246  <b>Fabrication and Erection of Structural Steel Work</b>  IS: 2016  IS: 814  IS: 1852  IS: 3502  IS: 6911  IS: 3757  IS: 6623  IS: 6649  IS: 800  IS: 816  IS: 4000  IS: 9595  IS: 817	Washers for corrugated sheet roofing.  Code of practice for laying and fixing of sloped roof covering using plain and corrugated galvanised steel sheets.  Plastic translucent sheets made from thermosetting polyester resin (glass fibre reinforced).  Specification for continuously pre-painted galvanised steel sheets and coils.  Specification for plain washers.  Specification for covered Electrodes for Metal Arc Welding for weld steel.  Specification for Rolling and Cutting Tolerances for Hot rolled steel products.  Specifications for chequered plate.  Specification for stainless steel plate, sheet and strip.  Specification for high strength structural bolts  Specification for high strength structural nuts.  High Tensile friction grip washers.  Code of practice for use of structural steel in general building construction.  Code of practice for use of Metal Arc Welding for General Construction.  Code of practice for assembly of structural joints using high tensile friction grip fasteners.  Code of procedure of Manual Metal Arc Welding of Mild Steel.  Code of practice for Training and Testing of Metal Arc Welders.		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 91 OF 119



CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनडीपीसी NTPC
	IS: 1811  IS: 9178  IS: 9006  IS: 7215  IS: 12843  IS: 4353  SP: 6 (Part 1 to 7)  IS: 1608  IS: 1599  IS : 228  IS : 2595  IS : 1182  IS : 3664  IS : 3613  IS : 3658  IS : 5334	Qualifying tests for Metal Arc Welders (engaged in welding structures other than pipes).  Criteria for Design of steel bins for storage of Bulk Materials.  Recommended Practice for Welding of Clad Steel.  Tolerances for fabrication steel structures.  Tolerance for erection of structural steel.  Recommendations for submerged arc welding of mild steel and low alloy steels.  ISI Handbook for structural Engineers.  Method of Tensile Testing of Steel products other than sheets, strip, wire and tube.  Method of Bend Tests for Steel products other than sheet, strip, wire and tube  Methods of chemical Analysis of pig iron, cast iron and plain carbon and low alloy steel.  Code of Practice for Radio graphic testing.  Recommended practice for Radiographic Examination of fusion welded butt joints in steel plates.  Code of practice for Ultra sonic Testing by pulse echo method.  Acceptance tests for wire flux combination for submerged Arc Welding.  Code of practice for Liquid penetrant Flaw Detection.  Code of practice for Magnetic Particle Flaw Detection of Welds.		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 92 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनडीपीसी NTPC
	<p><b>Plastering and Allied Works</b></p> <p>IS : 1635      Code of practice for field slaking of Building lime and preparation of putty.</p> <p>IS : 1661      Application of cement and cement lime plaster finishes.</p> <p>IS : 2333      Plaster-of-paris.</p> <p>IS : 2402      Code of practice for external rendered finishes.</p> <p>IS : 2547      Gypsum building plaster.</p> <p>IS : 3150      Hexagonal wire netting for general purpose.</p> <p><b>Acid and Alkali Resistant Lining</b></p> <p>IS : 158      Ready mixed paint, brushing, bituminous, black, lead free, acid, alkali &amp; heat resisting.</p> <p>IS : 412      Specification for expanded metal steel sheets for general purpose.</p> <p>IS : 4441      Code of practice for use of silicate type chemical resistant mortars.</p> <p>IS : 4443      Code of practice for use of resin type chemical resistant mortars.</p> <p>IS : 4456      Method of test for chemical resistant tiles. (Part I &amp; II)</p> <p>IS : 4457      Specification for ceramic unglazed vitreous acid resistant tiles.</p> <p>IS : 4832      Specification for chemical resistant mortars.</p> <p>Part I      Silicate type</p> <p>Part II      Resin type</p> <p>Part III      Sulphur type</p> <p>IS : 4860      Specification for acid resistant bricks.</p> <p>IS : 9510      Specification for bitumasitc, Acid resisting grade.</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 93 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS	एनडीपीसी NTPC		
	<p><b>Water Supply, Drainage and Sanitation</b></p> <p>IS : 458                      Specification for concrete pipes.</p> <p>IS : 554                      Dimensions for pipe threads, where pressure tight joints are made on thread.</p> <p>IS : 651                      Specification for salt glazed stoneware pipes.</p> <p>IS : 774                      Flushing cisterns for water closets and urinals.</p> <p>IS : 775                      Cast iron brackets and supports for wash basins and sinks.</p> <p>IS : 778                      Copper alloy gate, globe and check valves for water works purposes.</p> <p>IS : 781                      Cast copper alloy screw down bib taps and stop valves for water services.</p> <p>IS : 782                      Caulking lead.</p> <p>IS : 783                      Code of practice for laying of concrete pipes.</p> <p>IS : 1172                      Basic requirements for water supply, drainage and sanitation.</p> <p>IS : 1230                      Cast iron rain water pipes and fittings.</p> <p>IS : 1239                      Mild steel tubes, tubulars and other wrought steel fittings.</p> <p>IS : 1536                      Centrifugally cast (Spun) iron pressure pipes for water, gas and sewage.</p> <p>IS : 1537                      Vertically cast iron pressure pipes for water, gas and sewage.</p> <p>IS : 1538                      Cast iron fittings for pressure pipe for water, gas and sewage.</p> <p>IS : 1703                      Ball valves (horizontal plunger type) including float for water supply purposes.</p> <p>IS : 1726                      Cast iron manhole covers and frames.</p> <p>IS : 1729                      Sand cast iron spigot and socket, soil, water and ventilating pipes, fittings and accessories.</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 94 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			<div>एनडीपीसी NTPC</div>
	IS : 1742	Code of practice for building drainage.		
	IS : 1795	Pillar taps for water supply purposes.		
	IS : 1879	Malleable cast iron pipe fittings.		
	IS : 2064	Code of practice for selection, installation and maintenance of sanitary appliances.		
	IS : 2065	Code of practice for water supply in building.		
	IS : 2326	Automatic flushing cisterns for urinals.		
	IS : 2470 (Part-I & II)	Code of practice for installation of septic tanks.		
	IS : 2501	Copper tubes for general engineering purposes.		
	IS : 2548	Plastic seat and cover for water-closets.		
	IS : 2556 (Part 1 to 15)	Vitreous sanitary appliances (vitreous china).		
	IS : 2963	Non-ferrous waste fittings for wash basins and sinks.		
	IS : 3114	Code of practice for laying of cast iron pipes.		
	IS : 3311	Waste plug and its accessories for sinks and wash basins.		
	IS : 3438	Silvered glass mirrors for general purposes.		
	IS : 3486	Cast iron spigot and socket drain pipes.		
	IS : 3589	Electrically welded steel pipes for water, gas and sewage (200mm to 2000mm nominal diameter).		
	IS : 3989	Centrifugally cast (Spun) iron spigot and socket soil, waste and ventilating pipes, fittings and accessories.		
	IS : 4111 (Part I to IV)	Code of practice for ancillary structure in sewerage system.		
	IS : 4127	Code of practice for laying of glazed stone-ware pipes.		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 95 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
	<p>IS : 4764</p> <p>IS : 4827</p> <p>IS : 5329</p> <p>IS : 5382</p> <p>IS : 5822</p> <p>IS : 5961</p> <p>IS : 7740</p> <p>IS : 8931</p> <p>IS : 8934</p> <p>IS : 9762</p> <p>IS : 10446</p> <p>IS : 10592</p> <p>IS : 12592</p> <p>IS : 12701</p> <p>SP: 35</p> <p>-</p> <p><b>Doors, Windows and Allied Works</b></p> <p>IS : 204</p> <p>Part-I</p> <p>Part-II</p>	<p>Tolerance limits for sewage effluents discharged into inland-surface waters.</p> <p>Electro plated coating of nickel and chromium on copper and copper alloys.</p> <p>Code of practice for sanitary pipe work above ground for buildings.</p> <p>Rubber sealing rings for gas mains, water mains and sewers.</p> <p>Code of practice for laying of welded steel pipes for water supply.</p> <p>Cast iron grating for drainage purpose.</p> <p>Code of practice for road gullies.</p> <p>Cast copper alloy fancy bib taps and stop valves for water services.</p> <p>Cast copper alloy fancy pillar taps for water services.</p> <p>Polyethylene floats for ball valves.</p> <p>Glossary of terms for water supply and sanitation.</p> <p>Industrial emergency showers, eye and face fountains and combination units.</p> <p>Specification for precast concrete manhole covers and frames.</p> <p>Rotational moulded polyethylene water storage tanks.</p> <p>Handbook on water supply and drainage.</p> <p>Manual on Sewerage and sewage treatment (Published by CPH &amp; EEO) As updated.</p> <p>Tower Bolts</p> <p>Ferrous metals.</p> <p>Nonferrous metals.</p>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 96 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS		<div>एनटीपीसी NTPC</div>	
	IS : 208	Door Handles.		
	IS : 281	Mild steel sliding door bolts for use with padlocks.		
	IS : 362	Parliament Hinges.		
	IS : 420	Specification for putty, for use on metal frames.		
	IS : 1003 Part-I door	Specification for timber panelled and glazed shutters- (Part-I) shutters.		
	IS : 1038	Steel doors, windows and ventilators.		
	IS : 1081	Code of practice for fixing and glazing of metal (steel and aluminium) doors, windows and ventilators.		
	IS : 1341	Steel butt hinges.		
	IS : 1361	Steel windows for industrial buildings.		
	IS : 1823	Floor door stoppers.		
	IS : 1868	Anodic coatings on Aluminium and its alloys.		
	IS : 2202 (Part-II)	Specification for wooden flush door shutters (solid core type); particle board face panels and hard board face panels		
	IS:2209	Mortice locks (vertical type).		
	IS:2553	Safety glass		
	IS:2835	Flat transparent sheet glass.		
	IS:3548	Code of practice for glazing in buildings.		
	IS:3564	Door closers (Hydraulically regulated).		
	IS : 3614	Fire check doors; plate, metal covered and rolling type.		
	IS:4351	Steel door frames.		
	IS:5187	Flush bolts.		
	IS:5437	Wired and figured glass		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 97 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
		<p>IS:6248 Metal rolling shutters and rolling grills.</p> <p>IS:6315 Floor springs (hydraulically regulated) for heavy doors.</p> <p>IS:7196 Hold fasts.</p> <p>IS:7452 Hot rolled steel sections for doors, windows and ventilators.</p> <p>IS:10019 Mild steel stays and fasteners.</p> <p>IS:10451 Steel sliding shutters (top hung type).</p> <p>IS:10521 Collapsible gates.</p> <p><b>Roof Water Proofing and Allied Works</b></p> <p>IS:1203 Methods of testing tar and bitumen.</p> <p>IS:1322 Specification for bitumen felts for water proofing and damp proofing.</p> <p>IS:1346 Code of practice for water proofing of roofs with bitumen felts.</p> <p>IS:1580 Specification for bituminous compound for water proofing and caulking purposes.</p> <p>IS:3067 Code of practice for general design details and preparatory work for damp proofing and water proofing of buildings.</p> <p>IS:3384 Specification for bitumen primer for use in water proofing and damp proofing.</p> <p><b>Floor Finishes and Allied Works</b></p> <p>IS:1237 Specification for cement concrete flooring tiles.</p> <p>IS:1443 Code of practice for laying and finishing of cement concrete flooring tiles.</p> <p>IS:2114 Code of practice for laying in-situ terrazzo floor finish.</p> <p>IS:2571 Code of practice for laying in-situ cement concrete flooring.</p> <p>IS:3462 Specification for unbacked flexible PVC flooring.</p> <p>IS:4971 Recommendations for selection of industrial floor finishes.</p>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 98 OF 119


CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
	IS:5318 IS:8042 IS:13801	Code of practice for laying of flexible PVC sheet and tile flooring. Specification for white portland cement. Specification for chequered cement concrete flooring tiles.		
	<b>Painting and Allied Works</b>			
	IS:162 IS:1477 Part-I Part-II	Specification for fire resisting silicate type, brushing, for use on wood, colour as required. Code of practice for painting of ferrous metals in buildings. Pretreatment. Painting.		
	IS:1650 IS:2074	Specification for colours for building and decorative finishes. Specification for red oxide-zinc chrome, priming, ready mixed paint air drying.		
	IS:2338 Part-I Part-II	Code of practice for finishing of wood and wood based materials. Operations and workmanship Schedules		
	IS:2395 Part-I Part-II	Code of practice for painting concrete, masonry and plaster surfaces. Operations and workmanship. Schedule.		
	IS:2524 Part-I Part-II	Code of practice for painting of nonferrous metals in buildings. Pretreatment. Painting.		
	IS:2932 IS:2933	Specification of synthetic enamel paint, exterior, under-coating and finishing. Specification enamel paint, under coating and finishing.		
	IS:4759 IS:5410	Code of practice for hot dip zinc coating on structural steel and other allied products. Specification for cement paint		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C		GENERAL TECHNICAL REQUIREMENTS	PAGE 99 OF 119





CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनडीपीसी NTPC
	<p>IS:5411                      Specification for plastic emulsion paint-for exterior use (Part-I)</p> <p>IS:6278                      Code of practices for white washing and colour washing.</p> <p>IS:10403                      Glossary of terms relating to building finishes.</p> <p><b>Piling and Foundation</b></p> <p>IS:1080                      Code of practice for design and construction of simple spread foundations.</p> <p>IS:1904                      Code of practice for design and construction of foundations in Soils; General Requirements.</p> <p>IS:2911                      Code of practice for designs and construction of Pile foundations (Relevant Parts).</p> <p>IS:2950                      Code of practice for designs and construction of Raft (Part-I) foundation.</p> <p>IS:2974                      Code of practice for design and construction of machine (Part-I TO V) foundations.</p> <p>IS:6403                      Code of practice for determination of Allowable Bearing pressure on Shallow foundation.</p> <p>IS:8009                      Code of practice for calculation of settlement of foundation subjected to symmetrical vertical loads.</p> <p>Part-I                      Shallow foundations.</p> <p>Part-II                      Deep foundations.</p> <p>IS:12070                      Code of practice for design and construction of shallow foundations on rocks.</p> <p>DIN:4024                      Flexible supporting structures for machines with rotating machines.</p> <p>VDI:2056                      Criteria for assessing mechanical vibrations of machines.</p> <p>VDI:2060                      Criteria for assessing rotating imbalances in machines.</p> <p><b>Stop Log and Trash Rack</b></p> <p>IS:4622                      Recommendations for fixed - wheel gates structural design.</p> <p>IS:5620                      Recommendations for structural design criteria for low head slide gates.</p> <p>IS:11388                      Recommendations for design of trash rack for intakes.</p> <p>IS:11855                      General requirements for rubber seals for hydraulic gates.</p> <p><b>Roads</b></p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 100 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
	<p>IRC:5</p> <p>IRC:14</p> <p>IRC:16</p> <p>IRC:19</p> <p>IRC:21</p> <p>IRC:34</p> <p>IRC:36</p> <p>IRC:37</p> <p>IRC:56</p> <p>IRC:73</p> <p>IRC:86</p> <p>IRC:SP:13</p> <p>IRC - Publication</p> <p>IS:73</p> <p><b>Loadings</b></p> <p>IS:875 (Pt. I to V)</p> <p>IS:1893</p> <p>IS:4091</p> <p>IRC:6</p> <p>M.O.T.</p> <p><b>Safety</b></p> <p>IS:3696 (Part I &amp; II)</p>	<p>Standard specifications and Code of practice for road bridges, section-I general Features of Design.</p> <p>Recommended practice of 2cm thick bitumen and tar carpets.</p> <p>Specification for priming of base course with bituminous primers.</p> <p>Standard specifications and code of practice for water bound macadam.</p> <p>Standard specifications and Code of practice for road bridges, section-III - Cement concrete (plain and reinforced).</p> <p>Recommendations for road construction in waterlogged areas.</p> <p>Recommended practice for the construction of earth embankments for road works.</p> <p>Guidelines for the Design of flexible pavements.</p> <p>Recommended practice for treatment of embankment slopes for erosion control.</p> <p>Geometric design standards for rural (non-urban) highways.</p> <p>Geometric Design standards for urban roads in plains.</p> <p>Guidelines for the design of small bridges &amp; culverts.</p> <p>Ministry of Surface Transport (Roads Wing), Specifications for road and bridge works.</p> <p>Specification for paving bitumen</p> <p>Code of practice for design loads other than earthquake) for buildings and structures.</p> <p>Criteria for earthquake resistant design of structures.</p> <p>Code of Practice for design and construction of foundation for transmission line towers &amp; poles.</p> <p>Standard specifications &amp; code of practice for road bridges, Section-II Loads and stresses.</p> <p>Deptt. of railways Bridge Rules.</p> <p>Safety code for scaffolds and ladders.</p>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 101 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			एनडीपीसी NTPC
	<p>IS:3764 Safety code for excavation work.</p> <p>IS:4081 Safety code for blasting and related drilling operations.</p> <p>IS:4130 Safety code for demolition of buildings.</p> <p>IS:5121 Safety code for piling and other deep foundations.</p> <p>IS:5916 Safety code for construction involving use of hot bituminous materials.</p> <p>IS:7205 Safety code for erection on structural steelwork.</p> <p>IS:7293 Safety code for working with construction machinery.</p> <p>IS:7969 Safety code for handling and storage of building materials</p> <p>IS:11769 Guidelines for safe use of products containing asbestos.</p> <p>- Indian Explosives Act. 1940 as updated.</p> <p><b>Architectural design of buildings</b></p> <p>SP:7 National Building Code of India</p> <p>SP:41 Handbook on functional requirements of buildings (other than industrial buildings)</p> <p><b>Miscellaneous</b></p> <p>IS:802 Code of practice for use of structural steel in (Relevant parts) overhead transmission line towers.</p> <p>IS:803 Code of practice for design, fabrication and erection of vertical mild steel cylindrically welded in storage tanks.</p> <p>IS:10430 Criteria for design of lined canals and liner for selection of type of lining.</p> <p>IS:11592 Code of practice for selection and design of belt conveyors.</p> <p>IS:12867 PVC handrails covers.</p> <p>CIRIA Design and construction of buried thin-wall pipes.</p> <p>Publication</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C		GENERAL TECHNICAL REQUIREMENTS
		PAGE 102 OF 119		

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS 		
	<p><b>REFERENCE CODES AND STANDARDS FOR CONTROL AND INSTRUMENTATION</b></p> <p>The design, manufacture, inspection, testing &amp; installation of all equipment and system covered under this specification shall conform to the latest editions of codes and standards mentioned below and all other applicable VDE, IEEE, ANSI, ASME, NEC, NEMA, ISA AND Indian Standards and their equivalents.</p> <p><b>Temperature Measurements</b></p> <ol style="list-style-type: none"> <li>Instrument and apparatus for temperature measurement - ASME PTC 19.3 (1974).</li> <li>Temperature measurement - Thermocouples ANSI MC 96.1 - 1982.</li> <li>Temperature measurement by electrical Resistance thermometers - IS:2806.</li> <li>Thermometer - element - Platinum resistance - IS:2848.</li> </ol> <p><b>Pressure Measurements</b></p> <ol style="list-style-type: none"> <li> <ol style="list-style-type: none"> <li>Instruments and apparatus for pressure measurement - ASME PTC 19.2 (1964).</li> <li>Electronic transmitters BS:6447.</li> </ol> </li> <li>Bourdon tube pressure and vacuum gauges - IS:3624 - 1966.</li> <li>Process operated switch devices (Pr. Switch) BS-6134.</li> </ol> <p><b>Flow Measurements</b></p> <p>Instruments and apparatus for flow measurements - ASME PTC 19.5 (1972) Interim supplement, Part-II.</p> <p>Measurement of fluid flow in closed conduits - BS-1042.</p> <p><b>Electronic Measuring Instrument &amp; Control Hardware/ Software</b></p> <ol style="list-style-type: none"> <li>Automatic null balancing electrical measuring instruments - ANSI C 39.4 (Rev. 1973): IS:9319.</li> <li>Safety requirements for electrical and electronic measuring and controlling instrument - ANSI C 39.5 - 1974.</li> <li>Compatibility of analog signals for electronic industrial process instruments - ISA - S 50.1 (1982) ANSI MC 12.1 - 1975.</li> <li>Dynamic response testing of process control instrumentation ISA - S 26 (1968).</li> </ol>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 103 OF 119


CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			
	<ol style="list-style-type: none"> <li>5. Surge Withstand Capability (SWC) tests - ANSI C 37.90 a/IEEE-472 or suitable class of IEC-255-4 equivalent to ANSI C37.90a/IEEE-472.</li> <li>6. Printed circuit boards - IPC TM - 650, IEC 326 C.</li> <li>7. General requirement and tests for printed wiring boards - IS 7405 (Part-I) 1973.</li> <li>8. Edge socket connectors - IEC 130-11.</li> <li>9. Requirements and methods of testing of wire wrap terminations DIN 41611 Part-2.</li> <li>10. Dimensions of attachment plugs &amp; receptacles - ANSI C 73 - 1973 (Supplement ANSI C 73 a - 1980).</li> <li>11. Direct acting electrical indicating instrument - IS:1248 - 1968 (R).</li> <li>12. Standard Digital Interface for Programmable Instrumentation - IEEE-488.2 - 1990.</li> <li>13. Information Processing Systems - Local Area Networks - Part 2 : Logical Link Control - IEEE-802.2 - 1989.</li> <li>14. Standard for Local Area Networks : Carrier Sense Multiple Access with Collision Detection - IEEE-802.3 - 1985.</li> <li>15. Supplements A, B, C and E to Carrier Sense Multiple Access with Collision Detection - IEEE-802.3 - 1988.</li> <li>16. Standard for Local Area Networks : Token - Passing Bus Access Method - IEEE-802.4 - 1985.</li> <li>17. Standard for Local Area Networks : Token - Ring Access Method and Physical Layer Specification - IEEE-802.5 - 1985.</li> <li>18. IEEE Guide to Software Requirements Specifications - IEEE-830 - 1984.</li> <li>19. Hardware Testing of Digital Process Computers - ISA RP55.1 - 1983.</li> <li>20. Electromagnetic Susceptibility of Process Control Instrumentation - SAMA PMC 33.1 - 1978.</li> <li>21. Interface Between the Data Terminal Equipment and Data Circuit - Terminating Equipment Employing Serial Binary Data Interchange - EIA-232-D-1987.</li> <li>22. Electromagnetic Compatibility for Industrial Process Measurement and Control Equipment, Part 3 : Radiated Electromagnetic Field Requirements - IEC 801-3-1984.</li> </ol>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE		TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 104 OF 119


CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS 		
	<p><b>Instrument Switches and Contact</b></p> <ol style="list-style-type: none"> <li>Contact rating - AC services NEMA ICS 2 - 1978 (with revision through May 1983), Part - 2-125, A6000.</li> <li>Contact rating - DC services NEMA ICS 2-1978 Part-2 125, N600.</li> </ol> <p><b>Enclosures</b></p> <ol style="list-style-type: none"> <li>Type of Enclosures - NEMA ICS Part - 6 - 1978 (with Rev. 1 4/80) through 110.22 (Type 4 to 13).</li> <li>Racks, panels and associated equipment - EIA : RS - 310 C- 1983 (ANSI C 83.9 - 1972).</li> <li>Protection class for Enclosures, cabinets, control panels &amp; desks - IS:2147 - 1962.</li> </ol> <p><b>Apparatus, enclosures and installation practices in hazardous area</b></p> <ol style="list-style-type: none"> <li>Classification of hazardous area - NFPA 70 - 1984, Article 500.</li> <li>Electrical Instruments in hazardous dust location - ISA - 512.11, 1973.</li> <li>Intrinsically safe apparatus - NFPA 493 1978.</li> <li>Purged and pressurised enclosure for electrical equipment in hazardous location - NFPA 496-1982.</li> <li>Enclosures for Industrial Controls and Systems - NEMA IS 1.1 - 1977.</li> </ol> <p><b>Sampling System</b></p> <ol style="list-style-type: none"> <li>Stainless steel material of tubing and valves for sampling system - ASTM 296-82, Grade 7 P 316.</li> <li>Submerged helical coil heat exchangers for sample coolers ASTM D11 92-1977.</li> <li>Water and steam in power cycle - ASME PTC 19.11.</li> <li>Standard methods of sampling system - ASTM D 1066-99.</li> </ol> <p><b>Annunciators</b></p> <ol style="list-style-type: none"> <li>Specifications and guides for the use of general purpose annunciators - ISA S 19.1, 1979.</li> <li>Surge withstand capability tests - ANSI C 37.90a - 1989/IEEE-472 or suitable class of IEC 255-4 equivalent to ANSI C37.90a 1989/IEEE-472</li> <li>Damp heat cycling test - IS:2106</li> </ol>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 105 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS	एनडीपीसी NTPC		
	<p>4. Specification for Electromagnetic Susceptibility - SAMA DMC 33, 1/78</p> <p><b>Protections</b></p> <ol style="list-style-type: none"> <li>1. Relays and relay system associated with electric power apparatus. ANSI C 37.90, 1 - 1989.</li> <li>2. General requirements &amp; tests for switching devices for control and auxiliary circuits including contactor relays - IS:6875 (Part-I) - 1973.</li> <li>3. Turbine water damage prevention - ASME TDP-1-1980.</li> <li>4. Boiler safety interlocks - NFPA Section 85 B - 1984, 85 C - 1991.</li> </ol> <p><b>UPS System</b></p> <ol style="list-style-type: none"> <li>1. Practices and requirements for semi-conductor power rectifiers - ANSI C 34.2, 1973.</li> <li>2. Relays and relays system associated with electrical power apparatus - ANSI C 3.90 - 1983.</li> <li>3. Surge withstand capability test - ANSI C 37.90 1 -1989.</li> <li>4. Performance testing of UPS - IEC 146.</li> <li>5. Stationary cells &amp; Batteries Lead Acid type (with tubular positive plates) specification IS-1651-1991.</li> <li>6. Recommended practice for sizing large lead storage batteries for generating stations &amp; sub-stations - IEEE-485-1985.</li> <li>7. Printed Circuit Board - IPC TM 650, IEC 326C.</li> <li>8. General Requirements &amp; tests for printed wiring boards, IS:7405 (Part-I) 1973.</li> </ol> <p><b>Control Valves</b></p> <ol style="list-style-type: none"> <li>1. Control valve sizing - Compressible &amp; Incompressible fluids - ISA S 75.01-1985.</li> <li>2. Face to face dimensions of control valves - ANSI B 16.00 - 1973.</li> <li>3. ISA Hand Book of Control Valves - (ISBN : B: 1047-087664-234-2).</li> <li>4. Codes for pressure piping - ANSI B 31.1</li> <li>5. Control Valve leak class - ISA RP 39.6</li> </ol>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 106 OF 119	


CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS	एनडीपीसी NTPC		
	<p><b>Process Connection &amp; Piping</b></p> <ol style="list-style-type: none"> <li>Codes for pressure piping "power piping" - ANSI B 31.1.</li> <li>Seamless carbon steel pipe ASTM - A - 106.</li> <li>Forged &amp; Rolled Alloy steel pipe flanges, forged fittings and valves and parts - ASTM - A - 182.</li> <li>Material for socket welded fittings - ASTM - A - 105.</li> <li>Seamless ferritic alloy steep pipe - ASTM - A - 335.</li> <li>Pipe fittings of wrought carbon steel and alloy steel - ASTM - A - 234.</li> <li>Composition bronze of ounce metal castings - ASTM - B - 62.</li> <li>Seamless Copper tube, bright annealed - ASTM - B - 168.</li> <li>Seamless copper tube - ASTM - B - 75.</li> <li>Dimension of fittings - ANSI - B - 16.11.</li> <li>Valves flanged and butt welding ends - ANSI - B - 16.34.</li> </ol> <p><b>Instrument Tubing</b></p> <ol style="list-style-type: none"> <li>Seamless carbon steel pipe - ASTM - A 106.</li> <li>Material of socketweld fittings - ASTM - A105.</li> <li>Dimensions of fittings - ANSI - B - 16.11.</li> <li>Code for pressure piping, welding, hydrostatic testing - ANSI B 31.1.</li> </ol> <p><b>Cables</b></p> <ol style="list-style-type: none"> <li>Thermocouples extension wires/cables - ANSI MC 96.1 - 1992.</li> <li>Requirements for copper conductor-Wiring cables for telecommunications &amp; information processing system - VDE:0815.</li> <li>Colour coding of single or multi-pair cables - ICEA - S - 61-402 (third edition) NEMA WCS - 1979 with revisions thorough 2/83.</li> <li>Insulation &amp; Sheathing compounds for cables : VDE 0207 (Part-4, 5 &amp; 6).</li> <li>Guide design and installation of cable systems in power generating stations ( insulation, jacket materials) - IEEE Std. 422-1977.</li> <li>Rules for Testing insulated cables and flexible cables : VVDE - 0472</li> <li>Requirements of vertical flame propagation test - IEEE 383 - 1974 (R 1980)</li> </ol>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 107 OF 119	



CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS			
	<p>8. Standard specification for tinned soft or annealed copper wire for electrical purpose - ASTM B-33-81.</p> <p>9. Oxygen index and temperature index test - ASTM D - 2863.</p> <p>10. Smoke density measurement test - ASTM D - 2843.</p> <p>11. Acid gas generation test - IEC - 754 - 1.</p> <p>12. Swedish Chimney test - SEN - 4241475 (F3).</p> <p>13. Teflon (FEP) insulation &amp; sheath test - ASTM D - 2116.</p> <p>14. Thermocouple compensating cables - Testing requirements &amp; sampling plan IS:8784.</p> <p>15. PVC insulated electric cables for working voltage upto and including 1100 V - IS:1554 (Part-I).</p> <p><b>Cable Trays, Conduits</b></p> <p>1. Guide for design and installation of cable systems in power generating station (Cable trays, support systems, conduits) - IEEE Std. 422, 1977, NEMA VE-1 1979, NFPA 70-1984.</p> <p>2. -do- Test Standards. NEMA VE-1-1979.</p> <p>3. Zinc coating "hot dip" on assembled products for galvanising of carbon steel cable trays - ASTM A - 386-78.</p> <p><b>Public Address System</b></p> <p>1. Specifications for loud speakers - IS:7741 (Part-I, II and III)</p> <p>2. Code of safety requirement for electric mains operated audio amplifiers - IS:1301</p> <p>3. Specification for Public Address Amplifiers - IS:10426.</p> <p>4. Code of practice for outdoor installation of PA system - IS:1982.</p> <p>5. Code of practice for installation for indoor amplifying and sound distribution system - IS:1881.</p> <p>6. Basic environmental testing procedures for electronic and electrical items - IS:9000.</p> <p>7. Characteristics and methods of measurements for sound system equipment - IS:9302</p> <p>8. Code of practice of electrical wiring installations (System voltage not exceeding 650 volts) - IS:732</p>			
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 108 OF 119	

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS <div data-bbox="1284 113 1429 184" style="float: right;">  </div>		
	<div data-bbox="386 218 1422 394"> <p>9. Rigid steel conduits for electric wiring - IS:9537 (Part-I and II)</p> <p>10. Fittings for rigid steel conduits for electrical wiring - IS:2667</p> <p>11. Degree of protection provided by enclosure for low voltage switchgear and control gear - IS:2147.</p> </div> <div data-bbox="386 422 766 453"> <p><b>Vibration Monitoring System</b></p> </div> <div data-bbox="386 483 685 573"> <p>1. API 670 - 1994</p> <p>2. BS : 4675 Part-2</p> </div>		
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C	GENERAL TECHNICAL REQUIREMENTS	PAGE 109 OF 119

## ANNEXURE-III

	Project :	Stage ::	LIST OF ITEMS REQUIRING QUALITY PLAN AND SUB-SUPPLIER APPROVAL					DOC. NO.:		
	Package :							REV. NO.:		
	Supplier :							DATE :		
	Contractor No. :		SUB-SYSTEM :					PAGE : OF		
S. N.	Item	QP/ Insp. Cat.	QP No.	QP Sub. Schedule	QP approval schedule	Proposed sub-supplier	Place	Sub-suppliers approval status / category	Sub-supplier Details submission schedule	Remarks

## LEGENDS

SYSTEM SUPPLIER/SUB-SUPPLIER APPROVAL STATUS CATEGORY (SHALL BE FILLED BY NTPC)

A – For these items proposed vendor is acceptable to NTPC. To be indicated with letter “A” in the list alongwith the condition of approval, if any.

DR – For these items “Detailed required” for NTPC review. To be identified with letter “DR” in the list.

NOTED – For these items vendors are approved by Main Supplier and accepted by NTPC without specific vendor approval from NTPC. To be identified with “NOTED.”

QP/INSPN CATEGORY:

CAT-I : For these items the Quality Plans are approved by NTPC and the final acceptance will be on physical inspection witness by NTPC.

CAT-II : For these items the Quality Plans approved by NTPC. However no physical inspection shall be done by NTPC. The final acceptance by NTPC shall be on the basis review of documents as per approved QP.

CAT-III : For these items Main Supplier approves the Quality Plans. The final acceptance by NTPC shall be on the basis certificate of conformance by the main supplier.

UNITS/WORKS : Place of manufacturing Place of Main Supplier of multi units/works.


FORMAT NO.: QS-01-QAI-P-1/F3-R0

1/1


Engg. Div. / QA&amp;I

LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION – VI, PART-C	GENERAL TECHNICAL REQUIREMENT	PAGE 110 OF 119
--	---	-------------------------------	-----------------


## ANNEXURE-IV


	Project :		Stage ::		STATUS OF ITEM REQUIRING QP& SUB-SUPPLIER APPROVAL				DOC. NO.:		
	Package :								REV. NO.:		
	Contractor :								DATE :		
	Contractor No. :								PAGE : OF		
S. N.	Item / Service	QP/ Insp. Cat.	QP Sub. Schedule Approval schedule	Date of sub-mission	Date of commt Appl.	Status Code C/II/I	Proposed Sub-suppliers	Place of manufacturing works	Approval Status	Sub-supplier detail submission schedule	Remarks
FORMAT						1/1		Engg. Div. / QA&I			


# ANNEXURE-V

		Project :		Stage :		<b>FIELD WELDING SCHEDULE</b> (To be raised by the contractor) Welding Code: .....						DOC. NO.:				
		Contractor :										REV. NO.:				
		Contractor No. :				DATE :										
		System :				PAGE : OF										
Sl. No.	DRG No. for Weld Location and Identification mark	Description of parts to welded	Matl. Spec.	Dimensions		Process of welding	Type of Weld	Electrode filler spec.	WPS. No.	Min. pre-heat	Heat treatment		NDT method/ Quantum	REF		Remarks
											Temp.	Holding time		Spec. No.	ACC Norm Ref.	
NOTES:																
SIGNATURE																
FORMAT						1/1						Engg. Div. / QA&I				

LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATION SECTION – VI, PART-C	GENERAL TECHNICAL REQUIREMENT	PAGE 112 OF 119
--	---	----------------------------------	-----------------


CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS (Annexure-VI)				
	S. No.	Description of Drgs./Docs.	No. of Prints	No. of Portable Hard Disk	
	1	Drawings, Data sheets, Design calculations, Purchase specifications and other documents			
		First submission and submission with major changes			
		▪ Layout (A0&A1 sizes)	3	-	
		▪ Other Drawings/Documents (A0 & A1 sizes)	3	-	
		▪ P&ID (All sizes)	3	-	
		a) Final drawings/documents (Directly to site)	3	2	
		b) "As Built" Drawing/Documents (Directly to site)	3	2	
		c) Analysis reports of Equipments / piping / structures components/system employing software packages as detailed in the specifications.	2	2	
	2	Erection Manual (Directly to site)	3 sets	2	
	3	Operation & Maintenance manual i) First Submission	0	--	
		ii) Final Submission (Directly to site)	3 sets	2	
	4	Plant Hand Book i) Final Submission	1	1	
	5	Commissioning and Performance Test Procedure manual i) First Submission	1 set	--	
4		ii) Final Submission (Directly to site)	3 sets	2	
LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C		GENERAL TECHNICAL REQUIREMENTS Annexure-VI		PAGE 113 OF 119

CLAUSE NO.	GENERAL TECHNICAL REQUIREMENTS (Annexure-VI)				
	S. No.	Description of Drgs./Docs.	No. of Prints	No. of Portable Hard Disk	
	6	Performance and Functional Guarantee Test Report i) First Submission	1 sets	—	
		ii) Approved Copies (Direct to Site)	3 sets	2	
	7	Project Completion Report (Directly to site)	3 sets	2	
4 LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW) EPC PACKAGE	TECHNICAL SPECIFICATIONS SECTION VI, PART-C		GENERAL TECHNICAL REQUIREMENTS Annexure-VI		PAGE 114 OF 119

	<b>CORPORATE QUALITY ASSURANCE/ कॉरपोरेट गुणवत्ता आश्वासन</b> <b>MAIN CONTRACTOR'S PROPOSAL CUM EVALUATION REPORT</b> <b>मुख्य संविदाकार प्रस्ताव सह मुल्यांकन रिपोर्ट</b>	


Ref No: संदर्भ सं.:		Date: तिथि:	
i.	Main Contractor मुख्य संविदाकार		
ii.	Project परियोजना		
iii.	Package Name पैकेज का नाम	Package No पैकेज सं.	
iv.	Proposed Item/Scope of Sub-contracting उप-संविदा(अनुबंध) का प्रस्तावित मद/ दायरा		
v.	Item covered under निम्नलिखित के अंतर्गत शामिल मद	Schedule-1 /अनुसूची- 1	As per contract clause No- अनुबंध के अनुसार खंड सं.- -
		Schedule-2 अनुसूची- -2	
vi.	If item is Schedule-1 and proposed sub-vendor is indigenous, Main Contractor to explain how the contractual provisions will be fulfilled  /यदि मद अनुसूची -1 है और प्रस्तावित उप-विक्रेता स्वदेशी है, तो मुख्य संविदाकार को स्पष्ट करना होगा कि संविदा/अनुबंध के प्रावधान कैसे पूरे किए जाएंगे		
vii.	Name and Address of the proposed Sub-vendor's works /प्रस्तावित सब-वेंडर का नाम तथा पता		
viii.	PO placement date/ Start of manufacturing (if self-manufactured) as per L2 network पीओ नियोजन की तिथि / एल- 2 नेटवर्क के अनुसार विनिर्माण (यदि स्व-निर्मित है) की शुरुआत		
ix.	Item Description (Type/Size/Rating/Scope of Sub-Contracting) मद का विवरण (प्रकार / आकार / रेटिंग / उप-अनुबंध का दायरा)	Total quantity of proposed item envisaged in this package (Nos/ Running Meters/ Kgs/ Tons etc) इस पैकेज में परिकल्पित प्रस्तावित मद की कुल मात्रा (संख्या / क्रियाशील मीटर / किलोग्राम / टन आदि)	Quantity proposed to be procured from proposed sub-vendor (Nos/ Running Meters /Kgs /Tons etc) प्रस्तावित उप-विक्रेता (संख्या / क्रियाशील मीटर / किलोग्राम / टन आदि) से खरीदी जाने वाली मात्रा
			Timeline for quantity requirements as per project schedule & whether the proposed Sub-vendor equipped with adequate capacity to supply proposed order quantity in time / परियोजना समय सूची के अनुसार मात्रा आवश्यकताओं के लिए समय-सीमा और क्या प्रस्तावित उप-विक्रेता समय पर प्रस्तावित मांग की मात्रा की आपूर्ति करने में पूरी तरह से सक्षम है
x.	Supply experience of the proposed sub-vendor (including supplies to Main Contractor, if any) for similar item/scope of sub-contracting, for last 3 years (Note:- Only relevant experience details w.r.t. proposed item/scope of subcontracting to be brought out here) पिछले 3 वर्षों के लिए उप-अनुबंध के समान मद / दायरे के लिए प्रस्तावित सब-वेंडर (मुख्य संविदाकार हेतु		



	<b>CORPORATE QUALITY ASSURANCE/ कॉरपोरेट गुणवत्ता आश्वासन</b> <b>MAIN CONTRACTOR'S PROPOSAL CUM EVALUATION REPORT</b> <b>मुख्य संविदाकार प्रस्ताव सह मुल्यांकन रिपोर्ट</b>	

आपूर्ति, यदि कोई हो, सहित) का आपूर्ति अनुभव (नोट: - उप-अनुबंध के प्रस्तावित मद / दायरे के संबंध में केवल प्रासंगिक अनुभव के विवरण का उल्लेख हो							
<b>Project/Package</b> परियोजना/पैकेज	<b>Customer Name</b> ग्राहक का नाम	<b>Supplied Item</b> (Type/Rating/Model /Capacity/Size etc) आपूर्ति मद (प्रकार/रेटिंग /मॉडल /क्षमता/आकार आदि)	<b>PO ref no/date</b> पीओ संदर्भ सं. /तिथि	<b>Supplied Quantity</b> आपूर्ति की मात्रा	<b>Date of Supply</b> आपूर्ति की तिथि		
We confirm that as per our assessment, the proposed sub-vendor has requisite capabilities & supply experience and is suitable for supplying the proposed item/scope of sub-contracting/हम अपने आकलन के अनुसार इस बात की पुष्टि करते हैं कि, प्रस्तावित उप-विक्रेता के पास अपेक्षित क्षमता और आपूर्ति करने का अनुभव है और उप-अनुबंध के दायरे /प्रस्तावित मद की आपूर्ति के लिए उपयुक्त है।							
<b>Name:</b> नाम:		<b>Desig:</b> पद:		<b>Contact No:</b> दूरभाष सं.:		<b>Sign:</b> हस्ताक्षर:	<b>Date:</b> तिथि:


Company's Seal/Stamp:- कंपनी का मुहर:-

	<b>CORPORATE QUALITY ASSURANCE/ कॉरपोरेट गुणवत्ता आश्वासन</b> <b>SUB-VENDOR QUESTIONNAIRE/ सब-वेंडर प्रश्नावली</b>
---	---

<b>i.</b>	<b>Item/Scope of Sub-contracting</b> उप-संविदा(अनुबंध) का मद/ दायरा			
<b>ii.</b>	<b>Address of the registered office</b> पंजीकृत कार्यालय का पता  	<b>Details of Contact Person</b> संपर्क व्यक्ति का विवरण  (Name, Designation, Mobile, Email) (नाम, पदनाम, मोबाइल, ईमेल)		
<b>iii.</b>	<b>Name and Address of the proposed Sub-vendor's works where item is being manufactured</b> प्रस्तावित उप-विक्रेता के कार्यों का नाम और पता, जहां मद का निर्माण किया जा रहा है  	<b>Details of Contact Person:</b> संपर्क व्यक्ति का विवरण  (Name, Designation, Mobile, Email) (नाम, पदनाम, मोबाइल, ईमेल)		
<b>iv.</b>	<b>Annual Production Capacity for proposed item/scope of sub-contracting</b> उप-संविदा(अनुबंध) के प्रस्तावित मद / दायरे के लिए वार्षिक उत्पादन क्षमता			
<b>v.</b>	<b>Annual production for last 3 years for proposed item/scope of sub-contracting</b> उप-संविदा(अनुबंध) के प्रस्तावित मद / दायरे के लिए पिछले 3 वर्षों का वार्षिक उत्पादन			
<b>vi.</b>	<b>Details of proposed works</b> प्रस्तावित कार्यों का विवरण			
<b>1.</b>	<b>Year of establishment of present works</b> वर्तमान फैक्टरी की स्थापना का वर्ष			
<b>2.</b>	<b>Year of commencement of manufacturing at above works</b> उपरोक्त फैक्टरी में निर्माण कार्य शुरू होने का वर्ष			
<b>3.</b>	<b>Details of change in Works address in past (if any)</b> पूर्व में फैक्टरी स्थल में परिवर्तन का विवरण (यदि कोई हो)			
<b>4.</b>	<b>Total Area</b> कुल क्षेत्र			
<b>4.</b>	<b>Covered Area</b> शामिल क्षेत्र			
<b>5.</b>	<b>Factory Registration Certificate</b> फैक्टरी पंजीकरण प्रमाण पत्र	<b>Details attached at Annexure – F2.1</b> विवरण अनुलग्नक-एफ 2.1 पर संलग्न है		
<b>6.</b>	<b>Design/ Research &amp; development set-up</b> डिजाइन / अनुसंधान और विकास सेटअप (No. of manpower, their qualification, machines & tools employed etc.) (श्रमिकों की संख्या, उनकी योग्यता, मशीन और उपलब्ध उपकरण आदि)	<b>Applicable / Not applicable if manufacturing is as per Main Contractor/purchaser design</b> <b>Details attached at Annexure – F2.2</b> (if applicable) लागू / लागू नहीं, अगर विनिर्माण मुख्य संविदाकार / खरीददार के डिजाइन के अनुसार है) विवरण अनुलग्नक –एफ 2.2 पर संलग्न है। (यदि लागू हो)		
<b>7.</b>	<b>Overall organization Chart with Manpower Details (Design/Manufacturing/Quality etc)</b> मैनपावर विवरण के साथ समग्र संगठन का चार्ट( डिजाइन / विनिर्माण / गुणवत्ता आदि )	<b>Details attached at Annexure – F2.3</b> विवरण अनुलग्नक – F2.3 में संलग्न है।		
<b>8.</b>	<b>After sales service set up in India, in case of foreign sub-vendor(Location, Contact Person, Contact details etc.)</b> भारत	<b>Applicable / Not applicable</b> लागू / लागू नहीं		

Format No. : QS-01-QAI-P-04/F2-R0 DATED 19.01.18


Engg. div./QA&I

	<b>CORPORATE QUALITY ASSURANCE/ कॉरपोरेट गुणवत्ता आश्वासन</b> <b>SUB-VENDOR QUESTIONNAIRE/ सब-वेंडर प्रश्नावली</b>

	में बिक्री सेवा की स्थापना के बाद, विदेशी उप-विक्रेता के मामले में( स्थल , संपर्क व्यक्ति, संपर्क विवरण आदि)	<i>Details attached at Annexure – F2.4</i> विवरण अनुलग्नक -2.4 पर संलग्न है।
9.	<i>Manufacturing process execution plan with flow chart indicating various stages of manufacturing from raw material to finished product including outsourced process, if any</i> फ्लोचार्ट सहित विनिर्माण प्रक्रिया निष्पादन योजना , जिसमें आउटसोर्स प्रक्रिया, यदि कोई हो, सहित कच्चे माल से तैयार उत्पाद तक विनिर्माण के विभिन्न चरणों को दर्शाया गया हो,	<i>Details attached at Annexure – F2.5</i> विवरण अनुलग्नक - F2.5में संलग्न है।
10.	<i>Sources of Raw Material/Major Bought Out Item</i> कच्चे माल के स्रोत / खरीदे हुए मुख्य मद	<i>Details attached at Annexure – F2.6</i> विवरण अनुलग्नक - F2.6में संलग्न है।
11.	<i>Quality Control exercised during receipt of raw material/BOI, in-process , Final Testing, packing</i> कच्चे माल / खरीदे हुए मद, प्रक्रियाबद्ध, अंतिम परीक्षण, पैकिंग करते समय गुणवत्ता नियंत्रण	<i>Details attached at Annexure – F2.7</i> विवरण अनुलग्नक - F2.7 पर संलग्न है
12.	<i>Manufacturing facilities (List of machines, special process facilities, material handling etc.)</i> विनिर्माण सुविधा( मशीनों की सूची , विशेष प्रक्रिया सुविधाएं, सामग्री रख-रखाव आदि)	<i>Details attached at Annexure – F2.8</i> विवरण अनुलग्नक - F2.8में संलग्न है।
13.	<i>Testing facilities (List of testing equipment)</i> परीक्षण सुविधाएं( परीक्षण उपकरण की सूची )	<i>Details attached at Annexure – F2.9</i> विवरण अनुलग्नक – F2. 9 में संलग्न है।
14.	<i>If manufacturing process involves fabrication then-</i> यदि निर्माण प्रक्रिया में फेब्रिकेशन की गई है तो- <i>List of qualified Welders</i> पात्र वेल्डर की सूची <i>List of qualified NDT personnel with area of specialization</i> विशेषज्ञता के क्षेत्र सहित पात्र एनडीटी कार्मिकों की सूची	<i>Applicable / Not applicable</i> लागू / लागू नहीं <i>Details attached at Annexure – F2.10</i> विवरण अनुलग्नक - F2.10में संलग्न है। <i>(if applicable)</i> लागू / लागू नहीं
15.	<i>List of out-sourced manufacturing processes with Sub-Vendors' names &amp; addresses</i> सब-वेंडर द्वारा बाह्य स्रोतों (उनके नाम और पते सहित)से करवाएं गए निर्माण प्रक्रियाओं की सूची	<i>Applicable / Not applicable</i> लागू / लागू नहीं <i>Details attached at Annexure. –F2.11</i> विवरण अनुलग्नक - F2.10में संलग्न है। <i>(if applicable)</i> (यदि लागू हो)
16.	<i>Supply reference list including recent supplies</i> नवीनतम आपूर्ति सहित आपूर्ति संदर्भ सूची	<i>Details attached at Annexure – F2.12</i> विवरण अनुलग्नक - F2.12 में संलग्न है। <i>(as per format given below)</i> ( नीचे दिए गए प्रारूप के अनुसार )
<i>Project/ package परियोजना /पैकेज</i>	<i>Customer Name</i> ग्राहक का नाम	<i>Supplied Item (Type/Rating/Model /Capacity/Size etc)</i> आपूर्ति की गई वस्तु (प्रकार / रेटिंग / मॉडल / क्षमता / आकार आदि)
17.	<i>Product satisfactory performance feedback letter/certificates/End User Feedback</i> उत्पाद के संतोषजनक प्रदर्शन संबंधी फीडबैक पत्र / प्रमाण पत्र / अंतिम उपयोगकर्ता फीडबैक	<i>Attached at annexure - F2.13</i> अनुलग्नक F2. 3पर संलग्न है
18.	<i>Summary of Type Test Report (Type Test Details, Report No, Agency, Date of testing) for the proposed product</i>	<i>Applicable / Not applicable</i> लागू / लागू नहीं


Format No. : QS-01-QAI-P-04/F2-R0 DATED 19.01.18

Engg. div./QA&I

	<b>CORPORATE QUALITY ASSURANCE/ कॉरपोरेट गुणवत्ता आश्वासन</b> <b>SUB-VENDOR QUESTIONNAIRE/ सब-वेंडर प्रश्नावली</b>
---	---




	<i>(similar or higher rating)</i> प्रस्तावित उत्पाद (एक समान या उच्च रेटिंग वाले) के लिए टाइप टेस्ट रिपोर्ट (टाइप टेस्ट विवरण, रिपोर्ट संख्या, एजेंसी, जांच की तारीख) का सारांश नोट: - रिपोर्ट प्रस्तुत करने की आवश्यकता नहीं है <b>Note:- Reports need not to be submitted</b>	<i>Details attached at Annexure – F2.14</i> विवरण अनुलग्नक - F2.1 4 में संलग्न है <i>(if applicable)</i> (यदि लागू हो)				
19.	<b>Statutory / mandatory certification for the proposed product</b> प्रस्तावित उत्पाद के लिए वैधानिक / अनिवार्य प्रमाणीकरण	<i>Applicable / Not applicable</i> लागू / लागू नहीं <i>Details attached at Annexure – F2.15</i> <i>(if applicable)</i> (यदि लागू हो)				
20.	<b>Copy of ISO 9001 certificate</b> आईएसओ 9001 प्रमाण पत्र की प्रति <i>(if available)</i> (यदि उपलब्ध हो)	<i>Attached at Annexure – F2.16</i> अनुलग्नक में संलग्न - F2.1 6 है				
21.	<b>Product technical catalogues for proposed item</b> <i>(if available)</i> प्रस्तावित मद के लिए उत्पाद तकनीकी कैटलॉग (यदि उपलब्ध हो)	<i>Details attached at Annexure – F2.17</i> विवरण अनुलग्नक - F2.1 7 में संलग्न है				
<table border="1" style="width: 100%;"> <tr> <td style="width: 25%;"> <b>Name:</b>  <b>नाम:</b> </td> <td style="width: 25%;"> <b>Desig:</b>  <b>पद:</b> </td> <td style="width: 25%;"> <b>Sign:</b>  <b>हस्ताक्षर:</b> </td> <td style="width: 25%;"> <b>Date:</b>  <b>तिथि:</b> </td> </tr> </table>			<b>Name:</b> <b>नाम:</b>	<b>Desig:</b> <b>पद:</b>	<b>Sign:</b> <b>हस्ताक्षर:</b>	<b>Date:</b> <b>तिथि:</b>
<b>Name:</b> <b>नाम:</b>	<b>Desig:</b> <b>पद:</b>	<b>Sign:</b> <b>हस्ताक्षर:</b>	<b>Date:</b> <b>तिथि:</b>			

**Company's Seal/Stamp:- कंपनी की मुहर / मोहर: -**

	<b>TITLE</b> <b>LARA STPP STAGE-II (2X800MW)</b> <b>MILL REJECT SYSTEM (CONVEYOR TYPE)</b>  <b>SPECIFIC TECHNICAL REQUIREMENTS</b>	SPECIFICATION NO. PE-TS-508-160-A101	
		SECTION - I	
		REV 0	
		Sub Section -IA	Date April 2024
		Page 1 of 1	

**ANNEXURE – VIII**

**INPUT DRAWINGS**



ALL SOLENOIDS SHALL BE DOUBLE COILED

NOTE :-  
1. FOLLOWING PREFIXES TO BE USED  
FOR KKS TAG NO. IN DETAIL DRAWINGS


UNIT NO.	PREFIX
UNIT-1	1
UNIT-2	2
UNIT-COMMON	9


2. THE SCHEME IS TYP. FOR ONE UNIT AND SHALL BE SIMILAR FOR ALL THREE UNITS.
3. INSTRUMENTS SHOWN HERE ARE TENTATIVE. ACTUAL REQUIREMENT OF INSTRUMENTS INCLUDING REDUNDANCY SHALL BE GOVERNED BY C&I SPECIFICATION.
4. THE INSTRUMENTATION FURNISHED IN THE PID IS A MINIMUM REQUIREMENT HOWEVER ANY INSTRUMENT REQUIRED FOR COMPLETENESS OF THE SYSTEM SHALL BE PROVIDED BY BIDDER WITHOUT ANY COST IMPLICATION IMPLICATION. FOR REDUNDANCY CRITERIA, VENDOR TO FOLLOW THE CLAUSE PERTAINING TO REDUNDANCY CRITERIA MENTIONED SPECIFIC TECHNICAL REQUIREMENT

COMMON LEGEND:

- MC - MECHANICAL CONVEYOR
- LS - LIMIT SWITCH
- SOL-SOLENOID VALVE
- RLT-RADIO FREQUENCY LEVEL TRANSMITTER
- RFLS-RADIO FREQUENCY LEVEL SWITCH
- TS-TEMPERATURE SENSOR (RTD)
- ZSS- ZERO SPEED SWITCH
- PS- PRESSURE SWITCH
- PG- PRESSURE GAUGE
- PVI- PYRITE HOPPER INLET VALVE
- PVO- PYRITE HOPPER OUTLET VALVE


CUSTOMER		NTPC LIMITED.	
CUSTOMER'S CONSULTANT			
JOB No.	508		
STATUS	CONTRACT		
DISTRIBUTION			
TO		DEPT	NAME
REV	DATE	ALT	QND
01	3.6.15	PKK	RM
01	22.4.24	RB	PKK
BHARAT HEAVY ELECTRICALS LTD		BHARAT HEAVY ELECTRICALS LTD	
POWER SECTOR		POWER SECTOR	
PROJECT ENGINEERING MANAGEMENT		PROJECT ENGINEERING MANAGEMENT	
NEW DELHI		NEW DELHI	
TITLE		DRAWING No.	
FLOW DIAGRAM FOR MILL, RECTS		PE-DG-508-160-A001	
HANDLING SYSTEM			
DEPT.	SCALE	SIGN	DATE
SHEET	1	OF	1
REV			














PLAN AT EL(+2.149M)




SECTION X-X



SECTIONAL PLAN Y-Y



KEY PLAN FOR UNIT-1



KEY PLAN FOR UNIT-2

NOTES:-

- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH CONTRACT TERMS AND CONDITIONS, TECHNICAL SPECIFICATIONS AND SCHEDULE OF ITEMS.
  - ALL DIMENSIONS ARE IN MM & ELEVATIONS IN METERS UNLESS STATED OTHERWISE.
  - ALL ELEVATIONS ARE REFERRED TO THE FINISHED FLOOR LEVEL OF POWER HOUSE BUILDING AS EL(+3.000 M WHICH CORRESPONDS TO RL(+209.50M ABOVE M.S.L.
  - FOR OTHER NOTES AND STD. DETAILS REF. DRG. PE-DG-508-600-C001 (NTPC DRG NO. NTPC NO. 9587-001-315-PVC-C-0001 )
  - BAR MARKED Y DENOTES FOR STEEL OF GRADE Fe-500 CONFORMING TO IS:1786.
  - GRADE OF CONCRETE IS M30 UNLESS NOTED OTHERWISE.
  - CLEAR COVER TO OUTERMOST REINFORCEMENT (INCLUDING TIES) SHALL BE AS FOLLOWS:-
- | ITEM                           | TOP | BOTTOM | SIDE |
|--------------------------------|-----|--------|------|
| a) MILL FOUNDATION & PEDESTALS | 50  | 75     | 50   |
- ALL HOOKS, BENDS, LAPS AND SPLICES SHALL BE AS PER IS 2502, SP 34 AND IS:13920 UNLESS OTHERWISE INDICATED.
  - LAP LENGTH FOR M30 GRADE CONC. SHALL BE 46d WHERE 'd' IS DIA OF THE SMALLER BAR.
  - LAPING OF BARS SHALL BE SUITABLY STAGGERED AND IN NO CASE MORE THAN 50% BARS SHALL BE LAPPED AT ANY SECTION.
  - NET SAFE BEARING CAPACITY IS 45t/m<sup>2</sup> AT EL(-)9.80M FOR UNIT-1 & EL(-)8.80M FOR UNIT-2.
  - MILL FOUNDATION SHALL BE CAST IN SINGLE POUR UP TO CONSTRUCTION JOINT. CONSTRUCTION JOINT TO BE PROVIDED AS SHOWN IN THE DRAWING.
  - ANCHOR BOLT ASSEMBLY TO BE SUPPLIED AT SITE BY BHEL (HYD.) AND EMBEDDED BY CIVIL CONTRACTOR AFTER PROPER CLEANING. CIVIL CONTRACTOR SHALL USE TEMPLATES (BHEL SUPPLY) FOR MAINTAINING LOCATION EXACT AND VERTICAL ALIGNMENT OF BOLTS.
  - BHEL/ERECTOR SHALL REFER FOR ORIENTATION, ALIGNMENT AND SIZES OF ANCHOR BOLT ASSEMBLY AND SHEAR KEY WITH BHEL HYD. DRG. 0-00-610-8709 BEFORE CONCRETING OF PEDESTAL.
  - GRouting SHOULD BE DONE ONLY AFTER FINAL ALIGNMENT OF MILL.
  - FOUNDATION ROCKETS SHOULD BE PERPENDICULAR TO THE FLAT SURFACE OF FOUNDATION.
  - BACK FILLING SHALL HAVE TO BE DONE ENSURING PROPER COMPACTION AS PER SPECIFICATION & IS-2720 (PART-VII) USING APPROVED SOIL. BACK FILLING SHALL BE CARRIED OUT IN LAYERS NOT EXCEEDING 300 MM. AND EACH LAYER TO BE COMPACTED SO AS TO ACHIEVE 90% COMPACTION AS PER STANDARD PROCTOR DENSITY TEST FOR COHESIVE SOIL.

ENGINEERING REFERENCE DRAWINGS :-

- 9587-001-301-PVC-C-108 (PE-DG-508-100-M001) ----- PLOT PLAN
- 9587-999-POC-F-001 NTPC DRG. ----- GENERAL LAYOUT PLAN.
- 0-00-610-8709-----FOUNDATION PLAN OF HP 1103 MILL-DYNAMIC CLASSIFIER (WITH PLANETARY GEAR BOX)

CONST. REFERENCE DRAWINGS :-

- PE-00-508-616-C001(9587-001-315-PVC-C-0240)-----MILL & BUNKER BAY - G.A. OF COLUMN FOUNDATIONS
- PE-00-508-615-C002(9587-001-315-PVC-C-0231)-----BOWL MILLS - FOUNDATION RC DETAILS

LEGEND:

- NGL = NATURAL GROUND LEVEL
- FGL = FINISH GROUND LEVEL
- (TYP.) = TYPICAL
- R/F = REINFORCEMENT
- TOG = TOP OF GROUT
- FEL = FINISHED FLOOR LEVEL


SPECIAL NOTE:

BHEL HEREBY CONFIRMS THAT THIS DRAWING/DOCUMENT MEETS ALL THE CONTRACT REQUIREMENTS INCLUDING SAFETY AND STATUTORY REQUIREMENTS AND FACILITATE EASY OPERATION AND MAINTENANCE. IN CASE ANY DEVIATION IS FOUND, THE CONTRACTOR SHALL CARRY OUT ALL REQUIRED CHANGES/ MODIFICATIONS WITHOUT ANY COST IMPLICATIONS TO NTPC. IN ADDITION, PENALTY ON ACCOUNT OF NONCOMPLIANCE OF CONTRACT SPECIFICATION AS DEMAND FIT BY THE EMPLOYER SHALL BE RECOVERED.


BHEL-PROJECT ENGINEERING MANAGEMENT/CIVIL			
THIS DRAWING MARKED (✓) IS RELEASED FOR			
<input checked="" type="checkbox"/> COMMENTS/REVISION	<input checked="" type="checkbox"/> PLANNING	<input checked="" type="checkbox"/> INFORMATION	<input checked="" type="checkbox"/> AS BUILT DRAWING
<input checked="" type="checkbox"/> CONSTRUCTION	<input checked="" type="checkbox"/> AS BUILT DRAWING	<input checked="" type="checkbox"/> AS BUILT DRAWING	<input checked="" type="checkbox"/> AS BUILT DRAWING
STAMP ALL PREVIOUS REVISION AS SUPERSEDED			
NAME	AMIT TRIPATHI	DATE	15.03.2024
SIGNATURE		DATE	15.03.2024

NTPC DRG. NO.	NTPC NO. 9587-001-315-PVC-C-0230
CUSTOMER	NTPC LIMITED (A GOVERNMENT OF INDIA ENTERPRISE)
PROJECT	LARA SUPER THERMAL POWER PROJECT (2380MW STAGE-II)
DESIGN	BHARAT HEAVY ELECTRICALS LTD POWER SECTOR
PROJECT ENGINEERING MANAGEMENT	NOIDA (U.P.)
DATE	15.03.2024


TITLE	DRWING NO.	DEPT.	SCALE	SHEET	OF	REV.	RI
BOWL MILL FOUNDATION-GA & CONCRETE OUTLINE DETAILS	PS-DG-508-615-C001			1	1		
MPL	CIVIL	ELEC	MECH	WATER	MAX		
DATE							




SECTION 1-1




SECTION 2-2




SECTION 3-3




SECTION 4-4




SECTION 5-5  
(FOR LUBE OIL)




TYPICAL LUG DETAILS  
OF CORNER ANGLE




PLAN OF SHEAR KEY



DETAIL-E  
(DETAIL FOR CABLE ENTRY)

		<b>TECHNICAL SPECIFICATION</b> <b>2X800 MW LARA TPP STAGE II</b> <b>PACKING SPECIFICATION</b>				<b>PE-TS-508-160-A101</b>	
						<b>Rev. No. 00</b>	
						<b>Date : APRIL 2024</b>	
<b>ANNEXURE-IX</b>							
<b>PACKING REQUIREMENT</b>							
<b>COMMON GUIDELINES FOR PACKING</b>							
<b>1. GENERAL:</b>							
1.1		The Components/Assemblies need to be packed suitably to avoid physical damage & corrosion during transit & storage. This packing shall be suitable for different handling operations and for the adverse conditions during transportation and during indoor / outdoor storage of materials.					
1.2		All the equipment shall be suitably protected, coated, covered or boxed and crated to prevent damage or deterioration during transit, handling and storage at site till the time of erection. The Contractor shall be responsible for all loss or damage during transportation, handling and storage due to improper packing.					
1.3		The identification marking indicating the name and address of the consignee shall be clearly marked in indelible ink on two opposite sides and top of each of the packages. In addition the Contractor shall include in the marking gross and net weight, outer dimension and cubic measurement.					
1.4		Each package shall be accompanied by a packing note quoting specifically the name of the Contractor, the number and date of contract and names of the office placing the contract, nomenclature of contents and Bill of Material.					
<b>2.</b>		<b>TYPES OF PACKING:</b>					
		The following 5 types of packing have been standardized for packing of General Components/ Assemblies.					
a		<b>OP'</b> - Open Type.					
b		<b>PP'</b> - Partially Packed.					
c		<b>CP'</b> – Crate/Box Packing - Components/Equipment requiring physical protection.					
d		<b>'CQ'</b> - Case Packing – Machined components-Small & Medium Components/ Assemblies/ Equipment which require corrosion & physical protection.					
e		<b>'CR'</b> - Case Packing – Electrical/Electronic Components/ Assemblies, which require special packing viz. Water Proof, Shock Proof etc...					
<b>3.</b>		<b>DESCRIPTION OF TYPES OF PACKING:</b>					
		The various types of packing, as standardized above, are described below.					
3.1		<b>'OP' - Open Type</b>					
		In case, of components which are not affected by water & dust and do not require special protection, are generally not machined, shall be sent as open packages. However, these components may be sent in crates, wherever necessary.					
3.2		<b>PP' - Partially Packed</b>					
3.2.1		Components which need special protection at selected portions only shall be despatched partially packed. Machined surfaces should not be allowed to come directly in contact with the wood. Such surfaces should be protected with 100GSM(Colourless) Multi Layered Cross Laminated Polyethylene					
3.2.2		Film. All sharp corners and edges shall be protected by rubber mats to prevent damage to the polyethylene film.					
3.3		<b>'CP' - Crate Packing</b>					
		Assemblies/Components which need only physical protection from the point of view of handling shall be despatched duly packed in crates.					
3.4		<b>'CQ' - Case Packing - Machined Components/Assemblies/Equipment</b>					
3.4.1		Small and medium sized components/assemblies/equipment due to size/weight and to avoid handling and pilferage problems shall be packed in Case/Containers. Wherever required adequate quantity of silica gel or VCI Powder/Tablets, packed in thin muslin cloth cotton bags shall be suitably placed. Small machines/components of less weight shall be provided with suitable cushioning by Rubberised coir. The components inside the case shall be entirely covered with 100GSM(Colourless) Multi Layered Cross Laminated Polyethylene Film, wherever required. This may be prescribed for electronic parts/critical machined components/surfaces.					
3.4.2		For mechanical product like valves where motors are separately securely wrapped in polyethylene, the requirement of individual component wrapping shall be exempted.					
3.5		<b>CR' - Case Packing - Electrical &amp; Electronic Components/Assemblies</b>					
		Delicate components likely to be damaged e.g. Gauges, Instruments etc. are to be wrapped in waxed paper or polyethylene air bubble film and packed in cartons. Adequate quantity of Silica gel packed in cotton bags of 100grams each are to be suitably placed in the cartons. The cartons shall be entirely covered with 100GSM(Colourless) Multi Layered Cross Laminated Polyethylene Film before being packed in the cases. VCI Powder/Tablets can be used as an alternative to Silica Gel.					

	<b>TECHNICAL SPECIFICATION</b> <b>2X800 MW LARA TPP STAGE II</b> <b>PACKING SPECIFICATION</b>	<b>PE-TS-508-160-A101</b>
		<b>Rev. No. 00</b>
		<b>Date : APRIL 2024</b>

#### 4 PREPARATION OF PACKING CASES

<b>4.1 DIMENSIONS:</b>	
a)	Thickness of planks for Front, rear, top and bottom sides and binding, jointing battens shall be 25/20mm +2/-3 mm as per applicable drawings of the respective units/manufacturers.
b)	Width of all planks including the tongue shall be more than 125mm and after planing it shall be minimum 100mm.
c)	Minimum number of planks shall be used for a shook.
d)	Horizontal, vertical, diagonal planks shall be given for binding (number of such planks depend on the dimension of panel.
e)	Width of binding planks shall be minimum 100mm.
f)	Distance between any 2 binding planks shall be less than 750mm.
g)	diagonal planks shall be used in between vertical binding planks when distance between inner to inner of vertical planks is more than 750mm
h)	Distance of the outer edges of these planks from the edge of case shall be less than 250mm.
i)	Diagonal planks are not required for top planks and width side, if the width of pallet is less than 750mm.

<b>4.2 HOOP IRON STRIPS</b>	
	These are used for strapping the boxes. The width of the strips shall be 19+1mm and thickness 0.6+0.01mm. The material shall be free from rust. If sufficient nailing is done for bigger boxes, strapping need not be done.

<b>4.3 BRACKETS</b>	
	These brackets are used for nailing to the corners of cubicle boxes. The brackets shall be of mild steel of thickness min 2mm and width 25+1mm. The brackets shall be of "L" shape, the length of each side being 100+2mm. Two holes shall be provided towards the end of each side for screwing /nailing.


<b>4.4 MULTI LAYERED CROSS LAMINATED POLYTHELENE FILM</b>	
	100GSM (Colourless) Multi Layered Cross Laminated Polythelene Film are used to make covers to the jobs individually. The cross lamination gives qualities of extra toughness, together with flexibility and lightness coupled with good weather resistance to ultra violet rays.

<b>4.5 RUBBERISED COIR:</b>	
	The rubberized coir is used as cushioning material. For the packing of loose items, items are to be arrested by using rubberized coir. For the packing of cubicles rubberized coir of thickness 25mm and width 75mm shall be used.


<b>5 MULTI LAYER CROSS LAMINATED POLY FILM WHILE PACKING OF CUBICLES/CASING</b>	
5.1	The inner surface of 4 sides of shook's shall be nailed with Multi-layer cross laminated poly film (as per 4.4) using blue nails wherever 2 pieces of Cross laminated poly film are used, the joint shall have an overlap of minimum 20mm.
5.2	The inner surface of top cover shall be nailed with Multi-layer cross laminated poly film. This sheet shall project outside on 4 sides by at least 100mm and shall be nailed properly on sides. Joining of sheets should have overlap of minimum 20mm.
5.3	The cubicles shall be covered with Multi-layer cross laminated poly film.

<b>6 PACKING OF LOOSE ITEMS/SPARES</b>	
6.1	Inner surfaces of all 6 sides shall be lined with Multi Layered Cross Laminated Polythelene Film (as per clause 5.4) using blue nails.
6.2	Rubberized coir of minimum 25mm thickness and 100 mm width shall be nailed to inner surfaces of bottom and 4 sides of box.
6.3	Internal packing: Items that go into the box shall be packed using 100GSM, (Colourless) Multi Layered Cross Laminated Polyethylene Film. Any space left between the job and the sides and the top of the box shall be filled with rubberized coir to get proper cushioning effect.
6.4	Certain items like transformers, reactors, breakers, etc., shall be bolted to the bottom of the box using bolts, nuts and washers.
6.5	Silica gel held in cotton bags shall be kept at proper places in the box.
6.6	Packing slip kept in polyethylene bag shall be placed in the box.
6.7	Two numbers of hoop iron strips shall be strapped tightly on the case using clips.
6.8	Stencil marking of various details and marking of various symbols shall be done as per BHEL instructions using indelible/non-washable marking ink.
6.9	Loose items to be kept inside the cubicle/casing
	- Other items which are given loose in addition to cubicle shall be packed in separate boxes.





	<b>TECHNICAL SPECIFICATION</b> <b>2X800 MW LARA TPP STAGE II</b> <b>PACKING SPECIFICATION</b>	<b>PE-TS-508-160-A101</b> <b>Rev. No. 00</b> <b>Date : APRIL 2024</b>
---	---	---

7 TYPICAL PATTERN OF WOODEN BOX
---------------------------------



8 SEALED PACKING:	
	Components sub-assemblies and assemblies sensitive to climatic conditions shall be packed seal tight. All the openings of the sensitive components, sub-assemblies and assemblies shall be blanketed to prevent the ingress of dust and moisture. The components sub-assemblies and assemblies are completely covered with 2 layers of polyethylene sheet. All sharp corners and
9 MARKINGS/STENCILINGS	
9.1 "HANDLE WITH CARE", "FRAGILE DO NOT TURN OVER".	
9.2 Besides the caution signs the product information's shall be stencilled of letters with 13mm to 50mm height.	
9.3 In case of consignment consists of more than one package, each package shall carry its package no as given in shipping list. All caution signs shall be stencilled in high quality full glossy out door finishing paint red in colour (AA56126). All other markings shall be carried out in black enamel.	
9.4 Caution signs & other markings shall be stencilled on both the end shooks & the side shooks.	
9.5 Caution sign (for slinging) shall be stencilled only on side shooks at the appropriate place.	
9.6 In case the size of package is small for using the stencils, then hand written letters/figures shall be allowed.	



	<b>TECHNICAL SPECIFICATION</b> <b>2X800 MW LARA TPP STAGE II</b> <b>PACKING SPECIFICATION</b>	PE-TS-508-160-A101
		Rev. No. 00
		Date : APRIL 2024

BHEL – <unit> - <location> - <pin>			
CONSIGNEE			
MATERIAL			
CUSTOMER REF.	MO. NO.		
DESPATCH ADVICE NOTE NO	CASE NO		
DIMENSIONS(MM) L x B x H	<table border="1"> <tr> <td>NET WT -KGS</td> <td>GROSS WT -KGS</td> </tr> </table>	NET WT -KGS	GROSS WT -KGS
NET WT -KGS	GROSS WT -KGS		
SPECIAL INSTRUCTIONS	HANDLE WITH CARE - KEEP DRY DO NOT DROP - DO NOT TILT		

Figure 4 – TYPICAL MARKING PLATE (225 X 170)



Figure 5

Easy spares [Initial and O&M] Traceability and Identification at units and as well as at sites:

**Note**

Protective coating applied on machined surfaces should not be disturbed. The plastic covering should be put back carefully so that it prevents ingress of dust and moisture. Some packing may have vapour phase inhibitor (VPI) paper enclosed inside the packing cases. This should be restored to its original place as far as possible.

**TITLE**

**LARA STPP STAGE-II (2X800MW)**  
**MILL REJECT SYSTEM (CONVEYOR TYPE)**  
**SPECIFIC TECHNICAL REQUIREMENTS**

SPECIFICATION NO. PE-TS-508-160-A101

SECTION - I

REV 0

Sub Section

Date April 2024

Page 1 of 1

**SUB-SECTION IB – Specific Technical Requirement (Electrical)**



**TECHNICAL SPECIFICATION FOR  
MILL REJECT SYSTEM  
(ELECTRICAL PORTION)  
LARA SUPER THERMAL POWER PROJECT  
STAGE-II (2X800 MW)**

SPECIFICATION NO. PE-TS-XXX-XXX-XXXX  
VOLUME II B  
REV 01                      DATE 16.04.2024  
PAGE 1 OF 1

**SPECIFIC TECHNICAL REQUIREMENTS: ELECTRICAL**

- 1.0 Scope for supply, and erection & commissioning of various equipment forming part of electrical system for this package shall be as per Annexure-I [Scope of Work (Electrical)].
- 2.0 Make of all electrical equipment/ items supplied shall be reputed make. Same shall be subject to approval of BHEL/customer after award of contract without any commercial implications. Tentative make list of various Electrical items (Motors/ lugs/glands) is attached.
- 3.0 All QPs shall be subject to approval of BHEL/customer after award of contract without any commercial implication.

**4.0 DOCUMENTS TO BE SUBMITTED ALONG WITH BID**

- 4.1 Bidder shall confirm total compliance to the electrical specification without any deviation from the technical/ quality assurance requirements stipulated.
- 4.2 No technical submittal such as copies of data sheets, drawings, write-up, quality plans, type test certificates, technical literature, etc, is required during tender stage. Any such submission even if made, shall not be considered as part of offer.

**5.0 LIST OF ENCLOSURES**

- 5.1 Electrical scope between BHEL & vendor (Annexure-I).
- 5.2 Technical specification - Motors (Annexure-II).
- 5.3 Datasheets –Motor (Annexure-III)
- 5.4 Quality Plan for motors. (Annexure-IV)
- 5.5 Load data format (Annexure-V).
- 5.6 Explanatory note for Cable routing & Cable schedule format (Annexure-VI)
- 5.7 Tentative make list for electrical items (motor, lugs, glands) (Annexure-VII)
- 5.8 Tentative list of cable sizes (Annexure-VIII)




**ELECTRICAL SCOPE BETWEEN BHEL AND VENDOR (FOR EPC PROJECTS)****PACKAGES: MILL REJECT SYSTEM****SCOPE OF VENDOR: SUPPLY, ERECTION & COMMISSIONING OF VENDOR'S EQUIPMENT****PROJECT: LARA SUPER THERMAL POWERPROJECTSTAGE-II (2X800 MW)**

S.NO	DETAILS	SCOPE SUPPLY	SCOPE E&C	REMARKS
1	415V MCC	BHEL	BHEL	240 V AC (supply feeder)/415 V AC (3 PHASE 4 WIRE) supply shall be provided by BHEL as per load data provided by vendor at contract stage for all equipment supplied by vendor as part of contract.
2	Local Push Button Station (for motors)	BHEL		Located near the motor.
3	Power cables, control cables and screened control cables for a) both end equipment in BHEL's scope b) both end equipment in vendor's scope c) one end equipment in vendor's scope	BHEL BHEL BHEL		1. For 3.b) & c): Sizes of cables required shall be informed by vendor at contract stage (based on inputs provided by BHEL) in the form of cable listing. Finalisation of cable sizes shall be done by BHEL. Vendor shall provide lugs & glands accordingly. 2. Termination at BHEL equipment terminals by BHEL. 3. Termination at Vendor equipment terminals by Vendor.
4	Cable trays, accessories & cable trays supporting system  100/ 50 mm cable trays/ Conduits/ Galvanised steel cable troughs for local cabling	BHEL  BHEL		Local cabling from nearby main route cable tray (BHEL scope) to equipment terminal (vendor's scope) shall be through 100/ 50 mm cable trays/ conduits/ Galvanised steel cable troughs, as per approved layout drawing during contract stage.
5	Cable glands, lugs and bimetallic washers for equipment supplied by Vendor	Vendor		Bimetallic washers shall be used for bimetallic connections.
6	Conduit and conduit accessories for cabling between equipment supplied by vendor	BHEL		
7	Junction box for control & instrumentation cable	Vendor		Number of Junction Boxes shall be sufficient and positioned in the field to minimize local cabling.
8	Lighting	BHEL		
9	Equipment grounding (including electronic earthing) & lightning protection	BHEL		Vendor shall indicate location of Electronic Earth pit in their Civil assignment drawing
10	Below grade grounding	BHEL		

**ELECTRICAL SCOPE BETWEEN BHEL AND VENDOR (FOR EPC PROJECTS)****PACKAGES: MILL REJECT SYSTEM****SCOPE OF VENDOR: SUPPLY, ERECTION & COMMISSIONING OF VENDOR'S EQUIPMENT****PROJECT: LARA SUPER THERMAL POWERPROJECTSTAGE-II (2X800 MW)**


S.NO	DETAILS	SCOPE SUPPLY	BHEL	REMARKS
11	LT Motors with base plate and foundation hardware	Vendor		
12	Any other equipment/ material/ service required for completeness of system based on system offered by the vendor (to ensure trouble free and efficient operation of the system).	Vendor		In case the requirement of Junction Box arises on account of Power Cable size mis-match due to vendor engineering at later stage, vendor shall supply the Junction Box for suitable termination

	TECHNICAL SPECIFICATION MILL REJECT SYSTEM LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW)		PE-TS-XXX-YYY-HZZZ	
			Issue No: 01	
			Rev. No. 00	
			Date :	
TECHNICAL DATA - PART - A				
SL.NO	DESCRIPTION	UOM	DETAIL	
1.0	DESIGN CODES & STANDARDS			
1.1	Three phase induction motors :		IS15999, IEC:60034, IS: 12615, IS: 325	
1.2	Energy Efficient motors		IS 12615, IEC:60034-30	
1.3	Mechanical Vibration of Rotating Electrical Machines with Shaft Heights 56 mm and Higher - Measurement, Evaluation and Limits of Vibration Severity		IS 12075/IEC 60034-14	
1.4	Designation of Methods of Cooling of Rotating Electrical Machines		IS 6362	
1.5	Designation for types of construction and mounting arrangement of rotating electrical machines		IS 2253	
2.0	DESIGN /SYSTEM PARAMETERS			
2.1	Rated voltage	V	415	
2.2	Frequency	Hz	50	
2.3	Permissible variations for			
a)	Voltage	%	+/-10	
b)	Frequency	%	(+)3 to (-)5	
c)	Combined	%	10 (absolute sum)	
2.4	System fault level at rated voltage for 1 sec	kA	50	
2.5	Short time rating for terminal boxes for 0.25 sec	kA	50	
2.6	Type of motors		Squirrel cage induction motor	
a)	Non-VFD		Suitable for direct on line starting	
b)	VFD (if applicable)		Suitable for inverter duty	
2.7	Efficiency class			
a)	Output rating (at 50 deg.C ambient temperature)		Efficiency class	
i)	upto 50 KW		IE4	
ii)	50- 200 KW		IE3	
2.8	Rating			
a)	Motor duty		Continuously rated-S1	
b)	Design margin over continous max. demand of the driven equipment (min)		10%	
3.0	CONSTRUCTION FEATURES			
3.1	Winding		Electrolytic grade copper conductor	
3.2	Enclosure Details			
a)	Degree of protection			
	i) Indoor application		IP 55	
	ii) Outdoor application		IP 55 (Additional Canopy to be provided)	
b)	Method of ventilation		Totally enclosed fan cooled (TEFC) type	
3.3	Insulation			
a)	Class		'F' with temperature rise limited to class 'B'	
b)	General Characteristics		Non-hygroscopic, oil resistant, flame resistant	

c)	Special Characteristics		VPI insulation for VFD motors
3.4	Bearings		
a)	Horizontal motors		Grease lubricated ball or roller bearings
b)	Vertical motors		Grease lubricated ball or roller bearings or combined thrust and guide bearing
3.5	Main terminal box		
a)	Type		Detachable type
b)	Location		In accordance with Indian Standards clearing the motor base-plate/ foundation
c)	Terminals		Stud or lead wire type, substantially constructed and thoroughly insulated from the frame
d)	Markings		Phase markings on terminals and direction of rotation marked on the non-driving end
e)	DOP		Same as motor
f)	Position when viewed from the non driving end		Left hand side
g)	Rotation		90 Deg.
h)	Space heater (for ratings 30 kW and above)		Suitable for 240V, 50Hz 1 ph AC. Separate terminal box provided for space heaters.
f)	Cable glands/lugs/gland plates		
i)	Size		As per cable size used
ii)	Lugs		Solderless crimping type heavy duty (Aluminium lugs for Aluminium cables and copper lugs for copper cables)
iii)	Glands		Double compression Ni-Cr plated brass glands
iv)	Gland plate thickness		3 mm (hot/cold rolled sheet steel) or 4 mm (non magnetic material for single core cables)
3.6	Earthing points		
a)	No. of points on motor body		Two earthing points on opposite sides with two separate and distinct grounding pads complete with tapped holes, GI bolts and washers.
b)	No. of points on motor terminal box		One earthing point complete with tapped holes, GI bolts and washers.
c)	Earthing Flat size		
i)	LT Motors above 125 KW		50 x 6mm GS flat
ii)	25 KW to 125 KW		25 x 6mm GS flat
iii)	1KW to 25 KW		25 x 3mm GS flat
iv)	Fractional kW		8 SWG GS Wire
3.7	Painting		Corrosion proof epoxy based paint with suitable additives to be used.
a)	Paint shade		RAL 5012 (Blue)
b)	Thickness of paint		The thickness of finish coat shall be minimum 50 microns (minimum total DFT 100 microns).
3.8	Minimum spacing between gland plate & centre of bottom terminal stud		
a)	UP to 3 KW		As per manufacturer's practice.
b)	Above 3 KW - upto 7 KW		85 mm
c)	Above 7 KW - upto 13 KW		115 mm
d)	Above 13 KW - upto 24 KW		167 mm

e)	Above 24 KW - upto 37 KW		196 mm
f)	Above 37 KW - upto 55 KW		249 mm
g)	Above 55 KW - upto 90 KW		277 mm
h)	Above 90 KW - upto 125 KW		331 mm
i)	Above 125 KW-upto 200 KW		385/203 (For Single core cables only) mm
3.9	Minimum inter-phase and phase-earth air clearances with lugs installed		
a)	UP to 110 KW		10mm
b)	Above 110 KW and upto 150 KW		12.5mm
c)	Above 150 KW		19mm
4.0	<b>PERFORMANCE PARAMETERS</b>		
4.1	Starting requirement		
a)	Minimum permissible voltage as a percentage of rated voltage, at start to bring the driven equipment upto rated speed		a) Up to 85% of rated voltage for ratings below 110 KW b) Up to 80% of rated voltage for ratings from 110 KW to 200 KW
b)	Maximum locked rotor current		As per IS 12615
c)	Starting duty		Two hot starts in succession, with motor initially at normal running temperature.
d)	The locked rotor withstand time		Speed switches mounted on the motor shaft shall be provided in cases where below requirements are not met.
	Starting time of motors at minimum permissible voltage during starting		The locked rotor withstand time under hot condition at highest voltage limit
i)	upto 20 secs.		atleast 2.5 secs. more than starting time
ii)	more than 20 secs. and upto 45 secs		atleast 5 secs. more than starting time
iii)	more than 45 secs.		more than starting time by at least 10% of the starting time
e)	Ratio of locked rotor KVA at rated voltage to rated KW (max.)		
i)	Below 110KW		10
ii)	From 110 KW & upto 200 KW		9
4.2	Torque		
a)	Accelerating torque at any speed with the lowest permissible starting voltage		at least 10% motor full load torque
b)	Pull out torque at rated voltage		at least 205% of full load torque
4.3	Noise level (max.)		85 dB(A)
4.4	Vibration limits		As per IS 12075
5.0	<b>INSPECTION/TESTING</b>		


5.1	<p>LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED.</p> <p>The following type test reports shall be submitted for each type and rating of LT motor of above 100 KW only.</p> <ol style="list-style-type: none"> <li>1. Measurement of resistance of windings of stator and wound rotor.</li> <li>2. No load test at rated voltage to determine input current power and speed</li> <li>3. Open circuit voltage ratio of wound rotor motors ( in case of Slip ring motors)</li> <li>4. Full load test to determine efficiency power factor and slip</li> <li>5. Temperature rise test</li> <li>6. Momentary excess torque test.</li> <li>7. High voltage test</li> <li>8. Test for vibration severity of motor.</li> <li>9. Test for noise levels of motor(Shall be limited as mentioned above.)</li> <li>10. Test for degree of protection and</li> <li>11. Overspeed test.</li> </ol>		
5.2	<p>The type test listed above should have been conducted within 10 yrs prior to supply under this contract. In absence of type tests reports or in case reports are not found to be meeting the specification/standards requirements, vendor shall conduct all such type tests without any commercial/delivery implication to BHEL according to the relevant standards and reports shall be submitted to the owner for approval.</p>		
5.3	<p>The type test reports once approved for any projects shall be treated as reference. For subsequent projects of NTPC, an endorsement sheet will be furnished by the manufacturer confirming similarity and "No design Change". Minor changes if any shall be highlighted on the endorsement sheet.</p>		
5.4	<p>All acceptance and routine tests as per the specification and relevant standards shall be carried out.Charges for these shall be deemed to be included in the equipment price.</p>		
5.5	<p>For motor rating upto 50 KW, BHEL QP No. PE-QP-999-Q-006 Rev 02 is to be followed. For motor ratings above 50 kW NTPC Quality assurance plan will be followed.</p>		

	<p align="center"><b>TECHNICAL SPECIFICATION FOR MRS (ELECTRICAL PORTION) LARA SUPER THERMAL POWER PROJECT STAGE-II (2X800 MW)</b></p>	<p>SPECIFICATION NO. PE-TS-XXX-XXX-XXX</p> <p>VOLUME II B</p> <p>REV 010                      DATE 16.04.2024</p> <p>PAGE 1 OF 1</p>
--	--	--

#### **TECHNICAL SPECIFICATION OF CABLE GLANDS AND LUGS**

Cable glands shall conform to BS:6121. Cable glands shall be made of heavy duty brass machine finished and nickel chrome plated. Thickness of plating shall not be less than 10 micron. All washers and Hardware shall also be made of brass with nickel chrome plating. Rubber components shall be of neoprene or better synthetic material and of tested quality.


Cable lugs/ferrules shall be solderless crimping type suitable for power and control cables as per the DIN 46239. Aluminium solderless crimping lugs/ ferrules shall be used for Aluminium cables and Copper lugs/ferrules shall be used for Copper cables. Bimetallic washers or bimetallic type lugs shall be used for bimetallic connections

	<b>TECHNICAL SPECIFICATION</b> <b>MRS</b> <b>LARA SUPER THERMAL POWER</b> <b>PROJECT</b> <b>STAGE-II (2X800 MW)</b>		<b>PE-TS-XXX-YYY-HZZZ</b> Issue No: 01 Rev. No. 00 Date :	
<b>TECHNICAL DATA - PART - B (SUPPLIER DATA TO BE FURNISHED AFTER AWARD OF CONTRACT)</b>				
<b>SL.NO</b>		<b>UOM</b>	<b>DETAIL</b>	
1.0	<b>GENERAL</b>			
i)	Manufacturer & Country of origin.			
ii)	Equipment driven by motor)			
iii)	Motor type			
iv)	Country of origin			
v )	Quantity	nos.		
2.0	<b>DESIGN AND PERFORMANCE DATA</b>			
i)	Frame size			
ii)	Type of duty			
iii)	Type of enclosure and method of cooling			
vi)	Type of mounting			
vii)	Direction of rotation as viewed from DE END			
viii)	Standard continuous rating at 40 deg.C. ambient temp. as per Indian Standard	(KW)		
ix)	(A) Derated rating for specified normal condition i.e. 50 deg. C ambient temperature	(KW)		
	(B) Rating as specified in load list	(KW)		
xi)	Rated speed at rated voltage and frequency	rpm		
xii)	At rated Voltage and frequency			
	a) Full load current	A		
	b) No load current	A		
xiii)	Power Factor at			
	a) 100% load			
	b) At duty point			
	c) 75% load			
	d) 50% load			
	e) NO load			
	f) Starting.			
xiv)	Efficiency at rated voltage and frequency			
	a) 100% load			
	b) At duty point			
	c) 75% load			
	d) 50% load			
xv)	Starting current( <i>inclusive of IS tolerance</i> ) at			
	a. 100 % voltage	A		
	b. Minimum starting voltage	A		
xvi)	Starting time with minimum permissible voltage			
	a. Without driven equipment coupled	sec		
	b. With driven equipment coupled	sec		
xvii)	Safe stall time with 110% of rated voltage			
	a. From hot condition	sec		



	b. From cold condition	sec	
xviii)	<b>Torques :</b>		
	a. Starting torque at min. permissible voltage	(kg-mtr.)	
	b. Pull up torque at rated voltage.	(kg-mtr.)	
	c. Pull out torque	(kg-mtr.)	
	d. Min accelerating torque available	(kg-mtr.)	
	e. Rated torque	(kg-mtr.)	
xix)	Stator winding resistance per phase ( at 20 Deg.C.)	Ohm	
xx)	GD <sup>2</sup> value of motors		
xxi)	Locked rotor KVA input (at rated voltage)		
xxii)	Locked rotor KVA/KW.		
xxiii)	<b>Bearings</b>		
	a. Type		
	b. Manufacturer		
	c. Self Lubricated or forced Lubricated		
	d. Recommended Lubricants		
	e. Guaranteed Life in Hours		
	f. Whether Dial Type thermometer provided		
	g. Oil pressure Gauge/switch		
	i. Range		
	ii. Contact Nos. & ratings		
	iii. Accuracy		
xxiv)	<b>Vibration</b>		
	a) Velocity	mm/s	
	b) Displacement	microns	
xxv)	Noise level	db	
<b>3</b>	<b>CONSTRUCTIONAL FEATURES</b>		
i	Stator winding insulation		
	a. Class & Type		
	b. Tropicalised (Yes/No)		
	c. Temperature rise over specified max.		
	i. Cold water temperature of 38 DEG. C.		
	ii. Ambient Air 50 DEG. C.		
	d. Method of temperature measurement		
	e. Stator winding connection		
	f. Number of terminals brought out		
ii	Type of terminal box for		
	a. stator leads		
	b. space heater		
	c. Temperature detectors		
	d. Instrument switch etc.		
iii)	For main terminal box		
	a. Location		
	b. Entry of cables		
	c. Recommended cable size		
	d. Fault level	MVA	
iv)	Temperature detector for stator winding		
	a. Type		
	b. Nos. provided		
	c. Location		
	d. Make		
	e. Resistance value at 0 deg. C	ohms	

vi)	Paint shade		
vii).	Weight of(approx)		
	a. Motor stator (KG)		
	b. Motor Rotor (KG)		
	c. Total weight (KG)		
<b>4</b>	Relevant motor curves		


	MANUFACTURER/ BIDDER/ SUPPLIER NAME & ADDRESS		STANDARD QUALITY PLAN		SPEC. NO. :	DATE:
	CUSTOMER :		CUSTOMER :		QP NO.: PE-QP-999-Q-006, REV-02	DATE: 17.04.2020
	PROJECT:		PROJECT:		PO NO.:	DATE:
	ITEM: AC ELECT. MOTORS UPTO 50 KW (415V)		SYSTEM:		SECTION: II	SHEET 1 of 2

S. NO.	COMPONENT & OPERATIONS	CHARACTERISTICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD	AGENCY	REMARKS
1	2	3	4	5	6	7	8	9	**	
		1.WORKMANSHIP	MA	VISUAL	100%	MFG. SPEC.	MFG. SPEC.	LOG BOOK	P -	
		2.DIMENSIONS	MA	VISUAL	100%	MFG. DRG./ MFG. SPEC.	MFG. DRG./ MFG. SPEC.	LOG BOOK	P -	
1.0	ASSEMBLY	3.CORRECTNESS COMPLETENESS TERMINATIONS/ MARKING/ COLOUR CODE	MA	VISUAL	100%	MFG.SPEC./	MFG.SPEC.	LOG BOOK	P -	

Page 245 of 313

2.0	PAINTING	1.SHADE	MA	VISUAL	SAMPLE	MFG. SPEC/ APPROVED DATASHEET	MFG. SPEC/ APPROVED DATASHEET	LOG BOOK	✓ P	V -	
3.0	TESTS	1.ROUTINE TEST INCLUDING SPECIAL TEST	MA	VISUAL	100%	IS-325 / IS-12615/ APPROVED DATA SHEET	IS-325 / IS-12615/ APPROVED DATA SHEET	TEST/ INSPN. REPORT	✓ P	V *	* NOTE -1
		2.OVERALL DIMENSIONS & ORIENTATION	MA	MEASUREMENT & VISUAL	100%	APPROVED DRG/ DATA SHEET	APPROVED DRG/ DATA SHEET	TEST/ INSPN. REPORT	✓ P	V *	* NOTE -1 & NOTE-2

BHEL				BIDDER/SUPPLIER				FOR CUSTOMER REVIEW & APPROVAL			
ENGINEERING		QUALITY		Sign & Date		Sign & Date		Doc No:		Sign & Date	
Prepared by:	HEMA KUSHWAHA	Checked by:	KUNAL GANDHI	Sign	Seal	Reviewed by:	Name	Seal			
Reviewed by:	PRAVEEN DUTTA	Reviewed by:	RITESH KUMAR JAISWAL			Approved by:					

	MANUFACTURER/ BIDDER/ SUPPLIER NAME & ADDRESS		STANDARD QUALITY PLAN				SPEC. NO. :		DATE:	
			CUSTOMER :				QP NO.: PE-QP-999-Q-006, REV-02		DATE: 17.04.2020	
			PROJECT:				PO NO.:		DATE:	
			ITEM: AC ELECT. MOTORS UPTO 55KW (LV (415V))				SYSTEM:		SECTION: II	
								SHEET 2 of 2		

		3.NAMEPLATE DETAILS	MA	VISUAL	100%	-	IS-325 / IS-12615 / APPROVED DATA SHEET	SAME AS COL. 7	TEST/ INSPN. REPORT	✓	P	V	-
4.0	PACKING	SURFACE FINISH & COMPLETENESS	MA	VISUAL	100%	100%	AS PER MFG. STANDARD / (#).	AS PER MFG. STANDARD / (#).	INSPC. REPORT	✓	P	W	-
(#)													

NOTES:

1. Routine tests on 100% motors shall be done by the vendor. However, BHEL/ Customer shall witness routine tests on random samples. The sampling plan shall be mutually agreed upon.
2. For exhaust/ventilation fan motors of rating up to 1.5 KW, only routine test certificates shall be furnished for scrutiny.
3. In case test certificates for these tests on similar type, size and design of motor from independent laboratory are available, the same is valid for 5 years.
4. BHEL reserves the right to perform repeat test, if required.
5. After packing and prior to issue MDCC, photographs of items to be despatched shall be sent to BHEL for review.
6. In case of any changes in QP commented by customer at contract stage, same shall be carried out by bidder without any implication to BHEL/ Customer.
7. Project specific QP to be developed based on customer requirement.
8. For export job, BHEL technical specification for seaworthy packing to be followed.
9. Packing shall be suitable for storage at site in tropical climate conditions.
10. Latest revision/ year of issue of all the standards (IS/ ASME/ IEC etc.) indicated in QP shall be referred.

LEGENDS:

\*RECORDS, IDENTIFIED WITH "TICK"(✓) SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION,  
 \*\* M: SUPPLIER/ MANUFACTURER/ SUB-SUPPLIER, B: MAIN SUPPLIER/ BHEL/ THIRD PARTY INSPECTION AGENCY, C: CUSTOMER,  
 P: PERFORM, W: WITNESS, V: VERIFICATION, AS APPROPRIATE  
 MA: MAJOR, MI: MINOR, CR: CRITICAL  
 D: DOCUMENTATION

BHEL				BIDDER/ SUPPLIER				FOR CUSTOMER REVIEW & APPROVAL			
ENGINEERING		QUALITY		Sign & Date		Sign & Date		Doc No:		Sign & Date	
Prepared by:	HEMA KUSHWAHA	Checked by:	KUNAL GANDHI	Sign	Date	Reviewed by:	Name	Seal			
Reviewed by:	PRAVEEN DUTTA	Reviewed by:	RITESH KUMAR JAISWAL			Approved by:					



CLAUSE No.

CHAPTER NAME

**MOTOR**

TESTS/CHECKS	Visual	Dimensional	Make/Type/Rating /General Physical Inspection	Mech/Chem. Properties	NDT /DP/MPI/UT	Metallography	Electrical Characteristics	Welding/Brazing(WPS/PQR)	Heat Treatment	Magnetic Characteristics	Hydraulic/Leak/Pressure Test	Thermal Characteristics	Run out	Dynamic Balancing	Routine & Acceptance tests as per IS-4722 /IS- 9283/IS- 2148/IEC60034\IEC 60079-I/ IS- 12615	Vibration	Over speed	Tan delta, shaft voltage & polarization index test	Paint shade, thickness & adhesion
TEMS/COMPONENTS	Plates for stator frame, end shield, spider etc.	Y	Y	Y	Y	Y			Y										
	Shaft	Y	Y	Y	Y	Y	Y		Y										
	Magnetic Material	Y	Y	Y			Y			Y		Y							
	Rotor Copper/Aluminium	Y	Y	Y			Y		Y										
	Stator copper	Y	Y	Y			Y		Y			Y							
	SC Ring	Y	Y	Y			Y	Y	Y										
	Insulating Material	Y	Y	Y			Y					Y							
	Tubes, for Cooler	Y	Y	Y			Y		Y		Y								
	Sleeve Bearing	Y	Y	Y			Y		Y		Y								
	Stator/Rotor, Exciter Coils	Y	Y	Y			Y	Y											
	Castings, stator frame, terminal box and bearing housing etc.	Y	Y	Y				Y											
	Fabrication & machining of stator, rotor, terminal box	Y	Y			Y		Y	Y										
	Wound stator	Y	Y				Y	Y											
	Wound Exciter	Y	Y				Y	Y											
	Rotor complete	Y	Y				Y						Y	Y					
	Exciter, Stator, Rotor, Terminal Box assembly	Y	Y				Y												

CHAPTER NAME

Y

1. The manufacturer is to furnish a detailed Quality Plan indicating the practices & Procedure followed along with relevant supporting documents during QP finalization. However, following methodology to be followed for Inspection Categorization:

i) **Motor rating up to 50 KW: Inspection CAT- III :** Acceptance of Motor up to 50 KW is based on COC of the Manufacturer and Main Contractor confirming as follows;

ii) **Motor rating above 50 KW & less than 75 KW: Inspection CAT-II as per NTPC approved MQP:** Acceptance of Motor rating above 50 KW & less than 75 KW is based on NTPC report as per IS:12615 - 2018 (including latest revision) duly witnessed by main contractor along with COC of the Manufacturer and Main Contractor confirming as follows:

iii) Motor rating **75 KW** & above: **Inspection CAT-I**: As per NTPC approved MQP;

5. For LT Motors, stator core stack length & grade, no load loss and winding resistance w.r.t. type tested motor for IE2/IE3 shall be checked/verified in addition to

**LARA SUPER THERMAL POWER PROJECT**  
**STAGE-II (2X800 MW)**  
**EPC PACKAGE**



## ANNEXURE-VI

### CABLE SCHEDULE FORMAT

[illegible]



**Explanatory notes for filling up cable list for routing through WinPath, the cable routing program (developed by Corporate R&D) being used in PEM.**

1. For the purpose of clarity, it may please be noted that the information given in regard to the cables to be routed through WinPath as per the system elaborated below is called "Cable List", while the term "Cable Schedule" applies to the cable list with routing information added after routing has been carried out.
2. The cable list shall be entered as an MS Excel file in the format as per enclosed template EXT\_CAB\_SCH\_FORMAT.XLS. No blank lines, special characters, header, footer, lines, etc. shall be introduced in the file. No changes shall be made in the title line (first line) of the template.
3. The field properties shall be as under:
  - a. UNITCABLENO: A/N, up to sixteen (16) characters; each cable shall have its own unique, unduplicated cable number. In case this rule is violated, the cable cannot be taken up for routing.
  - b. FROM: A/N, up to sixty (60) characters; the "From" end equipment/ device description and location to be specified here. Information in excess of 60 characters will be truncated after 60 characters.
  - c. TO: A/N, up to sixty (60) characters; the "To" end equipment/ device description and location to be specified here. Information in excess of 60 characters will be truncated after 60 characters.
  - d. PURPOSE: A/N, up to sixty (60) characters; the purpose (i.e. power cable/ indication/ measurement, etc.) to be specified here. Information in excess of 60 characters will be truncated after 60 characters.
  - e. REMARKS: A/N, up to forty (40) characters; Any information pertinent to routing to be specified here (e.g., cable number of the cable redundant to the cable number being entered). Information in excess of 40 characters will be truncated after 40 characters.
  - f. CABLESIZE: A/N, 7 characters exactly as per the codes indicated below shall be specified here. The program cannot route cables described in any other way/ format.
  - g. PATHCABLENO: Field reserved for utilization by the program. User shall not enter any information here.
4. One list shall be prepared for each system/ equipment (i.e., separate and unique cable lists shall be prepared for each system).
5. The cables shall be described as per the scheme listed below:

A	NN	A	NNN
Cable	No. of cores	Cable code	Cable size
Voltage	(e.g. 01,03,3H, 07)	(See C below)	(e.g. 035,185,2.5, 0.5)
Code (see B below)			

(A) SYSTEM VOLTAGE CODES:

(ac) A = 11KV, B = 6.6KV, C = 3.3KV, D = 415V, E = 240V, F = 110V  
 (dc) G = 220V, H = 110V, J = 48V, K = +24V, L = -24V

(B) CABLE VOLTAGE CODES:

A = 11KV (Power cables)

Explanatory notes for filling up cable list for routing through WinPath, the cable routing program (developed by Corporate R&D) being used in PEM.

B = 6.6KV (Power cables)  
C = 3.3KV (Power cables)  
D = 1.1KV (LV & DC system power & control cables)  
E = 0.6KV (0.5 sq. mm. Control cables)

(C) CABLE CODES

PVC Copper

A = Armoured FRLS	B = Armoured Non-FRLS
C = unarmoured FRLS	D = Unarmoured Non-FRLS

PVC Aluminium

E = Armoured FRLS	F = Armoured Non-FRLS
G = unarmoured FRLS	H = Unarmoured Non-FRLS

XLPE Copper

J = Armoured FRLS	K = Armoured Non-FRLS
L = unarmoured FRLS	M = Unarmoured Non-FRLS

XLPE Aluminium

N = Armoured FRLS	P = Armoured Non-FRLS
Q = unarmoured FRLS	R = Unarmoured Non-FRLS

S = FIRE SURVIVAL CABLES  
T = TOUGH RUBBER SHEATH  
U = OVERALL SCREENED  
V = PAIRED OVERALL SCREENED  
W = PAIRED INDIVIDUAL SCREENED  
Y = COMPENSATING CABLES  
I = PRE-FABRICATED CABLES  
Z = JELLY FILLED CABLES

# ANNEXURE-VII

## INDICATIVE SUB-VENDOR LIST LARA SUPER THERMAL POWER PROJECT STAGE-II (2x800 MW)

ITEM/SERVICE DESCRIPTION	SL NO.	VENDOR NAME	ADDRESS	PHONE	REMARKS
LT MOTOR	1	ABB	FARIDABAD		UPTO 55KW
	2	ABB	BANGALORE		
	3	JYOTI LTD.	VADODARA		
	4	TIPM	JAPAN		UPTO 15 KW (NON FLAME PROOF)
	5	HYOSUNG	SOUTH KOREA		
	6	WEG	BRAZIL		
	7	HYUNDAI	SOUTH KOREA		
	8	LHP	SOLAPUR		
	9	CGL	AHMEDNAGAR		RQP, FOR FLAME PROOF MOTOR
	10	TMEIC	JAPAN (NAGASAKHI)		
	11	NGEF	BANGALORE		UPTO 15 KW
	12	BHARAT BIJLEE	MUMBAI		RQP, FOR FLAME PROOF ALSO
	13	KEC	BANGALORE/ HUBLI*		*UPTO 90KW, RQP, FOR FLAME PROOF ALSO
	14	MARATHON	KOLKATA		RQP (UPTO 690V & 600 KW) FOR FLAME PROOF ALSO
	15	ABB	SWEDEN		UPTO 55KW
	16	HAVELL	NEEMRANA		UP TO 90KW
	17	KAWAMATA	JAPAN		UP TO 75 KW
	18	TIPS	JAPAN		UP TO 45KW
CABLE GLANDS	1	ALLIED TRADERS & EXPORTERS	C-124 A, SECTOR-2, NOIDA -201 301, UTTAR PRADESH, INDIA	Mr. Vijay Mohan Sood +(91)-(120)-2525694 +(91)-(120)-3052594 +(91)-(11)-23287156 vijay_mohansood@yahoo.com	
CABLE GLANDS	2	ARUP ENGG & FOUNDARY WORKS	391/119, PRINCE ANWAR SHAH ROAD, CALCUTTA-700068	033 2473 0850	
CABLE GLANDS	3	BALIGA LIGHTING EQPT.PVT.LTD.	63A, CP RAMASWAMY ROAD, ALWARPET, P.B.No 6910, CHENNAI-600018	44-24995505, 22680990-4	
CABLE GLANDS	4	COMMET BRASS PRODUCTS	NUTAN CHEMICAL COMPOUND, WALBHAT ROAD, GOREGAON, MUMBAI-400063	91-022-26852961/62/63 comet@vsnl.net	
CABLE GLANDS	5	DOWELLS	M/S. DOWELLS ELECTRICALS 47/47A, SATGURU INDUSTRIAL ESTATE. OFF AAREY ROAD, GOREGAON (EAST). MUMBAI 400 063.	CEO : Mr. Jayantibhai S. Patel TEL: 022-32504770./022-29270876/ 022-29270878.	
CABLE GLANDS	6	ELECTROMAC INDUSTRIES	27/28AF NEW EMPIRE IND. ESTT., R.KRISHNA MANDIR RD.JB NGR, ANDHERI(E), MUMBAI-400059	91-22-28324829 / 66919034 devang@electromacglands.com	
CABLE GLANDS	7	INCAB	HARE STREET, KOLKATA, WEST BENGAL-700001	91-33-2480161/62/63/64 Fax : 91-33-2485766	
CABLE LUGS	1	DOWELLS	M/S. DOWELLS ELECTRICALS 47/47A, SATGURU INDUSTRIAL ESTATE. OFF AAREY ROAD, GOREGAON (EAST). MUMBAI 400 063.	CEO : Mr. Jayantibhai S. Patel TEL: 022-32504770./022-29270876/ 022-29270878.	
CABLE LUGS	2	UNIVERSAL MACHINES LTD.	4.B.B.D.BAG (EAST) 90, STEPHEN HOUSE, 5TH FLR CALCUTTA-700001	033 2282 2540	



**TECHNICAL SPECIFICATION FOR  
MILL REJECT SYSTEM  
(ELECTRICAL PORTION)  
LARA SUPER THERMAL POWER PROJECT  
STAGE-II (2X800 MW)**

SPECIFICATION NO. PE-TS-XXX-XXX-AXXX  
VOLUME II B  
REV 01                      DATE 16.04.2024  
PAGE 1 OF 1

**ANNEXURE VIII**

**TENTATIVE LIST OF CABLE SIZES**


1.1 kV, XLPE INSULATED POWER CABLES		1.1 kV, CONTROL CABLES	225V, SCREENED CONTROL CABLES	
ARMOURED, AL CONDUCTOR	ARMOURED, CU CONDUCTOR	COPPER CONDUCTOR PVC INSULATED ARMOURED CONTROL CABLES	TYPE 'F' CABLES, ARMOURED (IO)	TYPE 'G' CABLES, ARMOURED (O)
1C-150	2C-2.5	2C-1.5	2P - 0.5	2P - 0.5
1C-300	3C-2.5	3C-1.5	4P - 0.5	4P - 0.5
1C-630	4C-2.5	5C-1.5	8P - 0.5	8P - 0.5
2C-10		7C-1.5	12P - 0.5	12P - 0.5
2C-25		12C-1.5		16P - 0.5
2C-95		14C-1.5		20P - 0.5
3C-10		19C-1.5		
3C-16		5C-2.5		
3C-25		10C-2.5		
3C-50		14C-2.5		
3C-95		19C-2.5		
3C-150				
3C-240				
3.5C-25				
3.5C-50				
3.5C-95				
3.5C-150				
3.5C-240				
4C-10				



**TITLE**  
**LARA STPP STAGE-II (2X800MW)**  
**MILL REJECT SYSTEM (CONVEYOR TYPE)**  
**SPECIFIC TECHNICAL REQUIREMENTS**

SPECIFICATION NO. PE-TS-508-160-A101	
SECTION - I	
REV 0	
Sub Section	Date April 2024
Page 1 of 1	

**SUB-SECTION IC – Specific Technical Requirement (C&I)**

	<b>TECHNICAL SPECIFICATION</b> <b>MILL REJECT HANDLING SYSTEM</b> <b>2x800MW LARA TPP STAGE II</b>	PE-TS-508-145-HZZZ
		Issue No: 01
		Rev. No. 00
		Date :

<b>GENERAL TECHNICAL REQUIREMENT</b>
--------------------------------------


**C&I TECHNICAL REQUIREMENT**

1	Control of Mill Handling Reject System shall be through DCS located in Control Room.
2	Complete Field Instrumentation for monitoring and operation of Mill Handling Reject System shall be provided by Vendor.
3	The quantity of instruments for the system shall be as per tender P & ID wherever provided of the respective system as a minimum, for bidding purpose.
4	Bidder to provide one number local control panel for each pyrite hoppers. This local panel will act as interface between the DCS and the field devices for commands & feedbacks.
5	Every panel-mounted instrument, requiring power supply, shall be provided with a pair of easily replaceable glass cartridge fuses of suitable rating. Every instrument shall be provided with a grounding terminal and shall be suitably connected to the panel grounding bus.
6	Bidder to provide temperature transmitter along with junction box & other erection hardware.
7	The PROFIBUS protocol design shall be further validated by BHEL and approved by NTPC during detailed engineering and any variation/ changes required based on DDCMIS system requirements and actual field installation, operational philosophy etc. shall be considered by bidder without any implications.
8	Redundancy of sensors shall be provided by bidder (i) Triple redundancy for all analog and binary inputs required for protection of system/drives. (ii) For all other control functions dual redundancy of the sensors shall be provided by the bidder.
9	415V AC / 230V AC UPS Power supply shall be provided by BHEL at a single point, All necessary hardware for deriving other power supply from given feeder shall be in Vendor's scope.
10	Root valves, impulse piping, drain cocks, gauge-zeroing cocks, valve manifold, junction boxes and all other accessories required for erection of local / remote instruments shall be provided by Vendor. Double root valve to be provided where the design pressure is or more than 40kg/cm <sup>2</sup> .
11	The contacts of equipment mounted instruments, sensors, switches etc. for external connection including spare contacts shall be wired out in flexible/rigid conduits, independently to suitably located common junction boxes.
12	All instruments other than profibus type shall be terminated on JB/LCP in field. Number of Junction Boxes shall be sufficient and positioned in the field to minimize local cabling (max 12-15 mtrs) and trunk cable.
13	All the outdoor field instruments such as transmitters/meters etc. shall be provided with suitable Free standing cabinet(s)/panel/rack so that the equipment are protected against rain/ sunlight etc.
14	All Junction Boxes, Solenoid valves and Local control panels which are not installed inside building, suitable canopy shall be provided and design of canopy shall be approved by Employer during detailed engineering.
15	For all profibus devices GSD/DD and DTM files are to be provided for configuration/ testing in the DCS for proper interfacing and diagnostics.
16	Bidder's presence is required for at EDN Bangalore during FAT of DDCMIS for certifying correctness & completeness of implementation of Control logic in DCS. Bidder's presence is required in multiple visits at site during commissioning of DDCMIS for assistance related to process correctness. All the expenses like boarding, lodging and travel, air fare etc. shall be in bidder's scope.
17	The design of the control systems and related equipment shall adhere to the principle of 'Fail Safe' Operation wherever safety of personnel / plant equipment is involved. 'Fail Safe' operation signifies that the loss of signal, loss of excitation or failure of any component shall not cause a hazardous condition. However, it shall also be ensured that occurrence of false trips are avoided / minimized.

18	All the equipments shall be suitably protected, coated, covered or boxed and crated to prevent damage or deterioration during transit, handling and storage at Site till the time of erection. While packing all the materials, the limitation from the point of view of the sizes of railway wagons available in India should be taken account of. The Bidder shall be responsible for any loss or damage during transportation, handling and storage due to improper packing. BHEL/NTPC shall have right to insist for completion of works in shops before despatch of materials for transportation.
19	Number of pairs to be selected for Screen/ Control cable a. F-Type: 2P/4P/8P/12P(Size : 0.5 mm <sup>2</sup> ) b. G-Type: 2P/4P/8P/12P(Size : 0.5 mm <sup>2</sup> ) c. Core Cable: 3CX2.5sqmm2/ 5CX2.5sqmm2
20	<b>TYPE TEST GENERAL REQUIREMENT</b>
20.1	Submission of type test results and certificate shall be acceptable provided:
20.2	The same has been carried out by the Bidder/ sub-vendor on exactly the same model /rating of equipment.
20.3	There has been no change in the components from the offered equipment & tested equipment.
20.4	The test has been carried out as per the latest standards alongwith amendments as on the date of Bid opening.
20.5	In case the approved equipment is different from the one on which the type test had been conducted earlier or any of the above grounds, then the tests have to be repeated and the cost of such tests shall be borne by the Bidder/ sub-vendor within the quoted price and no extra cost will be payable by the Employer on this account.
20.6	The schedule of conduction of type tests/ submission of reports shall be submitted and finalized during pre-award discussion.
20.7	For the type tests to be conducted, Contractor shall submit detailed test procedure for approval by Employer. This shall clearly specify test setup, instruments to be used, procedure, acceptance norms (wherever applicable), recording of different parameters, interval of recording, precautions to be taken etc. for the tests to be carried out.
21	<b>ANNUAL MAINTAINENCE SERVICE (AMS) FOR PROFIBUS INSTRUMENTS</b>
21.1	The requirements specified below are applicable for warranty (defect liability period) and 3 years AMS period.
21.2	The Contractor's scope shall also include providing Post Warranty Maintenance for 3 years after completion of warranty period of the offered wireless systems and all associated components as per specification. The AMS shall include tools and tackle as required; travel, boarding & lodging of service engineer. In the event of any malfunction of the system hardware/system software, experienced service engineer shall be made available at site within 48 hours on the receipt of such information from Employer.
21.3	Employer personnel will work on system day-to-day basis and wherever possible, Employer shall inform the type of failure of hardware/ software to Contractor based on diagnostic available with the system. However Contractor shall be fully responsible to attend and rectify the root cause and the failure within 48 hrs. Contractor may utilize the spares available with Employer, if necessary and available with Employer at site, which are part of mandatory spares supplied with system as per this specification. However, the consumed spares shall be replenished to Employer within 2 months' time.
21.4	<b>The services under Post Warranty Maintenance Agreement, shall broadly comprise of the following:</b>
21.4.1	Periodic Maintenance Site visits, minimum four (4) times in a year (total days expected 16 in a year), schedule of visits to be discussed and finalized jointly between Contractor and client after placement of order/ delivery. It shall include inspection of general healthiness of the system, study and advice on daily maintenance, inspection of Hardware & Software, if any problem is reported, running of test programs, on-line servicing and solving reported problems. System shall be checked online.
21.4.2	Software Maintenance/ Support Contractor shall maintain the existing operating & application software for any debugging requirements to have consistent performance of the system.
21.4.3	Emergency Service In the event of any malfunction of the wireless system hardware/system software during this period, Service Engineer must report at site within 48 hrs. of report of failure. The system must be brought back within 48 hours after reporting at site.

21.4.4	<p>Contractor shall note that while carrying out the Annual Maintenance Contract activities, Employer's engineers shall associate with the Contractor. On-job training of these associated engineers shall be covered under this scope. This shall include all items being supplied by Contractor, including any bought out items but not limited to the following:</p> <p>Labour, at no additional cost, to repair any system devices , to provide tests, and adjustment to system devices.</p>
--------	--



	TECHNICAL SPECIFICATION MILL REJECT HANDLING SYSTEM 2 X 800MW LARA TPP STAGE II		PE-TS-508-145-HZZZ
			Issue No: 01
			Rev. No. 00
			Date :
TECHNICAL DATA - PART - A			
SL.NO	DESCRIPTION	UOM	DETAIL
1.0	DESIGN CODES & STANDARDS		
1.1	Impulse pipes, tubes (material, rating)		ANSI B31.1, ANSI B31.1a, ANSI/ISA 77.70
1.2	Valves (material, pr. Class, size)		ASTM A182/ASTM A105 as per ASME 16.34
1.3	Fittings (size, rating, material)		ANSI B31.1, ANSI B31.1a, ASME B16.11
1.4	Installation schemes		BS 6739-2009, ANSI/ISA 77.70
1.5	Actuator		EN15714-2
1.6	Fieldbus concepts		IEC 61158
1.7	Instruments and apparatus for pressure measurement		ASME PTC19.2
1.8	Electronic transmitters		BS-6447, IEC-60770
1.9	Bourdon tube pressure and vacuum gauges		IS-3624
1.10	Colors for ready mixed paints and enamels.		IS-5
1.11	Annunciator Sequences and Specification		ISA-18.1
1.12	Instrument and apparatus for temperature measurement		ASME PTC 19.3(1974)
1.13	Temperature measurement by electrical Resistance thermometers		IS:2806
1.15	Type of Enclosures		NEMA ICS Part - 6 - 1978 (with Rev. 1 4/80) through 110.22 (Type 4 to 13)
1.16	Racks, panels and associated equipment		EIA : RS - 310 C- 1983 (ANSI C83.9 - 1972)
1.17	Protection class for enclosures, cabinets, control panels & desks		IS:2147 -1962
2.0	DESIGN /SYSTEM PARAMETERS		
2.1	SPECIFICATION - PRESSURE TRANSMITTER, DIFFERENTIAL PRESSURE TRANSMITTER, DP BASED FLOW AND LEVEL TRANSMITTER		
	Output		Profibus PA complying to IEC 61158, digital output
	Turndown ratio		50:1
	Accuracy	%	0.06%
	Stability (% of calibrated range)	%	+/-0.25% for 10 year
	Diaphragm seal material		Suitable for process fluid
	Diagram fill fluid		Inert liquid
	Wetted parts		All wetted parts upto diaphragm seal shall be suitable for process application.
	Housing		Metallic housing with durable corrosion resistant coating
	Protection		Weather proof IP-67
	Display		Integral digital display
	Diagonstic feature		Required
	Electrical connection		1/2" NPT (f)
	Manifold		2/3 valve non integral manifold for PT and 5 valve non integral manifold for DPT
2.2	SPECIFICATION - PRESSURE GAUGE, DIFFERENTIAL PRESSURE GAUGE		
	Sensing element		Bourdon for high pressure, diaphragm/bellow for low pressure
	Sensing element material		SS316
	Movement material		SS316
	Body material		SS316
	Dial size	mm	150mm

	End connection	inch	1/2 inch NPT (m)
	Accuracy		±1% of span
	Scale		Linear, 270° arc graduated in metric units
	Range selection	%	Cover 125% of max. of scale
	Over range test		Test pr. for the assembly shall be 1.5 to the max. Design pr. At 38°C.
	Diaphragm seal material		Suitable for process fluid
	Diaphragm fill fluid		Inert liquid
	Wetted parts		All wetted parts upto diaphragm seal shall be suitable for process application
	Housing		IP-55
	Zero/span adjustment		External
	Accessories		Blow out disc, siphon, snubber, pulsation, dampener, chemical seal, gauge isolation valve
2.3	<b>DATASHEET - TEMPERATURE TRANSMITTER</b>		
	Transmitter Type		Profibus PA complying to IEC 61158 with EMC compatibility as per EN 61326, Dual input (Trip/Protection), Single Input (other application)
	Compatibility		fully compatible with RTDs
	Protection Class		IP-67
	Display		Integral digital display
	Diagonstic feature		self-indicating diagnostics
	Operating ambient temperature (with display)		70 deg C
	Electrical Connection		1/2" NPT(F)
	Composite Accuracy		RTD =<0.25% of 0-250 deg C span
	Changeover facility		Bump less changeover to second sensor in case first sensor fails with alarm facility.
	Composite accuracy Calculation		Accuracies of temperature transmitter for converting sensor input to output + temperature effect on these accuracies at ambient temperature of 50 deg C (based on the figure/ formula given in the standard product catalogue for span as specified for RTD).
	Emergency/failure Measures		In case of failure (open or burn-out) of RTD, transmitter shall provide low temperature output.
2.4	<b>DATASHEET - RESISTANCE TEMPERATURE DETECTOR (RTD)</b>		
	Type		Four wire, Pt-100 (100 Ohms resistance at zero degree Centigrade).
	No. of element		Duplex
	Housing		Diecast Aluminium
	Protection Class		IP-65
	Head		Head of TE to be provided with sufficient space and arrangement to mount head mounted temperature transmitter. Plug in connectors are to be provided for external signal cable connection. TE terminal head shall be spring loaded for positive contacts with the thermo well.
	Insulation and sheathing		Mineral (magnesium oxide) insulation and SS316 sheath
	Calibration and accuracy		As per IEC-751/ DIN-43760 Class-A for RTD
	Accessories		Thermo well and associated fittings
2.5	<b>DATASHEET - THERMOWELL</b>		
	Design		One piece solid bored type of step-less tapered design

	Material		SS316
2.6	<b>SPECIFICATION - PRESSURE/ DRAFT SWITCHES/ DP SWITCHES</b>		
	Repeatability		+/-0.5% of full range
	No. of contacts		2 No.+2NC. SPDT snap action dry contact
	Rating of contacts		60 V DC, 6 VA (or more if required by DDCMIS)
	Elect. Connection		Plug in socket.
	Set point adjustment		Provided over full range.
	Dead band adjustment		Adjustable/ fixed as per requirement of application.
	Enclosure		Weather and dust proof as per IP-55, metallic housing.
	Power Supply (where applicable)		As per Contractor's Standard practice.
	Sensing Element		Piston actuated for high pressure and diaphragm or bellows for low pr./ vacuum as per suitability to the application.
	Material		316 SS
	End connection		½ inch NPT (F)
	Over range/ proof pressure		150% of maximum operating pr.
	Accessories		Siphon, snubber, chemical seal, pulsation dampeners as required by process
	Mounting		Suitable for enclosure/ rack mounting or direct mounting
2.7	<b>SPECIFICATION - GW RADAR TYPE LEVEL TRANSMITTER</b>		
	Type		Microprocessor based 2 wire type (loop powered), HART protocol compatible Guided wave radar transmitter.
	Principle		TDR (Time domain reflectometry)
	Probe Type & Material		(i) Coaxial probe of SS316/316L. If required, probe shall be suitable for overfill prevention.
			(ii) Rod probe, cable probe of SS316/SS316L can be used for applications wherever coaxial probe is not suitable.
	Output signal		4-20 mA DC along with superimposed digital signal (based on HART protocol), suitable for over fill prevention.
	Accuracy		+/-0.5% of calibrated span or minimum 5mm.
	Power supply		24 VDC +/-10%.
	Housing		Weather proof as per IP-65, metallic housing with durable corrosion resistance coating.
	Adjustment/ calibration		Using hand held HART calibrator/ centralized PC based system (as applicable).
	Zero & span adjustment		Continuous, temper proof, remote as well as manual adjustability from instrument. It should be possible to calibrate the instrument without any level in the tank/sump etc.
	Display		Integral digital display.
	Load Impedance		500 ohms (minimum).
	Electromagnetic compatibility		Shall meet EN 61326-1 (1997) and AmdtA1, class A equipment/EN 50081-2 & EN 50081-2 & EN 50082-2
	Mounting		(i) External cage shall be provided where ever side mounting is required. External cage and other mounting accessories to be provided by the contractor.
			(ii) Where ever top mounting is required, all mounting accessories, stilling well (as required) etc., shall be provided by the contractor.
			(iii) All weather canopy shall be provided for protection from direct sunlight and direct rain for open locations.
2.8	<b>SPECIFICATION - LEVEL GAUGE</b>		
	Sensing element and material		Tempered toughened borosilicate gauge glass steel armoured reflex or transparent type
	Body material		304 SS

	End connection		Process connection as per ASME ptc , 3/4" and drain/vent 15 NB
	Accuracy	%	± 2%
	Scale		Liner vertical
	Housing		304 SS leak proof
	Over range test		Test pr. for the assembly shall be 1.5 to the max. Design pr. At 38°C.
	Wetted parts		All wetted parts upto diaphragm seal shall be suitable for process application
	Accessories		Gasket for all KEL-F shield for transparent type vent and drain valves of steel/SS as per CS /Alloy process requirement.
	Length of Gauge glass		Length of gauge glass shall not be more than 1400 mm. If the vessel is higher, multiple gauge glasses with 50 mm overlapping shall be provided.
2.9	<b>DATASHEET - RF LEVEL SWITCH</b>		
	Sensing Element		Radio Frequency type
	Material		316 SS
	End connection		Manufacturer standard
	Over range/ proof pressure		150% of maximum operating pr.
	Repeatability		+/-0.5% of full range
	No. of contacts		2 No.+2NC. SPDT snap action dry contact
	Rating of contacts		60 V DC, 6 VA (or more if required by DDCMIS)
	Elect. Connection		Plug in socket.
	Set point adjustment		Provided over full range.
	Dead band adjustment		Adjustable/ fixed as per requirement of application.
	Enclosure		Weather and dust proof as per IP-55, metallic housing.
	Accessories		All mounting accessories
2.10	<b>DATASHEET - SOLENOID VALVE</b>		
	Type		2/3/4 way SS 316/Forged Brass (depending on the application subject to Employer's approval during detailed Engg.)
	Power supply		24 V DC + 10%.
	Electrical connection		Plug and socket
	Insulation		Class 'H'
	IP Class		IP65
	Limit switches (for open/close feedback)		Required
2.11	<b>SPECIFICATION - LIMIT SWITCH</b>		
	Type		Inductive proximity type
	Mounting arrangement		Inside the enclosure
	Operating voltage Range	V	10-40 V DC
	Sensing system		Inductive Proximity type , 2 Wire
	Sensor Contact Type		NO
	Reverse polarity and short circuit protection		Yes
	IP Class-Sensor		IP67
	IP Class-Enclosure(Switch box)		IP67
	Cable entry-Enclosure(Switch box)		2 no-1/2" NPT
	Casing material-Sensor		Brass /SS
	Enclosure(Switch box) Housing material		FRP or SS
	Operating Ambient temp(sensors)	DegC	-5 to 70 deg C
	Max allowed Voltage Drop across sensor	V	5 V
	Standard applicable		EN 60947-5-2 or equivalent.

	Applicable for	Manual valves and solenoid operated on-off valves
	Corrosion resistance	Silver plated with high conductivity and non corrosive
	Protection class	IP 55
	Contact rating	shall be sufficient to meet the requirement of DCS subject to a minimum of 60 V, 6 VA rating
2.12	<b>SPECIFICATION - JUNCTION BOX</b>	
	No. of ways	12/24/36/48/64/72/96/128
	Material and Thickness	4mm thick Fiberglass Reinforced Polyester(FRP)
	Type of terminal blocks	Rail mounted cage-clamp type suitable for conductor size upto 2.5 mm <sup>2</sup> . A M6 earthing stud shall be provided.
	Protection Class	IP- 55 min. for indoor & IP-65 min for outdoor applications.
	Grounding	To be provided
	Color	RAL 7035
	Spare Terminals	At least 20% unused terminals
2.13	<b>DATASHEET - LOCAL CONTROL PANEL</b>	
2.13.1	<b>Construction</b>	
	Type	Skid mounted
	Construction	Folded
	Devices & equipments	Panel enclosure, secondary instruments, annunciation system, selector switch, push buttons, indicating lamps/ led cluster, relays, MCBs, clamp on terminals, plug socket, panel light, space heater, nameplate, earth bus
	Enclosure sheet material	Cold rolled sheet steel
	Enclosure sheet thickness	Minimum 3.0 mm for load bearing sections (mounted with instruments)
		2.0 mm for doors
		Minimum 2.0 mm for other sections
	Height	Minimum 1100 mm
	Frame thickness	Minimum 3.0 mm
	Internal plate thickness	2.5 mm
	Gland plate thickness	3.0 mm
	Cable gland	Double compression
	Base channel	ISMC 100 with anti-vibration mounting & foundation bolts
	Class of protection	IP-55
2.13.2	<b>Doors</b>	
	Rear doors	Required with integral lockable handle
	Door locking	Door when locked shall be held at minimum three places.
	Type	Removable type with concealed hinges to facilitate maintenance work
	Suitable pocket inside the door	Required for keeping the drawings / documents
	Double door	Required with suitable glass windows as per the requirement.
2.13.3	<b>Power &amp; control supply</b>	
	Input power supply	415V 3 phase AC
	No. Of feeders	Two
	Control supply	230V AC
	Additonal requirement for control supply	MCBs
		Supervisory relay along with a pilot lamp to indicate control supply 'on'
		Auto changeover unit mounted on panel

2.13.4	<b>Internal wiring</b>		
	Voltage	V	1100 V
	Material & size		PVC insulated copper multi strand wire /flexible of 1.5mm <sup>2</sup> , power cable 2.5sqmm
	Routing and runs		Through PVC troughs, AC & DC wires shall be kept separately
	Colour		Separate colours for AC & DC wires
	Ferruling		Cross ferruling
2.13.5	<b>Painting details*</b>		
	Painting shade & thickness - exterior / interior (these details shall be finalised during detailed engineering)		RAL 5012 & minimum 85 microns / glossy white & minimum 70 microns
2.13.6	<b>Gasket</b>		
	At door & removable cover		Neoprene
2.13.7	<b>Ventilation system along with louvers</b>		
	Cooling fan		2 x 100%, covered with removable wire mesh
2.13.8	<b>Terminal block</b>		
	Type		Clip on, separate for AC & DC circuits
	Voltage		1100 V
	Tb points		Cage clamp
	Mounting height from finished floor	mm	>=250 mm
	Spare	%	20%
	Identification strip		To be provided
2.13.9	<b>Illumination</b>		
	Light		Led tubelight
	Shrouded cover	W	15W minimum
	Operating power supply		240V 50 Hz AC
	Operable through		Panel door switch
	Power receptacle		15 Amp, 3-pin
2.13.10	<b>Earthing studs</b>		
	Termination to main station earth		Internally with 10 mm bolts at extreme ends for connection
2.13.11	<b>Alarm annunciator system</b>		
	No. Of windows	Nos.	Minimum 20
	Facia		Solid state discrete
	Hooter		10W
	Annunciator spare (with electronics)		10% spare window or minimum 2nos. Whichever is more
	Lamp test provision		Required
2.13.12	<b>Mounting devices on panel</b>		
	On front side		All operable and indicating devices
	Inside panel		Aux. Relays, terminal, PVC trough, MCBs etc.
	Easy access for operation / maintenance.		Required


2.14	<b>VARIABLE FREQUENCY DRIVE (VFD)</b>		
2.14.1	<b>OPERATING CONDITIONS</b>		
	Ambient Temperature		50 Deg
	Relative Humidity		95% at 40DegC
	Rated frequency		50 Hz with a variation of +3% & -5%, and 10% combined variation of voltage and frequency unless specifically brought out in the specification.
	Voltage level for the VFD output to be fed to		415V/690V, Low Voltage, Three Phase AC (LV VFD)
2.14.2	<b>SYSTEM DESCRIPTION</b>		
	Type of drive		3-Phase Diode / Thyristor / Multi Stage IGBT / IGCT / SGCT/ IEGT
	Type of Cooling of VFD		Naturally air cooled/forced air cooled
	Converter Type		Full wave diode rectifier/active front end type
	Inverter Type		Thyristor/IGBT/IGCT/SGCT/IEGT
2.14.3	<b>GENERAL REQUIREMENTS</b>		
	Design		Modern proven design in power plant/industry
	415 V/690 V LV VFD		Current Source Inverter (CSI) or Voltage Source Inverter (VSI) type with minimum Twelve (12) pulse design / 6 pulse with active front end harmonic filter.
			For drives less than 100 KW Six (6) pulse
	Impact of VFD operation on Motors/ cables & supply system		no inherent detrimental impact
	Multiple VFDs for particular application		shall be of same design so as to ensure 100 % interchangeability of components
2.14.4	<b>TECHNICAL AND OPERATIONAL REQUIREMENTS</b>		
	System Design		Shall be designed to deliver the motor input current and torque for the complete speed torque characteristics of the driven equipment, with worst input supply voltage and frequency variation.
			Shall be suitable for the load characteristics and the operational duty of the driven equipment
	Overload capacity of the controller :		
	- for constant torque applications		150% of the rated current for one minute
	- for variable torque applications at rated		110% of rated current for one minute
	- If the motor load exceeds the limit		Automatically reduction of the frequency and voltage to the motor to guard against overload.
	Operating modes		Variable torque changing as a function of speed / Constant torque over a specific speed range / Constant power over a specific speed range / Any other
	Total harmonic voltage and current distortion		Shall comply to IEEE 519 & IEC 61000
	Withstanding power		Capable of thermal, dynamic stresses and transient mechanical torque, resulting from short circuit
	Damage control		Any damage resulting from short circuit or internal fault shall be limited to the component concerned.
	Easy access to hardware		To be provided
	Provision for replacement of card (in case of		To be provided
	Allowable speed variation		Within range 10-110% or as per the requirement of driven equipment with speed set accuracy of +1% of rated maximum speed and steady state regulation of +0.5% of rated speed as per system requirement
	Power Factor for LV VFD		0.95 (minimum)
	Maximum allowable audible noise		85 dB (A) at a distance of one meter under rated loaded with all cooling fan operating conditions.
	Circuit components protection		Suitably protected against over voltages, surges, lightning etc.
	Programmed warning and fault protection function		Display a message in complete English words or Standard English abbreviations
	Drive's fault history		At least 30 time tagged fault messages to be stored
	AC environment for VFDs (>=100KW)		Required
	AC environment for VFDs (<100KW)		Not required

	Fiber optic cable connection		To be provided preferably to ensure high network reliability
2.14.5	<b>VFD COMPATIBILITY WITH THE MOTOR</b>		
	Inherent output harmonic resonance		Shall not be present in operating speed range
	Limitations of the motor cable length		VFD shall provide stable operation of motor from high-voltage dv/dt stress, regardless of cable length to motor, in case of any limitation, the vendor shall clearly state the limitations in the motor cable distance in his proposal
	If cable length becomes critical due to system requirements & constraints		filters/ chokes etc. shall be provided by the VFD manufacturers as an integral part of the VFD to mitigate the reflected wave effect of harmonics.
2.14.6	<b>BYPASS ARRANGEMENT (Optional)</b>		
	Bypass mode		Operation of Motor with VFD bypassed
	Bypass mode operation		During starting (under rated conditions) the motor will be switched on in VFD Mode to limit the starting current and after gaining speed, the load would be switched over to bypass mode.
	Comprehensive motor protection scheme for		Shall be decided during detailed engineering
2.14.7	<b>STANDBY VFD ARRANGEMENT (Optional)</b>		
	Common standby arrangement with		Required
	Changeover module		Complete protection, interlocks & control required
2.14.8	<b>EFFICIENCY</b>		
	Efficiency		Minimum 98%
	Efficiency evaluation parameters		Input transformer, harmonic filters and power factor correction (if applicable), VFD converters, cooling fans and output filter, as applicable in the system. Auxiliary controls : VFD control boards, cooling fans/pumps
	Valid test report		Required
2.14.9	<b>COOLING SYSTEM</b>		
	Type		Air cooled Design
	Air-flow pressure switches		Required for monitoring purpose
	Temperature detectors		Required for monitoring purpose
	Cooling fans		Integral to the VFD/ enclosure, If the fan fails, the system must generate the alarm/trip for the fan failure
2.14.10	<b>MOTOR</b>		
	Type		Three (3) phase squirrel cage inverter duty Induction motor with VPI insulation (Resin poor) suitable for VFD application
	Bearings		Insulated bearing on at least one side for motor frame size above 250 frame
	Power Supply Requirement		Solid state power supply consisting of an adjustable frequency inverter for speed control Motor shall be suitable for the current waveforms produced by the power supply including the harmonics generated by the drive.
	Motor Insulation design		To accept the applied voltage waveform, within the Vpeak and dv/dt limits as per IEC-61800
2.14.11	<b>OUTPUT FILTER (AS APPLICABLE):</b>		
	Output/ dv/dt filter		Required for protection of motor from high voltage dv/dt stress. Shall be included within the VFD enclosure
2.14.12	<b>DC LINK CAPACITOR (AS APPLICABLE):</b>		
	Type		Self-healing film or electrolytic type having high life time
	Discharge resistors		Required, shall be capable of reducing the residual charges to zero just after the capacitor is disconnected from the supply source.
	Suitable for high ripple currents		Yes
2.14.13	<b>AC/DC Reactor (As applicable)</b>		
	Type		Dry type, air cored, self cooled, indoor type. Suitable for withstanding earth fault continuously
	Insulation		Thermal Class 155(F), temperature rise is limited to thermal class 130 (B)



	Noise level		Shall not exceed value specified in NEMA TR-1
2.14.14	<b>VFD PANEL REQUIREMENTS</b>		
	Enclosure frames		Required
	Load bearing members		Required
	Cable entry		Bottom of the panel with a removable bolted un-drilled gland plate.
	Protection (as per IS/IEC 60947)		IP: 4X or better for LV VFD
	Enclosure Design Criteria		Shall avoid harmonic and inductive heating effects and to shield any outside equipment from interference, to eliminate any radio frequency interference
	Protection against electromagnetic emissions		To be provided
	Illuminating lamp		Required
	Space heater with switch fuse		Required
	Variable setting thermostat.		Required
	Ventilation using air filters and fans/pumps		Required, to ensure that maximum temperature inside the cubicle is within permissible limits for reliable and continuous operation of the system.
	Terminal block		Separate Terminal block for power and control cable
2.14.15	<b>LT &amp; HT CABLES</b>		Required, suitable for VFD system
2.14.16	<b>CONTROL AND PERFORMANCE REQUIREMENTS</b>		
	Automatic current limiting feature		Required, to control motor currents during startup and provide a "soft start" torque profile for the motor load combination
	Current and torque limit adjustments		Required
	Drive Speed control		Local or Remote mode
	Local / Remote selection provision		from VFD panel
	Parameter Monitoring		<ul style="list-style-type: none"> <li>- Input and output voltage of Drive</li> <li>- Input and output current of Drive</li> <li>- Motor speed</li> <li>- Input and output power frequency of Drive</li> <li>- Torque</li> <li>- Output kWhr of Drive</li> <li>- Ambient temperature</li> <li>- Run/stop and local/remote status displayed</li> </ul>
	Operator console panel features		Front mounted Backlit alphanumeric display A keypad with keys for parameterization and adjusting parameter Facility / port to connect external hardware Upload and download of all parameter settings from one drive to another drive for start up and operation User-friendly licensed software for operation and fault diagnostic
	Protection features		i) Converter transformer: short circuit, over current, earth fault & winding temperature high protection. ii) Incoming and outgoing line surge protection. iii) Under / over voltage protection iv) Phase loss, phase reversal, overload, negative phase sequence, locked rotor protection. v) Instantaneous Over current & Earth fault protection vi) Converter/Inverter module failure indication. vii) Over frequency/speed protection. viii) Ventilation failure indication & alarm. ix) Over temperature of VFD x) Bearing temperature protection. xi) System earth fault protection. xii) Speed reference loss protection.
	Operator Control Panel (on the front panel door)		Start / stop (in local/remote mode) Speed control (Raise / lower) Acknowledge/Accept/ Test Push Button for annunciation Auto / Manual / Test Mode select Emergency stop Trip-Remote Breaker

2.14.17	<b>DIAGNOSTIC FEATURES</b>		Microprocessor/PLC based digital diagnostic system which monitors its own control functions and displays faults and operating conditions.
			Information regarding failure of any of the system including shut down of the system shall be available.
			It shall be possible to retrieve the record of events prior to tripping of the system or de-energization.
			Auxiliary supply to the system components or to the electronics (firmware) for the diagnostics / display shall be taken care of by the manufacturer for this purpose.
2.14.18	<b>SERVICEABILITY / MAINTAINABILITY</b>		
	Power Component Accessibility		All power components in the converter sections shall be designed for rack-out accessibility for ease of maintenance and to minimize repair downtime.
	Marking / Labelling		Sleeve type wire marker tags or other acceptable means of permanent identification shall be applied to power and control wiring. Individual labels shall be provided for all major components of the VFD system.
2.15	<b>Impulse piping for water area/equipment</b>		
	Painting color scheme		Grey RAL 9002
	Identification Tag/band color scheme		Sea green, ISC no. 217
2.16	<b>Impulse piping for oils</b>		
	Painting color scheme		Grey RAL 9002
	Identification Tag/band color scheme		Light Brown, ISC no. 410
2.17	<b>Impulse piping for air</b>		
	Painting color scheme		Grey RAL 9002
	Identification Tag/band color scheme		Sky Blue, ISC no. 101
3.0	<b>INSPECTION/TESTING</b>		
3.1	Type Test requirement		Yes
	Item-1		Electronic Transmitters
	Test & Standard -1		As per Standard, BS-6447 / IEC-60770
	Test to be specifically conducted		No
	NTPC's approval required. on Test certificate		Yes

	<b>TECHNICAL SPECIFICATION</b> <b>MILL REJECT HANDLING SYSTEM</b> <b>2x800MW LARA TPP STAGE II</b>		PE-TS-508-145-HZZZ
			Issue No: 01
			Rev. No. 00
			Date :
<b>TECHNICAL DATA - PART - B (SUPPLIER DATA TO BE FURNISHED AFTER AWARD OF CONTRACT)</b>			
<b>SL.NO</b>	<b>DESCRIPTION</b>	<b>UOM</b>	<b>DETAIL</b>
	<b>FOLLOWING DATA SHALL BE FILLED UP BY VENDOR FOR EACH INSTRUMENT</b>		
1.0	MAKE		
1.1	MODEL		
1.2	TAG NO. / KKS NO.		
1.3	SERVICE		
1.4	QUANTITY		
1.5	OPERATING PRESSURE		
1.6	OPERATING TEMPERATURE		
1.7	DESIGN PRESSURE		
1.8	DESIGN TEMPERATURE		
1.9	RANGE		



TECHNICAL SPECIFICATION  
MILL REJECT HANDLING SYSTEM  
2x800MW LARA TPP STAGE II

PE-TS-508-145-HZZZ  
Issue No. 01  
Rev. No. 00  
Date :

**Note:** This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the Practices and Procedure adopted alongwith relevant supporting documents.

MEASURING INSTRUMENTS

Item Components	Dimensions (R)	Make, Model, Type, Rating (R)	Process / Electrical connection (R)	Calibration (R)	Test as per standard (R)	Insulation Resistance (R)	IBR Certification (As applicable) (R)	Hydro Test (R)	Material Test certificate (R)
Sub System Assembly									
Pressure Gauge (IS-3624)	Y	Y	Y	Y	Y				
Temp. Gauge (BS-5235)	Y	Y	Y	Y	Y				
Pr./D.P. Switch (BS-6134)	Y	Y	Y	Y	Y	Y			
Electronic Transmitter (IEC-60770)		Y	Y	Y	Y	Y	Y		
Temp. Switch	Y	Y	Y	Y	Y	Y			
Electrical Metering Instrument (IS-1248)	Y	Y	Y	Y	Y	Y			
Transducer (IS-14570)	Y	Y	Y	Y	Y	Y			
RTD (IS-2848)	Y	Y	Y	Y	Y	Y			
Thermowell	Y	Y	Y	Y	Y				

R-Routine Test A- Acceptance Test Y – Test applicable

PROCESS CONNECTION AND PIPING

Tests	Visual & Dimensions @	GA, BOM, Layout of component & construction details @	Flattening, flaring, hydro test, hardness check as per IS 1171 standard (A)	Component Ratings @	Wiring @	Make, Model, Type, Rating @	IR & HV @	Review of TC for instrument devices (R)	Accessibility of TBs/Devices Illumination, grounding @	Tubing @	Leak/Hydro test (A)	Chemical/physical	Proof pressure	Tests as per
Items														
Junction Box	Y	Y*		Y		Y	Y							
Impulse pipes and tubes	Y		Y			Y						Y		
Socket weld fittings ANSI B-16.11	Y					Y					Y	Y		Y
Compression fittings	Y					Y					Y	Y	Y	
Instrument valves & Valve manifolds	Y					Y					Y	Y		

\*-applicable for painted junction boxes.

©-Routine Test A-Acceptance Test Y – Test applicable

LOCAL CONTROL PANEL

Tests	Pre Power on Check (R)	Post Power on Check (R)	Internal cabling / Wiring check (R)	Door Alignment, wireless, and	Louvers, Fans, wire mesh, Lifting	HV / IR on wired panels (R)	Paint Shade, Thickness and	Hardware Make as per BOM (R)	Dimensions, GA, layout (R)
Items									
Local Control Panel	Y	Y	Y	Y	Y	Y	Y	Y	Y


R-Routine Test A- Acceptance Test Y – Test applicable

**Note:**

- Pre power on check: - Wire dressing, looseness, Availability of Fuses and MCB, Modules are inserted properly, Earthing connection, Input Voltage checking.
- Manufacturer also needs to include their practices and procedure in MQP along with relevant supporting documents.


VARIABLE FREQUENCY DRIVE

Item Components	Electrical Properties	Mechanical Properties	Chemical Properties	Dimensions / Finish	Type/ Rating/Functional check	HV/IR	Routine test as per relevant std.	Constructional Features	IS-6005 Seven tank process	Paint finish/ shade/thickness			Degree of Protection Test	Final testing as per Relevant IS/IEC
Sub System Assembly														
Sheet Steel (IS-513)		Y	Y	Y										
Aluminum / Copper Bus-bar (IS-5082/IS-613/IS-1987)	Y	Y	Y	Y										
Support Insulator (BS-2782/IEC-660/IS-10912)	Y	Y	Y	Y										
Control / Selector Switch (IS-6875)					Y	Y	Y							
Contactors / MCB (IS-13947)					Y	Y	Y							
OIL Protection relays (IS-3231)					Y	Y	Y							
C.T / V.T / Indicating Meter (IS-2705/3156/1248)					Y	Y	Y							
Fuse/ Fuse carrier (IS-13703)					Y	Y	Y							
Terminals/Jugs/pvc wires (IS-13947/IS-694)	Y			Y	Y	Y	Y							
Timers (IS-3231)					Y	Y	Y							
Push Button / Lamp/ (IS-6875)					Y	Y	Y							
Control Transformer (IS-12021)					Y	Y	Y							
Mimic, Annunciator					Y	Y	Y							
GASKE T (IS-11149)		Y	Y	Y	Y	Y	Y							
Fabrication								Y						
Pretreatment & Painting									Y	Y				
VFD panel										Y	Y	Y	Y	Y

	TECHNICAL SPECIFICATION <PACKAGE NAME> <PROJECT NAME>	PE-TS-XXX-YYY-HZZZ
		Issue No: 01
		Rev. No. 00
		Date :

## PACKING REQUIREMENT


Sl.no	DESCRIPTION
1	<b>Type of Packing:</b>
1.1	Item shall be fully covered with multi layered cross laminated colourless polyethylene sheet of at least 100 GSM and shall be packed inside wooden box or crate or fixed on wooden pallet depending upon the size.
1.2	Item shall be firmly fixed to the bottom of the packing box/crate/pallet with the help of supports/blocks to arrest the movement from all sides. The branch pipe ends and all opening shall be protected with polyethylene blind end caps.
1.3	Loose items/accessories like nipples, expander/reducer, root valves etc. shall be separately packed with polyethylene sheet of at least 100 GSM inside the packing box/crate.
2	<b>Quality of wood:</b>
2.1	<b>Quality of wood:</b> Wood used for packing box shall be Pinewood, Rubber wood, Mango wood, Fir wood, Silver Oak wood or other as per availability with moisture content not exceeding 30%.
3	<b>Cushioning material and moisture absorber:</b>
3.1	Suitable cushioning shall be provided by rubberized coir/ thermocol / expanded soft polyethylene foam.
3.2	Adequate quantity of packed desiccant shall be suitably placed inside the packing box.
4	<b>Packing slip &amp; holder:</b>
4.1	Packing slip kept in polyethylene bag shall be placed inside the wooden box at appropriate place.
4.2	One copy of packing slip wrapped in polyethylene bag covered in galvanized iron tin sheet/ aluminium packing slip holder shall be fixed on the external surface the packing box.

	<b>TECHNICAL SPECIFICATION</b> <b>MILL REJECT HANDLING SYSTEM</b> <b>2x800MW LARA TPP STAGE II</b>	PE-TS-508-YYY-HZZZ
		Issue No. 01
		Rev. No. 00
		Date :


### DOCUMENTATION REQUIREMENT

<b>DRAWINGS &amp; DOCUMENTS TO BE SUBMITTED BY SUCCESSFUL BIDDER AFTER AWARD OF CONTRACT ALONG WITH SUBMISSION SCHEDULE</b>		
<b>Sl. No.</b>	<b>DOCUMENT TITLE</b>	<b>SUBMISSION SCHEDULE</b>
1	TECHNICAL DATASHEETS OF TRANSMITTERS,LOCAL INSTRUMENTS, MOV ETC.	
2	IO LIST	
3	INSTRUMENT SCHEDULE	
4	CONTROL & OPERATIONAL WRITE-UP FOR THE SYSTEM WITH SET POINTS	
5	CABLE SCHEDULE (IN EXCEL FORMAT)	
6	CABLE INTERCONNECTION	
7	WIRING DIAGRAM	
8	HMI PICTURES/PLANT SCHEMATICS	
9	ANNUNCIATION & SOE LIST	
10	INSTRUMENTS INSTALLATION DIAGRAM	
11	QUALITY PLAN DULY SIGNED & STAMPED FOR APPLICABLE ITEMS	
12	CALIBRATION CERTIFICATES	


<b>DRAWINGS &amp; DOCUMENTS TO BE SUBMITTED AS FINAL/AS-BUILT DOCUMENT</b>	
<b>Sl. No.</b>	<b>DOCUMENT TITLE</b>
1	APPROVED DOCUMENTS
2	CALIBRATION CERTIFICATES
3	O&M MANUAL
4	ALL TEST CERTIFICATES


	TECHNICAL SPECIFICATION <PACKAGE NAME> <PROJECT NAME>	PE-TS-XXX-YYY-HZZZ
		Issue No. 01
		Rev. No. 00
		Date :


## SUB VENDOR LIST


 एक महारत्न कम्पनी		PROJECT : Talcher-III ( 2X660MW)					LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES									DATE :04.02.2022	
		CONTRACTOR:										
		CONTRACT NO :										
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark	
		I				Honeywell Automation India Ltd	Pune	A				
		I				GE	France	A				
		I				SIEMENS	Gurugram	A				
		I				BHEL	Bengaluru	A			For MAX DNA System	
		I				Yokogawa	Bengaluru	A				
		I				GE Power India Ltd	Noida	A				
		I				Toshiba	Japan	A				
		I				ABB	Bengaluru	A				
		I				Emerson Process Management Ltd	Pawane	A				
11	Dust Emission Monitor											
		III				Durag India Instrumentation Pvt Ltd	Bengaluru	A			1. For Durag Germany Make Extractive Type Dust density analyser 2. Other components shall be as per approval letter CQA/NTPC BARH-STPP-I / D-263 / Durag India Instrumentation Pvt Ltd Bengaluru Dated 28.08.2019	
		III				Sick India Pvt Ltd	Mumbai	A			1.For SICK AG Make Extractive Type Dust density analyser 2. Other components shall be as per approval letter CQA/NTPC BARH-I /S-907/M/S SICK India Pvt Ltd dated 28.08.2019	
		III				Environment SA India Pvt Ltd	Navi Mumbai	A			1.For ENEVA UK Make Extractive Type Dust density analyser 2. Other components shall be as per approval letter No.: CQA/NTPC BARH-I / E-335 / M/S Environment SA India Pvt Ltd Dated 16.09.2019	
		III				Land Instruments International	UK	A			For In Situ type /Optical Transreceiver type	
		III				Codel	UK	A			For In Situ type /Optical Transreceiver type	
		III				Durag Industrie Elektronik GmbH & Co KG	Germany	A			For In Situ type /Optical Transreceiver type & Extractive Type	
		III				Emerson Process Management	Ireland	A			For In Situ type /Optical Transreceiver type	
		III				SICK AG	Germany	A			For In Situ type /Optical Transreceiver type & Extractive Type	
		III				ENEVA	UK	A			For Extractive Type Dust density analyser	
12	Electrical Actuators											
12-A	Electrical Actuator (With gear box if applicable )											
		II				Antrieb Technik Pvt Ltd	Chennai	A			For low torque applications only	
		II				Auma	Bengaluru	A				
		II				Limitorque	Faridabad	A			Model no L120,SMB,LY series, Gear Box T, HBC Series	
		II				Rotork	Bengaluru	A			For low torque app (Up to 1000 Nm )	
		II				Rotork Controls (India) Private Ltd	Chennai	A			For low torque app (Up to 1000 Nm ) & High torque 4000 to 7000 Nm With integral starter for non critical applications	





 एन टी पी सी एक महारत्न कंपनी		PROJECT : Talcher-III ( 2X660MW)					LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES									DATE :04.02.2022	
		CONTRACTOR:										
		CONTRACT NO :										
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval_Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark	
		III				Auma	Germany	A				
		III				Limitorque	USA	A				
		III				Rotork	UK	A			For low torque app (Up to 1000 Nm)	
		III				Nippon gear	Japan	A				
		III				Drehmo GMBH	Germany	A			C Matic Series (DMC/DMCR)	
12-B	Electrical Actuator- Non-Intrusive (With gear box if applicable )											
		I				Auma India Pvt Ltd	Bengaluru	A			Also acceptable for Field Bus based applicable	
		III				Flowserve	USA	A			Also acceptable for Field Bus based applicable	
		III				Bernard Controls	France	A				
12-C	Electrical actuator for ID/FD/PA Blade pitch ,JGV &SCOOP											
		III				Harold Beck & Sons Inc	USA	A				
		III				SIPOS Aktronik GmbH	Germany	A				
13	Electronics Transmitter (Pressure , DP and DP based Flow/Level )											
13-A	Electronics Transmitter (Pressure , DP and DP based Flow/Level )											
		III				ABB Ltd	Bengaluru	A			2600T & critical item from ABB Italy/ Their approved source;	
		III				Emerson Process Management Ltd	Pawane	A				
		III				Siemens Ltd	Thane	A			Model:-SITRANS P	
		III				Honeywell Automation India Ltd	Pune	A				
		III				Baldota Control and Equipment Pvt Ltd	Navi Mumbai	A			PT & DPT of LD 301 Series (SMAR)	
		III				Yokogawa India Limited	Bengaluru	A			EJA-E 110,430,530 SERIES & all raw material and BOI under knocked down condotion ( sensor assembly as a single unit) shall be sourced from M/S Yokogawa Japan	
		III				M/s Endress + Hauser India Automation Instrument Pvt Ltd	Aurangabad	A				
		III				Emerson (Rosemount)	USA	A				
		III				Yokogawa	Japan	A				
		III				ABB	Germany / Italy	A			2600T & critical item from ABB Italy/ Their approved source;	
		III				Siemens	France	A			Sitrans P DSIII Series	
		III				Fuji Electric	France	A			FCX -AIII SERIES	
		III				Fuji	Japan	A				
13-B	Electronics Transmitter -Field Bus Based (Pressure , DP and DP based Flow/Level )											
		I				ABB India Ltd	Bengaluru	A			One no of Transmitter will be sent at DDCMIS supplier for function testing of field bus communication with DDCMIS during FAT	
14	EQMS											


 एन टी पी सी NTPC		PROJECT : Talcher-III ( 2X660MW)					LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES									DATE :04.02.2022	
		CONTRACTOR:										
		CONTRACT NO :										
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval_Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark	
		III				Durag GmbH	Germany	A			D-VTA-201	
		III				Lenox	USA	A				
		III				Mirion	UK	A				
		III				Piper GmbH	Germany	A				
		III				Sabota GmbH	Germany	A				
25	H2 Gas Analyser											
		I				ABB India Ltd	Bengaluru	A			M/s ABB Germany /UK Make analyser	
		I				Adage Automation Pvt. Ltd	Goa	A			1.M/s Siemens, Garmany (Calomat 6) Make analyser 2. Pl refer Note-07	
		I				Yokogawa India ltd	Bengaluru	A			M/s Yokogawa Japan (Gas Densitybased ) Make analyser	
		I				SIEMENS	Gurugram	A			M/s Siemens, Garmany (Calomat 6) Make analyser	
		III				GE Sensing EMEA	Ireland	A			Conductivity based	
		III				ABB	UK	A				
		III				Emerson (Rosemount)	USA	A				
		III				Environment One Corporation	USA	A			Conductivity based	
26	HEA ignitor											
		I				Durag India Instrumentation Pvt Ltd	Bengaluru	A			M/S Durag Germany make HEA Ignitor	
		I				Hindustan Thermometers	Ambala	A			Conditional as per approval ref no 01/CQA/0270-102 dated 17.09.2012.Spark tip of their own make is also acceptable	
		I				Fives combustion System Pvt Ltd	Vadodara	A				
		I				Boiler control Pvt Ltd	Puddukottai (Tamilnadu)	A			Approved for Aux Boiler package only	
		III				Unison Industries	USA	A				
		III				Durag GmbH	Germany	A				
		III				Ignition system INC	USA	A				
		III				Tesi SPA	Italy	A				
27	High Temp. cable (PTFE/FEP)											
		II				Thermocables	Hyderabad	A				
		II				Tempsens	Udaipur	A				
		II				Habia cables	Sweden	A				
		II				Thermo Electrica BV	Netherland	A				
		II				Lapp cables	Germany	A				
		II				Kerpen cables	Germany	A				
		II				TEW & C	USA	A				
28	Impulse Pipes/Tubes											
		II				Mahrashtra Seamless	Raigarh	A			For CS Pipes only	
		II				Ratnamani Metals and Tubes	Gandhinagar	A			For SS only.	
		II				Heavy Metals and Tubes	Gandhinagar	A			For SS & CS only.	
		II				ISMT	Ahamadnagar	A			For CS/ AS upto Gr 22 Pipes only	
		II				Nippon Steel & Sumitomo Metals corporation	Japan	A				
		II				TPS Tecnitube	Germany	A				
		II				Veluric & Manessmann	Germany	A				
		II				Trouvay and Cauvin	France	A				
		II				Sandvik	Sweden	A			For SS only	
29	Instrument Cables ( F.G & T/C Cables )											


 एनटीपीसी एक महारत्न कंपनी		PROJECT : Talcher-III ( 2X660MW)					LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES									DATE :04.02.2022	
		CONTRACTOR:										
		CONTRACT NO :										
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval_Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark	
		Note-2				Goyolene Fibers ( India) Pvt Ltd	Silvassa	A			F&G Type Cable	
		Note-2				Temsens Instruments Ind Pvt Ltd	Udaipur	A				
		Note-2				Havells India	Alwar	A			F Type Cable	
		Note-2				Paramount Communication Ltd	Khuskhera	A				
		Note-2				Polycab	Daman	A				
		Note-2				Delton	Faridabad	A				
		Note-2				KEI	Bhiwadi (Raj)	A				
		Note-2				Elkey Telelinks	Faridabad	A				
		Note-2				CORDS	Kaharani	A				
		Note-2				CORDS	Bhiwadi	A				
		Note-2				Nicco	Kolkata	A				
		Note-2				Universal Cable	Satna	A				
		Note-2				Thermocables	Hyderabad /Mahboobnagar	A				
		Note-2				Gupta Power Infrastructure Ltd.	Khurdha	A				
		Note-2				CMI	Faridabad	A				
		Note-2				Advance Cables Pvt Ltd	Bengaluru	A			F&G Type Cable	
		Note-2				Gemscab Industries Ltd	Bhiwadi (Raj)	A			F&G Type Cable	
		Note-2				Apar Industries Limited	Valsad	A			F&G Type Cable	
		Note-2				Suyog Electricals Ltd	Halol (Gujrat)	A				
		Note-2				Special Cables Pvt Ltd	Rudrapur	A				
		Note-2				T C Communication	Ghaziabad	A				
		Note-2				TEW & C	USA	A				
		Note-2				Habia cables	Sweden	A				
		Note-2				Kerpen cables	Germany	A				
		Note-2				Lapp cables	Germany	A				
		Note-2				Thermo elecrt a Bv	Netherland	A				
30	Intelligent Battery charger 24V DC / DCDB/BHMS											
		II				Chabbi Electricals	Jalgaon	A			Rectifier module, Controller module and Battery Health monitoring system shall be of M/s Vertiv make	
		II				Eltek SGS Pvt Ltd	Gurugram	A				
31	Large Video Screen (LED Based)											
		I				Pyrotech Electronics Pvt Ltd	Udaipur	A				
		I				Delta India Electronics Pvt Ltd	Gurugram	A				
		I				Barco Electronics system (P) Ltd	Noida	A				
		I				Planner System Inc	USA	A				
32	Level switch- Conductivity type											
		II				Raman Instruments ( System integrator of Delta Morbey/ Emerson Mobrey /Solartron -Mobrey)	Delhi	A			1.M/S Emerson (Morbey) UK system 2.PI refer Note-07	
		II				HI Tech System & services Ltd ( System Integrator of Levelstate systems Ltd ,UK )	Kolkata	A			1. M/S Leveckstate UK System .Vessel from M/s Hi Tech 2.PI refer Note-07	
		II				BHEL	Trichurapalli	A				
		III				Emerson -Mobrey (Solartron mobrey)	UK	A				
		III				Levelstate Svstems Ltd	UK	A				

 एन टी पी सी एक महारत्न कंपनी		PROJECT : Talcher-III ( 2X660MW)					LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES									DATE :04.02.2022	
		CONTRACTOR:										
		CONTRACT NO :										
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval_Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark	
		III				Yarway	USA	A				
33	Local Instrument Enclosure/Rack											
		I				Pyrotech Electronics Pvt. Ltd	Udaipur	A			BOI from LOA approved sources	
		I				Sajas electrical	Trichurapalli (Tamilnadu)	A			BOI from LOA approved sources	
		I				Prammen	Puddukottai (Tamilnadu)	A			BOI from LOA approved sources	
		I				Chemin C&I Pvt Limited	Puducherry	A			1- BOI from LOA approved sources 2.Fabrication at M/s LUFT tech India 3- Painting at M/s Supream Coater & Fabricator	
34	Master Slave Clock System											
		I				Signals and Systems Pvt. Ltd. (SANDS )	Chennai	A				
		I				Masibus	Gandhinagar	A				
		I				Sertel Electronics Pvt. Ltd.	Chennai	A				
		II				Hopf Elektronik GmbH	Germany	A				
		II				Hathway	USA	A				
		II				Mein Berg	Germany	A				
		II				Moser Baer AG	Switzerland	A				
35	Mercury Analyser											
		I				Analyser Instrument Co. Pvt Ltd (AIC)	Kota	A			1. Mercury Analyzer from PS Analytical UK 2.System integration & supply of components like, Enclosure with AC, calibration cylinders, PC will be done by M/s Analyser Instrument Co. Pvt Ltd (AIC) Kota . 3.Pl refer Note-07	
		III				Environment SA India Pvt Ltd	Navi Mumbai	A			1-Mercury analyzer with accessories will be from Mercury instruments GmbH Germany . 2- Other components like, sample line between probe to mercury analyzer will be supplied by M/s Environment SA India Pvt Ltd .	
		III				Thermo Fisher Scientific India Pvt Ltd	Pune	A			1. Mercury Analyser shall be from Thermofisher USA 2. Other approval conditions are as per approved letter ref no 01/CQA/9578-001/Thermofisher dated 09/12/2016	
		III				Durag India Instrumentation Pvt Ltd	Bengaluru	A			Analyser from M/s Verewa Umwelt Germany	
		III				Mercury Instruments GmbH	Germany	A				
		III				SICK AG	Germany	A				
		III				Themofisher	USA	A				
36	PA System (IP Based)											
		III				BNA Technology Consulting Ltd.	Bengaluru	A			BOI shall be from LOA approved sources.	
		III				Armtel	Russia	A				
		III				Zenitel	Norway	A			1.PA system active component , Proprietary item will be Zenitel Norway make 2.Other components & BOI shall be from LOA approved sources	


 एन टी पी सी एक महारत्न कंपनी		PROJECT : Talcher-III ( 2X660MW)					LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES									DATE :04.02.2022	
		CONTRACTOR:										
		CONTRACT NO :										
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval_Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark	
		I				Adaptive Engineering Private Limited	Ahmedabad	A			For M/s Schneider make system	
		I				Greenwave Solutions Private Limited	Kolkata	A			For M/s Rockwell make system	
		I				Dreamz Automation	Ghaziabad	A			For M/s SIEMENS make system	
		I				Creative Robotics	Ghaziabad	A			For M/s Honeywell make system	
		I				Kruti Techno Engineer Pvt Ltd	Chhapraula (GB Nagar	A			For M/s SIEMENS make system	
		I				EDS Instruments & Systems Pvt Ltd	Chennai	A			For M/s Honeywell make system	
		I				Delsys Automation Technologies Pvt Ltd	Chennai	A			For M/s Emerson make system	
		I				Hindustan Controls and Equipment Ltd	Kolkata	A			For M/s Emerson make system	
		I				Vollkraft Engineering And Consultant (P) Ltd	Kolkata	A			For M/s Emerson make system	
		I				SSM Infotech Solutions Pvt Ltd	Surat	A			For M/s Schneider make system	
		I				Sun Industrial Automation & Solutions	CHENNAI	A			For M/s Schneider make system	
38	Pneumatic Actuator Regulating (Power Cylinder HAD,CAD SADC & Burner Tilt )											
		I				Instrumentation Limited	Palakkad (Kerala)	A				
		I				Kelton	Cochin (Alleppy)	A				
		I				SMC Corporation India Private Ltd	Noida	A			Up to Bore size 12 inches	
		I				IMI Norgren Herion Pvt Ltd	Noida	A				
		II				Dong Woo Valve Control Co. Ltd	S.Korea	A				
		II				Shin Hwa Engineering Co. Ltd	S.Korea	A				
39	Radar type level transmitter											
		III				Limaco	Russia	A			High Frequency Type	
		III				Emerson Process Management Ltd	Pawane	A			For M/s Emerson Singapore make	
		III				Endress & Houser	Aurangabad	A				
		III				SIEMENS	Canada	A				
		III				B M Technology	Italy	A			For Non Contact type	
		III				Magnetrol	Belgium	A				
		III				ABB	USA	A			K-Tech Brand	
		III				Endress & Houser	Germany	A				
		III				Saab Rosemeount	Sweden	A				
		III				Emerson Process Management	Singapore	A			Rosemount 3300 series for GW Radar & 5600 Series for Non-Contact type	
		III				Endress & Houser	Germany	A				
		III				Vega Grieshaber KG	Germany	A				
40	Short Term Fire Proof cable											
		III				nVent Solutions limited	UK	A				
		III				Wrexham Mineral	UK	A				
		III				KME	Italy	A				


		<b>PROJECT : Talcher-III ( 2X660MW)</b> <b>PACKAGE : EPC PACKAGES</b> <b>CONTRACTOR:</b> <b>CONTRACT NO :</b>					<b>LIST OF C&amp;I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL</b>				<b>REVISION NO : 00</b> <b>DATE :04.02.2022</b>
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval_Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark
41	SWAS (Sampling Handling System and Dry Panel)										
		I				Emerson Process Management Ltd	Navi Mumbai	A			Analysers and Other BOI Componets from LOA agreed source
		I				Forbes Marshall	Pune	A			Analysers and Other BOI Componets from LOA agreed source
		I				SEPL	Pune	A			Analysers and Other BOI Componets from LOA agreed source
42	Water Analyser (Chloride, Conductivity, Dissolved Oxygen,pH, Hydrazine, Concentration , Phosphate, Silica, Seldium,Turbidity, Total Iron, Degassed Cation Conductivity )										
		III				Emerson Process Management Pvt Ltd	Pawane	A			For Conductivity,pH, Dissolved Oxygen, Turbidity
		III				Mettlet Toledo India Pvt Ltd	Vasai	A			For pH Analyser (1. PH analyser from M/S Mettler Toledo GmbH Switzerland 2. Other components like, Housing, Panel mounting kit, Tubing's & easy clean mechanism will be supplied by M/s Mettler Toledo India Pvt Ltd )
		III				Endress Hauser India Pvt. Limited	Mumbai	A			For pH Analyser (1. pH sensor with cable , analyser ,retract & cleaning assembly , electrolyte reservoir ( As applicable) will be supplied from Principals of M/S Endress Hauser India Pvt. Limited. 2. Other components like, Flow through assembly shall be supplied from M/S Endress Hauser India Pvt. Limited approved sources. )
		III				Thermo Fisher Scientific	USA	A			For Chloride,Dissolved Oxygen,Hydrazine
		III				ABB	UK	A			For Chloride,Dissolved Oxygen,Hydrazine, Phosphate, Silica,Sodium,Turbidity
		III				Hach	USA	A			For Conductivity, pH,Concentration, Phosphate, Silica,Turbidity
		III				ABB	USA	A			For Conductivity, pH
		III				Yokogawa	Japan	A			For Conductivity
		III				Hach	Switzerland	A			For Dissolved oxygen, Hydrazine, Silica,Sodium
		III				Yokogawa	Japan	A			For pH
		III				Eutech Instrument PTE Ltd	Singapore	A			For Silica
		III				Orion	USA	A			For Sodium
43	Temp Transmitter										
43-A	Temp Transmitter										
		III				Endress & Houser	Aurangabad	A			
		III				Emerson Process Management Ltd	Pawane	A			For M/s Emerson Singapore make
		III				Yokogawa	Bengaluru	A			Make Yokogawa japan and calibration at Yokogawa Banglore


 एन टी पी सी एक महारत्न कम्पनी		PROJECT : Talcher-III ( 2X660MW)					LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES									DATE :04.02.2022	
		CONTRACTOR:										
		CONTRACT NO :										
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval_Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark	
		III				ABB	Bengaluru	A			For M/s ABB Germany make	
		III				WIKA Instruments India Pvt Ltd	Pune	A			For M/s WIKA Germany make Model no T-32	
		III				Honeywell Automation India Ltd	Pune	A				
		III				Yokogawa	Japan	A				
		III				Moore	USA	A				
		III				M System co Ltd	Japan	A			Model No-B3HU-0	
		III				Emerson	U.S.A/Singapore/Germany	A				
		III				ABB	Germany	A				
		III				Emerson Process Management	Germany	A				
43-B	Temp Transmitter -Field Bus based Single/Dual Input											
		I				ABB India Ltd	Bengaluru	A			One no of TT will be available at DCS supplier for function testing of field bus communication with DCS during FAT	
44	Turbine supervisory Instruments along with vibration analysis system.											
		I				GE	Pune	A			For GE Bently ,USA make system	
		I				Meggitt India Pvt Ltd	Bengaluru	A			For Meggitt (Vibrometer) Switzerland make system	
		I				Forbes Marshall	Pune	A			For Shinkawa ,Japan make system	
		II				GE BENTLY	USA	A				
		II				SHINKAWA	JAPAN	A				
		II				MEGGITT	Switzerland	A				
45	Ultrasonic Type Flow Meter (for Stack)											
		III				Sick India Pvt ltd	Mumbai	A			For Sick AG Germany make	
		III				Sick AG	Germany	A				
		III				Durag	Germany	A				
		III				Teledyne	USA	A				
46	Ultrasonic type level Transmitter											
		III				EIP Enviro	Noida	A			1-Ultrasonic level Tx shall be BM Technology Italy make 2-Required mounting arrangement , Testing, Calibration shall be carried out at M/s EIP Works.	
		III				E & H	Aurangabad	A				
		III				Emerson Process Management Ltd	Pawane	A			Complete Intrument Transmitter & Probe to be procured from Mobrey UK , only intergration & configuration at Pawane works	
		III				BM Technology	Italy	A				
		III				Siemens Miltronics	Canada	A				
		III				Nivelco Process Control	Hungary	A				
		III				E & H	Germany	A				
		III				HAWK Measurement PTY Ltd	Australia	A				
47	UPS With ACDB											
		Note-5				Vertive Energy Pvt Ltd	Pune	A			Upto 125 KVA for 1 phase and 300 KVA for 3 Phase	
		Note-5				Vertive Energy Pvt Ltd	Mumbai	A			Upto 160 KVA	
		Note-5				Hitachi Hirel Power Electronics Pvt Ltd	Gandhinagar	A			Upto 160 KVA,	


 एन टी सी एक महारत्न कम्पनी		PROJECT : Talcher-III ( 2X660MW)					LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES									DATE :04.02.2022	
		CONTRACTOR:										
		CONTRACT NO :										
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark	
50	Field Bus Cable/ Profibus Cable- PA & DP type											
		I				LAPP India Pvt Ltd	Bangalore	A				
51	Field bus components ( Field bus modules ,segment protector ,surge protector & SS JB )											
		III				Phoenix Contact Inc	USA	A			Materiall will be allowed to dispatch from the vendor works as CAT-III item ,however all material except SS junction box will be available at DDCMIS supplier works for functional testing .	
		III				Pepperl + Fuchs Pte Ltd	Singapore	A			Materiall will be allowed to dispatch from the vendor works as CAT-III item ,however all material will be available at DDCMIS supplier works for functional testing .	
52	Stockyard Management System( Including 3D profiling scanner ,Thermal Imaging Camera, RTK GPS)											
		III				TSA	Brazil	A			For 3D profiling / Tripple-IN Germany make	
		I				EIP Enviro	Noida	A			For 3D profiling / 1-Tripple-IN Germany make Laser Scanner and RPU along with software from TSA Brazil inline with the M/s TSA Letter. 2- Other item like ethernet cable, Ethernet Switch, Junction Box required for execution of 3D stockpile managemmmnt system can be supplied by EIP Enviro	
53	Perimeter Intrusion Detection System											
		III				Senstar	Canada	A				
54	Radar based Perimeter Surveillance System											
		III				Magos System Ltd	Israel	A			Third Party “Cyber Penetration report “ shall be provided along with material TC/COC	
55	Thermal Camera ( PTZ)											
		III				FLIR Commercial Systems INC	USA	A				
Main Contractor approved sources (Note-12)												
MC-1	Amonia Analyser	III				Main Contractor Approved Sources						
MC-2	Amonia leak detector	III				Main Contractor Approved Sources						
MC-3	Air Filter Regulator	III				Main Contractor Approved Sources						
MC-4	Anemometer	III				Main Contractor Approved Sources						
MC-5	Annunciator	III				Main Contractor Approved Sources						
MC-6	Battery Health Monitoring System	III				Main Contractor Approved Sources						
MC-7	Biofouling/ Deposit Monitor	III				Main Contractor Approved Sources						
MC-8	Coal bunker Level monitor	III				Main Contractor Approved Sources						
MC-9	Compression Fittings(SS)	III				Main Contractor Approved Sources						
MC-10	Condensing Pots	III				Main Contractor Approved Sources						
MC-11	Conduits /Pipe (GI)	III				Main Contractor Approved Sources						
MC-12	Conduits lead coated ( Flexible )	III				Main Contractor Approved Sources						



 एक महारत्न कंपनी		PROJECT : Talcher-III ( 2X660MW)					LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES									DATE :04.02.2022	
		CONTRACTOR:										
		CONTRACT NO :										
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval_Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark	
MC-13	Copper tubing/Brass connectors	III				Main Contractor Approved Sources						
MC-14	Coriolios Type Mass Flow meter	III				Main Contractor Approved Sources						
MC-15	Coupling /Interposing Relays	III				Main Contractor Approved Sources						
MC-16	Density Indicator	III				Main Contractor Approved Sources						
MC-17	Desk for OWS/EWS/Printer/Server	III				Main Contractor Approved Sources						
MC-18	Digital Indicators	III				Main Contractor Approved Sources						
MC-19	Dust Sensor	III				Main Contractor Approved Sources						
MC-20	Dew point sensor/meter (H2)	III				Main Contractor Approved Sources						
MC-21	Flow Gauge	III				Main Contractor Approved Sources						
MC-22	Flow Indicator cum Totaliser	III				Main Contractor Approved Sources						
MC-23	Flow Switch	III				Main Contractor Approved Sources						
MC-24	FRP Junction Box	III				Main Contractor Approved Sources						
MC-25	Furniture for control Room( Chair, Almira, Lock)	III				Main Contractor Approved Sources						
MC-26	Furnace exit gas temp probe	III				Main Contractor Approved Sources						
MC-27	Graphic Interface Unit	III				Main Contractor Approved Sources						
MC-28	Hand Held Calibrator	III				Main Contractor Approved Sources						
MC-29	Hart Management System	III				Main Contractor Approved Sources						
MC-30	Humidistat / Thermostat / Gyserstat / Airstat	III				Main Contractor Approved Sources						
MC-31	Instant Corrosion Rate Monitor & Portable Corrosion Meter	III				Main Contractor Approved Sources						
MC-32	Impact head type flow element	III				Main Contractor Approved Sources						
MC-33	Instrument Tube Fittings (Air)	III				Main Contractor Approved Sources						
MC-34	Instrument Valve	III				Main Contractor Approved Sources						
MC-35	IR Detector	III				Main Contractor Approved Sources						
MC-36	KVM Switch/Matrix KVM Switch	III				Main Contractor Approved Sources						
MC-37	Level gauge (Transperent & Reflex, Tubular type)	III				Main Contractor Approved Sources						
MC-38	Level Indicator (Float & Board type)	III				Main Contractor Approved Sources						
MC-39	Level switch - Float/Displacer Type	III				Main Contractor Approved Sources						
MC-40	Level Switch (RF Type)	III				Main Contractor Approved Sources						
MC-41	Level switch capacitance type	III				Main Contractor Approved Sources						
MC-42	Limit Switch	III				Main Contractor Approved Sources						
MC-43	Maintenance and Calibration Equipment	III				Main Contractor Approved Sources						
MC-44	Mini UPS-Type C configuration	III				Main Contractor Approved Sources						
MC-45	Orifice plate assembly	III				Main Contractor Approved Sources						
MC-46	On line carbon in Ash analyser	III				Main Contractor Approved Sources						
MC-47	Pitot Tube	III				Main Contractor Approved Sources						
MC-48	Pr./Vaccum./DP Gauges	III				Main Contractor Approved Sources						
MC-49	Press, DP, Vacuum Switch	III				Main Contractor Approved Sources						
MC-50	Printer (Dot Matrix/Inkjet / Laser)	III				Main Contractor Approved Sources						
MC-51	Psychrometer	III				Main Contractor Approved Sources						
MC-52	Pulse jet Controller	III				Main Contractor Approved Sources						
MC-53	Pulse Valve	III				Main Contractor Approved Sources						
MC-54	Residual Chlorine Analyser	III				Main Contractor Approved Sources						
MC-55	Rotameter	III				Main Contractor Approved Sources						
MC-56	Reverse Rotation Indicator	III				Main Contractor Approved Sources						
MC-57	Synchronising Relay	III				Main Contractor Approved Sources						
MC-58	Synchroscope	III				Main Contractor Approved Sources						
MC-59	Semaphore Indicators	III				Main Contractor Approved Sources						
MC-60	Sight Flow Indicator	III				Main Contractor Approved Sources						
MC-61	Smart Positioner	III				Main Contractor Approved Sources						
MC-62	Socket Weld Fittings	III				Main Contractor Approved Sources						
MC-63	Solenoid Valve	III				Main Contractor Approved Sources						


 एन टी पी सी एक महारत्न कम्पनी		PROJECT : Talcher-III ( 2X660MW)					LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES									DATE :04.02.2022	
		CONTRACTOR:										
		CONTRACT NO :										
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark	
MC-64	Solid Mass Flow Meter	III				Main Contractor Approved Sources						
MC-65	Terminal Block (Cage and Clamp type)	III				Main Contractor Approved Sources						
MC-66	Temperature cum Humidity Indicator	III				Main Contractor Approved Sources						
MC-67	Temperature Element(Thermocouple , RTD & Thermowell)	III				Main Contractor Approved Sources						
MC-68	Temperature Gauge( With Thermowell)	III				Main Contractor Approved Sources						
MC-69	Temperature Switch	III				Main Contractor Approved Sources						
MC-70	Transducer	III				Main Contractor Approved Sources						
MC-71	Tube thicknes Meter	III				Main Contractor Approved Sources						
MC-72	Voltmeter/ Watterhour Meter	III				Main Contractor Approved Sources						
MC-73	Valve manifolds	III				Main Contractor Approved Sources						
MC-74	Electric to Pneumatic Converter	III				Main Contractor Approved Sources						
MC-75	Network components	III				Main Contractor Approved Sources						
MC-76	Isolator	III				Main Contractor Approved Sources						
MC-77	ORP Monitor /Analyser	III				Main Contractor Approved Sources						
MC-78	Ultrasonic Type Flow Transmitter	III				Main Contractor Approved Sources						
MC-79	Chlorine Leak detector	III				Main Contractor Approved Sources						
MC-80	Density Meter	III				Main Contractor Approved Sources						
MC-81	Electro Magenetic Flow meter	III				Main Contractor Approved Sources						
MC-82	Postive dispalcement Type Flow Meter	III				Main Contractor Approved Sources						
MC-83	Level Scanner (3 D)for Solid Application	III				Main Contractor Approved Sources						
MC-84	Mosaic tiles /Console items	III				Main Contractor Approved Sources						
MC-85	Electrical Control Panel ( UCP/Backup)	III				Main Contractor Approved Sources						
MC-86	Electrical Indicating Instruments (Mosaic Compatible)	III				Main Contractor Approved Sources						
MC-87	OWS/EWS/Server	III				Main Contractor Approved Sources						
MC-88	Bio Matrix Reader	III				Main Contractor Approved Sources						
MC-89	ANPR	III				Main Contractor Approved Sources						
MC-90	UVSS	III				Main Contractor Approved Sources						
MC-91	Comd & Control System	III				Main Contractor Approved Sources						
MC-92	Access & Controller Software	III				Main Contractor Approved Sources						
MC-93	IR LED based Illuminator	III				Main Contractor Approved Sources						
MC-94	ATB Bolloard	III				Main Contractor Approved Sources						
MC-95	Boom Barrier	III				Main Contractor Approved Sources						
MC-96	Touchless biometric recorder	III				Main Contractor Approved Sources						
MC-97	GPS Sensor based Vehicle Monitoring system	III				Main Contractor Approved Sources						
MC-98	10mp digital camera with tripod for photo capture	III				Main Contractor Approved Sources						
MC-99	2D GIS map application	III				Main Contractor Approved Sources						
MC-100	Audible alarm device	III				Main Contractor Approved Sources						
MC-101	CameraPoles	III				Main Contractor Approved Sources						
MC-102	Card Reader	III				Main Contractor Approved Sources						
MC-103	Door Frame Metal Detector -DFMD	III				Main Contractor Approved Sources						
MC-104	Door sensor	III				Main Contractor Approved Sources						
MC-105	Egress Switch	III				Main Contractor Approved Sources						
MC-106	EM LOCK	III				Main Contractor Approved Sources						
MC-107	Emergency exit / door override switch	III				Main Contractor Approved Sources						
MC-108	Emergency Siren /Hooter	III				Main Contractor Approved Sources						
MC-109	Flap barrier	III				Main Contractor Approved Sources						
MC-110	Flash Lights for covering perimeter area for clear view from PTZ in night time	III				Main Contractor Approved Sources						
MC-111	Geo fencing	III				Main Contractor Approved Sources						
MC-112	Glass Break switch at Emergency Exit	III				Main Contractor Approved Sources						
MC-113	Guard tour	III				Main Contractor Approved Sources						

 एन टी पी सी एक महारत्न कम्पनी		PROJECT : Talcher-III ( 2X660MW)				LIST OF C&I ITEMS REQUIRING QUALITY PLAN AND SUB SUPPLIER APPROVAL				REVISION NO : 00	
		PACKAGE : EPC PACKAGES								DATE :04.02.2022	
		CONTRACTOR:									
		CONTRACT NO :									
Sr No	Item Description	QP Inspection Category	QP No	QP submission SCH	QP approval SCH	Proposed Sub Supplier	Country	SS Approval Status (Note-1)	SS Detail Sub.SCH	SS Approval SCH	Remark
MC-114	Half Height Turnstile	III				Main Contractor Approved Sources					
MC-115	Handheld Walkie - Talkie	III				Main Contractor Approved Sources					
MC-116	HHMD	III				Main Contractor Approved Sources					
MC-117	Long Range RFID Reader	III				Main Contractor Approved Sources					
MC-118	Monitors 24 Inch Full HD	III				Main Contractor Approved Sources					
MC-119	Network Panel	III				Main Contractor Approved Sources					
MC-120	Optical Time Domain Reflector-meter (OTDR) with all accessories	III				Main Contractor Approved Sources					
MC-121	Panic Button with Audible Alarm	III				Main Contractor Approved Sources					
MC-122	Panic button/SOS button supportin SIP protocol	III				Main Contractor Approved Sources					
MC-123	RFID based Stickers	III				Main Contractor Approved Sources					
MC-124	Sliding Gate	III				Main Contractor Approved Sources					
MC-125	SMS gateway	III				Main Contractor Approved Sources					
MC-126	Storage Device (SAN/NAS/DAS) of 100 TB each	III				Main Contractor Approved Sources					
MC-127	Traffic Light	III				Main Contractor Approved Sources					
MC-128	Turnstile - half height	III				Main Contractor Approved Sources					
MC-129	SPIKE BARRIER	III				Main Contractor Approved Sources					
MC-130	CHAIN LINK FENCE	III				Main Contractor Approved Sources					
MC-131	X-ray Baggage Scanner	III				Main Contractor Approved Sources					
MC-132	Static Radio Set	III				Main Contractor Approved Sources					
LEGENDS :											
1.0 SYSTEM SUPPLIER / SUB SUPPLIER APPROVAL STATUS CATEGORY											
A - For those items proposed vendor is acceptable to Customer. To be indicated with letter "A" in the list alongwith the condition of approval, if any.											
2.0 QP INSPECTION CATEGORY :											
CAT - I : For those items the Quality Plans are approved by Customer and final acceptance will be on physical inspection witness by Customer											
CAT - II : For those items the Quality Plans are approved by Customer. However no physical inspection shall be done by Customer. The final acceptance by Customer shall be on the basis of review of documents.											
CAT - III :For these items Quality control to be exercised as per Main contractor Quality Assurance System. The final acceptance by NTPC shall be on the basis of Certificate of Conformance (COC) by Main Contractor.											
UNITS/WORKS : Place of manufacturing- Place of main supplier of multi units/works.											
NOTE - 1 : A: Vendors to submit project specific documents as per Sub-QR requirements in case the Vendor is approved under collaboration agreement.											
B: In case approved sub vendor is offering product with latest model/series apart from earlier approved, vendors to submit project specific documents as per Sub-QR requirements.											
NOTE - 2 : For Instrument cable <= 1 KM inspection category CAT - III, For > 1 KM to <= 10 KM Inspection category CAT - II COC & FOR> 10 KM Inspection category CAT-I											
NOTE - 3 : For Fiber Optic cable <=10KM inspection category CAT - III & for > 10KM Inspection category CAT-II											
NOTE-4 : Batteries for UPS <= 10 KVA and batteries for intelligent battery charger 24 V DC <= 40 Amp inspection category CAT-III & for Batteries for UPS> 10KVA and batteries for intelligent battery charger 24 V DC > 40 Amp rating											
NOTE-5 UPS <= 10 KVA rating inspection category CAT-III & for > 10KVA rating inspection category CAT-I											
NOTE - 7 - EMPTY CABINETS, COMPUTERS, SIGNAL ISOLATOR/ MULTIPLIER and TB SHALL ALSO BE ACCEPTABLE FROM OWNER ACCEPTED IN QP. IF THE TOTAL INTEGRATED PANEL AND FAT IS CONDUCTED INDEGENEOUSLY											
NOTE-8 : For the C & I instruments mounted on the skid of the main item or supplied as a integral part of the main item, instrument to be supplied as per proven practice of the manufacturer meeting the Customer technical specification											
NOTE-9- This item is a bought out component of main equipments like DDCMIS, PLC, TSL, CCTV, PA system etc											
NOTE-10- For these controlled items, vendor shall be proposed for owner acceptance with-in the agreed contract schedule of the package											
NOTE-11 - Major Bought-Out-Items are to be procured from LOA approved sources & the same shall be finalized during the finalization of Manufacturing Quality Plan . MQP shall be duly vetted by OEM with their project specific authorisation letter .											
NOTE-12 : Main contractor approved sub vendors are acceptable those are evaluated / assessed as per Main contractor Quality Management System for vendor approval. Main contractor to inform the finally selected vendor to NTPC as soon as PO is placed for these items. In case of sub-QR Note-1 is also applicable.											

	<b>TECHNICAL SPECIFICATION</b> <b>MILL REJECT HANDLING SYSTEM</b> <b>2x800MW LARA TPP STAGE II</b>	PE-TS-508-145-HZZZ
		Issue No. 01
		Rev. No. 00
		Date :

**Please refer attached drawings for this portion**

This document is the property of NATIONAL THERMAL POWER CORPORATION LTD.



4 PAIR, 0.5 mmSq.

SHIELD BUS

SIGNAL GROUND

**एन टी पी सी**  
**NTPC**

( A GOVERNMENT OF INDIA ENTERPRISE )  
ENGINEERING DIVISION

## TYPICAL THERMAL POWER PROJECT

## INTERFACING OF FIELD INSTRUMENTS/ SWGR SWITCH (COC) TERMINATION DETAILS

REV. NO.

DESIGN CHART

M	E	C	C&I	ARCH.
---	---	---	-----	-------

APPROVED	DATE
----------	------

57E

A3

SCALE  
NTS


DEG. NO.
----------

0000-999-POI-A-065

SH 01 OF 14

REV	NO
-----	----

A



\* Bl/Ge/Gr/Wt CORE SHALL BE TERMINATED IN TERMINAL 1 OR 3, 11 OR 13, 21 OR 23 AND 31 OR 33 RESPECTIVELY DEPENDING ON THE PARTICULAR TYPE OF CONTACT (NO OR NC) IS TO BE WIRED TO DDCMIS.

FOR TENDER PURPOSE ONLY


		<b>एन टी पी सी लिमिटेड</b> <b>NTPC LIMITED</b> (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION	
PROJECT		TYPICAL THERMAL POWER PROJECT	
TITLE		INTERFACING OF FIELD INSTRUMENTS SWITCH TERMINATION DETAILS NO/NC	
SIZE	SCALE	DRG. NO.	REV. NO.
A3	NTS	0000-999-POI-A-065	A
		SH 02 OF 14	

REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	M	E	C	C&I	ARCH.	APPD.	DATE
A	FIRST ISSUE										29.04.06

INTERNAL WIRING/2 PAIR,0.5 mmSq.(TYP)

INTEGRAL JB OF LIE/LIR  
(4-20mA)

MARSHALLING/TERMINATION  
CUBICLE




FOR TENDER PURPOSE ONLY

नाटिपीसी लिमिटेड  
**NTPC LIMITED**  
(A GOVERNMENT OF INDIA ENTERPRISE)  
ENGINEERING DIVISION

C	NOTE REGARDING CABLE IS ADDED.										10.12.13	PROJECT	TYPICAL THERMAL POWER PROJECT				REV. NO.
B	INTERNAL WIRING FOR LIE/LIR MOUNTED SHOWN WIRING OF STAND ALONE TXTR SHOWN										10.12.08	TITLE	INTERFACING OF FIELD INSTRUMENTS 4-20mA				
A	FIRST ISSUE										12.1.05						
REV.NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	M	E	C	C&I	ARCH.	APPD	DATE	SIZE	SCALE	DRG. NO.	REV. NO.		
												A3	NTS	0000-999-POI-A-065	c		
CLEARED BY															SH 04 OF 14		



This document is the property of NATIONAL THERMAL POWER CORPORATION LTD.  
No part of this document will be reproduced by any means without the written permission.



- NOTE: 1) ABOVE IS THE TYP. DRG. FOR DIN RAIL MOUNTED TEMP TRANSMITTERS FOR RTD APPLICATION. EXACT TYPE OF TEMP TRANSMITTER SHALL BE AS PER PART-A OF SPECIFICATION.  
2) THE EXACT GROUPING OF TEMP TXs SHALL BE FINALISED DURING DETAILED ENGG. STAGE.

FOR TENDER PURPOSE ONLY

NTPC

**NTPC LIMITED**  
( A GOVERNMENT OF INDIA ENTERPRISE )  
ENGINEERING DIVISION

PROJECT: TYPICAL THERMAL POWER PROJECT

TITLE: INTERFACING OF FIELD INSTRUMENTS  
TYPICAL RTD CONNECTION WITH TEMP TRANSMITTERS INJBs

A	FIRST ISSUE											29.04.01
REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD	M	E	C	C&I	APCH.	APPD	DATE	
					CLEARED BY							


CHECKED BY

SIZE	SCALE	DRG. NO.	REV. NO.
A5	NTS	0000-999-POI-A-065	C

SH 05 OF 14




### Marshalling/ Termination Cubicle POST-A




- 1) \* FEEDBACKS OF SOVs CAN BE GROUPED IN FIELD JB AND MULTI PAIR CABLE IS TO BE USED FROM FIELD JB TO MARSHALLING/TERMINATION CUBICLE FOR FEEDBACKS OF GROUP OF SOVs. TYP ARRANGEMENT IS SHOWN FOR A GROUP OF TWO SOVs WITH OPEN AND CLOSE LIMIT SWITCHES.
- 2) NO. OF LIMIT SWITCHES/NO. OF CONTACT IN LIMIT SWITCHES SHALL BE PROVIDED FOR EACH VALVE AS PER SPEC. REQUIREMENT/ PHILOSOPHY FOR RESPECTIVE SYSTEM.
- 3) \*\* MULTIPAIR CABLE IS TO BE USED FOR CONNECTION OF COMMAND OUTPUTS FROM MARSHALLING/TERMINATION CUBICLE TO RELAY PANEL FOR A GROUP OF SOVs.

### Marshalling/ Termination Cubicle POST-B




		नेशनल थर्मल पावर कॉर्पोरेशन लिमिटेड <b>National Thermal Power Corporation Ltd.</b> (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION	
PROJECT		TYPICAL THERMAL POWER PROJECT	
TITLE		INTERFACING OF FIELD INSTRUMENTS INTERFACE OF DDCMIS WITH MCC/SWGR/ACTUATOR (SINGLE COIL SOLENOID)	
REV. NO.	DESCRIPTION	SIZE	SCALE
B	FIRST ISSUE	A3	NTS
DRAWN		DRG. NO.	
DESIGN		0000-999-FOI-A-065	
CHKD.		REV. NO.	
M		C	
E		C	
C		C	
C&I		C	
ARCH.		C	
APPD		C	
DATE		30.10.02	
CLEARED BY		SH 08 OF 14	

This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission.



**नैशनल थर्मल पावर कॉर्पोरेशन लिमिटेड**  
**National Thermal Power Corporation Ltd.**  
 (A GOVERNMENT OF INDIA ENTERPRISE)  
 ENGINEERING DIVISION

												PROJECT				TYPICAL THERMAL POWER PROJECT																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
																TITLE				INTERFACING OF FIELD INSTRUMENTS INTERFACE OF DDCMIS WITH MCC/SWGR/ACTUATOR (DOUBLE COIL SOLENOID)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
B												FIRST ISSUE				NO. 1				30.10.99																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
REV. NO.												DESCRIPTION				DRAWN				DESIGN				CHKD.				W				E				C				CM				ARCH				APPD				DATE				SIZE				SCALE				DRG. NO.				REV. NO.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			



- NOTE: 1) ABOVE IS THE TYP DRG. FOR DIN RAIL MOUNTED TEMP TRANSMITTER FOR T/C APPLICATION. EXACT TYPE OF TEMP TRANSMITTERS SHALL BE AS PER PART-A OF SPECIFICATION.
- 2) THE EXACT GROUPING OF TEMP TXs SHALL BE FINALISED DURING DETAILED ENGR. STAGE.
- 3) AFTER GROUNDING OF T/C CABLES ON JB, THE CABLE PAIR OF FIRST ELEMENT WILL BE DIRECTLY CONNECTED TO TT AND FOR CABLE PAIR OF SECOND ELEMENT LOOP SHALL BE KEPT, BEFORE TERMINATION AT INPUT "Bn" FOR FUTURE USE.

FOR TENDER PURPOSE ONLY




**NTPC LIMITED**  
( A GOVERNMENT OF INDIA ENTERPRISE )  
ENGINEERING DIVISION

PROJECT: TYPICAL THERMAL POWER PROJECT

TITLE: INTERFACING OF FIELD INSTRUMENTS  
TYPICAL T/C CONNECTION WITH TEMP TXs IN JBs

REVNO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	W	E	C	C&I	ARCH.	APPD	GATE	DATE	SIZE	SCALE	DRG. NO.	REV. NO.
A	FIRST ISSUE											20/04/06	A3	NTS	0000-999-POI-A-065	C

This document is the property of NATIONAL THERMAL POWER CORPORATION LTD.  
No part of this document will be reproduced by any means without the written permission.



# LIST OF MATERIALS

ITEM NO.	DESCRIPTION
1.	1/2" / 3/4" / 1" NPS SCH 40/80/160/XXS/P91 (AS PER PROCESS REQUIREMENT) NIPPLE OF MATERIAL SAME AS THAT OF MAIN PIPE.
2.	1/2"/3/4"/1" SW GLOBE VALVE/GATE VALVE
3.	3/4" / 1" x 1/2" SW REDUCING INSERT
4.	1/2" / 3/4" PIPE
5.	1/2" / 3/4" SW EQUAL TEE
6.	1/2" / 3/4" SW GLOBE VALVE.
7.	1/2" / 3/4" NPS SW x 1/2" / 3/4" NPT(M) CARBON/ALLOY STEEL NIPPLE.
8.	1/2" / 3/4" NPT(F) CAP.
9.	1/2" / 3/4" PIPE UNION.
10.	8" SS SYPHON
11.	1/2" BLIND 300lbs RF ANSI FLANGE DRILLED AND TAPED FOR 1" NPT PIPE.
12.	SUITABLE ADAPTER.
13.	1/4" CHROME MOLY STEEL TUBE.
14.	
15.	1"/3/4" SW EQUAL TEE.
16.	DIAPHRAGM(WAFER ELEMENT)
17.	ISOLATION VALVE 316 SS,1/4"SW

## NOTES:-

1. THE MATERIAL SPECIFICATION AND SCHEDULE NO. OF IMPULSE PIPE & NIPPLE AS LISTED HEREIN SHALL BE AS PER TECHNICAL SPECIFICATIONS.
2. THE MATERIAL SPECIFICATION AND RATING OF FITTINGS AS LISTED SHALL BE AS PER SPECIFICATIONS. WELDED/THREADED FITTINGS SHALL CONFIRM TO ANSI-B.16-11.
3. INSTRUMENTS VALVES BODY STEM MATERIAL AND PRESSURE CLASS SHALL BE AS PER TECHNICAL SPECIFICATIONS.
4. FOR BOILER AIR/FLUE GAS SERVICES SOURCE CONNECTIONS IMPULSE PIPING AND ALL FITTINGS SHALL BE OF 3/4" NB SIZE.
5. GAUGES SHALL NOT BE MOUNTED ON THE PIPE. IT WILL BE MOUNTED ON A CHANNEL OR FRAME OR A RACK.
6. \* SLOPE APPROX. 50 MM / METRE.

FOR TENDER PURPOSE ONLY

एन टी पी सी  
NTPC

**NTPC LIMITED**  
( A GOVERNMENT OF INDIA ENTERPRISE )  
ENGINEERING DIVISION

PROJECT **TYPICAL THERMAL POWER PROJECT**

TITLE **INSTRUMENT INSTALLATION DIAGRAM  
(FOR PRESSURE GAUGE)**

REV.	NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	M	E	C	CAI	ARCH.	APPD	DATE
A	1	FIRST ISSUE										21.08.12
CLEARED BY												

SIZE	SCALE	DRG. NO.	REV. NO.
A3	N.T.S.	0000-999-POI-A-022	A

The diagram illustrates a pressure transmitter system. At the top, a box labeled "PRESS. TRANSMITTER" is connected to a vertical line with five circular components labeled 9, 8, 5, 7, and 5 from top to bottom. A horizontal line from the bottom of this vertical line leads to a component labeled 13, which is connected to a line labeled "SLOPE". This line then leads to a valve (4) and a circular component (1). To the right, another box is connected to a vertical line with components 14, 11, and 20. This line is connected to a component labeled 22, which is also connected to the "BULKHEAD OF LOCAL INSTRUMENT ENCLOSURE/RACK".

(b) ELEVATION

DIRTY AIR/FLUE GAS PRESSURE MEASUREMENT

**DP/PRESS. TRANSMITTER**

**PURGE AIR CONNECTION**

**MIN. 1500 MM**

**VENT**

**BULBHEAD OF LOCAL INSTRUMENT ENCLOSURE/RACK**

**TO INSTRUMENT END**


**FROM PROCESS END**

**2-VALVE MANIFOLD**

**NOTES:-**

1. SEE NOTE
2. IMPULSE I
3. THE SLOP
4. THE EXACT ETC WILL MANUFACT
5. COMMON WILL BE M FOR EACH PURGE RO

TO INSTRUMENT END



FROM PROCESS END

DETAIL OF  
2-VALVE MANIFOLD

ITEM NO.	DESCRIPTION
1.	42 x 405 MM W.S. BLACK PIPE
2.	W42x2 TO 3/4" REDUCING INSERT
3	W42x2(F) W.S.CAP
4.	3/4" SW GLOBE VALVE/GATE VALVE
5.	3/4" NPS PIPE
6.	3/4" NPS SW 3/4" NPT(M) CS/AS NIPPLE
7.	3/4" SW EQUAL TEE
8.	3/4" NPS SCH 80 CARBON/ALLOY STEEL NIPPLE
9.	3/4" NPT(F) CS/AS CAP
10.	3/4" SW CS/AS EQUAL CROSS
11.	1/2" TUBE ADAPTER
12.	3 VALVE MANIFOLD
13.	3/4" PIPE UNION
14.	2 VALVE MANIFOLD
15.	3/4" SW 4 WAY VALVE
16.	QUICK DISCONNECT FITTING
17.	3/4"SWx1/2"SW BRANCH TEE
18.	1/2" NB SEAMLESS GI PIPE
19.	1/2" NPT (F) GI FITTING
20.	SS TUBE
21.	FLEXIBLE HOSE WITH ONE END SOCKET WELDED (PIPE SIDE) & OTHER END WITH SUITABLE FITTINGS.
22.	3/4" x 1/2" S.S. TUBE UNION

1. SEE NOTES UNDER DRG NO.0000-999-POI-A-022.
2. IMPULSE LINE DRAIN CONNECTIONS SHALL BE DONE AS PER TECHNICAL SPECIFICATIONS
3. THE SLOPE IN THE HORIZONTAL OF THE IMPULSE PIPE SHALL BE APPROX. 50 mm/mtr.
4. THE EXACT ORIENTATION OF THE TRANSMITTERS WITH RESPECT TO VALVE MANIFOLDS ETC WILL BE FINALISED DURING DETAILED ENGINEERING KEEPING IN VIEW THE MANUFACTURER'S RECOMMENDATIONS.
5. COMMON INSTRUMENT AIR HEADER (1"NB) USING REDUNDANT AIR FILTER PURGE AIR ROTAMETERS AS SHOWN IN EACH TRANSMITTER ENCLOSURE REQUIRING PURGE AIR PURGE AIR ETC. CAN INSURE THAT THE AIR WILL BE TAPPED FROM THIS HEADER USING INDIVIDUAL PURGE ROTAMETERS AS SHOWN IN DRG. NO. 0000-999-POI-A-034 TYPICALLY.

**एन टी पी सी**  
**NTPC**


PROJECT	TYPICAL THERMAL POWER PROJECT
---------	-------------------------------

TITLE	INSTRUMENT INSTALLATION DIAGRAM (PRESSURE MEASUREMENT USING PRESS / DP TRANSMITTERS (INST./SERVICE, DIRTY AIR/FLUE GAS))
-------	--


SIZE	SCALE	DRG. NO.	REV. NO.
A3	N.T.S.	0000-999-POI-A-023	A

Page 295 of 313

This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission.




**TRANSMITTER MOUNTED BELOW INSTRUMENT SOURCE POINT**




**TRANSMITTER MOUNTED ABOVE INSTRUMENT SOURCE POINT**

### LIQUID PRESSURE MEASUREMENT




**TRANSMITTER MOUNTED BELOW INSTRUMENT SOURCE POINT**



**TRANSMITTER MOUNTED ABOVE INSTRUMENT SOURCE POINT**

### STEAM PRESSURE MEASUREMENT



**VACUUM PRESSURE MEASUREMENT**

#### NOTES:-

1. SAME NOTES UNDER DRG. NO. 0000-999-POI-A-023.
2. FOR VACUUM APPLICATION OTHER PORT OF TRANSMITTER SHALL BE KEPT OPEN TO ATMOSPHERE.

**FOR TENDER PURPOSE ONLY**

#### LIST OF MATERIALS

ITEM NO.	DESCRIPTION
1.	1/2" / 3/4" / 1" NPS SCH. 80/160/XXS/PS1 NIPPLE OF MATERIAL SAME AS THAT OF MAIN PIPE
2.	3/4" / 1" SW GLOBE VALVE
3.	3/4" / 1" TO 1/2" REDUCING INSERT
4.	1/2" NPS PIPE
5.	1/2" SW EQUAL TEE
6.	1/2" SW GLOBE VALVE
7.	1/2" NPS SCH. 80/160 SW 1/2" CS/AS COUPLER
8.	1/2" PIPE UNION
9.	2/3 VALVE MANIFOLD (FOR DETAIL SEE DRAWING NO.0000-102-POI-A-023)
10.	SUITABLE ADAPTER
11.	SS TUBE
12.	1/2" PIPE x 1/2" TUBE UNION
13.	1/2" NPS SCH. 80/160 SW 1/2" NPT(M) CS/AS NIPPLE

**NTPC**

**NTPC LIMITED**  
( A GOVERNMENT OF INDIA ENTERPRISE )  
ENGINEERING DIVISION


PROJECT **TYPICAL THERMAL POWER PROJECT**

TITLE **INSTRUMENT INSTALLATION DIAGRAM  
(PRESSURE MEASUREMENT USING PRESS /DP  
TRANSMITTERS STEAM/LIQUID VACUUM)**

REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	M	E	C	C&I	ARCH.	APPD.	DATE
A	FIRST ISSUE										21.08.12
Cleared By											

SIZE A3	SCALE N.T.S.	DRG. NO. 0000-999-POI-A-025	REV. NO. A
------------	-----------------	--------------------------------	---------------

This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission



LIST OF MATERIALS	
ITEM NO.	DESCRIPTION
1.	42x2 TO 3/4" SW REDUCING INSERT.
2.	3/4" SW GLOBE VALVE.
3.	1/2" SW GLOBE VALVE FOR LIQUID APPLICATION & 3/4"/1" IN GAS/AIR APPLICATION
4.	1/2" NPS 40/80/160 (AS PER PROCESS REQUIREMENT) CARBON/ALLOY STEEL PIPE.
5.	1/2" SW EQUAL TEE.
6.	1/2" NPS SW x 1/2" NPT (M) NIPPLE.
7.	1/2" NPT (F) CAP.
8.	1/2" PIPE x 1/2" PIPE UNION.
9.	5 VALVE MANIFOLD (FOR DETAIL REFER DRAWING NO.0000-999-POI-A-026.
10.	3/4" SCH 80 CARBON/ALLOY STEEL PIPE.
11.	3/4"/1/2" SW EQUAL TEE.
12.	3/4"x1/2" TUBE UNION.
13.	1/2" SCREWED GLOBE VALVE.
14.	1/2" NPT (M) PLUG.
15.	3/4" SW GATE VALVE.
16.	3/4" SW EQUAL CROSS.
17.	WAFER ELEMENT FOR USE WITH 3"ANSI R.F. VALVE.
18.	3"BLIND 300lbs R.T. WELD NECK FLANGE DRILLED FOR 1" SCH 40/80 PIPE
19.	3" BLIND FLANGE.
20.	1"NPS SCH. 40/80 (AS PER PROCESS REQUIREMENT) CS PIPE.
21.	1" SW EQUAL TEE.
22.	3/4" x 1/2"SW REDUCING INSERT.
23.	3/4" SW x 3/4" NPT (M) CS/AS NIPPLE
24.	3/4" NPT (F) CS/AS CAP.
25.	1/4" NPS ALLOY STEEL PIPE.
26.	1" x 3/4" SW REDUCING INSERT.
27.	3/4" SW x 1/2" PSW BRANCH TEE.
28.	3/4" PIPE UNION
29.	1/2" CLAMP UNION (THREADED) SUITABLE FOR FLEXIBLE CONNECTION OF NYLON REINFORCED PVC TUBE.
30.	SS TUBE
31.	3/4" SW 4 WAY VALVE.
32.	QUICK DISCONNECT FITTINGS.
33.	1/4" SW ISOLATION VALVE 316SS
34.	1/2" x 1/2" SS PIPE UNION.




**NTPC LIMITED**  
( A GOVERNMENT OF INDIA ENTERPRISE )  
ENGINEERING DIVISION


REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	M	E	C	C&I	ARCH.	APPD.	DATE
A	FIRST ISSUE										21.08.12
Cleared By											

PROJECT		TYPICAL THERMAL POWER PROJECT									
TITLE		INSTRUMENT INSTALLATION DIAGRAM DIFF. PRESS. MEASUREMENT (LIQUID, OIL, AIR/GAS SERVICE)									
SIZE	SCALE	DRG. NO.	0000-999-POI-A-030							REV. NO.	A
A3	N.T.S.										


This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission.




**ELEVATION**  
LOCAL LEVEL INDICATION USING GAUGE GLASS



**ELEVATION**  
LOCAL LEVEL INDICATION USING MULTIPLE GAUGES  
FOR INCREASED RANGE NOT COVERED IN A SINGLE UNIT



**ELEVATION**  
FLOAT OR DISPLACER OPERATED EXTERNAL CAGE TYPE LEVEL SWITCH INSTALLATION



LIST OF MATERIALS	
ITEM NO.	DESCRIPTION
1.	3/4" x 1" NPS SCH.40/80/160/P91 (AS PER PROCESS REQUIREMENT) CARBON /ALLOY STEEL PIPE.
2.	3/4" SW GLOBE VALVE.
3.	3/4" SW UNION.
4.	3/4" NPT GLOBE VALVE.
5.	3/4" NPT (M) CAP.
6.	3/4" NPT (F) UNION CONNECTION.
7.	1" SW EQUAL UNION.
8.	1" x 1/2" SW REDUCING INSERT.
9.	1" SW EQUAL TEE.
10.	1/2" SW GLOBE VALVE.
11.	1/2" NPS SWx1/2" NPT(M) CS/AS NIPPLE.
12.	1/2" NPT (F) CAP.
13.	3/4"x1/2" NPS SCH.40/80 CS/AS PIPE.
14.	1/2" NPS SCH.80/160 CS/AS NIPPLE.
15.	1" SW GLOBE VALVE.

**NOTES:-**

- FOR LEVEL GAUGE 3/4" AND FOR LEVEL SWITCH 1" PROCESS CONNECTION SHALL BE PROVIDED.
- NOTES UNDER DRG. NO. 0000-999-POI-A-023 (WHICHEVER ARE RELEVANT).

**FOR TENDER PURPOSE ONLY**



**NTPC LIMITED**  
( A GOVERNMENT OF INDIA ENTERPRISE )  
ENGINEERING DIVISION

PROJECT **TYPICAL THERMAL POWER PROJECT**


TITLE **INSTRUMENT INSTALLATION DIAGRAM  
(LEVEL GAUGE & SWITCHES)**

REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	M	E	C	C&I	ARCH.	APPD.	DATE
A	FIRST ISSUE										21.08.12
Cleared by											

SIZE A3	SCALE N.T.S.	DRG. NO. 0000-999-POI-A-031	REV. NO. A
------------	-----------------	--------------------------------	---------------



This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission.



#### LIST OF MATERIALS

ITEM NO.	DESCRIPTION
1.	1" NPS SCH.40/80/160/XXS/PB1 (AS PER PROCESS REQUIREMENT) CARBON /ALLOY STEEL PIPE.
2.	1" SW GLOBE VALVE.
3.	3/4"/1" TO 1/2" REDUCING INSERT.
4.	1/2" NPS SCH.80/160/XXS (AS PER PROCESS REQ.)CS/AS PIPE.
5.	1/2" SW EQUAL TEE.
6.	1/2" SW GLOBE VALVE.
7.	1/2" NPS SWx1/2" NPT(M) CS/AS NIPPLE.
8.	1/2 NPT (F) CAP.
9.	1/2" PIPE UNION.
10.	5-VALVE MANIFOLD (FOR DETAILS REF. DRG. NO.0000-999-POI-A-026).
11.	SUITABLE ADAPTER.
12.	1/2" PIPE x 1/2" TUBE UNION.
13.	S.S. TUBE.

#### NOTES:-

1. SAME NOTES AS UNDER DRG. NO.0000-999-POI-A-023 (WHICHEVER ARE RELEVANT).
- \* TO DRAIN HEADER IN LIE/LIR.

**ELEVATION**  
TRANSMITTER MOUNTED BELOW INSTRUMENT SOURCE POINT

**ELEVATION**  
TRANSMITTER MOUNTED ABOVE INSTRUMENT SOURCE POINT

FOR TENDER PURPOSE ONLY

LEVEL MEASUREMENT OF CLEAR NON-VISCOUS OR NON-CORROSIVE LIQUID IN CLOSED VESSEL WITH CONDENSABLE ATMOSPHERE USING D/P TRANSMITTER



**NTPC LIMITED**  
( A GOVERNMENT OF INDIA ENTERPRISE )  
ENGINEERING DIVISION

PROJECT TYPICAL THERMAL POWER PROJECT




TITLE INSTRUMENT INSTALLATION DIAGRAM  
(LEVEL MEASUREMENT USING D/P TRANSMITTERS)

																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							</
--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	----

SH 1 OF 2

This document is the property of NATIONAL THERMAL POWER CORPORATION LTD.  
No part of this document will be reproduced by any means without the written permission.

## PRESS. MEASUREMENT




FOR TENDER PURPOSE ONLY

<div style="display: flex; justify-content: space-between;"> <div> <p>प्र. सं. सं. सं.</p> <p><b>NTPC</b></p> </div> <div> <p><b>NTPC LIMITED</b></p> <p>(A GOVERNMENT OF INDIA ENTERPRISE)</p> <p>KNOWLEDGE DIVISION</p> </div> </div>											
PROJECT TYPICAL THERMAL POWER PROJECT											
TITLE INSTRUMENT SOURCE CONNECTION DETAILS											
REV. NO.	DESCRIPTION	DESIGN	DESIGN	CHKD.	M	E	C	CL	ARCH.	APPRO.	DATE
A	FIRST ISSUE										
CLEARED BY										SIZE A4	SCALE N.T.S.
										DRG. NO. 0000-999-POI-A-035	REV. NO. A


This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission.

### PRESSURE MEASUREMENT


(SYSTEM PR. >40Kg/Sq Cm CL 9000)




(SYSTEM PR. >40Kg/Sq Cm CL 6000)



(SYSTEM PR. <40Kg/Sq cm Nb 25 CL 3000)



(SYSTEM PR. <40Kg/Sq cm Nb 15 CL 3000)




#### NOTES:-

1. MATERIAL OF THE BOSS AND NIPPLE SHALL BE THE SAME AS THE PIPE INTO WHICH IT IS WELDED AND CONFORM TO ANSI B 16.11.
2. THE LENGTH OF THE NIPPLE SHOULD BE 250mm.
3. THE OTHER END OF THE NIPPLE SHALL BE SOCKET WELDED WITH 1" GLOBE VALVE OF MATERIAL AS PER ANSI B 16.1.
4. TWO ISOLATED VALVES ARE TO BE USED FOR PRESSURE = >40 Kg/Cm<sup>2</sup>.
5. EDGE HOLE MUST BE CLEAN AND SQUARE OR ROUNDED SLIGHTLY (1/64" RADIUS) FREE FROM BURRS, WIRE EDGES OR OTHER IRREGULARITIES.
6. ORIENTATION OF TAP WILL BE VARY WITH TYPE OF PROCESS FLUID AND NATURE OF RUN OF THE PIPE.
7. ACTIVITIES TO BE COMPLETED AT THE SHOP, WELD THE COUPLING (OR BOSS) ON THE PIPE AND DRILL PRESSURE CONNECTION HOLE (SAME AS I D OF NIPPLE) IN THE PIPE IN ALIGNMENT WITH HOLE IN THE COUPLING.
8. ALL DIMENSIONS ARE IN mm UNLESS OTHERWISE STATED.

FOR TENDER PURPOSE ONLY

<div style="display: flex; justify-content: space-around; align-items: center;"> <div style="border: 1px solid black; padding: 2px;"> </div> <div style="text-align: center;"> <b>NTPC LIMITED</b>  <small>(A GOVERNMENT OF INDIA ENTERPRISE)</small>  <small>ENGINEERING DIVISION</small> </div> </div>									
<b>PROJECT</b> TYPICAL THERMAL POWER PROJECT									
<b>TITLE</b> INSTRUMENT SOURCE CONNECTION DETAILS									
REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	BY	DATE	SCALE	DRG. NO.	REV. NO.
A	FIRST ISSUE	[Signature]	[Signature]	[Signature]	[Signature]	[Signature]	A4	N.T.S.	0000-999-POI-A-035
CLEARED BY							SP-2 OF 14		


## TEMP. MEASUREMENT



### NOTES:-

1. THIS TYPE OF THERMOWELL INSTALLATION IS SUITABLE FOR THE PROCESS PIPE OF 2" NPS AND SMALLER.
2. FOR STEAM SERVICE THIS TYPE OF THERMOWELL INSTALLATION 90° BEND MAY BE USED ONLY IN VERTICAL PLANE.
3. THE LENGTH OF THE LARGER PIPE SECTION SHALL BE MINIMUM 150mm (IT MUST BE GREATER THAN THERMOWELL LENGTH).

THERMOWELL SUITABLE FOR THE BOSS




### NOTES:-

1. INCLINED INSTALLATION OF THERMOWELL SHALL BE APPLICABLE FOR 4" AND SMALLER LINE SIZE BUT LIMITED TO MIN. 3" LINE SIZE.
2. FOR 2" AND SMALLER LINE SIZE NECESSARY EXPANDER OF MIN. 3" SIZE OF MAIN PIPING SPECIFICATION SHALL BE USED.
3. THIS TYPE OF INSTALLATION IS APPLICABLE FOR HORIZONTAL AND VERTICAL PIPE SECTION.
4. FOR STEAM SERVICES EXPANDER SECTION MAY BE USED ONLY IN VERTICAL RUN.
5. THE EXPANDER SECTION SHALL BE OF ADEQUATE LENGTH (ATLEAST 3-4 TIMES DIA OF THE MAIN PROCESS PIPE AT BOTH SIDE OF THE INSTALLED THERMOWELL).

FOR TENDER PURPOSE ONLY

<div style="display: flex; justify-content: space-between; align-items: center;"> <div> </div> <div> <b>NTPC LIMITED</b>  <small>(A GOVERNMENT OF INDIA ENTERPRISE)</small>  <b>ENGINEERING DIVISION</b> </div> </div>									
<b>PROJECT</b> TYPICAL THERMAL POWER PROJECT (SG PACKAGE)									
<b>TITLE</b> INSTRUMENT SOURCE CONNECTION DETAILS									
<b>REV. NO.</b> A <b>DESCRIPTION</b> FIRST ISSUE	<b>DRW. NO.</b> 0000-999/102-POI-A-035 <small>SH-4 OF 14</small>	<b>SCALE</b> N.T.S.	<b>SIZE</b> A4	<b>DATE</b>	<b>APPROVED</b>	<b>CHECKED</b>	<b>DATE</b>	<b>BY</b>	<b>DATE</b>

## TEMP. MEASUREMENT




### NOTES:-

1. FLOW INSTALLATION OF THERMOWELL SHALL BE APPLICABLE FOR 4" AND SMALLER LINE SIZE BUT LIMITED TO MINIMUM 3" LINE SIZE.
2. FOR 2" AND SMALLER LINE SIZE NECESSARY EXPANDER OF ELBOW FORM (AS SHOWN) OF MINIMUM 3" SIZE SHALL BE USED.
3. ELBOW EXPANDER SECTION IN HORIZONTAL PLANE MAY BE USED FOR LIQUID SERVICES. ONLY STEAM SERVICES EXPANDER SECTION MAY BE USED IN VERTICAL PLAN.

FOR TENDER PURPOSE ONLY

<div style="display: flex; justify-content: space-between; align-items: center;"> <div> </div> <div> <b>NTPC LIMITED</b>  <small>( A GOVERNMENT OF INDIA ENTERPRISE )</small>  <b>ENGINEERING DIVISION</b> </div> </div>																																	
<div style="display: flex; justify-content: space-between;"> <div> <b>PROJECT</b> TYPICAL THERMAL POWER PROJECT         </div> <div> <b>TITLE</b> INSTRUMENT SOURCE CONNECTION DETAILS         </div> </div>																																	
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 10%;">REV. NO.</td> <td style="width: 30%;">DESCRIPTION</td> <td style="width: 10%;">DRAWN</td> <td style="width: 10%;">DESIGN</td> <td style="width: 10%;">CHKD.</td> <td style="width: 10%;">U</td> <td style="width: 10%;">T</td> <td style="width: 10%;">C</td> <td style="width: 10%;">DIL</td> <td style="width: 10%;">ARCH</td> <td style="width: 10%;">APPD.</td> <td style="width: 10%;">DATE</td> </tr> <tr> <td>A</td> <td>FIRST ISSUE</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>										REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	U	T	C	DIL	ARCH	APPD.	DATE	A	FIRST ISSUE										
REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	U	T	C	DIL	ARCH	APPD.	DATE																						
A	FIRST ISSUE																																
<div style="display: flex; justify-content: space-between;"> <div> <b>SIZE</b> A4         </div> <div> <b>SCALE</b> N.T.S.         </div> <div> <b>DRG. NO.</b> 0000-999-POI-A-035         </div> <div> <b>REV. NO.</b> A         </div> </div>																																	

## TEMP. MEASUREMENT




### NOTES:-

1. THIS TYPE OF TEMPERATURE BOSS SHALL BE USED FOR THE PROCESS PRESS EQUAL/ABOVE 40 Kg/Cm2(g).
2. THE MATERIAL OF THE BOSS SHOULD BE SIMILAR TO THAT OF PIPING MATERIAL OF SPECIFICATION.
3. ALL WELD TO BE TESTED IN ACCORDANCE WITH APPLICABLE CODES BY MANUFACTURER.
4. MATERIAL OF THE THERMOWELL SHALL BE OF 316SS.
5. THERMOWELL SHALL BE DRILLED BARSTOCK TYPE.
6. INTERNAL BORE OF THE THERMOWELL SHOULD BE SELECTED BASED ON THE NORMAL SIZE OF THE SENSING ELEMENT AS PER ASME,PTC-19.3.
7. THE BOTTOM DIAMETER OF THE THERMOWELL TYPICALLY SHOWN HERE SHALL BE SUBJECT TO VARIATION BASED ON THE INTERNAL BORE OF THERMOWELL AND THICKNESS OF THERMOWELL MATERIAL TO WITHSTAND THE PROCESS PRESS AND TEMP. AS PER ASME,PTC-19.3.
8. THE TYPE OF TAPERED THERMOWELL SHALL BE USED FOR LIQUID VELOCITIES UP TO 92M.P.S.(300F.T.P.S.).
9. THERMOWELL WITH THE INSULATION LAG EXTENSIONS SHALL BE USED WHEREVER APPLICABLE.
10. ACTIVITIES TO BE COMPLETED AT THE SHOP. WELD THE BOSS ON THE PIPE AND DRILL THE HOLE IN THE PIPE IN ALIGNMENT WITH HOLE IN THE BOSS. PROVIDE INTERNAL THREAD AS PER IS:554 TO MATCH WITH THE THERMOWELL EXTERNAL THREAD.
11. ALL DIMENSIONS ARE IN MM UNLESS OTHERWISE STATED.
12. WILL BE SUITABLE TO MATCH THE STUB DIMENSIONS AS PER RC 1 1/2
13. THE "U" & "L" DIMENSIONS SHALL BE SELECTED BASED ON PARTICULAR APPLICATION AND THE SAME SHALL BE SUBJECT TO OWNER'S APPROVAL DURING DETAILED ENGINEERING.
14. ALL DIMENSIONS ARE INDICATIVE ONLY.

FOR TENDER PURPOSE ONLY

<div style="display: flex; justify-content: space-between;"> <div> <p>एन टी पी सी</p> <p><b>NTPC</b></p> </div> <div> <p><b>NTPC LIMITED</b></p> <p>(A GOVERNMENT OF INDIA ENTERPRISE)</p> <p>ENGINEERING DIVISION</p> </div> </div>			
PROJECT		TYPICAL THERMAL POWER PROJECT	
TITLE		INSTRUMENT SOURCE CONNECTION DETAILS	
REV. NO.	DESCRIPTION	DATE	BY
A	FIRST ISSUE		
DRAWN BY		CHKD BY	APPD BY
CLEANED BY		DATE	
SIZE	SCALE	DRG. NO.	REV. NO.
A4	N.T.S.	0000-999-POI-A-035	A
		SH-6 OF 14	

## TEMP. MEASUREMENT




### NOTES:-

1. THIS TYPE OF TEMPERATURE BOSS IS APPLICABLE FOR THE PROCESS PRESSURE/TEMPERATURE BELOW 40 Kg/Cm<sup>2</sup>(g)/400°C
2. FOR PRESSURE TIGHT JOINTS THE BOSS SHOULD HAVE INTERNAL TAPERED PIPE THREAD Rc 1 AS PER IS:554. THE LENGTH OF THREAD ENGAGEMENT SHOULD BE AS PER ABOVE STANDARD.
3. PIPES HAVING PROBABILITY OF PROLONGED VIBRATION SEAL WELDING MAY BE DONE ALL AROUND AFTER TIGHTENING THERMOWELL WITHIN THE BOSS.
4. SEE NOTES-2 TO 14 OF DRG. NO. 0000-999-POI-A-035, Sh-6 Of 14.

FOR TENDER PURPOSE ONLY


<div style="display: flex; justify-content: space-around; align-items: center;"> <div style="border: 1px solid black; padding: 2px;"> <small>एन टी पी सी</small>  <b>NTPC</b> </div> <div style="text-align: center;"> <b>NTPC LIMITED</b>  <small>(A GOVERNMENT OF INDIA ENTERPRISE)</small>  <b>ENGINEERING DIVISION</b> </div> </div>										
<div style="display: flex; justify-content: space-between;"> <div>PROJECT</div> <div>TYPICAL THERMAL POWER PROJECT</div> </div>										
<div style="display: flex; justify-content: space-between;"> <div>TITLE</div> <div>INSTRUMENT SOURCE CONNECTION DETAILS</div> </div>										
REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD	W	E	C	CAL	APPRD.	DATE
A	FIRST ISSUE									
<small>PREPARED BY</small>										
		SIZE		SCALE		DRG. NO.		REV. NO.		
		A4		N.T.S.		0000-999-POI-A-035		A		
<small>Sh-7 Of 14</small>										

## LEVEL MEASUREMENT



### NOTES:-

1. THIS TYPE OF PROCESS CONNECTION SHALL BE USED FOR LEVEL GAUGE AND EXTERNAL CAGE TYPE FLOAT OR DISPLACER OPERATED LEVEL SWITCH.
2. FOR GAUGES 3/4" NIPPLE ALONG WITH 3/4" SW SOURCE VALVE AND FOR SWITCHES 1" NIPPLE ALONG WITH 1" SW SOURCE VALVE SHALL BE PROVIDED AS PROCESS CONNECTION.
3. SOURCE CONNECTION ON VESSEL SHOULD NOT BE LOCATED AT PLACES SUBJECTED TO INTERFACE AND TURBULENCE FROM INLETS AND OUTLETS.
4. IF LOWER CONNECTION IS TAKEN FROM BOTTOM OF THE VESSEL THEN THE NIPPLE MUST BE 100 mm TO 150 mm ABOVE THE BOTTOM OF THE VESSEL.



### NOTES:-

1. THIS TYPE OF PROCESS CONNECTION SHALL BE PROVIDED FOR TANK LEVEL MEASUREMENT OF VISCOUS OR CORROSIVE LIQUID USING FLUSH DIAPHRAGM/WAFER TYPE LEVEL TRANSMITTER.
2. WELDING OF MATCHING FLANGE TO GATE VALVE SHALL BE DONE BY BIDDER.

FOR TENDER PURPOSE ONLY

<div style="display: flex; justify-content: space-between; align-items: center;"> <div> <p>एन टी पी सी</p> <p><b>NTPC</b></p> </div> <div> <p><b>NTPC LIMITED</b></p> <p>(A GOVERNMENT OF INDIA ENTERPRISE)</p> <p>ENGINEERING DIVISION</p> </div> </div>									
PROJECT: TYPICAL THERMAL POWER PROJECT									
TITLE: INSTRUMENT SOURCE CONNECTION DETAILS									
REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHECK	DATE	SIZE	SCALE	DRG. NO.	REV. NO.
A	FIRST ISSUE					A4	N.T.S.	0000-999-POI-A-035	A
Cleared by						57-13 of 14			






**TITLE**  
**LARA STPP STAGE-II (2X800MW)**  
**MILL REJECT SYSTEM (CONVEYOR TYPE)**  
**STANDARD TECHNICAL REQUIREMENTS**

SPECIFICATION NO. PE-TS-508-160-A101	
SECTION: III	
REV 00	
Sub-Section	Date April 2024
Page 1 of 1	

**SECTION – III**  
**DOCUMENTS TO BE SUBMITTED ALONG WITH THE BID**

	<b>TITLE</b> <b>LARA STPP STAGE-II (2X800MW)</b> <b>MILL REJECT SYSTEM (CONVEYOR TYPE)</b> <b>STANDARD TECHNICAL REQUIREMENTS</b>	SPECIFICATION NO. PE-TS-508-160-A101	
		SECTION: III	
		REV 00	
		Sub-Section	Date April 2024
		Page 1 of 1	


**DRAWINGS/ DOCUMENTS TO BE SUBMITTED WITH THE BID**

Bidder shall submit the following drawings/documents along with their bid:

- a) Pre-qualification requirement (PQR) documents
- b) Signed and stamped copy of Compliance cum Confirmation Certificate
- c) Signed and stamped copy of Utility requirement sheet of Vol-III.
- d) Un-priced copy of price format indicating quoted/ not quoted against each row / column.
- e) Guaranteed Power Consumption Format (shall be submitted in open along with techno commercial offer only)

*OFFER WILL BE CONSIDERED AS INCOMPLETE IN ABSENCE OF ANY OF ABOVE DOCUMENTS.*

*DOCUMENT OTHER THAN ABOVE, IF ANY, SUBMITTED WITH THE OFFER WILL NOT FORM PART OF CONTRACT AND ACCORDINGLY WILLNOT BE CONSIDERED FOR BID EVALUATION.*


	<b>TITLE</b> <b>LARA STPP STAGE-II (2X800MW)</b> <b>MILL REJECT SYSTEM (CONVEYOR TYPE)</b> <b>STANDARD TECHNICAL REQUIREMENTS</b>	SPECIFICATION NO. PE-TS-508-160-A101	
		SECTION: III	
		REV 00	
		Sub-Section	Date April 2024
		Page 1 of 1	

### **COMPLIANCE CUM CONFIRMATION CERTIFICATE**

The bidder shall confirm compliance with following by signing/ stamping this compliance certificates (every sheet) and furnishes same with the offer.

- a) The scope of supply, technical details, construction features, design parameters etc. shall be as per technical specification & there are no exclusions, other than those resolved as per 'Schedule of Deviations', with regard to same.
- b) There are no other deviations w.r.t. specifications other than those furnished in the 'Schedule of Deviations'. Any other deviation, stated or implied, taken elsewhere in the offer stands withdrawn unless specifically brought out in the 'Schedule of Deviations'
- c) Bidder shall submit QP in the event of order based on the guidelines given in the specification & QP enclosed therein. QP will be subject to BHEL/ CUSTOMER approval & customer hold points for inspection / testing shall be marked in the QP at the contract stage. Inspection/ testing shall be witnessed as per same apart from review of various test certificates / Inspection records etc. This is within the contracted price with extra implications to BHEL after award of the contract.
- d) All drawings / data-sheets / calculations etc. submitted along with the offer shall be considered for reference only, same shall be subject to BHEL/ CUSTOMER approval in the event of order.
- e) The offered materials shall be either equivalent or superior to those specified in the specification & shall meet the specified / intended duty requirements. In case the material specified in the specifications is not compatible for intended duty requirements then same shall be resolved by the bidder with BHEL during the pre-bid discussions, otherwise BHEL/ Customer's decision shall be binding on the bidder whenever the deficiency is pointed out.  
  
For components where materials are not specified, same shall be suitable for intended duty, all materials shall be subject to approval in the event of order.
- f) The commissioning spares shall be supplied on 'As Required Basis' & prices for same included in the base price itself. Prices for special tools & tackles, if any, shall also be included in the base price.
- g) All sub vendors shall be subject to BHEL/ CUSTOMER approval in the event of order.
- h) Guarantee for plant /equipment shall be as per relevant clause of GCC /SCC /Other Commercial Terms & Conditions.
- i) In the event of order, all the material required for completing the job at site shall be supplied by the bidder within the ordered price even if the same are additional to approved billing break up, approved drawing or approved Bill of quantities. This clause will apply in case during site commissioning additional requirements emerges due to customer and / or consultant's comments. No extra claims shall be put on this account.
- j) Schedule of drawings submissions, comment incorporations & approval shall be as stipulated in the specifications. The successful bidder shall depute his design personnel to

BHEL's/ Customer's/ Consultant's office for across the table resolution of issues and to get documents approved in the stipulated time.

	<b>TITLE</b> <b>LARA STPP STAGE-II (2X800MW)</b> <b>MILL REJECT SYSTEM (CONVEYOR TYPE)</b> <b>STANDARD TECHNICAL REQUIREMENTS</b>	SPECIFICATION NO. PE-TS-508-160-A101	
		SECTION: III	
		REV 00	
		Sub-Section	Date April 2024
		Page 1 of 1	

- k) As built drawings shall be submitted as and when required during the project execution.
- l) That the bidder has not tempered with this compliance cum confirmation certificate and if at any stage any tempering in the signed copy of this document is noticed then same shall be treated as breach of contract and suitable actions shall be taken against the bidder.



**TITLE**  
**LARA STPP STAGE-II (2X800MW)**  
**MILL REJECT SYSTEM (CONVEYOR TYPE)**  
**STANDARD TECHNICAL REQUIREMENTS**

**SPECIFICATION NO.** PE-TS-508-160-A101  
**SECTION:** III  
**REV** 00  
**Sub-Section**  
**Date** April 2024  
Page 1 of 1

## PRE-BID CLARIFICATION SCHEDULE

S. No.	Section/Clause /Page No.	Statement of the referred clause	Clarification Required

The bidder hereby certifies that above mentioned are the only clarifications required on the technical specification for the subject package.

SIGNATURE: \_\_\_\_\_

NAME: \_\_\_\_\_

DESIGNATION: \_\_\_\_\_

COMPANY: \_\_\_\_\_

DATE: \_\_\_\_\_

COMPANY SEAL



**TITLE**  
**LARA STPP STAGE-II (2X800MW)**  
**MILL REJECT SYSTEM (CONVEYOR TYPE)**  
**STANDARD TECHNICAL REQUIREMENTS**

**SPECIFICATION NO.** PE-TS-508-160-A101  
**SECTION:** III  
**REV** 00  
**Sub-Section**  
**Date** April 2024  
Page 1 of 1

## **UTILITY REQUIREMENT**

S. No.	Utility	Requirement	Tapping point location
1.	Instrument air	Pressure - 5-7 bar Flow - 1.5 m <sup>3</sup> /min per unit	3-6 m at first column of mill bay
2.	Service water	Pressure - 2.5-3 bar Flow - 6-8 m <sup>3</sup> / hour per unit	3-6 m at first column of mill bay

The bidder has to submit signed and stamped copy of this sheet along with bid.

<b>LARA STPP STAGE-II (2X800MW) - Mill Reject Handling System</b>						
<b>GUARANTEED POWER CONSUMPTION FORMAT</b>						
<b>Mode: CONVEYOR TYPE</b>						
<b>Sl.No.</b>	<b>Description / Item</b>	<b>Working</b>	<b>Standby</b>	<b>Power Consumption (KW) (at motor input terminal)</b>	<b>Duty Factor</b>	<b>Total Power Consumption (KW)</b>
<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>	<b>5</b>	<b>6</b>	<b>7 = 3 x 5 x 6</b>
1	Total Power Consumption per Unit	1	0		1.00	
					<b>Total KW</b>	
<b>Notes</b>						
1	Power consumption (KW) of motors shall be measured at motor input terminals when the system operating at the rated capacity, Power consumed by Horizontal conveyor and Bucket Elevator motors along with vent fan motor and vibrating feeder (if applicable) shall be taken into consideration for the purpose.					
2	The base auxiliary power is 35 KW per Unit. Quoted power by bidder at column no. (7) shall be evaluated with respect to base auxiliary power. For bid evaluation purpose, excess power quoted by bidder over base auxiliary power, shall be loaded with 4642 USD per KW (USD conversion rate shall be taken as defined in NIT).					
3	Power quoted by bidder shall be termed as 'Guaranteed Power consumption' (GPC) and bidder shall be liable to demonstrate compliance to GPC value during PG test/ Demonstration test at site. If the actual power consumption exceeds the guaranteed power consumption, liquidated damages shall be payable by the Contractor at the rate of 4642 USD per KW excess power consumption, over the guaranteed power consumption indicated by bidder in his bid. Such liquidated damages may be recovered by the BHEL by deduction from the contract price or by enforcing the contract performance guarantee or in any other manner deemed fit by the BHEL. For this purpose, the drives of standby equipment shall not be considered.					
4	Guaranteed Power Consumption Format shall be submitted in open along with techno commercial offer only.					