BHARAT HEAVY ELECTRICALS LIMITED,
RANIPET- 632 406.

TECHNICAL SPECIFICATION FOR SEWAGE TREATMENT PLANT

YADADRI TPS 5x800MW
DAMERACHERLA, NALGONDA DISTRICT

00	09.08.21	A.Kumar ABH	Srivatsan SS	VNS	Fresh issue
Rev.No	Date	Prepared	Checked	Approved	Remarks

INDEX

S.No.	Description	Reference	PAGE No.
1.	Technical Specification for STP	ROS 6279	1 - 12
2.	E,C&I specification	ROS4370	13 - 281
3.	Special conditions of Contract (SCC)	ROS9065	282 - 287
4.	Mandatory spares	Annexure-1	288 - 293
5.	Sub Vendor List	Annexure-2	294 - 481
6.	Quality Plan	Annexure-3	482 - 492
7.	Master Drawing List (MDL)	Annexure-4	493 - 494
8.	PG test procedure	Annexure-5	495 - 507
9.	Drawings/ Documents attached	Annexure-6	508 - 541
10.	Hoists Specification	Annexure-7	542 - 550
11.	Quality Assurance, Control	Annexure-8	551 - 565
12.	Drawings & Documents to be submitted	Annexure-9	566 - 568
13.	Painting Specification	Annexure-10	569 - 580
14.	Health Safety & Environment plan (HSE)	Annexure-11	581 - 662
15.	Additional General Technical requirement	Annexure-12	663 - 683
16.	Engineering services	Annexure-13	684 – 691
17.	Project management & site services	Annexure-14	692 - 707
18.	Spares, Tools, Tackles & Consumables	Annexure-15	708 - 710
19.	Civil specification	Annexure-16	711 - 1064
20.	General Specification for Erection, Commissioning & PG test (ROS 9066)	Annexure-17	1065 - 1073
21.	General specification requirements	Annexure-18	1074 - 1169
22.	Deviation format	Annexure-A	1170
23.	Compliance cum confirmation schedule	Annexure-B	1171 – 1172

SECTION -1

1.0 SCOPE OF INQUIRY/ INTENT OF SPECIFICATION

1.1 The specification is intended to cover design, engineering, manufacture, fabrication, assembly, inspection and testing at vendor's & sub-vendor's works, painting, mandatory spares along with spares for erection and commissioning, startup and commissioning as required, forwarding, proper packing, shipment and delivery at site on FOR site basis, unloading, handling & transportation within site , Erection & Commissioning, trial run, complete Civil design & construction drawings, preparation & submission of "As Built" drawings, PG test at site and handing over of Sewage Treatment Plant as per the details in different sections / volumes of this specification for 5X800 MW TSGENCO YADADRI TPS, DAMARACHERLA.

1.2 The contractor shall be responsible for providing all material, equipment & services, required to fulfill the intent of ensuring operability, maintainability, reliability and safety of the complete work indicated in this specification. In addition, Bidder shall take all necessary additional steps in all stages of execution to ensure that required performance is met with, irrespective of whether it has been specifically listed herein or not. Bidder shall consider all / any required component / accessory necessary for proper performance of the equipment. Bidder shall assume full responsibility for providing requisite facilities to complete supply, erection and commissioning of STP.

1.3 It is not the intent to specify herein all the details of design and manufacture. However, the equipment shall conform in all respects to high standards of design, engineering and workmanship and shall be capable of performing the required duties in a manner acceptable to purchaser who will interpret the meaning of drawings and specifications and shall be entitled to reject any work or material, which in his judgment is not in full accordance herewith.

1.4 The extent of supply under the contract includes all items shown in the drawings, notwithstanding the fact that such items do not figure in the specification or schedules. Similarly, the extent of supply also includes all items mentioned in the specification and /or schedules, notwithstanding the fact that such items do not figure in the drawing.

1.5 The general terms and conditions, instructions to tenderer and other attachment referred to elsewhere in the specification are part of the tender specification. The equipment materials and works covered by this specification are subject to compliance to all attachments referred to in the specification. The bidder shall be responsible for, and governed by all requirements stipulated herein.

1.6 While all efforts have been made to make the specification requirement complete & unambiguous, it shall be bidders' responsibility to ask for missing information, ensure completeness of specification, to bring out any contradictory / conflicting requirement in different sections of the specification and within a section itself to the notice of BHEL and to seek any clarification on specification requirement in the format enclosed with this specification. In absence of any such clarifications, in case

of any contradictory requirement, the more stringent requirement as per interpretation of BHEL/ Customer shall prevail and shall be complied by the bidder without any commercial implication on account of the same. Further in case of any missing information in the specification not brought out by the prospective bidders as part of pre-bid clarification, the same shall be furnished by BHEL/ Customer as and when brought to their notice either by the bidder or by BHEL/ customer themselves. However, such requirements shall be binding on the successful bidder without any commercial & delivery implication.

1.7 Deviations, if any, should be very clearly brought out clause by clause in the enclosed schedule; otherwise, it will be presumed that the vendor's offer is strictly in line with NIT specification.

1.8 In case all above requirements are not complied with, the offer may be considered as incomplete and would become liable for rejection.

1.9 Unless specified otherwise, all through the specification, the word contractor shall have same meaning as successful bidder / vendor and Customer /Purchaser / Employer will mean BHEL and / or Customer (TSGENCO: Telangana State Power Generation Corporation Ltd.) including their consultant as interpreted by BHEL in the relevant context.

1.10 The equipment covered under this specification shall not be dispatched unless the same have been finally inspected, accepted and dispatch release issued by BHEL / Customer.

1.11 BHEL's / Customer's representative shall be given full access to the shop in which the equipment is being manufactured or tested and all test records shall be made available to him.

SECTION – 2

2.0 PROJECT INFORMATION

1	Name of the Project	Yadadri Thermal Power Station
2	Station Capacity	5x800 MW (Coal Based)
3	Owner	Telangana State Power Generation Corporation Limited (TSGENCO)
4	Site Location	Site is located 7 km from the NH5. Veerlapalem Village, Damaracherla Mandal, Nalgonda District, Telangana State
5	Latitude	16º 40'19" N
6	Longitude	79º 35' 18" E
7	Nearest Town	30km from Miryalaguda and 170 KM from Hyderabad by road.
8	Nearest railway Station	12km Damercherla
9	Nearest Airport	130 km Vijayawada 170 km Hyderabad
10	Site Conditions	
	Elevation above MSL	91 m
	Temperature –Minimum	10ºC during Winter
	- Maximum	47ºC during Summer
	- Design Ambient	50ºC
	- Ambient (performance)	38ºC
	Relative Humidity for design / efficiency	48 – 84 %
	Annual Rainfall - Average	753 mm
	- Maximum	1043 mm
	- Lowest	383
	Mean Wind Speed	8 kmph
	Wind Pressure	As per the latest revision of IS 875/1987
	Siesmic Co-efficient	Zone –III, as per IS 1893 (Part-IV)
11	Source of water	Source of water is Krishna River near Madachelu area that is about 1 km ie on upstream side of confluence point of Tungapahad Vagu and Krishna River. Water will be pumped through pipe line (of length 7 km) from this point to the project site.
12	Source of Coal	The boiler is designed for pulverised coal either 100% imported or 50% imported & 50% indigenous coal.

SECTION – 3

3.0 SCOPE OF SUPPLY

This specification is intended to cover the Design, engineering, manufacture, assembly, inspection and testing at manufacturer's and/or his sub-contractors works, proper packing, delivery at site, transportation, unloading/handling at site, storage at site, site fabrication, site painting, erection including testing/ commissioning at site, trial run and performance testing of Sewage treatment plant for 5x800 MW YADADRI TPS including complete Civil design, Electrical and C&I as specified and as necessary. The complete Sewage treatment plant, pumping, piping of sewage, Biodigesters are referred as STP in this specification.

1. The Broad scope of supply shall be as per following.

a. Sewage treatment plant comprising of sewage pumping & piping upto equalization sump from various areas of the power plant, bio digesters at various locations of the power plant, fixed bar screen, oil & grease separator, sewage equalization sump, sewage transfer pumps, aeration tank, air blower, settling tank, hypochlorite solution dosing system, sludge transfer pumps, sludge drying bed, sludge disposal trolley, clear water storage tank, clear water transfer pumps, Dual media filters, backwash water supply pumps, activated carbon filter, treated water storage tank, treated water transfer pumps and all other equipment and accessories required for complete Sewage treatment plant of Yadadri 5x800MW power plant.

b. All integral and interconnected pipe works, valves, strainers, pressure relief valves, instrument stubs, specialties, sumps, gates, all types of pipe supports, pipe racks, pipe bridges etc. for the entire system shall be provided by Bidder.

c. Necessary piping, fitting, valves, drains, vents, sampling etc, required for the complete STP. Piping of Sewage from various collection pits shall be burried and Bidder shall submit the sewage piping network for approval. Sufficient Man-holes shall be considered along the sewage piping. Typical piping network and manhole requirements/ details are attached in Annexure-6 of this specification.

d. All consumables (lubricating oil, inhibitor for oil), spares required for erection, commissioning & PG test of complete system shall be provided by Bidder

2. Electrical

The specification of Electrical, scope & terminal points shall be as per ROS-4370

3. Control & Instrumentation

The specification of C&I, scope & terminal points shall be as per ROS-4370

4. Scope of Services

a. Design & engineering of entire Sewage treatment plant (STP)

b. Complete civil design of Entire STP

c. Erection and Commissioning, unloading, storage and handling at site of all equipment of STP.

d. Arrangement of all the required instrumentations in addition to the erected instrumentations and tools/reagents required for calibration/recuperation of them as well as the erected instrumentations to carry out trial run, commissioning and Performance Guarantee test shall be in the scope of bidder. The calibration/recuperation shall be in the scope of bidder for these purposes
e. Pre- Commissioning work such as flushing, hydraulic testing etc. Necessary consumables and instrumentation as required for inspection and testing at works as well as at site including pre-commissioning activities shall be arranged by the successful bidder at their own cost
f. Minor Civil work including chipping of foundation, grouting below base plate for all structures, equipment, grouting of anchor bolts wherever these are not placed in the foundation during casting of foundation itself etc. To the extent possible, vendor shall ensure to supply all foundation bolts timely so as to facilitate placement of these bolts while casting the foundation. Wrapping, coating and protection of all the buried pipe shall be as per IS 10221
g. Supervision of all Civil works of entire Sewage treatment plant
h. Arrangement of all lubricants, instruments, reagents for carrying out trial run, commissioning and PG test
i. All personnel required during commissioning, trial run and PG Test
j. All tools & tackles required for the system shall be provided by Bidder.
k. Trial run for requisite period
l. Performance guarantee testing
m. Painting of all equipment as per painting specification. Touch up painting at site. Bidder to note that paint shed shall be finalized during detailed engineering as per customer & BHEL requirement and any variation in the painting schedule as finally approved by customer shall be taken care by bidder without any commercial and delivery implication.
n. Preparation of civil assignment drawings i.e. pedestals details; insert plates / embedment's plates required for supporting pipes and equipment etc. and civil design of the complete STP, sewer network & biodigesters. In case any modification is required in the civil work already done based on civil inputs given by vendor, rework shall be done at the cost and risk of the vendor.
o. Preparation & submission of all drawings –Mechanical, Civil, E, C&I
p. Preparation of drawings / document / P&ID's in AutoCAD, 3D modelling software and providing soft copy of same to BHEL
q. Material receipt, storage and issue for Erection & Commissioning shall be in Bidder's scope. Bidder shall store all high value items under lock & key, using containers only. Required containers shall be arranged by Bidder.
r. Training of plant Owner's personnel, O&M operators' personnel on plant operation and maintenance
s. All statutory clearances required, including local Govt. body / municipal offices as applicable shall be in Bidder's scope
t. Protection of all the erected equipment and instrumentations from any damage or pilferages shall be in bidder scope.
u. Any other service required for making the installation complete in all respect within battery limits and for satisfactory erection & commissioning of the system as well as

to meet any statutory requirement relevant to the package, unless specifically EXCLUDED from scope of services.

5. Painting

a. Supply and application of shop painting and final painting at manufacturer's works and at site for the entire system as specified elsewhere in this Bid Document

6. Consumables

a. All consumables (lubricating oil, inhibitor for oil), spares required for erection, commissioning & PG test of complete system shall be provided by Bidder

7. Terminal points

a. The details regarding terminal points are provided in Design memorandum, Layout and P&ID drawings.
b. Sewage from buildings will be terminated in identified Sewage collection pits/ lifting stations by BHEL.
c. Installation of Sewage transfer pumps, piping of sewage (burried piping), required man-holes & termination of Sewage in equalization tank/sump shall be in Bidder's scope.
d. Treated water from STP shall be terminated at treated water transfer pump outlet along with 100m flexible hose by Bidder. Further usage of water will be by BHEL.
e. Backwash waste from DMF/ ACF shall be terminated in equalization tank.
f. Sludge cake from Sludge drying bed shall be disposed by BHEL/ Customer. 1no. Sludge disposal trolly shall be provided by Bidder.
g. Service air supply (25NB connection) at 5 to 7 kg/cm2 (g) – near STP.
h. Service water connection (50NB connection) – near STP & service water connection (25NB connection) for individual sewage sumps/ lifting stations.
i. Potable water connection (50NB connection) – near STP.
j. Instrument air connection (50NB connection) - near STP.
k. Distribution and piping of Service air, Instrument air, Service water and Potable water inside STP area shall be in bidder's scope.
l. Bidder to arrange Drinking water of their own during E&C for their work force.
m. Disposal of all debris produced during erection & commissioning from the location to the identified place shall be in bidder scope

8. Exclusions

a. Chemicals are excluded from Bidder's scope
b. All civil work including foundation of equipment by BHEL. However, complete grouting for equipment, fixing and any concreting inside vessels, etc., shall be in the scope of bidder.
c. Civil Pedestals for pipe supports (if applicable as STP pipes will be burried) will be provided by BHEL. However, auxiliary structure, supports components for piping is in bidder's scope.
d. Air conditioning, ventilation & fire fighting facilities.
e. Refer to E, C&I specification for exclusions

f. Potable water, service water up to terminal points is by BHEL and further piping and termination as per requirement is in Vendor scope.

9. Civil

a. Complete civil design & civil construction drawings (including building architecture drawings) required for Sewage treatment plant package. Civil design for Sewage piping network to STP, Biodigesters, STP, & sewage treated water transfer shall also be in Bidder' scope.
b. Also civil works including operating / maintenance platforms and interconnection platforms (if any) with ladders / stairs & handrails, structural supports and hangers for pipes / cables / ducts, crane rails, all embedment's and inserts with lugs including anchor fasteners, bolts etc., dressing of foundations, grouting of pockets and underpinning of base plates for equipment / structures and fixing supports, filling and finishing of openings in walls, floors, cladding, roof and trenches shall be in Bidder's scope
c. Sewage piping from lifting stations to sewage equalization sump, all tanks, sumps in STP. Bidder to refer to relevant clauses of entire tender document for scope of sewage lifting stations, sewerage network etc.

10. Material handling requirements

a. Bidder shall provide required number of Electric hoist for STP.
b. Capacity of monorail hoists/ crane or chain pulley block wherever indicated are minimum and capacity of such hoists/ cranes etc. shall be suitable for handling 125% of maximum weight to be handled during erection and maintenance of the equipment in the pump house, buildings etc. as the case may be.
c. Bidder to refer to Hoists specification for guidelines for selecting cranes/ hoists

11. Additional notes for Erection & Commissioning

a. Water (Raw water) required for construction purposes will be provided at one single point within the plant area at free of charge for construction purpose and bidder has to make their own arrangement for further distribution by arranging required pipes, valves, pumps, etc.
b. Water (Raw water) for labour colony and staff colony shall be provided at single point on chargeable basis at the prevailing Government Tariff and bidder has to make their own arrangement for further distribution by arranging required pipes, valves, pumps, etc.
c. The construction power (415V, 3 phase) will be provided at a single point for construction purpose at free of charge by BHEL. Construction power shall be provided from the nearest Substation / tapping point within the plant premises. For the purpose of measurement of power consumed, the contractor shall provide Energy meter with valid calibration certificate. Distribution from this source to different locations is to be arranged by the bidder at their cost.
d. For the purpose of planning, contractor shall furnish along with tender the estimated requirement of power (month wise) for execution of work in terms of maximum kW demand.

e. Adequate water less urinals and biotoilet shall be arranged by the contractor within quoted rates, at site of construction with proper disposal arrangement.
f. Storage of electrodes shall be done in an air conditioned / controlled humidity room as per requirement, at their own cost by the contractor.
g. Adequate lighting facilities such as flood lamps, hand lamps and area lighting shall be arranged by the contractor at the site of construction, pre assembly yard and contractor's material storage area etc. at their cost.

SECTION-4

4.0 General requirements of specification

1. Approved Design memorandum (Drg.no. 4-WT-055-01388)
2. P& ID for STP System 1-WT-055-01590
3. Qualification requirement shall be as per tender specification specified elsewhere.
4. Bidder to refer to the specification for list of Mandatory spares and include the same in scope of supply **(Annexure-1)**.
5. Sub Vendor list shall be as per attached list **(Annexure-2)**. Bidder shall submit the list of finalized Sub Vendor for all the equipment during contract stage for approval by BHEL.
6. Quality plan shall be as per attached quality plan document **(Annexure-3)**. However, Bidder shall submit Quality plan for all the equipment supplied, services & works during contract stage for approval by BHEL.
7. Minimum list of drawings shall be as per attached master drawing list **(Annexure-4)**. However, bidder shall submit the list during contract stage for approval by BHEL.
8. Bidder shall submit the PG test procedure for Sewage treatment plant for approval and same shall be followed. Requirements are specified in **(Annexure-5)**
9. List of reference documents/ drawings which are part of this tender are provided as **Annexure-6**.
10. Project schedule for Sewage treatment plant shall be submitted by Bidder for approval. However, bidder to ensure to match with the overall project schedule of the BOP packages.
11. Refer **Annexure-7** for Technical requirements for Hoist
12. Refer **Annexure-8** for Quality Assurance requirements
13. Refer **Annexure-9** for List of Drawings & Documents to be submitted along with bid and after award of contract.
14. Bidder to refer to Painting Specification **Annexure-10** for meeting the requirements of this package.
15. Bidder to also refer to the General conditions of contract (GCC) and Special conditions of contract (SCC) (ROS:9065).
16. Bidder to refer to Health Safety and Environment plan for Site Operation by Subcontractors in **Annexure-11.**
17. Refer **Annexure-12** for Additional General Technical requirements
18. Refer **Annexure-13** for Engineering services requirements
19. Refer **Annexure-14** for Project Management and site services
20. Refer **Annexure-15** for Spares, Tools, Tackles & Consumables

21. Refer **Annexure-16** for Civil design specifications
22. Refer **Annexure-17** for General Specification for Erection & Commissioning.
23. Refer **Annexure-18** for General specification requirements from TSGENCO specification.
24. Refer **Annexure-A** Technical Deviation format
25. Refer **Annexure-B** for Compliance and confirmation schedule
26. Bidder to refer to relevant section of specification of Service air. Bidder to integrate with overall service air distribution piping and ensure distribution to required areas within this plant package.
27. Bidder to consider proper Packaging for shipping and storage at site and the procedure shall be duly submitted to Customer
28. Bidder shall furnish 3D model in editable format to ensure integration with overall 3D model of the Power plant.
29. Bidder shall provide AutoCAD files of all drawings.
30. Customer approved Design Philosophy & P&ID attached with this specification is minimum requirement and to be complied by Bidder. Bidder to design the equipment/system for safe and trouble free operation of Plant to meet the performance duty required by systems.
31. The Sewage treatment plant complete with all accessories shall conform to this technical specification, Design memorandum & PID. The decision of BHEL shall be final in case of any discrepancy.
32. All the instruments shall be supplied along with necessary fittings, accessories, valve manifold, root valves, Canopy & Structural steel as required. Instrument Installation, along with hardware shall be in bidder scope
33. The make shall be as per approved vendor list. The model of various instruments/items/systems shall be subject to approval of owner/purchaser during detailed engineering stage. No commercial implication in this regard shall be acceptable. In case of any conflict or repetition of clauses in the specification, the more stringent requirements among them are to be complied with.
34. Each valve/instrument shall be fitted with a stainless steel or aluminium nameplate indicating the valve/instrument service and reference number in accordance with the approved equipment coding system
35. All valves above 150NB shall be double flanged. All valves dimension standard shall be as per ASME B16.5 standards.
36. The above given scope is indicative & minimum. Any item/ equipment not indicated above however required for the completeness of the system shall be supplied by bidder without any technical, commercial and delivery implication to BHEL
37. Uniformity of make and type of instruments and control components shall be followed throughout for rationalization of spares' inventory, except for certain proprietary items where this requirement cannot be met.

SECTION-5

5.0 PUMPS & PIPING SELECTION CRITERIA

Sl. No.	Pipe Size	Velocity in m/sec		
		Below 50mm	**50mm-150mm**	**200mm & above**
1	Pump Suction for Water		1.2-1.5	1.2-1.8
2	Pump Discharge for Water	1.2-1.8	1.8-2.4	2.1-2.5
3	Header		1.5-2.4	2.1-2.4
4	Compressed Air Below 2Kg/cm2(g)	15-20	20-30	25-35
5	Compressed Air Above 2Kg/cm2(g)	20-30	25-40	35-45
6	Suction to compressor/Blowers		7-8	
7	Pump Suction for Chemical Solution	1.0-1.2	1.1-1.3	
8	Pump Discharge for chemical solution	1.2-1.4	1.3-1.5	
GRP PIPES				
9	For GRP Pipe with negative suction		1.2 (Max)	2 (Max)
10	For GRP Pipe with pressurized suction		1.5 (Max)	
11	For GRP Pipe Delivery		2.0 (Max)	2.0 (Max)

SECTION-6

6.0 IMPORTANT POINTS TO BIDDERS

1. If the vendor has suggestions/ requirements of any additional instruments/ equipment over & above as shown in the P & ID drawing, the same shall be clearly indicated and suitably covered in the commercial bid also separately.

2. The specification for the instruments/ equipment available in the main specification shall be taken for such additional requirements (or) Customer should be contacted.

COPYRIGHT AND CONFIDENTIAL
The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED;
It must not be used directly or indirectly in any way detrimental to the interest of the company.

BHARAT HEAVY ELECTRICALS LIMITED,
RANIPET- 632 406.

TECHNICAL SPECIFICATION FOR ELECTRICAL CONTROL & INSTRUMENTATION 5 X 800MW TSGENCO YADADRI TPS SEWAGE TREATMENT PLANT

				
07.08.2021	AJV	MKV	VNS	Fresh issue
Date	Prepared	Checked	Approved	Remarks

1. SPECIFIC TECHNICAL REQUIRMENTS (ELECTRICAL):

The equipment and services to be provided by bidder under this specification shall be as detailed here below but shall not be limited to the following:

a) Services and Equipment as per "Electrical Scope between BHEL and Vendor".
b) Any item/work either supply of equipment or erection material which have not been specifically mentioned but are necessary to complete the work for trouble free and efficient operation of the plant shall be deemed to be included within the scope of this specification. The bidder without any extra charge shall provide the same.
c) Supply of mandatory spares as specified in the specifications of mechanical equipment.
d) Electrical load requirement for STP.
e) All equipment shall be suitable for the power supply fault levels and other climatic conditions mentioned in the enclosed project information.
f) Bidder to furnish list of makes for each equipment at contract stage, which shall be subject to customer / BHEL approval without any commercial and delivery implications to BHEL.
g) Various drawings including GA drg, data sheet as per required format, quality plans, calculations, test reports, test certificates, operation and maintenance manuals, characteristic curves, wiring diagrams/schemes etc. shall be furnished as specified at contract stage. All documents shall be subject to customer / BHEL approval without any commercial implications to BHEL.
h) Motors shall meet minimum requirement of Electric motor specification (PE-DC-417-565-E003 Rev. No. 02)
i) Vendor to clearly indicate equipment locations and local routing lengths in their cable listing furnished to BHEL.

1.1. EQUIPMENT & SERVICES TO BE PROVIDED BY PURCHASER FOR ELECTRICAL & TERMINAL POINTS:

Refer "Electrical Scope between BHEL and Vendor given as Annexure-I".

1.2. DOCUMENTS TO BE SUBMITTED ALONG WITH BID

Bidder shall confirm total compliance to the specification without any deviation from the technical / quality assurance requirements stipulated. In line with this, the bidder as technical offer shall furnish signed and stamped copies of the following:

a) Standard Deviation Deposition Report/Deviations list attached elsewhere in specification/ Enquiry documents.
b) A copy of this sheet "Electrical Scope between BHEL and Vendor" with bidder's signature and company stamp.
c) Electrical load requirement.

Technical submittals such as copies of data sheets, drawings, write-up, quality plans, type test certificates, technical literature etc, are not required during tender stage. Any such submission even if made, shall not be considered as part of offer.

2. SPECIFIC TECHNICAL REQUIREMENTS (C&I):

a) Operation & Control of STP System shall be from STP PLC (BIDDER Scope) as well as through Backup Mimic Control Panel (BIDDER Scope).Detailed specification of PLC (KTPS VOLUME-VI, SECTION VI) and with respective PLC configuration diagram (4-WT-060-01143) consisting of master clock interface, dedicated OPC server, operator workstation, engineering workstation, Laptop, Optic fiber cables, PLB HDPE conduits, Light Interface units, FO patch cords etc are also part of the specification and bidder shall consider the same.

b) 3 No: of Remote I/Os to be considered for remote sumps. Remote I/O Panels shall be provided with push buttons, indicating lamps and annunciation system. Refer P&ID for RIO panel locations.

c) Backup Mimic control panel shall have coloured mimic indicating the complete P&ID with push buttons for pump/blowers/drives, LEDs for drive status, valve positions and tank levels & annunciation windows.

d) Uninterrupted power supply (UPS in bidder scope) of 2X10 KVA or 2X20 KVA(select nearest higher rating to the calculated KVA rating) shall be considered**.** Detailed specification of UPS (KTPS VOLUME-V B, SECTION XIV) and with respective single line diagram (PE-DG-417-145-I004 UPS SLD) is also part of the specification and bidder shall consider the same. BHEL shall provide 3phase 415 VAC power supply feeder from BHEL MCC.

e) Dual redundant Optic fibre communication (OFC) cables preferably of single mode type shall be considered in bidder's scope for communication from PLC to Central control room located in main plant power house area and from PLC to RIO panels. The cables shall be laid through HDPE conduits of size 25 NB with joint couplers, Optic termination kits/junction boxes so that the monitoring, control and operation of STP plant from CCR's are established as part of commissioning. A total length of 8 KM of OFC in vendor's scope.

f) Bidder to include all the instruments (PG, PIT, LIT, FIT, Analysers etc.) as indicated in P&ID as minimum and as required for the package along with necessary fittings, remote chemical seal diaphragm accessories and valve manifolds etc. **Instruments which are used for protection/CLCS shall be triple redundant, which are used for interlock and permissive shall be dual redundant and those used for alarm or indication shall be single.** Detailed specification of instruments and fittings is also part of the specification and bidder shall consider the same.

g) Motor operated valves shall be rated for 415 V three phase only. Refer Drive Control Philosophy (PE-DM-417-145-I002 Rev 03). Detailed specification of electric actuators is also part of the specification and bidder shall consider the same.

h) The junction boxes/LIE/LIR/Solenoid Valve boxes for termination of instruments / valve limit switches/Pneumatic tubings etc are in bidder's scope. Detailed specification of junction boxes/LIE/LIR/SOV Boxes are also part of the specification and bidder shall consider the same.

i) All Open-close type pneumatic operated valves shall be provided with limit switch (for both open and close feedback) and quick exhaust valves. Solenoid valves for operation of these valves shall be

grouped in solenoid valve (SOV) boxes. Detailed specification of Solenoid valve box is provided elsewhere in this specification. Pneumatic control valves, if any, shall be provide with SMART positioners and position transmitters. Refer Drive Control Philosophy (PE-ETP-417-145-I002 Rev 03). Positioner shall be Smart type with HART communication protocol, With regulating input as 2 wire 4-20 mA(24 V). Housed in cast aluminium casing (with polyurethane paint); IP65 degree of protection for enclosure. Material of accessories shall be SS. The allowable drift rate will be +2% of set point/ hour maximum. The positioner shall be mounted on the actuator. Air filter regulator shall be provided for each pneumatic control valves.

j) Bidder shall consider supply of Local control panel (LCP) for submersible pumps, as applicable, to interface between the PLC and the field devices for commands & feedbacks, associated valves and instruments. LCP shall have the provision of command (start/stop) & feedback interface with plant PLC. Detailed specification of LCP is also part of the specification and bidder shall consider the same. BHEL shall provide 415 VAC supply feeder at a single point for LCP. Further distribution to various motor shall be in Bidder's scope. Provision for separate Terminal block/wiring diagram for power and control blocks of control panel to be ensured. LCP shall have canopy and all required MCCB/MPCB, relay, contactor, terminals, HMI and readable/accessible components such as Illuminated push buttons, annunciators. All Push Buttons shall be illuminated type. 20% spare TB shall be provided and it shall be segregated for considering voltage level, analog, binary signal, annunciator signal etc. These requirements shall be considered in addition to that specified in LCP & JUNCTION BOXES SPECIFICATION.

k) Bidder to include necessary VFD drives for speed adjustment in his scope, if applicable. BHEL shall provide 415 VAC supply feeder at a single point for VFD. Any control supplies other than the above, if required by VFD, has to be derived by the Bidder and all necessary hardware/software for the same shall be in bidder's scope. Bidder to furnish electrical power requirement along with the bid in prescribed format. Refer to KTPS VOLUME-V A, SECTION XII for detailed VFD specification.

l) Panel dimensions shall be chosen liberally such that double door opening is available at front /rear or both at front & rear which shall be finalized during detailed engineering by BHEL to accommodate the panels within plant layout. Maximum single (half door) width acceptable is 600mm.

m) Vendor representative shall be available at site at the time of commissioning of the system and Vendor to delegate/depute their person/experts as per owner/consultant requirements.

n) The make/model of various instruments/items/systems shall be subject to approval of owner/purchaser during detailed engineering stage. No commercial implication in this regard shall be acceptable. In case of any conflict or repetition of clauses in the specification, the more stringent requirements among them are to be complied with.

o) Mandatory spare to be supplied by bidder.

p) The design, manufacture, inspection, testing, site calibration and installation of all C&I equipment and systems covered under this specification shall conform to the latest editions of applicable codes

and standards eg. ANSI, ASME, IEEE, ISO, IEC, IGCI, AWS, NFPA, AISC, IGS, SAMA, UBC, UL, NESC, NEMA, ISA, DIN, VDE, IS etc.

q) For instrument & control cable scope of supply refer 'Electrical scope sheet between BHEL & vendor

r) Instrument installation drawings are to be provided by bidder. All instrument fitting and erection hardware as per instrument installation diagram shall be in bidder's scope.

s) Every panel- mounted instrument, requiring power supply, shall be provided with a pair of easily replaceable glass cartridge fuses of suitable rating. Every instrument shall be provided with a grounding terminal and shall be suitably connected to the panel grounding bus.

t) The make of all the items shall be from approved sub-vendor list.

u) Bidder shall provide Cable Schedule in BHEL format provided in Electrical portion of the specification. Also, cable interconnections detail for complete system shall be in Bidders' scope.

v) Editable & PDF copy of Drawings/Documents and data to be furnished after award of the contract:

a. Control & operational write-up for the system, Recommended control scheme/ logic diagram, Process manuscript for implementation in PLC,List of Drives (Pumps, Agitators, Motorised valves etc)
b. I/O list (PLC) for each Stage1 & Stage 2
c. GA & wiring diagram of local control panel and its Power Requirement.
d. Local control panel and field instruments quality plan. Local control panel & instruments data sheet.
e. JB grouping document.
f. Cable schedule and cable interconnection drawing
g. Instrument schedule indicating range, operating pressure, flow etc along with selected make & model.
h. Alarm Schedule,SOE schedule
i. Instrument hook-up diagram.
j. Mandatory spare BOQ
k. Filled up Electrical Load data as per Attached Formats
l. Filled up UPS load list Attached Formats
m. Filled up Motor datasheets as per Attached Formats
n. Filled up Cable Schedule as per Attached Formats

Any other document decided during detailed engineering.

NOTES:

1. All equipment items shall be of latest design with proven on track record from reputed experienced manufacturers of specified type and range of equipment. The make/model of various instruments/items/systems and instrument sub-vendor shall be subject to approval of BHEL/Customer during detailed engineering stage.
2. The above given scope is indicative & minimum. Any item/ equipment not indicated above however required for the completeness of the system is to be supplied by bidder without any technical, commercial and delivery implication to BHEL.

3. Documents of C&I System shall be submitted to end user/owner for approval during detail engineering. Changes, if any, shall be accommodated by the bidder without any price/time implication.
4. Uniformity of make and type of instruments and control components shall be followed throughout for rationalization of spares' inventory, except for certain proprietary items where this requirement cannot be met.

2.1. HART HAND HELD CALIBRATOR

Hand held calibrators (Two nos. for each type) shall be provided for adjustment/ calibration/maintenance of the HART compatible transmitters. The hand held calibrator shall be suitable for all types of transmitters supplied in the package. If one type of hand held type calibrator is not suitable for communicating with all types of transmitters, then separate hand held calibrator shall be provided.

2.2. FIBRE OPTIC CABLE

(4 core, multi-tube, Armoured, Direct Burial 9µm/125µm SM FO cable)

Requirement is for PLB HDPE duct which shall be suitable for underground fibre optic cable installation by blowing as well as conventional pulling. The PLB HDPE duct shall be suitable for laying in trenches by directly burying, laying through G.I/RCC hume duct and laying through trench less digging.

Construction

The PLB HDPE duct shall have two concentric layers viz. outer layer and inner layer. The outer layer shall be made of HDPE material and the inner layer of solid permanent lubricant. These concentric layers shall be co-extruded and distinctively visible in cross-section under normal lighting conditions and generally conform to IS-9938. The colour of the PLB HDPE duct shall be blue with white stripes. In the finished PLB HDPE duct, the coextruded inner layer of solid permanent lubricant shall be continuous and integral part with HDPE outer layer and preferably be white in colour. The inner layer of solid permanent lubricant shall not come out during storage, usage and throughout the life of the duct. The duct shall be supplied in a continuous length of 1000meter in coil form, suitable for transportation, installation and handling purposes. The finished duct shall be of good workmanship such that the duct is free from blisters, shrink holes, flaking, chips, scratches, roughness, break and other defects. The duct shall be smooth, clean and in round shape, without eccentricity. The ends shall be cleanly cut and shall be square with axis of the duct.

The base HDPE resin used for manufacturing outer layer of duct shall conform to any grade of IS-7328 or IS 2530 or to any equivalent standard meeting the following requirement
a) Density (outer and inner layer): 940 to 958kg/m3 at 27°C. The density of completed PLB HDPE shall not differ by more than 0.003gms/cc from this value when tested as per IS:2530 or IS:7328.
b) Melt Flow Rate (MFR): 0.2 to 1.1 g/10 minutes at 190°C & 5 kg load. Performance requirement - generally as per IS 4984:1995 / IS 14151 / ASTM D-1693 IS 12235
a) Tensile Strength at Yield: 20 N/mm2 minimum
b) Crush Resistance at approx. 50Kg load, deflection not greater than 10% with load on and deflection not greater than 2% (after recovery)

c) Impact resistance as per IS:12235 – No crack or split
d) Environmental Stress Crack resistance as per ASTM D-1693 – No failure

General:
The HDPE duct shall in general conform to the following standard and the technical specifications as applicable
a) IS: 4984 / IS: 2530 / IS:14151/(part1) / IS:9938 / IS:7328 / IS12235(Part-9) /IS:5175
b) TEC-spec no. GR/CDS-08/03/Mar-11 -HDPE duct for use as duct for optical fibre cable.
Marking: Manufacture's name or trade mark, Year of manufacturing, Type of PLB HDPE duct and size, Running length marking.
Immunity: The cables shall be immune to corrosive element found naturally in the ground.
Life of cable: The minimum expected life of the cable shall be 25 years.
Length of the cable drum: The length can be standard factory length. Care to be taken to minimize wastage while cutting to length by optimizing drum lengths in line with site requirement. Drum to have a tolerance of +5%. Proper End plugs to be provided per drum
32/26mm PLB HDPE DUCT
The nominal size of the duct shall be 32mm and shall meet the following requirements.
(i) Outside diameter 32mm + 0.3mm
(ii) Wall thickness 3mm +/-0.2 mm
(iii) Thickness of permanent lubricant >0.2mm
(iv) Lubrication – Permanently lubricated for blowing of Optical fibre cable
(v) Standard length 500m or 1000 meters nominal
COMMON SUPPLY:
i. **Push fit Couplers** to provide durable airtight joint be provided. QUANTITY –**1 No. per 75m** length of Duct
ii. End Plugs **1 No. per 350m** and Cable sealing plugs **1 No. per 250m** should be included
iii. **2 Nos. each** Duct Cutters and C-Spanner to be included per supply.

Manufacturer's Datasheet and QAP shall be submitted before manufacturing.

Test Certificates for Dimensional conformance, Raw material conformance (Density and flow rate) and Performance conformance shall be provided with datasheet

Packaging & Forwarding - Acceptable tolerance is +5% per drum per standard packing length. Vendor shall ensure adequate packaging to protect the drums /other boxes against damage during transit. Proper End caps to be provided per drum.

2.3. TECHNICAL SPECIFICATION -WATER SYSTEM RELATED SPECIAL INSTRUMENTS

2.3.1. RESIDUAL CHLORINE ANALYZER (If Applicable)

Type	Amperometric
Electrode	Platinum / Gold and copper electrode shall be provide with cell cleaning system
Indication	LCD in analyzer panel
Range	0 to 20.0 mg / L (ppm)

Accuracy	2% or better
Sensitivity	0.01 mg / L
Output signal	4-20 mA DC (isolated) into 600 ohms
Alarm annunciation	Dual Alarm setpoints (240V AC, 5A) (Field adjustable)
Calibration	Zero and span adjustment Final calibration / adjustment of analyzer to be done at site and duly verified by titration.
Temp. Compensation	0-50 °C
Sample drain	Yes
Enclosure	Stainless Steel (IP-65)
Power supply	240 V AC, 50 Hz, 1 Phase (through UPS)
Accessories	Chemical Reagents

2.3.2. VARIABLE AREA (MAGNETIC TYPE) METAL TUBE ROTAMETER / FLOW INDICATING TRANSMITTER(if Applicable)

For flow measurements, the maximum operating flow will be within 70 to 80% of the Maximum scale range.

Type	Online-Flange mounting
Application	Chemical medium as per process requirement
Metering Tube	Metal Tube with Indicator Box and 4-20mA transmitter output (Two wire- 24 V DC)
Float MOC	SS316/Suitable for the chemical medium handled
MOC of Metal Tube and Indicator Box	Stainless Steel - Weather proof IP 55 construction or better.
Graduated Scale	Engraved black on white background. The lower-range value shall be considered within 10-15% of the upper range value. Value of the nearest range as per Table. 4-20mA output to be configured as LINEAR. 4mA=Lower range value 20mA=Upper range value
Process connection	Pipe Size & MOC of wetted parts: (PVDF lined SS316 tube MOC for H2So4 & Hcl) (SS316 tube MOC for chemical service. Flanged connection: ANSI B16.5 Class 150 at both ends. Both inlet and outlet flanges shall be in same axis. Process flow: Inlet- Down and Outlet-Up.
Temperature	Ambient 25 to 35 Deg C
Accuracy	+/-2% of Full Scale or better
Power Supply	24 V DC

2.4. TECHNICAL SPECIFICATION –SOLENOID VALVE BOX

2.4.1. GENERAL REQUIREMENTS:

a. Each variant of the SVEB shall be supplied with required no. of Solenoid Valves (SOV), Air Filter cum Regulator (AFR), tubing with necessary fittings, isolation valves,mounting fasteners, internal wiring, Terminal Blocks (TBs) etc.
b. The solenoid valve coil wires shall be terminated in a terminal block located inside the enclosure box.
c. The inlet ports of the solenoid valves shall be connected to a common inlet manifold to which the air supply shall be made through the AFR.
d. The outlet / vent connections of the solenoid valve shall also be connected using SS 316 double compression type bulkhead tube fittings.
e. Stickers have to be fixed for the SOV to indicate tag number. Separate Tag plates shall be mounted with plate screws for each outgoing impulse tube .Tag numbers shall be legibly inscribed on the tag plates.
f. For airline tubing from SOV boxes to pneumatic actuator copper tubes shall be considered. The copper tube shall have uniform OD of ¼ inch. The copper tubes shall be PVC sheathed. All the threaded tube fittings offered shall be of the NPT type threading. The fittings to be used with copper tubes shall be of brass, Compression type. All the above tubing and necessary fittings are in bidders scope.

2.4.2. TECHNICAL REQUIREMENTS

a.	Enclosure material & Removable gland plate	4 mm FRP sheet(UV stabilised)
b.	Enclosure protection:	IP 65 as per IEC 60529
c.	Terminal block type & arrangement:	Rail mounted cage-clamp type suitable for conductor size upto 2.5 mm2. A M6 earthing stud shall be provided
d.	Terminal block insulating material:	Melamine
e.	Terminal block voltage grade :	650 V (Minimum)
f.	Mounting plate	SS, minimum 2 mm thickness
g.	Door Gasketing:	Neoprene gasket 6 mm thick
h.	Door Opening:	Hinged, lockable type
i.	Number of earthing terminals:	Two. Just above the earthing terminal Symbol to be provided, black lines on yellow background
j.	All fasteners supplied	SS 316
k.	Canopy	To be provided
l.	Cable entry	Bottom Entry drilled on Cable Gland Plate. Refer Annexure for gland size. Double compression type Gland in scope of supply of bidder.
m.	Mounting	Mounting brackets and SS fasteners to be provided

2.4.3. TERMINAL BLOCK

Suitable DIN rails along with clamps and screws shall be provided for terminal block mounting .All terminals are to be numbered serially by suitable identification label of PVC material in white background with black numbers. Terminal blocks shall be fixed to T.B supporting DIN rail by means of suitable end plates with screws. Common connections shall be limited to 2 (two) wires per terminals

Terminal block type & arrangement : suitable for 2.5 sq mm cable, DIN rail mounted, Melamine type having voltage grade 650 V (Minimum)

2.4.4. SOLENOID VALVE:

a.	Quantity	As required
b.	Type	3/2 or 5/2 or 2 way single coil Solenoid valve (as applicable)
c.	Body	SS
d.	Plunger/trim	SS316
e.	Coil Enclosure	SS316,IP 65
f.	Needle valve	¼" to be provided for each SOV
g.	Pressure range	4 to 7 Kg/sq. cm
h.	Duty	Continuous
i.	Coil Voltage	24 V DC
j.	Class of insulation	" H"
k.	Manual override	Required for each SOV
l.	Shut off class	tight shut off
m.	Power	Low power type Solenoid Valves shall be considered.

2.4.5. AIR FILTER CUM REGULATOR (AFR)

a.	Quantity	One for each solenoid valve box
b.	Type	Automatic Drain
c.	Inlet Pressure	4 – 7 Kg / sq. cm
d.	Filtering particles	> 5 microns
e.	Filter Element	Sintered bronze

f.	Output pressure	0 – 7 Kg / sq. cm
g.	Output Gauge Range	0-10 Kg/sq.cm
h.	Output Pressure Gauge	50 mm Diameter dial(min)
i.	Blow down valve	To be provided
j.	Air connection Inlet	suitable SS316 end fittings to be provided for 1/2" NPT SS tube

2.5. DOCUMENTS TO BE SUBMITTED ALONG WITH BID

Bidder shall confirm total compliance to the specification without any deviation from the technical / quality assurance requirements stipulated. In line with this, the bidder as technical offer shall furnish signed and stamped copies of the following:

d) SDDR of Enquiry documents.

e) A copy of this sheet "PLC configuration diagram (4-WT-060-01330) & "UPS single line Diagram (PE-DG-417-145-I004)" with bidder's signature and company stamp.

Technical submittals such as copies of data sheets, drawings, write-up, quality plans, type test certificates, technical literature etc, are not required during tender stage. Any such submission even if made, shall not be considered as part of offer.

3. LIST OF ENCLOSURES

a) Annexure-I: General Requirements Control & Instrumentation
b) Annexure-II: Field Instrumentation & Analysers Specification
c) Annexure-III: LCP And Junction Boxes Specification
d) Annexure-IV: Erection Hardware
e) Annexure-V: Lt Motor Specification
f) Annexure-VI: Drive Control Philosophy
g) Annexure-VII: Programmable Logic Controller(PLC)
h) Annexure-VIII: Uninterruptible Power Supply(UPS)
i) Annexure-IX: Electric Actuator
j) Annexure-X: Fibre Optic Cable(OFC)
k) Annexure-XI: Variable Frequency Drive
l) Annexure-XII: Electrical Scope Between BHEL And Vendor
m) Annexure-XIII: Electrical Load List Format
n) Annexure-XIV: Standard Quality Plan
o) Annexure-XV: Instrument Schedule Format
p) Annexure-XVI: Cable Schedule Format

GENERAL REQUIRMENTS
CONTROL & INSTRUMENTATION

1.00.00 **INTENT OF SPECIFICATION**

1.01.00 This part of the specification is intended to provide the technical guidelines for the fully coordinated Control & Instrumentation system with auxiliaries and accessories ~~for the 1 x 800 MW Stage-VII , Unit # 12 Kothagudem Thermal Power Station for Telangana State Power Generaton Corporation Ltd. (TSGENCO).~~.The duty of services specified below and in other drawings and documents forming part of this specification are considered required for safe, reliable, trouble free and efficient operation with adequate maintenance facilities as per modern power station practice and as per terms and conditions enumerated in this specification.

1.02.00 DELETED

1.03.00 In conformity with the guidelines provided in the specification, the scope of works shall completely cover all the Control & Instrumentation equipment, functions, activities and documentation specified under the accompanying Technical Specifications and shall not be limited to the following:

a) Detailed design and engineering of the manufactured equipment; system integration and system engineering.

b) Complete manufacture including shop testing before shipment.

c) Specifying, procurement, quality inspection of bought-out items from sub-suppliers. Design co-ordination for and integration with bought-out items with sub - suppliers.

d) DELETED

e) Providing engineering drawings, documents, licensed copy of software and developmental tools, data, instruction, operation and maintenance manual etc. for Owner's review/ approval / record.

f) Arranging for Owner's inspection and testing of manufactured as well as bought-out items at the respective works.

g) Packaging and transportation of instruments, equipment, accessories and erection hardware from the manufacturer's works to the site, including transit insurance.

h) DELETED

i) DELETED

j) DELETED

k) Pre-assembly (if any), erection, testing and commissioning of all the equipment and instruments supplied, in totality.

l) Performing availability tests and Performance and Guarantee tests.

m) Prepare and submit approved & as-built drawings and documents in hard and soft copies.

n) Furnishing of spares, tools and tackle and test instruments.

o) Fulfilling post-commissioning liabilities.

p) Arranging for the training of Owner's personnel of different categories at manufacturer's works as well as plant site.

q) Other activities detailed in subsequent sections of the Specification.

r) Any other activity, not mentioned explicitly, but felt essential by Bidder for successful completion of work.

1.04.00 The requirements enumerated in this specification are qualitative in nature and are based on typical configuration of the plant for the purpose of bidding. It shall be the responsibility of Bidder to offer Control & Instrumentation system to meet the actual functional requirements of the plant offered.

1.05.00 DELETED

1.06.00 DELETED

1.07.00 PLC / microprocessor based standalone control and monitoring systems shall be provided ~~for offsite packages~~ .Opeartor workstations & Back up control panels / desks shall be located in local control room as operator interface . Also suitable servers / soft links (OPC) and time synchronization including all required software & hardware shall be provided for all PLC / ~~microprocessor based offsite packages~~ for interfacing with plant Master Clock System (MCS) and DDCMIS for monitoring and limited control. Separate OPC server shall be provided for ~~off-site~~ PLCs to export the plant data to MIS / ERP requirement.

1.08.00 All OPC links shall be redundant bidirectional and HAD (Historical Data Access) - AE (Alarms and Events) based. In general all softlinks shall be dual redundant.

1.09.00 It is not the intent to completely specify the details of design and construction features herein. Nevertheless, the instruments / equipment and their installation shall conform to high standards of engineering design and workmanship in all respects.

1.10.00 In the event of conflict between requirements of any two clauses of this specification / documents or requirements of different codes / standards specified, the more stringent requirements as per the interpretation of the Owner shall apply.

2.00.00 **GENERAL PERFORMANCE REQUIREMENT**

2.01.00 Control & Instrumentaion equipment shall be guaranteed to meet the performance, functional and accuracy requirements enumerated in the specification.

2.02.00 Control & Instrumentation equipment shall be guaranteed against manufacturing defect for at least two (2) years from the date of handing over to Owner.

2.03.00 The guaranteed performance criteria shall be met in full during the guarantee period.

2.04.00 Any predictable or planned deterioration and / or obsolescence of equipment shall be clearly brought out in the Bid.

2.05.00 Control & Instrumentation equipment shall be capable of maintaining the specified performance and accuracy standard over the complete regime of operation of main equipment, taking into account the excursion of parameters during emergency or malfunction of main equipment.

2.06.00 In the event of loss of a major plant equipment, controls shall be coordinated to ensure that the plant is automatically brought to a safe holding condition consistent with maintaining maximum safe generation permissible under reduced plant availability.

2.07.00 Control & Instrumentation system shall not impose any limitation or constraint on the operation of the main equipment. It shall be possible to utilize any in-built over capacity in design of an equipment with complete controllability and observability.

2.08.00 The control system shall be designed to prevent abnormal swings due to loss of control power, instrument air, failure of any system component, open/short circuits or any other such failure or degradation in the system and shall drive the plant and equipment to fail safe condition.

2.09.00 All modulating devices shall be in stay put condition during any of the above failures if not otherwise asked in the control philosophy.

2.10.00 Mean Time Between Failure (MTBF) of the instruments shall be considerably higher than the equipment they shall cater to in order to avoid shutdown on account of instrumentation failure.

2.11.00 Bidder shall introduce redundant control equipment or instruments wherever it is felt that the introduction of the same may lead to reduction of downtime of plant and equipment, in addition to the cases clearly identified in the specification.

2.12.00 In cases where continuous monitoring of performance of equipment is envisaged, Bidder shall supply instruments of suitable accuracy class to meet the accuracy requirements of the calculation as per ASME standard.

2.13.00 All instruments and control equipment shall ensure high reliability, low downtime and ease of maintenance.

2.14.00 Protective systems and their safety features shall be guaranteed to ensure the main equipment safety in the event of tripping, maloperation and malfunction.

2.15.00 The performance guarantee shall be on complete system basis as well as on the basis of isolated, individual instrument or component.

2.16.00 Bidder shall replace all instruments failing to meet the performance stipulations of the specification at any stage of the project.

2.17.00 All instruments / equipment shall be capable of performing satisfactorily in continuous commercial operation conforming to all relevant codes and regulatory requirement under the specified environmental conditions.

2.18.00 In general, equipment located in air condition environment shall be capable of operating without any degradation of performance or damage for at least twelve (12) hours to keep the plant in running condition in case failure of air conditioning units. For any equipment or component that cannot conform to this requirement, Bidder shall consider back-up packaged split type air conditioning unit/s.

2.19.00 Trial Operation

The trial operation shall be conducted by Bidder as per the stipulation of this specification which shall be witnessed and signed off by Owner.

2.20.00 Performance and guarantee test

Bidder shall perform the tests for performance and guarantee as per the stipulations of this specification.

2.21.00 Performance and Guarantee Test Procedure

Bidder shall perform the tests for performance and guarantee as per the stipulations of the specification

Bidder shall guarantee that the Control System shall be responsive and stable and shall maintain the deviation of controlled variables from set point within the limits specified in the specification. Bidder shall operate the unit fully in automatic mode with no intervention from the operator. Bidder shall successfully demonstrate the performance of the Control Systems as per attached table before acceptance and taking over by Owner.

2.22.00 Total System Availability

Bidder shall guarantee the total system availability of 99.7% by selecting suitable components and by judicious incorporation of redundancies.

3.00.00 **GENERAL DESIGN REQUIREMENTS**

3.01.00 Equipment and system shall be designed and constructed to perform accurately and safely under the environmental and operating conditions described or implied in this specification without undue heating, vibration, wear, corrosion.

3.02.00 Equipment and systems shall be supplied from latest proven product range of reputed experienced manufacturer whose successful performance has been established by a considerable record of satisfactory operation in large capacity coal fired thermal power stations. Bidder shall obtain Owner's approval for the selected manufacturers for critical items.

3.03.00 The equipment, systems and accessories furnished shall be designed and constructed to meet the all specification requirements and performance specification during the continuous service life of the plant. Equipment or components that cannot meet these requirements shall be identified in the Bid and their expected failure rate be indicated. Otherwise, it shall be deemed that the equipment or components are suitable for the service life of the entire plant.

3.04.00 Bidder shall indicate the year in which the offered models of the instruments and control system have been introduced and how long the commercial production of the same is expected to continue. In any case, Bidder shall ensure supply of spare parts for lifetime of the plant. In case if it is felt by Bidder that certain equipment/components is likely to become obsolete, Bidder shall clearly bring it to the notice of Owner and indicate step proposed to deal with such obsolescence like maintaining "bonded spares" with the manufacturer/s.

3.05.00 Any part/module of the C&I system which are not listed under recommended spares shall be deemed as having life expectancy not less than the expected life of the plant i.e. 30 years.

3.06.00 Bidder shall supply proven latest version of hardware and software available at the time of system designing. All software user licenses shall be valid for entire life of power plant. User should not have to pay any recurring license fee during the usage period of the system. In case of future up-gradation of software, Bidder shall remain committed to upgrade the supplied system at per with the new version within the warranty period and ensure successful integration of the system without any additional cost to owner. Beyond the warranty period and during the remaining life of the plant, any upgradation in hardware and software shall be brought to the notice of Owner indicating whether it shall be possible to upgrade the system by partially replacing,

3.07.00 All C&I equipment like field instruments eg. transmitters, switches, positioners etc., shall be of latest models.

3.08.00 For the sake of completeness of the system and in order to ensure desired performance & safety measures, any hardware or software item felt required, shall be in the scope of Bidder irrespective of their explicit or implicit inclusion in this specification .

3.09.00 All the modules of the control and monitoring system including for ~~DDCMIS~~ / PLC / Proprietary control system shall be from latest procuct range and from same family only.

4.00.00 **GENERAL TECHNICAL REQUIREMENTS**

4.01.01 Control & Instrumentation system design will aim at high availability, fuel efficient performance, plant & personnel security and high level of automation with minimum deployment of operational manpower.

4.02.00 Uniformity of make and type of instruments and control components shall be followed throughout for rationalization of spares' inventory, except for certain proprietary items where this requirement can not be met. Bidder shall , however take the Owner's approval on the make and type during detailed engineering for such proprietary items .

4.03.00 In general, the plant operation shall not depend on local measurement or local manual operation.

4.04.00 DELETED

4.05.00 Transmitters shall be SMART type and of unform make . Each SMART equipment shall communicate in the form of analog signal 4-20 mA DC with superimposed digital signal, zero adjustment, calibration and diagnostic from remote location. Two no. HART portable communicator ~~for each offsite package and five nos. for BTG and auxiliaries~~ shall be supplied.

In general transmitters shall be used instead of switches.

4.06.00 Power supply for Transmitters, contact interrogation, interposing relay and solenoid shall generally be ungrounded 24V D.C only. Power supplies for

interrogation, relay and solenoid shall be provided from the control systems viz. DDCMIS , PLC , proprietary control systems . In all cases redundancy in power modules shall be considered.

4.07.00 When more than one device utilizes the same signal, the signal source shall meet such signal requirement and with proper isolation and without overloading. Short circuiting or grounding of one device shall not have any perceptible influence on any other consumer point nor shall change the transmitter calibration.

4.08.00 DELETED

4.09.00 Electronics located outside control room areas shall be tropicalized and enclosed in dust & weatherproof cabinets suitable for the environment.

4.10.00 Local instruments shall be provided in cases where these are required for maintenance, commissioning and recommissioning of major equipment or for calibration and setting of other instruments and for equipment safety. All equipment like field instruments like transmitters, switches, positioners etc., shall be of latest models

4.11.00 In general, instruments installed outdoors and in areas where these may be exposed to Heat , Dust , splashing oil, water, steam etc. shall be mounted in closed type enclosures. For other areas (indoor), open type racks may be used.

4.12.00 Drain from instrument rack/enclosure shall be routed to nearby plant drainage system.

Temperature measurement shall have up scale / down scale drive to protect from process upset in case of sensor failure. Both the elements of duplex temperature sensors shall be terminated to junction boxes. For RTDs ring - tong type lugs shall be used at Junction Boxes ,especially for motor winding temp JB, Motor bearing temperature JB at both motor end and at field local JB end.

4.13.00 In general, for temperature measurements up to 300°C, Platinum resistance temperature detectors shall be used unless the area is prone to vibration. For temperature measurement above 300°C up to 750°C, Chromel-Alumel (K) type thermocouple shall be used. For high temperature applications, noble-

metal thermocouple (TC) such as Pt Rh-Pt (R) type in inconel sheathed thermowell shall be used. For lower temperature with vibration prone areas Iron Constantan (J) / Chromel constantan (E) type thermocouples shall be used .

4.14.00 Temperature elements shall be in sheath tube and in thermowells of suitable material. Thermowell made of Tungsten carbide shall be used for highly abrasion application. In all flue gas path , thermo wells shall be provided with protecting semicircular SS pipe to protect against erosion

4.15.00 Temperature elements shall be directly connected to their respective input modules through compensating cables. For Boiler Metal temperature measurement Remote I/O or for bulk data acquisition shall be provided for monitoring in DDCMIS.

4.16.00 In general, temperature switching function shall be configured by use of temperature elements and software configured limit value monitors instead of using conventional field mounted temperature switch.

4.17.00 The instruments and control equipment shall be logically grouped in electronic cabinets in functional order for convenient fault location, troubleshooting and maintenance.

4.18.00 Equipment and devices, which require maintenance, shall be suitably located to ensure easy accessibility.

4.19.00 On-line automatic periodic testing, self-checking & diagnostic facility shall be provided with fault indication for easy identification of the faulty module. The system shall continuously check health of the component elements including the stand-by ones and shall permit carrying out of the on-line checks while maintaining safe condition of the plant without endangering the safety of equipment and without influencing the process being controlled.

4.20.00 Failure of equipment used for alarm & trip purposes shall initiate alarm.

4.21.00 Automatic unadministered switchover to standby equipment (such as fan /blower /pump) is foreseen in case of either running equipment is not adequate to maintain the desired process condition or due to tripping of running equipment.

4.22.00 End positions of manually operated suction valves of critical pumps and all other manual operated critical isolation valves shall be monitored & interlocked.

4.23.00 In case of HT motors, winding temperature for each stator winding and bearing temperature of motors & driven equipment shall be monitored for abnormal rise. For monitoring of such temperature in a local panel where no operator station has been provided suitable electronic display device driven by output of DDCMIS / PLC system shall be provided.

4.24.00 DELETED

4.25.00 Electrical drives rated at 30 KW or more and for crital drives including all lub oil pumps, fuel oil pumps current rated at less than 30 KW shall be monitored for current in DDCMIS.

4.26.00 Process fluids shall not be piped directly in to Central Control Room (CCR) and Electronicl Equipment Room (EER) areas.

4.27.00 Ergonomically & aesthetically designed furniture viz. control desks & chairs shall be provided for workstations, programming stations, PCs and various peripherals at control room/computer room/equipment room. Furniture shall include documentation racks, tables for laydown etc.

4.28.00 KKS identification system shall be adopted consistent with the plant equipment numbering system.

4.29.00 DELETED

4.29.01 DELETED

4.29.02 DELETED

4.29.03 DELETED

4.30.00 DELETED

4.30.01 DELETED

4.31.00

4.31.01 DELETED

4.31.02 DELETED

4.31.03 DELETED

4.31.04 DELETED

4.31.05 Common DDCMIS nework shall also control and monitor packages envisaged for PLC based local control systems. Operator workstations shall be provided in CCR for the overall control and monitoring through this netework. Such links (OPC) with Common DDCMIS are largely foreseen as Optical Fiber redundant bidirectional data hiways. as applicable as indicated in configuration drawing

4.32.06 DELETED

4.32.07 In general no relay based control system is acceptable. These shall be either DDCMIS or PLC based only.

4.32.00 DELETED

4.32.01 DELETED

4.34.00 DELETED

4.35.01 DELETED

4.35.02 DELETED

4.36.00 DELETED

4.36.01 DELETED

4.37.00 DELETED

4.38.00 DELETED

4.39.00 DELETED

4.40.00 DELETED

4.41.00 DELETED

4.42.00 DELETED

4.43.00 DELETED

4.44.00 DELETED

4.45.00 Local Instruments , Flow Elements and Control Valves

Required local instruments including gauge boards, etc. and Flow Elements , Control valves shall be provided for safe and efficient operation of the plant. .

4.46.00 Erection Hardware

Standard and good engineering practice of international standard shall be adopted throughout. All materials supplied shall be suitable for tropical, dust laden, humid power plant environment and shall be from reputed manufacture.

4.47.00 C&I Cabling

Instrumentation cables shall be copper, overall screened for binary signals and individual pair and overall screened for analog signals. All cables shall be FRLS type (inner and outer sheath) ,armored, other than short run cables which may be unarmored. Unarmored cables shall run through conduits.

C&I cable type shall also include FO , Prefab , Coaxial , compensating cable , special cable etc

The screen shall be grounded at the remote panel end at control / equipment room only.

5.00.00 CODES AND STANDARDS

The design, manufacture, inspection, testing, site calibration and installation of all C&I equipment and systems covered under this specification shall conform to the latest editions of applicable codes and standards eg. ANSI, ASME, IEEE, ISO, IEC, IGCI, AWS, NFPA, AISC, IGS, SAMA, UBC, UL, NESC, NEMA, ISA, DIN, VDE , IS etc. Generally, the following latest edition of codes and standards prevailing at the time of award of contract shall be applicable.

1) Temperature Measurement

   a) Instrument and apparatus for temperature measurement - ASME PTC 19.3 (1974).

   b) Temperature Measurement - Thermocouples - ANSI - MC 96.1 - 1982.

   c) Temperature Measurement by electrical resistance thermometers - IS: 2806

   d) Thermometer-element-Platinum resistance - IS: 2848 / DIN 43760.

2) Pressure Measurement

   a) Instrument and apparatus for pressure measurement - ASME PTC 19.2 (1964).

   b) Bourdon tube pressure and vacuum gauges - IS: 3624/1996.

3) Flow Measurement

   a) Instruments and apparatus for flow measurement - ASME PTC 19.5 (1972) Interim supplement, Part-II

   b) Measurements of fluid flow in closed conduit - BS 1042.

4) Electronic Measuring Instruments and Control Hardware

   a) Automatic null balancing electrical measuring instruments -ANSI C 39.4 (Rev. 1973), IS 9319

   b) Safety requirements for electrical and electronic measuring and controlling instrumentation - ANSI C 39.5 / 1974.

   c) Compatibility of analog signals for electronic industrial process instruments - ISA-S 50.1: ANSI MC 12.1 / 1975.

   d) Dynamic response testing of process control instrumentation - ANSI MC 4.1 (1975) - ISA -S26 (1968).

   e) Surge withstand capability (SWC) tests - ANSI C 37.90A (1989), IEC-255.4.

   f) Printed circuit boards - IPC TM-650, IEC 326C.

   g) General requirements and tests for printed wiring boards - IS-7405 (Part-I)/1973.

   h) Edge socket connectors - IEC 130-11.

   i) Requirements and methods of testing of wire wrap terminations--DIN 41611 Part-2.

   j) Dimensions of attachment plugs and receptacles- ANSI C73-1973.(Supplement ANSI C73a – 1980)

   k) Direct Acting Electrical Indicating Instruments - IS - 1248 - 1968

5) Instrument Switches and Contacts

   a) Contact Rating - AC services NEMA ICS Part-2 125, A-600

   b) Contact Rating - DC services NEMA ICS Part-2 125, N-600

6) Enclosures

   a) Enclosures for Industrial Controls and Systems–NEMA ICS-6-110.15 through 110.22

   b) Racks, panels and associated equipment -EIA: RS-310-B-1983 (ANSI C83.9 - 1972) / IEC 60947 / IEC 60529

   c) Protection Class for Enclosures , Cabinets Control Panels and Desks - IS 2147 1962

7) Apparatus, Enclosures and Installation Practices in Hazardous Area

   a) Classification of hazardous area - NEMA Article 500, Volume-6, 1978./ NFPA Article 500 , Vol.70-1984

   b) Electrical Instruments in hazardous dust locations - ISA-RP 12.11.

   c) Intrinsically safe apparatus - NFPA Article 493 Volume-4 1978.

   d) Purged and pressurized enclosure for electrical equipment in hazardous location - NFPA Article 496 Volume-4, 1982.

8) Sampling System

   a) Stainless Steel material of tubing and valves, for sampling system - ASTM A 269-79 GRTO-316.

   b) Submerged helical coil heat exchangers for sample coolers -- ASTM D11-98.

   c) Steam and water sampling ,conditioning and analysis in the power cycle - ASME PTC - 19.11

   d) Standard methods of sampling system - ASTM D 1066-69

9) Annunciators

   a) Specifications and guides for the use of general-purpose annunciators - ISA RP 18.1.

   b) Surge withstand capability tests -ANSI C37.90 a -1971 and IEEE Standard 472-1974.

10) Interlocks, Protections

   a) Relays and relay system associated with electric power apparatus - IEEE Standards 3.13.

   b) Surge withstand capability tests - ANSI C37.90 a - 1971 and IEEE Standard 472-1974.

   c) General requirements and tests for switching devices for control and auxiliary circuits including contactor relays - IS-6875 (Part-I)/1973.

   d) Turbine water damage prevention - ASME-TDP-1-1980.

   e) Boiler safety interlocks - NFPA Section 85B, 85D, 85E, 85F, 85G.

   f) Installation and operation of Pulverized fuel system - ANSI / NFPA 8503

   g) Functional diagramming of Instrument and control systems - SAMA PMS 22.1

   h) Digital interface for programmable instrumentation - ANSI / IEEE 488

11) Control Valves

a) Control valve sizing (Incompressible fluids) - ISA-S39.2 / 1972.

b) Control valve sizing (Compressible fluids) - ISA-S39.4 / 1972.

c) Control Valve seat leakage – ANSI / FCI 70.2

d) Face to face dimensions of Control Valves - ANSI B16.10

e) Control Valve Capacity Test Procedure – ISA – S75.02

12) Process connection Piping and Tubing

a) Seamless Carbon Steel Pipe - ASTM-A-106.

b) Forged carbon steel fittings - ASTM-A-105.

c) Dimensions of fittings - ANSI-B16.11.

d) Code for pressure piping, welding, hydrostatic testing - ANSI-B 31.1.

e) Nomenclature for instrument tube fittings - ISA-RP 42.1 / 1982.

f) Seamless Stainless Steel Tube ASTM A-213 TP 316 / ASTM A-269 TP 316

g) Seamless Alloy Steel Pipe ASTM A 335 P22

h) Seamless Stainless Steel Pipe ASTM A-312 TP 316

i) Forged and Rolled alloy steel pipe flanges , forged fittings , valves and parts ASTM A - 182

j) Pipe fittings of wrought carbon steel and ally steel - ASTM A - 234

k) Composition bronze metal castings ASTM B - 62

l) Seamless copper tube , bright annealed ASTM B- 168

m) Valves flanged and butt welding ends ANSI B 16.34

13) Cables

a) Thermocouple extension wires / cables - ANSI MC96.1.

b) Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy-IPCEA S-61-402

c) Guide for design and installation of cable system in power generating station (insulation, jacket materials) -IEEE Standard 422.

d) Requirements of vertical tray flame test - IEEE 383

e) Standard specification for tinned soft or annealed copper wire for electrical purpose - ASTM B33.

14) Electronic Cards, Subassemblies and Components

a) Unpackaged

i)	Vibration	:	IEC-68.2.6
ii)	Shock	:	IEC-68.2.27
iii)	Drop & Topple	:	IEC-68.2.31

b) Packaged

Vibration, Drop & Static Compression - NSTA.

c) Electromagnetic Compatibility

i)	Electrical Fast Transient	:	IEC-801.4
ii)	Surge Withstand	:	IEC-255.4
iii)	Radiated Electromagnetic Field	:	IEC-801.3
iv)	Electrostatic Discharge	:	IEC-801.2
v)	Electromagnetic Emissions	:	VDE 0871, Class-B

15) Cable Trays, Conduits

a) Guide for the design and installation of cable system in power generating station (cable trays, support systems, conduits)- IEEE Standard 422, NEMA VE-1, NEC-1981. Test Standards NEMA VE-1-1979.

b) Galvanizing of carbon steel cable trays - ASTM A-386.

Codes and standards as described in different subsections of this specification shall also be followed .

Items such as thermowells, control valves, flow elements and other in line devices in high and medium pressure steam, feed water and similar services, which fall under the purview of Indian Boiler Regulation Act shall be either certified by IBR or shall be certified by authorities acceptable to IBR. It shall be responsibility of Bidder to obtain the necessary approval of the concerned Authority / Chief Inspector of Boilers for the design and design calculations, manufacturing and erection procedure as called for under the IBR Act for all items requiring such certification.

6.00.00 DESIGN CRITERIA

This section lays down the general design criteria to be adapted in designing the Control & Instrumentation system of the plant.

6.01.00 General Requirements

6.02.00 Instrumentation, control and automation devices and accessories shall be designed with the following considerations:

a) Stable in spite of temperature fluctuations.

b) Able to withstand high humidity.

c) Weather proof.

d) Dust proof.

e) Corrosion resistant.

f) Erosion resistant.

g) Able to withstand high vibration.

h) Easily accessible for operation & maintenance.

6.03.00 Parts subject to high pressure, temperature or other severe duty shall be of materials and construction suitable for the service conditions and long operating life.

6.04.00 Components of instruments, control devices, accessories, piping etc. which contact steam, condensate or boiler feed water shall be manufactured from copper-free materials.

6.05.00 Instrument Accuracy, Standard Scales and Ranges

6.05.01 Instrument Accuracy

Instruments shall meet the following general requirements.

a) Pressure measurement shall be linear with respect to the measured pressure.

b) Flow meter shall meet the specified accuracy criteria when operating between 25 and 100 % of full-scale flow. The accuracy shall include the effect of errors in the differential head measuring device, square root converter and signal generator.

c) Level measurement shall be linear with respect to the measured level based on a water specific gravity of 1.00.

d) Wherever the measured parameter is influenced by process pressure & temperature, required compressibility correction shall be introduced.

6.05.02 Instrument Scale Displays

a) All displays shall be in engineering units. Instrument scales displayed on screen will have graduations with scale divisions based on multiples of 10. The smallest division shall preferably be a whole number approximately 1% of the scale range if not otherwise impracticable.

b) Pressure instrument shall have the unit suffixed with ‘a’ or ‘g’ to

indicate absolute or gauge pressure, respectively.

c) Scales and charts of all instruments shall have linear graduations

6.05.03 Instrument Ranges

Instrument range shall be selected to have the normal reading, preferably between 50% and 70% of full scale for linear parameters and 70% to 80% for flow measurements. Deviation indicators shall have the null position at mid scale. The normal operating parameter shall be identified with a clear green mark.

6.06.00 Operability & Maintainability

6.06.01 The system shall be designed such that any 'single-failure' shall not lead to loss of availability of the plant, alteration in operating routine or degradation of performance. This shall be achieved by judicious introduction of redundancy at all critical levels. The plant operator remains totally transparent to 'single-failures'.

6.06.02 The system and operator interfaces / consoles shall be designed for the operation of the unit with minimum operational manpower deployment . Bidder shall ensure proper operability and also take into account protections to achieve no accidental maloperations .

6.06.03 The choice of hardware shall take into account sound maintainability principles and techniques and shall not be limited to the following:

a) Standardization of parts.

b) Minimum use for special tools.

c) Modular and hot replacement.

d) Logical grouping of functions.

e) Separate and non-interactive adjustability.

f) Malfunction identification facility through self-diagnostics.

g) Easy removal, replacement and repair.

h) Easy assembly and disassembly.

i) Fool-proof design to preclude improper mounting and installation.

j) Redundancy of critical parts.

k) Unique process equipment vis a vis hardware identifiability by assigning sub-racks / sub-rack sections to specific plant areas.

6.06.04 Intercommunications in between sub-racks and system termination cabinets and in between sub racks and other panels shall be made by prefabricated connectors and cables with mechanical latch.

6.06.05 Adequate test facility shall be incorporated in the design.

6.07.00 Established Reliability & Availability

6.07.01 The minimum target reliability of each component/module shall be established by taking into consideration its Mean time between failure (MTBF) and Mean time to repair (MTTR), so that availability of the complete system is assured for 99.7%.

6.07.02 In order to establish the target reliability Bidder shall perform necessary availability tests and burn-in tests for major systems. Surge protection for solid state systems, selection of proper materials, manufacturing processes, quality controlled components and parts, adequate derating of electronic components and parts shall be ensured to meet the reliability and life expectancy goals.

6.07.03 Continuous self-checking features shall be incorporated in system design with automatic transfer to healthy/redundant circuits to enhance the reliability of the complete system.

6.08.00 Security and Failure Philosophy

6.08.01 General

It is essential that interlock, protection, supervision and automatic control systems shall have high integrity. Control & Instrumentation system shall meet the following requirements:

a) No single failure shall cause failure of the control.

b) No single fault shall cause the protection system to operate spuriously or cause the protection system to become inoperative.

c) Grouping of the control functions into system blocks shall be such that failure of any one block will only partly degrade the overall system.

d) Control system shall be structured with redundancy so that no single failure within the control system can cause the failure of plant on duty and at the same time cause the standby plant to be unavailable.

e) Due to control system failure if a final control element or plant item does not respond then the control element shall go into a fail safe status.

f) Field wiring for contact interrogation or device control shall be protected such that a fault on the cable does not cause loss of more than a minimum tolerable functionality of the system.

6.08.02 Measurement , Control & Channel Redundancy

To meet the failure and self checking criteria for the control system, measurement redundancy shall be provided for all the critical parameters. Throughout the control system, the security and validity of signals are to be ensured based on the following design principles.

a) Where a plant measurement is to be duplicated or triplicated such signals shall be separately fed to the different input modules.

b) Signals, after due security and validity checking by means of voting, averaging, median, difference monitoring or similar technique shall be used for control functions.

c) Where duplicated measurements are used, provision shall be there for selecting any one as the duty signal. Continuous monitoring of difference between the signals shall be made.

d) For binary and analog inputs required for protection of SG , TG and major auxiliaries whose non availability may result in loss of generation triple sensing devices shall be provided . Binary and analog inputs , which are required for protection of more than one equipment as well as protection signals for important auxiliaries and HT drives etc. triple sensing devices shall be provided .Also other binary and analog inputs required for CLCS dual sensing devices shall be provided . However,for those binary and analog inputs which are also required for protection in addition to CLCS, triple sensing devices shall be provided.

e) Measurement system, CLCS and OLCS shall all be configured with redundancy at processor modules,communication modules, data bus and power supply modules.Triple redundancy shall be followed as described elsewhere in the specification.All servers shall be dual redundant.

f) Both CLCS & OLCS shall be configured with Redundant I/O channels for each sensor/signals. Where redundant sensors are provided redundant I/O channels shall be provided for each sensors/signals.

g) Redundant sensors shall be provided for all control applications. For all closed loop controls (CLCS) triple redundant sensors shall be provided. This will include sensors provided for compensation also. Similarly for critical protection logic requirements triple redundant sensors for 2 out of 3 logic shall also be provided to avoid spurious tripping. For all other control application dual redundant sensors shall be provided.Dual and Triple redundant sensors shall also be provided as described elsewhere in the specification.

h) DELETED

6.08.03 Redundancy in input / output modules

1. Redundancy

a) Redundancy in input / output modules for close loop control systems, open loop control system, protection, interlocking and sequential control shall be provided as follows:

i) Wherever redundant sensors are employed each sensor shall be wired to a separate input module so that even if one input module fails, the parameter will be available from the other input module.

ii) If only one sensor is provided then redundant input cards shall be provided and wired accordingly.

iii) Redundant output card shall be provided for the signals from

Control System going to final drive control elements.

b) DELETED

c) In addition to above, 20% wired input/output spare channel shall be provided for each I/O module.

2. Bidder to note that all I/O ,Processor , network interface, communication modules etc., shall be sourced from their Original Principlal's works.

3. The system shall be provided with extensive diagnostic features so that a system failure can be diagnosed down to the module level giving location and nature of fault. Ease of maintenance and trouble shooting shall be a primary consideration in equipment selection.

4. The system shall provide inherently safe operation under all plant disturbances and component failures so that under no circumstances safety of the plant personnel nor equipment is zeopardized.. The DDCMIS hardware shall be suitably sized to ensure that the implemented scheme meets the desired requirements. The Bidder through detailed calculations shall establish the adequacy of the system selected and demonstrate the same during shop testing and site testing.

6.08.04 Data highway Redundancy

There shall be Redundancy in the system for high reliability of communication. The redundant buses shall work continuously. All communication modules, bus couplers, bus interfaces etc. shall also be hot redundant.

Communication between the operator station and the functional groups of control microprocessors shall be by means of hot redundant data highways. Redundancy failure shall also be indicated in operating station.

All soft links amongst DDCMIS and various PLC / proprietary control systems including MCS shall be redundant bidirectional OPC link.

6.08.05 Redundancy for Power supply unit

All power supply feeders from UPS (in parallel mode having 50% load sharing) or 24 V DC system (in parallel mode having 50% load sharing) shall be redundant with auto changeover in each ACDB/DCDB panel.

6.08.06 Redundancy in Operaotr's Console

Operators' Consoles shall have fall back feature . so that in case of failure of any console , its functions can be taken up in an adjacent console and LVS.

6.08.07 Design Of Enclosures

6.08.08 Design of outdoor enclosures shall be weather proof, dust-tight, drip-proof and shall take into account the environmental conditions.

6.08.09 Enclosures shall be adequately sized so that the maximum permissible temperature rise above 50 Deg C ambient is 10 Deg C (maximum).

6.08.10 Enclosures design shall also take into account greatest possible personnel safety.

6.09.00 Electrical Noise Control

6.09.01 Equipment furnished by Bidder shall incorporate necessary techniques to eliminate problems caused by electrical noise interferences and power line borne surges encountered in power plant environment. Equipment, which are vulnerable to electrical noise interference or surge shall be suitably immunized to eliminate possible problems.

6.09.02 Bidder shall be responsible for implementation of the shielding, input balancing, ripple filtration and grounding for field inputs to achieve installation with minimum noise coupling.

6.09.03 Radiated immunity test shall be in accordance to IEC 801.3.

6.10.00 Surge-Protection For Solid State Equipment

6.10.01 All solid-state equipment shall be able to withstand the surges inherent in a powerhouse environment. Equipment shall be designed to successfully withstand surges without damage to components and/or wiring on application of surge wave whose shape and characteristics are defined in ANSI publication C37.90-a (IEEE-472-1974) entitled "Guide for Surge Withstand Capability (SWC) Tests".

6.10.02 To immunize the system against surge, coupling free wheeling diodes, surge suppressors, opto / galvanic isolators shall be used as required.

6.11.00 Burn-In And Elevated Temperature Test

Solid-state equipment / system shall be certified to be tested for a minimum period of 168 hours continuously under power. Solid-state logic systems shall be subject to the elevated temperature test and burn-in test as complete assemblies.

6.12.00 Elevated Temperature Test

a) During the first 48 hours the ambient temperature shall be maintained at 50^{O} C and the equipment shall be made to repeatedly perform operations it will be expected to perform in service with loads on various components being equal to those which will be experienced in actual service.

b) The 48 hours test period shall be continuous but shall be divided into four 12-hour segments. The power supply voltage during each 12 hours segment shall be nominal voltage for 11 hours; followed by 110 percent of nominal voltage for 30 minutes; followed by 90 percent of nominal voltage for 30 minutes.

c) During the elevated temperature test the cubicle doors shall be kept closed and inside temperature in the zone of highest heat dissipating component /module shall be monitored. Temperature rise inside the cubicle shall not exceed 10 Deg.C above the ambient temperature of 50 Deg.C.

6.13.00 Burn in Test

The 48 hours elevated temperature test shall be followed by 120 hours of burn in test at normal operating temperature. This test shall also be conducted as per above procedure.

6.14.00 Panels, Cubicles and Enclosures

6.15.00 General

a) All panels, cubicles and enclosures shall be furnished complete with integral piping, internal wiring, convenience outlets, internal lighting, grounding, ventilation, space heating, vibration isolating pads and other accessories.

b) Unless otherwise specified cable entry for panels / desks / cabinets shall be through bottom via glanding plate. Fireproof seal shall be used to seal the bottom to prevent entry of dust.

c) Panels and cabinets shall be constructed from steel sheet reinforced as required to provide true surface and adequate support for devices mounted thereon. Thickness of the CRCA steel for UCP / backup panel and other panels/cabinets shall be as described in Section VII of this volume of the specification. Panels and cabinets shall be of adequate strength to support mounted components during shipment and to support a concentrated load of 100 Kilograms on their top after erection.

d) Panel /cabinet shall have eyebolt on top for lifting.

e) Mounting , wiring , powering of all items to be mounted / installed on desks irrespective of the source of procurement shall fall in the scope of erection of Bidder ,this shall include freeissue items furnished by Owner.

6.15.01 Surface Preparation and Painting

Sheet metal exterior steel surfaces shall be sand blasted, ground smooth and painted as specified below:

a) Suitable filler shall be applied to all pits, blemishes and voids in the surface. The filler shall be sanded so that surfaces are level and flat; corners are smooth and even. Exposed raw metal edges shall be ground burr-free. The entire surface shall be blast clean to remove rust and scale. Oil, grease and salts etc. shall be removed from by one or more solvent cleaning methods prior to blasting.

b) Two spray coats of epoxy primer urface shall be applied to all exterior and interior surfaces, each coat of primer urface shall be of dry film thickness of 1.5 mil. A minimum of two spray coats of final

finish color (Catalyzed epoxy or polyurethane) shall be applied to all surface of dry film thickness 2.0 Mil. The finish colors for exterior and interior surfaces shall conform to the following shades:

i) Exterior : Opaline green shade 275 of IS: 5

ii) Interior - Brilliant Glossy White.

c) Paint films, which show sags, cheeks, blisters, teardrops, fat edges or other painting imperfections shall not be acceptable.

6.15.02 Wiring

Wiring within the panels shall conform to NEC standards and shall be factory installed and tested at the works. All interior wiring shall be installed neatly. Features shall not be limited to the following :

a) All spare contacts of relays, switches and push buttons shall be wired up to the terminal blocks.

b) Each wire shall be identified at both ends with wire designation as per approved wiring diagram. Heat shrinkable type ferrules with indelible computerized print shall be used with cross- identification.

c) Wire termination shall be made with insulated sleeve and crimping type lugs. All external connections shall be made with one wire per terminal. Wire shall not be spliced or tapped between terminals. Open-ended terminal lugs shall not be used.

d) Internal wiring shall be terminated uniformly on one side of the terminal block leaving the other side available for termination of outgoing cables.

e) Thermocouple lead wires, analyzer measuring lead wires, or any other lead wires carrying measuring signal of the order of low mili volt or micro volt shall be electrically and physically isolated from other AC and DC wiring.

f) All low-level signal cables shall be separately bundled from control cable.

g) Wires shall be dressed and run in troughs with clamp-on type covers. Wirings shall be neatly bunched in groups by non-metallic cleats or bands. Each group shall be adequately supported along its run to prevent sagging or strain on termination.

h) Shield wires shall be terminated on separately.

i) Common connections shall be limited to two wires per terminal.

j) Wiring to door mounted devices shall be provided with multi-strand wires of (49 strands minimum) adequate loop lengths of hinge-wire so that multiple door openings will not cause fatigue to the conductor.

k) Wiring shall be arranged to enable instruments or devices to be removed and/or serviced without disturbing the wiring. No wire shall be routed across the face or rear of any device in a manner, which will

impede the opening of covers or obstruct access to leads, terminals or devices.

l) Panel internal wiring shall follow distinct color-coding to segregate different voltage levels viz. 24V DC, 48V, 110V AC, 240V AC, 220V DC etc.

m) Panels /cabinets /desks shall be provided with removable gasketted cable gland plates and cable glands. Split type grommets shall be used for prefab cables.

n) Wire shall be multistranded annealed flexible high purity copper conductor with heat resistant FRLS PVC insulation and shall pass vertical flame test per IPCEAS-1981.

o) Wire sizes used for internal wiring shall not be lower than the followings :

Control wiring (switches, pushbuttons etc.)	: 1.5 Sq.mm
Power supply/receptacle /illumination wiring	: 2.5 sq. mm or higher as per load
4-20mA DC current and low voltage signal upto 48V DC	: 0.5 Sq. mm

p) Identification of conductors shall be done by insulation color-coding identified on drawings or by printed wiring lists.

6.15.03 Grounding

a) System cabinet AC and DC ground shall be electrically isolated from each other and also electrically isolated from the Instrumentation signal ground. All the above ground shall be individually connected to the single point on the ground pit. Dedicated redundant earth pit shall be provided which shall be away from the HV equipment. This earth pit shall not be shared with other electrical equipment ground and shall also be insulated from other electrical system ground to ensure single point grounding of the system. Grounding resistance shall be better than 1.0 ohm. IEEE guideline shall be followed while designing the grounding system.

b) Panels and cabinets shall be provided with a continuous tinned copper ground bus bar of minimum 25 mm x 6 mm cross section, extending along the entire length of the panel / desk / cabinet assembly. The ground bus shall be bolted to the panel structure and effectively ground the entire structure.

c) The panel /desk /enclosure /JB ground shall have two (2) bolt drilling with GI bolts and nuts at each end to connect to GI/ copper flat ground riser by means of insulated copper ground cable of required cross section with lug.

d) Circuits requiring grounding shall be individually and directly connected to the panel ground bus.

e) For electronic system cabinets, the electronic system ground bus shall be similar but insulated from the cabinet and shall be separately connected to the system ground. Signal cable shields shall be grounded at the panel end only and shall not be left open. The ground in between panels of a shipping section shall be firmly looped.

f) Electrical meters, relays, transmitters and switching devices, operating at a voltage less than 50V may be grounded through the steel structure.

6.16.00 Panel / Cabinet/ Desk/ Enclosures / junction boxes & instruments Environmental Protections

a) Panels, cabinets, desks, distribution boxes, racks ,junction boxes, terminal boxes , instruments and all other field mounted equipment / enclosures shall suit the environmental condition of the area and shall not be inferior than the requirement indicated in the following table.

SL. NO.	LOCATION	ENCLOSURE TYPE
1.	Indoor type non- ventilated enclosure in non-hazardous area	IP-54
2.	Indoor type ventilated enclosure in non-hazardous area	IP -42
3.	Enclosure in Air conditioned area	IP-32 with suitable canopy at top to prevent ingress of dripping water.
4.	Outdoor type in non-hazardous areas	IP-65 with anticorrosion coating.
5.	Outdoor in hazardous areas	As per requirements of the NEC Code for the location

b) The construction of electrical enclosures located in areas subject to conditions classified in the National Electrical Code (NEC) as hazardous shall be of a type designated suitable for the environment in which they are located.

6.17.00 Terminal Blocks

All ternminal blocks shall be provided complete with all required accessories including .Each terminal shall have LED indication with fuses to indicate and isolate earth faults. Spring-loaded (Cage-clamp type) terminals shall be used for termination of instrumentation cables at field JBs, FTCs and local panels.

7.00.00 METERING BASES AND CHART UNITS

The following system of units shall be followed for various displays and scales unless otherwise mentioned:

i)	Pressure	: Kg/cm^2
	Differential Pressure	: mm of H_2O column / Kg/cm^2
ii)	Draught	: mm of H_2O column
iii)	Vacuum	: Kg/cm^2 (abs)/mm of Hg column
iv)	Temperature	: Degree Celsius (^{O} C)
v)	Flow (Steam, Water)	: Tonnes / hr, M^3/Hr
vi)	Flow (Oil)	: M^3 / Hr, Liter/Hr
vii)	Flow Air	: Tonnes / hr / M^3 / Hr.
viii)	Density	: gms / c.c.
ix)	Level	: Mm /%
x)	Conductivity	: Siemens / cm
xi)	Gas Analyzer	: Percentage by weight or as specified in respective case.
xii)	Dissolved Oxygen / Silica / Sodium	: ppm /ppb

8.00.00 PROCESS CONNECTION & INSTRUMENT HOOK UP

8.01.00 Instrument connection to the process system (piping, vessel etc.) shall be according to the process & piping specification upto and including the root valves. Root valves shall be installed as close as possible to the piping or vessel.

8.02.00 Each instrument shall have its own independent connection to the process except for instruments located on standpipe. Each instrument shall be connected independently to the standpipe through isolation valve.

8.03.00 Process connection for instruments lines and vessels shall be in accordance to standards such as ASME or other recognized international standards.

9.00.00 POWER SUPPLY SYSTEMS

9.01.00 Instrumentation power supply system shall include all conditioning equipment required to accommodate normal variations in the electrical supply. All panels and cabinets shall accept redundant power feeds from two different sources.

9.02.00 Type of power supply systems envisaged for the various C&I system including DDCMIS are as follows:

240V AC Redundant UPS system for C&I control & monitoring system

DELETED

10.00.00 ENVIRONMENTAL CONSIDERATIONS

C&I components shall operate properly with no degradation in expected lifetime or in operation parameter in the normal power plant environment. C&I system shall be designed considering all the operating conditions which may be encountered during installation and operation.

10.01.00 Temperature

10.01.01 Where the environmental extreme exceeds the capabilities of the selected system, Bidder shall take appropriate steps to control the environment.

10.02.00 Humidity

10.02.01 C&I system shall be designed to withstand the humidity limits specified for the project. Condensation shall not be allowed to form in the cabinets nor shall water be allowed to be admitted through conduit entering the cabinets from top or sides.

10.03.00 Atmospheric Contamination

10.03.01 Particulate contamination from fly ash and coal dust and gaseous contaminants such as SO2 and other flue gas constituents in the coal fired plant are foreseen. This hazard shall be taken into design considerations.

10.04.00 Vibration

10.04.01 Design of the systems shall include features such as locking devices, anti vibration pads etc, to withstand vibration. In general, C&I equipment shall be installed away from the vibration zone.

10.05.00 Lightning

10.05.01 Protection against lightning shall be considered by providing proper grounding, metal oxide varistors, spark gap lightning arrestor, optical isolator and isolation transformer.

11.00.00 SECURITY

11.01.00 Door lock shall be provided in all Panels, Cabinets and Enclosures.

11.02.00 System mode key switch or password to prevent tampering of system program.

11.03.00 Redundant elements of the system shall not be exposed to the common hazards. For example routing of the redundant network cable through separate cable raceway, using separate cabinet / separate rack for redundant controller and redundant IO modules.

12.00.00 ACCEPTANCE TESTS

The Bidder shall be required, as part of his Bid, to fully integrate and test all the equipment, included in his Bid and respective Control packages at site and at the manufacturer's works. Owner / Consultants shall witness these tests.

The Bidder shall consider in his Bid the following minimum tests:

(a) Factory Acceptance Test (FAT)

After completion of manufacture of all control and monitoring systems like DDCMIS , PLC, BOP nework PLC , Proprietary control systems , HART management system , RMCMS , MCS , Alarm annunciation system , AAQMS , CEMS , CCTV , Plant telephone System , CMIMS , SWAS , etc. and prior to delivery to site, the manufacturer shall functionally test the assembled system. The integrated test shall be carried out with all input / output cubicles, control processors, data highway, operator's consoles, Engineer's console and peripheral devices connected in the specified configuration. The fully configured software shall also be loaded and tested at the same time.

The FAT shall include , as a minimum , the following activities:

- Complete hardware and software inspection;
- Heat cycle run test as per the prevailing standards;
- Functional test of a 100 % of all configured points, logic routines, control functions, graphic displays, reports and logs;
- Demonstration of special calculations (e.g. efficiency calculation, performance calculations etc.);
- Testing of redundancy facilities to demonstrate automatic change over to standby data highway, power supply and control processor etc.;
- Demonstration of displays , logs and system diagnostic facilities;
- Demonstartion of spare capacity
- Demonstration of third party interface

The FAT shall be witnessed by the Owner / Engineer who shall be notified at least three (3) weeks before the commencement of the tests. The system shall have been fully pre-tested by the manufacturer at his works prior to notifying the Owner / Engineer to ensure any component, equipment or system fault have been identified and cleared. The test procedure for the FAT shall be issued to the Owner and agreed prior to notification. All documents / drawings and test equipment shall be available at the manufacturer's works during the FAT.

The FAT shall include a 72 hour continuous operational run, any equipment fault or failure during this time shall make this part of the test null and void and the test run shall be re-started after rectification of the fault. A test certificate, accompanied by the relevant test results, shall be issued after successful completion of the tests.

Duration of the FAT shall be at least six weeks for each system .

(b) Site Acceptance Test (SAT)

After installation, connection, integration with other systems and all pre-commissioning checks have been carried out on the complete system, the SAT shall be performed and witnessed by the Owner. The SAT shall include the following as a minimum:

a) Complete hardware , software and installation inspection;

b) Testing of redundancy facilities by simulating data highway, power supplies and control processor failures. All such units shall be tested to demonstrate of the automatic operation of the standby units and initiation of the relevant system alarms;

c) Demonstration of system diagnostic facilities; by the simulation of the appropriate fault conditions. The system fault reporting techniques shall also be demonstrated;

d) Testing of data highway integrity using continuity test equipment based on signal injection / reflection techniques;

e) Demonstration of data logging, displays, sequence of events trending system operation.

f) Pre-commissioning checks shall include the following as a minimum :

i) Calibration of all field instruments, analyzers and equipment, in the scope of supply of this package, at site;

ii) Loop checking, for all open and close loops, between source and destination with manual signal injection as well as from Operating Consoles for entire DDCMIS / PLC/ Proprietary control systems I/Os;

iii) Logic sequence check with the manual signal injection at signal source as well as checking of feed back signals.

All individual configured data points, logic routines, control functions, graphic displays and reporting facilities shall be verified as part of the loop tests.

The Owner shall be notified at least 2 weeks before the commencement of the test. The procedures shall be issued and agreed before notification.

A test certificate accompanied by the relevant test results shall be issued after successful completion of the calibration and test.

FIELD INSTRUMENTATION & ANALYSERS SPECIFICATION

1.00.00 SPECIFICATION FOR ELECTRONIC TRANSMITTERS

1.01.00 PRESSURE TRANSMITTER

1.	Working Principle	:	Smart (HART Compatible)
2.	Type	:	Microprocessor based, 2 – Wire
3.	Output Signal	:	4-20 mA DC along with superimposed digital signal
4.	Measuring Element	:	Capsule / Diaphragm
5.	Element material	:	SS-316 (Stainless Steel) or better
6.	Static Pressure	:	150 % of maximum span continuously, without affecting the calibration
7.	Turn-down ratio	:	100: 1
8.	Span and Zero	:	Continuous, tamper proof, remote as well locally adjustable with zero elevation and suppression by 100% of span
9.	Enclosure Class	:	IP-65 (Explosion proof for NEC Class-1, Division 1 area)
10.	Output Indicator	:	LCD (Integral indicator of 5 digit display)
11.	Nameplate	:	Tag number, service engraved in SS tag plate
12.	Body	:	SS
13.	Operating Voltage	:	24V DC
14.	Load	:	600 Ohms (min.) at 24 Volts D.C.
15.	Ambient Temperature	:	0 - 50 ^{O}C
16.	Performance:	:	
	i. Accuracy		$\pm$ 0.075% of Span or better

	ii. Repeatability		± 0.05% of Span or better
17.	Sealing/Isolation	:	Extended diaphragm (Silicon oil/ Flurolub filled) with 5 meters SS armoured capillary for corrosive/viscous/solid bearing or slurry type fluid applications
18.	Accessories	:	a. Universal mounting bracket suitable for 2" pipe mounting b. High tensile carbon steel U-bolts c. Siphon for steam and hot water services d. ½" NPT 2-valve stainless steel manifold, constructed from SS316 bar stock e. Companion flange with nuts, bolts and gaskets f. ½" NPT cable gland g. Handheld calibrator
19.	Adjustment/Calibration/ Maintenance	:	From handheld calibrator/ HART management system

Notes: For primary air/ secondary air/ flue gas applications, DP type transmitters shall be provided for pressure measurement.

LVDT type is not acceptable.

1.02.00 DIFFERENTIAL PRESSURE TRANSMITTER / FLOW TRANSMITTER

1.	Working Principle	:	Smart (HART Compatible)
2.	Type	:	Microprocessor based, 2 – Wire
3.	Output Signal	:	4-20 mA DC along with superimposed digital signal
4.	Measuring Element	:	Capsule / Diaphragm

5.	Element material	:	SS-316 (Stainless Steel) or better
6.	Static Pressure	:	150 % of maximum span continuously, without affecting the calibration
7.	Turn-down ratio	:	100: 1
8.	Span and Zero	:	Continuous, tamper proof, remote as well locally adjustable with zero elevation and suppression by 100% of span
9.	Enclosure Class	:	IP-65 (Explosion proof for NEC Class-1, Division 1 area)
10.	Output Indicator	:	LCD (Integral indicator of 5 digit display)
11.	Nameplate	:	Tag number, service engraved in SS tag plate
12.	Body	:	SS
13.	Operating Voltage	:	24V DC
14.	Load	:	600 Ohms (min.) at 24 Volts D.C.
15.	Ambient Temperature	:	0 - 50 ^{O}C
16.	Performance:		
	i. Accuracy	:	$\pm$ 0.075% of Span or better
	ii. Repeatability	:	$\pm$ 0.05% of Span or better
17.	Sealing/Isolation	:	Extended diaphragm (Silicon oil/ Flurolub filled) with 5 meters SS armoured capillary for corrosive/viscous/solid bearing or slurry type fluid applications
18.	Accessories	:	a. Universal mounting bracket suitable for 2” pipe mounting b. High tensile carbon steel U-bolts

c. Siphon for steam and hot water services

d. ½" NPT 5-valve stainless steel manifold, constructed from SS316 bar stock

e. Companion flange with nuts, bolts and gaskets

f. ½" NPT cable gland

g. Handheld calibrator

19. Adjustment/Calibration/ Maintenance : From handheld calibrator/ HART management system

1.03.00 Displacer Type Level Transmitters

1.	Type	:	Smart (HART Compatible)
2.	Stages of operation	:	Continuous
3.	Material	:	
4.	i. Displacer		SS-316
5.	ii. Suspension wire		SS-316
6.	iii. Torque tube housing		SS
7.	iv. Torque tube		Inconel
8.	v. Displacer chamber		SS
9.	vi. Transmitter Housing		SS
10.	Operating Voltage	:	24 V DC
11.	Transmission	:	Microprocessor based, 2-wire
12.	Output Signal	:	4-20 mA DC along with superimposed digital signal
13.	Static / overload	:	Maximum static pressure without

	pressure		permanent deformation or loss of accuracy
14.	Turn-down ratio	:	10 : 1 or better
15.	Zero & Span	:	Continuous, tamper proof, remote as well locally adjustable with zero elevation and suppression by 100% of span
16.	Enclosure Class	:	IP-65
17.	Output Indicator	:	LCD type (Integral indicator of 5 digit display)
18.	Nameplate	:	Tag number and Service engraved in stainless steel tag plate
19.	Ambient Temperature	:	0 - 50 ^{O}C
20.	Load Impedance	:	600 Ohms at 24 Volts (minimum)
21.	Process Connection	:	2” Flanged
22.	Performance - Accuracy	:	$\pm$ 0.075 % of span or better
23.	Accessories	:	a) Counter Flange, nuts, bolts, gaskets etc b) Weights for 5 point calibration of instruments c) Vent and drain plugs d) ½” NPT Glands e) Handheld calibrator
24.	Preferred Features	:	a) Test plug connection and cutout terminals physically separated from other electronics b) Electronic Damping facility (adjustable)
25.	Adjustment/Calibration/ Maintenance	:	From handheld calibrator/ HART management system

	26.	Applications	:	During detail engineering on Owner's approval

1.04.00 MASS FLOW METER

1.04.01 SENSOR

	1.	Measuring Principle	:	Coriolis Mass flow
	2.	Primary Element	:	Flow Tube of 316SS or better
	3.	Heating Arrangement	:	Integral
	4.	Temperature Control	:	For heavy fuel oil application
	5.	Process Connection	:	Flanged of rating as per process requirement
	6.	Drain	:	Self-draining facility
	7.	Enclosure	:	Stainless steel
	8.	Accessories	:	Counter flanges, Mounting nuts, bolts, gaskets etc.

1.04.02 TRANSMITTER

	1.	Measured quantities	:	Mass Flow rate, Total Mass Flow, Density
	2.	Input Signal Processing	:	Smart (HART compatible)
	3.	Display	:	LCD
	4.	Output	:	2 nos. isolated output of 4-20mA DC selectable from four measured quantities
	5.	Load	:	< 750 ohms
	6.	Power supply	:	240V AC, 50 Hz

7.	Turn Down	:	100:1
8.	Accuracy	:	± 0.2 % of measured value
9.	Housing	:	IP 65 (Explosion proof)
10.	Nameplate	:	Tag number, service engraved in stainless steel tag plate
11.	Accessories	:	a) Handheld calibrator b) Mounting U-bolts, nuts, bolts, prefab cable etc c) ½"NPT cable gland
12.	Adjustment/Calibration/ /Maintenance	:	From handheld calibrator/ HART management system
13.	Applications	:	Fuel Oil service

1.05.00 RADAR TYPE LEVEL MEASUREMENT

1.	Type	:	Smart (HART Compatible)
2.	Antenna	:	Co axial / guided wave radar /–Overspill protection
3.	Principle	:	TDR (Time Domain Reflectometry)
4.	Communication	:	Two wire 4-20mA DC with HART
5.	Environmental temperature	:	0 – 50 ºC
6.	Enclosure	:	IP-65 (Explosion proof for NEC Class-1, Division 1 area)
7.	Calibration	:	a) Self calibration with internal reference : b) Zero & Span calibration
8.	Process Connection	:	External cage mounting Flanged /screwed
9.	Electronic Housing	:	Epoxy painted Die-Cast aluminium

			alloy
10.	Antenna / Flange assembly	:	316 SS or Hestalloy (as required)
11.	Power supply	:	24 V DC
12.	Output Indicator	:	LCD
13.	Accuracy	:	5 mm or 0.1% of probe length
14.	Accessories	:	a) Handheld calibrator
		:	b) Counter Flange, nuts, bolts, gaskets etc
		:	c) ½"NPT cable gland
		:	d) SS Nameplate
15.	Adjustment/Calibration/ /Maintenance	:	From handheld calibrator/ HART management system
16.	Applications	:	Vessels under vacuum or low pressure applications, solid levels

1.06.00 ULTRASONIC LEVEL TRANSMITTER

1.	Type	:	Microprocessor based, 2-wire, Smart (HART Compatible)
2.	Operating Principle	:	Detection of reflected ultrasonic pulse
3.	Output Signal	:	4-20 mA DC along with superimposed digital signal
4.	Operating frequency	:	10 KHz to 50 KHz (typical)
5.	Display	:	LCD
6.	Temperature Compensation	:	Built in –Programmable
7.	Power supply	:	24 V DC
8.	Enclosure	:	SS, IP-65 (Explosion proof for NEC Class-1, Division 1 area)

9.	Zero & Span	:	Continuous, tamper proof, remote as well locally adjustable. It shall be possible to calibrate the instrument without any level in the sump/ tank
10.	Accuracy & Repeatability	:	0.15 % of span or better
11.	Resolution	:	0.1 % of span
12.	Operating temp.	:	Transmitter- 500 C and Sensor - 800 C
13.	MOC Sensor	:	SS-316/Body- PVC and Face – Polyurethene
14.	Mounting	:	4” Flanged/ 2” NPT for sensor and Transmitter on panel
15.	Accessories	:	a) Handheld calibrator b) Weather canopy for protection from direct sunlight and direct rain c) ½”NPT cable gland d) All mounting hardware (SS-316), Prefab cable e) SS Nameplate
16.	Diagnosis	:	On-line
17.	Status Indication	:	Power On, HI, HI-HI, Lo, LO-LO, Fault
18.	Output Contacts	:	2 SPDT, 230V, 5A
19.	Adjustment/Calibration/ /Maintenance	:	From handheld calibrator/ HART management system
20.	Applications	:	Coal Bunker, Water Service etc.

1.07.00 ULTRASONIC FLOW TRANSMITTER

1.	Type	:	Ultrasonic – Clamp On
2.	Accuracy	:	+/- 1 % of reading
3.	Repeatability	:	+/- 0.3 % of reading
4.	Rangeability	:	400 : 1
5.	Output Signal	:	4-20 mA DC with HART
6.	Measured Parameter	:	Volumetric flow, Totalized flow and flow Velocity
7.	Display	:	LCD with internal Key Pad (Flow rate & Totalization)
8.	Power Supply	:	24 V DC (2 Wire)
9.	Enclosure	:	SS (IP- 68 – Submersible)
10.	Mounting	:	SS Chain or Strap
11.	Accessories		1. Handheld calibrator 2. ½"NPT cable gland 3. Transducer cable 4. All mounting hardware (SS-316) 5. SS Nameplate
12.	Adjustment/Calibration/ /Maintenance	:	From handheld calibrator/ HART management system
13.	Applications	:	Plant water service

Note: Multi-path insertion type (minimum 4 path) Ultrasonic Flow meter shall be provided for Raw water/ Cooling Water flow measurements.

2.00.00 **HART HAND HELD CALIBRATOR**

Hand held calibrators (2 nos. for each type) shall be provided for adjustment/ calibration/maintenance of the HART compatible

transmitters. The hand held calibrator shall be suitable for all types of transmitters supplied in the package. If one type of hand held type calibrator is not suitable for communicating with all types of transmitters then separate hand held calibrator will be provided.

3.00.00 PROCESS ACTUATED SWITCHES

3.01.00 PRESSURE SWITCH

1.	Type	:	i. Piston for high pressure application ii. Bellow / Diaphragm for low pressure application
2.	Sensing element material	:	SS-316. All other wetted part SS316
3.	Case Material	:	SSt
4.	Setter Scale	:	Black graduation on white linear scale. Graduation 0-100% with red pointer for set points
5.	Over range	:	150 % of maximum pressure
6.	Adjustments	:	a) Internal Set Point
		:	b) Differential adjustment
7.	End Connection	:	1/2" NPT bottom connected
8.	Switch configuration	:	Two SPDT (240V, 5A AC/220V, 0.5A DC)
9.	Switch Type	:	Snap acting, shock & vibration proof
10.	Terminal Block	:	Suitable for full ring lugs
11.	Enclosure Class	:	IP-65 (Explosion proof for NEC Class-1, Division 1 area)
12.	Performance	:	a) Repeat accuracy ± 1.0%
		:	b) Accuracy of Setting Indication of ± 1.5%
13.	Ambient temperature	:	0 – 50 Deg.C

14.	Nameplate	:	Tag number, service engraved in SS tag plate
15.	Accessories	:	a) Silicon oil/ Flurolub filled Remote diaphragm seal with SS-316 capillary for corrosive/ viscous/ solid bearing or slurry type fluid applications b) Snubbers for pulsating fluid applications c) Siphons for steam and hot water services d) Retention ring and screws for surface mounting e) 1/2" NPT 2 Valve SS-316 barstock manifold f) ½" NPT cable gland
16.	Applications	:	During Detail Engineering on Owner's approval

3.02.00 DELETED

3.03.00 DELETED

3.03.01 DELETED

3.04.00 FLOW SWITCH

1.	Type	:	Paddle /Piston/Disk	
2.	Wetted part material	:	Stainless steel or Hastelloy for acidic application	
3.	End connection	:	a)	Threaded upto 1” line size with integral Tee
		:	b)	Flanged for line size > 1 ½”
4.	Enclosure material	:	Stainless Steel	
5.	Enclosure class	:	IP 65	
6.	Switch configuration	:	2 SPDT (5A, 240 V AC, 0.5A, 220V DC)	
7.	Repeatibility	:	2%	
8.	Cable connection	:	½”NPTF	
9.	Accessories	:	a)	Tee, Counter flange, nuts & bolts, suitable gasket etc
			b)	½”NPT cable gland
			c)	Stainless steel nameplate with alpha-numeric engraved for service and tag

3.05.00 DELETED

3.06.00 DELETED

3.07.00 DELETED

approval

4.00.00 **LOCAL INSTRUMENTS**

4.01.00 PRESSURE GAUGE AND DIFFERENTIAL PRESSURE GAUGE

1.	Type	:	Bourdon/Bellows/Diaphragm
2.	Sensing & Socket	:	SS-316
3.	Movement Material	:	SS-316
4.	Case Material	:	Stainless steel. IP-65 (Explosion proof for NEC Class-1, Division 1 area)
5.	Dial Size	:	Generally 150 mm
6.	Scale	:	Black lettering on white in 270 O arc.
7.	Window	:	Shatterproof glass
8.	Range Selection	:	Normal process pressure: 50~70 % of range
9.	Over-range Protection	:	125% of maximum range by internal stop. External stop at zero
10.	Adjustment	:	For Zero adjustment (Micrometer screw external) For Range adjustment (Micrometer screw internal).
11.	Element Connection	:	Argon welding
12.	Process Connection	:	1/2" NPT (M) Bottom for local, back for panel mounting
13.	Performance	:	Accuracy of $\pm$ 1.0 % of span or better
14.	Operating ambient	:	0 - 50 ^{O}C
15.	Safety Feature	:	Blow out disc /diaphragm at the back
16.	Accessories	:	a) Snubbers for pulsating fluid application.discharge b) Stainless steel Diaphragm seals

			for corrosive/ viscous/ solid bearing or slurry type fluid applications
		c)	3-Way SS316 Gauge cock for pressure gauges
		d)	5-valve SS316 manifold from barstock for differential pressure gauge
		e)	Siphons for steam and hot water services
	17. Nameplate	:	Tag number, service engraved in stainless steel tag plate

4.02.00 LEVEL INDICATOR (FLOAT & BOARD TYPE)

1.	Type	:	Float and Board
2.	Float Material	:	SS-316
3.	Float Cable	:	SS-316
4.	Indicator Assembly	:	Epoxy painted Aluminium
5.	Guide wire spring assembly	:	SS-316 (2 Nos.)
6.	Guide Wire Anchor	:	SS-316
7.	Scale Board	:	Anodized Aluminium with engraved marking (Minimum graduation 10mm), mounting brackets and suitable hardware required as per tank height
8.	Elbow Assembly	:	Anodized Aluminium
9.	Flanges	:	RF , ANSI 150 , SS (3 Nos.)
10.	Accuracy	:	± 10 mm or better
11.	Accessories	:	All mounting accessories including counter flange, nuts & bolts, suitable

gasket etc. as applicable, SS Tag plate

4.03.00 GAUGE GLASS

1.	Type	:	Reflex /Transparent
2.	Material		
	Glass	:	Toughened borosilicate resistant to thermal shock
	Body Material	:	~~Carbon Steel~~ Stainless Steel
	Enclosure	:	IP-65 (Explosion proof for NEC Class-1, Division 1 area)
3.	Integral cocks & valves/Fittings	:	i. SS 316
4.		:	ii. Rubber lined corrosion resistant stainless steel (for DM/RO service)
5.	Vessel Connection	:	ANSI Flanged SS316
6.	Accessories	:	i. Integral cocks ii. Drain Valves iii. Companion Flanges, Bolts, nuts, gaskets, SS Tag plate iv. Illuminating lamps, Mica shield as required v. Calibrated scale
7.	Pressure rating	:	Twice the maximum working pressure
8.	Temperature	:	300 ^{O} C
9.	Other details	:	For larger lengths (greater than 1200mm), additional gauge glasses shall be provided with minimum of 50 mm overlap.

4.04.00 SLIGHT GLASS

1.	Type	:	Flap-type.
2.	End connection	:	Screwed / Flanged
3.	Material		
	a) Body	:	SS- 304
	b) Cover plate	:	SS- 304
	c) Indicator	:	SS- 316
4.	Sight Glass	:	Toughened Borosilicate
5.	Gasket	:	Neoprene
6.	Bolts & Nuts	:	High tensile steel.
7.	Hydraulic Test Pressure	:	1.5 times maximum working pressure
8.	Accessories	:	Companion Flanges, Bolts, nuts, gaskets as required, SS Tag plate.

4.05.00 ROTAMETER

1.	Type	:	ON-LINE for line upto and including 50 mm NB. Borosilicate BY-PASS for line size above 50 NB
2.	Metering tube	:	Toughened Borosilicate
3.	Float	:	SS-316
4.	End fittings	:	SS-316
5.	Packing material	:	Teflon / PTFE
6.	Casing	:	Stainless Steel
7.	Gland Rings /Followers/ Other wetted parts	:	Stainless Steel
8.	Orifice Plate	:	Stainless Steel (for bypass type)
9.	Operating Temperature	:	0-50 Deg. c

10.	Test Pressure	:	200% of maximum operating pressure
11.	Scale	:	250 mm nominal length
12.	Graduation	:	Direct reading
13.	Process Connection	:	Flanged (RF) to line size as per ANSI standards (150#)
14.	Tapping	:	D & D/2
15.	Accuracy	:	+/- 2% of full scale reading
16.	Reproducibility	:	Within 0.5% of instantaneous reading
17.	Accessories	:	SS Tag Plate, orifice plate

5.00.00 TEMPERATURE ELEMENTS & ACCESSORIES

5.01.00 RESISTANCE TEMPERATURE DETECTOR

1.	Type	:	Platinum (Duplex), Ungrounded
2.	Platinum (Duplex), Ungrounded	:	100 ohm at 0 ^{O}C
3.	Base	:	Wound on ceramic (anti-inductive)
4.	Wiring	:	3 Wire
5.	Protecting Tube		
	a) O.D.	:	6 mm
	b) Material	:	SS-316, Seamless
	c) Filling	:	Magnesium oxide (Purity above 99.4%).
6.	Response time	:	a) 15 sec. (bare). b) 30 sec. (with thermowell)
7.	Calibration	:	DIN 43760
8.	Accuracy	:	± 0.5%
9.	Head		
	a) Type	:	IP-65 universal screwed type

	b)	Material	:	Stainless Steel
	c)	Terminal blocks	:	Nickel plated Brass-screw type / silver plated
	d)	Cable connection	:	½" NPT gland and grommet
	e)	Others	:	Terminal head cover with SS chain and suitable gasket. Head of TE to be provided with sufficient space and arrangement to mount head mounted temperature transmitter (as applicable).
10.	Accessories		:	a) Adjustable nipple-union-nipple [1/2" Sch 80 X ½" NPT] with thermowell connection b) Compression fittings/unions c) Flanges etc. (for flanged connections only) d) Thermowell (As specified below)
11.	Thermowell connection		:	½" NPT (M) or 150 RF Flanged
12.	Nameplate		:	Tag number, service engraved in stainless steel tag plate

Note: The specifications for RTDs of winding/ bearing of motor/pump, can be as per their manufacturer standards. The manufacturer shall submit the adequate supporting documents for establishing their standard practice. However, the type of RTD shall be Pt-100.

5.02.00 THERMOCOUPLES

1. Type :
   a) 16 SWG wire of Chromel Alumel) (Type-K)
   b) Duplex
   c) Ungrounded
2. Protecting Tube
   a) O.D. : 6 mm
   b) Material : SS-316, Seamless
   c) Filling : Magnesium oxide (Purity above 99.4%).
3. Response time :
   a) < 20 seconds for measurement
   b) < 10 seconds for control
4. Accuracy : $\pm$ 1.1^0 C up to 300 ^{0} C & 0.4% of measured temperature range above 300 ^{0}C
5. Head
   a) Type : IP-65 universal screwed type
   b) Material : Stainless Steel
   c) Terminal blocks : Nickel plated Brass-screw type / silver plated
   d) Cable connection : ½" NPT gland and grommet
6. e) Others : Terminal head cover with SS chain and suitable gasket.

			Head of TE to be provided with sufficient space and arrangement to mount head mounted temperature transmitter (as applicable).
7.	Accessories	:	a) Adjustable nipple-union-nipple [1/2" Sch 80 X ½" NPT] with thermowell connection b) Compression fittings/unions c) Flanges etc. (for flanged connections only) d) Thermowell (As specified below)
8.	Thermowell connection	:	½" NPT (M) or 150 RF Flanged
9.	Nameplate	:	Tag number, service engraved in stainless steel tag plate

5.03.00 TEMPERATURE GAUGE

1.	Type	:	Expansion type (Liquid filled system)
2.	Sensing Element Material	:	Bourdon – SS-316
3.	Bulb and Capillary Material	:	SS-316
4.	Capillary Tubing	:	Inner sheath - solid drawn Material copper tube Outer sheath - PVC tube
5.	Movement Materials	:	Stainless Steel / Direct Bourdon tip connection to pointer spindle
6.	Case Material	:	Stainless Steel stove enameled, black finish, threaded bezel ring, clear glass

			cover conforming to IP 65.
7.	Dial size	:	150 mm
8.	Scale	:	Black lettering on white background in 270 Deg.C arc
9.	Over range protection	:	125 percent of FSD
10.	Capillary Glanding	:	1/2" NPT(M) x compression fitting (SS) to suit capillary
11.	Instrument Connection	:	Bottom connection for local mounting, back connection for panel mounting
12.	Process Connection	:	½" NPT (M) or 150 RF Flanged
13.	Extension Neck Length	:	50 mm
14.	Compensation	:	a) Capillary compensation
15.		:	b) Case compensation
16.	Performance	:	a) Accuracy : + /- 1.0 percent of full scale Deflection
		:	b) Repeatability : Less than 0.5 percent of full range
		:	c) Response time: 15 seconds (max.).
17.	Capillary length	:	3.0 meters (local) / 15.0 metres (local panel)
18.	Other features	:	Shatter proof glass
19.	Nameplate	:	Tag number, service engraved in stainless steel tag plate
20.	Accessories	:	SS316 Thermowell

5.04.00 THERMOWELL

1.	Material	:	SS-316
2.	Manufacture	:	Drilled from bar stock, Hex Head, Tapered design (As per ASME PTC 19.3)

3.	Process connection	:	M33x2
4.	Certification	:	Not applicable
5.	Bore concentricity	:	+5% of wall thickness
6.	Identification mark	:	Tag number punched on head
7.	Surface treatment	:	Polish after machining
8.	Element connection	:	½" NPT (M) or 150 RF Flanged
9.	Head	:	Hex
10.	Length of the hex head	:	31.75 mm (min.)
11.	Accessories	:	SS Plug and chain for test thermo wells SS Nameplate, Flange with companion flange & all required accessories for flanged connections.

Note: Wake frequency calculations shall be furnished for all thermowells for approval.

Thermowells shall be designed such that the resonant frequency is above the exciting frequencies generated by vortex shedding in the process fluid.

5.05.00 METAL TEMPERATURE THERMOCOUPLE

1.	Measuring medium	:	Metal temperature
2.	Type	:	Chromel Alumel (Type-K) Duplex, Ungrounded
3.	Insulation	:	Mineral Insulation Magnesium Oxide
4.	Wire gauge	:	16 AWG
5.	Protective sheath	:	SS
6.	Protective sheath diameter	:	8 mm O.D.
7.	Characteristics	:	Special limits of error as in ANSI thermocouple MC 96.01
8.	Accessories	:	½" BSP SS sliding end connector, weld pad, clamps of heat resistant steel

1.	Type	:	Hydrometer Type
2.	Mounting	:	On line
3.	Accuracy	:	+/- 2% of range
4.	Scale	:	Black letter on white scale
5.	End connection	:	PVC flange

9.06.00 DENSITY/ CONCENTRATION METER

1.	Wetted Part		Stainless Steel
2.	Enclosure		Stainless Steel (IP-65)
3.	Power Supply		24 V DC
4.	Output signal	:	4-20 mA DC (isolated) into 600 ohms
5.	Accuracy		±0.001 g/cc
6.	Indication	:	LCD display
7.	Temp. Compensation	:	Integral
8.	Accessories		Mounting hardware, integral amplifier (if required), cable glands, tag plate etc.

10.00.00 **SOLENOID VALVES**

1.	Operating Principle	:	Electromagnetic (noiseless)
2.	Coil voltage rating	:	240 V AC /24 V DC (as required)
3.	Ways	:	2/3/4 way
4.	Port size	:	1/4" NPT all ports
5.	Body	:	SS bar stock
	Trim	:	SS-316
6.	Duty	:	Suitable for continuous energization
7.	Sealing	:	Airtight and leak proof
8.	Ambient Temperature	:	0 - 50 ^{O} C

9.	Fluid Temperature	:	0-150 ^{O} C (approx.)
10.	Coil Enclosure	:	Stainless Steel
11.	Insulation	:	Class-H
12.	Coil Casing	:	IP-65 (Explosion proof for NEC Class-1, Division-1 area)
13.	Mounting	:	On pipe or on panel
14.	Cable Connection	:	½" NPT
15.	Accessories	:	Cable glands, SS Tag plate

5.01.00 DELETED

6.00.00 **ANALYZERS**

All Analyzers shall be of microprocessor based design. The general technical specification of the analyzers is provided in this section. Bidder in his offer shall indicate the sample flow requirement of each analyzer and the total quantity of cooling water required for the system.

6.01.00 **CONDUCTIVITY ANALYZER**

A. Sensor

1.	Type of Cell	:	Flow thru'
2.	Conductivity Range	:	As per process
3.	Cell Constant	:	0.01 / 0.1 / 1.0 depeding upon range
4.	Temp. Compensation	:	Manual and Automatic (Integral) 0-100°C
5.	Process Connection	:	Screwed
6.	Wetted Parts	:	Electrodes-SS 316L/ Insulators KYNAR/ Viton
7.	Pressure Rating	:	10 kg/cm^2
8.	Accessories	:	Vessel (SS 316) with ½" NPT connection
9.	Cable	:	Upto transmitter in flexible conduct

B. Transmitter

1.	Type	:	Microprocessor based, Single stream
2.	Mounting	:	2" pipe
3.	Protection Class	:	IP-65 or better
4.	Output	:	4-20 mA DC (isolated)
5.	Display	:	Digital Display in Engineering Unit, Alarm Status.
6.	Zero/Span Adjustment	:	Front Panel Membrane type Keyboard

7.	Temp. Compensation	:	Automatic
8.	Diagnostic	:	Self diagnostic for electronics, electrode etc
9.	Alarm	:	Dual set point, hysterisis and time delay adjustable
10.	Enclosure	:	Die cast aluminum, epoxy coated
11.	Cable Termination	:	Internal (cable entry through conduit)
12.	Accuracy	:	± 1.0 % of measured range
13.	Response time	:	Less than 5 sec
14.	Stability	:	± 1.0 % of output range / month non-cumulative
15.	Accessories	:	a.2" pipe mounting bracket, Sensor cable with flexible conduit (as required), ½" NPT Cable Gland, SS Tag plate, For cation conductivity- Dual Ion-Exchange column, resin, etc. (minimum 12 months' requirements). b.Retractable type conductivity sensor along with flow chamber and other accessories shall be provided for vacuum application. Transmitter (local) along with 4-20 Ma output to SWAS room & DDCMIS shall also be provided.

6.02.00 **pH ANANYER**

A. Sensor

1.	Type of Cell	:	Flow thru'
2.	Range	:	0-14 pH
3.	Type of measurement	:	Combination electrode
4.	Temp. Compensation	:	Manual and Automatic (Integral) 0-100°C
5.	Process Connection	:	Screwed

6.	Measuring Electrode	:	Glass, high independence, thin electrode in one housing
7.	Pressure Rating	:	10 kg/cm^2
8.	Accessories	:	Vessel (SS 316) with ½" NPT connection
9.	Cable	:	Upto transmitter in flexible conduct
10.	Preamplifier	:	Integral or separate
11.	Liquid Junction	:	Ceramic / Kyner or equivalent
B.	**Transmitter**		
1.	Type	:	Microprocessor based, Single stream
2.	Mounting	:	2" pipe
3.	Protection Class	:	IP-65 or better
4.	Output	:	4-20 mA DC (isolated)
5.	Display	:	Digital Display in Engineering Unit, Alarm Status.
6.	Accuracy	:	± 0.2% of FSD or better
7.	Response time	:	Less than 5 sec
8.	Stability	:	± 0.001 pH /week
9.	Repeatability	:	± 1% or better
10.	Temp. Compensation	:	Automatic (Pt-100 sensor)
11.	Diagnostic	:	Self diagnostic for "Calibration requried"/ "Calibration O.K.", electrode checking etc.
12.	Alarm	:	Dual set point, hysterisis and time delay adjustable
13.	Enclosure	:	Die cast aluminum, epoxy coated
14.	Cable Termination	:	Internal (cable entry through conduit)
15.	Accessories	:	2" pipe mounting bracket, Sensor cable

				with flexible conduit (as required), ½" NPT Cable Gland, SS Tag plate, , Ultrasonic Electrode Cleaner, Buffer solution tablets

6.03.00 **SILICA ANALYZER**

1.	Type	:	Colorimetric monitor, gravity / pumped feed Microprocessor based
2.	No. of Streams	:	Multi-stream with atleast one stream as spare
3.	Output	:	4-20 mA DC (isolated) into 600 ohms
4.	Readout	:	Digital Indicating meter for direct readout
5.	Accuracy	:	± 1% of F.S.D or better
6.	Reproducibility	:	± 2% of F.S.D. or better
7.	Calibration	:	Manual & automatic
8.	Cycle time	:	Less than 10 min or better
9.	Operating temperature	:	0-50 ^{O} C
10.	Temperature Compensation	:	(Pt-100 Sensor)
11.	Mounting	:	2" pipe
12.	Life of light source	:	10,000 hours (approx.)
13.	Alarm Facility	:	2 HI & 2 LO independently adj. over span.
14.	Enclosure Protection	:	IP-65
15.	Accessories	:	Reagent cabinet , Sample strainer, Reagent Reservoir etc., Phenolic name plate, Reagents & consumables, Special cables.

6.04.00 **SODIUM ANALYZER ASSEMBLY**

1.	Type of Cell	:	Flow Through ion-selection electrode
2.	Flow Chamber	:	Plexi Glass Body or equivalent

3.	Measuring Electrode	:	Sodium Selective Glass Electrode
4.	Output	:	4-20 mA DC (isolated) into 600 ohms
5.	Temp. Compensation	:	Automatic upto 45 deg.C
6.	Read Out	:	Digital Indicating meter
7.	Accuracy	:	< 5% of reading
8.	Response Time	:	2 minutes or better
9.	Mounting	:	Flush Panel
10.	Calibration	:	Automatic
11.	Alarm Facility	:	2 HI and 2 LO independently adj. over span.
12.	Enclosure Protection	:	IP-65 or better
13.	Accessories	:	Phenolic tag plate, Sample filter, Pressure regulator & flow meter, Automatic calibration kit, Reagents and consumables, Special cables, ½" NPT cable gland.

6.05.00 DELTED

6.06.00 DELETED

6.07.00 DELTED

6.08.00 **TURBIDITY ANALYZER**

1.	T y p e	:	Nephelometric (Light reflection principle)
2.	Range	:	0.001-100 NTU
3.	Body	:	Corrosion resistant polystyrene
4.	Enclosure	:	IP-65 or better

5.	Output	:	4-20 mA DC isolated to a load of 600 Ohms (minimum)
6.	Readout	:	LCD Display
7.	Accuracy	:	Better than ± 2% of full scale
8.	Repeatability	:	± 1% of reading or ±0.002 NTU (which ever is greater)
9.	Accessories	:	Phenolic nameplate, Special cable upto transmitter with flexible conduit, ½" NPT Cable Glands, 2" pipe mounting bracket, Calibration kit & standard solution etc.

6.09.00 DELTED

6.10.00 **SAMPLE CONDITIONING SYSTEM**

Sample conditioning system shall be designed and constructed to receive and condition all samples as required by the respective analyzers. This shall include all conditioning equipment mentioned herein:

a) Sample filtering

b) Primary and final sample cooling and temperature control

c) Pressure reduction and control, as required

d) Flow rate control

e) Pressure and Temperature Protection

LCP AND JUNCTION BOXES SPECIFICATION

1.00.00 **GENERAL REQUIREMENT**

1.01.00 ENCLOSURES FOR INSTRUMENTS AND OTHER EQUIPMENT

1.01.01 All panels, cabinets, distribution boxes, junction boxes, terminal boxes and all other field mounted equipment / enclosures shall have suitable environmental protection as detailed in Section-I of this volume of the specification.

1.02.00 SURFACE PREPARATION & PAINTING

1.02.01 All sheet metal panel/ desk exterior steel surfaces shall be sand blasted, ground smooth and painted as specified below.

1.02.02 Suitable filler shall be applied to all pits, blemishes and voids in the surface. The filler shall be sanded so that surfaces are level and flat; corners are smooth and even. Exposed raw metal edges shall be ground burr-free. The entire surface shall be blast clean to remove rust and scale and all other residue due to the fabrication operation. Oil, grease and salts etc. shall be removed from the panels by one or more solvent cleaning methods prior to blasting.

1.02.03 Two spray coats of inhibitive epoxy primer surfacer shall be applied to all exterior and interior surfaces, each coat of primer surfacer shall be of dry film thickness of 1.5 mil. A minimum of two spray coats of final finish color (Catalyzed epoxy or polyurethane) shall be applied to all surface of dry film thickness 2.0 Mil. The finish colors for exterior and interior surfaces shall conform to the following shades:

- Exterior – Opaline green shade 275 of IS: 5 or equivalent international code..
- Interior - Brilliant White.

1.02.04 Paint films, which show sags, cheeks, blisters, teardrops, fat edges or other painting imperfections, shall not be acceptable.

1.03.00 WIRING

1.03.01 All spare contacts of relays, switches and push buttons shall be wired up to the terminal blocks. All intercommunications between sections of panels/desks shall be furnished.

1.03.02 Each wire shall be identified at both ends with wire designation as per approved wiring diagram. Heat shrinkable type ferrules with indelible computerized ink print shall be used with cross- identification.

1.03.03 All wire termination shall be made with insulated sleeve and crimping type lugs. Wire shall not be spliced or tapped between terminals. Open-ended terminal lugs will not be accepted. Wires shall not be looped around the terminal screws or studs.

1.03.04 Internal wiring should be terminated uniformly on one side of the terminal block leaving the other side available for termination of outgoing cables. Internal wiring shall be grouped so that all outgoing wiring to each particular remote location is terminated on adjacent terminal blocks. Interior wiring and jumperings shall be arranged so that external connections can be made from internal side of terminal blocks. Common connections shall be limited to two (2) wires per terminal.

1.03.05 Wiring shall be arranged to ensure free access to all instrument or devices for maintenance. No wire shall be routed across the face or rear of any device in a manner, which will impede the opening of covers or obstruct access to leads, terminals or devices

1.03.06 Wires shall be dressed and run in trays or troughs with clamp-on type covers. Wirings may be neatly bunched in groups by non-metallic cleats or bands. Each group shall be adequately supported along its run to prevent sagging or strain on termination.

1.03.07 Shield wires shall be terminated on separate terminal blocks. Common connections shall be limited to two wires per terminal. Signal circuit shields shall be grounded at the power supply end only or as recommended by manufacturer.

1.03.08 All low level signal cables shall be separately bundled to from control cable and maintained at 300 mm minimum spacing from control bundles.

1.03.09 Panel internal wiring shall follow distinct color-coding to segregate different voltage levels viz. 24V DC, 48V, 110V AC, 240V AC, 220V DC etc.

1.03.10 Thermocouple lead wires, analyzer measuring lead wires, or any other lead wires carrying measuring signal of the order of low milli volt or micro volt shall be electrically and physically isolated from other AC and DC wiring. Shielded wires used in such cases for panel internal wiring shall be continuous and ungrounded with the shield terminated individually and separately in panel terminal block.

1.03.11 Wiring to door mounted devices shall be provided with multi-strand wires of (49 strands minimum) adequate loop lengths of hinge-wire so that multiple door openings will not cause fatigue failure of the conductor.

1.03.12 Internal wiring in factory pre-wired electronic systems cabinets may be installed according to the Contractor's standard wire size, insulation, and method of termination on internal equipment. Insulation for all wiring, including circuit board wiring, back panel wiring, power supply wiring and interconnecting cables between devices shall pass the vertical flame test per IPCEAS-1981. Identification of conductors may be done by insulation color-coding identified on drawings or by printed wiring lists.

1.04.00 TERMINAL BLOCKS

1.04.01 All terminal blocks shall be rail mounted/ post mounted type, cage clamp type with high quality non-flammable insulating material of melamine suitable for working temperature of 105 Deg C. The terminal blocks in field mounted junction boxes, instrument enclosures racks etc. shall be suitable for cage clamp connections. The terminal blocks in Control Equipment Room termination/ marshalling cubicles shall be suitable for post mounted cage clamp connection at the field input end. The exact type of terminal blocks to be provided by Bidder shall be subject to Owner.

1.04.02 All terminal blocks shall be provided complete with all required accessories including assembly rail, locking pin and section, end brackets, small partitions, transparent covers, support brackets, distance sleeves, warning level, marking etc. For RTDs ring - tong type lugs shall be used at Junction Boxes.

1.04.03 The characteristics of the terminal blocks shall be as follows.

i) High contact force, independent of conductor cross-section and large contact surface area.

ii) Integrated self-loosening protection to avoid shifting of contact surface that may allow contamination of connection point.

iii) Inspection and maintenance free (resistant to thermal aging and vibration)

iv) Low and constant voltage drop

1.04.04 The insulation of the terminal blocks shall be of suitable thermoplastic material.

1.04.05 The spacing between Terminal blocks channels in panels and cubicles shall be adequate for routing the cable troughs and to allow adequate free workspace for termination and removal of wires. The terminal blocks shall be arranged with atleast 100 mm clearance between two sets of terminal blocks and junction box walls.

1.04.06 Signals of different voltage levels shall be clearly segregated by providing separate rows to each type of signal and by using terminal blocks of different color for each type of signal and by providing barrier strips between them.

1.04.07 Terminal blocks shall be provided with white marking strips / self-adhesive marker cards and where permitted by the safety codes and standards, shall be without covers. Power terminals and high voltage (above 48 volts) terminals shall have protection covers. All terminals shall be provided with permanent terminal identification numbers on both sides.

1.04.08 At least 20% spare unused terminals shall be provided on each terminal block for circuit modifications and for termination of all conductors in a multi-conductor control cable.

1.04.09 The bottom of the terminal block shall be at least 200 mm above the cable gland for bottom entry type panels.

1.04.10 For extending 24 V DC supply to panels, the size of the terminals shall be decided based on voltage drop and not based on current.

1.04.11 Other requirements of the terminal blocks are as follows:

i) The last terminal in a rail-mounted assembly shall be closed with an end plate and end bracket.

ii) For visual and electrical separation of terminal groups, partition plates shall be provided, which can be push fitted after forming an assembly.

iii) Design shall permit testing of incoming and outgoing signals by using suitable test plug and socket without disconnecting the cable connections.

iv) It shall be possible to use jumper plugs through the above test plug socket to connect adjacent terminals. Adequate number of short circuit jumper plugs shall be provided for the purpose.

v) Where more than one connection to a terminal block is required, two tier terminals shall be used.

1.05.00 GROUNDING

1.05.01 Separate Protective and Electronic system ground as required shall be provided.

1.05.02 All panels, desks, cabinets shall be provided with a continuous bare copper ground bus (Frame ground), bolted to the panel structure at bottom on both sides and effectively ground the entire structure. The bolts shall face inside of panels.

1.05.03 For electronic system cabinets the electronic system ground bus (Electronic ground) shall be similar but insulated from the cabinet and shall be separately connected to the system ground .The same ground may be used to earth the shield of shielded signal cables, otherwise a separate ground bus shall be provided for connecting the signal cable shields. Cable shields shall be grounded at the panel end only and shall never be left open .The electronic ground between panels of a shipping section shall be firmly looped.

2.00.00 **CONTROL DESKS & PANELS**

2.01.00 GENERAL

2.01.01 All control desk, panels etc. shall be furnished fully wired with necessary provision for convenience outlets, internal lighting, utility receptacles, grounding, ventilation, space heating, anti-vibration pads, internal piping &

accessories as required for completeness of the system.

2.01.02 The design shall conform to the EN ISO 11064 (Ergonomical design of Control Room), Part 1, 2 and 3.

2.01.03 The exact dimensions, material, construction details, grounding, general arrangement etc. shall be as per actual requirement and shall be finalized during detail engineering and subjected to Owner's approval.

2.01.04 Incoming power supply feeders shall be duplicated. Alarm shall be provided for failure of a power supply feed.

2.01.05 For Control desk/ panel mounted instruments/ devices etc. which are to be powered from UPS, all required conversion of interface equipments/ accessories to make such devices compatible with UPS supply shall be provided. All necessary hardware like input switches/ fuse unit for each feeder as well as switch fuse unit for each instrument/ device on the power supply line shall be provided. From UPS redundant feeders shall be provided wih suitably rated MCB and provision of fast auto changeover of UPS feeders.

2.01.06 Crating of the panels and desks shall be suitable for protection against shock, vibration, inappropriate handling and inclement weather conditions during transportation and warehousing. Mounted equipment shall have adequate protection against damage during handling, transit and storage. Suitable desiccant shall be used inside the packing case.

2.01.07 Nameplate

a) Nameplate shall be provided for instrument or device mounted on the panel.

b) Nameplates for panels shall be provided both in front and rear.

2.02.00 CONTROL DESK

2.02.01 Control desk shall be free standing, floor mounting, table top type with doors at back and shall be constructed of 3 mm thick (minimum) CRCA steel or Aluminium extrusion. Aluminium structure shall be anodized or powder coated paint finish. The top surface of control desk shall be 30 mm (minimum) thick with the top 12 mm (minimum) of acrylic solid surface and the remaining 18 mm of laminated medium density fibre (MDF) board.

2.02.02 Monitors with retractable keyboard shall be provided on the desk. Desk shall be arranged in arc-like shape without any sharp edges. Edges shall be extruded PVC or rounded post-formed laminate.

2.02.03 Desks shall be of modular, scalable and industrially ruggedized design and shall have connections for PA system handsets & telephone sets.

2.02.04 Desks shall have concealed cable trays for wire dressing. Both Horizontal & Side Managers (2 separate horizontal cable routing wire baskets for power & data cables) shall be provided.

Each User station will be provided with 2 separate power distribution units (1 for Main line & 1 for UPS line). Each power distribution unit will have 6 points of 5/13 Amp sockets, Mains MCB On/Off Switch & Indicator.

Adequate heat management provision for Exhaust of heat from within the Console Desk Assembly shall be provided. There will be multiple fans provided in the Main Control Desk. Each Fan will be of 230 VAC 250 CFM Ball Bearing based. Ventilation louvers will be provided on both Front & Rear Modesty with special Air Filters. Adequate space for CPU & Other equipments placed with in the desk.

2.02.05 Design shall include Earthing bolts.

2.02.06 Back installed items shall be suitably concealed from front view.

2.02.07 All operator workstations for SG, TG, Auxiliaries & Off-site Plants shall be mounted on this Control Desk. The cabling / wiring between OWS & CPUs, power supply cables etc. shall be aesthetically routed and concealed from view.

2.02.08 HARDWIRED DEVICES ON CONTROL DESK (DRAW OUT SECTION)

Release and Lamp Test push buttons shall be provided for a set of push buttons (decided during detail engineering stage). Depending on the type of control/ function, required number of push buttons/ indicating LEDs & their color, push button stations shall be selected. The size of push button stations shall be 24 x 48 mm or 25 x 50 mm and shall have service inscription details at the front. Emergency push buttons (with cover) shall be mounted on top of Control Desk.

2.03.00 BACK UP PANEL

2.03.01 Construction shall be from CRCA steel of thickness not less than 3mm.

2.03.02 Upright back-up panel shall be provided where hardwired devices shall be mounted on a mosaic grid type console. The mosaic grid tiles shall be of 24 mm x 48 mm (or 25 mm x 50 mm) size, made of heat & flame retardant, self extinguishing and non-hygroscopic material with flat matt finish without glare and non reflecting type.

2.03.03 DELETED

2.03.04 Colored Mimic for different Off-site plant control systems (as enumerated elsewhere in this specification) and hardwired annunciation system shall also

be mounted on the back up panels.

2.04.00 PANELS/CABINETS

2.04.01 All DDCMIS system modules, power supply components and other Local Control panels (PLC/Relay based) shall be housed in cabinets as specified below.

2.04.02 The cabinet mounted equipments shall be fully assembled, installed in mounting racks, wired and fully tested as per specification requirements and Owner approved drawings prior to shipment to the project site.

2.04.03 The Bidder shall ensure that the cabinets are complete & ready for installation before dispatch from manufacturing works. The installation work at project site for these cabinets shall only involve connections through multi-pair cables from marshalling cabinets (wherever provided) to system cabinets and inter-cabinet/cabinet to Control Desk/ Back up Panel.

2.04.04 All electronic cards, network components, power supply modules etc. located shall be suitably housed in cabinets and shall be neatly arranged in sub-racks. Network components shall be visible in door closed condition (e.g. Glass doors etc.) as approved by Owner.

2.04.05 Bidder shall design the cabinet internal arrangement, floor cutout and cable gland plate such that all the cables entering or leaving the cabinet can be properly glanded in the gland plate.

2.04.06 The packaging density of panels shall be such that the temperature rise within the panels shall never exceed 10°C above ambient even under worst operating conditions. Cooling Fans shall be provided wherever required and this shall be of industrial grade.

2.04.07 TECHNICAL PARTICULARS

1.	Material of Construction	:	Cold Rolled Coal Annealed (CRCA) steel sheet	
2.	Thickness of Sheet	:	a)	2.0 mm for faces supporting instruments / terminals
		:	b)	1.6 mm for other sides and top
3.	Construction	:	Welded throughout as per approved National Standards	
4.	Post welding operation	:	a)	Grounding of all welds to smoothness
		:	b)	Rounding of corners

		:	c)	Cleaning of weld spatters
5.	Panel height	:	2300 mm (approx)	
6.	Corners	:	7 mm inner radius	
7.	Dimensional Tolerances	:	a)	In height & length - 3 mm
			b)	In height between adjacent sections - 2 mm
			c)	Total for a group - 6 mm
8.	Doors	:	Double, recessed, turned back edges, full height front & rear	
	i) Thickness of Sheet	:	2 mm	
	ii) Hinges	:	Stainless steel	
	iii) Door latches	:	Three point type	
	iv) Door gaskets	:	Neoprene rubber on fixed frame to result dust proof/weatherproof enclosure	
	v) Opening of the doors	:	Outward	
	vi) Louvers	:	With removable wire mesh to ensure dust and vermin proof	
9.	Gland plates	:	Removable in sections 4 mm thick (bottom)	
10.	Cable entry	:	Bottom	
11.	Hardware	:	a)	Anti vibration pad- 15 mm
			b)	Predrilled base channel ISMC – 100 or equivalent for all sides
			c)	Stainless steel buff- finished 2 mm thick kick plate for all sides
			d)	Stainless steel scratch strips along desk edges fixed with pan-head recessed screws
			e)	Rubber strips to ensure air

tightness between kick plate and finished floor

f) Lifting hook / Eye bolt

g) Drawing pocket

h) Door switch, lamps, thermostat, heaters and industrial grade cooling fans,, illumination fixures

12.	Name Plate	:	Both at front and back surface of the panel
13.	Fixing of name plate	:	Stainless steel pan head screws
14.	Name plate material	:	Laminated phenolic (3 layers)
15.	Lettering	:	Black with white engraved
16.	Mounting of terminal blocks	:	Vertical angle support bracket tack welded on sheet steel plate, screwed on internal wall of enclosure

2.05.00 FURNITURE

All the furnitures in the Central / Local control Room (s), Engineers' rooms, Instrument laboratory , SWAS Room & any other rooms with C&I equipments located in different plant buildings under Bidder's scope shall be included in Bidder's scope of supply. Bidder shall provide following industrial grade furniture items as a minimum from reputed manufacturers/suppliers meeting International Standards. The furniture shall be modular and latest with ease of operational features. The furniture shall be modern, aesthetically designed, modular, flexible, space saving and future safe.

2.05.01 WORK STATION FURNITURE

Modular work station furniture, suitable for mounting servers & historians, programmer stations, PC based systems, printers (A4/A3 color laserjet) etc. shall be provided.

2.05.02 PC RACK

PC Racks shall be provided to mount CPUs of workstations/PCs of OWS/LVS etc. in control room. For each PC / workstation / monitor at least one chair shall be included.

2.05.03 CHAIRS

Industry standard revolving chairs with wheels and with provision for adjustment of height (hydraulically/gas lift) shall be provided for the operators, unit-in-charge & other personnel in control room area. These shall be designed for sitting for long duration such that these are comfortable for the back.

2.05.04 TABLES

Industry standard computer tables shall be provided & shall be as approved by Owner during detailed Engineering. Glass top teak wood horse shoe shaped table with vertical file mounting arrangement (two layers to house approx. 40 Nos of files and lockable drawers at both ends) for Engineering Room shall be provided.

2.05.05 ALMIRAHS

Steel Almirahs shall be provided for keeping documents in the documentation room. Glass doors for each rack shall be provided such that the documents are visible from outside. Size of the rack shall be sufficient to easily fit technical manuals. The exact details shall be approved by Owner during detailed Engineering.

2.05.06 KEYPAD

One keypad per unit shall be provided for the storing of keys of relevant areas of the unit in the control room.

2.05.07 LOCKERS

Suitable lockers shall be provided in the room adjacent to the control room for storing of personal articles of control room personnel. Also, lockers of bigger size shall be provided in documentation Room for storing of personal documents. Details shall be finalized and approved by Employer during detailed engineering.

3.00.00 **LVS PANEL**

3.01.00 An arc shaped Large Video Screen (LVS) panel shall be supplied for mounting large video screens in number of tiers in various Control rooms as specified elsewhere in this specification.

Biddr shall provide and fix ACP cladding around the LVS screen including covering the LVS back side and LVS stand. The cladding will be from floor finish to 600 mm above LVS screen like a self-standing partition with necessary openings for system requirement. ACP paneling shall be with 304 grade & approx. 0.5 mm mirror finish SS strip.

3.02.00 The profile, dimensions and the general arrangement shall be finalized & approved by Owner during detailed engineering. Recommendations, if any, for the control room lighting in order to ensure continuous proper viewing of the LVS screen by the operator & shift incharge (without any fatigue) shall be

clearly brought out by the Contractor in his offer, alongwith all relevant details/basis.

3.03.00 Any other requirement for proper LVS mounting & functioning & viewing shall also be specifically brought out by the Contractor in his offer, along with all relevant details.

4.00.00 **LOCAL INSTRUMENT RACK (LIR) & LOCAL INSTRUMENT ENCLOSURE (LIE)**

4.01.00 GENERAL

4.01.01 Devices (Transmitters/ Switches) located in the field shall be suitably grouped together to the extent possible and installed in the LIE (Closed Rack) and LIR (Open Rack) in Boiler/TG Building and Off-site plant areas.

4.01.02 Racks and enclosure shall be factory prefabricated & painted and shall complete with internal piping, tubing, manifold, isolation valves, blowdown valves, integral junction box, illumination etc.

4.01.03 No more than six instruments shall be grouped in a single rack / enclosure.

4.01.04 Racks shall be installed above the tapping points for air, flue gas and coal air mixture application whereas for applications such as for water and steam, racks to be installed below the source point.

4.01.05 Attention shall be paid in the layout to avoid air traps in liquid piping and water accumulation in air /gas piping.

4.01.06 Racks used for furnace, flue gas and air application shall be provided with intermittent & continuous air purging

4.01.07 Welding of impulse lines shall comply with the provisions of the latest applicable ANSI Code for Pressure Piping.

4.01.08 Earth stud shall be furnished at rack for safety grounding.

4.02.00 LOCAL INSTRUMENT ENCLOSURE (LIE)

4.02.01 Enclosure shall be free standing type. Racks shall be adequately reinforced to ensure true surfaces and to provide support. Major load - bearing posts shall be suitably supported by gusset plates or moment members.

4.02.02 Enclosure outer shall be constructed from at least 3 mm thick steel plate and epoxy painted to shade gray. Base frame shall be made of ISMC 100 and black colour finish.

4.02.03 2” NB galvanized pipes shall be laid horizontally and supported at two end channels to mount transmitters at accessible height. Center posts or any

member, which would reduce access, shall be avoided.

4.02.04 Double leaf interlocking front opening doors with three point locking shall be provided and shall be arranged for maximum possible access to the interior. Key shall be of identical for all enclosures.

4.02.05 Doors shall have concealed quick removal type pinned stainless steel hinges and locking handles. Gaskets shall be used between all mating sections to achieve dust and weather proof enclosure rated for IP-65 including the internal junction box. All enclosures shall have access doors on front side.

4.02.06 Removable type bulkhead plates of thickness not less than 6 mm shall be mounted at the racks with suitable high temperature gasket. Impulse lines within the enclosures shall be properly clamped.

4.02.07 All internal wirings between the instruments and junction box shall run through flexible conduits. No exposed wirings within transmitter racks both open and closed type, is admissible.

4.02.08 Racks shall have a common blowdown drain header, which will connect individual instrument blowdown line after suitable pressure breaking through regulating globe type blowdown valves. Covered funnels shall be used for saturated liquid and steam service, whereas, open funnels may be used for cold liquid services. Header (2" NB ASTM A 106, Sch-80 Gr. C) shall be suitably sloped and shall have one end flanged and extending beyond the rack for connection to plant drain header..

4.02.09 Each rack shall be provided with one receptacle, light fixtures with wire guard and one lighting switch each at instrument & Junction box compartments with wire guard. Lighting switches may be door actuated & mounted inside the panel. Outlet box, switch box and device covers shall be of galvanized stamped steel. Light switches and receptacles shall be installed inside the enclosure on the wall near the latch side of the enclosure door. Light fixtures shall be installed on the ceilings of the enclosures.

4.02.10 Power supplies for miscellaneous devices shall be provided with MCB located within the enclosures. MCB shall be mounted in fuse blocks. Nameplates shall be furnished above the MCB blocks, identifying the devices being served.

4.02.11 Vibration dampeners shall be installed for supporting each enclosure. The loading at each corner of the enclosure shall be determined by actual test weighting when construction is complete to determine the correct length of each dampener for proper loading of the dampener in accordance with manufacturer's recommendations

4.03.00 LOCAL INSTRUMENT RACK (LIR)

4.03.01 Rack shall be free standing type constructed from 6 mm thick steel channel frame provided with a canopy to protect the instrument from dripping water or

falling objects and shall be epoxy painted. Canopy shall be of CRCA steel sheet of at least 3 mm thickness.

4.03.02 Rack Major load-bearing posts shall be suitably supported by gusset plates or moment members. Suitable fenders grill shall be welded to the end-posts of the rack to outline a boundary beyond which no mounted equipment shall project to protect instrument from accidental contact during personnel movement. Center posts or any member, which would reduce access, shall be avoided.

4.03.03 2" NB galvanized pipes laid horizontally and supported at two end channels shall be employed at working accessible height for mounting of instruments.

4.03.04 All internal wirings between the instruments and junction box shall run through flexible conduits. No exposed wirings are admissible.

4.03.05 Racks shall have a common blowdown drain header, which will connect individual instrument blowdown line after suitable pressure breaking through regulating globe type blowdown valves. Covered funnels shall be used for saturated liquid and steam service, whereas, open funnels may be used for cold liquid services. Header (2" NB ASTM A 106, Sch-80 Gr. C) shall be suitably sloped and shall have one end flanged and extending beyond the rack for connection to plant drain header..

Each rack shall be provided with one receptacle, one light fixture with wire guard and one lighting switch. Outlet box, switch box and device covers shall be galvanized stamped steel. Light fixtures shall be installed on the canopy of the rack

4.03.06 Power supplies for miscellaneous devices shall be provided with MCB located within the enclosures. MCB shall be mounted in fuse blocks. Nameplates shall be furnished above the MCB blocks, identifying the devices being served.

4.04.00 JUNCTION BOX

1.	Type of Enclosure	:	Dust tight & weatherproof conforming to IP 65
2.	Material	:	3 mm sheet steel / fiberglass reinforced polyester(UV stabilized)
3.	Type of Cover	:	Solid unhinged with retention chain / Screwed at all four corners
4.	Paint	:	i) Exterior : Opaline green shade 275 of IS: 5 ii) Interior - Brilliant Glossy White.

			Surface / Two (2) inch Pipe stanchion
5.	Mounting	:	(At a dry compartment at one side of the enclosure / rack with front opening type door)
6.	Cable Entry	:	3 mm (min) Bottom / side Gland plate
7.	Gasket	:	Neoprene
8.	Grounding	:	Brass earth lug with green screw head External-2 nos , Internal-1no. (M6)
9.	Number of Drain Holes	:	Two at bottom capped
10.	Identification	:	Label for JB and Tags for cable
11.	Accessories	:	a) Rail mounted cage clamp type screwless terminals (suitable for conductor size up to 2.5sq.mm of suitable voltage grade) with markers and 20% spare terminals b) Cable gland (Brass) & raceways c) Ferrules & lugs (Brass) d) Aluminum back panel e) Canopy at top f) Mounting brackets g) bolts and nuts made of brass etc.

ERECTION HARDWARE

1.00.00 GENERAL TECHNICAL REQUIREMENTS

This section provides the general technical guidelines for the erection materials for instruments. All erection materials shall be of good quality and conform to the operating environment of the corresponding instrument.

However, any item required for erection of Bidder supplied system but not categorically indicated in this section, shall be supplied by the Bidder and all these items shall conform to International / National standards / codes.

1.01.00 Electrical Accessories

Electrical conduit and associated materials shall conform to the requirements of the articles which follow :

a) Rigid Steel Conduit

i) Conduits up to and including 25 mm shall be of 16 SWG and conduits above 25 mm shall be of 14 SWG. Minimum size of conduits shall be 19 mm.

ii) Each piece of conduit shall be straight, free from blister and other defects and covered with capped bushing at both ends.

iii) All rigid conduit couplings and elbows shall be hot dip galvanized rigid mild steel in accordance with IS:9537 Part-I (1980) and Part-II(1981).. The conduit interior and exterior surfaces shall have a continuous zinc coating with an over coat of transparent enamel lacker or zinc chromate. Conduits shall be furnished in standard length of 3 meters, threaded at both ends.

iv) All rigid conduit fittings shall conform to requirements of IS:2667,1976. Galvanised steel fittins shall be used wth steel conduit. All flexible conduit fittings shall be liquid tight, galvanized steel. The end fitting shall be compatiable with the flexible conduit supplied.

b) Flexible Conduit

i) Flexible conduit shall be of three layer construction of very high quality of lead coated steel. Outside and inside layer shall be reinforced with heat resistant material.

ii) Lead coating outside and inside of the conduit steel surface shall provide a non-corrosive characteristic particularly in acidic atmosphere. Besides flexibility, this shall be strong enough to stay at the desired profile without support and shall be durable and strong so as to offer sufficient mechanical protection. It shall also be fully liquid dust and air tight and shall withstand a continuous hydraulic pressure up to 2 Kg/Sq. cm and temperature up to 200 °C.

c) Special Fittings

i) Conduit sealing and fittings shall be provided as required and shall be consistent with the area and equipment with which they are installed.

ii) Double locknuts shall be provided on all conduit terminations not provided with threaded lugs and couplings. Locknuts shall be designed to securely bond the conduit to the enclosure when tightened. Locknuts shall not loosen due to vibration.

1.02.00 Electrical Junction Box:

Please refer to Section VII , Subsection – D of this volume of the Specification.

1.03.00 Cable Gland

1.	Type	: Double compression
2.	Entry Thread	: NPT / ET
3.	Material	: Brass
4.	Finish	: Cadmium Plated.
5.	Protection	: IP 54 or better
6.	Accessories	: Neoprene gasket, locknuts, reducers etc

1.04.00 Cable Tray

1.	Material	: Mild steel, slotted
2.	Thickness	: not less than 2.0 mm
3.	Finish	: Hot dip galvanized
4.	Perforation	: As per MFR standard
5.	Cover	: Suitable for tray

1.05.00 Process Hook Up Accessories & specification

Material and rating of the hook up items shall suit the piping and fluid condition. Hook up materials shall be IBR certified for applicable cases. Bidder shall furnish hook up drawings and the drawings for open racks & closed racks for owner's approval.

1.05.01 Seamless Stainless Steel Pipe

1.	Reference	: ASTM A-312 TP 316
2.	Material Grade	: TP 316
3.	Type	: Seamless /Plain end
4.	Size	: As applicable (e.g.½" NB etc)
5.	Schedule	: 40
6.	Standard Length	: 5 meter

1.05.02 Stainless Steel Pipe Fittings

	1.	Reference	: ASTM A-182 F 316 / ANSI B16.11
	2.	Type	: Forged
	3.	Rating	: 3000 lbs / 6000 lbs / 9000 lbs
	4.	Size	: To suit related SS pipe.
	5.	End connection	: Generally socket weld
	6.	Type of Fittings	: Reducing coupling, male-female reducer, straight coupling, equal tee, three piece union, elbow, cap etc.

1.05.03 Seamless Stainless Steel Tube

	1.	Reference	: ASTM A-213 , ASTM A-249 or ASTM A-269
	2.	Material Grade	: TP 316
	3.	Size	: As applicable (e.g.½" OD X 0.083" wall thickness / ¼" OD X 0.049" wall thickness etc.)
	4.	Type	: Cold drawn annealed, pickled, passivated, de-scaled, hydraulically cleaned seamless tube.
	5.	Properties	: The tube shall be free from scratches and suitable for bending and capable of being flared by hardened and tapered steel pin. The expanded tube shall show no crack or rupture. Hardness shall be RB 80.
	6.	Test Pressure	: 400 Kg/Sq. cm (minimum)
	7.	Tolerance	: ± 0.13 mm for outside diameter
			: ± 15 % for wall thickness
	8.	Standard Length	: 5 meter
	9.	Test	: Flare, Hardness, Ball and Bubble Test

1.05.04 Stainless Steel Tube Fittings

	1.	Reference	: ASTM-A-182
	2.	Type	: Double ferrule double compression
	3.	Material	: 316 Stainless steel forged
	4.	Ferrule	: 316 Stainless Steel

5.	Type of Fittings	: Male / female connector, elbow, cross /equal tee, straight connector, bulkhead union, ferrule etc. as required to suit installation.
6.	Size	: To suit SS tubing and NPT end connection

1.05.05 DELETED

1.05.06 DELETED

1.05.07 DELETED

1.05.08 DELETED

1.05.09 G.I.Pipe

1.	Reference	:	IS-1239, Part-I
2.	Type	:	Medium grade, threaded at both ends protected with end caps
3.	Material	:	Continuous ERW galvanized MS pipe
4.	General	:	Pipe shall be galvanized both inside and outside
5.	Size	:	As applicable (e.g 1/2”/3/4”/1” etc.)

1.05.10 G.I.Pipe Fittings

1.	Reference	:	IS-1239, Part-II for material, dimension, thread etc.
2.	Style	:	Threaded
3.	Type of Fittings	:	Equal tee, three piece union, unequal tee, straight socket, 90 Deg. elbow, reducing socket cap. etc. to suit installation.
4.	Size	:	Suitable to related G.I.Pipe

1.05.11 Carbon Steel Globe Valve

1.	Reference	: ASTM A-105
2.	Type	: Globe
3.	Construction	: Forged Body Cadmium Plated
4.	End Connection	: As applicable (eg. ½” Socket Weld etc.)
5.	Rating	: Cl. 800 / CL. 2500

	6.	Material	: Body - Carbon steel
			: Stem - Hardened Steel
			: Plug - AISI 316 SS
			: Seat- Stainless steel stellited
	7.	Packing	: Teflon / Grafoil as required
	8.	Yoke	: ASTM A105
	9.	Hand wheel	: Carbon steel
	10.	Design standard	: As per ANSI B 16.34

1.05.12 Stainless Steel Globe Valve

	1.	Reference	: ASTM A-182 F316
	2.	Type	: Globe
	3.	Construction	: Forged Body
	4.	End Connection	: As applicable (eg. ½" Socket Weld etc.)
	5.	Proof Pressure	: 400 Kg/Cm2
	6.	Material	: Body - Stainless steel
			: Stem - Hardened Steel
			: Plug - AISI 316 SS
			: Seat- Stainless steel stellited
	7.	Packing	: Teflon as required
	8.	Yoke	: ASTM A182 F316
	9.	Handwheel	: Carbon steel
	10.	Design standard	: As per ANSI B 16.34

1.05.13 Alloy Steel Globe Valve

	1.	Reference	: ASTM A-182 F22
	2.	Type	: Globe
	3.	Construction	: Forged Body

4.	End Connection	: As applicable (eg. ½" Socket Weld etc.)
5.	Rating	: CL. 2500
6.	Material	: Body - Alloy steel
		: Stem - Hardened Steel
		: Plug - AISI 316 SS
		: Seat- Stainless steel stellited
7.	Packing	: Grafoil as required
8.	Yoke	: ASTM A182 F22
9.	Handwheel	: Carbon steel
10.	Design standard	: As per ANSI B 16.34

1.05.14 Structural Steel

Steel supports for JB's, trays; tubes and related equipments shall not be limited to the following:

a) MS Angle
b) MS Channel
c) I-Beam
d) Hexagonal head Bolt & Nut with washer
e) Foundation Bolt & Nut
f) Expansion Bolt
g) Steel Plates / Flats
h) CRCA sheet
i) 50 NB Pipe
j) Pipe clamps, U Bolts & Nuts
k) Checker plate

1.05.15 Condensate Pot

1.	Reference	: ASTM A182 F22 /ASTM A105
2.	Material	: Alloy steel / carbon steel as per application
3.	Construction	: Drilled from barstock
4.	End connection	: As applicable (e.g 3 nos. ½" socket weld end etc.)

	5.	Accessories	: Vent valves

1.05.16 Instrument Valve Manifold

1.	Type	: Two valve manifold
		: Five valve manifold
2.	Mounting	: Remote 2” Pipe Mounting / Transmitter Rack mounting
3.	Construction	: Single block (bar stock)
4.	Material	: Forged body and bonnet AISI 316 stainless steel
5.	Ports	: Mfg std. (e.g 1/2 " NPT (F) etc.)
6.	Rating	: 420 Kg/Sq. cm at ambient
7.	Operating Temperature	: (-)30 to (+)170 Deg C
8.	Packing	: PTFE Wafer
9.	Seat & Stem	: AISI 316 SS
10.	Plug	: AISI 316 SS free to turn on stem / 17-4 PH
11.	Handle Bar	: AISI 316 SS
12.	Connection	: Straight
13.	Accessories	: Plugs for all ports, Mounting Bracket , bolts , nuts

1.06.00 Pneumatic Hook Up Accessories

1.07.00 Air Header

Technical Particulars	**For Panel**	**For Field**
Material of Construction	: Stainless steel	: Stainless steel
Inlet Connection	: 2" NPT (M)	: 1" NPT (M)
Header Take-off Material	: Stainless steel	: Stainless steel
Take off connection	: 1 / 2” NPT (M)	: 1/ 2” NPT (M)
Take-off Valves Material	: stainless steel	: stainless steel

Tube Take-off	: Tube adapter on valve	: Tube adapter on valve
Drain	: SS drain valve at lowest point	: SS drain valves at lowest point

LT MOTOR SPECIFICATION

1.0 This document covers the basic technical features of low tension (LT) squirrel cage induction AC motors employed for driving auxiliaries of BHEL-PEM scope packages in **5 x 800 MW YADRADRI TPS.**

2.0 CODES AND STANDARDS

All motors shall conform to the latest applicable standards as listed below;

1) Three phase induction motors: IS: 12615, IEC: 60034
2) Single phase AC motors: IS: 996, IEC: 60034
3) Crane duty motors: IS: 3177, IEC: 60034
4) Energy Efficient motors: IS 12615 or IEC: 60034-30 with Efficiency class IE3

3.0 DESIGN REQUIREMENTS

3.1 **Service Conditions**

The motors will be installed in hot, humid and tropical atmosphere highly polluted at places with coal dust and/or fly ash. For motor installed outdoor and exposed to direct sunrays, the effect of solar heat shall be considered in the determination of the design ambient temperature.
The design ambient temperature shall be 50 deg C.

3.2 Supply system and rated voltage of motors

KW rating	Supply system	Rated voltage of motor
Upto 0.2 kW	240V/415 V	240V415 V
Above 0.2 kW & up to 175kW	415 V	415 V

3.2.1 Supply voltage & variations shall be as follows:-

Voltage variation (AC Supply): (+/-) 10%
Frequency variation : (+) 3% to (-) 5%
Combined V & F variation : 10% (sum of absolute values)

During starting of large motor, the voltage may drop to 80% of the rated voltage for a period of 60 seconds. All electrical equipment while running shall successfully ride over such period without affecting system performance.

3.2.2 Motors shall be capable of running continuously at rated output for each of the conditions specified.

3.3 **Motor Rating**

All motors shall be rated for continuous duty. They shall also be suitable for long period of inactivity. LT motor rating at 50 degree C shall have at least 15% margin over the input power requirement of the driven equipment at rated duty point unless stated otherwise in driven equipment specification. The motor characteristics shall match the requirements of the driven equipment so that adequate starting, accelerating, pull up, break down and full load torques are available for the intended service.

3.4 **Starting Requirements**

3.4.1 Motor shall start smoothly and rapidly. Motor characteristics such as speed, starting torque, break away torque and starting time shall be properly co-ordinated with the requirements of driven equipment. The

accelerating torque at any speed with the minimum starting voltage shall be at least 10% higher than that of the driven equipment.

3.4.2 Motors shall be capable of starting and accelerating the load with direct on line starting without exceeding acceptable winding temperature.

The limiting value of voltage at rated frequency under which a motor will successfully start and accelerate to rated speed with load shall be taken to be a constant value of 85 (eighty five) percent rated voltage.

3.4.3 Continuous duty LT motors up to 175 KW Output rating (at 50 deg. C ambient temperature), shall be Premium efficiency (IE3) as per IEC: 60034-30/ IS: 12615 and the locked rotor current of motors shall as per IS 12615.
However, as per system requirement drives rated in the range of 160-210 KW may be considered in either 415V or 3.3 KV

3.4.4 Pump motor subject to reverse rotation shall be designed to withstand the stresses encountered when starting with shaft rotating at 125% rated speed in reverse direction.

3.4.5 The following frequency of starts shall apply

i) Three cold starts in succession with the motor being initially at a temperature not exceeding the ambient temperature.

ii) Two hot starts in succession with the motor being initially at a temperature not exceeding the rated load temperature.

iii) Three equally spread starts in an hour the motor being initially at a temperature not exceeding the rated load operating temperature (not to be repeated in the second successive hour)

3.4.6 Locked motor withstand time of hot motors at 110% rated voltage shall be as follows:

a) For motors with starting time upto 20 sec.

- at least 3 sec. more than starting time.

b) For motor with starting time above 20 secs but not exceeding 45 secs.

- at least 5.0 sec. more than starting time.

c) For motors with starting time above 45 secs.

- at least 10%. more than starting time.

The starting time of the motor referred above is at minimum permissible voltage. Wherever the above requirements are not complied with, speed switches of approved make & type shall be provided to bypass the locked rotor protection for a pre-selected time during starting of motors. The speed switches shall have one NO & one NC contacts having maximum interrupting capacity of 5 Amps at 240V AC and 0.25 amps at 220 V DC.
Hot thermal withstand curve shall have a margin of at least 10% over the full load current of the motor to permit relay setting utilising motor rated capacity.

3.5 **Running Requirements**

3.5.1 Motor shall run continuously at rated output over the entire range of voltage and frequency variations as given above.

3.5.2 The motor shall be capable of operating satisfactorily at full load for 5 minutes without injurious heating with 75% rated voltage at motor terminals.

3.5.3 The motor shall be designed to withstand momentary overload of 60% of full load torque for 15 second without any damage.

3.6 **Stress during bus Transfer**

3.6.1 The motor may be subjected to sudden application of 150% rated voltage during bus transfer, due to the phase difference between the incoming voltage and motor residual voltage.

3.6.2 The motor shall be designed to withstand any torsional and/or high current stresses, which may result, without experiencing any deterioration in the normal life and performance characteristics.

4.0 SPECIFIC REQUIREMENTS

4.1 **Enclosure**

All motor enclosures for outdoor, semi-outdoor & indoor application shall conform to the degree of protection IP-55 unless otherwise specified. Motor for outdoor or semi-outdoor service shall be of weather-proof construction with canopy. For hazardous area approved type of increased safety enclosure shall be furnished.

4.2 **Cooling**

4.2.1 The motor shall be self-ventilated type, either totally enclosed fan cooled IC 411(TEFC), totally enclosed tube ventilated IC 511(TETV) or closed air circuit air- cooled IC 611(CACA).

4.3 **Winding and Insulation**

All insulated winding shall be of copper. All motors shall have class F insulation but limited to class B temperature rise. Windings shall be impregnated to make them non-hygroscopic and oil resistant.

Tropical Protection

All motors shall have fungus protection involving special treatment of insulation and metal against fungus, insects and corrosion.

All fittings and hardware shall be corrosion resistant.

4.4 **Bearings**

4.4.1 Motor shall be provided with antifriction bearings, unless sleeve bearings are required by the motor application. Bearings shall be rated for minimum service life of 40,000Hrs.

4.4.2 Vertical shaft motors shall be provided with thrust and guide bearings. Thrust bearing of tilting pad type is preferred.

4.4.3 Bearings shall be provided with seals to prevent leakage of lubricant or entrance of foreign matters like dirt, water etc. into the bearing area.

4.4.4 Sleeve bearings shall be split type, ring oiled, with permanently aligned, close running shaft sleeves.

4.4.5 Grease lubricated bearings shall be pre-lubricated and shall have provisions for in-service positive lubrication with drains to guard against over lubrication. LT motors 15kW and above shall be provided with external greasing arrangement.

4.4.6 Oiled bearing shall have an integral self-cooled oil reservoir with oil ring inspection ports, oil sight glass with oil level marked for standstill and running conditions and oil fill and drain plugs.

4.4.7 Forced lubricated or water cooled bearing shall be used as per requirement.

4.4.8 Lubricant shall not deteriorate under all service conditions. The lubricant shall be limited to normally available types with IOC equivalent.

4.4.9 Bearings shall be insulated as required to prevent shaft current and resultant bearing damage.

4.5 **Noise & Vibration**

4.5.1 For 415V motors, maximum double amplitude vibrations upto 1500 rpm shall be 40 microns and 15 microns upto 3000 rpm.

4.5.2 The noise level shall not exceed 85db (A) at 1.5 meters from the motor.

4.6 **Motor Terminal Box**

4.6.1 Motor terminal box shall be detachable type and located in accordance with Indian Standards clearing the motor base- plate/ foundation

4.6.2 Terminal box shall be capable of being turned 360 deg in steps of 90 Deg. for LT motors unless otherwise approved.

4.6.3 The terminal box shall be split type with removable cover with access to connections and shall have the same degree of protection as motor.

4.6.4 The terminal box shall have sufficient space inside for termination/connection of XLPE insulated armoured aluminium cables.

4.6.5 Terminals shall be stud or lead wire type, substantially constructed and thoroughly insulated from the frame.

4.6.6 The terminals shall be clearly identified by phase markings, with corresponding direction of rotation marked on the non-driving end of the motor.

4.6.7 The terminal box shall be capable of withstanding maximum system fault current for a duration of 0.25 sec.

4.6.8 Motor terminal box shall be furnished with suitable cable lugs and double compression brass glands to match with cable used.

4.6.9 The gland plate for single core cable shall be non-magnetic type. A suitable cable adopter box shall be provided if the cable size does not allow the direct termination in the main TB.

4.6.10 Minimum clearances to be provided between phase to phase and phase to earth shall be as under-

Voltage Rating of Motor Minimum Ph-Ph & Ph-Earth clearance
0.415 kV : 25 mm

Note: In case it is not possible to maintain these clearances, the live parts shall be totally insulated from earth and other Phases. Adequate clearances shall be provided for cable connections.

4.7 **Grounding**

The frame of each motor shall be provided with two separate and distinct grounding pads complete with tapped hole, GI bolts and washer.
The cable terminal box shall have a separate grounding pad.

4.8 **Rating Plate**

In addition to the minimum information required by IS, the following information shall be shown on motor rating plate:

a) Temperature rise in Deg.C under rated condition and method of measurement.
b) Degree of protection.
c) Bearing identification no. and Type of lubrication, Quantity and frequency/ time interval
d) Location of insulated bearings.

5.0 ACCESSORIES

5.1 SPACE HEATERS

Motor of rating 30 kW and above shall be provided with space heaters, suitably located for easy removal or replacement. The space heater shall be rated 240 V, 1 Phase, 50Hz and sized to maintain the motor internal temperature above dew point when the motor is idle. The minimum cable size for space heater shall be 2.5 sq.mm copper cable.

5.2 DELETED

5.3 INDICATOR/ SWITCH

5.3.1 Dial type local indicator with alarm contacts shall be provided for the following:

Hot and cold air temperature of the closed air circuit for CACA motor.

5.3.2 Alarm switch contact rating shall be minimum 2.0 A at 220V D.C. and 10A at 240V A.C.

5.4 ACCESSORY TERMINAL BOX

5.4.1 All accessory equipment such as space heater, temperature detector, current transformers etc., shall be wired to and terminated in terminal boxes, separate from and independent of motor (power) terminal box.

5.4.2 Accessory terminal box shall be complete with double compression brass glands and pressure type terminals to suit owner's cable connections.

DRAIN PLUG

Motor shall have drain plugs so located that they will drain the water, resulting from the condensation or other causes from all pockets of the motor casing.

5.5 LIFTING PROVISIONS

Motor weighing 25 Kg. or more shall be provided with eyebolt or other adequate provision of lifting.

5.6 DOWEL PINS

The motor shall be designed to permit easy access for drilling holes through motor feet or mounting flange for installation of dowel pins after assembling the motor and driven equipment.

7.0 PAINTING

Colour scheme for motors shall be shade 631 of IS-5.

8.0 TESTING

8.1 Type Tests

For LT Motors, type test reports for type tests as per IS: 12615/ IEC: 60034 conducted on equipment similar to those proposed to be supplied shall be submitted. The type Test should have been conducted within last 5 years from enquiry date.

8.2 Routine Tests

All motors shall be subjected to routine tests as per IS: 12615/ IEC: 60034 in the presence of customer or customer representative.

9.0 **Variable Frequency Drive motor details:**

i) The motor shall be suitable for operation with a solid-state power supply consisting of an adjustable frequency inverter for speed control.
ii) The motor shall be suitable for the current waveforms produced by the power supply including the harmonics generated by the drive.
iii) The Motor shall be designed to operate continuously at any speed over the range 20-100 % of rated speed.
iv) The permitted voltage variation should take into account the steady state voltage drop across the AC drive and all other system components upstream of the motor.
v) Motors required to be transferred to DOL, by-pass mode shall be rated for specified variations in system line voltage and frequency. Starting current of motor in DOL, bypass mode shall be limited to value in motor specifications.
vi) The motor shall be constructed to withstand torque pulsations resulting from harmonics generated by the solid-state power supply.
vii) The motor insulation shall be designed to accept the applied voltage waveform, within the Vpeak and dv/dt limits as per IEC-61800-4.
viii) The drive manufacturer shall be solely responsible for proper selection of the motor for the given load application and the output characteristics of the drive.

LT MOTORS

A. GENERAL

1. Manufacturer & Country of origin.
(Shall be as per approved QA make)

2. Equipment driven by motor

3. Motor type

4. Quantity

B. DESIGN AND PERFORMANCE DATA

1. Frame size

2. Type of duty

3. Type of enclosure /Method of cooling/Degree of protection

4. Applicable standard to which motor generally conforms

5. Efficiency class as per IS 12615

6. (a) Whether motor is flame proof — Yes/No

   (b) If yes, the gas group to which it conforms as per IS:2148

7. Type of mounting

8. Direction of rotation as viewed from DE END__

9. Standard continuous rating at 40 deg.C. ambient temp. as per Indian Standard (KW)

10. Derated rating for specified normal condition i.e. 50 deg. C ambient temperature (KW)

11. Maximum continuous load demand of driven equipment in KW

12. Rated Voltage (volts)

13. Permissible variation of :

a. Voltage (Volts)

b. Frequency (Hz)

c. Combined voltage and frequency

14. Rated speed at rated voltage and frequency(RPM)

15. At rated Voltage and frequency:

a. Full load current

b. No load current

16. Power Factor at

a. 100% load

b. NO load

c. Starting.

17. Efficiency at rated voltage and frequrecy,

a. 100% load

b. 75% load

c. 50% load

18. Starting current (amps) at

a. 100 % voltage

b. 85% voltage

c. 80% voltage

19. Minimum permissible starting Voltage (Volts)

20. Starting time with minimum permissible voltage

a. Without driven equipment coupled

b. With driven equipment coupled

21. Safe stall time with 100% and 110% of rated voltage

    a. From hot condition

    b. From cold condition

22. Torques :

    a. Starting torque at min. permissible voltage(kg-mtr.)

    b. Pull up torque at rated voltage.

    c. Pull out torque

    d. Min accelerating torque (kg.m) available

    e. Rated torque (kg.m)

23. Stator winding resistance per phase (ohms at 20 Deg.C.)

24. GD^2 value of motors

25. No of permissible successive starts when motor is in hot condition

26. Locked Rotor KVA Input

27. Locked Rotor KVA/KW

28. Vibration limit :Velocity (mm/s)

29. Noise level limit (dBA)

C. CONSTRUCTIONAL FEATURES

1. Stator winding insulation

    a. Class & Type

    b. Winding Insulation Process

    c. Tropicalised (Yes/No)

d. Temperature rise over specified maximum ambient temperature of 50 deg C

e. Method of temperature measurement

f. Stator winding connection

2. Main Terminal Box

a. Type

b. Location (viewed from NDE side)

c. Entry of cables(bottom/side)

d. Recommended cable size (To be matched with cable size envisaged by owner)

e. Fault level (MVA), Fault level duration (sec)

f. Cable glands & lugs details (shall be suitable for power cable)

3. Type of DE/NDE Bearing

4. Motor Paint shade

5. Weight of

a. Motor stator (KG)

b. Motor Rotor (KG)

c. Total weight (KG)

D. List of accessories.

1. Space Heaters (Applicable for 30 KW & above motor) (Nos./Power in watts/supply voltage)

2. Terminal Box for Space Heater (Yes/No)

3. Speed switch (Yes/No)
No of contacts and contact ratings of speed switch

4. Insulation of bearing (Yes/No)

5. Noise reducer(Yes/No)

6. Grounding pads

   i) No and size on motor body

   ii) Nos on terminal Box

7. Vibration pads

   i) Nos and size

   ii) Location

8. Any other fitments

E. List of curves.

1. Torque speed characteristic of the motor

2. Thermal withstand characteristic

3. Starting. current Vs. Time

4. Starting. current Vs speed

5. P.F. and Effi. Vs Load

F. Additional Data to be filled for each rating of DC Motor

1. Rated armature voltage (Volt)

2. Rated field excitation (Amp)

3. Permissible % variation in voltage

4. Minimum Permissible Starting voltage (volt)

5. At rated voltage

   i) Full load Armature current.(Amp)

   ii) Full load Field current (Amp)

iii) No load Armature current (Amp)

6. Full load Field current (Amp)

7. No load Aramature current (Amp)

8. Minimum permissible field current(Amp) to avoid overspeeding at

   i) Maximum permissible voltage

   ii) Rated voltage

   iii) Minimum Permissible Voltage

9. Resistance (indicative Values) in ohm

   i) Armature winding (Arm + IP + Series) at 25 deg.C

   ii) Field Winding at 25 deg. C

10. Inductance (indicative values)

    i) Armature winding

    ii) Field winding

11. Value of trimmer resistance (ohm) to be connected in series with the shunt field to obtain rated speed at

    i) 220 V DC

    ii) 250 V DC

    iii) 187 V DC

12. Value of the external resistance (ohm) required to be connected in series with armature during starting only

13. Technical data sheet for external resistance box

14. GA drawing of motor

15. Starting time calculation

16. Starter resistance design calculation

17. Electrical connection diagram of motor

DRIVE CONTROL PHILOSOPHY (STATION C&I)

CUSTOMER:	TELANGANA STATE POWER GENERATION CORPORATION LTD TELANGANA, INDIA 5 x 800 MW YADADRI TPS, UNIT # 1 TO 5
CONSULTANT:	TATA CONSULTING ENGINEERS LIMITED BANGALORE, INDIA
	BHARAT HEAVY ELECTRICALS LTD POWER SECTOR PROJECT ENGINEERING MANAGEMENT NOIDA

REV.	DATE	ALTD	CHD	APPD
03	06.12.19	RINKY	RKR/SSB	SM
1.	REVISED IN LINE WITH DISCUSSION WITH TSGENCO DURING THE MEETING DTD. 29-31.10.2019 HELD AT BHEL PEM NOIDA.			
02	22.01.19	RINKY -sd-	RKR -sd-	SSB/SM -sd-
1.	REVISED IN LINE WITH COMMENTS RESOLUTION/MOM DURING THE MEETING HELD AT TSGENCO OFFICE FROM 8-9.01.19.			
01	10.05.18	GA -sd-	RKR -sd-	SSB/SM -sd-
1.	REVISED IN LINE WITH CUSTOMER COMMENTS RECD. VIDE TRANSMITTAL REF. NO. 11005A-IC-VDT-002 DTD 26.04.18			

JOB NO. 417

STATUS CONTRACT

DISTRIBUTION

COPY RIGHT AND CONFIDENTIAL
The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED it must not be used directly or indirectly in any way deterimental to the interest of the company.

DEPT CODE		NAME	SIGN	DATE
I	DRN	RINKY	-sd-	07.12.17
	DESN	RINKY	-sd-	07.12.17
	CHD	RKR	-sd-	07.12.17
	APPD	SSB/DP	-sd-	07.12.17

TITLE: DRIVE CONTROL PHILOSOPHY (STATION C&I)

DEPT. | SCALE | SIGN

DRAWING NO. PE-DM-417-145-I002

SHEET 1 OF 11 | REV. 03

A. DRIVE CONTROL PHILOSOPHY

The control philosophy for different type of Drives is detailed below:

1 Bi-directional drives with Integral Starter (Open/Close duty and inching/regulating duty)

a) All bi-directional drives shall have integral starter. These drives shall be operable from Remote i.e. from Central Control Room (CCR).

b) Remote manual operation of all drives shall be done from Operator Works Station (OWS/LVS).

c) Remote control commands i.e. open/close generated from DCS shall be issued to Integral Starter through interposing relays, mounted in Integral Starter. For open/close duty bi-directional drives, DCS output command shall be latched in DCS, except for inching duty bi-directional drives where latching is not required.

d) Necessary electrical protections shall be realized at Integral Starter, whereas process interlocks and protection shall be realized in DCS.

e) Following signal exchange shall take place between Integral Starter & DCS.

- Open & close command.
- Integral Starter Disturbed (Loss of power supply/Loss of control supply/ Motor thermostat trip/ Thermal O/L /Local/off/Remote S/S in Local or Off mode/Stop PB optd/Torque open/close cutoff).
- Valve status feedback by means of limit switches (open/close).
- Valve status feedback by means of torque switches (open/close).
- Valve position feedback (4-20mA) for inching duty drives.

The above signal exchanges are diagrammatically represented in sheet no. 7.

2 Unidirectional LT Drives (Contactor Operated)

a. Unidirectional LT drives shall be operable from Remote i.e. from Central Control Room (CCR). Drives shall be provided with Local Emergency Stop Push Button (EPB). Deleted.

b. Remote manual operation of all drives shall be done from OWS/LVS. Deleted. 2

c. Remote control commands i.e. start/stop, shall be generated from DCS and shall be issued to MCC through interposing relays mounted in respective MCC. DCS output command shall be latched in MCC. EPB (stay put type), in MCC supplier's scope, shall be wired directly to MCC to stop the motor irrespective of motor being in remote/local mode. The EPB shall be provided with press to lock and turn to release type, keyless mechanism. Under its locked position, the drive operation shall be inhibited. 2

d. Necessary electrical protections for the drives shall be realised at MCC, whereas process interlocks and protections shall be realized in DCS.

e. Following signal exchange shall take place between MCC & DCS

i. Drive Start & Stop commands.
ii. Drive ON & OFF feedback.
iii. MCC disturbed (Thermal O/L /Control supply fail/ EPB operated/ MCC isolated.
iv. Deleted. 2

f. Current transducers, 4-20mA types (in MCC suppliers scope), shall be mounted in the MCC for monitoring the current in DCS for all the drives ≥ 30 KW, for important drives <30 KW including all lube oil pumps. Auxiliary power supply to these transducers shall be provided from the control power supply of the respective MCC.

The above signal exchanges are diagrammatically represented in sheet no. 8.

3 Solenoid Operated Drives

a. Solenoid operated drives shall be operable from remote i.e. CCR only.

b. Remote manual operation of all drives shall be done from OWS.

c. Remote control commands i.e. open/close shall be generated from DCS and shall be issued to the respective solenoid through interposing relays located in Interposing Relay panels.

d. Necessary process interlocks shall be realized in DCS.

e. Following signal exchange shall take place between solenoid operated drive & DCS

i. Valve open & close command.

ii. Valve status feedback by means of limit switches (open/close), wherever available.

The above signal exchanges are diagrammatically represented in sh. no. 9.

4 HT/LT Unidirectional Drives (Breaker operated).

a. Remote manual operation of Breaker operated drives shall be normally from remote i.e. Station DCS in main Control Room through OWS/LVS and Local/remote selection of drives shall also be done in DDCMIS.

b. Remote/Switchgear (SWGR) selection shall be realized from SWGR mounted R/S selector switch.

c. Following are the operational combinations for breaker operated drives:

- SERVICE POSITION – Drive Operation (Start/Stop) shall be from CCR with R/S (Remote/SWGR) selector switch in Remote position.

-TEST POSITION – SWGR Testing (Start/Stop) from SWGR.

Switchgear mounted 'Trip/Neutral/Close' switch shall be provided for testing of switchgear when 'R/S' selector switch is selected as 'SWGR'.

2


d. Remote control commands i.e. start/stop, pulse type, shall be generated from DCS and shall be issued to Switchgear through interposing relays located in the respective Switchgear. Further there is Local/remote selection in DDCMIS. Local selection in DDCMIS means, command from local PB, provided near the drive, will be executed through DDCMIS whereas in case of remote mode of selection in DDCMIS, the command from OWS will be processed, not through local PB.

e. The EPB shall be wired directly to switchgear to stop the motor irrespective of motor being in remote/local mode. The EPB (stay put type), in SWGR supplier's scope, shall be provided with press to lock and turn to release type, keyless mechanism. Under its locked position, the drive operation shall be inhibited.

f. Necessary electrical protections for the drive shall be realised at Switchgear, whereas process interlocks and protections are realised in DCS.

g. Following signal exchange shall take place between switchgear and DCS: -

i. Drive Start & Stop commands.
ii. Drive ON & OFF status feedback.
iii. Switchgear Disturbed (Control power supply fail/Trip coil Unhealthy).
iv. Switchgear Available (Breaker in Service position, Breaker Spring Charged, Breaker in REMOTE & Master Trip Relay not optd.)
v. Master Trip Relay (86 Relay) operated.
vi. Emergency Stop PB operated.
vii. Breaker in TEST Position.
viii. Local Start



h. Current transducers, 4-20mA types (in SWGR suppliers scope), shall be mounted in the SWGR for monitoring the current in DCS. Auxiliary power supply to these transducers shall be provided from the control power supply of the respective switchgear.

The above signal exchanges are diagrammatically represented in sh. no. 10.

B. ANALOG DRIVE CONTROL PHILOSOPHY

Analog Drives Control

1.1 A drive control function residing in Distributed Processing Units (DPUs) is used to position the pneumatically operated control valves/Dampers through SMART positioner (for Burner Tilt also). Interlock and protection Open/Close Commands, originating from field or generated internally in Control Logics (ACS), are interfaced with the drive control function residing in processors.

1.2 Control Valve actuator design shall take care of fail safe condition i.e. bringing valve to full open/full close or stay put mode, on signal (pneumatic/electric) failure.

1.3 Auto/Manual operator control and display for various control loops shall be provided through OWS, using Analog Displays.

1.4 Analog Displays have following functionality:

- Auto/Manual selection with control device “Raise/Lower Buttons”
- Set point indication with “Raise/Lower Buttons”
- Indication for deviation between set point and measured value
- Measured value indication
- Final control element portion indicators

The above signal exchanges with DCS are diagrammatically represented in sh.no. 11.

C. CABLE

For interconnection of analog signals (4-20mA) to DDCMIS, in general "armoured" 0.5 sq mm color coded individually and over all screened twisted pair shall be used (F Type). However, for position feedback signals of bidirectional drives and current feedback signals of HT/LT drives 2P, G type cable shall be used as only one analog signal is involved.


For interconnection of binary signals (24V DC) to DDCMIS, "armoured" 0.5 sq. mm color coded over all screened twisted pair cable shall be used (G Type).

D. LIST OF CRITICAL DRIVES <30KW WITH CURRENT MEASUREMENT

i. ID Fan sealing air motor
ii. Seal Oil Pump
iii. AOP motor for hyd. coupling-MDBFP
iv. AC / DC Scanner Air Fan
v. HP B/P Lube Oil Pump Motor
vi. Regenerative Air Heater Main Motor
vii. Jacking Oil Pump Drive Motor for BFP's
viii. LOPs of ID/FD/PA Fans
ix. All Lube Oil Pumps

3

DCS INTERFACE FOR BIDIRECTIONAL DRIVE (WITH INTEGRAL STARTER)




NOTE:

* DISTURBED= Loss of Power supply (1 Phase/3 Phase)/ Loss of control supply/ Motor thermostat trip/ Thermal over load/Torque open/close cutoff Local/Off/Remote Sel. switch Stop PB optd.

	PROJECT: 5X800 YADADRI THERMAL POWER STATION UNIT # 1 TO 5	DRG.NO.	PE-DM-417-145-I002
		DATE	06.12.2019
	TITLE: DDCMIS INTERFACE FOR BIDIRECTIONAL DRIVE	REV.NO.	03
		SHT	7 OF 11

DCS INTERFACE FOR UNIDIRECTIONAL LT DRIVE



NOTE:–


1) EPB OF RESPECTIVE DRIVE WILL BE MOUNTED NEAR TO DRIVE ONLY. (1)

2) 4–20mA CURRENT TRANSDUCER SHALL BE CONSIDERED. FOR LTUDs >30 KW AND IMPORTANT DRIVES, LUBE OIL PUMPS (REFER CLAUSE D, SHEET 6 OF 11) (2)

PROJECT: 5X800 YADADRI THERMAL POWER STATION UNIT # 1 TO 5	DRG.NO.	PE–DM–417–145–I002
	DATE	06.12.2019
TITLE: DDCMIS INTERFACE FOR UNIDIRECTIONAL LT DRIVE	REV.NO.	03
	SHT	8 OF 11

ROS-6279

DCS INTERFACE FOR SOLENOID DRIVE
(24V DC / 240V AC UPS)




NOTES:

** MCB SHALL BE PROVIDED FOR EACH SOLENOID

FOR ON/OFF TYPE, SOLENOID ACTUATED CONTROL VALVE.

	PROJECT: 5X800 YADADRI THERMAL POWER STATION UNIT # 1 TO 5	DRG.NO. PE-DM-417-145-I002
		DATE 06.12.2019
	TITLE: DDCMIS INTERFACE FOR SOLENOID DRIVE (SINGLE COIL)	REV.NO. 03
		SHT 9 OF 11

DCS INTERFACE FOR SOLENOID DRIVE
(24V DC / 240V AC UPS)




NOTES:

** MCB SHALL BE PROVIDED FOR EACH SOLENOID

FOR ON/OFF TYPE, SOLENOID ACTUATED CONTROL VALVE.

PROJECT: 5X800 YADADRI THERMAL POWER STATION UNIT # 1 TO 5	DRG.NO.	PE-DM-417-145-I002
	DATE	06.12.2019
TITLE: DDCMIS INTERFACE FOR SOLENOID DRIVE (DOUBLE COIL)	REV.NO.	03
	SHT	9a OF 11

DCS INTERFACE FOR HT/LT UNIDIRECTIONAL DRIVES(BREAKER OPERATED)




NOTE:-
EPB OF RESPECTIVE DRIVE WILL BE MOUNTED NEAR TO DRIVE ONLY.
1

PROJECT: 5X800 YADADRI THERMAL POWER STATION UNIT # 1 TO 5	DRG.NO.	PE-DM-417-145-I002
	DATE	06.12.2019
TITLE: DDCMIS INTERFACE FOR UNIDIRECTIONAL HT DRIVE	REV.NO.	03
	SHT	10 OF 11

ROS-6279

DCS INTERFACE FOR ANALOG DRIVE (WITH SMART POSITIONER)



NOTES:

** APPLICABLE TO VALVES WHERE PROTECTION OPEN/CLOSE ACTION FOR CONTROL DEMAND OVERRIDING IS REQUIRED.

	PROJECT: 5X800 YADADRI THERMAL POWER STATION UNIT # 1 TO 5	DRG.NO.	PE–DM–417–145–I002
		DATE	06.12.2019
	TITLE: TYPICAL HOOK–UP DIAGRAM ANALOG DRIVE (WITH SMART POSITIONER)	REV.NO.	03
		SHT	11 OF 11

PROGRAMMABLE LOGIC CONTROLLER (PLC) SPECIFICATION

VOLUME : VI

SECTION-VI

SUB SECTION - A

DISTRIBUTED DIGITAL CONTROL AND MANAGEMENT INFORMATION SYSTEM (DDCMIS)

1.00.00 **GENERAL REQUIREMENTS**

1.01.00 DELETED

1.02.00 System shall be highly reliable with the availability of not less than 99.7% with adequate redundancy and fault tolerant configuration.

1.03.00 DELETED

1.04.00 Remote input output (RIO) stations as a data concentrator for acquisition and monitoring of Boiler metal temperature and other remote areas are foreseen. RIO shall be industrially ruggedized and if required , shall be provided with integral air conditioner considering the harsh environment.

1.05.00 DELETED

1.06.00 DELETED

Common DDCMIS network shall also control and monitor packages envisaged for PLC based local control systems. Operator workstations shall be provided in CCR for the overall control and monitoring through this netework. Such links (OPC) with Common DDCMIS are largely foreseen as Optical Fiber redundant bidirectional data hiways.

1.07.00 DELETED

1.08.00 DELETED

1.09.00 DDCMIS shall be configured to broadly perform the following basic functions:

a) Automatic sequencing of the start-up, shutdown and load swing of equipment and auxiliaries including group / plant level start-up to minimize operator's intervention under normal operating conditions ensuring safety of man and machine as well as to ensure high plant availability (OLCS & Sequence functions).

b) Automatic regulation of various valves and dampers to achieve guaranteed performance of various controlled variables and to achieve most fuel-efficient operating regime (CLCS functions).

c) Acquisition, alarms, sequence of events, display, real time & history trend, logs, report generation and archiving of plant data and maintain historical data for a defined period (DAS functions).

d) DELETED

e) DELETED

f) DELETED

h) Off-line system configuration, simulation of control loops and logics, control loop tuning and debugging.

i) Facility for simulation of control loops / logic.

j) Providing tools for automatic generation of documents like loop & logic diagrams.

1.10.00 DDCMIS shall consist of the following broad sub-systms.

a) Input / Output Subsystem

b) Controller (OLCS & CLCS) Subsystem

c) Data Acquisition Subsystem (DAS)

d) DELETED

e) DELETED

f) Human Machine & Peripheral Interface (HMI) Subsystem

g) Engineering and Diagnostic Station (ES)

h) DELETED

1.11.00 DELETED

1.12.00 DELETED

1.13.00 DELETED

1.14.00 Bidder shall furnish all required equipment and materials including system hardware and firmware components, peripherals and operator work station, all necessary licensed software platforms - compilers, interpreters, builder packages etc; programming, diagnostic and test routines, instruments and equipment; development of application software, data base, screens, graphics and other functional programs; establishing the network structure, debugging and loading; develop and follow a quality assurance plan, system integration, simulation and checkouts; offering the system for Owner's shop inspection and testing including hardware, software and heat-run tests, packaging for transportation, delivery at plant site, unloading, warehousing, installation, site integration, program loading and documentation, system check-out, interconnection with field inputs, pre-commissioning checking, commissioning including tuning of control loops and put the complete system in operation with necessary site modifications, conduct performance guarantee tests, system availability test and develop as-built documentation.

1.15.00 Bidder shall supply all related documentation including original software manuals, application software manuals, operation and maintenance manuals,

instruction handbooks for graphic and data-base building and other related documents and manuals in hard copies as well as in soft medium. Bidder shall furnish the entire plant database and configuration in as-built condition in DVDs for reloading/ record.

1.16.00 Bidder shall also supply maintenance and trouble shooting tools viz. test instruments, extender cards, DVDs containing programs including virus detection and elimination programs, DVD writers, and DVD for copying, diagnostic programs etc.

1.17.00 Bidder's scope of supply shall include the supply of commissioning and mandatory spares as per guidedelines given in the specification.

1.18.00 Bidder's scope of work shall also include the training of Owner's personnel at original equipment designer / manufacturer's office and providing the guarantee for the equipment supplied.

1.19.00 DELETED

1.20.00 DELETED

1.21.00 Dual power supply feed shall be considered for all cabinets.

1.22.00 Interposing relays for switchgear unit / MCC, other systems if any shall be provided in IPR panel. This IPR panel shall be located in Control Equipment room .

1.23.00 The system shall have the capability and facility for expansion through the addition of controller modules, I/O cards, peripherals like Large Video Screen (LVS), operator workstations (OWS), printers etc., while the existing system is fully operational. The system shall have the capability to add any new control loops, groups/subgroups in control system, while the existing system is fully operational.

1.24.00 It shall also be possible to remove/replace any of the redundant controller module without switching off the power to the corresponding rack and this will not result in system disturbance or loss of any controller functions for the other controller. The on-line removal/insertion of controller, I/O modules etc. shall in no way jeopardize safety of plant and personnel.

1.25.00 No single failure either of equipment or power source shall be capable of rendering any part/system/sub-system of DDCMIS inoperative to any degree. The items which shall be redundant with automatic change-over (including the associated software), as a minimum are CLCS / OLCS Controllers, Communication Controllers, Data Highways, Local / Remote communication highway , Power supply arrangement (feeders, modules) ,Output modules for HT drives, Servers. Sensors shall also be redundant. Detailed Redundant philosophy shall be as stipulated elsewhere in this volume of the specification.

1.26.00 All the signal exchange between various functional groups of each control systems shall be implemented through redundant system bus.

1.27.00 Spare philosophy

The following spare philosophies shall be applicable for all the control and monitoring systems eg. DDCMIS including SOE , PLC , Proprietary Control Systems .

a) 10 % spare channel shall be provided in each type of input / output .10% hot spare for each type of I/O modules (installed) shall be provided in each functional group . fully wired upto the marshalling/ termination TBs .

b) Wired-in "usable" space for 20% modules along with Field Terminal assemblies, PCB/Connectors (if any in the offered system) in each of the system cabinets for mounting electronic modules shall be provided by the Bidder for future use.

c) HMI system shall be provided with capacity to handle at least 1 no. of each type of peripherals/equipments, additionally, like OWS, LVS, printers, PCs etc., over and above already specified, without any additional hardware or software. HMI system data base (if applicable) shall have provision of at least twenty five (25) percent extra points of above mentioned signals.

d) Each controller shall have thirty (30) percent spare functional capacity to implement additional function blocks, over and above implemented logic/ loops. Further, each controller shall have spare capacity to handle minimum 30% additional inputs/ outputs of each type over and above implemented capacity. Each of the corresponding communication controllers shall also have same spare capacity as that of controller

e) Twenty (20) percent spare relays of each type and rating, mounted and wired in relay cabinets. All contacts of relays shall be terminated in terminal blocks of relay cabinets. In each of the relay cabinets, 10 % spare terminal blocks shall be provided so that additional relays can be mounted and wired.

f) Twenty (20) percent spare terminal blocks in each marshalling / termination cabinets.

1.28.00 DELETED

1.29.00 The System shall have the following capabilities, as minimum: -

a) Scan, acquire, validate, time-tag, process, store, update, archive, retrieve and display all analog and digital data and parameter.

b) Monitor real and calculated variables for multi-level alarm conditions.

c) Accept and execute operator's commands and pre-programmed routines and run-times.

d) Perform all open and closed loop control functions.

e) Display plant mimics, bar-graphs, control faceplates, point description, trend graphs (real time & history) in interactive mode with the operator.

f) Prepare and print logs and reports.

g) Performance calculation based on real-time and manually entered data.

h) Dynamically reconfigure itself on command from engineering station.

i) Run diagnostics, program hang up checks, system checks and routines.

j) System information and diagnostic alarm like failure of I/O module, Multifunction controller, communication modules, node failure, CPU loading, Network loading, workstation diagnostic etc.

k) Dynamic data exchange through OPC with other systems.

1.30.00 Interface with GPS master clock for time synchronization shall be provided.

1.31.00 Security

Multiple security levels with hard and soft key lock shall be provided with two (2) or more at operator levels and one (1) at Engineer level to make it possible to restrict access to critical parameters and minimize the possibility of operator errors.

2.00.00 CONTROL SYSTEM DESCRIPTION

2.01.00 DDCMIS shall be configured such that degradation of performance in the event of a single failure of control equipment shall be eliminated. However, such failures shall be suitably annunciated to draw the attention of the plant personnel. Multifunction controllers, Communication Processors and Power supply modules (both for control and field supplies) for all open- and closed-loop controls shall be hot redundant to minimize risk arising out of failure. All redundant modules shall be hot- withdrawable and hot-insertable.

2.02.00 Single multi-loop controller pairs shall handle OLCS, CLCS & Sequential functions of specific plant areas as per the functional grouping.

2.03.00 DELETED

2.04.00 DELETED

2.05.00 Maximum permissible loading of various components shall be as follows:

a) Multi-loop Multifunction Controller – 50%.

b) Input / Output - 80%

c) Workstation / console – 80%

d) DELETED

e) Data Highway / communication link – 50%

f) Other computing modules – 60%

2.06.00 Control functions shall be judiciously assigned to various controllers such that,

a) Controllers are uniformly loaded and partitioned as per functionality of the process and equipment.

b) Loops are assigned logically to the controllers so that peer-to-peer active data transactions are kept at minimum and a simple correlation exists between plant equipment / system and corresponding controller.

c) Complete failure of a controller partition can only affect a portion of the plant and equipment and which shall be manageable by the operator without any outage of the unit.

2.07.00 Response time of the control system should be adequate to maintain control over the process under all regimes of operation. Response time shall include the delay and dead time both internal and external. Response time pertaining shall include I/O scan time, data communication time, processing time etc. Maximum permissible time for various functions under worst loading condition are as follows:

a) Scanning rate :

i) Analog signals : 1 sec. for measurement.

ii) Digital signals : 100 ms.

DELETED

(b) Loop execution time :

i) CLCS : 250 ms. (For all Loops)

ii)OLCS :100 ms. (For all Loops)

(c) Controller output update

i) CLCS : every 250 ms. (For all CLCS Loops)

ii) OLCS : every 100 ms (For all OLCS Loops)

(d) Updating rate

i) Analog display : 2 sec. (for measurement)

(ii) Analog display : 1 sec. for OLCS/CLCS

(iii) Digital value display :4 sec. (for measurement)

(iv) Digital value display :1 sec. for OLCS/CLCS

(e) Time for display in CRT screen : 1-2 sec. on demand

(f) Keyboard command execution time : 1 sec

Faster response is required for some critical equipment and systems such as Turbine generator control, HP/LP Bypass control, MFT etc. and for those systems, requirements for scan time shall be guided by the respective equipment and systems dynamics.

2.08.00 Manipulation of set point shall be permissible from the Operator's terminal in incremental mode.

2.09.00 It shall be permissible to transfer a loop from "auto" mode to "manual' mode or vice versa from operator's terminal. All such transfers shall be bumpless and procedureless. During transition from "auto" mode to "manual", the output to the final element shall be maintained until manipulated from the operator's terminal. Similarly, during transfer from "manual" mode to "auto"; when effected from the operator's terminal, the auto output shall take-off from the last value and shall regulate the final element in a predetermined and adjustable ramp to final computed value as per the control loop algorithm. This will necessitate continuous auto-tracking between "auto" mode and "manual" mode outputs.

2.10.00 Binary control shall be implemented in hierarchical structure..

2.11.00 DELETED

2.12.00 The drives, which are part of a sequence, shall be operable in sequence mode from Operator's terminal. In sequence mode, a single command shall initiate predetermined sequence of operation. Following information, as a minimum, shall be available at the monitors.

a) All permissive

b) Start & Stop sequence

c) Start sequence complete

d) Stop sequence complete

e) Sequence fail

f) Stepwise sequential progress of operation indication with permissive for each step to enable the operator that for particular step all permissive are met and the step is executed.

g) Disturbance indication

h) Sequential operation indication on monitor in the form of ladder logic diagram

i) Override of hold-up sequence as per operator's discretion.

2.13.00 DELETED

3.00.00 **INPUT / OUTPUT SUB SYSTEMS**

3.01.00 The system shall have features not limited to the following:

a) Interface with field sensors, Signal conditioning, A/D conversion, Signal validation, Diagnostic, Engineering conversion, Time stamping, Limit value monitor etc.

b) Interface with smart transmitter though smart interface module with optical and galvanic isolation. Alternatively, standalone field bus management system shall be used.

c) Channels individually addressable during routine diagnostic check.

d) Failure reporting.

e) Replaceable under system power on condition.

f) I/O bus and I/O communication processor shall be redundant.

3.02.00 Number of channels in IO module shall not be more than the following:

i) Analog input - 8 channel

ii) Analog output - 8 channel

iii) Binary input - 16 channel (one changeover contact is equivalent to 2 inputs)

iv) Binary output - 16 channel

3.03.00 Signals for panel mounted instruments , annunciators etc, where provided, shall be fed from I/O level.

3.04.00 Separate redundant power supplies for powering field sensors shall be provided. This interrogation power supplies shall not be derived from the rack power supply used for control modules.

3.05.00 Analog Input modules shall have , but not limited to , the following features,

a) Inputs type : 4-20 mA DC, RTD (Pt 100) , Thermocouple or voltage inputs.

b) Signal isolation : Galvanic/ Opto-coupler (Galvanic separation shall conform to EN 50020)

c) Fuse protection and fuse failure detection.

d) Transmitter power supply : 24 V DC.

e) Input filtering for noise level.

f) Cold junction compensation for thermocouples.

g) Transmitter monitoring for parity, wire break and limit values.

h) Monitoring of A/D conversion.

i) Conversion to engineering units.

j) Test for normal or extended range.

k) Detection of open circuit for thermocouples.

l) Alarm limit testing for high, high-high , low, and low-low substituted values.

3.06.00 Analog output modules shall have , but not limited to , the following features,

a) Outputs : 4-20 mA DC or voltage form.

b) Direct or reverse operation

c) Loop check back of output

d) Default options upon failure

. 3.07.00 Binary / Digital input modules shall have , but not limited to , the following features,

a) Signal isolation (optical).

b) Fuse protection.

c) Contact bounce protection.

d) Field cable monitoring.

e) Short circuit protection.

f) Configurable as status input, latched input.

g) Alarming of abnormal state.

h) Non-coincidence monitoring for binary inputs for all changeover signals.

i) Interrogation voltage for digital inputs shall be 24 / 48 V DC.

.

3.08.00 Binary / Digital output modules shall have , but not limited to , the following features,

a) Individually fused.

b) Individual contact suppression.

c) Configurable as momentary, latched or pulse-width modulated outputs.

d) Individually definable default state.

e) Output read back verification.

f) Short circuit protection.

3.09.00 Each of the dual / triple redundant binary & analog inputs shall be wired to separate input modules.

3.10.00 Triple/dual analog sensors are required both in CLCS and OLCS for control purpose, then all of these triple/dual sensors shall be wired to the controller where CLCS loop is configured. If based on the same set of sensors, any protection action is required in OLCS (e.g., protection stop of drive) in another controller(s), then CLCS Controller shall provide three digital outputs for each such controller from three separate output modules (at defined LVM-Limit Value Monitor blocks inside Controller). The three such digital outputs of CLCS controller shall be acquired in each of the OLCS controllers in three separate digital input modules. Similar philosophy will be used when triple/dual analog sensors are required in OLCS in multiple controllers for protection function.

3.11.00 If triple/dual/single binary sensors are required in OLCS in multiple controllers for protection function in these controllers, each of these sensors shall be shared among these controllers

3.12.00 The input sharing scheme shall be subject to Owner's approval during detailed engineering.

4.00.00 **CONTROLLER SUB SYSTEMS**

4.01.00 This shall have the features not limited to the following:

a) Real time multi tasking.

b) Redundant communication ports with speed of 1000 Mbps or more.

c) Deterministic and peer-to-peer Communication with other controllers.

d) Redundant controllers placed separately and no sharing of motherboard.

e) Redundant Controllers, redundant power supply, redundant communication modules.

f) Hot-withdrawable and hot-insertable.

g) RIO and RTU support

h) Processing time of parameter freely configurable.

4.02.00 For CLCS function, controllers shall have system resident library functions including linearizers, characterizers, square root extractors, signal limiter, one-out-of-two selector, Median selection, averaging, PID block, logical functions, Auto / manual selector and other software configured mathematical blocks to be strung together to form the desired strategy for control. Synthesizing, configuring, tuning or adjusting control loops should not involve writing elaborate programs.

4.03.00 CLCS shall act on modulating control valves, dampers, or other regulating devices to achieve stable control action under steady state condition, for load swings in the step / range over the entire load range with permissible variation in parameters and under failure/trip or limiting condition of process equipment.

4.04.00 Open Loop Control System (OLCS) shall perform interlocking, protection, sequential functions including individual drive control function with their associated safety protection. OLCS shall provide adequate and reliable protection & safeguard for various equipment and shall assist the operator in easy, safe & efficient starting, stopping and tripping of various drives in the plant.

4.05.00 OLCS shall perform drive control functions like permissive, start, stop, auto-start, auto-stop, wait- and step-timing control, drive interface and other related binary functions. It shall also check the drive status feed back like On, Off, Fault, Local & Remote selection, Normal & Trial selection, Switchgear disturbance, Electrical protection operated, Safety interlock operated, standby mode etc. and display on the screen.

4.06.00 For OLCS function, controllers shall have system resident library functions including logic functions, timers, registers, counters, Boolean operators,

encoders, one-out-of-two selector, two-out-of-three voting system, logical functions, HT/LT drive control and other software configured mathematical blocks to be strung together to form the desired strategy. Synthesizing, configuring or adjusting control loops should not involve writing elaborate programs.

4.07.00 Each Multi-loop controller, interfacing with the redundant control bus, shall cater to a group of related loops and shall have its own in-built communication function.

4.08.00 The system shall have 1:1 redundancy with respect to the processor modules, power supply modules, communication modules and network interface. In redundant controller configuration, “main” and the “hot stand-by” controllers shall be identical in all respects. Any one of the two controllers can be selected as ‘main’ controller. During normal operation, output of the stand by controller shall be disabled. However, standby controller shall receive and update its database from field inputs and main controller.

The system shall be designed in such a manner that in the event of failure of the primary controller, the entire configuration of the failed controller shall be instantaneously and automatically transferred to the back-up controller without operator’s intervention. Mode changeover in either direction shall be bumpless . Simultaneously, a message should appear on the monitors of the Operator's / Engineer's work station indicating the failure. Redundancy of processor / controller shall mean the fulfilment of the following requirements:

a) Automatic synchronisation of primary processor/controller of DDCMIS with secondary processor/controller

b) Bumpless switchover to secondary processor/controller of DDCMIS when the primary fails.

c) Automatic program and data equalisation in the event of any on-line program / edit executed in the primary processor/controller of DDCMIS.

d) Automatic “Forcing Bit” update in the secondary processor/controller of DDCMIS when any “ Forcing is applied in the primary processor / controller of DDCMIS.

4.09.00 When a controller is put back after removal for maintenance or if a new controller is put in service, there shall be provision for high speed down loading of data from the hot controller without affecting the main highway traffic.

4.10.00 In case of internal diagnostic failure of a multi-loop controller pair, all concerned loops shall trip to manual and drive will go to its fail safe position dictated by the process.

4.11.00 The functional capabilities of the controllers shall not be limited to the following :-

a) Accepting commands from and providing feedback to Operator's Terminal.

b) Interact with other subsystems via Control System Bus.

c) Carry out computation.

d) Carry out control actions.

e) Perform binary and sequential operations.

f) Self-monitoring and auto-diagnostic leading to changeover to stand-by and reporting of failure.

g) Program modification and configuration in Boolean form via Engineering Terminal, on line.

h) On line system tuning and setting.

i) Testing and simulation.

j) Capable of accepting IRIG-B or any other standard format time reference signal from external Master clock system and shall be able to synchronise with the time reference of the Master clock system. Also possible to use the same time reference signal for all the equipment throughout the DDCMIS.

4.12.00 Transfer of control mode from automatic to manual and vice-versa shall be procedureless and bumpless by incorporating output tracking facilities.

4.13.00 The controller's gain shall automatically and accurately adapt to the number of drive units in a given subsystem that are on auto mode to maintain constant loop gain.

4.14.00 Excursion of a control signal beyond acceptable values shall cause the corresponding control loop to trip automatically to manual mode with the control output latching-in at the last value, until manipulated in manual mode.

4.15.00 Controllers shall not act without validation check of the field inputs.

4.16.00 The controller capability shall, as a minimum, include (i) P, PI, PD and PID control functions and their variations (ii) cascade control (iii) feed forward control (iv) On-Off control, (v) Ratio and bias control, (vi) Logical operation. Other advanced control strategy like adaptive & predictive control etc. can be considered for important loops like Furnace Draft, combustion control, FW flow control etc. in addition to SH/RH temperature control .Bidder shall furnish write up on the same. Controller assignment / partitioning shall be judiciously decided considering minimum manageable outage of the equipment /system in case of failure of a functional group. .

4.17.00 DELETED

5.00.00 **DATA ACQUISITION SUB-SYSTEM**

The system is meant for acquiring the plant data for monitoring purpose shall be implemented in multi-loop processor and shall acquire, process and store the following types of plant data for display, performance calculation and monitoring purpose. Data acquisition subsystem shall also include various gateways capable of acquiring, processing and storing data from third party system data highways.

5.01.00 The Real time Data Highway shall be a high speed communication network with communication speed of 1000 Mbps or more. This data highway shall link all the stations /control nodes in the system in the ring topology so that highest network availability is achieved. Data highway and links shall be hot redundant and fault tolerant.

5.02.00

5.03.00 The networks shall be secured from the interconnected private and public networks by incorporating suitable proven hardware and software firewalling and antivirus protection.

5.04.00 Each network element shall have two independent couplers linking the dual data highways. All messages received through dual highways shall be validated individually for error and between themselves for fidelity of both the highways. Faulty data highway shall be automatically isolated, without any loss of data but with appropriate alarm. Erroneous messages shall be flagged and rejected.

5.05.00 Communication protocol shall conform to OPC compliant ISO 7-layer protocol in master less, token ring or token bus (as per IEEE-802.4) or any standard proven & accepted protocol in deterministic mode. In case of Ethernet network, it shall be fast and full duplex type. Extensive error checking or error correcting codes shall be used in these levels to improve the reliability of communication.

6.00.00 DELETED

6.01.00 DELETED

6.02.00 DELETED

6.03.00 DELETED

6.04.00 DELETED

6.05.00 DELETED

6.06.00 DELETED

6.07.00 DELETED

6.08.00 DELETED

6.09.00 DELETED

6.10.00 Logs : (provisional and minimum)

i)	Hourly Log	-	60 plant data and 10 computed data
ii)	Shift Review Log	-	40 plant data and 15 computed data
iii)	Daily Log	-	20 plant data and 15 computed data
iv)	Monthly Log	-	20 plant data and 15 computed data
v)	Yearly Log	-	20 plant data and 15 computed data
vi)	Alarm Log	-	1000 plant data and 15 computed data
vii)			
viii)			
ix)			

x)

xi)

xii)

xiii)

xiv)

xv)	Pre-Trip & Post Trip Log	-	1 second interval for 10 seconds
xvi)	Maintenance logs	-	For the equipment with motor rating 30 KW and above.

6.11.00 DELETED

6.12.00 Alarm Display

alarm points with paging feature shall be provided. Keyboard shall have the function keys such as alarm acknowledge, reset, paging, summary display etc. Format of the alarm page display shall be finalized during detailed engineering.

7.00.00 DELETED

8.00.00 DELETED

8.01.00

DELETED

8.01.01 DELETED

8.02.00 DELETED

DELETED

DELETED

DELETED

DELETED

DELETED

9.00.00

9.00.00 DELETED

9.01.00 DELETED

9.02.00 DELETED

9.03.00 DELETED

9.04.00 DELETED

9.05.00 DELETED

9.06.00 DELETED

9.07.00 DELETED

9.08.00

9.09.00

9.10.00

9.11.00

Minimum technical requirements for the Laptops shall be as follows

i)	Processor	:	i7 or latest.
ii)	Hard Disk	:	2 TB
iii)	RAM	:	16 GB DDR 3
iv)	Screen	:	15 inch with touch.
v)	Wifi	:	802.11 ac OR higher.

vi)	Wifi model	:	Intel Centrino Wireless - AC 3160.
vii)	Blue tooth	:	4
viii)	USB ports	:	3
ix)	Hard Drive Speed	:	5400 pm
x)	Graphics Card	:	Intel HD Graphics 4400
xi)	Opearting System	:	Windows 10 and Office 10 or latest versions.
xii)	Softwares	:	Acrobat Reader Professional 10 , AUTOCAD 10 or latest versions.
xiii)	Antivirus	:	Licensed for 4 years.

9.12.00 Hardware and Software technical requirements including for workstations , servers , printers etc. shall be as described elsewhere in this section. All software user licenses shall be valid for entire life of power plant. User should not have to pay any recurring license fee during the usage period of the system. It shall be possible to upgrade the installed system with the latest available version of the software model during the plant life.

9.13.00 The requirements stated above are preliminary. The exact details shall be finalized during detailed engineering. Bidder shall highlight any limitation of the offered MIS for such requirements in the bid

10.00.00 HUMAN MACHINE INTERFACE (HMI) AND PERIPHERALS

10.01.00 Operator's window to the process shall be various workstations with color 24" TFT monitors, Keyboard, mouse, dot matrix & colour laserjet printers, Sixty seven (67) inch LVS , multimedia beeper/buzzer etc., multimedia beeper/buzzer etc.

10.02.00 Operator's terminals shall permit the operation and monitoring of the unit under normal condition and in all emergencies.

10.03.00 Each terminal shall be independent with its hardware including adequate local memory for resident database. The resident data shall be continuously updated at all terminals. Operator station shall have auto reboot feature.

10.04.00 HMIs shall be built for high performance with non-proprietary open system configuration.

10.05.00 Operation shall be menu driven in latest windows environment. Display screens shall be user friendly and no special software knowledge shall be required to operate the system

10.06.00 Each HMI shall be adequate with all operators' function such as quick access to plant & process. Complete operation of the unit shall be possible from any operator station. Multiple active windows, not less than 4 (four) nos., simultaneously, shall be displayed on the HMI screen.

10.07.00 Display navigation shall be with least number of keystrokes or steps.

10.08.00 Functional requirements shall be , but not limited to the followings:

a) Issuance of control command like start / stop, set point adjustment, auto / manual, increase / decrease etc.

b) Plant graphic, overview display, area display, loop / drive display, control related displays, other standard displays for monitoring, trending of parameters.

c) Display & print of SOE / Trend / Graphic / System Diagnostic.

d) Alarm display & acknowledgement.

e) Print of screen, logs, operator message, etc.

f) Last command call.

g) Copy & paste.

h) Display of sequential / logic and tag with facility of forcing through suitable password

i) Multiple pop up faceplate for drive control & point detail.

10.09.00 All OWS / LVS shall be fully interchangeable i.e. all operator functions including control, monitoring and operation of any plant area or drive shall be possible from any of the OWS / LVS at any point of time without the necessity of any action like downloading of additional files.

10.10.00 No single failure in HMI shall lead to non-availability of more than one OWS or one LVS. In such an event i.e., single failure leading to non-availability of any OWS/LVS, it shall be possible to operate the entire plant in all regimes of operation including emergency conditions from each of the other available OWS/LVS.

10.11.00 LVS based overview displays shall be provided, which shall be overlaid across all the LVS for viewing as video wall.

10.12.00 DELETED

11.00.00 **ENGINEERING AND DIAGNOSTIC STATION**

11.01.00 It shall perform programming /configuration of complete system and HMI and perform system diagnostic. System shall be adequately protected with software & hardware locks etc., against any inadvertent and un-authorized access.

11.02.00 It shall be capable of storing data, loading, editing, testing, tuning, and monitoring all the controllers. System shall be complete with monitor, keyboard, mouse and colour LaserJet printer.

11.03.00 Programming technique shall not require any special knowledge on programming and shall be easy to learn. It shall archive all the addresses, setting parameters, screen statistics etc. for future downloading in case any controller/operator's terminal is replaced by a new one or any data is lost or during rebooting of the system. The unit shall remain on-line and serve as the administrator for the entire network, if required.

11.04.00 Bidder shall also provide minimum of ~~five~~ one laptop computers with latest hardware configuration and loaded with suitable operating , application program including licensed softwares as a backup engineering cum programming and configuration station. This loaded laptops shall be handed over by Bidder well in advance of FAT to TSGENCO head- quarters ,vidyut soudha , Hyderabad.

The minimum technical requirements for Laptops shall be as indicated elsewhere in this subsection of the specification.

11.05.00 Each station shall execute the functions not limited to the followings:

a) System configuration

b) Data Base configuration

c) Graphics display generation and modification

d) OLCS/CLCS Control algorithm generation and modification

e) Report/Log configuration and modification

f) System access configuration

g) Downloading of program

h) High level programming language.

11.06.00 Each station shall be equipped with a DVD writer for archiving of the configuration.

11.07.00 The station shall be capable of generating all real time graphics, trends, plots etc, necessary for optimum tuning of the controllers. This feature shall also be duplicated in the operator's station.

11.08.00 Open loop configuration shall be programmed in the Engineering Terminal in simple Boolean form.

11.09.00 Engineering/ stations of the unit shall also serve as Diagnostic Stations to perform system maintenance functions This shall serve as an aid to the maintenance engineer and supplement various functions available in the engineering terminal for system diagnostics and fault location upto module level identifying location on the panel and sub rack where the fault has occurred. The standard diagnostic displays provided in the engineering cum diagnostic terminal and operator's terminal shall be identical. The fault may be grouped section-wise or station-wise on the initial screen and subsequent paging should specifically lead to the rack number, card number, type of card etc, so that any fault on the system shall become transparent to the operator and maintenance personnel without approaching individual cubicles for fault finding. These displays shall also be available in OWS / LVS. Individual

transmitter signals, their status and selected value for control/ measurement shall also be available on Engineering station / LVS/OWS in the CLCS displays and the popups .The system shall also provide guidance for fault clearance and shall reduce downtime of the system

11.10.00 The system maintenance function shall not be limited to the followings:

a) Station status overview.

b) System alarm message display.

c) Individual station status display.

d) Data base equalization.

e) Date and time setting.

f) Network status display

12.00.00 **PLANT OPERATIONAL DISPLAYS**

12.01.00 The data presented in plant operational and monitoring displays shall be easily understandable, comprehensive and presented in soothing colors so that prolonged exposure to the screens do not lead to eye fatigue. Screens shall be glare free.

12.02.00 DELETED

12.03.00 DELETED

12.04.00 . Control Overview Screen

a) Overview display screen - Display of status & values of all analog control loops in one screen in color graphic form. The display shall present all the controlled parameters in color bar graph representing the value on a 100% span scale and/or the control deviation in a center-zero scale. The color of the scale shall indicate the alarm / healthy / control status of the variables. The point address code shall associate with each bar to enable the operator to select parameter display by direct addressing.

b) Group display screen - group of related control loops, and or measurement parameters and / or related drives displayed in one screen. The display can be in controller face plate form showing the controlled variable, A/M status of the controller; engineering value of measurement parameter on a 100 % span bar graph form; status of binary drives etc. Typically, a group screen shall be composed of 8 parameters or loops.

c) Individual display screen - displaying one control loop, tag number of associated elements, schematic representation of the loop, trend of the controlled variable/s, alarm history, sectional plant sub-system display related to the loop, various settings including tuning parameters, alarm / trip settings etc., representing a complete data bank for the loop. Similarly, for binary drives, the representation shall include a sectional mimic for the drive area, control ladder, status of the drive, tag number, different delay and other settings etc.; all in one screen.

d) Plant sub - system display - mimic diagrams meant for direct operation by vectoring cursor on the screen .The display shall have a fixed part representing the P & I diagram and a dynamic part refreshing parameter values and status of drives. There will be an overall plant sub-system display from which operator shall zoom into the specific area of interest. Additionally, operator shall be able to directly address specific displays by their area identification code. The displays shall be animated to represent changes. Extensive color coding shall be utilized to represent status of drives, alarm conditions, open / close status etc., together with the color coding for various lines carrying different fluids.

e) Flow chart / logic / ladder screens - meant for sequence logic operations to represent the progress of the sequence, time-out conditions, forced or bypass conditions, hang-ups and prompts.

f) Operator's guidance message screen - displaying process flags and prompts to the operator to assist in selecting course of action in the events of start-up and emergencies.

g) Trend Display - System shall be capable to display at least eight (8) numbers of real time trends with eight (8) different colors per page with selectable time frame to implement variation in resolution. The facility to magnify trend on Y-axis by 1, 2, 5 & 10 and scrolling within the range ±100% shall be provided. Also the facility to magnify X-axis by 1, 2, 4 or 8 and scrolling shall be provided.

h) Screen Partitioning - The system shall be capable to implement screen partitioning to facilitate easy comparison of trending between two or more assigned screens and also display of X-T and X-Y trends on the same page and other combinations as per the requirement of operating personnel.

i) Multi-windows - The system shall have facility of multi- windows & pop ups to allow related information to be displayed in different windows. The types of windows shall be tentatively as follows :-

a) Alarm window for display of all acknowledged & unacknowledged alarms in different colours. Alarm priority shall also be distinguished by colour.

b) System help window for display of messages corresponding to illegal key operations.

c) Help windows for user defined help messages.

d) Trend window display with trend recording graphs.

e) Faceplate window to display Instrument faceplate of called tag number.

f) Process window for display of process data.

h) MIMIC, System Diagnostic, Engineering menus etc.

13.00.00 DELETED

13.01.00

13.02.00

13.03.00

13.04.00

13.05.00

14.00.00 **INTERFACE WITH PLC / MICROPROCESSOR BASED PROPRIETARY CONTROL SYSTEM**

14.01.00 Redundant and Bidirectional Communication link (OPC) in between DDCMIS and various control systems including PLC shall be optical fiber based. Fibre optic redundant cables shall run in two physically separate conduits

14.02.00 20 % tag handling capacity over the configured tags shall be kept as spare for future expansion.

15.00.00 HARDWARE & SOFTWARE SPECIFICATION

Major hardware and the software general features are indicated below. Modules shall be environmentally ruggedized and tropicalized.

15.01.00 Hardware Specification

The following requirements are only indicative and minimum technical requirements for Operator's and Engineering stations , Servers, printers etc,. However, Bidder shall supply the equipment with latest configuration available at the time of detailed engineering and shall furnish the technical particulars during detailed engineering for Owner's approval.

15.02.00 System Cabinet

General specification for panel and cabinets described elsewhere in this specification shall apply.

a) The modules shall be arranged logically and sequentially in the sub-racks inside the cabinet. Modules associated with a closed loop / open loop controller viz. input cards, output cards etc. shall be housed together with the corresponding controller in the same cabinet.

b) If, after housing a controller with associated cards in a sub rack 25 % or less card slots are left vacant, the same shall not be used to accommodate any card related to any other system. Adjacent slots to dissipative cards shall be left vacant for proper cooling air circulation within the panels. For future modification 10% spare module slots shall be provided to accommodate 10% spare modules specified elsewhere in this specification.

c) If cards related to a particular controller spill over beyond one sub rack at least 4 cards slots shall be kept vacant before cards related to other systems can be placed in the sub rack. Vacant slots shall be covered with blank plates.

d) Cards, in a sub rack, shall be uniformly grouped, type-wise and functionality wise.

15.03.00 Termination & Relay Cabinet

a) In no case the number of terminal blocks accommodated in each section shall exceed 1000. Terminal blocks shall preferably be arranged in four vertical rows in two sidewalls with two sets of cable troughs (one for incoming and one for outgoing) arranged on two sides of the terminal block. At least 20% terminal blocks shall be left as spare. This shall be in addition to the terminal blocks for 20% wired channel.

b) Terminal assignment in the termination cabinet will be such that cables originating from a field junction box shall be terminated in one termination cabinet only. This will facilitate use of multi-core cable for field wiring. For each incoming cable an additional terminal block shall be provided adjacent to signal wire termination point for termination and continuation of cable screen.

c) Relay used for interfacing with other system shall be modular, plug in type and provided with snap on transparent cover. Rating shall be of 24V DC and shall have at least 2 changeover contacts. All contacts of the relay shall be terminated in terminal blocks. Each relay shall be provided with “Coil on” indication LED and coil protection diode. At least 10% of installed capacity shall be kept as spares.

d) Spare requirement

Bidder shall provide at least 20% or minimum two numbers, whichever are higher, spare channels as hot on rail spares in each configured I / O modules. In addition to this 10% or minimum one number, whichever is higher, extra assigned complete spare I / O modules mounted on rails in sub racks as hot on rail spare for each category of installed I / O modules shall also be provided. Spare modules shall be distributed over each controller group. Spare channel and modules shall be fully wired up to termination cabinets.

15.04.00 Controller

15.04.01 Controller shall be Microprocessor based, multi-loop and multi-function type. Controller shall be based on 32-bit processor. These can be configured from hand-held station through front plug and from Engineering Terminal .Diagnostic features shall include invalid command checking, automatic periodic illegal address detection, routine check and memory parity check, , time - out checking, watch dog report to engineering terminal ,processor status display LED, processor fault.

15.05.00 Operator’s & Engineering Station

1.	Processor	: Latest , minimum Intel Core i5
2.	Configuration	: Tower
3.	Internal clock	: 3.2 GHz (minm.)
4.	Architecture	: 32 bit
5.	Video Card	: PCI
6.	RAM	: 4 GB (Minimum) DDR
7.	Hard drive	: 500 GB SATA
8.	Cache	: 512 KB Level 2

9.	CD/DVD Drive	: CD - Both Read & Write for OWS. Both CD & DVD Read & Write for ES
10.	Audio controller	: 16-bit
11.	Operating system	: Latest , Window
12.	Graphic accelerator	: 8MB (minm.)
13.	Communication ports	: 2nos. (minm.) Ethernet ports(1000 MB) , 4 nos. USB ports (minm.)

15.06.00 Server (OPC SERVER)

15.06.01 Two nos. Intel , Xeon 1.9 GHz(minm.) processor with 2 x 4GB (minm.) DDR RAM ,3 nos. 600 GB SAS Hard disk , DVD +/- RW Drive . RAID 5 configuration , Ethernet ports(1000 MB) , Windows (latest) .

15.07.00 Monitor

1.	Type	: TFT monitor
2	Screen diagonal	: 24 inch flat
3	Display	: XGA or better
4	Resolution	: 1024 X 768 or better
5	Degree of protection	: IP-30
6	External Controls	: Brightness, contrast, Horizontal / Vertical amplification & shift
7	Power supply	: 240 V, 50 Hz, 1 phase
8	Ambient temperature	: 0-50 ^{O} C
9	Humidity	: 95% non-condensing
10	Version	: To suit industrial application

b) Key Board

1.	Type	: Flat spill proof membrane type or Positive depression type
2.	Different keys	a) Soft and user defined function keys for software/ programming including text

correction, scan rate alteration, zooming/ flashing color selection etc.

b) Panel select keys for alarm summary, control loop display, overview, trend, graphic, operator guide message etc.

c) Standard Alphanumeric keys

d) Alarm acknowledge keys

e) Cursor keys

f) Mode/loop status switching keys

g) Setting change keys

h) Print-out command keys

i) Other keys as required to operate the system

3.	Key lock	: Lockable type push button mounted on keyboard
4.	Life Expectancy	50 million cycles per key
5.	Version	: To suit industrial application

c) Laser Printer

1.	Type	: Laser jet , tabletop, network ready
2.	Printer Memory	: 256 MB (min.)
3.	Speed	: Monochrome 24 ppm - A4, Color 6 ppm - A3/A4
4.	Resolution	: 1200 x 1200 DPI in color
5.	No. of color (Basic)	: 4 (four) minimum
6.	Power supply	: 240 V, 50 Hz, 1 phase
7.	Ambient temperature	: 0-50 Deg C
8.	Humidity	: 95% non-condensing

9.	Size of paper	: Letter, A4, Legal, Ledger, A3
10.	Print media	: Plain paper, transparencies, thick stock, glossy stock, envelopes
11.	Accessories	: Adapters, Connector Cable, Multiplexer switch (4 point)

15.08.00 Large Video Screen

15.08.01 Bidder shall supply Sixty seven (67) inch or similar Large Video Screen (LVS) display unit in 1 (one) row upright in front of the operator in CCR and local control rooms with seamless integration with DDCMIS for control and monitoring of the plant .Salient plant parameters, plant status, alarms, graphics etc. shall be available in the screen .The System shall be configurable such a way that output of any of the operator station can be directed to any LVS through the controller . The system shall be configured such that any of the operators sitting on the same Ethernet shall be able to work on the LVS sitting at his own position with his local keyboard & mouse in addition to the dedicated Key board of the LVS. This LVS shall be used as an OWS with its own dedicated electronics like Processor, Keyboard and mouse etc. The LVS controller/s shall interface with DDCMIS for monitoring and display of real time information. The quantities shall be as per attached Control System Archtectures and Plant Control System Overview Diagram.

a) The system shall display complete and partial overview of the plant, alarms in the form of normal window appearance, important parameters of the plant and the electrical system in the form of SLD etc.

b) Large Video Screen system shall be based on Digital Light Processing Technology. The software shall have capability to display multiple windows on the screen. The system shall have facility to zoom on any part of the display.

Lamp shall be LED type with lamp life more than 60,000 hours.

c) The LVS . shall have the following minimum features.

1.	Cube & Controller	: Cube & Controller should be from the same manufacturer.
2.	Manufacturing	: OEM should have a manufacturing setup in India for Video Walls running successfully for the last 3 years or more.
3.	Reputed	: The OEM should be an established multinational in the field of video walls and

	Company		should have installations around the world.
4.	Chip Type	:	Chip 0.95" Digital Micro Mirror Device
5.	Resolution	:	1400 x 1050 native DMD chip resolution
6.	Light Source Type	:	LED light source with separate LED array for each colour (RGB)
7.	Brightness ANSI	:	Minimum 700 Lumens
8.	Brightness Uniformity	:	≥ 90 %
9.	Dynamic Contrast	:	1400000:1 or more
10.	Redundant Dual Supply	:	Cube should be equipped with built in a Dual Redundant Power Supply
11.	Hot Swappable Power Supply	:	Cube should have a Hot swappable Power Supply In built
12.	Control	:	IP based control to be provided
13.	Remote	:	IR remote control should also be provided for quick access
14.	Screen to Screen Gap	:	≤ 0.2mm
15.	Screen Support	:	Screen should have a Anti Reflective Glass Backing to prevent bulging
16.	Control BD Input Terminal	:	Input: 2 x Digital DVI Input: 1 x HDMI Input: 1 x 3G-SDI

			Input : 1 x Display Port Output: 1 x Digital DVI , 1 x 3G-SDI
17.	Cooling Inside Cube	:	By Means of a heat pipe
18.	Maintenance Access	:	Rear
19.	CONTROLLER	:	
	Display controller	:	Controller to control Video Walls in a matrix of 5(C) x 1(R) with outputs , video inputs and Universal inputs along with necessary software's
	Processor	:	Single Quad Core Intel® Xeon/i7 64-bit 2.0 GHz CPU or better Min 4GB
	HDD	:	Min 500 GB Hard Disk Hard disk Capacity should be upgradable
	RAID	:	:* RAID Support
	Networking	:	* Dual-port Gigabit Ethernet Controller inbuilt Support for Add on Network adapters Support for Optical Fiber interface Adapters
	Accessories	:	DVD-R,DVD+RW,, Keyboard, mouse
	OS	:	* Supports 64-bit Operating Systems Windows 7
	Power Supply	:	(1 + 1) Redundant AC-DC high-efficiency

d) All connecting cable and accessories shall be supplied.

e) The display program shall be such that the entire viewing areas of the screens are utilized and sides are not left blank. It shall be possible to

call up a screensaver display to show Owner's company logo when the screens are not in active operation.

f) The controller shall also be loaded with DDCMIS software so that in case of failure of all HMI workstations the LVS can be used as an operator workstation.

15.09.00 Managed Switch

Data highway shall be of high speed Ethernet and full duplex configuration. Network shall be built on the Managed Ethernet switches for better control of data traffic & performance and future expansion. Switch configuration shall be redundant with seamless changeover without any upset in the process or equipment. Failure reporting shall be available at HMI. MTBF of the switch shall be more than 20 Years. Configuration shall be automatic.

All Ethernet switches to be used in the plant shall be of same type and shall conform the specification requirements.

Other requirements shall be as follows ,

a) All managed switches shall work in IEC-61850-3 protocol environment and shall support IEC-62439 standard ring redundancy topology (MRP) and also fast MRP. It shall also support IEC-62439-3 standard PRP& HSR technology with 0 ms recovery time and also support IEC-61850 switch (RSP & MSP switches)

a) Switch shall have the capacity for maximum of 4 Giga bit fiber port and 24 fast ethernet port.

c) Switch shall act as IGMP-querier and minimum 2 alarm contacts shall be available

d) It shall have High MTBF value

e) It shall support ACA adaptor for reconfiguration of the switch in case of failure to reduce MTTR value to less than one minute and shall have minimum of 4 fibre and 4 copper din rail switch RSPL.

15.10.00 Relays

Relays shall be rated for control supply of 24V / 48 V DC. Each relay shall have two changeover type contacts & the rating of contacts shall be 5 A 240V AC & 0.2A at 220V DC. All the contacts of relays shall be wired upto the cabinet terminal blocks.

15.11.00 Furniture

Bidder shall include a complete set of furniture for the Control Room and computer Room of ergonomic design from reputed manufacturer especially designed for computer peripherals. The set of furniture shall include but not be limited to control desk, chair, printer table, computer tables etc, all necessary furniture for Computer Room peripherals, cabinets for storage of manuals / booklets/recorder charts, storage racks for special tools/ diskettes and Shift Charge Engineer's desk/chair/side rack etc.

15.11.01 DELETED

15.11.02 Following furniture , but not limited to , shall be provided for each Local control room:

a) 4 Nos. cushioned revolving, independently adjustable seat and back chairs.

b) Glass top Teak wood / MDF table for mounting Operator Station monitors.

c) Printer tables.

d) Glass top Teak wood / MDT table for System Engineering Room / Engineering stations with drawer at end.

e) Glass top teak wood / MDF table with vertical file mounting arrangement (two layer to house approx. 40 Nos of files and lockable drawers at both end) for System Engineering Room / Engineers.

15.12.00 Software Specification

15.12.01 General

The system shall utilize a readily upgradeable, public domain software platform proven for real-time operation environment at the control and monitoring level overlaid with a relational database program. The desirable features are enumerated below.

a) The operating system shall be suitable for real-time operation both at process as well as HMI end.

b) The software system shall be fully modular.

c) The software shall meet the following general requirements.

i) Simple, easy-to-learn language for editing and on-line operation.

ii) Wide range of peripheral support.

iii) Effective task scheduling and support of multiple priority structure including event based interrupt etc.

iv) Effective debugging.

v) Provision for on-line editing and program development without interrupting on-line functions.

vi) Self-diagnostic routines.

vii) Efficient memory management and effective utilization of system time.

viii) Quick start-up and loading.

ix) Support of multiprogramming and multi-user operation.

15.12.02 Memory Management / Operating System

a) The main memory capacity shall be adequate to minimize swapping.

b) Individual task shall reside in partitions, which can be split into sub-partition for parallel task handling.

c) The operating system shall automatically perform housekeeping functions including file management.

d) Task swapping shall be dynamic.

e) Programs called frequently or requiring rapid access shall remain as resident in main memory.

f) Individual program partitions shall be suitably linked.

15.12.03 Device Support

The operating system shall support the following devices.

a) CD R/RW /DVD R/RW /Pen drives.

b) Monitors.

c) Printer, key board, mouse/trackball.

d) Random Access Memories.

e) Communication interface (10/100 Base-T Ethernet, TCP/IP etc.)

f) Controller and other 32 bit systems

15.12.04 I / O Management

The I / O Management system shall have the following features.

a) Device independent address processing.

b) Peripheral diagnostic.

c) Retransmission on request.

d) Exclusive, shared and priority mode of device assignment.

e) Flagging of device failure, etc.

15.12.05 Program Development and System Generation

The operator shall have the flexibility to customize or develop program to suit the system requirement.

a) The system generation shall be on-line without interruption to the program under processing.

b) It shall be possible to introduce new programs dynamically.

c) The program development system may include its own assembler, editor, loader etc.

d) The program development process shall be conversational and shall reject faulty or erroneous entry with proper flagging.

e) New programs shall be automatically integrated into the system by interfacing with existing programs.

15.12.06 Power Failure Restart

a) I / O transfer stoppage shall not be abrupt.

b) Provision shall be there for manual restart and auto-restart on resumption of power supply.

c) In case of power failure interrupt the boxing-up sub-routine shall be automatically initiated.

d) In case of power failure, all data including register content, volatile memory content etc. shall be transferred to the bulk memory.

e) The program status shall be latched.

f) On resumption of supply. Registers shall be loaded and programs shall start from the status where they were latched earlier.

15.12.07 Check Routines & System Failure

On-line diagnostic routine shall be run continuously or periodically, as applicable. Detected failures shall be displayed in monitor & printer. The following checks shall be performed.

a) Peripheral failure.

b) Memory Failure/ Error.

c) Parity Error, Interrupt Error.

d) Program Hang-up.

e) Power Supply Failure.

f) Module Failure.

g) Interface Failure.

h) SC/OC failure

i) Controller Failure

j) Highway failure and communication failure etc.

k) Failure shall lead to graceful degradation of the system.

15.12.07 Database and Database Management

Data shall be keyboard addressable. It shall be safe-guarded against unwanted and unauthorized manipulation of data.

The database management system shall have the following salient features.

a) Open to integrate third party software program, Modular expandability, dynamic partitioning.

b) Sequential and random access to data and files.

c) It shall be possible to update, display, dump (selectively), create, search data by simple keyboard entries.

d) The editing language shall be simple and easy-to-learn type, requiring no detailed programming.

e) Easy to install through windows procedure.

15.12.08 Utility Programs

The utility program shall constitute a modular system. The priority status of lengthy routines shall be as low as to be interrupted from operator's terminal. Individual functions in the routine shall be amendable. Provision shall be there to initiate utility program from user programs. Broadly, the system shall perform the following functions by utility requests.

a) Selective dumping.

b) Dump memory (file to file or file to peripheral)

c) Execute a program selectively.

d) Tracing and break-pointing errors.

e) List debug commands and error messages.

f) Change debug input devices.

g) Operation on octal or hexadecimal numbers.

h) Memory search by interactive editor.

i) Reschedule job priorities, etc.

15.12.09 Programming Language

The programming languages shall support Relational Data Base Management in a global and truly distributed Client-Server environment and shall have the following minimum features.

a) Modern high-level block structures type.

b) Powerful, compact syntax.

c) Logical organization that facilitates documentation, modification and maintenance of programs.

d) Early detection of errors at compile and run time.

e) Fast debugging.

f) Improved program reliability.

g) Clearly defined data structure complemented by flexible user-declared data types.

h) Fast execution.

15.12.10 Editing Functions

a) The following editing functions shall be performed on the variable via on-line database editor. The editing of an access to the database shall be by simple English like easy-to-learn language.

b) For analog inputs the variables shall have different scan rate, linearization options, software filtering option etc. and can be assigned externally via the keyboard.

i) Assigning scan frequencies.

ii) Continuous scan and store in working/main memory and display or print-out on demand. Changing the scanning rate for trend display.

iii) Continuous scan, store and printout of values at a specified interval as routine.

iv) Execute immediate scan for a specified interval with or without display and/or print-out.

v) Assign abbreviated engineering unit in display and print-out along with absolute value.

vi) Assign Hi and Lo alarm limits.

vii) Assign Hi and Lo transducer range limits.

viii) Points to be deleted from and restored to scan status.

ix) Check whether the variable is within a specified limit and at a slow scan rate and immediate restoration of storage status at a higher scan rate in case of anomaly.

x) Specify individual coded sub-routines, which shall be executed when any alarm or return-to-normal message occurs.

xi) Define time averaging of analog inputs.

xii) Assign significant change/increment alarm limits.

xiii) Assign alarm dead bands.

xiv) Assign rate of change alarm limits and dead-bands.

xv) Provision to specify software filtering constant individually.

xvi) Linearization routines by polynomial approximation with specified or adaptive coefficients up to 5th order.

xvii) Assign an alphanumeric point value to each analog input and each calculated point.

xviii) Rounding-off facility when fed to MONITOR, graphic or digital display units.

xix) Serial tabulations on demand in time sequence with HH :MM :SS tag.

xx) Storage of maximum and minimum value amongst specified values or within a specified interval of time.

VOLUME : VI

SECTION-VI

SUB SECTION - B

PROGRAMMABLE LOGIC CONTROLER (PLC) / PROPRIETARY CONTROL SYSTEM

1.00.00 **GENERAL**

1.01.00 Each of the relevant BOP areas and different auxiliary systems shall be provided with dedicated PLC or proprietary control systems for overall operation and control.

1.01.01 The Common DDCMIS network shall also control and monitor the packages envisaged for PLC based local control systems. Operator workstations shall be provided in CCR for the overall control and monitoring of each system through network.

There shall be redundant bidirectional OPC link between this Common DDCMIS network and each Packge PLC for monitoring / performance activities.

These areas have been indicated with other details in Section-V of this volume of the specification.

1.02.00 These control systems shall conform to high standard of engineering meeting all applicable codes and standard, design and workmanship and shall meet the functional requirements in all respects and shall be capable of performing satisfactorily in continuous commercial operation under the specified environmental condition.

1.03.00 Further this part of the specification details the common technical and functional requirements applicable for all the systems unless specified elsewhere in the specification. Only specific requirements are indicated in this section .However ,Bidder shall also adhere to the Section-VI , Subsection A (DDCMIS) of this volume of the specification for other basic and detailed scope & services , philosophy & technical requirements of different hardwares and softwares including response time , loading , interface , redundancy criteria , display , logs ,spares criteria , drawings and document submission etc.

1.04.00 All local PLCs shall be supplied from one manufacturer for all plants and shall provide single unified hardware and software platform for realizing all the control and monitoring functions.

1.05.00 In general local PLC, ,Proprietary control system by third party system integrators shall not be allowed and only main PLC/ Proprietary control system manufacturer shall be allowed to do the design engineering , system integration etc. Owner will be the final authority in allowing third party system integrators , if required , for only small applications

1.06.00 Common DDCMIS shall basically control and monitor the BOP package systems , ~~as detailed in section V of the volume of specification~~ , through the workstations from the Central Control Room (CCR) during normal operation of the plant.. However, local control and monitoring facility of the equipments from the respective package control room and local panels shall also be available. However, if required, based on operator choice, normal and emergency operation from the local PLC system shall also be done. The control room operator shall have also access to common database for all the packages.

as applicable as indicated in configuration drawing

1.06.01 The redundant upper level network of each Package PLC system will be connected to redundant server to be located in Plant Engineer's room. Suitable Fibre optic cable shall be used for redundant interconnections.

1.06.02 The hot redundant Server shall continuously update all the inputs. The switchover to the hot standby Server shall be smooth and bump less with proper indication to the operator.

1.06.03 In addition to local PLC Workstations , programming activities for control systems of all the packages including set point change , logic build up & modifications , graphics build up & modifications etc . shall also be achieved through Common DDCMIS network workstation.

1.06.04 Common DDCMIS Network workstations stations, local workstations shall have access to the processor of the individual package control system for programming. Programming shall not require special computer skills. On the programming console, it shall be possible to do the programming, self-diagnostics, testing of sequence, simulation and any sequence modification.

1.06.05 All the screens as available in the local package monitors will be also available one to one basis in the Common DDCMIS network screens. Alarm monitoring / reporting, generation of logs, trends, calculations, printing of logs & reports etc. shall be available in local workstations as well as in remote Common DDCMIS network workstations .In case of failure of Common DDCMIS network, control and monitoring of the individual packages shall still be possible from the Operator Work Stations in the respective package control room

1.06.06 There shall be flexibility in operation from CCR Common DDCMIS network operator workstations. Any of the BOP packages can be controlled and monitored from any of the workstations. .

1.06.07 The system shall permit carrying out of the on-line dynamic test and self-diagnostic checks while maintaining safe condition and without endangering the safety of equipment without having any influence on the process being controlled.

2.00.00 GENERAL TECHNICAL REQUIREMENTS

2.01.00 Bidders scope of supply shall include , but not limited to , Hot standby local PLC / Proprietary control & monitoring system for each of BOP areas and shall consist of IO cards, remote and Local IO rack, control rack, redundant Power supply modules, redundant communication /networking and interconnection Cables, redundant processor and communication cards, redundant Servers, operator work stations / GUI , LVS , printer, redundant networking hardware, redundant interface hardwares / softwares with DDCMIS , MCS , PADO etc. , system cabinets ,startup, commissioning, mandatory and recommended spares, drawing, documents and training to owner's personnels at site and at vendors works etc.

2.02.00 All types of programming packages shall be licensed with facility of editing and configuration. For each of the PLC / proprietary control system, the programming software shall be supplied in a laptop for each package

preloaded with package in addition to other types of devices such as CD, DAT etc.

2.03.00 In addition to the Operator and/ cum Engineering workstations , Bidder shall also supply LCD screen based display unit, control switches and other operational keys (GUI). Bidder shall also provide minimum of one no. laptop computer for each PLC based package and with latest hardware configuration and loaded with suitable operating , application program including licensed softwares as a backup engineering cum programming and configuration station. This loaded laptop shall be handed over by Bidder well in advance of FAT to Owner's head office at Hyderabad .

2.04.00 The System shall allow dependable and effective control of the process equipment and shall be designed for maximum integrity and reliability. Integrity shall be maintained by providing a dual hot redundant system .The System shall have a capability to monitor and take actions for distributed functions from a central location.

2.05.00 The control & Instrumentation shall be through dedicated microprocessor based PLC ,Common DDCMIS network ,proprietary system for the each of the respective plants covering the total functional requirement of sequence control, regulatory control, interlock & protection, monitoring, alarm, data logging.

2.06.00 The loop cycle time shall be less than 1 sec for close loops and open loops. The switchover from main controller to redundant controller shall be bumpless; and shall be within one cycle time i.e. within 50 msec.

2.07.00 Each controller shall have 40% functional capacity to implement additional functional blocks over and above implemented logic / loops under worst loading conditions.

2.08.00 Field Input/Outputs

The System shall meet the following I/O card requirements.
The maximum number of inputs / outputs to be connected to each type of module shall be as follows:

a)	Analog input module	8
b).	Analog output module	8
c)	Binary input module	16
d)	Binary output module	16

2.09.00 Communications System

2.09.01 The Bidder shall include a dual hot redundant communication system

2.09.02 The data highway speed shall be 1000 Mbps.

2.10.00 Operator Interface

Operator Work Station (OWS) / GUI / LVS shall perform control monitoring and operation of all auxiliaries/ drives . However , Push button stations are

also to be provided with RIOs as detailed out in ~~Section V of this volume~~ of the specification .

2.11.00 Interface with Common DDCMIS system

Each PLC , proprietary control systems shall be interfaced to Common DDCMIS network with bidirectional OPC link .The link shall be redundant.

2.12.00 PLC shall be of latest version and all the modules like Control modules, communication modules, IO modules, network interface modules etc., modules shall be from the same family of hardwares and softwares and shall be sourced from Bidder's Original Principlal's works.

2.13.00 PLC shall have also , but not limited to, the following requirements ,

2.13.01 I/O LAN Speed shall be minimum 5 Mbps - 100 MBPS on Deterministic LAN.

2.13.02 I/Os shall be Rack based and not Din Rail Mountable .

2.13.03 Processors and I/Os shall be of same family.

2.13.04 Channel Level Diagnostics for DI/DO, AI & AO shall be provided . Each individual Channel healthiness shall be monitored at workstation / GUI level.

2.13.05 All PLC I/O Rack Power Supplies shall be redundant. Only Bulk power supply redundancy will not be acceptable.

2.13.06 Processor shall have minimum 256 PID loops execution capability. Minimum memory shall be 10 MB. It should be 32 Bit.

2.13.07 SOE module (if applicable) must stamp and store 250+ events at card level.

2.13.08 PLC shall store tag details and bit word addresses on upload of logic as well as tag descriptions.

2.13.09 I/O Bit forcing in Primary to reflect in secondary immediately. (single scan update)

2.13.09 Remote I/O Rack outside control room shall be on Fiber Optic communication only.

2.13.10 Processor shall be self learning in case of failure. No need to configure and program replaced processor.

2.14.00 Operating work stations must be Runtime license/servers. Client server architecture no acceptable.

2.15.00 Each operator work station must have minimum 8000 tags handling capability.

2.16.00 Auto Tuning feature of PIDs at PLC controller level shall be available.

2.17.00 Floating IP selection of Controller under PLC processor switchover condition

2.18.00 Automatic Program update on secondary on loading to Primary Processor.

2.19.00 Programming facility shall be available from Remote IO stations.

2.20.00 Processor shall support minimum 22000 IO handling capacity in Redundant configuration.

2.21.00 Online editing of Program shall be possible.

2.22.00 Processors shall be Hot back up.

2.23.00 Automatic synchronization of primary processor/controller of PLC with secondary processor/controller.

2.24.00 Bumpless switchover to secondary processor/controller of PLC when the primary fails.

2.25.00 Power supply module redundancy shall be true power supply redundancy

2.26.00 Automatic program and data equalization of primary processor/controller of PLC.

2.27.00 Automatic 'Forcing Bit' update in the secondary processor/controller of PLC when any Forcing is applied in the primary processor/controller of PLC. (Forcing Bit Table of both the PLCs must be automatically synchronised.)

2.28.00 Communication speed of 5 Mbps between PLC and I/O module network

2.22.00 Softwares


The latest version of all necessary applications and networking software shall be supplied for the system. The software tool shall have facility to interface with third party software packages. Window base operating system shall be provided. The system shall be OPC compliant. Easy upgradation and future expansion facility shall be available.

All softwares used shall be licensed versions only. All software user licenses shall be valid for entire life of power plant. User shall not have to pay any recurring license fee during the usage period of the system.

It shall be possible to upgrade the installed system with the latest available version of the software model during the plant life.

2.23.00 Redundant Uninterrupted Power Supplies (UPS) shall be provided for each Local PLC.. UPS specification shall be as per requirements indicated in Section V of this specification.

DRAWING NO.



NOTES:

1) INDUSTRIAL GRADE OWS/OEWS & 24" TFT MONITORS SHALL BE PROVIDED.
2) ALL PLCS SHALL HAVE DUAL HOT REDUNDANT PROCESSOR AND EACH RACK SHALL HAVE DUAL POWER SUPPLY MODULES, DUAL NETWORK COMMUNICATION CARDS/MODULE FOR DUAL REDUNDANT RING OR DUAL REDUNDANT STAR NETWORK.
3) REDUNDANT UPS POWER SUPPLY SHALL BE USED FOR PLC PANEL(S),RIO,BACKUP PANELS, OWS/EWS,4 WIRE INSTRUMENTS AND NETWORK COMPONENTS.FOR APPLICABLE UPS SCHEME REFER DWG:PE-DG-417-145-I004
4) PLC PANEL SHALL HAVE PROVISION TO ACCEPT TIME SYNC. SIGNAL (NTP/IRIG-B) FROM MASTER CLOCK SYSTEM.
5) PLC PANEL SHALL HAVE PROVISION FOR DATA EXCHANGE (OPC) WITH PLANT DCS. NECESSARY OPC CLIENT/SERVER SOFTWARE TO BE PROVIDED IN OPC SERVER.
6) NECESSARY PATCH CORD/CONVERTERS, LIU AT BOTH PLC AND DCS END SHALL BE IN BIDDER SCOPE FOR OPC LINK TO DDCMIS.
7) PLC SPECIFICATION SHALL BE AS PER KTPS TENDER SPECIFICATION VOLUME-VI, SECTION VI, SUBSECTION B ONLY
8) PLC PROCESSOR AND IO CARDS/MODULES SHALL BE FROM SAME FAMILY AND SHALL BE OF LATEST MODEL.
9) UPS SPECIFICATION SHALL BE AS PER KTPS TENDER SPECIFICATION VOLUME-V B,SECTION XIV.UPS SIGNALS TO PLC SHALL BE THROUGH HARD WIRED AND SOFT SIGNALS(MODBUS).
10) FIELD INSTRUMENT REDUNDANCY SHALL BE AS PER SPECIFICATION ONLY. PROTECTION & CLCS: TRIPLE REDUNDANCY; INTERLOCK/ PERMISSIVE: DUAL REDUNDANCY; MONITORING/ ALARM: SINGLE
11) ALL RTDS/ THERMO COUPLES IF APPLICABLE SHALL BE DUPLEX TYPE AND ALL TERMINALS SHALL BE WIRED TO RESPECTIVE DCS/ PLC

LEGEND:

PLC – PROGRAMMABLE LOGIC CONTROLLER
DCS – DISTURBUTED CONTROL SYSTEM
UPS – UNINTERRUPTED POWER SUPPLY
OWS/EWS – OPERATOR WORK STATION/ENGINEERING WORK STATION
HMI – HUMAN MACHINE INTERFACE
NTP – NETWORK TIME PROTOCOL
OPC – OLE PROCESS CONTROL
MCCB – MOULDED CASE CIRCUIT BREAKER
MCB – MINIATURE CASE CIRCUIT BREAKER
LCR – LOCAL CONTROL ROOM
CCR – COMMON CONTROL ROOM

REV	DATE	ALTERED: AJV
02	18.02.20	CHECKED: VNS
ZONE	REVISIONS MARKED	
REV	DATE	ALTERED: AJV
01	07.11.19	CHECKED: VNS
ZONE	REVISIONS MARKED	

CAUTION: The information on this document is the property of SIMA LAB AND BHARAT HEAVY ELECTRICALS LTD. It must not be used directly or indirectly in any way detrimental to the interest of the company.

PROJECT: YADADRI TPS - 5 x 800 MW
OWNER: TELANGANA STATE POWER GEN. CORPN. LTD.
OWNER'S CONSULTANT: TATA Consulting Engineers Limited
CONTRACTOR: BHARAT HEAVY ELECTRICALS LTD.
UNIT: BOILER AUXILIARIES PLANT.
RANIPET – 632 406.

SUB CONTRACTOR		NAME	SIGN	DATE	NO.OF VAR.
	DRN		AJ	24.08.19	
	CHD		MKV	24.08.19	---
	APPD		VNS	24.08.19	

DEPT	GRADE OF UNTOL.DIM	SCALE	WEIGHT (KG).	CWL DRG. NO:	ITEM NO.	NO. OF ITEMS
NPG		NTS				
CODE 9776	PR:QA:500					

TITLE: PLC CONFIGURATION ETP
CARD CODE: U 01
DRAWING NO.: 4-WT-060-01143 (A)
VER A
REV 02

UNINTERRUPTIBLE POWER SUPPLY (UPS) SPECIFICATION

SECTION-XIV

TECHNICAL SPECIFICATION
FOR
UNINTERRUPTIBLE POWER SUPPLY

1.00.00 **SCOPE OF WORK**

1.01.00 **Scope of Supply**

The scope of supply shall include Uninterruptible Power Supply (UPS) Systems with parallel redundant arrangement as specified ~~below~~ for ~~Main Plant, 400kV Switchyard control room, CHP control room with PLC system & associated RIOs and other~~ PLC based control systems ~~of off site packages~~ specified elsewhere in the specification.

DELETED

i) Each set of UPS system will consist of :

a. 2x100% capacity static inverter & input isolation transformer

b. 100 % capacity static switches (2 nos.)

c. One manual bypass switch

d. 2x100% capacity float-cum-boost chargers

e. 2x100% capacity UPS system battery (Lead Acid Plante Type) with back up time of 1 hour.

f. One step down transformer; (415 V three phase to 240 V single phase) for bypass

g. One static voltage regulator

h. Two AC distribution boards (ACDB-1A and ACDB-1B)

i. Interconnecting cable between UPS Equipment, battery and ACDB.

j. Two (2) nos. input output isolation transformer

Any other equipment necessary for complete of the system

ii) One (1) set of special tools and tackle.

iii) Mandatory Spare parts.

iv) All relevant drawings, data and instruction manuals.

2.00.00 CODES AND STANDARDS

a) All equipment and materials shall be designed, manufactured and tested in accordance with the latest applicable Indian Standards (IS) except where modified and/or supplemented by this specification.

b) Equipment and materials conforming to any other standard which ensures equal or better quality may be accepted. In such case, copies of the English version of the standard adopted shall be submitted along with the bid.

c) The electrical installation shall meet the requirements of Indian Electricity Rules as amended up to date and relevant IS Codes of Practice. In addition, other rules or regulations applicable to the work shall be followed.

3.00.00 DESIGN CRITERIA

3.01.00 Design Basis

a) UPS System provides a regulated and uninterrupted single phase A.C. power, within specified tolerances, to critical station loads during normal and emergency operation. Capacity of inverter output shall be computed by the contractor considering the above requirement. 25% spare margin shall be kept on the total of above requirement.

b) The UPS system excluding its battery shall be installed indoors in A.C. environment.

c) UPS shall be worked at its full capacity even battery is not connected with the system.

d) UPS system shall be compatible for satisfactory and well-coordinated operation with other related equipment as well as with input and output systems.

e) Energizing or de-energizing any portion of the system serviced by the UPS shall not cause output changes which will affect the operation or integrity of the remaining portions of the system in any way.

f) The equipment shall be self-protecting against all A.C. and D.C. transients, voltage surges and steady state abnormal voltages and currents.

g) The circuit protection shall be coordinated with UPS short circuit capacity and protective device characteristics so that a fault on any circuit shall result in minimum loss of function.

h) All non-interrupting components of UPS system shall be capable of withstanding the prevailing short circuit current without damage.

i) All circuit interrupting components shall be capable of withstanding and interrupting the prevailing short circuit currents without damage.

j) The procedure for battery sizing calculation shall be generally as per relevant IEEE, considering design margin as 15% and aging factor as 1.25

k) For continuous operation at specified ratings, temperature rise of the various components of UPS system shall be limited to the permissible values stipulated in the relevant standards and/or this specification.

l) The chargers, inverters, static switches, regulating transformers and voltage stabilizers should be arranged in such a way that any equipment can be fully isolated for maintenance without affecting in any way the operation of other panels/components.

m) The chargers, inverters, static switches, regulating transformers and voltage stabilizers should be arranged in such a way that any equipment will be fully isolated for maintenance without affecting in any way the operation of other panels/ components.

n) In the A.C. Distribution Board, the Bidder shall provide 10% or minimum one (1) no. spare feeder of each size and type of the outgoing feeders.

o) All the cooling fans inside the panels shall be of industrial grade only.

3.02.00 **System Concept**

System Concept

a) A.C. power source are available to the UPS system. The system is so designed that its load shall be served without interruption as long as one of the above power sources is available within specified limit of voltage and/or frequency.

The UPS will consist of two physically separate sets of equipment streams each consisting of the following:

i) One set of converter to convert incoming 240V, 1 Ph, 50 Hz A.C. power to suitable D.C.

ii) One set of suitable Battery Bank to get charged by the above referred converter and to feed the inverter described below.

iii) The Float-cum-Boost charger will be normally ON, supplying the DC load current and at the same time trickle charging the battery. The characteristics shall be such that if load is high and exceeds the charger capacity, the excess load shall be supplied by the battery.

iv) The Float-cum-Boost charger shall be provided with Solid State electronic regulators to prevent rising of charging current to avoid thermal runaway of the batteries.

v) The float-cum-boost charger shall also have provision for float, equalizing and boost charging the battery through manual selection.

vi) Output of the chargers shall be controlled automatically as well as manually. AUTO/MANUAL selector switch along with voltage/current setter shall be provided for this purpose.

vii) For ungrounded DC system, suitable ground fault detection system shall be provided in the battery charger panel to detect ground fault on either polarity for annunciation in charger panel.

viii) The batteries shall be so sized as to meet emergency load duty cycle requirements for one (1) hour as referred in Annexure-A. All momentary loads shall be treated as one-minute loads.

ix) One set of inverter to take D.C. input from above referred converter - Battery assembly output and to produce high quality 240V, 1Ph 50 Hz A.C. output power.

x) One set of standby bypass stream consisting of suitable transformer, voltage stabilizer etc. to produce regulated 240V, 1 Ph. 50 Hz A.C. power from new input 240V, 1 Ph. 50 Hz A.C. power.

xi) One set of static switch, synchronizing circuit to parallel the above-mentioned Inverter output and bypass stabilized raw power stream.

xii) One UPS A.C. power distribution board with suitable no. of output feeders.

Two sets of equipment streams as mentioned above will constitute the UPS system.

One set of synchronizing equipment and high performance static switch will parallel the above two streams and common output will be taken to loads which can accept only single non-redundant power input source.

For equipment requiring dual redundant input power source, separate cables will be taken from the individual UPS Power Distribution Boards of the above-mentioned two UPS streams.

The system will ensure highest system availability around 99%.

b) Each of the two UPS streams will be of 100% capacity and will normally work, each sharing 50% load. On failure of any stream, its load gets automatically transferred to the other inverter through static transfer switch.

c) If one UPS stream is out of service for any reason then the second UPS stream will be working with 100% UPS load.

d) Inside each stream on failure of its converter/battery/inverter assembly the standby A.C. source will back up to supply the 100% UPS load automatically through static transfer switch.

3.03.00 **Layout Criteria**

The UPS system will be located indoor.

The Contractor shall indicate the space requirement for the equipment offered by them separately for UPS cabinet, UPS battery and UPS distribution board.

Battery room ventilation shall be under the scope of the Contractor.

4.00.00 **SPECIFIC REQUIREMENTS**

4.01.00 **Static Inverter**

a) The static inverters shall be static type consisting of IGBT PWM type inverter, static filters, integrated control modules including necessary oscillators, voltage regulators, current limiting and surge suppression.

b) The inverter equipment shall include all necessary circuitry and devices to conform requirements like voltage regulation, soft start, transient recovery, protection, automatic synchronisation, wave shaping, etc. as specified herein.

c) Upon transfer of full load, the inverter output voltage shall not drop below 80% of nominal voltage during the first half cycle after transfer and 90% of nominal voltage in the next half cycle. The recovery to within ± 2% of voltage shall be in less than 50 milli-seconds.

d) On occurrence of a fault in branch circuit, the inverter shall be capable of clearing the highest rated branch circuit fuse in 4 milli-seconds or less.

e) The inverter shall be protected against overload, short circuit, 100% loss of load, as well as excursions, loss or restoration of D.C. input voltage and synchronising voltage. The overload capacity shall be 125% for 10 mins., 150% for 60 secs. and 300% for 4 msecs.

f) The D.C. input current shall never exceed twice the full load current except for a short circuit within the inverter.

g) For any value of the load and load power factor drawn by the equipment served, the inverter shall not impose on D.C. source any voltage oscillations in excess of 5 volts (RMS total all frequencies) or any current oscillations in excess of 3 percent (RMS total all frequencies) of the D.C. current at full load.

h) The inverter will be self protecting against A.C. and D.C. Transients, voltage surges and steady state abnormal voltage and currents likely to be encountered in the plant.

4.02.00 **Automatic Synchronisation**

a) Inverter equipment shall include stable solid state oscillator devices designed to automatically maintain the inverter output in phase and in synchronism with the stand-by A.C. source.

b) Facility shall be provided for automatic transfer to internal oscillator operation when the stand-by source frequency is beyond specified limits and the frequency shall be automatically controlled within 50 Hz plus or minus 0.5 Hz when the inverter operates in this mode.

c) Retransfer to stand-by A.C. source for synchronisation shall be automatic after the stand-by source frequency is restored to permissible limits and remains within this limit for an adjustable time delay period (up to 5 seconds).

d) Provision shall be made for stepless adjustment of synch- disconnect frequency range from 50 Hz $\pm$ 0.5 Hz to 50 Hz $\pm$ 2 Hz.

e) Automatic adjustment of phase relationship between inverter output and stand-by A.C. source shall be gradual at a controlled slow rate, which shall not exceed one hertz per second.

4.03.00 **Static Transfer Switch**

a) The static transfer switch shall be solid-state type using SCR for automatic/manual transfer of load from "inverter" to "stand-by" source and vice-versa.

b) Stand-by source can be either of the inverter or A.C. source depending on whether both the inverters are supplying 50% load each or one of the inverter is carrying 100% load.

c) The transfer time including sensing shall not be more than one-fourth cycle. Further the transition shall be make-before-break in both directions.

d) The capacity of static transfer switch shall be equal to the continuous full-load capacity of the inverter. The switch shall be provided with protective devices in both normal and alternate power source.

e) Static transfer switch shall be furnished with contact to alarm failure of the alternate source or opening of any fuse protecting the static switch.

f) Static transfer switch shall include all necessary circuitry and devices to meet the functional requirements of transfer initiation, transfer inhibit and re-transfer back to normal as detailed below

g) Transfer Initiation

i) The transfer of static switch from normal 'Inverter' position to 'stand-by' position shall be initiated by one of the following causes.

- Inverter failure and UPS system trouble
- Inverter output voltage failure.
- Manual push button operation

ii) The UPS bus shall be monitored by two voltage detectors. One fast acting circuit shall be used for detecting a complete and instantaneous voltage loss while the other slower acting averaging circuit with adjustable trip level shall be employed to detect voltage deviation beyond selected limits. Both voltage detector circuits shall automatically initiate operation of transfer switch.

iii) The static switch shall automatic transfer the load from inverter to stand-by source when the maximum I^2t capability of the inverter is reached and when the inverter output drops below 90%.

h) Transfer Inhibit

Automatic or manual transfer from inverter to stand-by A.C. source vice versa shall be inhibited when the inverter frequency is not synchronised to the alternate source.

i) Retransfer to Normal

1) The return to inverter mode shall be manual in all cases.

2) Manual transfer shall be initiated by push button actuation.

4.04.00 **Manual By-pass Switch**

a) Manual by-pass switch is used to isolate any static transfer switch for maintenance or repair without interruption to the UPS load.

b) The switch has also the facility of by-passing both the static transfer switches during start-up at the option of the operator.

c) Switch contact shall be make-before-break type.

d) The switch shall have current rating equal to the full load inverter current and necessary short time load carrying and interrupting capacity to meet the requirement of UPS system.

4.05.00 **Battery**

a) General

i. Each set of battery shall consist of number of cells assembled together on mounting racks.

ii. The battery shall be flooded cell Lead acid PLANTE type and shall be suitable for operating satisfactorily in humid and corrosive atmosphere. The batteries will be suitable for float /boost charging and will be suitable for continuous operation.

iii. The equipment shall comply with the requirement of latest revision of Indian standards issued by BIS (Bureau of Indian Standards): IS: 1652:1991 and IEEE Std. 485 for Lead Acid (Plante) Battery.

In case Indian Standards are not available for any equipment, Standards issued by IEC/BS/VDE/IEEE/NEMA or equivalent shall be applicable.

iv. Autofill system

Bidder to provide complete system for automatic water filling (topping-up) of lead acid plante' type batteries to avoid spillage of water and acid which spoils environment. The autofill system shall be intelligent and efficient where replenishment of water is done automatically without manual intervention. The water enters the cell through the 'autofil plug' and raises the electrolyte to a preset level controlled by the float. The float raises and closes the valve in the plug by a 2.5:1 level action. When the electrolyte level drops the float operated valve will open automatically Bidder to provide the total system including necessary storage tank, pipelines, autofill plugs and all peripherals etc. The material of all parts shall be acid proof plastic material.

b) Technical Requirement

i) The battery shall be heavy duty type suitable for power plant duty with float duty operation at constant voltage permanently applied to its terminals which is sufficient to maintain the limits of +10% and -15% of the nominal system voltage at any time during the duty cycle in state close to full charge and shall be designed to supply the load in the event of normal power supply failure.

ii) The rated ampere hour capacity of the cell/battery shall be at reference temperature of 27ºC, constant current discharge at 10 hours rate (C10) for Plante type Battery to meet end cell voltage of the Cell. A design margin of 20% shall be considered.

iii) The battery shall be suitable for being boost charged to fully charged condition from fully discharged condition within eight (8) hours.

iv) The batteries shall be so sized as to meet emergency load duty cycle requirements for one (1) hour. All momentary loads shall be treated as one-minute loads.

v) For PLANTE type Battery it shall be supplied uncharged for flooded cell with the electrolyte furnished in a separate non-returnable container. 10% extra electrolyte shall be furnished to cover spillage in transit or during erection.

vi) Each battery set shall consist of a group of cell electrically connected in series to attend the nominal voltage level specified on the data sheet. The terminal cells shall be supplied with connectors for termination to the charger. The supplier shall provide inter-cell connectors and related hardware and accessories required for normal operation and maintenance. All cell posts shall be shrouded and connectors insulated. Nickel plated copper shall be furnished to connect up cells of Battery set. For lead acid battery to prevent corrosion all copper/ brass material shall be effectively coated with lead.

vii) Cell container shall be made of heat resistant, tough translucent polypropylene (SAN) material to make the cell mechanically sturdy and facilitate visual electrolyte level checks for ease in of maintenance.

viii) The cell terminals posts shall be provided with connector bolts and nuts, made of Nickel plated steel or lead coated copper/brass material to prevent corrosion. The terminals shall be suitable for short circuit current and specified discharge current without damage to cell as a result of terminal heating.

ix) Flame arresting flip-open/ or ceramic vent cap shall be provided on the cell to avoid explosion and contamination.

x) The following information shall be permanently marked on the cell :

- Nominal voltage.
- Name or manufacturer/model reference.
- Rated capacity in ampere hour (Ah) with End Cell Voltage.
- Voltage for float operation of 27° with tolerance of ±1%.
- Month and year of manufacture.

xi) Battery racks shall be constructed of best quality teakwood with at least three (3) coats of electrolyte -resistant paint of approved shade forming a rigid structure. Cell shall be supported on PVC/porcelain/Hard Rubber insulator fixed on the rack with adequate clearance between adjacent cells.

xii) Each set of battery shall be equipped with a automatic battery condition (Health check) and performance monitoring system. The battery monitoring system shall compare measured figure during a partial discharge against stored characteristics for the type and capacity of the battery. The system shall be able to test, analyse and predict the battery performance, computing remaining capacity and battery efficiency. The automatic battery monitoring system shall compensate for cell temperature and discharge load current throughout the discharge cycle, premature failure of the batteries etc. The system shall have a programmable event log shall be secured in

the event of total power failure for a period upto six month. In addition to local indication and control the battery monitoring system shall include an RS. 232 output port to enable battery parameters and alarms to be monitored from plant DCS

4.06.00 **Float-cum-Boost Charger**

4.06.01 The charger shall be solid-state type with full wave fully controlled, bridge configurations. It shall be suitable for the inverter of IGBT type.

4.06.02 The charger shall be provided with automatic voltage regulation, current limiting, smoothing filter circuit and soft-start feature.

4.06.03 The charger shall have the provision of float, equalizing and boost charging. Further the charger shall be suitable for single and parallel operation.

4.06.04 Suitable circuitry shall be provided to ensure that the charging current is voltage regulated and current limited.

4.06.05 Each charger shall be rated to meet 100% UPS load plus recharge the fully discharged UPS battery within 8 hours.

4.06.06 Voltage control shall be stepless smooth and continuous. Float & equalizing control shall have an adjustable range of ± 5%.

For Other details as given in sub-section of Battery & Battery charger specification

4.07.00 **Step-down transformer and voltage stabilizer**

a) A three phase to single phase transformer along with associated voltage stabilizer shall be furnished with the UPS system.

b) The transformer and stabilizer shall be sized for 100% UPS load and shall coordinate with the largest branch circuit protection device for feeder short circuit current without sacrificing voltage regulation.

c) The voltage stabilizer shall employ silicon solid state circuitry and shall maintain the specified output voltage for 0 to 100% load with maximum input voltage variation as indicated in the annexure.

d) Provision shall be kept for dead closing of static transfer switch from stabilizer circuit to inverter when the output of the stabilizer is zero, but at that time the inverters are running.

4.08.00 **A.C. Distribution Boards**

a) The distribution boards shall be fixed type, of modular design in freestanding gasketted sheet steel enclosure conforming to IP-54. Sheet steel thickness shall be 2 mm minimum.

b) Each module shall be housed in a separate compartment complete with individual front access door. Working height shall be limited to 1800 mm from floor level.

c) A full height vertical cable alley shall be provided in each panel to facilitate module wiring. The alley shall be liberally sized and shall have removable cover at the front. Removable back covers shall be provided at the back of the panels.

d) Switches shall be double pole, air break, heavy duty type, capable of safely making and breaking the full load current of associate circuit.

e) Switch handle shall have position indicator and provision of padlocking in ON & OFF positions. Further it shall be interlocked with access door for safety.

f) Fuses shall be HRC, preferably link type, design to permit easy & safe replacement.

Visible indication shall be provided for indication of fuse.

4.09.00 **UPS Cabinets/Enclosures**

a) The UPS system components shall be housed in a sheet steel freestanding IP-42 enclosure with all access from the front. Sheet steel thickness shall be 2 mm minimum.

b) The enclosure shall consist of vertical cabinets housing modules in rack type sub-assemblies, connected mechanically and electrically to form a rigid, self-supporting, metal enclosed structure.

c) The modular units shall be mounted in pull out and/or swing trays. Each module shall be capable of being easily removed to provide for the ready inspection of major solid-state devices.

d) Vertical wiring trough shall be provided for the entire height of the UPS cabinet. Cable entry shall be from bottom only.

e) Adequate ventilating louvers and screens shall be provided. The top of the panel shall be protected by a suitable drip cover to prevent entrance of falling liquid and foreign material.

f) If the equipment supplied requires forced air cooling, the cooling system furnished shall meet the following requirement :

i) Two (2) nos. 100% cooling fans, industrial grade, shall be provided for each vertical panel.

ii) Completely independent duplicate protection, control and wiring systems shall be provided for the cooling fans for redundancy.

iii) The cooling fans shall be powered from the output of the associated inverter. Normally one fan will be running while the other is on stand-by.

iv) Each cooling fan shall be equipped with an airflow switch having an alarm contact that closes upon failure of airflow.

4.10.00 **Alarms**

a) Solid state audio-visual annunciation system shall be provided for inverters, static transfer switch, battery charger.

b) Alarm facia shall be provided on each charger and inverter panel, complete with proper actuating devices, circuitry and legends.

c) The arrangement shall be such that on occurrence of a fault the corresponding window will light up and stays lighted until the fault is cleared and reset button pressed.

d) Each time a window lights up a master relay will get energized to provide group alarm signals for remote DDCMIS alarm system.

e) The requirements of indication/metering/alarms are given in the annexure.

f) Alarm contacts shall be rated 0.5 A at 220 V DC and 5A at 240 V A.C.

g) All indicating meter shall be digital type with in-built transducers (4-20mA) for hooking up with DDCMIS.

4.11.00 **Lamp / Space Heaters / Receptacles**

a) The panels shall be provided with :

i) Internal illumination lamp with door switch.

ii) Space heater with thermostat control.

iii) 3-pin 6A receptacle with plug.

b) Lamp, heater and receptacle circuits shall have individual switch fuse units.

4.12.00 **Wiring / Cabling**

a) The panels shall be completely wired up. All wiring shall be done with flexible, 1100V grade, fire resistance PVC insulated wires with stranded 2.5 Sq.mm. copper conductors and routed through wiring troughs. Each wire shall be ferruled by plastic tube with indelible ink print at both end having terminal block No., terminal number as per approved wiring diagram.

b) Panels shall have removable gland plate for cable entry. All incoming/ outgoing cables shall be terminated in suitable terminal block.

c) Control terminal blocks shall be box-clamp type, minimum 10 Sq.mm. 20% spare terminals shall be furnished.

4.13.00 **Nameplate**

a) Engraved nameplates shall be provided for each panel and for each equipment/device mounted on it.

b) The material shall be anodised aluminium / lamicoid, 3 mm thick, with white letters on black background.

c) Nameplates shall be held by self-tapping screws. The size of nameplates shall be approximately 20 mm x 75 mm for equipment and 40 mm x 150 mm for panels.

d) Nameplates for panels shall be provided both on the front and rear.

e) Control and meter selection switches shall have integral nameplates. Nameplates for all other devices shall be located below the respective devices.

f) Instruments and devices mounted on the face of the panels shall also be identified on the rear with the instrument/device number. The number may be painted on or adjacent to the instrument or device case.

g) Caution notice on suitable metal plate shall be affixed at the back of each panel.

4.14.00 **Grounding**

a) Normal 3-phase A.C power supply will be grounded at the source. For grounding other than this, isolation transformer shall be furnished with the U.P.S.

b) The inverter D.C. input and A.C. output shall be electrically isolated from each other and from cabinet ground.

c) Panels shall have fully rated ground bus with two ground terminals, one at each end.

d) Each terminal shall comprise two-bolt drilling M10 G.I. bolts and nuts to receive ground connection of 50 x 6 mm G.S. flat.

e) Separate electronic grounding shall be provided for each UPS system.

4.15.00 **Tropical protection**

a) All equipment accessories and wiring shall have fungus protection, involving special treatment of insulation and metal against fungus insects and corrosion.

b) Screens of corrosion resistant material shall be furnished on all ventilating louvers to prevent the entrance of insects.

4.16.00 **Painting**

Finish paint shall be as per TSGENCO practice. Refer to clause no.1.16.00 of Section-I, Volume V-A.

5.00.00 **TESTS**

5.01.00 **Shop Tests**

5.01.01 Tests on Battery

a) Test for capacity - test for voltage during discharge

b) Ampere hour & watt hour efficiency test

c) Endurance test.

5.01.02 Tests on battery charger

a) Dielectric tests.

b) Voltage regulation check from 0 to 100% load with ± 10% input voltage variation.

c) Ripple content measurement.

d) Heat run test on current limiting value.

5.01.03 Tests on UPS System

a) Type & routine test for various components.

b) Burning test on PCBS - Assembled PCBS shall be tested at 70°C for 72 hours in loaded condition.

c) Rapid temperature cycling test at 70°C and 0°C for 30 minutes at each temperature - 5 such cycles.

d) Functional tests to demonstrate compliance with all specified requirements and published. Specifications such as frequency, regulation, voltage regulation, current limiting, fuse clearing capability of inverters, demonstration of phase and frequency control of inverter for synchronization with range of adjustments transfer and retransfer of static switches under influence of under voltage and over current, tests on chargers, batteries and other system component to confirm compliance with specification.

6.00.00 **DRAWINGS, DATA & MANUALS**

6.01.00 **To be submitted with the Bid**

6.01.01 UPS panels, Battery Charger and Battery layout drawing with dimensions

6.01.02 General Arrangement drawing of UPS panels

6.01.03 Bill of Material

6.01.04 Schematic drawing of UPS circuits

6.01.05 Battery cell voltage characteristics and data for different discharge rates

6.01.06 Technical leaflets on :

a) UPS System

b) Battery

c) Battery charger

d) Inverter

e) Static Switch

f) Manual bypass Switch

6.01.07 Duty cycle diagram and battery sizing calculation in the format of relevant IS Standard

6.01.08 Sizing calculation of UPS system, charger main equipment, viz. SCRs, rectifier transformers etc

6.01.09 Type test certificates for similar equipment.

6.02.00 To be submitted for Owner's Approval and Distribution
All relevant drawings and data pertaining to the equipment like GTP, GA drawing, BOM, foundation plan, schematic drawing, QAP, sizing calculations, etc shall be submitted by the Bidder for the approval of Owner/Owner's consultant. Also refer clause no. 1.19.02(u) of Section-I of Volume – V-A: Technical Specifications for Electrical Equipment & Accessories.

ANNEXURE-A

RATINGS & REQUIREMENTS

1.00.00	STATIC INVERTER		
1.01.00	Application	:	UPS System for Control system, DCS and other loads as required by Bidder.
1.02.00	Type	:	Static IGBT PWM type
1.03.00	Duty	:	Continuous
1.04.00	Enclosure	:	Sheet steel, IP42
1.05.00	Cooling	:	Natural convection or forced cooling using redundant fans.
1.06.00	Design Ambient temperature	:	50 Deg.C
1.07.00	Inverter capacity	:	To be decided by the Bidder
1.08.00	Overload capacity	:	300% for 4 m secs. 150% for 60 secs 125% for 10 mins 110% for continuous
1.09.00	Voltage		
	a) Inverter input, Battery output	:	To be decided by the Bidder
	b) Nominal output	:	240 V, 50 Hz, 1-phase
1.10.00	Voltage Regulation :		
	a) Steady state (0-100% load at all input voltages and all power factors)	:	$\pm$ 1.5%
	b) Transient voltage (On application or removal of 100% load)	:	$\pm$ 10%
	c) Time to recover from transient to normal voltage	:	50 milliseconds.

1.11.00 Wave form :

a)	Nominal frequency	:	50 Hz
b)	Frequency range for all conditions of input supplies, loads & temperature occurring simultaneous or in any combination (automatically controlled)	:	± 0.05 Hz.
c)	Synchronisation limits (for maintenance of synchronism between inverter and standby A.C source)	:	49 Hz to 51 Hz (factory set)
d)	Field adjustment range for (c) above	:	50± 0.05 Hz to 50± 2 Hz
e)	Total Harmonic Content	:	5% maximum at rated load
f)	Harmonic content for any single harmonic	:	3% maximum

1.12.00 Rated output current at rated output voltage with current limit not operating

a)	Current	:	200%
b)	Duration	:	100 milliseconds.

1.13.00 Efficiency at full load (Watt output/watt input) : 90% or better.

1.14.00 SCR derating from peak voltage and peak rating : 50%

2.00.00 STATIC SWITCH

2.01.00 Type : Solid-state, SCR

2.02.00 Duty : Continuous

2.03.00 Enclosure : Sheet Steel, IP42

2.04.00 Cooling : Natural convection or forced cooling using redundant fans.

2.05.00 Ambient Temperature : 50 Deg.C

2.06.00 Capacity

a) Continuous : Equal to full load capacity of the inverter.

	b) Overload	:	300% for 4 m secs. 150% for 60 secs 125% for 10 mins 110% for continuous
	c) Peak	:	1000% of continuous rating for 5 cycle.
2.07.00	Normal Voltage	:	240V, 50 Hz, 1-phase.
2.08.00	Transient Voltage Tolerance	:	340V peak above the nominal line voltage.
2.09.00	Transfer Time	:	less than 4 m secs.
3.00.00	MANUAL BY-PASS SWITCH/BREAKER		
3.01.00	Type	:	Maintained, make before break.
3.02.00	Voltage	:	600V
3.03.00	Rated Current	:	To meet the system requirement
4.00.00	BATTERY		
4.01.00	Application	:	UPS Battery
4.02.00	Design Ambient Temperature	:	50 Deg.C
4.03.00	Type	:	Lead Acid Plante type
4.04.00	Nos. of Cells per Battery	:	To be decided by the Bidder
4.05.00	Battery nominal voltage	:	To be decided by the Bidder
4.06.00	Battery AH rating	:	Bidder to compute considering 100% UPS load for 30 minutes followed by 60% UPS load for 30 minutes.
4.07.00	Method of working		
	a) Float charge (Normal)	:	2.23 Volts / Cell
	b) Boost charge (After complete discharge)	:	2.30 Volts / Cell
	c) End cell voltage	:	1.80 Volts
4.08.00	Mounting	:	Steel Rack
4.09.00	Connection	:	Cables

5.00.00 BATTERY CHARGER

5.01.00	Charger	:	Float + Boost
5.02.00	Type	:	Solid-state, full wave, fully controlled.
5.03.00	Duty	:	Continuous
5.04.00	Enclosure	:	Sheet Steel, IP42
5.05.00	Cooling	:	Natural convection or forced cooling using redundant fans.
5.06.00	Design Ambient Temperature	:	50 Deg.C
5.07.00	A.C. input :		
	a) Supply	:	415V, 3-phase, 50 Hz
	b) Voltage variation	:	±10%
	c) Frequency variation	:	+3% to -5%
	d) Combined volt frequency variation	:	10% (absolute sum)
	e) Short-circuit level	:	50 KA
	f) System earthing	:	Solidly grounded
5.08.00	D.C. output	:	100% UPS load plus restoring fully discharged battery to full charge condition in 8 hours.
5.09.00	Blocking Diode, Peak inverse voltage	:	800 V (minimum)

5.10.00 Performance Requirement

a) The output voltage of the charger shall be regulated within ± 1% of the set value for any load variation from 0 to 100% and A.C input voltage and frequency variation as indicated above in 4.06.00

b) The ripple content in charger D.C. output shall be limited to less than ± 1% with battery and less than ± 2% without battery.

6.00.00 DISTRIBUTION BOARDS

6.01.00	Type	:	Fixed, Modular.
6.02.00	Enclosure	:	Sheet Steel, IP54
6.03.00	Mounting	:	Free standing (can be attended from both front & back)

ANNEXURE-B

SET OF ACCESSORIES TO BE PROVIDED FOR EACH BATTERY BANK

a) One battery log book.

b) Two copies of printed instruction sheet.

c) One no. cell testing voltmeter (3-0-3 volts) complete with leads.

d) One no. rubber syringe type hydrometer suitable for specific gravity reading.

e) Three nos. pocket thermometer.

f) One no. thermometer (0 to 100°) with specific gravity correction scale.

g) One set cell bridging connector.

h) Battery racks suitable for accommodating the cells coated with paint.

i) Delrin insulator (with 5% extra), rubber pad etc. for rack.

j) Two nos. plastic filling bottle for filling up.

k) One pair of spanners.

l) Two pairs of rubber hand gloves.

m) Two nos. cell lifting straps.

n) One set of inter cell, inter tie and inter bank connectors as required for complete installation.

o) One cell charger for each set of battery bank (of AH capacity)

o) Apron.

p) Goggles.

q) 'No Smoking' Notice Board

NOTE: Any other accessories if required for satisfactory operation of the complete battery system shall also be included under the Scope of Contractor without any price implication.

UPS SINGLE LINE DIAGRAM

CUSTOMER:	TELANGANA STATE POWER GENERATION CORPORATION LTD TELANGANA, INDIA 5 x 800 MW YADADRI TPS, NALGONDA
OWNER'S CONSULTANT:	TATA CONSULTING ENGINEERS LIMITED BANGALORE, INDIA
	BHARAT HEAVY ELECTRICALS LTD POWER SECTOR PROJECT ENGINEERING MANAGEMENT NOIDA

JOB NO. 417
STATUS CONTRACT
DISTRIBUTION

COPY RIGHT AND CONFIDENTIAL
The information on this document is the property of BHARAT HEAVY ELECTRICALS LIMITED it must not be used directly or indirectly in any way deterimental to the interest of the company.

DEPT CODE		NAME	SIGN	DATE
I	DRN	NtJ	-sd-	23.11.17
	DESN	NtJ	-sd-	23.11.17
	CHD	RKR	-sd-	23.11.17
	APPD	SSB	-sd-	23.11.17

REV.	DATE	ALTD	CHD	APPD

REV.	DATE	ALTD	CHD	APPD
01	03.11.18	GA	RKR	SSB


1	THE DOC IS REVISED IN LINE WITH CUSTOMER/CONSULTANTS COMMENTS RECD. VIDE REF. NO. TCE.11005A-EL-VDT-118 DTD 23.10.18 .

TITLE: UPS SINGLE LINE DIAGRAM

DEPT.	SCALE
SIGN	

DRAWING NO. PE-DG-417-145-I004

SHEET 1 OF 3 REV. 01



BHEL	5X800 MW YADADRI TPS, NALGONDA	DRG. No.	PE−DG−417−145−I004	
	TITLE:− UPS SINGLE LINE DIAGRAM	REV. No.	01	DATE 03.11.18
		SHEET	2 OF 3	

L1

NOTES:


1. ACDB–1&2 NEUTRAL TO BE GROUNDED TO A DEDICATED GROUND.
2. ALL OUTPUT FEEDERS OF ACDB SHALL BE PROVIDED WITH AN LED AFTER THE FUSE FOR FEEDER ON INDICATION WITH FEEDER DESCRIPTION.
3. REDUNDANT FEEDERS SHALL BE LOCATED IN DIFFERENT ACDBs.
4. SINCE, THIS DIAGRAM IS AN SLD FOR UPS, DETAILS REGARDING SIZING HAVE NOT BEEN SHOWN. BHEL–EDN SHALL DO THE SIZING AND PREPARE TECHNICAL SPECIFICATION FOR PROCURING THE UPS.
5. THE FOLLOWING LIST OF ESSENTIAL SIGNAL EXCHANGE BETWEEN PLC AND UPS SHALL BE BOTH HARD WIRED (4–20MA) AND THROUGH THE SOFT SIGNALS.
   - A. UPS MAIN INPUT VOLTAGE AND CURRENT
   - B. CHARGER OUTPUT VOLTAGE ⚠1
   - C. BATTERY CHARGING AND DISCHARGING CURRENT
   - D. INVERTER OUTPUT VOLTAGE AND CURRENT
   - E. ACDB OUTPUT VOLTAGE AND CURRENT
   - F. INVERTER OUTPUT POWER FACTOR
   - G. SCVS O/P VOLTAGE, CURRENT.
   - H. AFTER LINE TRANSFORMER–1&2 VOLTAGES.
   - I. DC VOLTAGE, & CURRENT
   - J. STATIC SWITCH MAIN I/P , ALTERNATE I/P VOLTAGE
   - K. UPS–1&2 –KVA,KW O/PS.
   - L. UPS–1&2 POWER FACTOR, SYSTEM& GRID FREQUENCY.
   - M. EMERGENCY AC SUPPLY VOLTAGE & CURRENT.

ALL THE UPS INPUTS/OUTPUTS SIGNALS SHALL BE INDICATED IN I/O LISTR

6. IGBT'S WILL BE PROVIDED IN INVERTER CIRCUIT AND SCR'S WILL BE PROVIDED IN RECTIFIER CIRCUIT.

⚠1

LEGEND:



BHEL	5X800 MW YADADRI TPS, NALGONDA	DRG. No.	PE–DG–417–145–I004
	TITLE:– UPS SINGLE LINE DIAGRAM	REV. No.	01 DATE 03.11.18
		SHEET	3 OF 3

ELECTRIC ACTUATOR SPECIFICATION

VOLUME: V-A

SECTION-III

TECHNICAL SPECIFICATION FOR ELECTRIC MOTOR ACTUATORS

1.00.00 SCOPE

1.01.00 This Section covers the general requirements of Electric Motor Actuators for valves/dampers.

1.02.00 All electric motor actuators shall be furnished in accordance with this general specification and the accompanying driven equipment specification. All the electrical actuators shall be INTEGRAL type only.

2.00.00 STANDARDS

2.01.00 All electrical equipment shall conform to the latest applicable IS, ANSI and NEMA Standards, except when stated otherwise herein or in driven equipment specification.

2.02.00 Major standards, which shall be followed, are listed below. Other applicable Indian Standards for any component part even if not covered in the listed standards shall also be followed

i) IS-9334

ii) IS-325

3.00.00 SERVICE CONDITIONS

3.01.00 The actuator shall be suitable for operation in hot, humid and tropical atmosphere, highly polluted at places with coal dust and/or fly ash.

3.02.00 Unless otherwise noted, electrical equipment/system design shall be based on the service conditions and auxiliary power supply given in the general specification.

3.03.00 For actuator motor installed outdoor and exposed to direct sun rays, the effect of solar heat shall be considered in the determination of the design ambient temperature.

4.00.00 RATING

4.01.00 For isolating service, the actuator shall be rated for three successive open-close operation of the valve/damper or 15 minutes, whichever is longer.

4.02.00 For regulating service, the actuator shall be suitably time-rated for the duty cycle involved with necessary number of starts per hour, but in no case less than 150 starts per hour.

5.00.00 **PERFORMANCE**

The actuator shall meet the following performance requirements:

5.01.00 Open and close the valve completely and make leak-tight valve closure without jamming.

5.02.00 Attain full speed operation before valve load is encountered and imparts an unseating blow to start the valve in motion (hammer blow effect).

5.03.00 Operate the valve stem at standard stem speed and shall function against design differential pressure across the valve seat.

5.04.00 The motor reduction gearing shall be sufficient to lock the shaft when the motor is de-energised and prevent drift from torque switch spring pressure.

5.05.00 The entire mechanism shall withstand shock resulting from closing with improper setting of limit switches or from lodging of foreign matter under the valve seat.

6.00.00 **SPECIFIC REQUIREMENT**

6.01.00 **Construction**

6.01.01 The actuator shall essentially comprise the drive motor, torque/ limit switches, gear train, clutch, hand wheel, position indicator/ transmitter, in-built thermostat for over load protection, space heater and internal wiring.

6.01.02 The actuator enclosure shall be totally enclosed, dust tight, weather-proof suitable for outdoor use without necessity of any canopy. Degree of protection of enclosure for motor actuator shall be IP-65.

6.01.03 All electrical equipment, accessories and wiring shall be provided with tropical finish to prevent fungus growth.

6.01.04 The actuator shall be designed for mounting in any position without any lubricant leakage or operating difficulty.

6.02.00 **Motor**

6.02.01 The drive motor shall be three phase, squirrel cage, induction machine with minimum class B insulation and IPW-55 enclosure, designed for high torque and reversing service. Canopy shall be provided for outdoor service.

6.02.02 The motor shall be designed for full voltage direct on-line start, with starting current limited to 6 times full-load current.

6.02.03 The motor shall be capable of starting at 85 percent of rated voltage and running at 80 percent of rated voltage at rated torque and 85 percent rated voltage at 33 percent excess rated torque for a period of 5 minutes each.

6.02.04 Motor leads shall be terminated in the limit switch compartment.

6.02.05 Motor actuators for valves/dampers shall be with integral starter with 3phase/3wire, 415V AC and operable from remote.

6.02.06 Earthing terminals shall be provided on either side of the motor.

6.03.00 **Limit Switches**

Each actuator shall be provided with following limit switches: -

6.03.01 2 torque limit switches, one for each direction of travel, self-locking, adjustable torque type.

6.03.02 4 end-of-travel limit switches, two for each direction of travel.

6.03.03 2 position limit switches, one for each direction of travel, each adjustable at any position from fully open to fully closed positions of the valve/damper.

6.03.04 Each limit switch shall have 2 NO + 2 NC potential free contacts. Contact rating shall be 5A at 240V A.C. or 0.5A at 220V D.C.

6.04.00 **Hand Wheel**

Each actuator shall be provided with a hand wheel for emergency manual operation. The hand wheel shall declutch automatically when the motor is energized.

6.05.00 **Position Indicator/Transmitter**

The actuator shall have:

6.05.01 One (1) built-in local position indicator for 0-100% travel.

6.05.02 One (1) position transmitter, 4-20 mA current signal as position feedback, for remote indicator.

6.06.00 **Space Heater**

A space heater shall be included in the limit switch compartment suitable for 240V, 1 phase, 50 Hz supply.

6.07.00 **Wiring**

All electrical devices shall be wired up to and terminated in a terminal box. All wiring shall be done with 1100V grade fire resistance PVC insulated stranded copper conductor of not less than 2.5 Sq.mm cross section. All wiring shall be identified at both ends with ferrules. All the electrical actuators shall have uniform wiring.

6.08.00 **Terminal Box**

The terminal box shall be weather proof, with removable front cover and cable glands for cable connection. The terminal shall be suitable for connection of 2.5 Sq.mm copper conductor.

7.00.00 **ACCESSORIES**

As required for the driven equipment, the actuator shall be furnished with starting equipment mounted on the actuator. This shall include:

7.01.00 One (1) triple pole MCCB

7.02.00 One (1) reversing starter with mechanically interlocked contactors, 3 thermal overload relays, 2 NO + 2 NC auxiliary contacts for each contactor.

7.03.00 One (1) remote-local selector switch.

7.04.00 CLOSE-STOP-OPEN oil tight push buttons with indication lights.

7.05.00 415/240 V control transformer with primary & secondary fuses.

8.00.00 **TEST**

The actuator and all components thereof shall be subject to tests as per relevant Standards. In addition, if any special test is called for in equipment specification, the same shall be performed.

9.00.00 **DRAWINGS, DATA & MANUALS**

9.01.00 Drawings, Data & Manuals shall be submitted in triplicate with the bid and in quantities and procedures as specified in General Conditions of Contract and/or elsewhere in the specification for approval and subsequent distribution after the issue of 'Letter of Intent'.

9.02.00 **To be submitted with Bid**

Data sheet for each type of actuator shall be furnished along with internal wiring diagram, suggested control schematic and torque limit switch contact development and manufacturer's catalogues. Drawings, Data & Manuals shall be submitted in triplicate with the bid and in quantities and procedures as specified in General Conditions of Contract and/or elsewhere in the specification for approval and subsequent distribution after the issue of 'Letter of Intent'.

9.03.00 **To be submitted for Owner / Purchaser’s Approval and Distribution**

All relevant drawings and data pertaining to the equipment like GTP, GA drawing, foundation plan, BOM, control & schematics, QAP, etc. shall be submitted by the Bidder for approval of Owner/Owner’s consultant. Also refer clause no. 1.19.02(u) of Section-I of Volume – V-A: Technical Specifications for Electrical Equipment & Accessories.

ANNEXURE-A

DESIGN DATA

1.0 AUXILIARY POWER SUPPLY

Supply		Description	Consumer
L.V. Supply	(i)	415V, 3Ø, 3W, 50 Hz Effectively earthed Fault level 50 kA symm. for 1 sec.	Motors above 0.2kW upto less than 175kW.
	(ii)	240V AC/415V AC 240V, 1Ø, 2W, 50 Hz effectively earthed	Motors upto 0.2kW. Lighting, Space heating , A.C supply for Control & protective devices.
D.C. Supply		220V, 2W, unearthed Fault level 25* kA. for 1 sec.	D.C. alarm, control & protective devices

* Indicative only, the actual value will be decided by the Bidder, after substantiating the same by calculation.

2.0 RANGE OF VARIATION

A.C. Supply :

Voltage	:	± 10%
Frequency	:	+3% to -5%.
Combined Volt + frequency	:	10% (absolute sum)

During starting of large motor, the voltage may drop to 80% of the rated voltage for a period of 60 seconds. All electrical equipment while running shall successfully ride over such period without affecting system performance.

D.C. Supply :

Voltage	:	187 to 242

FORM NO. PEM-6666-0

BHEL	**SPECIFICATION FOR MOTORISED VALVE ACTUATOR**	SPECIFICATION NO.:
		VOLUME
		SECTION
		REV. NO. 00 DATE: 06.01.2015
		SHEET 1 OF 3

Data Sheet A & B

	DATA SHEET-A (TO BE FILLED BY PURCHASER)	DATA SHEET-B (TO BE FILLED-UP BY BIDDER)
GENERAL*	* PROJECT	**1 X 800 MW KOTHAGUDAM TPS**
	OFFER REFERENCE	
	* TAG NO. SERVICE	
	* DUTY	☐ ON / OFF ☐ INCHING
	* LINE SIZE (inlet/outlet): MATERIAL	
	* VALVE TYPE	☐ GLOBE ☐ GATE ☐ REG. GLOBE ☐ BUTTERFLY
	* OPENING / CLOSING TIME	
	* WORKING PRESSURE	
	AMBIENT CONDITION	SHALL BE SUITABLE FOR CONTINUOUS OPERATION UNDER AN AMBIENT TEMP. OF 0-55 DEG C AND RELATIVE HUMIDITY OF 0-95%
	VALVE SEAT TEST PRESS	BIDDER TO SPECIFY
	REQUIRED VALVE TORQUE	BIDDER TO SPECIFY
	ACTUATOR RATED TORQUE	BIDDER TO SPECIFY
CONSTRUCTION AND SIZING	CONSTRUCTION	TOTALLY ENCLOSED, DUST TIGHT, WEATHER PROOF,SUITABLE FOR OUTDOOR USE WITHOUT CANOPY, IP:65
	MECHANICAL POSITION INDICATOR	TO BE PROVIDED FOR 0-100% TRAVEL
	BEARINGS	DOUBLE SHIELDED, GREASE LUBRICATED ANTI-FRICTION.
	GEAR TRAIN FOR LIMIT SWITCH/TORQUE SWITCH OPERATION	METAL (NOT FIBRE GEARS). SELF-LOCKING TO PREVENT DRIFT UNDER TORQUE SWITCH SPRING PRESSURE WHEN MOTOR IS DE-ENERGIZED.
	SIZING	OPEN/CLOSE AT RATED SPEED AGAINST DESIGNED DIFFERENTIAL PRESSURE AT 90% OF RATED VOLTAGE. FOR ISOLATING SERVICE THREE SUCCESSIVE OPEN-CLOSE OPERATIONS OR 15 MINS. WHICHEVER IS HIGHER. FOR REGULATING SERVICE - 150 STARTS/HR MINIMUM
HANDWHEEL	* REQUIRED	■ YES ☐ NO
	* ORIENTATION	☐ TOP MOUNTED ☐ SIDE MOUNTED
	*TO DISENGAGE AUTOMATICALLY DURING MOTOR OPERATION.	
ELECTRIC ACTUATOR	ACTUATOR MAKE/MODEL	BIDDER TO SPECIFY
	MOTOR MAKE / MODEL / TYPE / RATING (KW)	BIDDER TO SPECIFY
	@ MOTOR TYPE	SQUIRREL CAGE INDUCTION MOTOR, STARTING CURRENT LIMITED TO SIX TIMES THE RATED CURRENT-INCLUSIVE OF **I.S.** TOLERANCE
	ACTUATOR APPLICABLE WIRING DIAGRAM	■ ENCLOSED ■ DRG. NO. 3-V-MISC-24227 R00 (INDICATIVE)
	COLOUR SHADE	■ BLUE (RAL 5012), To be decided during detail engg.
	PAINT TYPE **(## Refer Notes)**	☐ ENAMEL ■ EPOXY ☐ …….
	SHAFT RPM	BIDDER TO SPECIFY
	OLR SET VALUE	BIDDER TO SPECIFY
	@ STARTING / FULL LOAD CURRENT	BIDDER TO SPECIFY
	NO. OF REV FOR FULL TRAVEL	BIDDER TO SPECIFY
	@ PWR SUPP TO MTR / STARTER	415V, 3PH, AC, 3 WIRE
	@ CONTROL VOLTAGE REQUIREMENT	TO BE DERIVED FROM THE POWER SUPPLY TO THE STARTER ☐ 230 V ☐ 110 V
	@ ENCLOSURE CLASS OF MOTOR	☐ IP 65 ☐ FLAME PROOF

BHEL	**SPECIFICATION FOR MOTORISED VALVE ACTUATOR**	SPECIFICATION NO.:
		VOLUME
		SECTION
		REV. NO. 00 DATE: 06.01.2015
		SHEET 2 OF 3

Data Sheet A & B

		DATA SHEET-A (TO BE FILLED BY PURCHASER)	DATA SHEET-B (TO BE FILLED-UP BY BIDDER)
	@ INSULATION CLASS	CLASS-F TEMP. RISE LIMITED TO CLASS-B	
	@ WINDING TEMP PROTECTION	■ THERMOSTAT (3 Nos.,1 IN EACH PHASE) ☐ ----------	
	SINGLE PHASE / WRONG PHASE SEQUENCE PROTECTION	REQUIRED	
INTEGRAL STARTER	INTEGRAL STARTER	■ REQUIRED ☐ NOT REQUIRED	
	TYPE OF SWITCHING DEVICE	■ CONTACTORS ☐ THYRISTORS	
	TYPE	■ CONVENTIONAL ☐ SMART (NON-INTRUSIVE)	
	IF SMART	NOT APPLICABLE	
	a) SERIAL LINK INTERFACE	☐ INTEGRAL ☐ FIELD MOUNTED	
	b) SERIAL LINK PROTOCOL	☐ FOUNDATION FIELD-BUS ☐ PROFI-BUS ☐ DEVICE NET ☐.....	
	c) SERIAL LINK MEDIA	☐ TWISTED PAIR Cu-CBL ☐ CO-AXIAL Cu-CBL ☐ OFC	
	d) HAND HELD PROGRAMMER	☐ REQUIRED ☐ NOT REQUIRED	
	e) TYPE OF HAND HELD PROGRAMMER	☐ BLUETOOTH ☐ INFRARED ☐.....	
	f) MASTER STATION	☐ REQUIRED ☐ NOT REQUIRED	
	g) MASTER STN INTRFACE WITH DCS	☐ MODBUS ☐ TCP/IP	
	h) DETAILS OF SPECIAL CABLE	☐ ENCLOSED ☐ NOT REQUIRED	
	STEP DOWN CONT. TRANSFORMER	■ REQUIRED	
	OPEN / CLOSE PB	■ REQUIRED ☐ NOT REQUIRED	
	STOP PB	■ REQUIRED ☐ NOT REQUIRED	
	INDICATING LAMPS	■ REQUIRED ☐ NOT REQUIRED	
	LOCAL REMOTE S/S	■ REQUIRED ☐ NOT REQUIRED	
	STATUS CONTACTS FOR MONITORING	■ REQUIRED ☐ NOT REQUIRED	
	INTEGRAL STARTER DISTURBED SIGNAL	REQUIRED (O/L RELAY OPERATED, CONT. /POWER SUPPLY FAILED, S/S IN LOCAL, TORQUE SWITCH OPTD. MID WAY)	
INTERPOSING RELAY/OPTO COUPLER (Applicable for integral Starter)	TYPE OF ISOLATING DEVICE	■ INTERPOSING RELAY ☐ OPTO COUPLER ☐ EITHER	
	QUANTITY	☐ 2 NOs. ■ 3 NOs.	
	DRIVING VOLTAGE	■ 20.5 – 24V DC ☐ _____V DC	
	DRIVING CURRENT	■ 125mA MAX ☐ _____mA MAX	
	LOAD RESISTANCE	■ > 192 ohms - <25 k ohms ☐ > _____ohms - < _____ohms	
TORQUE SWITCH (Not Applicable for Smart Actuator) **($$ Refer Notes)**	MFR & MODEL NO.	BIDDER TO SPECIFY	
	OPEN / CLOSE	■1 No. ☐2Nos. / ■1 No. ☐2Nos	
	CONTACT TYPE	2 NO + 2 NC	
	RATING	5A 240V AC AND 0.5A 220V DC	
	CALIBRATED KNOBS(OPEN&CLOSE TS)	REQUIRED FOR SETTING DESIRED TORQUE	
	ACCURACY	+3% OF SET VALUE	
LIMIT SWITCH (Not Applicable for Smart Actuator) **($$ Refer Notes)**	MFR & MODEL NO.	BIDDER TO SPECIFY	
	OPEN : INT : CLOSE	☐1 No ■2 Nos. / 2 Nos. (ADJ.) / ☐1 No. ■2Nos.	
	CONTACT TYPE	2 NO + 2 NC	
	RATING (AC / DC)	5A 240V AC AND 0.5A 220V DC	

FORM NO. PEM-6666-0

BHEL	**SPECIFICATION FOR MOTORISED VALVE ACTUATOR**	SPECIFICATION NO.:
		VOLUME
		SECTION
		REV. NO. 00 DATE: 06.01.2015
		SHEET 3 OF 3

Data Sheet A & B

	DATA SHEET-A (TO BE FILLED BY PURCHASER)	DATA SHEET-B (TO BE FILLED-UP BY BIDDER)	
POSITION TRANSMITTER	POSITION TRANSMITTER	■ REQUIRED ☐ NOT REQUIRED	
	MFR & MODEL NO.	BIDDER TO SPECIFY	
	TYPE	☐ ELECTRONIC (2 WIRE) R/I CONVERTER ■ ELECTRONIC (2 WIRE) CONTACTLESS	
	SUPPLY	■ 24V DC ☐	
	OUTPUT	■ 4-20mA	
	ACCURACY	± 1% FS	
SPACE HEATER	@SPACE HEATER	REQUIRED	
	@ POWER SUPPLY (NON INTEGRAL)	240V AC,1 PH.,50 Hz	
	@ POWER SUPPLY (INTEGRAL)	240V AC , 1 PH/415/240 V CTRL TRANSFORMER WITH PRIMARY AND SECONDARY FUSES	
	@ RATING		
TERMINAL BOX	ACTUATOR/MOTOR TERMINAL BOX	REQUIRED	
	ENCL CLASS ACTUATOR/MOTOR T.B.	@☐ IP 68 @☐.....	
	@ EARTHING TERMINAL	REQUIRED	
	PLUG & SOCKET(9 PIN) (FOR COMMD, LS/TS FEED BACK, PoT)	☐ REQUIRED ■ NOT REQUIRED ☐ 2 NOS. ☐ ----------	
CABLE GLANDS	@ POWER CABLE GLAND	SIZE:----------	
	@ SPACE HEATER CABLE GLAND	SIZE:----------	
	OTHER CONTROL CABLE GLANDS-1	INSTRUMENT CABLE SIZE FOR ON/OFF DUTY VALVES SHALL BE 8PXO.5 SQMM - ONE CABLE GLAND OF OD SIZE 20 MM. INSTRUMENT CABLE SIZE FOR INCHING DUTY TYPE VALVES SHALL HAVE TWO NO. CABLES (ONE NO. 8PXO.5 SQMM AND 2ND 2PXO.5 SQMM) - TWO NO. GLANDS OF OD SIZES 20 MM & 15 MM.	
	OTHER CONTROL CABLE GLANDS-2		
WEIGHT	TOTAL WEIGHT (ACTUATOR + ACCESSORIES)	BIDDER TO SPECIFY	_____ Kg.

NOTES:

1. **SCOPE**: DESIGN, MANUFACTURE, INSPECTION, TESTING AND DELIVERY TO SITE OF ELECTRIC ACTUATOR FOR INCHING OR OPEN / CLOSE DUTY.
2. **CODES & STANDARDS**: DESIGN AND MATERIALS USED SHALL COMPLY WITH THE RELEVANT LATEST NATIONAL AND INTERNATION STANDARD. AS A MINIMUM, THE FOLLOWING STANDARDS SHALL BE COMPLIED WITH:
   IS-9334, IS-2147, IS-2148, IS-325, IS-2959, IS-4691 AND IS-4722
3. TEMPERATURE RISE SHALL BE RESTRICTED TO 70 DEG. C FOR AMBIENT TEMPERATURE OF 50 DEG C.
4. CABLE GLANDS OF DOUBLE COMPRESSION TYPE, BRASS MATERIAL, WITH NICKEL COATING SHALL BE PROVIDED.
5. THE TORQUE SWITCHES SHALL BE PROVIDED WITH MECHANICAL LATCHING DEVICE TO PREVENT OPERATION WHEN UNSEATING FROM THE END POSITIONS. THE LATCHING DEVICE SHALL UNLATCH AS SOON AS THE VALVE LEAVES THE END POSITION. IF SUCH PROVISION IS NOT POSSIBLE, THE TORQUE SWITCHES SHALL BE BYPASSED BY END-POSITION LIMIT SWITCHES WHICH OPENS ON VALVE LEAVING END POSITION.THESE LIMIT SWITCHES ARE ADDITIONAL TO THE NUMBER OF LIMIT SWITCHES SPECIFIED ELSEWHERE.
6. THE MOTOR SHALL OPERATE SATISFACTORILY UNDER THE +/- 10% SUPPLY VOLTAGE VARIATION AT RATED FREQUENCY, -5% TO +3% VARIATION IN FREQUENCY AT RATED SUPPLY VOLTAGE, SIMULTANEOUS VARIATION IN VOLTAGE & FREQUENCY THE SUM OF ABSOLUTE PERCENTAGE NOT EXCEEDING 10%.
7. THE MOTOR SHALL BE SUITABLE FOR DIRECT ON LINE STARTING.


$$ TORQUE SWITCH & LIMIT SWITCH SHALL ACT INDEPENDENT OF EACH OTHER. TANDEM OPERATION IS NOT ACCEPTABLE.

EPOXY PAINT IS RECOMMENDED FOR COASTAL AREAS.

	VENDOR COMPANY SEAL NAME SIGNATURE DATE

NOTES* = TO BE FILLED BY MPL (LEAD AGENCY). @= TO BE FILLED BY ES

DRAWING NO. 3-V-MISC-24227



CONTACT DEVELOPMENT DIAGRAM

OTS	1-2	OPEN AT OVER TORQUE DURING OPENING TRAVEL	
	3-4	CLOSE AT OVER TORQUE DURING OPENING TRAVEL	
CTS	5-6	OPEN AT OVER TORQUE DURING CLOSING TRAVEL	
	7-8	CLOSE AT OVER TORQUE DURING CLOSING TRAVEL	
OLS-1	9-10		
	11-12		
CLS-1	13-14		
	15-16		
OLS-2	17-18		
	19-20		
CLS-2	21-22		
	23-24		
SWITCH	TERMINAL NO.	FULL OPEN	a — INTERMEDIATE — b — FULL CLOSE
		VALVE POSITION	

INDICATES CONTACT CLOSED

INDICATES CONTACT OPEN

CONTACT RATING: 5A AT 250V AC & 0.5A AT 220V DC

SETTING PROCEDURE OF POSITION LIMIT AND TORQUE SWITCH

VALVES	OPEN		CLOSE	
	MAIN	BACK UP	MAIN	BACK UP
GATE VALVE OF 100 mm AND ABOVE IN 1500 CL AND ABOVE RATINGS	OLS	OTS *	CLS	CTS
ALL OTHER GATE & GLOBE VALVES	OLS	OTS *	CTS	#

- CLS NOT TO BE CONNECTED IN TRIP CIRCUIT

* - BYPASS OTS FOR INITIAL 5% OF TRAVEL (FOR GATE VALVES ONLY)

NOTE:-

1. ALL TORQUE AND LIMIT SWITCHES (OTS,CTS,OLS1&2, CLS1&2) ARE WITH 2NO+2NC CONTACTS '1NO+1NC' IS TERMINATED IN TBS 1-24, REMAINING CONTACTS ARE FOR INTERNAL USE. ANY SPARE CONTACTS WHICH ARE NOT USED INTERNALLY ARE TO BE TERMINATED IN TBS 25-32
2. CTS - TORQUE SWITCHES FOR CW ROTATION (CLOSE)
3. OTS - TORQUE SWITCHES FOR CCW ROTATION (OPEN)
4. OLS-1, OLS-2 - LIMITSWITCHES FOR POSITION OPEN
5. CLS-1, CLS-2 - LIMITSWITCHES FOR POSITION CLOSE
6. EPT - ELECTRONIC POSITION TRAMSMITTER (Contactless , FOR INCHING DUTY)
7. R1-R2-POTENTIOMETER 2 x 100 OHMS (FOR ON-OFF DUTY)
8. FOR COMMANDS & EPT EITHER INTERNALLY GENERATED 24 VDC OR EXTERNAL SUPPLY OF 24VDC CAN BE USED
9. M - MOTOR 3ø 415V 50 Hz AC SUPPLY

REV	DATE	ALTERED
		CHD & APPD

CAUTION: The information on this document is the property of BHARAT HEAVY ELECTRICALS LTD. It must not be used directly or indirectly in any way detrimental to the interest of the company.

TYPE OF PRODUCT OR NAME OF CUSTOMER/PROJECT: ELECTRICAL VALVE ACTUATORS (AC) WITH INTEGRAL STARTERS (DRAWN FOR INTERMEDIATE POSITION OF VALVES)

BHARAT HEAVY ELECTRICALS LTD.,
UNIT: HIGH PRESSURE BOILER PLANT.
TIRUCHIRAPALLI-620014.
365-121

	NAME	SIGN	DATE	NO.OF VAR.
DRN	N.P.ESWAR	N.P	07.10.04	
CHD	D.DINAKARAN	D.D	07.10.04	
APPD	K.ARUNACHALAM	K.A	07.10.04	

DEPT: VL | CODE | SCALE | WEIGHT (KG). | REFERENCE INFORMATIONS | NO. OF ITEMS

TITLE: WIRING DIAGRAM (TERMINAL PLAN) FOR ACTUATOR WITH INTEGRAL STARTER

CARD CODE: U 01

DRAWING NO.: 3-V-MISC-24227

REV: 0

FIBRE OPTIC CABLE SPECIFICATION

1.07.00 DELEED

1.08.00 DELETED

1.09.00 Optical Fiber Cable

Bidder shall supply and install optical fiber cable and all cable accessories and fittings like Light Interface Unit, Surge suppressors, Opto isolators, Interface converters, Fiber Optic Card Cage, Fiber Optic Line Driver, Repeater/ Modem, cable glands, grommets, lugs, termination kits etc on as required basis.

Optical Fiber Cable shall be 4/8/12 core. Each core shall be of ultra pure fused silica glass with UV cure acrylate suitable to withstand temperature between 20 and 80ºC. The cable shall have multiple mono mode fiber. On as required basis so as to avoid usage of any repeaters. . Fiber optic cable shall be of loose buffer tube design with 4 fibers per buffer tube (minimum). Interstices and buffer tubes shall be filled with water blocking compound such as thixotropic gelly to protect against moisture and vibration.Buffer tube shall

be made of materials like Poly-Butelene Terathylate (PBT). They shall be colored for easy identification.. Buffer tubes shall be stranded around Central Strength Member utilizing Reverse Oscillating Lay (ROL). Blank fillers shall be used as necessary to maintain circular cable structure.

The central strength member shall be Fiber Reinforced Plastic (FRP) or other material with equivalent mechanical strength to provide both tensile and anti-buckling strength to cable.

The interstices between buffer tube and jacket layers shall be protected from water intrusion by a combination of dry water blocking yarns and tapes. These dry materials shall be easily removable from core during cable preparation without use of cleaning solvent.

In addition to central strength member, additional strengthening substance like aramid yarns shall be applied helically over the cable core to provide additional tensile strength to cable.

The cable shall be of dual jacket and armoured. Inner sheath consists of medium density poly ethelyne extruded over cable core. Two highly visible ripcords are placed under the jacket to aid in sheath removal. Electrolytically chrome plated corrugated steel taped (ECCST) armouring is provided around inner jacket to provide additional cable compression strength and rodent protection. The armour is covered with outer black MDPE sheath with FRLS and UV resistance properties. A ripcord is also placed under neath the armour for easy outer sheathing removal. The cable shall be suitable for a maximum tensile force of 2000N during installation and once installed, a tensile force of 1000N minimum. The compressive strength of cable shall be 3000N minimum and crush resistance 4000N minimum. Minimum bending radius shall be equal to or more than 15D.

Specification for G.652 Monomode Fiber:

Sl. No.	Attribute	Value
1	Core Diameter	9±1 micrometer
2	Cladding Diameter	125±1 micrometer
3	Cladding non circularity	≤1.0%
4	Attenuation coefficient at (i) 1290 nm to 1340 nm (ii) 1525 nm to 1575 nm	 <0.36 Db/km <0.25 Db/km
5	Chromatic dispersion coefficient at (i) 1310 nm (ii) 1550 nm	 <3.5 ps/ nm.km <18 ps/ nm.km
6	Polarization Mode Dispersion (PMD)	≤0.5 ps/√km

	coefficient	
7	Mode field diameter at (i) 1310 nm (ii) 1550 nm	9.2±0.4 micrometer 10.50±1.0 micrometer
8	Mode field concentrality error	≤0.5 micrometer
9	Proof test	≥1%
10	Fiber Curl	≥ 4.0 m
11	Macro bend test on fiber at 1550 nm	≤0.1 dB

The entire length of the cable shall be marked with the manufacturer name, month and year of manufacture, coded description of the cable based on Telcordia's(Bellcore) SR-2014 Suggested Optical Cable Code (SOCC),progressive sequential length marking at every meter interval on outer sheath.

Following tests as per anty approved standards such as FOTP, IEC etc shall be carried out on the cables:

a. Attenuation and dispersion characteristics test
b. Proof test
c. Macro-Bend Resistance Test
d. Mechanical Tests
e. Low and High Temperature Cable Bend Test
f. Impact Resistance Test
g. Compressive Strength Test
h. Tensile Strength Test
i. Cable Twist Test
j. Cable Cyclic Flexing Test
k. Environmental Characteristics Test
l. Temperature Cycling Test
m. Color Performance Test
n. Cable Aging Test
o. Water Penetration Test
p. Lightning Test
q. Routine Test/ Sample Test
r. Site Test (Continuity and Attenuation)

s. FRLS Test

1.10.00 DELETED

VARIABLE FREQUENCY DRIVE

VOLUME : V-A

SECTION-XII

TECHNICAL SPECIFICATION FOR VARIABLE FREQUENCY DRIVES

CONTENTS

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE OF SUPPLY
2.00.00	CODES AND STANDARDS
3.00.00	TYPE
4.00.00	PERFORMANCE REQUIREMENT
5.00.00	CONTROL REQUIREMENT
6.00.00	PANEL CONSTRUCTION
7.00.00	COOLING
8.00.00	EQUIPMENT/COMPONENT SPECIFICATION
9.00.00	POWER TRANSFORMER
10.00.00	POWER CONVERTER
11.00.00	DC LINK REACTOR
12.00.00	OUTPUT FILTER
13.00.00	BY PASS FEATURE
14.00.00	CT/PT/METERS
15.00.00	LOCAL MOTOR CONTROL STATIONS
16.00.00	PROTECTION, CONTROL, METERING, INDICATION AND ANNUNCIATION
17.00.00	OPERATOR CONTROL PANEL

CONTENT [Contd…]

CLAUSE NO.	DESCRIPTION
18.00.00	PROTECTIVE FEATURES
19.00.00	CONTROL
20.00.00	INDICATORS
21.00.00	METERING
22.00.00	AUDIO-VISUAL ANNUNCIATION
23.00.00	FAULT DIAGNOSTIC
24.00.00	EXTERNAL POWER SUPPLY FOR AUXILIARY AND CONTROL CIRCUIT
25.00.00	RELIABILITY FEATURES
26.00.00	MAINTENANCE FEATURE
27.00.00	PAINTING
28.00.00	INSPECTION, TESTING AND ACCEPTANCE
29.00.00	DRAWINGS, DATA & MANUALS

VOLUME : V-A

SECTION-XII

TECHNICAL SPECIFICATION FOR VARIABLE FREQUENCY DRIVES

1.00.00 SCOPE OF SUPPLY

1.00.01 VFD system shall consist of all components required to meet the performance, protection, safety and certification criteria of this specification.

1.00.02 Each VFD shall be furnished complete with :-

Fittings and accessories.

a. Auxiliary Equipment

b. All supporting steel work and hardwares

1.00.03 One set of special tools and tackles

1.00.04 Mandatory Spare parts

1.00.05 All relevant drawings, data and instruction manuals.

2.00.00 CODES AND STANDARDS

DC reactor – IEC 289

HT Circuit Breaker – IEC 56

Motors – IS 325 / IEC 34 / IS 4722

Transformers – IS 2026

Bushings – IS 2099 / IEC 137

Bushing CT – IEC 185 / IS 2705

Semiconductor converter – IEC 146

AC Contactor – IEC 158-1 / VDE 0660

3.00.00 TYPE

System shall be load commutated invertor type, 12-pulse design, having two channels (each channel with six pulse design) for each motor.

4.00.00 PERFORMANCE REQUIREMENTS

4.01.00 The system shall be energy efficient, designed as standard product and shall provide very high reliability, high power factor, low harmonic distortion and low vibration/ wear/ noise.

4.02.00 The system shall be designed to deliver the motor input current and torque for the complete speed torque characteristics of the large fan drives like ID Fans

and other motors as specified in the specification elsewhere as per requirement with input supply variation of ± 10% and frequency variation of ±5%. It shall be capable of withstanding the thermal and dynamic stresses and the transient mechanical torque, resulting from short circuit.

4.03.00 The drive system shall be designed to operate in one or more of the following operating modes as to suit characteristics of the driven equipment

i) Variable torque changing as a function of speed i.e. speed squared

ii) Constant torque over a specific speed range

iii) Constant power over a specific speed range where the torque decreases when speed increases

4.04.00 The drive controller shall be equipped with microprocessor based digital regulator with programmable functions. The power control regulator logic shall provide for an acceleration/deceleration current limit curve and shall be capable of field be separately programmable from 0.1 to 20 seconds.

4.05.00 Each channel and motor rating shall be rated to meet the requirements of driven equipment. The system shall be designed for linear continuous speed control from 20% to 100% of rated speed and shall be of a modern proven design and fully compatible with excitation system offered.

4.06.00 The Total Harmonic Distortion (THD) of the voltage and current at inverter output shall be as per IEC 61800-4 and it shall be considered in the design of the motor.

4.07.00 Harmonics at the supply side of the drive system at primary of the main input transformer shall be restricted within the maximum allowable levels of current and voltage distortion as per recommendations in the latest edition of IEEE-519.

4.08.00 The overload capacity of the controller shall be 150% of rated current of motor for one minute for constant torque applications, and 115% of rated current for one minute for variable torque application at rated voltage. If the motor load exceeds the limit, the drive shall automatically reduce the frequency and voltage to the motor to guard against overload. If the load demand exceeds the current limit for more than one (1) minute, the drive shall shut down to prevent overheating of the motor and damage to the drive.

4.09.00 During operation, the system shall be capable of developing sufficient torque under all load condition to respond to a 20% alteration in speed set point within a time limit up to 60 seconds.

4.10.00 The integrator action of the speed set point alteration shall be independently adjustable for both an upward and downward alteration. The minimum time interval between set point adjustments by the distributed control system shall be considered as 10 second.

4.11.00 The drive shall trip incase the speed exceeds 105% of the maximum operational speed or reduces to 95% of the minimum operational speed for more than 10 second.

4.12.00 Maximum noise level from the drive at 1meter distance, under rated load with all normal cooling fans operating shall not exceed 85dBA.

4.13.00 Variable frequency drive shall be arranged so that it can be operated in a circuit mode, disconnected from the motor for start up adjustment and troubleshooting/ maintenance.

4.14.00 Voltage at motor neutral terminal shall be floating and neutral shall be insulated adequately for Load Commuted Inverter (LCI) operation.

4.15.00 The drive system shall ensure following

a) Harmful VFD induced harmonics which can create motor heating are eliminated.

b) VFD induced torque pulsation are limited to maximum 1% (even at low speed) so there is minimal stress to the equipment.

c) Motor is protected from dv/dt stresses.

d) No appreciable increase in motor audible noise.

4.16.00 Electrical performance of the system shall comply to IEEE, IEC and equivalent international standard.

5.00.00 **CONTROL REQUIREMENT**

5.01.00 The system shall operate on constant V/f supply with required voltage boost capability in low frequency mode of operation.

5.02.00 Short time voltage dip up to 20% of nominal voltage (e.g. in case of a large motor start up connected to the same bus as VFD) shall not cause the control system to stop functioning and shall not trip the drive system.

5.03.00 The system shall also be equipped with a facility which will restart the system in case of voltage dip over 20% or power interrupter for less than 2 seconds, with recovery of the voltage to its normal value. The drive shall have the facility to block this feature, if required by operator. Upon restart the converter shall be capable of synchronizing onto a rotating motor and develop full acceleration torque within 10 seconds.

5.04.00 The power controller shall be controlled to always start the motor in the forward direction. Logic shall be provided to prevent the motor from being started in the reverse direction.

5.05.00 The drive motor shall be speed controlled corresponding to 4-20mA or 0-10V reference input signal. Unless otherwise specified, upon complete loss of the users speed reference signal, the drive shall automatically run at constant speed as at 8-100% of the last speed reference available prior to the loss of signal.

5.06.00 It shall be possible to vary the speed of the drive in either manual or auto mode.

Auto/manual selection shall be from VFD panel unless otherwise specified.

- With the selector switch in "manual" mode, the operator shall be able to set the speed through keypad, mounted on front of the drive panel or from speed increase/decrease push buttons from the field. Motor operated potentiometer shall be provided as a speed set point device.

- With selector switch in "auto" mode, speed of the motor shall be controlled from a 4-20mA signal, from PLC/DDCMIS system. Necessary equipment like protocol converter as required for interfacing with PLC/DDCMIS shall also be provided in the drive panel.

5.07.00 The required provision for the interface with remote ~~DDCMIS~~ PLC located at control room shall be either through hardwired connection (with potential free contacts and transducers as described elsewhere in this specification) or serial link.

5.08.00 Deleted

5.09.00 The closed loop control feedback for the drive system having output transformer shall be tapped from the secondary side of the output transformer.

6.00.00 **PANEL CONSTRUCTION**

6.01.00 The panel shall include suitable semi conducting power devices (line commuted thyristors/Diodes/IGBT). Modules with protective devices, reactors (if required), filters (if required), control circuit, control accessories, indication and annunciation etc, the construction of the panel shall provide effective protection against electromagnetic emissions and shall meet design requirement of integrated standards

6.02.00 Upstream breaker "ON/OFF/TRIP" indications and remote breaker closing and trip push button shall be provided on the front door.

6.03.00 Safety Interlock shall be provided so that power cabinet can't be opened unless the up stream breaker is disconnected, safety-grounding switch is closed and DC link capacitor is discharged. Power source breaker can only be closed once the earthing switch is open and panel door is closed with lock defeat facility.

6.04.00 Duplicate control supply with automatic changeover shall be provided. Protection shall be provided against AC/DC transients, voltage surge etc. of power and control device.

6.05.00 The drive shall be housed in sheet steel panels fabricated with 2mm thick cold rolled sheet steel. The panel shall be suitable for indoor installation, if not otherwise specified. The panel shall be free standing with degree of enclosure

protection as IP-41. The maximum operating height shall be 1800mm approximately.

6.06.00 Bolted un-drilled gland plate shall be provided at bottom. Clamp type terminals shall be used for connection of all wires up to $10mm^2$ and terminal for higher sizes shall be bolted type suitable for cable lugs. Minimum space for power cable termination shall be 600mm clear from bottom of the cable gland plate.

6.07.00 Bus bars shall be of electrolytic copper, color coded separately for AC and DC system. All the live parts shall be sleeved/ shrouded to ensure complete safety to personnel intending to carry out routine inspection by opening the panel doors. All the equipment inside the panel and on the doors shall be provided with suitable nameplate.

6.08.00 All the switches, component and accessories which are essential for normal and emergency operation shall be mounted on the door and shall be operable externally. All the analog instruments, where provided, shall be switchboard type, back connected; 72x72mm.Scale shall have red mark indicating maximum permissible operating rating.

6.09.00 Each panel shall be provided with illuminating lamp/11W CFL with switch and fuse. 5/15A, 240V power socket with switch and fuse shall be provided. Each panel shall have space heater with switch fuse and variable setting thermostat.

6.10.00 Copper earth bus of min. 50x6 mm size shall be provided in the panel with provision for connection to purchaser's plant earth grid. All the non-metallic components/parts shall be connected to the main earth bus bar. Separate earth bus bar and stud for electronic control system as required shall be provided.

6.11.00 All the metal parts shall be treated so as to ensure efficient anti-corrosive protection. Hard wares shall be zinc passivated or electrogalvanised. Panel enclosure and structure supports shall be thoroughly cleaned and degreased to remove mill scale and rust etc. Paint shade of external surface shall be as per Section-X of Volume – IIA: Lead Specification.

6.12.00 All panels shall be of same height so as to form a uniform line-up, to give good aesthetic appearance.

6.13.00 All the control wiring shall be enclosed in plastic/metal channel. Each wire shall be identified at both ends by self-sticking wire marker tapes of PVC ferrules. Power and control wiring inside the panel shall be done with BIS approved, PVC insulated, fire retardant, copper conductor wire. $1.5mm^2$ size wire shall normally be used provided the control fuse rating is 10 Amps or less and 2.5mm2 size for control fuse rating above 16A for electrical circuits and 0.7 mm2 for electronic circuits. All wires shall be ferruled and terminals shall be properly numbered, minimum 20% spare terminal shall be provided.

6.14.00 All electronic modules and components shall be accessible from front of panel only. Modular assemblies for both the system control electronic equipment and power electronic equipments shall be used.

6.15.00 All low voltage compartment and cabling shall be electrically and physically separated from the high voltage compartment.

6.16.00 DC link capacitor and pre charging and discharging circuit shall be preferably mounted in the rear of the panel.

6.17.00 Suitable removable type hooks shall be provided for lifting the panel.

6.18.00 Perspex type transparent insulating material shall be used for covering live compartments.

6.19.00 Drive keypad, operator control panel required for control, monitoring and measurements shall be supplied and installed outside the panel on the front door. It shall be accessible for operation without opening the front door and shall be non-removable type.

6.20.00 All the equipment shall be complete with cable glands, lugs etc. and cable glands shall be single or double compression type for indoor and outdoor equipment respectively.

7.00.00 **COOLING**

7.01.00 The drive panel shall be naturally cooled type as per manufacturer's standards. If unavoidable, forced type cooling system shall be provided. Cooling system shall include well-dimensioned panel, adequate cooling airflow path, module cooling fan and if necessary, panel-cooling fan shall be considered. Vendor shall ensure that the panel dimensions and the flowpaths have been designed for continuous running at the specified ambient without overheating. For fan cooled drives, redundant ventilating fans (N+1) shall be provided. The VFD panels shall be located in an air-conditioned room.

7.02.00 Necessary starters shall be provided within the VFD panels for the ventilation fans, any other auxiliary motor etc. The system provided shall be interfaced with drive starting and shut down such that safety interlocks such as start permit from cooling system to drive and trip signal from cooling system to drive in case of cooling system failure etc., shall be incorporated in the overall sequence logic.

7.03.00 MCB for motor space heater, auxiliary power supply if required for local panel, drive panel space etc. shall be included and mounted in easy accessible location.

8.00.00 **EQUIPMENT/COMPONENT SPECIFICATION**

8.01.00 **Motor**

i) The motor shall be suitable for operation with a solid-state power supply consisting of an adjustable frequency inverter for speed control.

ii) The motor shall be suitable for the current waveforms produced by the power supply including the harmonics generated by the drive.

iii) The Motor shall be designed to operate continuously at any speed over the range 20-100 % of rated speed.

iv) The permitted voltage variation should take into account the steady state voltage drop across the AC drive and all other system components upstream of the motor.

v) Motors required to be transferred to DOL, by-pass mode shall be rated for specified variations in system line voltage and frequency. Starting current of motor in DOL, bypass mode shall be limited to value in motor specifications.

vi) The motor shall be constructed to withstand torque pulsations resulting from harmonics generated by the solid-state power supply.

vii) The motor insulation shall be designed to accept the applied voltage waveform, within the Vpeak and dv/dt limits as per IEC-61800-4.

viii) The drive manufacturer shall be solely responsible for proper selection of the motor for the given load application and the output characteristics of the drive.

Other details shall be as given in specification of Electric motors.

9.00.00 POWER TRANSFORMER

Indoor dry type and shall be suitable for rating complying with system details. Other details as given in sub-section of LT Aux. Transformer specification.

10.00.00 POWER CONVERTER

i) The static power shall consist of a line side power converter for operation as a rectifier and a load side power converter for operation as a fully controlled inverter. Power converter shall be fast switching, most efficient and low loss type.

ii) Adequate short circuit and over voltage protection shall be provided for the converter and inverter system.

iii) All power converter devices shall include protective devices, snubber networks and dv/dt networks as required.

iv) The current rating of the converter's semi-conductor components shall not be less than 120% of the nominal current flowing through the elements at full load of the VFD through the whole speed range.

v) All power diodes shall be of silicon type with minimum Vbo rating as 2.5 times the rated operating voltage.

vi) The power converter circuit shall be designed so that motor can be powered at its full nameplate rating continuously without exceeding its rated temperature rise due to harmonic currents generated by the inverter operation.

vii) The conversion devices and associated heat sinks shall be assembled such that individual devices can be replaced without requiring the use of any special precautions/tools.

viii) The cooling system of the electronic components, if provided, shall be monitored and necessary alarms shall be provided to prevent any consequential damage to the power control devices.

ix) Offered system shall also take in account the distance between drive panel and motor and system shall include all material and accessories to make system suitable for a distance of 350m.

11.00.00 DC LINK REACTOR

i) Smoothing reactors for the DC link shall be designed to sufficiently decouple the rectifier and inverter portion of the converter and to limit fault currents in this circuit.

ii) Reactor shall be air-core type, natural cooling and housed in a separate enclosure in ventilated room.

iii) Reactor shall be suitable for withstanding earth fault continuously and for operation with the non-sinusoidal current wave shapes and DC components under all operational conditions of the system without exceeding its temperature limits.

iv) Noise level shall not exceed value specified in NEMA TR-1

12.00.00 OUTPUT FILTER

VFD output current waveform should be inherently sinusoidal at all speeds, with harmonic limits as specified in this specification. Output filter shall be provided if required. Output filter capacitors shall be provided with discharge circuits to ensure that all residual stored charge is reduced to less than 50 V DC within 300 seconds after a loss of AC voltage. All capacitor shall be maintenance free and self-healing type.

The VFD system shall inherently protect motor from high voltage dv/dt stress, independent of cable length to motor. Output filter shall be an integral part of the VFD system and included within the VFD enclosure.

13.00.00 BYPASS FEATURE

i) Bypass breaker / contactor-HRC fuse complete with protection, annunciation and metering shall be provided.

ii) All Variable frequency drives (VFD) having bypass feature shall have motor protection relay along with necessary control and metering etc. Switching scheme shall be such that in case of drive mal-operation, the motor could be taken on bypass control manually, while the drive could be attended by opening its isolation devices.

iii) Safety interlock between inverter and bypass breaker/contactor shall be provided such that closing of healthy device is inhibited in case of external fault.

14.00.00 **CT/PT/METERS**

As required for the system offered and shall be suitable for variable frequency operation.

15.00.00 **LOCAL MOTOR CONTROL STATION**

i) The local motor control station is to be installed in the field near the motor. Components and accessories that are required in the local motor control station may be mounted on the local field mounted panel envisaged for the driven equipment.

ii) Meters in the local control station shall be suitable for 4-20mA transducer outputs and shall be calibrated for the actual motor current. Further, the drives with bypass facility, the meters shall be capable of reading bypass full load and starting currents, as well as the drive current.

16.00.00 **PROTECTION, CONTROL, METERING, INDICATION & ANNUNCIATION**

16.01.00 The system vendor shall provide all the necessary system control, protection; alarm equipment and metering for the entire drive system and its auxiliary equipment.

16.02.00 Automatic sequence control shall include start-up of cooling system, auxiliary system of the motor, interlock checking, automatic start and run-up of drive, planned and emergency shutdown. The same shall be processed through microprocessor-based system.

17.00.00 **OPERATOR CONTROL PANEL**

i) Each drive shall be equipped with a front mounted operator control panel consisting of a backlit alphanumeric display and a keypad with keys for parameterization and adjusting parameter which shall be limited to Start/Stop, Local/Remote, Auto/Manual, Increase/Decrease, menu navigation and protection and measurement parameter selection, etc. Also local operation during maintenance should be possible & the same shall be provided inside the panel.

ii) All parameter names, fault messages, warnings and other information shall be displayed in complete English words or Standard English abbreviations to allow the user to understand what is being displayed without the use of a manual or cross-reference table. This shall also

be used for the modification of all electrical values, configuration parameters, drive menu parameters, application and activity function access, faults, local control, adjustment storage, self test and diagnostics. Keypad shall be operable with password for changing the protection setting, safety interlock etc. However the parameters such as measurements, setting, and mode of drive etc. Shall be allowed to be viewed without any password.

iii) Operator console shall have facility / port to connect external hardware such as Lap-Top etc. Console shall have facility for upload and download of all parameter settings from one drive to another identical drive for start up and operation.

iv) Drive system control also have facility to receive tripping signal from up stream breaker for tripping and also provision for closing upstream breaker after all required process parameters are achieved.

v) User-friendly software for operation and fault diagnostic shall be loaded in the drive system panel before commissioning.

18.00.00 **PROTECTIVE FEATURES**

The system offered shall incorporate adequate features, properly coordinated for the drive control and for motor but not limited to the following :

i) Incoming line surge protection.

ii) Under / Over voltage protection.

iii) Phase loss, phase reversal protection.

iv) Programmable Over current Protection and under load protection.

v) Inverter fault.

vi) Over frequency operation.

vii) Ventilation loss.

viii) Over temperature of equipment.

ix) Over speed of motor.

x) Specific motor protection, including motor winding, bearing temperatures, over current, Overload, negative phase sequence, locked rotor and earth fault protections etc.

xi) System Earth fault protection.

xii) Over and under frequency, rotor earth fault, field failure protection for synchronous motor

xiii) Additional protection for drive system

19.00.00 **CONTROL**

The following controls shall be provided as a part of the operators control Panel or through separate switches.

i) Start/Stop

ii) Speed Control (Raise/lower)

iii) Auto/Manual/Test mode

iv) Local/Remote

v) Emergency Stop

vi) Start/Stop for by pass starter (where specified)

vii) Trip-Remote Breaker

viii) Sequential switching of filters

20.00.00 **INDICATORS**

Vendor shall provide indications as required for normal operation and for easy maintenance, which shall be limited to the following indications :

i) Motor running

ii) Motor stopped

iii) VFD System Fault

iv) System ready to start

v) AC mains ON

vi) Motor over speed

vii) Rectifier output 'ON'

viii) Motor zero speed

ix) Rectifier breaker trip

Above indications may be provided as a part of the operator control panel, i.e., door mounted keypad or through hardwired indicating lamps/LEDS.

Potential free contacts of items i-iv shall be wired separately for remote indications in PLC/DDCMIS system.

21.00.00 **METERING**

Digital display of the following parameters shall be as a part of the Operator Control Panel, selected by the operator.

i) Input AC voltage

ii) Input AC frequency

iii) Input AC current

iv) Output voltage

v) Output current VFD / Bypass

vi) Output frequency

vii) Motor thermal state

viii) Drive thermal state

ix) Motor speed

x) Motor energy meter

xi) DC Link voltage

xii) Hour Run

Necessary transducer shall be provided with 4-20mA output for indicating motor speed and motor current in PLC/DDCMIS unless otherwise specified for other parameters.

22.00.00 **AUDIO-VISUAL ANNUNCIATIONS**

i) The system shall incorporate audio-visual annunciations for protection, for various fault conditions, for the Drive motor, Supply cables, DC Reactor and the Converter, output transformer etc.

ii) Alarms shall also be included for the failure of various auxiliaries together with identifications of the failing unit, loss of cooling system, various protections devices provided for converter transformer etc.

iii) Audio-visual window annunciations shall be provided on the front of the panel. All annunciations as required for normal and satisfactorily operation of the drive system shall be included as per vendor standards. These annunciations can be part of operator console panel or separately mounted type.

iv) Vendor shall include audio-visual alarm as required for normal operations and maintenance of the system but not limited to the following :

1. Rectifier fuse failure
2. Main AC failure
3. Inverter fuse failure
4. Inverter overload
5. Inverter high temperature
6. Cooling system failure
7. Motor failed to start
8. Transformer failure
9. Battery monitoring healthiness
10. Communication and measurement system unhealthy
11. Motor temperature high
12. Harmonic filters monitoring

Common potential free contacts shall be provided for above annunciations and these shall be wired up to terminal block for remote alarm and monitoring.

23.00.00 FAULT DIAGNOSTIC

Fault diagnostic shall be built into the system to supervise the operation and failure of the system. The information regarding failure of any of the system including shut down of the system shall be available for a period of minimum 4 days (96 hours) after a shut down even though no supply would be available to the system. The system may be totally de-energized for maintenance or otherwise. It shall be possible to retrieve the record of events prior to tripping of the system or de-energisation. Auxiliary supply to the system components or to the electronics (firmware) for the diagnostics / display shall be taken care by the manufacturer for this purpose.

24.00.00 EXTERNAL POWER SUPPLY FOR AUXILIARY AND CONTROL CIRCUIT

Auxiliary power supply for devices external to VFD module, space heater supply for Motor, VFD panel space heater, auxiliary power supply for transformers, cubicle 11W CFL lamps etc. shall operate on 240 volts single phase AC provided by purchaser.

All control circuit shall operate at maximum voltage of 240V AC.

Vendor shall include supply of all control transformers, protective devices, required accessories etc. and any other control supply voltage as required for the system shall be derived from the power supply made available by other.

25.00.00 RELIABILITY FEATURES

The expected lifetime of the drive system shall be 25 years. The system including all individual components forming part of the system shall have a minimum MTBF of 4 years.

26.00.00 **MAINTENANCE FEATURES**

The controller design shall incorporate the following maintenance features :

- Modular construction
- All components shall be easily accessible

Standard diagnostics to aid maintenance personnel. These shall include LED or alphanumeric displays, test or measurement points.

27.00.00 **PAINTING**

27.01.00 All metal surfaces shall be thoroughly cleaned and de-greased to remove mill scale, rust, grease and dirt. Fabricated structures shall be pickled and then rinsed to remove any trace of acid. The under-surface shall be prepared by applying a coat of phosphate paint and a coat of yellow zinc chromate primer. The under-surface shall be made free from all imperfections before undertaking the finishing coat.

27.02.00 After preparation of the under surface, the panel shall be provided with epoxy based powder coating. Panel finish shall be free from imperfections like pinholes, orange peels, runoff painted.

27.03.00 All unpainted steel parts shall be zinc passivated, cadmium plated or suitably treated to prevent rust and corrosion. If these parts are moving elements, then these shall be greased.

27.04.00 For paint shade of finish coat, refer Section-X of Volume – IIA: Lead Specification.

28.00.00 **INSPECTION, TESTING AND ACCEPTANCE**

28.01.00 During fabrication, the drive shall be subject to inspection by owner, or by an agency authorized by the owner, to assess the progress of work, as well as to ascertain that only quality raw material is used. The manufacturer shall furnish all necessary information concerning the supply to owner's inspectors.

28.02.00 All tests shall be carried out at the manufacturer's works under his care and expense. The tests shall be witnessed by an inspector of the owner or an agency authorized by the owner. Prior notice of minimum of 4 weeks shall be given to the inspector for witnessing the test.

28.03.00 The routine test shall be conducted on all the drive system. However type test shall be performed on one system of each rating and type unless otherwise agreed between purchaser and manufacturer. For the purpose of testing, drive system shall include input/output transformer (where applicable), switchgears, converter, filters etc.

28.04.00 The routine and type tests to be performed on the drive system shall be as follows :

Routine Tests

a. Visual Inspection

It involves checking of the various equipments/components fault diagnostic unit, wiring, terminals, earthing ratings etc, in line with the approved drawings and visual inspection shall not be limited to the following;

i) Dimensions and door layout Vis-à-vis the approved drawings

ii) Degree of protection of cubicles

iii) Simulation facility of control signals for testing purposes

iv) Memory function of fault diagnostic

v) Voltage/Current rating power semiconductor elements

vi) Cable termination size and number of terminals, cable-supporting etc.

vii) Accessibility of components

viii) External signals and indication/alarm signals on converter

ix) Earthing of cubicles and cubicle doors

b. Insulation Test

c. Light load and functional test

d. Load characteristics test

e. Load duty test

f. Checking of Auxiliary devices

g. Checking the properties of the control equipment

h. Checking the protective devices

i. Checking of control and functional requirements

j. High voltage test

k. Shaft current/bearing insulation

l. Automatic restart/re-acceleration

Type Tests

a. Allowable full load current versus speed

b. Efficiency

c. Temperature rise

d. EM Immunity

e. EM Emission

f. Current sharing

g. Voltage division

h. Line side current distortion content
i. Power factor

j. Audible noise

k. Torque pulsation

l. Motor vibration

m. Dynamic performance

n. Current limit and current loop test

o. Speed loop test capability to ride through voltage less than 80%

p. Test capability to restart the system and resynchronize converter onto running motor after a voltage interruption

Type test certificate from independent testing agency for similar equipment can be accepted if it is carried out within 5 years from the date of inspection.

29.00.00 **DRAWINGS, DATA & MANUALS**

29.01.00 Drawings, Data & Manuals shall be submitted in triplicate with the bid and in quantities and procedures as specified in General Conditions of Contract and/or elsewhere in the specification for approval and subsequent distribution after the issue of 'Letter of Intent'.

29.02.00 **To be submitted with the bid** :-

a. General arrangement drawings showing outline dimensions, cable entry openings, fixing/foundation details, weights and door openings.

b. Bill of materials

d. Type test reports

f. General Technical Particulars

29.03.00 **To be submitted for Owner / Purchaser's Approval and Distribution**

All relevant drawings and data pertaining to the equipment like GTP, GA drawing, foundation plan, BOM, control & schematics, QAP, etc. shall be submitted by the Bidder for approval of Owner/Owner's consultant. Also refer clause no. 1.19.02(u) of Section-I of Volume – V-A: Technical Specifications for Electrical Equipment & Accessories.

PROJECT: 5 x 800 MW TSGENCO YADADRI TPS
ELECTRICAL SCOPE BETWEEN BHEL AND VENDOR

PACKAGE: STP

S.NO	DETAILS	SCOPE SUPPLY	SCOPE E&C	REMARKS
1	415V MCC	BHEL	BHEL	1. 415 V AC (3 Phase, 3 Wire) supply to motors, 415 V AC (3 Phase, 4 Wire) supply to other equipment etc. shall be provided by BHEL based on load data provided by vendor at contract stage for the equipment supplied by vendor as part of contract. 2. Any other voltage level (AC/DC) required will be derived by the vendor.
2	Local Push Button Station (for motors)	BHEL	BHEL	Located near the motor.
3	Power cables, control cables and screened control cables for a) both end equipment in BHEL's scope b) both end equipment in vendor's scope c) one end equipment in vendor's scope	BHEL BHEL BHEL	BHEL Vendor BHEL	1. For 3.b) & c): Sizes of cables required shall be informed by vendor at contract stage (based on inputs provided by BHEL) in the form of cable listing. Finalisation of cable sizes shall be done by BHEL. Vendor shall provide lugs & glands accordingly in his scope. 2. Termination at BHEL equipment terminals by BHEL. 3. Termination at Vendor equipment terminals by Vendor.
4	Junction box for control & instrumentation cable	Vendor	Vendor	Refer C & I portion of specification for philosophy of using junction boxes
5	Any special type of cable like compensating, co-axial, prefab, MICC, fibre optical etc.	Vendor	Vendor	Refer C&I portion of specification for scope of fibre Optical cables if used between PLC & DCS.
6	a) Cable trays, accessories & cable trays supporting system b) 100/ 50 mm cable trays/ Conduits/ Galvanised steel cable troughs for local cabling	BHEL Vendor	BHEL Vendor	Local cabling from nearby main route cable tray (BHEL scope) to equipment terminal (vendor's scope) shall be through 100/ 50 mm. cable trays/ conduits/ Galvanised steel cable troughs, which shall be supplied by vendor.

7	Cable glands ,lugs and bimetallic strip for equipment supplied by Vendor	Vendor	Vendor	1. Double compression Ni-Cr plated brass cable glands 2. Solder less crimping type Aluminium lugs for Aluminium power cables and heavy duty tinned copper lugs for copper power cables 3. Solder less crimping type heavy duty copper lugs for control cables.
8	Conduit and conduit accessories for cabling between equipments supplied by vendor	Vendor	Vendor	Conduits shall be medium duty, hot dip galvanised cold rolled mild steel rigid conduit as per IS: 9537.
9	Lighting	BHEL	BHEL	
10	Equipment grounding & lightning protection	BHEL	BHEL	
11	Below grade grounding	BHEL	BHEL	
12	LT Motors with base plate and foundation hardware	Vendor	Vendor	Makes shall be subject to customer/ BHEL approval at contract stage. All motors shall be 3 Phase only.
13	Mandatory spares	Vendor	-	Vendor to quote as per specification.
14	Recommended O & M spares	Vendor	-	Not applicable for this project.
15	Any other equipment/material/service required for completeness of system but not specified above (to ensure trouble free and efficient operation of the system).	Vendor	Vendor	
16	a) Input cable schedules (Control & Screened Control Cables) b) Cable interconnection details for above c) Cable block diagram	Vendor Vendor Vendor	- - -	Cable listing for Control and Instrumentation Cable (excluding power cables) in enclosed excel format shall be submitted by vendor during detailed engineering stage.
17	Electrical Equipment , above ground earthing & cable tray layout drawings	Vendor	-	For ensuring cabling requirements are met, vendor shall furnish Electrical equipment layout & cable tray layout drawings (both in print form as well as in AUTOCAD) of the complete plant (including electrical area) indicating location and identification of all equipment requiring cabling, and shall incorporate cable trays routing details marked on the drawing as per PEM interface comments. Cabling arrangement of the same (wherever overhead cable trays, trenches, cable ducts, conduits etc.) shall be decided during contract stage. Electrical equipment layout & cable tray layout drawing shall be subjected to BHEL/ customer approval without any commercial implications to BHEL.
18	Electrical Equipment GA drawing	Vendor	-	For necessary interface review.

19	Uninterrupted Power supply	Vendor	Vendor	415 V AC (3 Phase, 4 Wire) supply to UPS shall be provided by BHEL based on load data provided by vendor at contract stage for the equipment supplied by vendor as part of contract. Further cabling to battery racks, UPS to ACDB, ACDB to field equipment cabling by vendor.
20	PLC System	Vendor	Vendor	PLC power from ACDB to PLC & signal cabling to field equipment cabling by vendor. OFC cabling (if applicable as per specification) shall be by vendor. Electronic earthing cables upto nearest earth pit shall be by vendor.
21	Electric Operated Hoist with isolating switch	Vendor	Vendor	BHEL will provide one number 415 V(3ph, 4W) supply feeder only up to isolating switches for crane hoist. Any other voltage level (AC/DC) required will be derived by the vendor. Motor starter shall be part of crane control panel. Flexible Power cables(festoon cable)/ shrouded DSL from isolator to hoist & upto motor shall be supplied by vendor . Earthing arrangement shall be part of hoist cable. Input Power Cable from MCC supply feeder to isolating switch shall be in BHEL scope.

NOTES

1. Make of all electrical equipments/items supplied shall be reputed make & shall be subject to approval of BHEL/customer after award of contract.
2. All QPs shall be subject to approval of BHEL/customer after award of contract without any commercial implication.
3. In case the requirement of Junction Box arises on account of Power Cable size mis-match due to vendor engineering at later stage, vendor shall supply the Junction Box for suitable termination.
4. Vendor shall indicate location of Electronic Earth pit in their Civil assignment drawing.

LOAD TITLE	RATING (KW / A)		FULL LOAD CURRENT FLC(A)	UNIT (U)/STN. (S)	Nos.		VOLTAGE CODE*	FEEDER CODE*	EMER. LOAD (Y)	CONT.(C)/ INTT.(I)	STARTING TIME> 5 SEC (Y)	LOCATION (Tag. No.)	RATING & FLC CHECKED FROM MOTOR/VALVE APPROVED DATASHEET (Y/N)	BOARD NO.	CABLE		BLOCK CABLE DRG. No.	CONTROL CODE	REMARKS	LOAD No.	KKS NO.
	NAME PALTE	MAX. CONT. DEMAND (MCR)			RUNNING	STANDBY									SIZE CODE	Nos					
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
NOTES: 1. COLUMN 1 TO 14 & 20 SHALL BE FILLED BY THE REQUISITIONER (ORIGINATING AGENCY); REMAINING COLUMNS ARE TO BE FILLED UP BY PEM (ELECTRICAL)																					
2. ABBREVIATTIONS : * VOLTAGE CODE (7):- (AC) A=11 KV, B=6.6.KV, C= 3.3 KV, D=415 V, E = 240 V (1 PH), F = 110 V (DC) : G =220V, H = 110 V, J = 48 V, K = +24V, L= -24V																					
: **FEEDER CODE (8) :- U = UNIDIRECTIONAL STARTER, B = BIDIRECTIONAL STARTER, S = SUPPLY FEEDER, D = SUPPLY FEEDER (CONTACTOR CONTROLLED)																					
BHEL	LOAD DATA (ELECTRICAL)		JOB NO.										ORIGINATING AGENCY				PEM (ELECTRICAL)				
			PROJECT TITLE										NAME				DATA FILLED UP ON				
			SYSTEM / S										SIGN.				DATA ENTERED ON				
			DEPTT. /SECTION										SHEET 1/2		REV. R0		DE'S SIGN. & DATE				

STANDARD QUALITY PLAN

PEM :: C&I

STANDARD QUALITY PLAN FOR LOCAL CONTROL PANEL

STD QUALITY PLAN NO.: **PE-QP-999-145-I056**
VOLUME
SECTION
REV. NO. 01 DATE: 18-02-2020
SHEET 1 OF 7

Sl. No.	Component / operation	Characteristics Checked	* Category	Type/Method of Check	Extent of Check	Reference documents	Acceptance Norms	Format of Records	Agency $ P	Agency $ W	Agency $ V	Remarks
	INCOMING											
1.0	Sheet Steel (CRCA & HR)	1. Chemical Composition	MA	Chemical analysis	Sample	IS:1079Relevant IS:513 standard	Relevant IS:1079 IS:513standard	Test Certificate	3	---	2	
		2. Bend Test	CR	Mech. test	Sample	Relevant IS:1079 IS:513 standard	Relevant IS:1079 IS:513 standard	Log Book	2	---	---	
		3. Surface finish	MA	Visual	100%	Factory Standard / Sample	Factory Standard / Sample	Log Book	2	---	---	
		4. Waviness	MA	Visual	100%	Factory Standard	No Waviness	Log Book	2	---	---	
		5. Thickness	MA	Measurement	100%	BHEL Spec.	BHEL Spec.	Log Book	2	---	---	
		6. Mill marking	MA	Visual	100%	Factory Standard	Factory Standard	Log Book	2	---	1	
2.0	Flats / Angles / Channels	1. Dimensions	MA	Measurement	Sample	Relevant standard	Relevant standard	Log Book	2	---	---	
		2. Surface Defects	MA	Visual	100%	Factory Standard / Sample	Factory Standard / Sample	Log Book	2	---	---	
		3. Straightness	MA	Measurement	100%	Factory Std.	Factory Std.	Log Book	2	---	---	
		4. Mill marking	MA	Visual	100%	Relevant IS:2062 standard	Relevant IS:2062 standard	Log Book	2	---	1	
3.0	Cables / Wires	1. Visual / Surface defects	MA	Visual	100%	BHEL Spec. and IS:1554 or IS:694 standard	BHEL Spec. IS:1554 or IS:694 standard	Log Book	2	---	---	
		2. IR and HV	MA	Electrical	100%	BHEL Spec. IS:1554 or IS:694 standard	BHEL Spec. IS:1554 or IS:694 standard	Log Book	2	---	---	

LEGEND: * CR - Critical characteristics; MA - Major characteristics; MI - Minor characteristics

$ P - Agency Performing the Test. W - Agency Witnessing the Test. V - Agency Verifying the Test.

1 - BHEL 2 - Vendor 3 - Sub-vendor

PEM :: C&I

STANDARD QUALITY PLAN FOR LOCAL CONTROL PANEL

STD QUALITY PLAN NO.: **PE-QP-999-145-I056**
VOLUME IIB
SECTION D
REV. NO. 01 DATE: 18-02-2020
SHEET 2 OF 7

Sl. No.	Component / operation	Characteristics Checked	* Category	Type/Method of Check	Extent of Check	Reference documents	Acceptance Norms	Format of Records	Agency $ P	Agency $ W	Agency $ V	Remarks
		3. Conductor a) Resistance b) Size c) Sheet colour	MA MA MA	Electrical Measurement Visual	100% 100% 100%	BHEL Spec. IS:1554 or IS:694 standard	BHEL Spec. IS:1554 or IS:694 standard	Log Book	2	---	---	
		4. Type / Routine Test Certificates	MA	Verification	100%	BHEL Spec. IS:1554 or IS:694 standard	BHEL Spec. and IS:1554Relevantor IS:694 standard	Log Book	3	---	2	
4.0	Electrical Components like Annunciator Transformers Lamps Switches PBs Contactors Relays Timers Space Heaters Thermostat Indicating meters etc.	1. Verification at make and Type	CR	Visual	Sample	BHEL Spec. and BOM	BHEL Spec. and BOM	Log Book	2	---	---	
		2. Verification of Test Certificates	CR	Scrutiny of Type / Routine T.Cs.	100%	RelevantIS standard	Relevant IS standard	Log Book	2	---	---	
		3. Operation / Functional check	CR	Electrical	Sample+ 100%@	Relevant standard Relevant Indian & Catalogue Std & Catalogue	standard Relevant Indian &StdCatalogue&Catalogue	Log Book	2	---	---	+ for relay & contactors only @ for all components except relays & contactors.
		4. I.R.	MA	Electrical	100%	Relevant standard Relevant Indian &StdCatalogue&Catalogue	RelevantstandardIndian Std & Catalogue & Catalogue	Log Book	2	---	---	
		5. H.V.	MA	Electrical	100%	standard Relevant Indian &StdCatalogue&Catalogue	RelevantstandardIndian Std & Catalogue & Catalogue	Log Book	2	---	---	
		6. Calibration	MA	Electrical	100%	Relevant standard Relevant Indian &StdCatalogue&Catalogue	RelevantstandardIndian Std & Catalogue & Catalogue	Log Book	2	---	1	
		7. Pick up / Drop off Voltage	MA	Electrical	100%	standard Relevant Indian Std & Catalogue & Catalogue	RelevantstandardIndian Std & Catalogue & Catalogue	Log Book	2	---	---	

LEGEND: * CR - Critical characteristics
MA - Major characteristics
MI - Minor characteristics

$ P - Agency Performing the Test.
W - Agency Witnessing the Test.
V - Agency Verifying the Test.

1 - BHEL
2 - Vendor
3 - Sub-vendor

PEM :: C&I

STANDARD QUALITY PLAN FOR LOCAL CONTROL PANEL

STD QUALITY PLAN NO.: **PE-QP-999-145-I056**
VOLUME IIB
SECTION D
REV. NO. 01 DATE: 18-02-2020
SHEET 3 OF 7

Sl. No.	Component / operation	Characteristics Checked	* Category	Type/Method of Check	Extent of Check	Reference documents	Acceptance Norms	Format of Records	Agency $ P	Agency $ W	Agency $ V	Remarks
5.0	Misc. Components like Gaskets, Terminal Blocks etc.	1. Verification of Type / Make	MA	Visual	Sample	BHEL Spec. & Mfrs. Catalogue	BHEL Spec. & Mfrs. Catalogue	Log Book	2	---	---	
		2. Surface defects	MA	Visual	Sample	BHEL Spec. & Mfrs. Catalogue	BHEL Spec. & Mfrs. Catalogue	Log Book	2	---	---	
		3. IR / HV on Terminal Blocks	MA	Electrical	Sample	BHEL Spec. & Mfrs. Catalogue	BHEL Spec. & Mfrs. Catalogue	Log Book	2	---	---	
6.0	**IN PROCESS** Blanking / Bending / Forming	1. Dimensions	MI	Measurement	100%	Approved Mfr. drgs.	Approved Mfr. drgs.	Log Book	2	---	---	
		2. Surface defects after bending	MA	Visual	100%	Factory Standard	Factory Standard	Log Book	2	---	---	
7.0	Nibbling / Punching	1. Cutout Sizes	MI	Measurement	100%	Approved Mfr. drgs.	Approved Mfr. drgs.	Log Book	2	---	---	
		2. Deburring	MA	Visual	100%	Approved Mfr. drgs.	Approved Mfr. drgs.	Log Book	2	---	---	
8.0	**ASSEMBLY** Frame Assembly & Sheet fixing	1. Dimensions	MA	Measurement	100%	Approved drg. / Mfr. Standards	Approved drg. / Mfr. Standards	Log Book	2	---	2	
		2. Alignment	MA	Measurement	100%	Approved drg. / Mfr. Standards	Approved drg. / Mfr. Standards	Log Book	2	---	2	
		3. Welding Quality	MA	Visual	100%	Approved drg. / Mfr. Standards	Approved drg. / Mfr. Standards	Log Book	2	---	2	
		4. Surface defects	MA	Visual	100%	Approved drg. / Mfr. Standards	Approved drg. / Mfr. Standards	Log Book	2	---	2	

LEGEND: * CR - Critical characteristics
MA - Major characteristics
MI - Minor characteristics

$ P - Agency Performing the Test.
W - Agency Witnessing the Test.
V - Agency Verifying the Test.

1 - BHEL
2 - Vendor
3 - Sub-vendor

PEM :: C&I

STANDARD QUALITY PLAN FOR LOCAL CONTROL PANEL

STD QUALITY PLAN NO.:	**PE-QP-999-145-I056**
VOLUME	IIB
SECTION	D
REV. NO.	01 DATE: 18-02-2020
SHEET	4 OF 7

Sl. No.	Component / operation	Characteristics Checked	* Category	Type/Method of Check	Extent of Check	Reference documents	Acceptance Norms	Format of Records	Agency $ P	Agency $ W	Agency $ V	Remarks
9.0	Pre-treatment and Painting	1. Pretreatment Process	MA	Visual	100%	Factory Standard & Relevant IS:6005 standard	Factory Standard & Relevant IS:6005 standard	Log Book	2	---	1	
		2. Process parameters like bath temp. concentration etc.	MA	Measurement	Periodic	Factory Standard & Relevant IS:6005 standard	Factory Standard & Relevant IS:6005 standard	Log Book	2	---	1	
		3. Dipping / Removal Time	MA	Measurement	100%	Factory Standard & IS: 6005 Relevant standard	Factory Standard & Relevant IS:6005 standard	Log Book	2	---	1	
		4. Surface quality after every dip	MA	Visual	100%	Factory Standard & IS: 6005 Relevant standard	Factory Standard & Relevant IS:6005 standard	Log Book	2	---	1	
		5. Primer after phosphating	MA	Visual, Thickness	100%	Factory Standard & Relevant IS:6005 standard	Factory Standard & IS: 6005 Relevant standard	Log Book	2	---	1	
		6. Putty Application & Rubbing after primer	MA	Visual	100%	Factory Standard & Relevant IS:6005 standard	Factory Standard & Relevant IS:6005 standard	Log Book	2	---	1	
		7. Paint first coat	MA	Visual, Thickness	100%	Factory Standard & Relevant IS:6005 standard	Factory Standard & Relevant IS:6005 standard	Log Book	2	---	1	
		8. Putty Application and Rubbing after first coat of paint	MA	Visual	100%	Factory Standard & Relevant IS:6005 standard	Factory Standard & IS: 6005 Relevant standard	Log Book	2	---	1	
		9. Paint second coat	MA	Visual, Thickness, Scratch test Colour adhesion	100%	Factory Standard & Relevant IS:6005 standard	Factory Standard & Relevant IS:6005 standard	Log Book	2	---	1	

LEGEND: * CR - Critical characteristics; MA - Major characteristics; MI - Minor characteristics

$ P - Agency Performing the Test. W - Agency Witnessing the Test. V - Agency Verifying the Test.

1 . BHEL 2 . Vendor 3 . Sub-vendor

PEM :: C&I

STANDARD QUALITY PLAN FOR LOCAL CONTROL PANEL

STD QUALITY PLAN NO.: **PE-QP-999-145-I056**
VOLUME IIB
SECTION D
REV. NO. 01 DATE: 18-02-2020
SHEET 5 OF 7

Sl. No.	Component / operation	Characteristics Checked	* Category	Type/Method of Check	Extent of Check	Reference documents	Acceptance Norms	Format of Records	Agency $ P	Agency $ W	Agency $ V	Remarks
10.	Panel Wiring	1. Wiring Layout	MA	Visual	100%	Approved drgs. & Specs.	Approved drgs. & Specs.	Log Book	2	---	---	
		2. Wiring Termination (Crimped Lugs)	MA	Visual	100%	Approved drgs. & Specs.	Approved drgs. & Specs.	Log Book	2	---	---	
		3. Ferrule numbers	MA	Visual	100%	Approved drgs. & Specs.	Approved drgs. & Specs.	Log Book	2	---	---	
		4. Colour of wiring	MA	Visual	100%	Approved drgs. & Specs.	Approved drgs. & Specs.	Log Book	2	---	1	
		5. Size of Conductor	MA	Measurement	100%	Approved drgs. & Specs.	Approved drgs. & Specs.	Log Book	2	---	1	
11.	Component Mounting	1. Correct components	MA	Visual	100%	Approved drgs., Specs. & BOM	Approved drgs., Specs. & BOM	Log Book	2	---	---	
		2. Fixing	MA	Visual	100%	Approved drgs., Specs. & BOM	Approved drgs., Specs. & BOM	Log Book	2	---	---	
	FINAL											
12.	Final Inspection	1. Workmanship	MA	Visual	100%	Factory Standard	Factory Standard	Inspection Report	2	1	1	At Random by BHEL, based on 100 % internal test reports by Mfr.
		2. Component layout (neatness, accessibility & safety) Mounting / Proper fixing of all components	MA	Visual	100%	BHEL approved drg. / Spec.	BHEL approved drg. / Spec.	Inspection Report	2	1	1	
		3. Components identification Marking / Name plates	MA	Visual	100%	BHEL approved drg. / Spec.	BHEL approved drg. / Spec.	Inspection Report	2	1	1	

LEGEND: * CR - Critical characteristics; MA - Major characteristics; MI - Minor characteristics

$ P - Agency Performing the Test. W - Agency Witnessing the Test. V - Agency Verifying the Test.

1 - BHEL 2 - Vendor 3 - Sub-vendor

PEM :: C&I

STANDARD QUALITY PLAN FOR LOCAL CONTROL PANEL

STD QUALITY PLAN NO.: **PE-QP-999-145-I056**
VOLUME IIB
SECTION D
REV. NO. 01 DATE: 18-02-2020
SHEET 6 OF 7

Sl. No.	Component / operation	Characteristics Checked	* Category	Type/Method of Check	Extent of Check	Reference documents	Acceptance Norms	Format of Records	Agency $ P	Agency $ W	Agency $ V	Remarks
		5. Dimensions	MA	Measurement	100%	BHEL approved drg. / Spec., BOM	BHEL approved drg. / Spec., BOM	Inspection Report	2	1	1	At Random by BHEL, based on 100 % internal test reports by Mfr.
		6. Door functioning	MA	Functional	100%	BHEL approved drg. / Spec.	BHEL approved drg. / Spec.	Inspection Report	2	1	1	
		7. Paint Shade	CR	Visual	100%	BHEL approved drg. / Spec.	BHEL approved drg. / Spec.	Inspection Report	2	1	1	
		8. Paint Thickness	CR	Measurement	100%	BHEL approved drg. / Spec.	BHEL approved drg. / Spec.	Inspection Report	2	1	1	
		9. Workmanship of Gaskets	MA	Visual	100%	Factory Standard	Factory Standard	Inspection Report	2	1	1	
		10. Wiring Layout	MA	Visual	100%	BHEL approved drg.	BHEL approved drg.	Inspection Report	2	1	1	
		11. Wire Termination	MA	Pulling manually	Sample	-----	Firm termination	Inspection Report	2	1	1	
		12. Continuity	MA	Electrical	100%	-----	Continuity OK	Inspection Report	2	1	1	

LEGEND: * CR - Critical characteristics; MA - Major characteristics; MI - Minor characteristics
$ P - Agency Performing the Test.; W - Agency Witnessing the Test.; V - Agency Verifying the Test.
1 - BHEL; 2 - Vendor; 3 - Sub-vendor

STANDARD CHECK LIST FOR C&I INSTRUMENTS

CHECK LIST FOR TRANSMITTER(PIT, DPIT, FIT, LIT, TIT, VIT)

Sl. No.	Test / Checks	Quantum of check	Reference Doc. / Acceptance Norms	Agency **			Remarks
				M	C	B	
1	CHECKS FOR			P	W	V	
	VISUAL.						
	MODEL/TAG No						
2	PROCESS CONNECTION	SEE NOTE-1		P	W	V	
3	ACCURACY	BELOW		P	W	V	
4	REPEATABILITY			P	W	V	
5	HYSTERESIS			P	W	V	
6	EFFECT OF TEMP VARIATION ON ACCURACY		APPROVED SPEC./	P	W	V	
7	SPAN / ZERO ADJUSTMENT		DATA SHEETS	P	W	V	
8	EFFECT OF SUPPLY VOLTAGE VARIATION	ONE / TYPE		P	W	V	
9	EFFECT OF LOADING (500 OHM METERS)			P	W	V	
10	HIGH PRESSURE TEST	SEE NOTE-1 BELOW		P	W	V	
11	BURN-IN TEST	ONE / TYPE		P	W	V	
12	DEGREE OF PROTECTION			P	W	V	
13	ACCESSORIES AS APPLICABLE	SEE NOTE-1 BELOW		V	V	V	

Legend :

** M = Manufacturer / Sub-contractor, C = Contractor / Nominated Inspecting Agency, B = BHEL, P = Perform, W = Witness, V = Verification

STANDARD CHECK LIST FOR C&I INSTRUMENTS

CHECK LIST FOR PRESSURE & DP GAUGE

Sl. No.	Test / Checks	Quantum of check	Reference Doc. / Acceptance Norms	Agency **			Remarks
				M	C	B	
1	CHECK FOR	SEE NOTE-1 BELOW	APPROVED SPEC./ DATA SHEETS	P	W	V	
	SENSOR TYPE						
	DIAL SIZE						
	MODEL NO/TAG NO						
	RANGE/SCALE						
	SWITCH CONTACT RATING & NOS.						
	END CONNECTION						
2	CALIBRATION			P	W	V	
	ACCURACY						
	REPEATABILITY						
	SET POINT ADJUSTMENT						
3	OVER PRESSURE & LEAK TEST			P	W	V	
4	OPERATION OF PRESSURE. RELIEF DEVICE	ONE		P	W	V	
5	REVIEW OF TC FOR	FOR LOT		V	V	V	
	MATERIALS OF SENSOR						
	MOVEMENT						
	PROCESS CONNECTION						
	HOUSING						
6	REVIEW OF TC FOR DEGREE OF PROTECTION	TYPE TEST		V	V	V	
7	ACCESSORIES AS APPLICABLE	SEE NOTE-1 BELOW		V	V	V	

Legend :

** M = Manufacturer / Sub-contractor, C = Contractor / Nominated Inspecting Agency, B = BHEL, P = Perform, W = Witness, V = Verification

STANDARD CHECK LIST FOR C&I INSTRUMENTS

CHECK LIST FOR LEVEL GAUGE

Sl. No.	Test / Checks	Quantum of check	Reference Doc. / Acceptance Norms	Agency **			Remarks
				M	C	B	
1	CHECK FOR	SEE NOTE-1 BELOW	APPROVED SPEC./ DATA SHEETS / DRWGS	P	W	V	
	TYPE						
	MODEL/ TAG NO.						
	DAIL SIZE						
	RANGE/SCALE						
	END CONNECTION						
2	DIMENSIONS, PROCESS CONNECTION			P	W	V	
3	ACCURACY			P	W	V	
4	MATERIAL TC FOR	ONE / LOT		P	V	V	
	BODY ISO.						
	VALVE						
	GAUGE GLASS						
5	HYD. TEST	SEE NOTE-1 BELOW		P	W	V	
6	ACCESSORIES AS APPLICABLE			P	W	V	

Legend :

** M = Manufacturer / Sub-contractor, C = Contractor / Nominated Inspecting Agency, B = BHEL, P = Perform, W = Witness, V = Verification

STANDARD CHECK LIST FOR C&I INSTRUMENTS

CHECK LIST FOR ANNUNCIATORS

Sl. No.	Test / Checks	Quantum of check	Reference Doc. / Acceptance Norms	Agency **			Remarks
				M	C	B	
1	CHECK FOR	SEE NOTE-1 BELOW	APPROVED SPEC./ DATA SHEETS	P	W	V	
	TYPE/ MODEL						
	DIMENSIONS OF HARDWARE						
	MODULARITY						
	SEQUENCE						
	FACIA DETAILS						
2	FUNCTIONAL TEST	100%		P	W	V	
3	IMMUNE TO STEP VARIATIONS IN THE POWER SUPPLY	SEE NOTE-1 BELOW		P	W	V	
4	DEGREE OF PROTECTION FOR ENCLOSURE	TYPE TEST		P	W	V	
5	I/R CHECK	SEE NOTE-1 BELOW		P	W	V	
6	RESPONSE			P	W	V	

Legend :

** M = Manufacturer / Sub-contractor, C = Contractor / Nominated Inspecting Agency, B = BHEL, P = Perform, W = Witness, V = Verification

Note :

1. Quantum of check shall be as below :
   100 % - By Manufacturer
2. Manufacturer to maintain calibrated instrument having better accuracy than the item under test. Inspecting engineer shall check the same.
3. Manufacturer to carry out ROUTINE TEST on 100 %.
4. Contractor to provide compliance certificate for tests/checks verified by contractor and submit the same along with test certificates to be verified by BHEL.

INSTRUMENT SCHEDULE FOR WATER CHEMISTRY PACAKAGES- ANNEXURE - VI																									
Project : TSGENCO 5X 800 MW YADADRI								OPER	DESIGN	OPER	DESIGN	OPER	DESIGN										MAKE	MODEL	REMARKS
PID Drg. No & Name:							MEDIUM	PRESS	PRESS	TEMP	TEMP	Flow	Flow	Min Inst Range	Max Inst Range	Max Inst Range Unit	SETPOINT	TYPE	PROCESS CONNECTION-INST	PROCESS CONNECTION-PIPING	ELECTRICAL CONNECTION			
S.No	Tag No.	Description	Legend/TYPE	Qty	Scope	Drg. Reference		Kg/cm2	Kg/cm2	DEGC	DEGC	m3/hr	m3/hr				ALARM								

CABLE SCHEDULE FORMAT

UNITCABLENO	FROM	TO	PURPOSE	CABLE SCOPE (BHEL PEM/ VENDOR)	REMARKS	CABLESIZE	PATHCABLENO	TENTATIVE CABLE LENGTH

CABLE SIZES FINALISED FOR THE PROJECT

1.1 kV, XLPE INSULATED POWER CABLES		1.1 kV, CONTROL CABLES	SCREENED CONTROL CABLES		FS CABLE EPR INSULATED Cu CABLE	
ARMOURED, AL CONDUCTOR	ARMOURED, CU CONDUCTOR	COPPER CONDUCTOR HRPVC INSULATED ARMOURED CONTROL CABLES	TYPE F (INDIVIDUAL & OVERALL SCREENED CABLES)	TYPE G (OVERALL SCREENED CABLES)	POWER	CONTROL
1C-400	2C-2.5	5C-2.5	2P	2P	1C-400	3C-2.5
1C-630	3C-2.5	7C-2.5	4P	4P	2C-95	5C-2.5
2C-10		12C-2.5	8P	8P	3C-240	
2C-25		5C-4	12P	12P		
2C-50			20P			
2C-95						
3C-10						
3C-25						
3C-50						
3C-95						
3C-185						
3C-240						
3.5C-25						
3.5C-50						
3.5C-95						
3.5C-185						
4C-10						

NOTES:

1. 2C-2.5, 3C-2.5 XLPE insulated cables shall be used for both power as well as control cable application.
2. Control cable sizes shall be selected from above as per requirement. All sizes may not be used.

Explanatory notes for filling up cable list for routing through WinPath, the cable routing program (developed by Corporate R&D) being used in PEM.

1. For the purpose of clarity, it may please be noted that the information given in regard to the cables to be routed through WinPath as per the system elaborated below is called "Cable List", while the term "Cable Schedule" applies to the cable list with routing information added after routing has been carried out.
2. The cable list shall be entered as an MS Excel file in the format as per enclosed template EXT_CAB_SCH_FORMAT.XLS. No blank lines, special characters, header, footer, lines, etc. shall be introduced in the file. No changes shall be made in the title line (first line) of the template.
3. The field properties shall be as under:
    a. UNITCABLENO: A/N, up to sixteen (16) characters; each cable shall have its own unique, unduplicated cable number. In case this rule is violated, the cable cannot be taken up for routing.
    b. FROM: A/N, up to sixty (60) characters; the "From" end equipment/ device description and location to be specified here. Information in excess of 60 characters will be truncated after 60 characters.
    c. TO: A/N, up to sixty (60) characters; the "To" end equipment/ device description and location to be specified here. Information in excess of 60 characters will be truncated after 60 characters.
    d. PURPOSE: A/N, up to sixty (60) characters; the purpose (i.e. power cable/ indication/ measurement, etc.) to be specified here. Information in excess of 60 characters will be truncated after 60 characters.
    e. REMARKS: A/N, up to forty (40) characters; Any information pertinent to routing to be specified here (e.g., cable number of the cable redundant to the cable number being entered). Information in excess of 40 characters will be truncated after 40 characters.
    f. CABLESIZE: A/N, 7 characters exactly as per the codes indicated below shall be specified here. The program cannot route cables described in any other way/ format.
    g. PATHCABLENO: Field reserved for utilization by the program. User shall not enter any information here.
4. One list shall be prepared for each system/ equipment (i.e., separate and unique cable lists shall be prepared for each system).
5. The cables shall be described as per the scheme listed below:

A	NN	A	NNN
|	|	|	|
Cable Voltage Code (see B below)	No. of cores (e.g. 01,03,3H, 07)	Cable code (See C below)	Cable size (e.g. 035,185,2.5, 0.5)

(A) SYSTEM VOLTAGE CODES:

(ac) A = 11KV, B = 6.6KV, C = 3.3KV, D = 415V, E = 240V, F = 110V

(dc) G = 220V, H = 110V, J = 48V, K = +24V, L = -24V

(B) CABLE VOLTAGE CODES:

A = 11KV (Power cables)

Explanatory notes for filling up cable list for routing through WinPath, the cable routing program (developed by Corporate R&D) being used in PEM.

B = 6.6KV (Power cables)
C = 3.3KV (Power cables)
D = 1.1KV (LV & DC system power & control cables)
E = 0.6KV (0.5 sq. mm. Control cables)

(C) CABLE CODES

PVC Copper

A = Armoured FRLS	B = Armoured Non-FRLS
C = unarmoured FRLS	D = Unarmoured Non-FRLS

PVC Aluminium

E = Armoured FRLS	F = Armoured Non-FRLS
G = unarmoured FRLS	H = Unarmoured Non-FRLS

XLPE Copper

J = Armoured FRLS	K = Armoured Non-FRLS
L = unarmoured FRLS	M = Unarmoured Non-FRLS

XLPE Aluminium

N = Armoured FRLS	P = Armoured Non-FRLS
Q = unarmoured FRLS	R = Unarmoured Non-FRLS

S = FIRE SURVIVAL CABLES
T = TOUGH RUBBER SHEATH
U = OVERALL SCREENED
V = PAIRED OVERALL SCREENED
W = PAIRED INDIVIDUAL SCREENED
Y = COMPENSATING CABLES
I = PRE-FABRICATED CABLES
Z = JELLY FILLED CABLES

BHARAT HEAVY ELECTRICALS LIMITED,
RANIPET- 632 406

SPECIAL CONDITIONS OF CONTRACT

YADADARI- TPS 5 x 800 MW
DAMERACHERLA

00	03.02.20	A.Kumar ABH	SS	MSM	Fresh issue
Rev. No	**Date**	**Prepared**	**Checked**	**Approved**	**Remarks**

Project Information

	Project Name	5 X 800 MW TSGENCO YADADRI TPS
	Ultimate Customer	TELANGANA STATE POWER GENERATION CORPORATION LIMITED [TSGENCO]
	Location of Plant	Location: At Virlapalem Village, Damaracherla Mandal, Nalgonda District, Telangana State, India. Site is located 7 Kms from NH5. Access by: Nearest Railway Station: 6.5 Km from Damaracherla. Nearest Airport: Vijayawada airport (130 Km) Nearest sea port: Vishakhapatnam Sea Port. Access by road: 30KM from Miryalaguda Latitude: 16° 42'20.40 N. Longitude: 79° 34'41.56 E Elevation above MSL: 85m
	Consignee Address (Ship to)	Construction Manager/ BHEL site office C/o Chief Engineer TSGENCO Yadadri Thermal Power Project- 5 X 800 MW, Veerlapalem Village, Damaracherla Mandal, Nalgonda District, Telangana State
	Mode of Dispatch	By Road / Rail / Sea on Door Delivery and Freight PrePaid Basis.
	Unloading at site	By Vendor
	Storage at site	By Vendor, preferably in a container with lock & key for items like small valves, instruments, panels etc.
	Movement of Material within Site	By Vendor
	Provision of facilities at Site	Construction Power: Construction Power (3 phase AC 415V) shall be provided free of cost within the plant premises. Construction Water: Construction water shall be provided free of cost within the plant premises. Land for Temporary store (open and closed store): Limited area of land within the plant premises as allotted by M/s.TSGENCO shall be provided free of cost, subject to availability. Land for Labour colony: Land for construction of temporary accommodation may be available free of cost, subject to availability. However, all other infrastructure/facilities as per prevailing statutory norms shall be provided by the bidder at his cost.

		All facilities like open area development temp. Illumination, temp roads and drains, securities, fire safety equipment etc. shall be in the scope of bidder at his cost. No tree felling should be done without prior approval of TSGENCO. Establishment of Quality control lab for construction works is to be arranged by the bidder at his cost.
	Inspection Agency (Domestic supplies)	Vendor shall give inspection call in line with approved QAP / Customer Hold Points to Regional BHEL-CQS center / Third Party Inspection Agency (TPIA) (as informed by BHEL) on "BHEL CQS Website"; with a copy of inspection call to BHEL (respective units) for arranging Customer/Third Party participation (wherever applicable), with an advance notice of 15 days for participation in inspection/ Joint inspection on the proposed date. The MDCC shall be issued by customer based on the BHEL-CQS/TPIA report OR Joint inspection report of BHEL CQS/TPIA & Customer (wherever applicable).
	Inspection Agency (Imported supplies)	In case of Imported Supplies advance notice of 30 days for participation in inspection (if applicable, in line with approved QAP / Customer Hold Points) to be given. The Test Certificates & Inspection reports duly accepted by the Foreign Vendor Inspection agency/BHEL/TSGENCO in line with approved QAP/Customer Hold Points shall be submitted to BHEL. The above Inspection reports & Test certificates shall be reviewed by BHEL in line with the Technical Specifications & Approved Data sheets and then sent to customer for their clearance. The customer dispatch clearance (MDCC) will be given to the Foreign Vendor or their representative in India through BHEL after acceptance/clearance of above test certificates by Customer.
	Material Receipt Certificate (MRC)	For Packages wherever E&C is in the scope of Vendor, The vendor shall arrange Material Receipt Certificate from the project site, duly signed by Customer and BHEL-Site after receipt & physical verification of the material at site.
	Packing, Identification & marking	• The supplier shall include and provide for securely protecting and packing the materials so as to avoid loss or damage during handling & transport by air, sea, rail and road. • All packing shall allow for easy removal and

		checking at site. Special precaution shall be taken to prevent rusting of steel and iron parts during transit by sea. Gas seals or other materials shall be adopted by the Contractor for protection against moisture during transit. • The number of each package in a shipment shall be shown in fraction, numerator showing number of the package and the denominator showing total number of packages in a lot / consignment. The packages number shall be generally prepared in the sequence in which they will be required for erection. • Each package delivered under the Contract shall be marked by and at the expense of the supplier and such marking must be distinct and in English language (all previous irrelevant markings being carefully obliterated). Such marking shall show the description and quantity of contents, the name and address of consignee, the gross weight and net weight of the package, the name of the Contractor with a distinctive number of mark sufficient for purposes of identification. All markings shall be carried out with such materials as to ensure quickness of drying, fastness and indelibility. Each equipment or parts of equipment shall, when shipped or railed or otherwise dispatched be tagged with reference to the assembly drawings and corresponding part numbers. Each bale or package shall contain a packing note quoting specifically the name of the Contractor, the number and date of contract and the name of the office placing the contract, nomenclature of the stores and include a schedule of parts for each complete equipment giving the part numbers with reference to the assembly drawing and the quantity of each part, drawings nos. and tag numbers. • Rotor bearings should not be used as a support while packing • Besides wherever necessary, packing shall bear a special marking "TOP","BOTTOM", "DO NOT TURN OVER", "KEEP DRY", "HANDLE WITH CARE" etc. • All packing cases, containers (excluding marine container), packing and other similar materials shall be new. • Notwithstanding anything stated in this clause, the Contractor shall be entirely responsible for loss, damage or depreciation or deterioration to the materials & supplies due to faulty and/or insecure packing.

		• One copy of respective standard manufacturer's erection instruction/operation instruction manual shall be kept in each package/container for immediate reference. • Each and every package box shall be marked with the following, as a minimum: (i). Name and address of Consignee: (ii). Project reference: (iii). Contract No.: (iv). Packing No.: (1/10, 2/10, 3/10 ..... when there are 10 packages for one consignment) (v). Net Weight/Gross Weight: (vi). Port of Loading: (vii). Destination Port: (viii). Packing Mark: [symbols indicating "TOP","BOTTOM", "DO NOT TURN OVER", "KEEP DRY", "HANDLE WITH CARE" etc. (ix). Type of Equipment: "E" (for Equipment supply) "T" (for Tools & Tackles) "S" (for Mandatory Spares) • Two copies of packing list should be kept in case/package No. 1 of each consignment of the goods and four copies in each case (three inside the box and one copy in a special packet at the outer side of the Box).
	Commissioning spares	The commissioning spares shall be properly packed separately in separate box and each spare shall be properly tagged giving details (to match the description given in the packing slip) to facilitate their proper identification. Three copies of packing list is to be kept inside the box and one copy in a special packet at the outer side of the Box.
	Mandatory Spares	The Mandatory spares shall be properly packed separately in separate box indicating Mandatory Spares in bold letters and each spare shall be properly tagged giving details i.e. item number of the equipment in line with the Ultimate Customer Contract & Number per item (to match the description given in the packing slip) to facilitate their proper identification by ultimate customer M/s TSGENCO. Three copies of packing list along with Manufacturing drawing no. Reference, Catalogue reference etc. is to be kept inside the box and one copy in a special packet at the outer side of the Box
	Submission of	As per Technical specification/ Kickoff meeting.

	Final Drawing / Documents along with O&M Manual, Type Test Certificates (if any)	
	"item-rate" items	The quantity indicated in the BOQ / Price bid is approximate only and is liable for variation. The quantity of each item may vary to any extent as per requirement. Payment will be as per actual quantity executed as certified by BHEL Engineer. Contractor shall not be eligible for any compensation on this account.
	Surplus materials	Ownership of any plant and equipment in excess (i.e, surplus material including scrap and commissioning spares) of the requirements for the facilities shall lie with the bidder, upon completion of trial operation or at such earlier time when BHEL and bidder agree that the surplus material / scrap in question are no longer required for the completion of facilities. TSGENCO / BHEL will issue necessary gatepass for taking back the surplus materials / scrap after such agreement.
	Demurrage charges	No demurrage charges shall be payable
	Penalty for Guaranteed power consumption and performance	As per the Technical specification
	HSE guidelines	As per **Annexure-11**
	Warranty	Warranty for water system packages shall be 12 months from the date of handing over of packages to customer.
	Vendor/Sub vendor approval	TSGENCO informed that in view of their previous experience, Chinese vendors to be avoided. Vendor list subject to Customer Approval.

LIST OF MANDATORY SPARES – STP

1.	**Spares for Horizontal Centrifugal Pumps**	
1.1.	Shaft	2 Nos.
1.2.	Shaft Sleeve	4 Nos.
1.3.	Impeller	2 Nos.
1.4.	Impeller locking nut and bolt	8 Nos.
1.5.	Impeller wear ring	8 Nos.
1.6.	Casing wear ring	8 Nos.
1.7.	Oil Seal	8 Nos.
1.8.	Oil Deflector	6 Nos.
1.9.	Oil Ring	6 Nos.
1.10.	Gland Packing	8 Sets
1.11.	Lantern Ring	6 Nos.
1.12.	Mech Seal Assembly	2 Nos.
1.13.	Stationary/Carbon Packing and O" Ring for Mechanical Seal"	6 Sets
1.14.	Oil Level Gauge	6 Nos.
1.15.	Coupling	4 Nos.
1.16.	Rubber Bush for Coupling	4 Nos.
1.17.	O" Rings "	4 Sets
1.18.	Suction Strainers Element	6 Nos.
1.19.	Bearing for Pump Motor	4 Sets
2.	**Spares for Vertical Type Centrifugal Pumps**	
2.1.	Complete Bowl assembly	2 Sets
2.2.	Impeller (s)	2 Sets
2.3.	Shafts	2 Sets
2.4.	Casing wearing (s)	2 Sets
2.5.	Impeller wear ring (s)	2 Sets
2.6.	Shaft Sleeves	4 Sets
2.7.	Shaft Couplings	2 Sets
2.8.	Shaft nuts & keys	2 Sets
2.9.	Lantern rings	2 Sets
2.10.	Bell mouth liner	2 Sets
2.11.	Bearings	2 Sets
2.12.	Pump motor coupling	2 Sets
3.	**Spares for Vertical Type Submersible Pumps**	
3.1.	Impeller	2 Nos.
3.2.	Impeller key	2 Nos.
3.3.	Wearing rings (Impeller & Casing)	4 Nos.
3.4.	Impeller Shaft, line shaft and head shaft	2 Nos.
3.5.	Shaft Sleeves	4 Nos.
3.6.	Stuffing box	2 Nos.
3.7.	Coupling between Pump & motor, bushes, pins with all fasteners & coupling Guards.	2 Nos.
3.8.	Impeller, Line and Head shaft bearings	2 Nos.
3.9.	Gland Packing & Gland Assembly	2 Nos.
3.10.	Mechanical seal	2 Nos.

3.11.	Motor bearing	2 Nos.
4.	**Spares for Screw Pumps**	
4.1.	Rotor	2 Nos.
4.2.	Shaft	2 Nos.
4.3.	Mechanical seal	2 Nos.
4.4.	Packing for Stuffing Boxes	400%
4.5.	Bearing	2 Nos. for each shaft
5.	**Spares for Air blowers**	
5.1.	Impeller with Shaft	2 Sets
5.2.	Bearings	2 Sets
5.3.	Oil seal	10 Sets
5.4.	Filter	2 Sets
6.	**Spares for Agitators**	
6.1.	Gear Box Unit Complete	4 Nos.
6.2.	Bearing for Gear Box Unit	4 Sets
6.3.	Coupling complete(Motor/Gearbox and gearbox/agitator)	4 Sets
6.4.	Coupling Bolts	4 Sets
6.5.	Coupling shim pack (if applicable)	8 Sets
6.6.	Oil seals	8 Sets
7.	**Spares for Valves**	
7.1.	**Diaphragm Valves (if applicable)**	
	i) Manual Diaphragm valves	10% of total quantity used for each type and size with minimum no. four (4) for each type and size.
	ii) Auto Diaphragm valves	10% of total quantity used for each type and size with minimum no. four (4) for each type and size.
	iii) Spare Diaphragm for above	10% of total quantity used for each type and size with minimum no. four (4) for each type and size.
	iv) Diaphragm	10% of total quantity used for each type and size with minimum no. two (2) for each type and size
7.2.	i) Non return valves (NRV)	4 nos. of each size & type
	ii) Flaps for above NRV	4 nos. of each size
7.3.	Gate/Globe/Ball valves/plug valve/needle valve	
	i) Upto 4”	10% of total quantity used for each type and size with minimum no. four (4) for each type and size.
	ii) Above 4”	2 nos. each type and size.
7.4.	Butterfly valve	
	i) Upto 4”	10% of total quantity used for each type and size with minimum no. four (4) for each type and size.
	ii) Above 4””	2 nos. each type and size

8.	ELECTRICAL, CONTROL & INSTRUMENTATION ITEMS	
8.1.	**UPS System**	
8.1.1.	Fuse	6 (Six) times of total quantity of each type of fuses used in the system
8.1.2.	SCR	20% of total quantity of each type used in the system or minimum 4(Four) nos. whichever is more.
8.1.3.	Diode	20% of total quantity of each type used in the system or minimum 4(Four) nos. whichever is more.
8.1.4.	IGBT	4 (four) nos.
8.1.5.	Electronic Module/ PCB	
8.1.5.1.	Static Switch	2 nos. each type of Electronic Card/PCB/modules used in the system
8.1.5.2.	Inverter	2 nos. each type of Electronic Card/PCB/modules used in the system
8.1.5.3.	Static voltage Regulator	2 nos. each type of Electronic Card/PCB/modules used in the system
8.1.5.4.	Charger	2 nos. each type of Electronic Card/PCB/modules used in the system
8.1.5.5.	UPS of 2 KVA rating or below.	Two Complete set
8.1.5.6.	Selector Switch	2 (two) no. each type
8.1.5.7.	Digital Voltage/ Current Indicator (LCD type)	2 (two) no. each type
8.1.5.8.	Indication Lamp- Complete assembly (Red/ Green colour)	2 (two) no. each type
8.1.5.9.	Cooling Fan - 240 VAC supply	2 (two) no. each type
8.1.6.	UPS Battery	
8.1.6.1.	Battery Cell (Uncharged, Dry)	20% of total quantity
8.1.6.2.	Inter connecting cell strips	20 nos.
8.1.6.3.	Rubber gloves	2 Pairs
8.1.6.4.	Voltmeter for measuring cell voltage (Center zero type)	2 nos.
8.1.6.5.	Appron & Goggles	2 sets
8.1.6.6.	Cell lifting puller	2 nos.
8.1.6.7.	Insulated socket spanner with handle	2 nos.
8.1.6.8.	Terminal screw with bellaville washer	20% of total quantity used
8.1.6.9.	Thermometer	2 nos.
8.2.	**Control Panel/Desk Mounted Items/Back up panel**	
8.2.1.	Push Button	
8.2.1.1.	Complete assembly	10Nos for each colour or 10% of installed capacity, whichever is more
8.2.1.2.	Contact Element (1NO + 1NC) Block	40Nos or or 10% of installed capacity, whichever is more
8.2.2.	Selector Switch	20Nos. for each type and rating or or 10% of installed capacity, whichever is more
8.2.3.	Indicating Lamps complete assembly	20Nos. for each Colour and type or or 10% of installed capacity, whichever is more
8.2.4.	Mimic Lamps	20Nos. for each Colour and type or 200% of the total quantity, whichever is more
8.2.5.	MCB	4Nos. for each type and rating or 20% of each type & rating, whichever is more
8.2.6.	Door Limit Switch	4Nos.
8.2.7.	Annunciation system	
8.2.7.1.	Lamp Box with Facia & Lamps (LED type)	50Nos. or 10% of total quantity, whichever is more

8.2.7.2.	Hooter	2Nos.
8.2.8.	Blank Tiles	20% of installed capacity
8.2.9.	Fuses/ Fuse holder	200% of each type & rating
8.3.	**Electric Actuator/Motorised Valve**	
8.4.	**415 V 3 ph integral starter type**	
8.4.1.	Complete set of Actuator	2Nos. for each type and rating
8.4.2.	Limit Switch	6 Nos each type and rating
8.4.3.	Torque Switch	6 Nos each type and rating
8.4.4.	Auxiliary Contact	2 nos each type and rating
8.4.5.	Motor	2 nos each type and rating
8.4.6.	Complete Seal kit	2Sets for each type and rating
8.4.7.	Complete O-Ring Set	2Sets
8.4.8.	Electronic Card	Two(2) for each type/make
8.4.9.	Feedback Assembly (4-20mA) for Inching type	Two(2) for each type/make
8.5.	**Motor**	
8.5.1.	**415 Volt Motor (above 30KW Rating upto 200KW)**	
8.5.1.1.	End Shield Cover Driving & Non-Driving End	2 Sets for each type and rating of Motor
8.5.1.2.	Driving End & Non-Driving End Bearing	2 Sets for each type and rating of Motor
8.5.1.3.	Cooling Fan	2 Sets for each type and rating of Motor
8.5.1.4.	Motor Space Heater	2 Sets for each type and rating of Motor
8.5.1.5.	Motor Terminal Block	2 Sets for each type and rating of Motor
8.5.1.6.	Complete Set of Coupling	2 Sets for each Application
8.5.2.	**415 Volt Motor (Upto 30KW Rating)**	
8.5.2.1.	Driving End & Non-Driving End Bearing	6 Sets for each type and rating of Motor
8.5.2.2.	Cooling Fan	4 Nos. for each type and rating of Motor
8.5.2.3.	Motor Terminal Block	10 Nos. for each type and rating of Motor
8.5.2.4.	Complete Set of Coupling	2 Sets for each Application
8.6.	**Field Instruments**	
8.6.1.	Transmitters/ Gauges/Switches etc. along with relevant accessories	20% of total or at least Four (whichever is higher) for each type along with accessories.
8.6.2.	Temperature Element (RTD/Thermo-couple) with thermowell	100% of each type, range and immersion length .
8.6.3.	**Analysers**	
8.6.3.1.	Field sensor	4 nos. of each type/model
8.6.3.2.	Field transmitter/ complete electronic unit	2 nos of each type/model
8.6.3.3.	Power supply card	2 nos of each type/model
8.6.3.4.	Instrumentation hardware	2 nos. each item
8.7.	**Process Connection Piping (Impulse piping/tubing, sampling piping / tubing & air supply piping as applicable)**	
8.7.1.	Valves of all types	20% of each type, class, size & model
8.7.2.	Valve Manifolds (2 way/3 way/5 way)	20% of each type, class, size & model
8.7.3.	Fittings	20% of each type, class, size & model
8.7.4.	Filter Regulators	40% of each model

8.8.	**Junction Box**	
8.8.1.	Junction box	20% of total quantity for each size but minimum 4 nos.
8.8.2.	Terminals in Terminal blocks	20 nos. of each type
8.9.	**PLC/ Proprietary Control System**	
8.9.1.	Network cards, Communication Interface cards	10% for each type or but minimum 2 no.
8.9.2.	I/O Cards (Each type)	10% for each type but minimum 4 nos.
8.9.3.	Controller Cards	2 nos.
8.9.4.	SER Cards	10% for each type or but minimum 2 no
8.9.5.	All other Electronic Modules	10% for each type or but minimum 2 no.
8.9.6.	Relays	20% of total quantity
8.9.7.	Power Supply Modules & Power Packs for control system	10% for each type and range but minimum 2 nos.
8.9.8.	Network Items (Network switch/ LIU unit/ Transceiver/ FO patch cord etc.)	20% of total nos. used for each type and model in the system or minimum 4(four) no. whichever is more.
8.9.9.	MCB (Miniature case circuit breaker)	20% or minimum 20 nos. whichever is higher for each type and rating.
8.9.10.	Fuses	400% or minimum 100 no's for each type and rating
8.9.11.	Racks for housing I/O & Processor Modules	2(two) no. each type used in the system
8.9.12.	Prefab interconnecting cables with connectors	20% of total nos. used in the system or minimum 8(Eight) nos. whichever is more for each type.
8.9.13.	Network communication cable with end connectors	20% of total nos. used in the system or minimum 8(Eight) nos. whichever is more for each type.
8.9.14.	I/O bus cables with connectors for remote I/O units	2 nos. of each type & length
8.9.15.	Fibre optic cable Converter / Deconverter	2 nos.
8.9.16.	Cooling Fans	4 nos. for each cabinet
8.9.17.	Loose Connectors	10 nos. of each type
8.9.18.	Colour TFT Monitor	2 nos. complete set
8.9.19.	Hard Disk Drive for the work Station	2 nos. complete set
8.9.20.	Key board , mouse / trackball with connecting cables and plugs	2 nos. each type.
8.9.21.	Printers Catriges	4 nos. of each type

8.9.22.	SMPS for printers	2 nos. of each type/ rating
8.9.23.	SVGA cards for printers	2 nos. of each type
8.9.24.	Key Board & Cursor control device	2 nos. of each type
8.9.25.	Complete Set of Operators Work Station	2no. complete set
8.9.26.	Terminal Block	20% of total nos. used in the system for each type and rating.
8.9.27.	Read-Write CD/DVD	4 (four) no. complete set
8.9.28.	Blank CD/DVD	100 nos.

Note:
For calculation of spare quantity in % fractional numbers to be rounded up to next higher integer.

SUB-VENDOR LIST

1. Bidder shall follow the attached approved Sub-Vendor list. The Sub Vendor list provided is compiled list of all BHEL units and sufficient Sub-Vendors have been already approved by TSGENCO. No additional Vendors will be entertained for the equipment already available in the Sub-Vendor list.

2. Incase any equipment is not specified in the list, Bidder shall submit the credentials of the Sub Vendors during contract stage for Approval.

3. Credentials shall consist of the following as minimum
   a. List of references for similar application
   b. Minimum 2nos. of Purchase Orders of similar references
   c. Minimum 2nos. of Performance certificates/ Inspection clearance reports
   d. Sub Vendor Catalogues

4. Finalized list of Sub Vendors will be submitted to TSGENCO for intimation/ approval/ clearance.

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082. www.tsgenco.telangana.gov.in
Phone: 040 – 23499261 Fax: 040 – 23499263.

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, Vidyut Soudha, Khairatabad, Hyderabad-500 082. Email ID: cetpctgenco@gmail.com	M/s Bharat Heavy Electrical Ltd., INDUSTRIAL SYSTEMS GROUP P O Box No.1249, Prof CNR Rao Circle , Malleswaram, Banglore-560012. Mail ID: rsp@bhel.in

Lr.No.CE/TPC/SE-5/EME-09/YTPS(5X800MW)/F.NO.9/D.No.04 /19,Dt: 30.01.2019.

Sir,

Sub: TSGENCO – Yadadri TPS(5X800MW) – Approval of additional vendor M/s Tenova india Pvt Ltd, Chennai for 'Machine Package' – Certain Clarifications-Reg.

Ref: 1.Lr no.CE/TPC/SE-5/EME-09/YTPS(5x800MW)/F.No.09/D.No.01/19,Dt:05.01.2019
2.M/s BHEL Letter Ref: IS-1-15-2001/Additional Vendors-machine, Dt: 08.01.2019

*****

Further to letter communicated by TSGENCO vide reference (1)st cited, and reply by M/s BHEL on the subject matter vide reference (2)nd cited, it is to clarify that M/s Tenova India Pvt Ltd is approved for supplying 'Stacker & Reclaimer','Wagon Tippler' only based on end user certificates but not approved for sourcing machine like Crusher, Screens, Paddle feeders and Apron feeders from approved vendors of TSGENCO. This is for information and further necessary action.

Yours faithfully,

30/1/19

CHIEF ENGINEER/TPC

Copy to:
1. SE/Tech to the Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
2. Superintending Engineer-3/TPC/TSGENCO/Vidyut Soudha/Hyderabad
3. DE/Tech to the Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263.

From:	To:
Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL/RC Puram, Heavy Power Equipment Plant,R C Puram CONTRACT MANAGEMENT DEPARTMENT Hyderabad – 502 032 , INDIA Ph: 040-23182451,Mob:9491306087 Email: naickravi@bhel.in

Kind Attention:Mr. B. Ravindra naick , Dy. Manager

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No.06/19,Dt:08.01.19

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of New vendors for C&I and Mechanical items furnished by M/s BHEL/RC Puram/Hyderabad– Reg.

Ref:1.M/s BHEL/RC Puram/Hyderabad letter YTPS/VL/HYD/00, Dated 26.07.2018.

2.M/s TCE Recommendations letter TCE.11005A /PJ/K/015, dated 13.11.2018

******

Please refer to the letter 1st cited above, wherein M/s BHEL/R C Puram/Hyderabad has requested for approval of vendors for certain C&I and Mechanical items for Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of following list of items does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: List of TSGENCO Approved Vendors of M/s BHEL/R C Puram/Hyd Unit.

Yours faithfully,
8/1/19
Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. Superintending Engineer /Tech to The Chairman & Managing Director/TSGENCO/VS/HYD
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/R C Puram/Hyderabad
Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 06 /19,Dt: 08.01.2019

Sl. No.	Name of System/ Package	Name of Vendors/Place	TSGENCO Remarks
		T&C VENDORS	
1	OIL PURIFICATION UNIT	1.ALFALAVAL, PUNE/SWEDEN	Approved
		2.PALL INDIA PVT. LTD., Mumbai	Approved
		3.PENNWALT CORPORATION, USA	Approved
2	SIMPLEX FILTER	1.EPE PROCESS FILTERS & ACCUMULATORS, Hyderabad	Approved
		2.HYDAC TECHNOLOGY GMBH,Germany	Approved
		3.BOLL & KIRCH FILTERBAU GMBH, Germany	Approved
		4.HYDAC (INDIA) PVT. LTD., Maharashtra	Approved
		5.PALL EUROPE LTD. Great Britain	Approved
		6.PALL INDIA PVT. LTD.,Mumbai	Approved
		7.FILTER CONCEPT PRIVATE LIMITED, Ahmedabad.	Not Approved
		8.GRAND PRIX ENGINEERING PVT. LTD, Haryana.	Not Approved
3	CONTROL VALVES (PNEUMATIC ACTUATED)	1.INSTRUMENTATION LTD, Palakkad	Approved
		2.KOSO FLUID CONTROLS PVT. LTD.-Palakkad	Approved
		3.EMERSON PROCESS MANAGEMENT, Chennai	Approved
		4.SEVERN GLOCON INDIA, Chennai	Approved
		5.KSB MIL CONTROLS LIMITED,THRISSUR(Older name MIL CONTROLS LIMITED)	Approved
		6.BOMAFA SPECIAL VALVE SOLUTIONS, Gujarat.	Not Approved
		PUMPS PRODUCT	
4	DC STARTER CUBICLES	1.LARSEN & TOUBRO LIMITED, Hyderabad	Approved
		2.C AND S ELECTRIC LIMITED, New Delhi	Not Approved
		3.INDUSTRIAL CONTROLS & AUTOMATION , Mumbai	Not Approved
		4.BCH ELECTRIC LTD, Secunderabad.	Approved

PV Seeniy 8/1/19
Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/R C Puram/Hyderabad
Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 06/19,Dt: 08.01.2019

Sl. No.	Name of System/ Package	Name of Vendors/Place	TSGENCO Remarks
5	R.C VALVES FOR BFP	1.CONTROL COMPONENTS INC., USA	Approved
		2.KSB MIL CONTROLS LIMITED,THRISSUR(Older name MIL CONTROLS LIMITED)	Approved
		3.HOLTER REGELARMATUREN GMBH & CO. KG, GERMANY.	Approved
		4.DRESSER PRODUITS INDUSTRIELS, FRANCE	Approved
		5.CONTROL COMPONENT INDIA, CHITTOOR.	Not Approved
		6.EMERSON PROCESS MANAGEMENT, CHENNAI.	Approved
6	SUCTION STRAINER	1.PROCEDYNE ENGINEERS	Approved
		2.GUJARAT OTOFILT,	Approved
		3.JAY-EESH ENGINEERING COMPANY,Mumbai, INDIA	Approved
		4.FILTERATION ENGINEERS INDIA PVT LTD, MUMBAI, INDIA	Approved
		5.GRANDPRIX ENGINEERING PVT LTD, Haryana.	Not Approved
		6.NISAN SCIENTIFIC PROCESS, NAVI MUMBAI	Not Approved
		7.PATEL HEAT EXCHANGERS, Bhopal	Not Approved
7	Multi Disc Flexible Couplings for MHI BFPs, 660 to 800MWs	1.EUROFLEX TRANSMISSIONS (INDIA)	Approved
		2.JOHN CRANE FLEXI BOX (INDIA) PVT. LTD	Approved
		3.BIBBY TURBOFLEX.,	Approved
		4.RATHI TURBOFLEX PVT. LTD, PUNE.	Approved
		5.CUBIC TRANSMISSION PVT. LTD, HYDERABAD.	Approved
		6.KTR COUPLINGS INDIA PVT. LTD.	Not Approved
8	Connecting Coupling For CEP & CWP	1.CUBIC TRANSMISSION PVT. LTD.	Approved
		2.EUROFLEX TRANSMISSIONS (INDIA), Hyderabad.	Approved
		3.JOHN CRANE FLEXI BOX (INDIA) PVT. LTD	Approved
		4.RATHI TURBOFLEX PVT. LTD.,Pune	Approved
		5.UNIQUE TRANSMISSION (I) PVT LTD.,	Approved

9/1/19
Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/R C Puram/Hyderabad
Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 06 /19,Dt: 08.01.2019

Sl. No.	Name of System/ Package	Name of Vendors/Place	TSGENCO Remarks
		6.KTR COUPLINGS INDIA PVT. LTD., Pune.	Not Approved
		PULVERISERS & SWITCHGEAR	
9	Grinding Rolls	1.M/s AIA ENGINEERING, Nagpur	Approved
		2.M/s AIA ENGINEERING Ahmedabad	Approved
		3.MAGOTTEAUX INDUSTRIES PVT. LTD., Hyderabad.	Not Approved
		4.SHRI BALAJI INDUSTRIAL PRODUCTS LIMITED, Jaipur.	Not Approved
10	Bull Ring Segments	1.M/s AIA ENGINEERING, Nagpur	Approved
		2.M/s AIA ENGINEERING Ahmedabad	Approved
		3.MAGOTTEAUX INDUSTRIES PVT. LTD., Hyderabad.	Not Approved
		4.SHRI BALAJI INDUSTRIAL PRODUCTS LIMITED, Jaipur.	Not Approved
11	KNIFE GATE VALVE & ACCESSORIES	1.ASHWATHI CONTROLS PVT. LTD.AHEMDABAD	Approved
		2.GENERAL ENGINEERING CONSORTIUM, BANGALORE	Approved
		3.ORBINOX INDIA PVT LTD, INDIA, COIMBATORE.	Approved
		4.GALAXY CONTROLS PVT LTD, CHENNAI.	Approved
		5.M/s. Bray Controls India Private Limited- Chennai	Approved
		6.BACHMANN INDUSTRIES INDIA LTD.	Approved
		7.SURYA VALVES, CHENNAI.	Not Approved
		8.EXPERT ENGINEERING ENTERPRISES, BELGAUM, KARNATAKA.	Not Approved
		9.JASH ENGINEERING LIMITED, INDORE, M.P.	Not Approved
		10.KEROMIYONS INTECH PVT LTD, COIMBATORE.	Not Approved
		11.KRISHNA ENGINEERING COMPANY, BHOPAL.	Not Approved
		12.HI-TEC VALVES, CHENNAI.	Not Approved
12	PLANETARY	1.INDIAN OIL CORPN.LTD., HYDERABAD.	Approved

PU Secy 8/1/19

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/R C Puram/Hyderabad
Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 06/19,Dt: 08 .01.2019

Sl. No.	Name of System/ Package	Name of Vendors/Place	TSGENCO Remarks
	GEARBOX OIL	2.EXXONMOBIL LUBRICANTS PVT LTD, GURGAON.	Approved
		3.SHELL INDIA MARKETS PRIVATE LIMITED, MAHARASTHRA.	Not Approved
		4.CASTROL INDIA LIMITED, MUMBAI.	Not Approved
		5.HINDUSTAN PETROLEUM CORPN. LTD, CHENNAI.	Approved
		6.BHARAT P C L, HYDERABAD.	Approved
13	SPACE HEATERS	1.ESCORTS LIMITED,WORLI	Approved
		2.TRANSFORMER MANUFACTURING INDUSTRIAL , DHARANGADHARA, GUJARAT	Approved
		3.EELMESS THERMOSYSTEM TECHNIK GMBH&CO, GERMANY	Approved
		4.THERMOPADS PVT LTD., HYDERABAD.	Not Approved
		5.THERMEN HEATING TECHNOLOGIES, BANGALORE.	Not Approved
		6.RASHMI HEATERS PVT. LTD, PUNE.	Not Approved
14	AIR CYLINDER FOR KNIFE GATE VALVE	1.VELJAN HYDRAIR PVT. LTD, HYDERABAD.	Not Approved
		2.SALZGITTER HYDRAULICS PVT.LTD, HYDERABAD.	Approved
		3.FLUIDTECQ PNEUMATICS PVT. LTD, MAHARASTHRA.	Not Approved
		4.ROTEX MANUFACTURERS & ENGINEERS, THANE, MAHARASTHRA.	Approved
		5.ASCO NUMATICS(INDIA), CHENNAI.	Not Approved
15	SOLENOID VALVE FOR KNIFE GATE VALVE	1.VELJAN HYDRAIR PVT. LTD, HYDERABAD.	Not Approved
		2.AVCON CONTROLS PVT. LTD, MUMBAI.	Approved
		3.FLUIDTECQ PNEUMATICS PVT. LTD, MAHARASTHRA.	Not Approved
		4.ASCO NUMATICS(INDIA), CHENNAI.	Not Approved
16	LIMIT SWITCH FOR KNIFE GATE VALVE	1.BCH ELECTRIC LTD, SECUNDERABAD..	Approved
		2.HONEYWELL AUTOMATION INDIA LIMITED, PUNE.	Not Approved
		3.JAI BALAJI CONTROL GEARS PVT. LTD, CHENNAI.	Not Approved

PV seen 8/1/19

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/R C Puram/Hyderabad
Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 06/19,Dt: 08.01.2019

Sl. No.	Name of System/ Package	Name of Vendors/Place	TSGENCO Remarks
		COMMON ITEMS	
17	DUPLEX FILTER	1.HYDAC INDIA PVT LTD, Maharashtra	Approved
		2.EPE PROCESS FILTERS & ACCUMULATORS, Hyderabad	Approved
		3.PALL INDIA PVT. LTD., Mumbai	Approved
		4.FILTER CONCEPT PRIVATE LIMITED, GUJARAT.	Not Approved
		5.GRAND PRIX ENGINEERING PVT. LTD, HARYANA.	Not Approved
		6.UNIQUE ENGINEERING ENTPS. PVT. LTD, SECUNDERABAD.	Not Approved
		7.MIKROFLO FILTERS PVT.LTD, HYDERABAD.	Not Approved
		8.SUPERFLO FILTERS PVT.LTD., MAHARASTHRA.	Not Approved
18	GUIDED WAVE RADAR LEVEL TRANSMITTER	1.ABB GERMANY/FARIDABAD	Approved
		2.ABB LIMITED, NASHIK	Approved
		3.EMERSON PROCESS MGT(I) PVT LTD, Hyderabad.	Approved
		4.EMERSON PROCESS,USA/NAVI MUMBAI	Approved
		5.ENDRESS & HAUSER GMBH + CO., Germany	Approved
		6.ENDRESS + HAUSER (INDIA) PVT. LTD., Maharasthra.	Approved
		7.ENDRESS+HAUSER, GERMANY/INDIA	Approved
		8.MAGNETROL INTERNATIONAL N.V	Approved
		9.PUNE TECHTROL PVT LTD, PUNE	Approved
		10.SAAB ROSEMOUNT TANK GUAGING , PUNE	Approved
		11.V AUTOMAT AND INSTRUMENTS PVT LTD, NEW DELHI.	Not Approved
		12.YOKOGAWA, JAPAN/BANGLORE	Approved
19	LUBE OIL PUMP (SCREW TYPE)	1.ALEKTON ENGINEERING INDUSTRIES	Approved
		2.DELTA PD PUMPS PVT LTD, Mumbai	Approved
		3.LEISTRITZ , GERMANY	Approved

PV Seaiy 8/1/19

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/R C Puram/Hyderabad
Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 06/19,Dt:08.01.2019

Sl. No.	Name of System/ Package	Name of Vendors/Place	TSGENCO Remarks
		4.NETZSCH TECHNOLOGIES INDIA PVT LTD	Not Approved
		5.SETTIMA MECCANICA SRL	Approved
		6.TUSHACO PUMP, DAMAN (Note- Tushaco name changed to Allweiler)	Approved
		7.UT PUMPS & SYSTEMS PVT. LIMITED.	Approved
20	Resistance Temperature Detector (RTD) & THERMOCOUPLES	M/s BHEL/Hyderabad shall follow the approved vendors of YTPS(5X800MW) for temperature elements in line with M/s BHEL/EDN.	
21	THERMOWELLS	1.ASHCROFT INDIA PVT LTD-GUJARATH	Approved
		2.CARLO DYNATECH INDUSTRIES,Patancheru	Not Approved
		3.DETRIV INSTRUMENTATION, MUMBAI.	Approved
		4.GOA INSTRUMENTS INDUSTRIES , GOA	Approved
		5.H.GURU INSTRUMENTS (SI) PVT LTD ,BANGALORE	Approved
		6.INDUSTRIAL INSTRUMENTATION , KOLKATA	Approved
		7.MICRO PRECISION PRODUCTS (P) LTD., Haryana	Not Approved
		8.PRECISION ENGINEERING INDS,MUMBAI	Approved
		9.PRECISION MASS PRODUCTS PVT LTD, GUJARAT.	Not Approved
		10.PYRO ELECTRIC INSTRUMENTS GOA	Approved
		11.THERMAL INSTRUMENT INDIA, Maharashtra	Approved
		12.TM TECHNOMATIC S.R.L, ITALY	Not Approved
		13.TOSHNIWAL INDUSTRIES PVT.LTD - AJMER	Approved
22	LEVEL GUAGES	M/s BHEL/Hyderabad will be requested to follow the approved vendors of YTPS(5X800MW) for LEVEL GUAGES in line with M/s BHEL/EDN.	

P V Seeya 8/1/19

Chief Engineer/TPC

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263

From:	To:
Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL/Ranipet,Boiler Auxiliaries Plant, Indira Gandhi Industrial Complex, COMMERCIAL DEPARTMENT RANIPET - 632 406. INDIA Phone:(04172) 284817,Mob:9848265808 Email: mmahesh@bhel.in

Kind Attention: Mahesh M, Dy. Manager/Commercial

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 07 /19,Dt: 08.01.19

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of additional Vendors for for supplying of Electrical actuators furnished by M/s BHEL/Ranipet unit - Reg.

Ref: 1. M/s BHEL/Ranipet BAP:COMML:R827-R831 & R4L4:VENDOR LIST:REV-01 , dated 05.09.2018

2. M/s TCE/Hyderabad vide letter references TCE.11005A /PJ/K/015, dated 13.11.2018

******

Please refer to the letter 1st cited above, wherein M/s BHEL/Ranipet has requested for the following two additional vendors for supplying of Electrical actuators pertaining to Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors.

Sl. No.	Item Description	Vendor proposed/Place	TSGENCO Remarks
1	Actuators–Electrical (Open/Close type)	1.ANTRIEB TECHNIK PRIVATE LIMITED, CHENNAI.	Approved
		2.YANGZHOU HENGCHUN ELECTRONICS CO. LTD, JIANGSU, CHINA	Not Approved

Please note that this approval of vendors for Supply of following list of items does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Yours faithfully,

8/1/19

Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. Superintending Engineer /Tech. to CMD/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).

P.T.O

6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263

From:	To:
Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL/Trichy, High Pressure Boiler Plant, Tiruchirappalli-620 014, Tamil Nadu, INDIA. (P):0431-257-7156, Mob:9406903625, Email: rtoppo@bhel.in

Kind Attention:Sri RAHUL TOPPO, Dy. Manager, Comml/FB

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 08 /19,Dt:08.01.19

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of Vendors for for CONTROL VALVE furnished by M/s BHEL/Trichy unit - Reg.

Ref: 1.M/s BHEL/Trichy letter TP/11497/Vendor List/02 dated 23.07.2018.
2. M/s TCE/Hyderabad letter reference TCE.11005A /PJ/K/015, dated 13.11.2018.

******

Please refer to the letter cited above, wherein M/s BHEL/Trichy has requested for approval of vendors for CONTROL VALVE pertaining to Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of following list of items does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: List of TSGENCO Approved Vendors of M/s BHEL/Trichy Unit.

Yours faithfully,
P V Sesha Sai 8/1/19
Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. Superintending Engineer /Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

Annexure

M/s BHEL/Trichy Vendor approval list of CONTROL VALVE for Yadadri TPS(5X800MW)

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 08/19,Dt:08.01.2019

Sl. No.	Item Description	Name of Vendors /Place	TSGENCO Remarks
1	CONTROL VALVE	1.GE OIL & GAS INDIA PRIVATE LIMITED. COIMBATORE India(old name DRESSER VALVE INDIA PRIVATE LTD,INDIA)	Approved
		2. KSB MIL CONTROLS LIMITED THIRISSUR DIST, India(Old name MIL CONTROLS LIMITED)	Approved
		3.SEVERN GLOCON INDIA (P) LTD, CHENNAI. India	Approved
		4.KOSO INDIA PRIVATE LIMITED, India	Approved
		5.MASCOT VALVES PVT. LTD AHMEDABAD India	Not Approved
		6.CONTROL COMPONENT INDIA PVT LTD BANGALORE India	Approved
		7.DRESSER PRODUITS INDUSTRIELS S.A.S France	Approved
		8.CONTROL COMPONENTS INC USA	Approved
		9.FISHER SANMAR LIMITED India	Approved
		10.EMERSON PROCESS MANAGEMENT CHENNAI CHENNAI. India	Approved
		11.INSTRUMENTATION LTD., India	Approved
		12.FLOWSERVE INDIA CONTROLS PVT.LTD.,India	Approved

8/1/19

Chief Engineer/TPC

	TELANGANA STATE POWER GENERATION CORPORATION LIMITED (A Govt. of Telangana Undertaking) Vidyut Soudha, Hyderabad - 500082. Phone: 040 – 23499261 Fax: 040 – 23499323.

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, Vidyut Soudha, Khairatabad, Hyderabad-500 082. Email ID: cetpctgenco@gmail.com	M/s BHEL, Power Sector-Southern Region, Periyar EVR Building,690, Anna Salai, Nandanam, Chennai – 600 035. Phone: 044-28286715 Fax: 044-24323757.

Lr.No.CE/TPC/SE3/EME-15/YTPS(5X800MW)/F.NO. /D.No. 177/18, Dt: 12.12.2018.

Sir,

Sub: TSGENCO – Yadadri TPS(5X800MW) – Proceeding with Tendering for execution of CHP and AHP civil works as Package A & B of Units 1,2,3,4 & 5 for 5X800 MW Yadadri Thermal Power Station - Reg.

Ref : 1) M/s BHEL E-mail Letter Dt:24.03.2018.
2) M/s BHEL Letter Ref: BHEL PSSR: YADADRI TPP: 102, Dt:26.11.2018
3) M/s BHEL Letter Ref: BHEL PSSR: YADADRI TPP: 102, Dt:11.12.2018

*****

This has reference to the letter cited in ref (3) above, wherein M/s BHEL/PSSR has informed that they are in the process of floating the tender for execution of CHP and AHP civil works as Package A & B of Units 1,2,3,4 & 5 for 5X800 MW Yadadri Thermal Power Station and informed that the tender shall have the provision of Reverse Auction

In this connection it is to inform that time and again TSGENCO is requesting M/s BHEL that not resort to Reverse Auction for civil works which was agreed by M/s BHEL during finalization of Revised LOI and as per P.O conditions .

Hence the proposal furnished by M/s BHEL that the above tenders shall have the provision of Reverse Auction is not acceptable to TSGENCO.

This is for information and further necessary action.

Yours faithfully,

P V Seenivasa Rao

Chief Engineer/TPC

P.T.O

Copy to:

1. Chief Engineer/Construction/YTPS/ Dameracherla/Nalgonda(Dt)
2. Chief Engineer/ Civil/Thermal/TSGENCO/VS/Hyderabad
3. Superintending Engineer/Civil/YTPS(5X800MW)/Dameracherla.
4. Superintending Engineer-5/TPC/TSGENCO/VS/Hyderabad.
5. SE /Tech. to CMD/TSGENCO/VS/Hyderabad.
6. DE /Tech. to Director/Projects/TSGENCO/VS/Hyderabad.
7. ADE /Tech. to Director/Civil/TSGENCO/VS/Hyderabad.
8. Sri Y.A.Srinivasa Rao,GM(PMG)/BHEL Camp Office/Vidyut Soudha/Hyderabad.
9. Sri HariKrishnan/GM/BHEL/YTPS Site.
10. M/s Tata Consulting EngineersLimited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001. E-Mail id: ksridhar@tce.co.in.

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263

From:	To:
Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL/Piping Centre, Commercial Department, 80 GN Road, T Nagar , Chennai -600 017, Tel: 044-28161278 Email: vishnujyoti@bhel.in

Kind Attention: Mrs. G.V.V VISHNU JYOTI,Manager/Commercial

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 10 /19,Dt:08.01.2019

Sir,

Sub: TSGENCO – Approval of vendors for C&I and Mechanical items furnished by M/s BHEL/Piping Centre/Chennai unit – Reg.

Ref: 1. M/s BHEL/PC/Chennai Lr. Ref. YADADRI 5X800MW/7295/7296/7297/7298/7299/ VENDOR APP dated 05.10.18

2. M/s TCE Recommendations Letter reference TCE.11005A/PJ/K/016, dated 13.11.2018.

******

Please refer to the letters 1st cited above, wherein M/s BHEL/PC/Chennai has requested for approval of vendors for certain C&I and Mechanical items for Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of following list of items does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: List of TSGENCO Approved Vendors of M/s BHEL/PC/Chennai Unit.

Yours faithfully,

PV Seeni 8/1/19

Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. Superintending Engineer /Tech. to CMD/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s TCE Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

Annexure

M/s BEL/PC-Chennai Vendor Approval List

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 10 /19,Dt:08.01.2019

Sl. No.	Name of System/ Package	Name of Vendors/Place		TSGENCO Remarks
1	CONTROL VALVES	1) PARCOL S.P.A.	MILAN	Not Approved
		2) SHENJIANG VALVE CO LTD	ZHEJIANG PROVINCE, PRC , CHINA	Not Approved
		3) DAUME REGELARMATUREN GMBH,	ISERMHAGEN, GERMANY	Approved
		4) SPX FLOW TECHNOLOGY(INDIA)PVT.LTD.,	AHEMEDABAD	Not Approved
		5) EMERSON PROCESS MANAGEMENT CHENNAI,	CHENNAI	Approved
		6) MASCOT VALVES PVT. LTD	AHMEDABAD	Not Approved
		7) CONTROL COMPONENT INDIA PVT LTD	BANGALORE	Approved
		8) LESLIE CONTROLS INC	USA	Approved
		9) KOSO INDIA PRIVATE LIMITED.	NASHIK.	Approved
		10) SEVERN GLOCON INDIA (P) LTD	CHENNAI	Approved
		11) BOMAFA ARMATUREN GMBH,	GERMANY	Approved
		12) KSB MIL CONTROLS LIMITED,	THIRISSUR DIST	Approved
		13) EMET CONTROLS PVT LTD,	NASHIK	Not Approved
		14) R.K.CONTROL INSTRUMENTS PVT.LTD	THANE	Not Approved
		15) INSTRUMENTATION LTD.	KERALA	Approved
		16) FORBES MARSHALL ARCA VALVES PVT. LTD	CHENNAI	Approved
2	Cooling Water Pump	1) S.J.INDUSTRIES	CHENNAI	Not Approved
		2) KISHOR PUMPS PVT LTD	PUNE.	Approved
		3) FLOWMORE LTD.	GHAZIABAD	Approved
		4) SAM TURBO INDUSTRY PVT LIMITED	COIMBATORE	Approved
		5) VARAT PUMP & MACHINERY PVT LTD	KOLKATA	Approved
		6) SULZER PUMPS INDIA LTD	CHENNAI	Approved
3	LP STARTUP CONTROL VALVE	1) KOSO INDIA PRIVATE LIMITED	NASHIK	Approved
		2) CONTROL COMPONENT INDIA PVT LTD.	BANGALORE	Approved
		3) EMERSON PROCESS MANAGEMENT CHENNAI	CHENNAI	Approved
		4) SHENJIANG VALVE CO LTD,	ZHEJIANG PROVINCE, PRC,CHINA	Not Approved

8/1/19

Chief Engineer/TPC

Annexure
M/s BEL/PC-Chennai Vendor Approval List
Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 10 /19,Dt: 08.01.2019

		5) KSB MIL CONTROLS LIMITED,	THIRISSUR DIST	Approved
		6) INSTRUMENTATION LTD.	KERALA	Approved
4	Averaging Pitot Tube	1) TECHNOMATIC	ITALY	Not Approved
		2) STAR-MECH CONTROLS	HADAPSAR, PUNE.	Approved
		3) VERIS INC	CO 80503 USA	Not Approved
		4) MICRO PRECISION PRODUCTS (P) LTD	TEH & DIST : PALWAL	Approved
		5) SWITZER PROCESS INSTRUMENTS	CHENNAI	Approved
		6) MINCO (INDIA) PVT. LTD	GOA	Approved
5	CONDENSATE PUMP-LP	1) FLOWSERVE INDIA CONTROLS PVT.LTD.	COIMBATORE	Approved
		2) CLYDE PUMPS INDIA PVT LTD,	GHAZIABAD	Approved
		3) SAM TURBO INDUSTRY PVT LIMITED	COIMBATORE	Approved
		4) SULZER PUMPS INDIA LTD	NAVI MUMBAI	Approved
		5) PUMPSENSE FLUID ENGINEERING	KOLKATA	Approved
		6) ITT CORPORATION INDIA PRIVATE LTD	BARODA	Approved
		7) KIRLOSKAR BROTHERS LTD	PUNE	Approved
6	LI RACK	M/s BHEL/PC-Chennai shall follow the approved vendors of YTPS(5X800MW) for LI RACK in line with M/s BHEL/Trichy.		
7	LEVEL SWITCHES	M/s BHEL/PC-Chennai shall follow the approved vendors of YTPS(5X800MW) for LEVEL SWITCHES in line with M/s BHEL/EDN.		
8	PRESSURE SWITCHES	M/s BHEL/PC-Chennai shall follow the approved vendors of YTPS(5X800MW) for PRESSURE SWITCHES in line with M/s BHEL/EDN.		
9	THERMOWELL	1) GOA INSTRUMENT INDUSTRIES PVT LTD	GOA	Approved
		2) THERMAL INSTRUMENTS INDIA PVT LTD	VAPI	Approved
		3) BAUMER TECHNOLOGIES INDIA PVT.LTD	VAPI	Approved
		4) GAUGES BOURDON (I) PVT. LTD	CHENNAI	Approved
		5) PYRO ELECTRIC INSTRUMENTS GOA P LTD,	GOA	Approved
		6) NESSTECH INSTRUMENTS PVT.LTD	VAPI	Approved
		7) DETRIV INSTRUMENTATION	Mumbai, India	Approved

8/1/19

Chief Engineer/TPC

TELANGANA STATE POWER GENERATION CORPORATION LIMITED

(A Govt. of Telangana Undertaking)

Vidyut Soudha, Hyderabad - 500082. www.tsgenco.telangana.gov.in
Phone: 040 – 23499261 Fax: 040 – 23499263.

From:	To:
The Chief Engineer , Thermal Projects Construction, TSGENCO, Vidyut Soudha, Khairatabad, Hyderabad-500 082. Email ID: cetpctgenco@gmail.com	M/s Bharat Heavy Electrical Ltd., INDUSTRIAL SYSTEMS GROUP P O Box No.1249, Prof CNR Rao Circle , Malleswaram, Banglore-560012. Mail ID: amit_kumar@bhel.in

KIND ATTENTION: AMIT KUMAR,Sr.Manager(PMC)

Lr.No. CE/TPC/SE-3/EME-9/YTPS (5X800MW)/F.No.vendors/D.No.109 /18, Dt: 9.11.2018.

Sir,

Sub:-TSGENCO–Yadadri TPS (5X800MW)-Approval of vendors for Coal Handling Package for 5X800 MW Yadadri Thermal Power Station for M/s BHEL/ISG unit - Reg.

Ref: 1) M/s BHEL Letter Ref: BHEL-IS-1-15-2001/CHP,Dt:09.04.2018.

*****

Please refer your letter cited Ref(1) above, wherein M/s BHEL/ISG furnished Coal Handling Package for 5X800 MW Yadadri Thermal Power Station. The vendors are reviewed and TSGENCO hereby accords approval for the following vendors for Coal Handling Package for 5X800 MW Yadadri Thermal Power Station.

Vendor List for Coal handling package (CHP-Mechanical):

S. NO	Item description	Name of the vendor	TSGENCO Remarks
1	CONVEYOR PACKAGE	LARSEN & TOUBRO LTD, ECC DIVN, CHENNAI	Approved
		ELECON ENGINEERING COMPANY LTD, VALLABH VIDYANAGAR-GUJRAT	Approved
		TRF LTD., JAMSHEDPUR	Approved
		MCNALLY BHARAT ENGINEERING COMPANY LTD, KOLKATA	Approved
		THYSSENKRUPP INDUSTRIES INDIA PVT LTD, PIMPRI-PUNE	Approved
		FLSMIDTH Private Umited, CHENNAI	Approved
		SANDVIK ASIA PRIVATE U MITED, KOLKATA	Approved
		THE INDURE PVT., LTD., NEW DELHI	Approved
		BHEL-ISG, BANAGALORE	Approved
		Bengal Tools Limited, KOLKATA	Approved
		Bevcon Wayors Pvt Ltd., HYDERABAD	Not Approved
		BSBK Engineers Pvt. Ltd. NOIDA	Approved
		Promac Engineering Industries Ltd.,BANGALORE	Approved
2	STACKER & RECLAIMER	Larsen & Toubro, CHENNAI	Approved
		ELECON EPG PROJECTS LIMITED (Formerly Elecon Engineering Co Ltd), VALLABH VIDYANAGAR-GUJRAT	Approved
		TRF LIMITED, JAMSHEDPUR	Approved
		Mcnally Bharat Engineering Ltd, KOLKATA	Approved
		Krup Limited, PIMPRI PUNE	Approved
		FLSMIDTH Private Limited, CHENNAI	Approved

S. NO	Item description	Name of the vendor	TSGENCO Remarks
3	WAGON TIPPLER & SIDE ARM CHARGER	Larsen & Toubro, CHENNAI	Approved
		ELECON EPG PROJECTS LIMITED (Formerly Elecon Engineering Co., Ltd) VALLABH VIDYANAGAR-GUJRAT	Approved
		TRF LIMITED, JAMSHEDPUR	Approved
		McNally Bharat Engineering Ltd, KOLKATA	Approved
		Krup Limited, PIMPRI-PUNE	Approved
4	APRON & DRIBLE FEEDER	LARSEN & TOUBRO LTD, ECC DIVN, CHENNAI	Approved
		ELECON EPG PROJECTS LIMITED (Formerly Elecon Engineering Co., Ltd) VALLABH VIDYANAGAR-GUJRAT-GUJRAT	Approved
		TRF LTD., JAMSHEDPUR	Approved
		THYSSENKRUPP INDUSTRIES INDIA PVT LTD, PIMPRI-PUNE	Approved
5	SCREEN	LARSEN & TOUBRO LTD., MUMBAI	Approved
		ELECON ENGG COMPANY LTD VALLABH VIDYANAGAR-GUJRAT	Approved
		TRF LIMITED, JAMSHEDPUR	Approved
		McNally Bharat Engineering Ltd, KOLKATA	Approved
6	CRUSHERS	LARSEN & TOUBRO LTD., MUMBAI	Approved
		ELECON ENGG COMPANY LTD, VALLABH VIDYANAGAR-GUJRAT	Approved
		TRF LIMITED, JAMSHEDPUR	Approved
		McNally Bharat Engineering Ltd, KOLKATA	Approved
		THYSSON KRUPP INDUSTRIES, PIMPRI-PUNE	Approved
7	PADDLE FEEDER	LARSEN & TOUBRO LTD., MUMBAI	Approved
		ELECON, VALLABH VIDYANAGAR-GUJRAT	Approved
		TRF LIMITED, JAMSHEDPUR	Approved
		THYSSON KRUPP INDUSTRIES , PIMPRI-PUNE	Approved
8	VIBRATING FEEDER	LARSEN & TOUBRO LTD., MUMBAI	Approved
		ELECON, VALLABH VIDYANAGAR-GUJRAT	Approved
		Electromag, Mumbai/Vapi	Approved
		BEVCON, HYDERABAD	Not Approved
9	IDLER (ALL TYPES) WITH FRAMES	ROLLWEL CONVEYOR COMPONENTS PVT LIMITED, MUMBAI	Approved
		BEVCON, HYDERABAD	Not Approved
		L&T, CHENNAI	Approved
		ELECON EPG PROJECTS LIMITED (Formerly Elecon Engineering Co., Ltd),VALLABH VIDYANAGAR-GUJRAT	Approved
		TRF, JAMSHEDPUR	Approved
		MCNALLI BHARAT ENGINEERING PVT LTD, KOLKATA	Approved
		THYSSENKRUPP INDUSTRIES INDIA PVT LTD, PIMPRI-PUNE	Approved
		MACMET INDIA LIMITED, KOLKATA	Approved
		BSBK Engineers Pvt Ltd, NOIDA	Approved
		THE INDURE PVT., LTD., NEW DELHI	Approved

S. NO	Item description	Name of the vendor	TSGENCO Remarks
10	Pulleys with Plummer block, Bearing Sets.	LARSEN & TOUBRO LTD, ECC DIVN, CHENNAI	Approved
		ELECON EPG PROJECTS LIMITED (Formerly Elecon Engineering Co., Ltd), VALLABH VIDYANAGAR-GUJRAT	Approved
		TRF LTD., JAMSHEDPUR	Approved
		MCNALLI BHARAT ENGINEERING PVT LTD, KOLKATA	Approved
		THYSSENKRUPP INDUSTRIES INDIA PVT LTD, PIMPRI-PUNE	Approved
		MACMET INDIA LIMITED, KOLKATA	Approved
		BSBK Engineers Pvt Ltd, NOIDA	Approved
		FLSMIDTH Private Limited, CHENNAI	Approved
		Bevcon Wayors Pvt Ltd, HYDERABAD	Not Approved
		THE INDURE PVT., LTD., NEW DELHI	Approved
11	SCRAPPER - INTERNAL & EXTERNAL	BMH CONCARE TECHNOLOGIES INC, NAVI MUMBAI	Approved
		GOLDEN ENGINEERING INDUSTRIES, BHILAI	Approved
		THEJO ENGINEERING LTD, CHENNAI	Approved
		Hosch Equipment, Kolkata	Approved
		Kaveri Ultra Polymers Ltd. BANGALORE	Approved
		MARTIN, PUNE	Approved
12	Belt Weigher along with Panel	THERMO RAMSAY, AUSTRALIA.	Approved
		AVERY INDIA LTD., NEW DELHI.	Approved
		POWER BUILD, Limited, GUJARAT	Approved
		IPA, BANGALORE	Approved
		Schenk Process, CHENNAI	Approved
		PRECIA MOLEN, BANGALORE/CHENNAI	Approved
13	Brake with Thruster	SIEGERLAND-BREWSEN, GERMANY.	Approved
		STROM KRAFT, MUMBAI	Approved
		BCH ELECTRIC LIMITED, BANGALORE	Approved
		INDUSTRIES SYNDICATE, KOLKATA.	Approved
		SIEMENS INDIA LTD. BANGALORE	Approved
		KATEEL ENGINEERING INDUSTRY PL TD. BANGALORE	Approved
		Electromg Devices, Mumbai	Approved
		Industrial Components, KOLKATA	Approved
		EIectromagnetic Industries, VADODARA	Approved
14	EOT CRANES & HOISTS - ELECTRIC AND MANUAL	HERCULES HOISTS LTD. MUMBAI	Approved
		ARMSEL PVT. LTD., BANGALORE	Approved
		TRANSPADE ENGINEERS PVT LTD, BANGALORE	Approved
		TRACTEL TIRFOR INDIA PVT. LTD. NEW DELHI	Approved
		CENTURY CRANE ENGRS PVT. LTD. FARIBABAD	Approved
		TUOBRO FURGUSON (INDIA) PVT. LTD. KOLKATA	Approved
		CONSOLIDATE CRANES AND STRUCTURES, PUNE	Approved

S. NO	Item description	Name of the vendor	TSGENCO Remarks
15	Electric Hoists / Manual Hoist	WH Brady (Brady & Morris)	Approved
16	COAL SAMPLING SYSTEM	ADVANCED SYSTEMS SAMPLING PVT LTD, KOLKATA	Approved
		EASTMAN CRUSHER Co. (P) Ltd. KOLKATA	Approved
17	BELT VULCANISING MACHINE	NILOS, CHENNAI	Approved
		SV DATTAR, KOLKATA	Approved
		THEJO ENGINEERING LIMITED, CHENNAI	Approved
		Chanda & Co, KOLKATA	Approved
		SYNERGY, KOLKATA	Approved
18	WEIGH BRIDGE	ABB LIMITED, BANGALORE	Approved
		AVERY (I) LTD., Ballavgarh	Approved
		SCHENCK JENSON & NICHOLSON, KOLKATA	Approved
		SCHENCK PROCESS INDIA LIMITED, CHENNAI	Approved
		ESSAE DIGITRONICS PRIVATE LIMITED, BANGALORE	Approved
		IPA, Pvt. Ltd. BANGALORE	Approved
19	AIR CONDITIONING SYSTEM	VOL TAS LIMITED, MUMBAI.	Approved
		BLUE STAR LIMITED, MUMBAI.	Approved
		CARRIER AIRCONDITIONING & REFRIGERATION LTD, Gurgaon-Haryana	Approved
		GODREJ & BOYCE MFG. CO., LTD. BANGALORE	Approved
20	Dust Extraction System along with Panel	A.P.C. SYSTEMS & PRODUCTS PVT. LTD. KOLKATA	Approved
		C.DOCTOR & COMPANY PRIVAE LTD. AHMEDABAD	Approved
		DUSTVEN, BANGALORE	Approved
		WRC, Anand-Gujarat	Approved
		BEVCON, BANGALORE	Not Approved
21	COMPRESSOR	A ERZEN MACHINES INDIA PVT LTD. VADODARA	Approved
		ATLAS COPCO, BANGALORE	Approved
		ELGI, CHENNAI	Approved
		INGERSOLIRAND, GURGAON	Approved
22	VENTILATION SYSTEM	C. DOCTOR, AHMEDABAD	Approved
		DUSTVEN PVT.L TD. BANGALORE	Approved
		MESINA, MUMBAI	Approved
		SK SYSTEMS PRIVATE LIMITED, NEW DELHI	Approved
		A .P.C. SYSTEMS & PRODUCTS PVT. LTD, KOLKATA	Approved
		TAP Engineering, CHENNAI	Approved
		OSM Projects Pvt. Ltd. NOIDA	Not Approved
		Wollaque Ventilation and Conditioning Pvt. Ltd. NOIDA	Approved

S. NO	Item description	Name of the vendor	TSGENCO Remarks
23	DUST SUPPRESSION & WATER SYSTEM FOR CHP	SPRAYING SYSTEMS INDIA PVT. LTD. BANGALORE	Approved
		APC SYSTEM & PRODUCTS PVT. LTD. KOLKATA	Approved
		F. HARLEY, KOLKATA	Approved
		TPS INFRASTRUCTURE LTD. NEW DELHI	Approved
		CHEMTROLS SAMIL INDIA PVT LTD, NAVI MUMBAI	Approved
24	CONVEYOR BELTING AND BELT FEEDER BELTING	PHEONEX YULE, KOLKATA	Approved
		SEMPERTRANS, CHENNAI	Approved
		FORECH INDIA LTD, KOLKATA	Approved
		HINDUSTAN RUBBERS, SILVASA	Approved
		NORTHLAND RUBBER MILLS, NEW DELHI	Approved
		ORIENTAL RUBBER INDUSTRIES LTD.,PUNE	Approved
		JONSON RUBBER INDUSTRIES, NEW DELHI	Approved
		SOMI CONVEYOR BEL TINGS LIMITED, JODHPUR	Approved
		NRC INDUSTRIES LIMITED , AMRITSAR	Approved
25	ERW PIPES	STEEL AUTHORITY OF INDIA LTD.	Approved
		WELSPUN GUJARAT STAHL ROHERN LTD. MUMBAI	Approved
		ASIAN M ILLS PRIVATE LIMITED, AHMEDABAD	Approved
		Jotindra Steel & Tubes Ltd. FARIDABAD	Approved
		SURYA ROSHNI LIMITED, NEW DELHI	Approved
		JCO GAS PIPE LIMITED, NEW DELHI	Approved
		RATNAMANI METALS & TUBES LTD, GUJARAT	Approved
26	Bearings	Revolvo-GERMANY	Approved
		SKF, INDIA	Approved
		TIM KEN-GERMANY	Approved
		FAG, VADODARA	Approved
27	Split Type Bearings	Revolvo-GERMANY	Approved
		Cooper- GERMANY	Approved
		FLSmidth, CHENNAI	Approved
28	PLUMMER BLOCKS	Nandy Engineering, HOWRAW	Approved
		MASTA, Ahmedabad	Approved
		SIMCO, KOLKATA	Approved
29	Gear Box	Premium Transmission, Mumbai	Approved
		Flender Limited	Approved
		Elecon Engineering Co. Ltd. VALLABH VIDYANAGAR-GUJRAT	Approved
		New Allenbarry Works, Kolkata	Approved
		SHANTHI, Coimbatore	Approved
30	Fluid Coupling	Premium Transmission, Mumbai	Approved
		Fluidomat, Indore	Approved
		Elecon Engineering Co. Ltd. VALLABH VIDYANAGAR-GUJRAT	Approved
		Voith, GERMANY	Approved

S. NO	Item description	Name of the vendor	TSGENCO Remarks
31	Flexible Gear Coupling (Low Speed Coupling)	Elecon Engineering Co. Ltd.VALLABH VIDYANAGAR-GUJRAT	Approved
		GBM Mfg. {P} Ltd., Kolkata	Approved
		Fenner, BANGALORE	Approved
		Wellman Wacoma, KOLKATA	Approved
32	In-Line Magnetic Separator / Suspended Magnet along with Panel	Electro-Zavod, KOLKATA	Approved
		PBL, V.V.NAGAR	Approved
		Electromag, MUMBAI	Approved
		Electromagnetic Industries,Baroda-Gujarat.	Approved
		Magnet Industries-KOLKATA	Approved
		Magnetics Corporation of India,BANGALORE	Approved
		ERIEZ, UK	Approved
33	Elevator	ECE, GHAZIABAD	Approved
		OMEGA Elevators,Bangalore/Ahmedabad	Approved
34	Sump/Water Pump	KBL, KIRLOSHKER-WADI	Approved
		SAM, Coiambatore	Approved
		Metso, Gurgaon-Haryana	Approved
		M/S Mody Industry Pvt Ltd (M/s WPll LTD groups of company)	Approved
		KIRLOSKAR, Bangalore	Approved
		KSB, NASHIK	Approved
		BEACON WEIR LTD, CHENNAI	Approved
		Flowmore Limited, Gurgaon	Approved
		Kishor Pumps Pvt. Ltd ., Chennai	Approved
		KUBOTA CORPN., JAPAN	Approved
35	Metal Detector along with Panel	PBL, V.V NAGAR	Approved
		Electromag,MUMBAI	Approved
		Magnet Industries, KOLKATA	Approved
		Electrozavod, KOLKATA	Approved
		Electromagnetic Industries Baroda-Gujarat.	Approved
36	Skirt Sealing	Tega Industries, Kolkata	Approved
		Kaveri Ultra Polymers, Karnataka	Approved
37	Rail Clamp of Trippers	Industrial Components, KOLKATA	Approved
		Bengal Technocrats Pvt. Ltd., Kolkata	Approved
38	Flap Gate, Flow Divider, Rod Gate, Rack & Pinion Gate	BSBK Engineers Pvt. Ltd., Kolkata/ Noida	Approved
		BEVCON, Hyderabad	Not Approved
39	Lubrication System for SCR	CENLUB, KOLKATA	Approved
40	Buffer for SCR	Resistoflex Pvt. Ltd. KOLKATA	Approved
41	Geared Motor	Elecon, VALLABH VIDYANAGAR-GUJRAT	Approved
		Siemens Ltd, GERMANY/Bangalore	Approved
42	BELT FEEDERS	BEVCON, Hyderabad	Not Approved

S. NO	Item description	Name of the vendor	TSGENCO Remarks
43	TRAVELLING TRIPPERS,FIXED TRIPPERS & RAILS,COUNTER WEIGHTS	BEVCON, Hyderabad	Not Approved
44	TRIPPERS,FIXED TRIPPERS & Bunker Sealing Arrangement	BSBK, Kolkata / Noida	Approved
45	Duplex Strainers	M/s. Flair Strainers & Filters, Ahmedabad, Gujarat	Approved
46	Pipes	M/s. Jindal (India) Ltd. INDIA	Approved
47	Pipe fittings	M/s. N L Hazra & Son, KOLKATA	Approved
48	Ventilation fans	M/s. SK Systems Private Limited, New Delhi	Approved
49	Unitary air filtration (UAF) system	M/s. SK Systems Private Limited, New Delhi	Approved
50	Air pressure regulator & filter with pressure gauge	M/s. Asco Numatics (India) Pvt Ltd, CHENNAI	Approved
51	Water pressure regulator with pressure gauge	M/s. Asco Numatics (India) Pvt Ltd, CHENNAI	Approved
52	Hydraulic system	M/s Hagglunds, SWEDEN	Approved
		M/ s Maha Hydraulics, Chennai	Approved
		M/ s Rexroth, Ahmedabad, Gujarat	Approved

Please note that this approval of above vendors for the supply of Coal Handling Package for 5X800MW Yadadri Thermal Power Station does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

CHIEF ENGINEER/TPC

Copy to:

1. Executive Director/Civil/Thermal/TSGENCO/VS/Hyderabad.
2. Superintending Engineer/Civil/YTPS(5X800MW)/Dameracherla
3. FA & CCA/Accounts/TSGENCO/VS/Hyderabad.
4. SE /Tech. to CMD/TSGENCO/VS/Hyderabad.
5. DE /Tech. to Director/Projects/TSGENCO/VS/Hyderabad.
6. Sri Y.A.Srinivasa Rao,GM(PMG)/BHEL Camp Office/Vidyut Soudha/Hyderabad.

	TELANGANA STATE POWER GENERATION CORPORATION LIMITED **(A Govt. of Telangana Undertaking)** Vidyut Soudha, Hyderabad - 500082. www.tsgenco.telangana.gov.in Phone: 040 – 23499261 Fax: 040 – 23499263.

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, Vidyut Soudha, Khairatabad, Hyderabad-500 082. Email ID: cetpctgenco@gmail.com	M/s Bharat Heavy Electrical Ltd., INDUSTRIAL SYSTEMS GROUP P O Box No.1249, Prof CNR Rao Circle , Malleswaram, Banglore-560012. Mail ID: rsp@bhel.in

Lr.No.CE/TPC/SE-5/EME-09/YTPS(5X800MW)/F.NO.9/D.No.122/19,Dt: 401.2019.

Sir,

Sub: TSGENCO – Yadadri TPS(5X800MW) – Approval of additional vendors for 'Machine Package', 'Conveyor Package' of Coal Handling Plant for (5X800 MW) Yadadri Thermal Power Station furnished by M/s BHEL/ISG - Reg.

Ref: 1. M/s BHEL Letter Ref: IS-1-15-2001/Additional Vendors-machine, Dt: 25.10.2018
2. M/s BHEL Letter Ref: IS-1-15-2001/CHP-Conv.Pkg.addl.Vendors,Dt:29.11.2018
3. Lr.No.CE/TPC/SE3/EME-09/YTPS(5X800MW)/F.No.vendors/D.No.109/18, Dt:9.11.2018

*****

This has reference to the letters 1st & 2nd cited above, wherein M/s BHEL/ISG requested for approval of additional vendor for 'Machine Package', 'Conveyor Package' of Coal Handling Plant for (5X800 MW) Yadadri Thermal Power Station. Vide reference 3rd cited certain vendors were approval accorded by TSGENCO for CHP package. The credentials of vendors are reviewed and TSGENCO hereby accords approval for the following additional vendors for 'Machine Package', 'Conveyor Package' of Coal Handling Plant.

(a) Machine Package:

S. No	BHEL proposed vendor Name	Approval requested	TSGENCO Remarks
1	Thyssenkrupp Industries India Pvt, Ltd. Pune	screens	Approved
2	McnallyBharat Engineering Ltd, Kolkata	Paddle feeder	Not Approved
3	Tenova India Pvt. Ltd, Chennai	Machine Package	Approved for 'Stacker & Reclaimer' and 'Wagon Tippler'only.
4	M/s Furnance fabrica India Ltd, Kolkata.	Machine Package	Not Approved
5	Hunan Changzhong Machinery C.Ltd, China	Machine Package	Not Approved

(b) Conveyor Package:

S. No	BHEL proposed vendor Name	Approval requested	TSGENCO Remarks
1	M/s Mecon Limited, Ranchi	Conveyor package	Approved
2	M/s Datang Environment Industry Group Co .Ltd ,China	Conveyor package	Not Approved

Please note that this approval of additional vendor for 'Machine Package', 'Conveyor Package' of Coal Handling Plant for (5X800 MW) Yadadri Thermal Power Station, does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Yours faithfully,

CHIEF ENGINEER/TPC

Copy communicated to:

1. The Chief Engineer/Civil/TSGENCO/VS/Hyderabad.
2. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
3. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.

Copy to:

1. SE/Tech to the Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
2. Superintending Engineer-3/TPC/VS/Hyderabad.
3. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
4. Sri Y.A.Srinivas Rao,GM, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.
5. Sri N D Gautam / Sr.Deputy General Manager/PMG/ New Delhi
6. DE/Tech to the Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. ADE/Tech to the Director/Civil/TSGENCO/VS/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. M/s.TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad

	TELANGANA STATE POWER GENERATION CORPORATION LIMITED **(A Govt. of Telangana Undertaking)** Vidyut Soudha, Hyderabad - 500082. www.tsgenco.telangana.gov.in Phone: 040 – 23499261 Fax: 040 – 23499263.
From: The Chief Engineer, Thermal Projects Construction, TSGENCO, Vidyut Soudha, Khairatabad, Hyderabad-500 082. Email ID: cetpctgenco@gmail.com	To: M/s Bharat Heavy Electrical Ltd., INDUSTRIAL SYSTEMS GROUP P O Box No.1249, Prof CNR Rao Circle , Malleswaram, Banglore-560012. Mail ID: rsp@bhel.in

Lr.No.CE/TPC/SE-5/EME-09/YTPS(5X800MW)/F.NO.9/D.No.122/19,Dt:4.01.2019.

Sir,

Sub: TSGENCO – Yadadri TPS(5X800MW) – Approval of additional vendors for 'Machine Package', 'Conveyor Package' of Coal Handling Plant for (5X800 MW) Yadadri Thermal Power Station furnished by M/s BHEL/ISG - Reg.

Ref: 1. M/s BHEL Letter Ref: IS-1-15-2001/Additional Vendors-machine, Dt: 25.10.2018
2. M/s BHEL Letter Ref: IS-1-15-2001/CHP-Conv.Pkg.addl.Vendors,Dt:29.11.2018
3. Lr.No.CE/TPC/SE3/EME-09/YTPS(5X800MW)/F.No.vendors/D.No.109/18, Dt:9.11.2018

*****

This has reference to the letters 1st & 2nd cited above, wherein M/s BHEL/ISG requested for approval of additional vendor for 'Machine Package', 'Conveyor Package' of Coal Handling Plant for (5X800 MW) Yadadri Thermal Power Station. Vide reference 3rd cited certain vendors were approval accorded by TSGENCO for CHP package. The credentials of vendors are reviewed and TSGENCO hereby accords approval for the following additional vendors for 'Machine Package', 'Conveyor Package' of Coal Handling Plant.

(a) Machine Package:

S. No	BHEL proposed vendor Name	Approval requested	TSGENCO Remarks
1	Thyssenkrupp Industries India Pvt, Ltd. Pune	screens	Approved
2	McnallyBharat Engineering Ltd, Kolkata	Paddle feeder	Not Approved
3	Tenova India Pvt. Ltd, Chennai	Machine Package	Approved for 'Stacker & Reclaimer' and 'Wagon Tippler'only.
4	M/s Furnance fabrica India Ltd, Kolkata.	Machine Package	Not Approved
5	Hunan Changzhong Machinery C.Ltd, China	Machine Package	Not Approved

(b) Conveyor Package:

S. No	BHEL proposed vendor Name	Approval requested	TSGENCO Remarks
1	M/s Mecon Limited, Ranchi	Conveyor package	Approved
2	M/s Datang Environment Industry Group Co .Ltd ,China	Conveyor package	Not Approved

Please note that this approval of additional vendor for 'Machine Package', 'Conveyor Package' of Coal Handling Plant for (5X800 MW) Yadadri Thermal Power Station, does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Yours faithfully,

4/1/19

CHIEF ENGINEER/TPC

Copy communicated to:

1. The Chief Engineer/Civil/TSGENCO/VS/Hyderabad.
2. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
3. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.

Copy to:

1. SE/Tech to the Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
2. Superintending Engineer-3/TPC/VS/Hyderabad.
3. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
4. Sri Y.A.Srinivas Rao,GM, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.
5. Sri N D Gautam / Sr.Deputy General Manager/PMG/ New Delhi
6. DE/Tech to the Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. ADE/Tech to the Director/Civil/TSGENCO/VS/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. M/s.TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. of Telangana State Undertaking)
VIDYUTH SOUDHA, HYDERABAD-500082.
www.tsgenco.telangana.gov.in
Phone:040-23499321, Fax:040-23499323

From:	To:
The Executive Director/TPC A-Block,2nd Floor,TSGENCO, Vidyuth Soudha, Hyderabad-500 082.	M/s Bharat Heavy Electricals Limited, Power Sector-Project Engineering Management, PPEI Building, Sector-16A, Noida. Email ID: permindersingh@bhel.in

Kind Attention:Sri Perminder Singh, AGM.

Lr NO. ED/TPC/SE-3/EME-11/YTPS/F. PEM Cat Plan / D.No.13 /18,Dt:29.03.2018

Sir,

Sub: TSGENCO - YTPS (5X800MW) – Categorization Plan for PEM BOP/BOI packages (Rev.00) – Approval - Reg.

Ref: 1.LOI.No.ED/TPC/SE-III/EME-9/YTPS (5X800MW)/D.No.102/17, Dt.17.10.2017.
2. M/s BHEL letter Vide Ref: PS-PEM/PG-IV/TSGENCO/YADADRI/02,Dt:23-02-2018.

* * * * * *

Please refer to your letter 2nd cited above, wherein it was requested for approval of Categorization Plan for BOP/BOI packages (Rev.00) of PEM supplied items for YTPS (5x800MW). In this regard, it is to inform that as per the request of M/s BHEL,PEM the Categorization Plan is approved and the approved categorization plan is enclosed as Annexure-I.

Encl: As above

Yours faithfully,

EXECUTIVE DIRECTOR/TPC

Copy to:

1. Chief Engineer/ Electrical/YTPS Site/ Damara cherla/ Nalgonda Dist.
2. SE/Tech to the Chairman & Managing Director/TSGENCO/VS/Hyderabad.
3. DE/Tech to Director/Projects/TSGENCO/VS/Hyderabad.
4. M/s Tata Consulting Engineers, 73/1, Sheriff Centre, St. Marks Road, Bangalore-560 001.
5. Mr.Y.A.Srinivasa Rao, GM/BHEL Camp Office/Vidyuth Soudha/Hyderabad.

ANNEXURE-I

YADADRI (5X800 MW) –TSGENCO Approved Categorization for BHEL- PEM BOI & BOP packages

Sl.No.	Packages	Category Code proposed	Category Code approved
	CONTROL & INSTRUMENTATION		
1	CONTROL VALVE	I	I
2	FLOW ELEMENT - NOZZLE	I	I
3	FLOW ELEMENT - ORIFICE	I	I
4	ULTRASONIC FLOW METERS	III	II
	CIVIL		
Sl.No.	**Packages**	**Category Code proposed**	**Category Code approved**
5	VIS FOR BFP FOUNDATION	I	I
	ELECTRICAL		
Sl.No.	**Packages**	**Category Code proposed**	**Category Code approved**
6	ABOVE GROUND EARTHING MATERIALS	II	II
7	CABLE TERM.& JOINT KITS *	II	II
8	CABLE TRAY SUPPORT SYSTEM - WELDED(GALV)	II	II
9	CABLE TRAYS & ACC.	II	II
10	DC BATTERY CHARGER	I	I
11	DC LEAD ACID BATTERIES	I	I
12	ELECTRICAL LAB EQUIPMENT	I	I
13	FIRE SEALING SYSTEM	I	I
14	HT POWR CABLES	I	I
15	LT CONTROL CABLE	I	I
16	LTFIRE SURVIVAL CABLES	I	I
17	LT POWER CABLE	I	I
18	GENERATOR CIRCUIT BREAKER	I	I
19	MS ROD FOR BELOW GROUND EARTHING	III	II
20	NEUTRAL GROUNDING RESISTOR	I	I
21	PA SYSTEM	I	I
22	SCREENED CONTROL CABLES	I	I
23	SERVICE TRANSFORMER	I	I
24	STATION LIGHTING SYSTEM	II/III FOR LP, LDBS & FIXTURES-CAT-I	I/II ** FOR LP, LDBS & FIXTURES-CAT-I
25	TREFOIL CLAMPS	II	II
	MECHANICAL		
Sl.No.	**Packages**	**Category Code proposed**	**Category Code approved**
26	AIRCONDITIONING SYSTEM	II	I
27	CHAIN PULLEY BLOCK	III	III
28	CHEMICAL DOSING SYSTEM	III	II

* cable terminatios are to be procured strictly as per L2 schedule as there are low shelf life items

EXECUTIVE DIRECTOR/TPC

Sl.No.	Packages	Category Code proposed	Category Code approved
29	COMPRESSED AIR SYSTEM	I/II For Compressors, Air Dryers & Receivers-CAT-I	I/II ** For Compressors, Air Dryers & Receivers-CAT-I
30	D/G EOT CRANE ABOVE 45T-150T	I	I
31	D/G EOT CRANES UPTO 45T	II	II
32	ELECTRIC HOIST	II	II
33	ELEVATORS	I	I
34	FIRE TENDER	II	I
35	FUEL OIL HANDLING AND STORAGE SYSTEM	I/II	I/II **
36	LUBE OIL TRANSFER PUMPS	II	II
37	MILL REJECT SYSTEM	II	I/II **
38	MISC. TANKS(SITE FABRICATED) ONLY ENGG	II	II
39	OXYGEN DOSING SYSTEM	II	II
40	Single Girder EOT / HOT Misc. Cranes	II	II
41	VENTILATION SYSTEM	II	II
42	WEIGH BRIDGE	II	II
43	AIR RELEASE VALVES	II	II
44	AIR TRAPS	II	II
45	ALUMINIUM SHEETS/COILS	III	III
46	BALL VALVES	II	II
47	BUTTERFLY VALVES (STEAM SERVICE)	II For sizes over 600NB-CAT-I	II For sizes over 600NB-CAT-I
48	M.E. BELLOWS	II For sizes over 600NB-CAT-I	II For sizes over 600NB-CAT-I
49	STEAM TRAPS	II	II
50	STEEL GATE/GLOBE/NR VALVES(WATER SYSTEM)	II	II
51	THERMAL INSULATION - R-MATTRESSES/P-SECN	II	II
52	THERMAL INSULATION -ANCILLARY MATERIAL	III	III
53	APRDS	I	I
54	COLTCS	II	I
55	COOLING TOWER	I	I
56	DEBRIS FILTER	II	II
57	HEAT EXCHANGER (PLATE TYPE)	I	I
58	MISC. PUMPS (HORIZONTAL)	I/II For pumps with more than 75KW power requirement-CAT-I.	I/II ** For pumps with more than 75KW power requirement-CAT-I.

EXECUTIVE DIRECTOR/TPC

Sl.No.	Packages	Category Code proposed	Category Code approved
59	MISC. PUMPS (VERTICAL)	I/II For pumps with more than 75KW power requirement-CAT-I.	I/II ** For pumps with more than 75KW power requirement-CAT-I.
60	SELF CLEANING STRAINERS	II	II
61	CONICAL STRAINER	II	II
62	SUMP PUMPS/SUBMERSIBLE PUMPS	II	II
63	CONDENSATE POLISHING UNIT	II	I/II **
64	HYDROGEN GENERATION PLANT	II	I/II **
65	WORKSHOP EQUIPMENT	III	I/II **

NOTE:			
INSPECTION CATEGORY	**QAP APPROVAL BY**	**INSPECTION BY**	**MDCC BY**
I	CUSTOMER/CONSULTANT	CUSTOMER/CONSULTANT/ CUSTOMER appointed TPIA (Final inspection including document review as per approved QAP)	TSGENCO
II	CUSTOMER/CONSULTANT	BHEL or BHEL'S TPIA	TSGENCO on submission of TC/IR/documents.
III	BHEL	Testing by vendor s Quality dept. & TCs Shall be submitted to BHEL	BHEL
I/II**	BHEL has to submit the Sub-Breakup for Approval.		
For the items/Equipments which are not covered in the above list, BHEL has to submit such items to TSGENCO for Approval.			

29/05

EXECUTIVE DIRECTOR/TPC

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082. www.tsgenco.telangana.gov.in

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, Vidyut Soudha, Khairatabad, Hyderabad-500 082. E-Mail:cetpctgenco@gmail.com	M/s BHEL/EDN, Electronics Division, P.O. Box No.2606, Mysore Road, Banglore-560 026. E-Mail:abhilashreddy@bheledn.co.in

Lr.No.CE/TPC/421/YTPS (5X800 MW)/C&I-Vendors/D.No.135 /19, Dt:30.07.2019.

Sir,

Sub: TSGENCO – YTPS (5X800MW) – Controls & Instrumentation-Comments on Additional Vendor approval for supply of Electronic Transmitter as proposed by M/s BHEL/EDN - Reg.

Ref: 1) Lr. No. CE-PMC/YTPS/VL/AR-43, dt.22.06.2019,
2) M/s TCE email dated:27.06.2019.

* * *

This has reference to the M/s BHEL/EDN request letter (1) cited above regarding additional vendor approval for supply of Electronic Transmitter for YTPS (5X800MW).

In this regard, it is to inform that after careful review of credentials by TSGENCO and as per M/s TCE comments vide reference(2) above, M/s Toshniwal Industries Pvt Ltd is here with not approved as additional vendor for the supply of electronic transmitters for YTPS(5X800MW).

Yours faithfully

P V Sai 30/7/19

CHIEF ENGINEER/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
3. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
4. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
5. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
6. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
7. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
8. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
9. Sri Y.A.Srinivas Rao, BHEL/PMG, Vidyut Soudha, Hyderabad.

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
VIDYUT SOUDHA::HYDERABAD - 500082.

CIN: U40102TG2014SGC094070 Phone:040 – 23499261,Fax:040–23499263.
Web site: www.tsgenco.co.in email id: cetpctgenco@gmail.com

From:	To:
Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL/Trichy, High Pressure Boiler Plant, Tiruchirappalli-620 014, Tamil Nadu, INDIA. (P):0431-257-7156, Mob:9406903625, Email: rtoppo@bhel.in

Kind Attention:Sri RAHUL TOPPO, Dy. Manager, Comml/FB

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 139/20,Dt: 29 .06.2020

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of Additional Vendors for Mechanical items furnished by M/s BHEL/Trichy unit - Reg.

Ref: M/s BHEL/Trichy letter TP/11497/Vendor List/06 dated 21.12.2019.

******

Please refer to the letter cited above, wherein M/s BHEL/Trichy has requested for approval of Additional Vendors for Mechanical items pertaining to Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of list of items as per Annexure does not absolve M/s BHEL/Trichy of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: Annexure

Yours faithfully,

27/6/20

Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. Superintending Engineer/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri S.Anil Kumar, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

Annexure

M/s BHEL/Trichy Additional Vendor approval list of Mechanical items for Yadadri TPS (5X800MW)

M/s BHEL Lr Ref No: TP/11497/Vendor List/06, Dt:21.12.2019

Sl. No.	Name of System/ Package	Name of Vendors	TSGENCO Remarks
1.	INSULATION: CASTABLE REFRACTORY	TRL KROSAKI REFRACTORIES LIMITED., BANGALORE	Approved
		REFCOM(INDIA) PVT LTD., PURULIA	Not Approved
		TOTALE GLOBAL PVT LTD, CHENNAI.	Not Approved
2.	INSULATION: WOOLMATTRESS	LION INSULATION PRIVATE LIMITED, KOLAR ROAD, BHOPAL	Not Approved
3.	INSLN: POURABLE INSULATION	TRL KROSAKI REFRACTORIES LIMITED., BANGALORE	Not Approved
		CHAMPION CERAMICS PVT LTD, CHAMPA	Approved
		TOTALE GLOBAL PVT LTD, CHENNAI.	Not Approved
4.	VALVE: BLOCK VALVE	DEMBLA VALVES LTD.,	Not Approved
5.	SDM: FITTINGS GI/CS/AS	COMFIT & VALVES PVTLTD. MEHESANA	Approved
		PRESHZINGER ENGINEERING CO PVT LTD. HYDERABAD	Approved
		FLUID CONTROLS PRIVATE LTD., MUMBAI	Not Approved
		DYNAFLUID VALVES AND FLOW, BELGAUM	Approved
		H.P.VALVES & FITTINGS INDIA PVT LTD, CHENNAI	Not Approved
		ARYA CRAFTS & ENGINEERING PVT.LTD., VADODARA	Not Approved
6.	STRAINERS: DUPLEX	BHATIA ENGINEERING COMPANY, DELHI	Approved
		GRAND PRIX ENGINEERING PVT. LTD., FARIDABAD	Not Approved
7.	FURNACE MAINTENANCE PLATFORM	ALTREX B.V,Netharlands	Approved

P.V. Sai 23/12/19

Chief Engineer/TPC

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263.

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL/RC Puram, Heavy Power Equipment Plant,R C Puram CONTRACT MANAGEMENT DEPARTMENT Hyderabad – 502 032 , INDIA Ph: 040-23182451,Mob:9491306087 Email: naickravi@bhel.in

Kind Attention:Mr. B. ravindra naick , Dy. Manager

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No.141/18,Dt:23.10.18

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of Vendors for Electrical , C&I and Mechanical items furnished by M/s BHEL/R C Puram/Hyderabad unit - Reg.

Ref: M/s BHEL/RC Puram/Hyderabad letter YTPS/VL/HYD/00, Dated 26.07.2018.

******

Please refer to the letter cited above, wherein M/s BHEL/R C Puram/Hyderabad has requested for approval of vendors for certain Electrical , C&I and Mechanical items for Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of following list of items does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: List of TSGENCO Approved Vendors of M/s BHEL/R C Puram/Hyd Unit.

Yours faithfully,

PV Seshu 23/10/18

Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/R C Puram/Hyderabad

Sl.No.	Name of System/ Package	Name of Vendor/Place	TSGENCO Remarks
		T&C VENDORS	
1	TRANSFER OIL PUMP	1.DELTA P D PUMPS PVT LTD.,MUMBAI	Approved
		2.HYDAC (INDIA) PVT. LTD., Maharashtra	Approved
		3.ALLWEILER INDIA PVT LTD(Note- Tushaco name change to Allweiler)	Approved
		4.IDEX INDIA PVT LTD	Not Approved
2	JACKING OIL PUMP CONSOLE	1.HYDAC (INDIA) PVT. LTD., Maharashtra.	Approved
		2.TUSHACO PUMP , DAMAN (Note- Tushaco name change to Allweiler)	Approved
		3.DELTA P D PUMPS PVT LTD. Vapi, Gujarat	Approved
		4.IDEX INDIA PVT LTD, Mumbai	Not Approved
3	TURBINE ENCLOSURE	1.LLOYD INSULATIONS (INDIA) LTD., New Delhi	Approved
		2.BBM ACOUSTIC INDIA PVT. LTD., Pune	Approved
		3.INDIRA INDUSTRIES, Ranipet	Approved
		4.ACOUSTICS INDIA PVT LTD., Thiruchirapalli	Approved
		5.HAROLD INDUSTRIES (P) LTD, Hyderabad	Approved
		6.CREST ENGINEERS (PVT) LIMITED, New Delhi	Not Approved
4	OPEN TYPE TRANSMITTER RACK	1.KRISHNA INDUSTRIES, Hyderabad	Not Approved
		2.PANAM CONTROLS, Secunderabad	Approved
		3.NAGARJUNA FABRICATORS, Hyderabad	Approved
		4.GEM PRESSURE SYSTEMS (INDIA), Secunderabad	Approved
5	PRESSURE AND	1.GAUGES BOURDON INDIA, Navi Mumbai	Approved

25/10/15

Chief Engineer/TPC

Sl.No.	Name of System/ Package	Name of Vendor/Place	TSGENCO Remarks
	DIFFERENTIAL PRESSURE SWITCHES	2.PRECISION MASS PRODUCTS PVT LTD, Gandhinagar, Gujarat	Approved
		3.TRAFAG CONTROLS INDIA PVT LTD, Gurgaon	Approved
		4.SWITZER PROCESS INSTRUMENTS, Chennai.	Approved
6	PRESSURE & DIFF. PRESSURE TRANSMITTERS (ELECTRONIC - SMART)	1.EMERSON PROCESS MGT (I) PVT LTD, Secunderabad	Approved
		2.ABB LIMITED, Hyderabad	Approved
		3.FUJI ELECTRIC SYSTEMS CO. LTD.,ANDHERI (EAST) MUMBAI	Approved
		4.YOKOGAWA INDIA LIMITED, Bangalore	Approved
		5.HONEYWELL AUTOMATION INDIA LIMITED, Pune	Approved
7	THERMOMETERS (BIMETALLIC)	1.GOA INSTRUMENTS INDUSTRIES, Mapusa ,GOA.	Approved
		2.ASHCROFT INDIA PVT. LTD-Gujarat, GANDHINAGAR	Approved
		3.H.GURU INSTRUMENTS(S.I) PVT.LTD, Bangalore	Approved
		4.BAUMER TECHNOLOGIES, VAPI	Approved
		5.GAUGES BOURDON INDIA, Navi Mumbai	Approved
		6.THERMAL INSTRUMENT INDIA, Maharashtra	Not Approved
		7.WALCHANDNAGAR INDUSTRIES LIMITED,DHARWAD,KARNATAKA	Approved
		8.NESSTECH INSTRUMENTS PVT LTD, Vapi, Gujarath	Approved
		9.PRECISION MASS PRODUCTS PVT LTD, Gandhinagar, Gujarat	Approved
8	TEMPERATURE TRANSMITTER	1.EMERSON PROCESS MGT (I) PVT LTD, Mumbai	Approved
		2.ABB LIMITED, HYD	Approved
		3.YOKOGAWA INDIA LIMITED, Bangalore	Approved

PV Sooraj 25/10/11

Chief Engineer/TPC

Sl.No.	Name of System/ Package	Name of Vendor/Place	TSGENCO Remarks
		4.ENDRESS + HAUSER (INDIA) PVT. LTD., Mumbai	Approved
		5.HONEYWELL AUTOMATION INDIA LIMITED, Pune	Approved
9	LUBE OIL CONTROL VALVE (SELF REGULATING TYPE)	1.SAMSON AG MESS- UND REGELTECHNIK, Germany	Approved
		2.NUOVO PIGNONE SRL.BARI,ITALY	Approved
		3.SAMSON CONTROLS PVT LTD.,PUNE	Approved
		4.EMERSON PROCESS MANAGEMENT, Chennai	Approved
		5.NIRMAL INDUSTRIAL CONTROLS PVT LTD, Mumbai	Not Approved
		6.RK CONTROL INSTRUMENTS PVT LTD, Chennai	Not Approved
10	AIR FILTER REGULATORS	1.VELJAN HYDRAIR PVT. LTD. Hyderabad	Approved
		2.ABB LIMITED, Hyderabad	Approved
		3.SHAVO NORGERN I.PVT.LTD., Mumbai	Approved
		4.PLACKA INSTRUMENTS INDIA, Chennai	Approved
11	FRP JUNCTION BOXES	1.BALIGA LIGHTING EQUIPMENT PVT. LTD., Chennai	Approved
		2.DEVI POLYMERS PVT. LTD., Chennai	Approved
		3.HENSEL ELECTRIC INDIA PVT. LTD., Chennai	Approved
		4.SUCHITRA INDUSTRIES, Bangalore	Approved
		5.MANISHA COMPOSITEK PVT. LTD., Pune	Approved
		6.Arham Hi-Tech Design and Solution, Mumbai	Not Approved
PUMPS PRODUCT			
12	LIR WITH TRANSMITTERS	1.PANAM CONTROLS, Hyderabad, INDIA	Approved
		2.NAGARJUNA FABRICATORS, Hyderabad, INDIA	Approved
		3.INSTRUMENTATION LTD., Palakkad	Approved

PU Sastry 23/10/18

Chief Engineer/TPC

Sl.No.	Name of System/ Package	Name of Vendor/Place	TSGENCO Remarks
		4.PYROTECH ELECTRONICS PVT.LTD., Udaipur, Rajasthan, INDIA	Approved
		5.PROCON INSTRUMENTATION PVT.LTD, Chennai, Tamilnadu, INDIA	Approved
		COMMON ITEMS	
13	DIFFERENTIAL PRESSURE INDICATOR / GAUGES	1.A.N. INSTRUMENTS PVT. LTD., New Delhi ,INDIA	Approved
		2.GOA STATIC INSTRUMENTS, GOA	Approved
		3.H.GURU INSTUMENTS (SI) PVT.LTD, Bangalore, Karnataka	Approved
		4.GENERAL INSTRUMENT CONSORTIUM, Hyderabad, TELANGANA	Approved
		5.GAUGES BOURDON INDIA,NAVI MUMBAI	Approved
		6.BAUMER TECHNOLOGIES, MUMBAI	Approved
		7.SWITZER PROCESS INSTRUMENTS,CHENNAI	Approved
		8.SWITZER INSTRUMENTS LTD,MUMBAI, Maharashtra	Approved
		9.WIKA INSTRUMENTS INDIA PVT.LTD,Pune, INDIA	Approved
		10.PRECISION MASS PRODUCTS PVT LTD, Gandhinagar, Gujarat	Approved
		11.WALCHANDNAGAR INDUSTRIES LIMITED, Pune, Maharashtra	Approved
14	LT AC MOTORS	1.ABB LTD, Secunderabad	Approved
		2.BHARAT BIJLEE LIMITED, Mumbai	Approved
		3.CG POWER & INDUSTRIAL SOLUTIONS LTD,Ahmednagar, Maharashtra	Approved
		4.CROMPTON GREAVES LTD. Ahmednagar, Maharashtra	Approved
		5.KIRLOSKAR ELECTRIC CO LTD, Bangalore	Approved
		6.LAXMI HYDRAULICS PVT LTD, secunderabad	Approved
		7.SIEMENS INDIA LTD, CHENNAI	Approved

23/10/18

Chief Engineer/TPC

Sl.No.	Name of System/ Package	Name of Vendor/Place	TSGENCO Remarks
15	PRESSURE GAUGES	1.A.N. INSTRUMENTS PVT. LTD., Chennai	Approved
		2.ASHCROFT INDIA PVT LTD , GUJARAT	Approved
		3.BAUMER TECHNOLOGIES, MUMBAI	Approved
		4.BELLS CONTROLS LIMITED, Kolkata.	Approved
		5.BUDENBERG GAUGE CO LTD, UK	Approved
		6.FORBES MARSHALL (HYD) PVT LIMITED, Hyderabad	Approved
		7.GAUGES BOURDON INDIA, NAVI MUMBAI	Approved
		8.GENERAL INSTRUMENT CONSORTIUM ,Mumbai, INDIA	Approved
		9.GOA INSTRUMENT INDUSTRIES PVT LTD,GOA	Approved
		10.GOA STATIC INSTRUMENTS, GOA	Approved
		11.H.GURU INSTRUMENTS (S.I)PVT.LTD, Bangalore	Approved
		12.MANOMETER INDIA PVT LTD, THANE	Approved
		13.PRECISION MASS PRODUCTS PVT LTD, Gandhinagar, Gujarat	Approved
		14.THERMAL INSTRUMENT INDIA, Maharashtra	Not Approved
		15.WAREE INSTRUMENTS LIMITED, Mumbai	Approved
		16.WIKA ALEXANDER WIEGAND GMBH & CO, Germany	Approved
		17.WIKA INSTRUMENTS INDIA PVT.LTD, Pune	Approved
16	THERMOMETERS & TEMPERATURE GAUGES (GAS FILLED)	1.A.N INSTRUMENTS PVT LTD CHENNAI	Approved
		2.ASHCROFT INDIA PVT.LTD-GUJARATH	Approved
		3.BAUMER TECHNOLOGIES, VAPI	Approved
		4.BUDENBERG GAUGE CO LTD, UK	Approved

PV Sonia 23/10/19

Chief Engineer/TPC

Sl.No.	Name of System/ Package	Name of Vendor/Place	TSGENCO Remarks
	THERMOMETERS & TEMPERATURE GAUGES (GAS FILLED)	5.FORBES MARSHALL (HYD) PVT LIMITED, Hyderabad	Approved
		6.GAUGES BOURDON INDIA , NAVI MUMBAI	Approved
		7.GENERAL INSTRUMENTS CONSORTIUM, MUMBAI	Approved
		8.GOA INSTRUMENTS INDUSTRIES PVT LTD,GOA	Approved
		9.H.GURU INSTRUMENTS (S.I)PVT.LTD , BANGALORE	Approved
		10.NESSTECH INSTRUMENTS PVT LTD,Vapi, Gujarath	Approved
		11.NEW SCIENTIFIC REPAIRS TRADING CO, KOLKATA	Approved
		12.PRECISION MASS PRODUCTS PVT LTD, Gandhinagar, Gujarat	Approved
		13.PRESSURE & TEMPERATURE CONTROL, KOLKATA	Approved
		14.PYRO ELECTRIC INSTRUMENTS GOA P LTD,GOA	Approved
		15.WALCHANDNAGAR INDUSTRIES LIMITED, Pune	Approved

PV Soni 23/10/16

Chief Engineer/TPC

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL/Ranipet,Boiler Auxiliaries Plant, Indira Gandhi Industrial Complex, COMMERCIAL DEPARTMENT RANIPET - 632 406. INDIA Phone:(04172) 284817,Mob:9848265808 Email: mmahesh@bhel.in

Kind Attention: Mahesh M, Dy. Manager/Commercial

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No.142/18,Dt:23.10.18

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of Vendors for Electrical , C&I and Mechanical items furnished by M/s BHEL/Ranipet unit - Reg.

Ref: 1.M/s BHEL/Ranipet letter BAP:COMML:R827-R831 & R4L4:VENDOR LIST:REV00, Dated 31.07.2018.

2.M/s BHEL/Ranipet e-Mail dated 18.08.2018(For deletion of vendors).

******

Please refer to the letter/e-Mail cited above, wherein M/s BHEL/Ranipet has requested for approval of vendors for certain Electrical , C&I and Mechanical items for Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of following list of items does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: List of TSGENCO Approved Vendors of M/s BHEL/Ranipet Unit.

Yours faithfully,

23/10/18

Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

Annexure

YADADRI TPS(5X800MW) Approved Vendors List - M/s BHEL/Ranipet

Sl. No.	Name of System/ Package	Name of Vendors	Place	TSGENCO Remarks
1	Auxiliary Control Panel/LT Main Switch Board (Draw Out Type)	1.BHEL-EPD	BENGALURU	Approved
		2.C & S Electric Limited	New Delhi	Not Approved
		3.Controls and Schematics Limited	Hyderabad	Approved
		4.GE India Industrial Pvt Ltd	Bangalore	Approved
		5.L & T	Chennai	Approved
		6.Nitya Electrocontrols Private Limited	Noida	Not Approved
		7.BCH Electric Limited	New Delhi	Not Approved
		8.UNILEC Engineers Ltd	Gurgaon	Approved
2	ESP Switch Gear Panel (Draw Out Type)	1.BHEL-EPD	BENGALURU	Approved
		2.C & S Electric Limited	New Delhi	Not Approved
		3.Controls and Schematics Limited	Hyderabad	Approved
		4.GE India Industrial Pvt Ltd	Bangalore	Approved
		5.L & T	Chennai	Approved
		6.Nitya Electrocontrols Private Limited	Noida	Not Approved
		7.Schneider Electric India Pvt Ltd	Nasik	Approved
		8.Siemens	JOKA	Approved
		9.BCH Electric Limited	New Delhi	Not Approved
		10.UNILEC Engineers Ltd	Gurgaon	Approved
3	Lub oil system for FANS (ID, FD & PA)	1.PSI ENGINEERING SYSTEMS PVT LTD	CHENNAI	Approved
		2.CENLUB Industries Limited	FARIDABAD	Approved
		3.LINCOLN HELIOS(INDIA) LTD	Bengaluru	Approved
		4.SOUTHERN LUBRICATIONS PVT LTD	Bengaluru	Approved
		5.TA HYDRAULICS PVT LTD	Hyderabad	Not Approved
		6.YUKEN INDIA LTD	BENGALURU	Not Approved
		7.ANANDSHEEL HYDRAULICS PVT LTD	Hyderabad	Not Approved
		8.CENLUB Systems	Faridabad	Not Approved

P V Sooraj 23/10/17

Chief Engineer/TPC

		9.UNIQUE ENGINEERING ENTERPRISES PVT LTD	HYDERABAD	Not Approved
4	SPACER COUPLING FOR AXIAL FANS	1.CUBIC TRANSMISSIONS PVT LTD	HYDERABAD	Approved
		2.DIPL ING HERWARTH REICH GMBH	GERMANY	Not Approved
		3.SEIMENS LTD	Chennai	Approved
		4.ESCO COUPLING & TRANSMISSION PVT LTD.	BENGALURU	Not Approved
		5.KTR KUPPLUNGSTECHNIK Gmbh	GERMANY	Approved
		6.UNIQUE TRANSMISSION INDIA P LTD.	KOLKATA	Approved
		7.ESCO COUPLINGS NV	BELGIUM	Approved
		8.RATHI TURBOFLEX PVT LTD	PUNE	Approved
5	STEAM COIL AIR PRE HEATER	1.C DOCTOR INDIA PVT LTD	Ahmedabad	Approved
		2.PATEL AIRTEMP(INDIA) LTD	RAKANPUR	Approved
		3.BARODA EQUIPMENTS & VESSEL PVT LTD	BARODA	Approved
		4.C DOCTOR &COMPANY LTD	Coimbatore	Approved
		5.CHINTAMANI THERMAL TECHNOLOGIES PVT LTD	PUNE	Not Approved
		6.NU WAY HEATRANSFER PVT LTD	HYDERABAD	Not Approved
6	AIR RECEIVER	1.VEESONS ENERGY SYSTEM PVT LTD	TIRUCHIRAPALLI	Approved
		2.PATEL AIR TEMP(INDIA) LTD	RAKANPUR	Approved
		3.PATEL AIR TEMP(INDIA) LTD	MUMBAI	Approved
		4.C DOCTOR INDIA PVT LTD	AHMEDABAD	Approved
		5.PAR ENERGY INFRA PVT.LTD	Hyderabad	Approved
		6.AIRCON HANDLING SYSTEMS PVT LTD	BENGALURU	Approved
		7.JANTA ENGG & CO	FARIDABAD	Approved
		8.SRI RANG INDUSTRIES	Coimbatore	Approved
		9.BARODA EQUIPMENT &VESSELS PVT LTD	BARODA	Approved
		10.KTST Engineers Pvt Ltd	SINNAR, NASIK	Not Approved

PV Seeniv 25/10/17

Chief Engineer/TPC

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL/Ranipet,Boiler Auxiliaries Plant, Indira Gandhi Industrial Complex, COMMERCIAL DEPARTMENT RANIPET - 632 406. INDIA Phone:(04172) 284817,Mob:9848265808 Email: mmahesh@bhel.in

Kind Attention: Mahesh M, Dy. Manager/Commercial

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No.142/18,Dt:23.10.18

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of Vendors for Electrical , C&I and Mechanical items furnished by M/s BHEL/Ranipet unit - Reg.

Ref: 1.M/s BHEL/Ranipet letter BAP:COMML:R827-R831 & R4L4:VENDOR LIST:REV00, Dated 31.07.2018.

2.M/s BHEL/Ranipet e-Mail dated 18.08.2018(For deletion of vendors).

******

Please refer to the letter/e-Mail cited above, wherein M/s BHEL/Ranipet has requested for approval of vendors for certain Electrical , C&I and Mechanical items for Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of following list of items does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: List of TSGENCO Approved Vendors of M/s BHEL/Ranipet Unit.

Yours faithfully,

23/10/18

Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

Annexure

YADADRI TPS(5X800MW) Approved Vendors List - M/s BHEL/Ranipet

Sl. No.	Name of System/ Package	Name of Vendors	Place	TSGENCO Remarks
1	Auxiliary Control Panel/LT Main Switch Board (Draw Out Type)	1.BHEL-EPD	BENGALURU	Approved
		2.C & S Electric Limited	New Delhi	Not Approved
		3.Controls and Schematics Limited	Hyderabad	Approved
		4.GE India Industrial Pvt Ltd	Bangalore	Approved
		5.L & T	Chennai	Approved
		6.Nitya Electrocontrols Private Limited	Noida	Not Approved
		7.BCH Electric Limited	New Delhi	Not Approved
		8.UNILEC Engineers Ltd	Gurgaon	Approved
2	ESP Switch Gear Panel (Draw Out Type)	1.BHEL-EPD	BENGALURU	Approved
		2.C & S Electric Limited	New Delhi	Not Approved
		3.Controls and Schematics Limited	Hyderabad	Approved
		4.GE India Industrial Pvt Ltd	Bangalore	Approved
		5.L & T	Chennai	Approved
		6.Nitya Electrocontrols Private Limited	Noida	Not Approved
		7.Schneider Electric India Pvt Ltd	Nasik	Approved
		8.Siemens	JOKA	Approved
		9.BCH Electric Limited	New Delhi	Not Approved
		10.UNILEC Engineers Ltd	Gurgaon	Approved
3	Lub oil system for FANS (ID, FD & PA)	1.PSI ENGINEERING SYSTEMS PVT LTD	CHENNAI	Approved
		2.CENLUB Industries Limited	FARIDABAD	Approved
		3.LINCOLN HELIOS(INDIA) LTD	Bengaluru	Approved
		4.SOUTHERN LUBRICATIONS PVT LTD	Bengaluru	Approved
		5.TA HYDRAULICS PVT LTD	Hyderabad	Not Approved
		6.YUKEN INDIA LTD	BENGALURU	Not Approved
		7.ANANDSHEEL HYDRAULICS PVT LTD	Hyderabad	Not Approved
		8.CENLUB Systems	Faridabad	Not Approved

P V Sooraj 23/10/17

Chief Engineer/TPC

		9.UNIQUE ENGINEERING ENTERPRISES PVT LTD	HYDERABAD	Not Approved
4	SPACER COUPLING FOR AXIAL FANS	1.CUBIC TRANSMISSIONS PVT LTD	HYDERABAD	Approved
		2.DIPL ING HERWARTH REICH GMBH	GERMANY	Not Approved
		3.SEIMENS LTD	Chennai	Approved
		4.ESCO COUPLING & TRANSMISSION PVT LTD.	BENGALURU	Not Approved
		5.KTR KUPPLUNGSTECHNIK Gmbh	GERMANY	Approved
		6.UNIQUE TRANSMISSION INDIA P LTD.	KOLKATA	Approved
		7.ESCO COUPLINGS NV	BELGIUM	Approved
		8.RATHI TURBOFLEX PVT LTD	PUNE	Approved
5	STEAM COIL AIR PRE HEATER	1.C DOCTOR INDIA PVT LTD	Ahmedabad	Approved
		2.PATEL AIRTEMP(INDIA) LTD	RAKANPUR	Approved
		3.BARODA EQUIPMENTS & VESSEL PVT LTD	BARODA	Approved
		4.C DOCTOR &COMPANY LTD	Coimbatore	Approved
		5.CHINTAMANI THERMAL TECHNOLOGIES PVT LTD	PUNE	Not Approved
		6.NU WAY HEATRANSFER PVT LTD	HYDERABAD	Not Approved
6	AIR RECEIVER	1.VEESONS ENERGY SYSTEM PVT LTD	TIRUCHIRAPALLI	Approved
		2.PATEL AIR TEMP(INDIA) LTD	RAKANPUR	Approved
		3.PATEL AIR TEMP(INDIA) LTD	MUMBAI	Approved
		4.C DOCTOR INDIA PVT LTD	AHMEDABAD	Approved
		5.PAR ENERGY INFRA PVT.LTD	Hyderabad	Approved
		6.AIRCON HANDLING SYSTEMS PVT LTD	BENGALURU	Approved
		7.JANTA ENGG & CO	FARIDABAD	Approved
		8.SRI RANG INDUSTRIES	Coimbatore	Approved
		9.BARODA EQUIPMENT &VESSELS PVT LTD	BARODA	Approved
		10.KTST Engineers Pvt Ltd	SINNAR, NASIK	Not Approved

PV Seeniv 25/10/17

Chief Engineer/TPC

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL/Trichy, High Pressure Boiler Plant, Tiruchirappalli-620 014, Tamil Nadu, INDIA. (P):0431-257-7156, Mob:9406903625, Email: rtoppo@bhel.in

Kind Attention:Sri RAHUL TOPPO, Dy. Manager, Comml/FB

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No.143/18,Dt:23.10.18

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of Vendors for Electrical , C&I and Mechanical items furnished by M/s BHEL/Trichy unit - Reg.

Ref: M/s BHEL/Trichy letter TP/11497/Vendor List/02 dated 23.07.2018.

******

Please refer to the letter cited above, wherein M/s BHEL/Trichy has requested for approval of vendors for certain Electrical , C&I and Mechanical items for Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of following list of items does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: List of TSGENCO Approved Vendors of M/s BHEL/Trichy Unit.

Yours faithfully,

23/10/18

Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/Trichy

Sl. No.	Name of System/Package	Name of Vendors/Place	TSGENCO Remarks
1	BLOCK VALVE	1.INSTRUMENTATION LTD.,India	Approved
		2.GE OIL & GAS INDIA PRIVATE LIMITED. COIMBATORE India(old name DRESSER VALVE INDIA PRIVATE LTD,INDIA)	Approved
		3.R.K.CONTROL INSTRUMENTS PVT.LTD THANE India	Not Approved
		4.SAMSON CONTROLS PRIVATE LIMITED ,India	Approved
		5.KSB MIL CONTROLS LIMITED , India(Old name MIL CONTROLS LIMITED)	Approved
		6.AVCON CONTROLS PVT.LTD., India	Approved
		7.KOSO INDIA PRIVATE LIMITED. NASHIK. India	Not Approved
2	INSLN: CERAMIC WOOL	1.UNIFRAX INDIA LTD	Approved
		2.SIMOND FIBERTECH RAJKOT. India	Approved
		3.LLOYD INSULATIONS (INDIA) LIMITED, India	Approved
		4.MURUGAPPA MORGAN THERMAL CERAMICS L India	Approved
		5.SHREE CERAMIC FIBERS PVT LTD INDORE. India	Not Approved
3	CASTABLE REFRACTORY	1.CASTWEL INDUSTRIES , India	Approved
		2.MAHAKOSHAL REFRACTORIES PVT. LTD, India	Approved
		3.VISHWAKARMA REFRACTORIS PRIVATE , India	Approved
		4.CHAMPION CERAMICS PVT LTD, CHAMPA	Approved
		5.PREMIER REFRACTORIES OF INDIA KATNI India	Not Approved
		6.SHARADAA CERAMICS PVT. LTD., India	Approved
		7.BHASKAR REFRACTORIES&SW PIPES P LTD , India	Approved
		8.ABS REFRACTORIES PVT.LTD., India	Approved
		9.INDUSTRIAL ASSOCIATES, India	Approved
		10.DALMIA REFRACTORIES LIMITED , India	Approved
		11.SOUVENIOR CERAMICS , India	Approved
		12.OCL INDIA LTD, NEW DELHI	Approved
		13.VISHVA VISHAL ENGINEERING LTD ,India	Approved
		14.CALDERYS INDIA REFRACTORIES LTD., India	Approved
		15.PKV REFRACTORY PVT LTD, HOSPET India	Not Approved
4	FLOOR GRILLS	1.INDIANA GRATINGS PVT.LTD.	Approved
		2.RATAN PROJECTS & ENGG CO PVT LTD. KOLKATA. India	Approved
		3.GREATWELD ENGINEERNG PVT LTD	Approved
		4.BHOLARAM STEELS PVT.LTD	Approved
		5.ANKIT ELECTROGRATING RAIPUR. India	Approved
		6.VINFAB ENGINEERS INDIA PVT LTD, India	Approved
		7.PINAX STEEL INDUSTRIES PVT.LTD	Approved
		8.GALFAN ENGINEERS PRIVATE LTD	Approved
		9.PREMIER POWER PRODUCTS (CALCUTTA) KOLKATA. India	Approved

23/10/18

Chief Engineer/TPC

		10.KANADE ANAND UDYOG PVT LTD	Approved
5	INSLN:WOOL MATTRESS	1.MINSULATE MANUFACTURING COMPANY, JAMSHEDPUR	Approved
		2.DHANBAD ROCKWOOL INSULATION PVT LTD, JHARKAND	Approved
		3.HI-TEC ROCKFIBRE LTD, RAJNANDGAON	Approved
		4.POLYBOND INSULATION PVT.LTD., BHILAI India	Approved
		5.PUNJSTAR INSULATION FIBRE , India	Approved
		6.POLYBOND PROJECTS PVT LTD BHILAI. India	Not Approved
		7.GOENKA ROCKWOOL (INDIA) PVT LTD., RAIPUR (C.G) India	Approved
		8.ROCKWOOL INDUSTRIES NEW DELHI India	Approved
		9.ROCKWOOL (INDIA) LTD ,INDIA	Approved
		10.SHREERAM EQUITECH PVT. LTD., DISTRICT DURG India	Approved
		11.THERMOCARE ROCKWOOL (I) PVT. LTD. RAJNANDGAON India	Approved
		12.LLOYD ROCKFIBRES LTD India	Approved
		13.MINWOOL ROCK FIBRES LTD India	Approved
		14.JAMSHEDPUR MINERAL WOOL MFG.CO., India	Approved
6	INSLN:POURABLE INSUL	1.DALMIA REFRACTORIES LTD.	Approved
		2.INDUSTRIAL ASSOCIATES, India	Approved
		3.PREMIER REFRACTORIES OF INDIA KATNI India	Not Approved
		4.MAHAKOSHAL REFRACTORIES PVT. LTD,India	Approved
		5.ABS REFRACTORIES PVT.LTD.,India	Approved
		6.CASTWEL INDUSTRIES , India	Approved
		7.RAJASTHAN CERAMIC INDUSTRIES , India	Approved
		8.BHASKAR REFRACTORIES & SW PIPES P LTD , India	Approved
7	METAPOLY SHEET	1.MPIL STEEL STRUCTURES LTD., THANE India	Not Approved
		2.NATIONAL STEEL& AGRO INDUSTRIES	Approved
		3.MULTICOLOR STEELS (INDIA) PVT LTD.	Approved
		4.METCO ROOF PRIVATE LIMITED	Approved
		5.LLOYD INSULATIONS (INDIA) LIMITED, CHENNAI India	Approved
		6.GOVINDARAJA MUDALIAR SONS (P)LTD.	Approved
		7.BANSAL ROOFING PRODUCTS LIMITED	Approved
8	HEA IGNITOR ASSY	1.FIVES COMBUSTION SYSTEMS PVT. LTD , India	Approved
		2.TESI SPA ITALY Italy	Not Approved
		3.UNISON INDUSTRIES ,USA	Approved
		4.HAMWORTHY COMBUSTION ENGINEERING LTD , UK	Approved
		5.DURAG INDIA INSTRUMENTATION PVT. L , India	Approved
		6.HINDUSTAN THERMOMETERS, AMBALA India	Not Approved
9	VALVE: BUTTERFLY VALVE	1.STAFFORD CONTROLS LIMITED., CHENNAI India	Not Approved
		2.WEIR BDK VALVES-A unit of Weir ,India	Approved
		3.TYCO VALVES & CONTROLS INDIA P LTD , India	Approved
		4.INTER VALVE (INDIA) LTD, India	Approved
		5.DEMBLA VALVES LTD., THANE India	Not Approved
		6.MASCOT VALVES PVT. LTD AHMEDABAD India	Not Approved
		7.DELVAL FLOW CONTROLS PVT.LTD.	Approved

PV Sonawane 23/10/18

Chief Engineer/TPC

		8.GM ENGINEERING PVT LTD RAJKOT. India	Not Approved
10	KNIFE EDGE GATE VALV	1.BRAY CONTROLS INDIA PVT LTD- CHENNAI. India	Approved
		2.ORBINOX INDIA PVT. LTD.,India	Approved
		3.FOURESS ENGINEERING (I) LTD , India	Approved
		4.JASH ENGINEERING LIMITED, INDORE India	Not Approved
		5.GALAXY CONTROLS PVT LTD., CHENNAI India	Approved
11	SDM:BELLOWS:METALLIC	1.MADRAS HYDRAULIC HOSE PVT LTD CHENNAI India	Not Approved
		2.FLEXATHERM EXPANLLOW PVT LTD, India	Approved
		3.MB METALLIC BELLOWS PVT. LTD, India	Approved
		4.FLEXICAN BELLOWS & HOSES (P) LTD ,India	Approved
		5.LONE STAR INDUSTRIES CHENNAI India	Approved
12	Multicore Control Cable	1.CORDS CABLE INDUSTRIES LIMITED,India	Approved
		2.DELTON CABLES LIMITED, India	Approved
		3.GUPTA POWER INFRASTRUCTURE LTD KHURDA. India	Not Approved
		4.ASSOCIATED CABLES PVT LTD, India	Approved
		5.SPECIAL CABLES PVT LTD NEW DELHI. India	Not Approved
		6.PRESTIGE CABLE INDUSTRIES ,DELHI India	Not Approved
		7.THERMOCABLES LIMITED, India	Approved
		8.THERMO ELECTRIC INTERNATIONAL ,NETHERLANDS	Approved
		9.CMI LIMITED, DELHI India	Not Approved
		10.TEMPSENS INSTRUMENTS (I) PVT.LTD., UDAIPUR India	Not Approved
		11.SBEE CABLES (INDIA) LIMITED BANGALORE India	Not Approved
		12.ADVANCE CABLE TECHNOLOGIES (P) LTD, India	Approved
		13.CRYSTAL CABLE INDUSTRIES LTD., KOLKATA India	Approved
		14.MANOJ CABLES LIMITED. DELHI India	Not Approved
		15.TIRUPATI PLASTOMATICS PVT LTD. JAIPUR. India	Not Approved
		16.SUYOG ELECTRICALS LTD., BARODA India	Approved
		17.GOYOLENE FIBRES (I) PVT LTD. MUMBAI. India	Not Approved
		18.GEMSCAB INDUSTRIES LTD., DIST.ALWAR India	Approved
		19.MARUDHAR WIRES PRIVATE LIMITED CHENNAI India	Not Approved
		20.ULTRACAB (INDIA) LIMITED RAJKOT. India	Not Approved
		21.KEI INDUSTRIES LIMITED, NEW DELHI India	Approved
		22.POLYCAB WIRE PVT. LTD, India	Approved
		23.T C COMMUNICATIONS PVT LTD.,NEW DELHI	Approved
		24.DELTON CABLES LIMITED, NEW DELHI India	Approved
		25.MANSFIELD CABLE COMPANY LTD. NOIDA India	Not Approved
		26.ELKAY TELELINKS LIMITED, FARIDABAD India	Not Approved
		27.PARAMOUNT COMMUNICATION LTD, India	Approved
		28.KEC INTERNATIONAL LIMITED, CHENNAI India	Approved
		29.SPM POWER & TELECOM PVT LTD HYDERABAD. India	Not Approved
		1.PARAMOUNT COMMUNICATION LTD, NEW DELHI India	Not Approved
		2.SBEE CABLES (INDIA) LIMITED BANGALORE India	Not Approved
		3.SERVEL UDYOG (P) LTD ,INDIA	Approved

PV Sonawane 23/10/17

Chief Engineer/TPC

13	MULTIPAIR INSTRUMENT	4.GOYOLENE FIBRES (I) PVT LTD. MUMBAI. India	Not Approved
		5.TEMPSENS INSTRUMENTS (I) PVT.LTD., UDAIPUR India	Approved
		6.ASSOCIATED CABLES PVT LTD , India	Approved
		7.ADVANCE CABLE TECHNOLOGIES (P) LTD, India	Approved
		8.CMI LIMITED, DELHI India	Not Approved
		9.THERMOCABLES LIMITED, India	Approved
		10.POLYCAB, Daman	Approved
		11.MANSFIELD CABLE COMPANY LTD. NOIDA India	Not Approved
		12.UNIFLEX CABLES LIMITED , India	Approved
		13.INCAB, Pune	Approved
		14.KEI INDUSTRIES LIMITED, India	Approved
		15.KEC INTERNATIONAL LIMITED, India	Approved
		16.T C COMMUNICATIONS PVT LTD, India	Approved
		17.GEMSCAB INDUSTRIES LTD.,India	Approved
		18.SUYOG ELECTRICALS LTD., BARODA India	Approved
		19.GUPTA POWER INFRASTRUCTURE LTD KHURDA. India	Not Approved
		20.DELTON CABLES, Faridabad	Approved
		21.SPECIAL CABLES PVT LTD, India	Approved
		22.CORDS CABLES, Rajasthan	Approved
		23.ELKAY TELELINKS LIMITED, India	Approved
		24. ULTRACAB (INDIA) LIMITED RAJKOT. India	Not Approved
14	CABLE FLAME SCANNER	1.ADVANCE CABLE TECHNOLOGIES (P) LTD. BANGALORE India	Not Approved
		2.CORDS CABLE INDUSTRIES LIMITED., India	Approved
		3.THERMOCABLES LIMITED, India	Approved
		4.NICCO CORPORATION LTD , India	Approved
		5.DELTON CABLES LIMITED, India	Approved
		6.GOYOLENE FIBRES (I) PVT LTD. MUMBAI. India	Not Approved
15	ASH LEVEL SWITCH	1.NIVO CONTROLS , INDIA	Approved
		2.FLOWSTAR ENGINEERING PVT LTD FARIDABAD. India	Not Approved
		3.EIP ENVIRO LEVEL CONTROLS , India	Approved
		4.EIP BULK CONTROLS PVT.LTD, India	Approved
16	CCTV SYSTEM (Flame viewing)	1.SERTEL ELECTRONICS (P) LTD., CHENNAI India	Not Approved
		2.TOSHNIWAL INDUSTRIES PVT.LTD., India	Approved
		3.DURAG INDIA INSTRUMENTATION PVT. L BANGALORE India	Approved
		4.MIRION TECHNOLOGIES (IST) LTD , UK	Approved
		5.DIAMOND POWER SWEDEN AB , SWEDEN	Approved
		6.TLT ENGG. INDIA PVT.LTD., India	Approved
		7.HI-TECH SYSTEMS & SERVICES LTD., KOLKATA India	Not Approved
17	FLOW NOZZLES	1.MINCO (INDIA) PVT. LTD. GOA India	Approved
		2.INSTRUMENTATION LTD.,India	Approved
		3.STAR-MECH CONTROL(I) PVT. LTD. HADAPSAR, PUNE. India	Approved
		4.MINCO INDIA FLOW ELEMENTS PVT.LTD MUMBAI. India	Approved

P. V. Sconi 23/10/18

Chief Engineer/TPC

		5.GENERAL INSTRUMENTS CONSORTIUM, India	Approved
		6.ASIAN INDUSTRIAL VALVES AND INSTRUM ,India	Approved
		7.MICRO PRECISION PRODUCTS (P) LTD, India	Approved
		8.DYNAFLUID VALVES AND FLOW India	Approved
18	GAUGES:DP GAUGES	1.PRECISION MASS PRODUCTS PVT LTD GANDHINAGAR. India	Approved
		2.WALCHANDNAGAR INDUSTRIES LTD. DHARWAD. India	Approved
		3.WIKA INSTRUMENTS INDIA PVT.LTD , India	Approved
		4.GOA STATIC INSTRUMENTS ,GOA	Approved
		5.H GURU INSTRUMENTS(SI) P.LTD., India	Approved
		6.GENERAL INSTRUMENTS CONSORTIUM, India	Approved
		7.A.N.INSTRUMENTS PVT. LIMITED,India	Approved
		8.SWITZER INSTRUMENT LTD.,INDIA	Approved
19	GAUGES:PRESSURE GAUGE	1.BUDENBERG GAUGE CO LTD., UK	Approved
		2.GENERAL INSTRUMENTS CONSORTIUM, CHENNAI	Approved
		3.PRECISION MASS PRODUCTS PVT LTD GANDHINAGAR. India	Approved
		4.BAUMER TECHNOLOGIES INDIA PVT.LTD, India	Approved
		5.H GURU INSTRUMENTS(SI) P.LTD., BANGALORE	Approved
		6.WIKA INSTRUMENTS INDIA PVT.LTD, India	Approved
		7.GOA THERMOSTATIC INSTRUMENTS PVT. L ,GOA	Approved
		8.WALCHANDNAGAR INDUSTRIES LTD. DHARWAD. India	Approved
		9.A.N.INSTRUMENTS PVT. LIMITED, KOLKATA	Approved
20	TEMPERATURE GUAGES	1.A.N.INSTRUMENTS PVT. LIMITED, KOLKATA	Approved
		2.GENERAL INSTRUMENTS CONSORTIUM, CHENNAI	Approved
		3.PRECISION MASS PRODUCTS PVT LTD GANDHINAGAR. India	Approved
		4.H GURU INSTRUMENTS(SI) P.LTD., India	Approved
		5.GOA THERMOSTATIC INSTRUMENTS PVT. L GOA	Approved
		6.BAUMER TECHNOLOGIES INDIA PVT.LTD, India	Approved
		7.GOA INSTRUMENT INDUSTRIES PVT LTD, India	Approved
		8.WALCHANDNAGAR INDUSTRIES LTD. DHARWAD. India	Approved
21	LOCAL INSTRUMENT ENCLOSURE	1.SAJAS ELECTRICALS, TRICHY India	Not Approved
		2.PRAMMEN INDUSTRIES India	Approved
		3.INSTRUMENTATION LTD., India	Approved
		4.CHEMIN CONTROLS AND PONDICHERY India	Approved
		5.PYROTECH ELECTRONICS P.LTD(UNIT II) UDAIPUR India	Approved
22	LOCAL INSTRUMENT RAC	1.SAJAS ELECTRICALS, TRICHY India	Not Approved
		2.PRAMMEN INDUSTRIES India	Approved
		3.INSTRUMENTATION LTD., India	Approved
		4.CHEMIN CONTROLS AND PONDICHERY India	Approved
		5.PYROTECH ELECTRONICS P.LTD(UNIT II UDAIPUR India	Approved
23	VIBRATION MONITORING	1.BENTLY NEVADA INC, USA	Approved
		2.SHINKAWA ELECTRIC CO.LTD., TOKYO	Approved
		3.ROCKWELL AUTOMATION INDIA LIMITED , SAHIBABAD DIST. GHAZIABAD.	Approved
		4.IRD MECHANALYSIS LIMITED, MUMBAI	Approved

23/10/17

Chief Engineer/TPC

24	XLPE LT POWER CABLE	1.THERMOCABLES LIMITED, India	Approved
		2.CMI LIMITED, DELHI India	Not Approved
		3.PARAMOUNT COMMUNICATION LTD, India	Approved
		4.MANSFIELD CABLE COMPANY LTD. NOIDA India	Not Approved
		5.KEI INDUSTRIES LIMITED, India	Approved
		6.POLYCAB WIRE PVT. LTD, India	Approved
		7.ADVANCE CABLE TECHNOLOGIES (P) LTD. BANGALORE India	Not Approved
		8.KEC INTERNATIONAL LIMITED, CHENNAI India	Not Approved
		9.SBEE CABLES (INDIA) LIMITED BANGALORE India	Not Approved
		10.GEMSCAB INDUSTRIES LTD., India	Approved
		11.SRIRAM CABLES PVT.LTD., RAJASTHAN- India	Not Approved
		12.ASSOCIATED CABLES PVT LTD MUMBAI India	Not Approved
		13.ELKAY TELELINKS LIMITED, FARIDABAD India	Not Approved
		14.HAVELLS NEW DELHI	Approved
		15.UNIVERSAL CABLES ,SATNA	Approved
		16.GUPTA POWER INFRASTRUCTURE LTD KHURDA. India	Not Approved
		17.DELTON CABLES LIMITED, India	Approved
		18.CORDS CABLE INDUSTRIES LIMITED., India	Approved
		19.MANOJ CABLES LIMITED. DELHI India	Not Approved
		20.TIRUPATI PLASTOMATICS PVT LTD. JAIPUR. India	Not Approved
		21.SUYOG ELECTRICALS LTD., BARODA India	Approved
		22.CRYSTAL CABLE INDUSTRIES LTD., KOLKATA India	Approved
		23.GOYOLENE FIBRES (I) PVT LTD. MUMBAI. India	Not Approved
		24.PRESTIGE CABLE INDUSTRIES DELHI India	Not Approved
		25.SPECIAL CABLES PVT LTD NEW DELHI. India	Not Approved
		26.ULTRACAB (INDIA) LIMITED RAJKOT. India	Not Approved
		27.APAR INDUSTRIES LTD. MUMBAI India	Not Approved
25	HANDLING EQUIPMENT ELECTRICAL	1.MEGA CRANES INDIA PVT LTD COIMBATORE. India	Not Approved
		2.TECHNO INDUSTRIES, AHMEDABAD India	Not Approved
		3.CU-BUILT ENGINEERS PVT.LTD, PUNE India	Not Approved
		4.REVA INDUSTRIES LTD., FARIDABAD India	Approved
		5.GRIP ENGINEERS PVT LTD, India	Approved
		6.UNIVERSAL HOIST-O-FABRIK, India	Approved
		7.CONSOLIDATED HOISTS PVT LIMITED , India	Approved
		8.MANGLA HOIST PVT LTD NEW DELHI. India	Not Approved
		9.ARMSEL MHE PVT LTD India	Approved
		10.POWER BUILD LIMITED India.	Approved

PV Seriv 23/10/17

Chief Engineer/TPC

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
VIDYUT SOUDHA::HYDERABAD - 500082.
CIN: U40102TG2014SGC094070 Phone:040 – 23499261,Fax:040–23499263.
Web site: www.tsgenco.co.in email id: cetpctgenco@gmail.com

From:	To:
Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, VidyutSoudha, Khiarathabad Hyderabad-500 082.	M/s BHEL/Ranipet, Boiler Auxiliaries Plant, Indira Gandhi Industrial Complex, COMMERCIAL DEPARTMENT RANIPET - 632 406. INDIA Phone:(04172) 284817,Mob:9986789325 Email: pss@bhel.in

Kind Attention: P Somasekhar, Dy. Manager/Commercial

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No.158/20,Dt:10.08.2020

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of Vendors for Water System Package furnished by M/s BHEL/Ranipet unit - Reg.

Ref: M/s BHEL/Ranipet letter BAP:COMML: R4L9:Water package Vendors:Rev00, Dated 24.07.2020.

******

Please refer to the letter cited above, wherein M/s BHEL/Ranipet has requested for approval of vendors for Water System Package for Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of list of items as per Annexure does not absolve M/s BHEL/Ranipet of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: List of TSGENCO Approved Vendors of M/s BHEL/Ranipet Unit.

Yours faithfully,

10/8/2020

CHIEF ENGINEER/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. GM, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

Annexure

YADADRI TPS(5X800MW)- Approved Vendors List of Water System Package
M/s BHEL/Ranipet

Sl. No.	Name of System/ Package	Name of Vendor	TSGENCO Remarks
1.	Pre-treatment plant (PTP)	1. M/s. Clear Water Limited, New Delhi	Approved
		2. M/s. Gaja Engineering Private Ltd, Hyderabad	Approved
		3. M/s. Ion Exchange (India) Limited	Approved
		4. M/s. Effwa Infra & Research Pvt. Ltd, Thane	Not Approved
2.	Demineralization Plant (DMP)	1. M/s. Wipro Enterprises Pvt. Ltd, Mumbai	Approved
		2. M/s. BGR Energy Systems Ltd., Chennai	Approved
		3. M/s. Ion Exchange (India) Limited	Approved
3.	Cooling Water Treatment plant (CWTP)	1. M/s. Clear Water Limited, New Delhi	Approved
		2. M/s. Vasu Chemicals LLP, Mumbai	Approved
		3. M/s. Ion Exchange (India) Limited.	Approved
		4. M/s. Chembond Water Technologies Limited, Mumbai	Approved
		5. M/s. Dew Speciality Chemicals Pvt. Ltd, Noida	Not Approved
4.	Side Stream Filtration Plant (SSF)	1.M/s. Clear Water Limited, New Delhi	Not Approved
		2.M/s. Sureflo Techcon Pvt. Ltd, Mumbai	Approved
		3.M/s. Ion Exchange (India) Limited	Approved
		4.M/s. IEC Fabchem Limited, Gummudipoondi	Approved
		5.M/s. Otoklin Global Business Limited, Mumbai	Approved

10/9/2020

Chief Engineer/TPC

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263.

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, 3nd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL/RC Puram, Heavy Power Equipment Plant,R C Puram CONTRACT MANAGEMENT DEPARTMENT Hyderabad – 502 032 , INDIA Ph: 040-23182451,Mob:9491306087 Email: naickravi@bhel.in

Kind Attention:Mr. B. ravindra naick , Dy. Manager

Lr.No.CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No. 161 /18,Dt: 27.11.18

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Additional Vendor approval for SS seamless U tubes of HP heaters proposed by M/s BHEL/R C Puram/Hyderabad unit - Reg.

Ref: 1). M/s BHEL/RC Puram/Hyderabad letter YTPS/VL/HYD/00, Dated 26.07.2018.
2). Lr.No. ED/CE/TPC/SE-3/EME-14/YTPS/F.Vendors Approval/D.No.111/18, Dt:16.08.18
3). M/s BHEL/RC Puram/Hyderabad letter YTPS/VL/HYD/HP-01, Dated 05.09.2018.

******

Please refer to the letter 1st cited above, wherein M/s BHEL/R C Puram/ Hyderabad has requested for approval of vendors for heat exchangers as **"NO BOUGHT OUT ITEMS ARE THERE UNDER THIS CATEGORY. HOWEVER ALL THE RAW MATERIALS (TUBES, PLATES, TUBESHEET FORGINGS, DISHD ENDS HEMIHEAD ETC) REQUIRED FOR THE HEAT EXHCANGERS WHICH ARE UNDER BHEL HYD SCOPE OF SUPPLY WILL BE PROCURED FROM VENDORS AS PER BHEL PMD"** and approval has been accorded vide reference 2nd cited.

Further vide reference 3rd cited, M/s BHEL/R C Puram/Hyderabad requested for approval of additional vendor for the above item.

In this connection it is to inform that the approval issued from this office vide ref (2) cited holds good.

Yours faithfully,
23/11/18
CHIEF ENGINEER/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

	TELANGANA STATE POWER GENERATION CORPORATION LIMITED (A Govt. of Telangana Undertaking) Vidyut Soudha, Hyderabad - 500082. Phone: 040 – 23499261 Fax: 040 – 23499323.
From: The Chief Engineer, Thermal Projects Construction, TSGENCO, Vidyut Soudha, Khairatabad, Hyderabad-500 082. Email ID: cetpctgenco@gmail.com	To: M/s BHEL, Power Sector-Southern Region, Periyar EVR Building,690, Anna Salai, Nandanam, Chennai – 600 035. Phone: 044-28286715 Fax: 044-24323757.

Lr.No.CE/TPC/SE3/EME-15/YTPS(5X800MW)/F.NO. /D.No. 177/18, Dt: 12.12.2018.

Sir,

Sub: TSGENCO – Yadadri TPS(5X800MW) – Proceeding with Tendering for execution of CHP and AHP civil works as Package A & B of Units 1,2,3,4 & 5 for 5X800 MW Yadadri Thermal Power Station - Reg.

Ref : 1) M/s BHEL E-mail Letter Dt:24.03.2018.
2) M/s BHEL Letter Ref: BHEL PSSR: YADADRI TPP: 102, Dt:26.11.2018
3) M/s BHEL Letter Ref: BHEL PSSR: YADADRI TPP: 102, Dt:11.12.2018

*****

This has reference to the letter cited in ref (3) above, wherein M/s BHEL/PSSR has informed that they are in the process of floating the tender for execution of CHP and AHP civil works as Package A & B of Units 1,2,3,4 & 5 for 5X800 MW Yadadri Thermal Power Station and informed that the tender shall have the provision of Reverse Auction

In this connection it is to inform that time and again TSGENCO is requesting M/s BHEL that not resort to Reverse Auction for civil works which was agreed by M/s BHEL during finalization of Revised LOI and as per P.O conditions .

Hence the proposal furnished by M/s BHEL that the above tenders shall have the provision of Reverse Auction is not acceptable to TSGENCO.

This is for information and further necessary action.

Yours faithfully,

P V Seshu 12/12/18

Chief Engineer/TPC

P.T.O

Copy to:

1. Chief Engineer/Construction/YTPS/ Dameracherla/Nalgonda(Dt)
2. Chief Engineer/ Civil/Thermal/TSGENCO/VS/Hyderabad
3. Superintending Engineer/Civil/YTPS(5X800MW)/Dameracherla.
4. Superintending Engineer-5/TPC/TSGENCO/VS/Hyderabad.
5. SE /Tech. to CMD/TSGENCO/VS/Hyderabad.
6. DE /Tech. to Director/Projects/TSGENCO/VS/Hyderabad.
7. ADE /Tech. to Director/Civil/TSGENCO/VS/Hyderabad.
8. Sri Y.A.Srinivasa Rao,GM(PMG)/BHEL Camp Office/Vidyut Soudha/Hyderabad.
9. Sri HariKrishnan/GM/BHEL/YTPS Site.
10. M/s Tata Consulting EngineersLimited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001. E-Mail id: ksridhar@tce.co.in.

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)

Vidyut Soudha, Hyderabad - 500082. www.tsgenco.telangana.gov.in

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, Vidyut Soudha, Khairatabad, Hyderabad-500 082. E-Mail:cetpctgenco@gmail.com	M/s BHEL/EDN, Electronics Division, P.O. Box No.2606, Mysore Road, Banglore-560 026. E-Mail:abhilashreddy@bheledn.co.in

Lr.No.CE/TPC/421/YTPS (5X800 MW)/C&I-Vendors/D.No.248/18, Dt:03.11.2018

Sir,

Sub: TSGENCO – YTPS (5X800MW) – Approval of Controls & Instrumentation Sub Vendors for bought out items and Mechanical Lab items of M/s BHEL/EDN - Reg.

Ref: 1) M/s BHEL/EDN vide Lr.No:CE/PMC/YTPS/VL/AR-09, Dtd:30.05.2018.
2) M/s BHEL/EDN vide Lr.No:CE/PMC/YTPS/VL-Mech/AR-13, Dtd:11.07.2018.
3) M/s BHEL/EDN e-mail dtd:16.08.2018.
4) M/s TCE e-mail dtd:30.10.2018 and 31.10.2018.

* * *

With reference to the M/s BHEL/EDN's request letters (1) and (2) & e-mail vide ref(3) cited above ,and M/s TCE Comments cited (4) above, after careful examination, the Controls & Instrumentation vendors for bought out item and Mechanical Lab items of M/s BHEL/EDN are hereby approved as per the enclosed Annexure.

Further, the vendor approval for the following System/ Package i.e for S.No:54 & 72 should have the following technical specifications and are conditional approved as shown below:

For S.No:54:LCD Projector: Accepted, provided the projector shall have 4K LCD and SMART features.

For S.No:72: System Integrators (CCTV+Patrol guard):The System integrators should have supplied and completed the IP CCTV system having minimum 150 No's of cameras in a project of power plant or oil/gas industry.

TSGENCO insists that the complete system shall be in operation atleast for one year successfully.

Please note that this approval of C&I vendors for M/s BHEL/EDN does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: Annexure

Yours faithfully

CHIEF ENGINEER/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
3. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
4. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
5. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
6. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
7. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
8. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
9. Sri Y.A.Srinivas Rao, BHEL/PMG, Vidyut Soudha, Hyderabad.

ANNEXURE
Vendor List for Bought Out items of M/s BHEL/EDN for Project: 5 x 800MW Yadadri TPS

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
1	**Instrumentation, Control & Compensting / Thermocouple extension cables (PVC, FRLS Type)**	1	M/s ADVANCE CABLES TECHNOLOGIES, BANGALORE	Approved
		2	Apar industries, Bangalore	Not Approved
		3	M/s SUYOG ELECTRICALS LTD. ALKAPURI, BARODA	Approved
		4	Gemscab industries ltd, Bhiwadi	Approved
		5	NICCO cables,kolkata	Approved
		6	Industrial cables ltd, punjab	Not Approved
		7	KEC international ltd, Bangalore	Approved
		8	RJR industries, Bangalore	Not Approved
		9	Special Cables Pvt Ltd, New Delhi	Approved
		10	RJ industrial corporation, Uttarkhand	Not Approved
		11	M/s CORDS CABLES, RAJASTHAN	Approved
		12	M/s DELTON CABLES,FARIDABAD	Approved
		13	M/s GOYOLENE FIBRES ,MUMBAI	Approved
		14	M/s ELKAY TELELINKS LTD FARIDABAD, HARYANA	Approved
		15	M/s INCAB, PUNE	Approved
		16	M/s KEI INDUSTRIES LTD, CHENNAI	Approved
		17	M/s T C COMMUNICATION PVT. LTD, NEW DELHI	Approved
		18	M/s MANSFIELD CABLES COMPANY LTD. NOIDA, U.P.	Approved
		19	M/s GUPTA POWER INFRASTRUCTURE LTD. BHUBANESWAR	Not Approved
		20	M/s PARAMOUNT CABLES,ALWAR	Approved
		21	M/s POLYCAB,DAMAN	Approved

PV Sooiy 3/11/18
Chief Engineer
Thermal Projects Constructic
TSGENCO, Vidyut Soud
Khairatabad, Hyd-500

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		22	M/s THERMO CABLES, HYDERABAD	Approved
		23	M/S Udey Pyro cables, Vadodara	Not Approved
		24	M/s CMS Ltd, Faridabad	Not Approved
		25	Servel India Pvt. Ltd. , New Delhi	Not Approved
		26	Tempsens Instruments (I) Pvt. Ltd., Udaipur	Not Approved
		27	Gloster Cables Ltd., Secunderabad	Not Approved
		28	Devidayal & Mahindra cable Industries, Delhi	Not Approved
		29	Govind Cable Industries, Ghaziabad	Not Approved
2	**Control Cable**	1	M/s Torrent Power ltd, Gujarat	Not Approved
		2	M/S SPM Power & Telecom Pvt Ltd, Hyderabad.	Not Approved
3	**Lead Acid Battery (Plante type)**	1	M/s EXIDE INDUSTRIES, KOLKATA	Approved
		2	M/s HOPPECKE, GERMANY	Approved
4	**Master Slave Clock System**	1	M/s SERTEL, CHENNAI	Approved
		2	M/s MASIBUS, GANDHINAGAR.	Approved
		3	M/s SANDS, CHENNAI	Approved
5	**Walkie-Talkie System**	1	M/s Maurya Infotech, Bangalore	Approved
		2	M/s Sheetal Wireless, Pune	Approved
		3	M/s ICONET, Chennai	Approved
		4	M/s Micromap, Lucknow	Approved
		5	M/s HARITASA CHECKMATE ELECTRONICS, BANGALORE	Not Approved
Maintenance & Calibration Equipments (Electrical Package) EDN - BANGALORE Item wise Vendors				
6	**Portable Multifunction**	1	GE	Approved

Chief Engineer
Thermal Projects Constructio
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
	Calibrator (Microprocessor based)	2	Fluke	Approved
		3	Agilent (Keysight)	Approved
		4	Yokogowa	Approved
		5	Beamex	Approved
		6	Nagman	Not Approved
		7	Wika/Scandura	Approved
		8	Aoip France	Approved
		9	Time Electronics	Approved
		10	Eurotron	Approved
7	**Decade Resistance Box**	1	Toshniwal	Approved
		2	yokogowa	Approved
		3	Tinsley	Approved
8	**AC Universal bridge**	1	Fluke Amprobe	Approved
		2	GW Instek	Not Approved
		3	Aplab	Approved
		4	Wayne Kerr	Approved
		5	Agilent (Keysight)	Approved
		6	Yokogowa	Approved
		7	Tinsley	Approved
		8	Extech	Approved
9	**Signal Generator**	1	Fluke	Approved
		2	Aplab	Approved

Chief Engineer
Thermal Projects Construct
TSGENCO, Vidyut Soudh
Khairatabad, Hyd-500 0

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		3	Yokogawa	Approved
		4	Tektronix	Approved
		5	Agilent (Keysight)	Approved
10	**Hand Tachometer**	1	Fluke- Amprobe	Approved
		2	Extech	Approved
		3	Line Seiki	Not Approved
11	**Insulation tester of Different Range**	1	Fluke- Amprobe	Approved
		2	Extech	Approved
		3	Megger	Approved
		4	Yokogowa	Approved
		5	Tinsley	Approved
		6	Motwane	Approved
12	**Dc Regulated power supply**	1	Aplab	Approved
		2	Agilent(Keysight)	Approved
		3	GW Instek	Not Approved
13	**Stop watch (Digital Type)**	1	Extech	Approved
		2	casio	Approved
		3	Fluke-amprobe	Approved
14	**Continuity Tester**	1	Extech	Approved
		2	Fluke Amprobe	Approved
		3	Meco	Approved
		4	RS Components	Approved

Chief Engineer
Thermal Projects Constructio
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
15	**Tong Tester**	1	Fluke	Approved
		2	Yokogawa	Approved
		3	Agilent(keysight)	Approved
		4	Extech	Approved
		5	Nagman	Not Approved
		6	Meco	Approved
16	**High Range Tong Tester**	1	Fluke	Approved
		2	Yokogawa	Approved
		3	Agilent(keysight)	Approved
		4	Extech	Approved
		5	Nagman	Not Approved
		6	MECO	Approved
17	**Stabilised Power Supply**	1	APLAB	Approved
		2	ZEAL	Not Approved
18	**Stroboscope**	1	Lutron	Not Approved
		2	Fluke/fluke Amprobe	Approved
		3	RS Components	Approved
19	**Portable Trend Recorder**	1	Chino	Approved
		2	Yokogowa	Approved
		3	shinko	Approved
		4	Honeywell	Approved
		5	Fuji Electric	Approved

PV Sooraj 3/11/18
Chief Engineer
Thermal Projects Constructi
TSGENCO, Vidyut Soudh
Khairatabad, Hyd-500 08

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
20	**Electronic Test bench Computerised calibration system**	1	GE	Approved
		2	Scandura/Wika	Approved
		3	Convergent Technologies	Approved
		4	Nagman	Not Approved
		5	Tinsley	Approved
		6	Fluke	Approved
		7	Isothermal Technology	Approved
21	**Portable digital multimeter**	1	Fluke	Approved
		2	Yokogawa	Approved
		3	Agilent (Keysight)	Approved
		4	Extech	Approved
		5	Nagman	Not Approved
		6	Meco	Approved
		7	Tektronix	Approved
22	**Field Transmitter Calibrator**	1	Yokogowa	Approved
		2	wika/scandura	Approved
		3	Fluke	Approved
		4	GE	Approved
		5	Meriam	Not Approved
		6	ABB	Approved
		7	Emerson	Approved
		8	Honeywell	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
23	**Soldering Iron**	1	Soldron	Approved
		2	Hakko	Approved
24	**SOLDER SUCKER**	1	Soldron	Approved
		2	RS Components	Approved
25	**Desoldering Station**	1	Hakko	Approved
		2	Weller	Approved
		3	Xytronics	Approved
26	**VARIAC**	1	AE	Approved
27	**Power Pack**	1	Aplab	Approved
		2	Keithly	Not Approved
		3	Tektronix	Approved
		4	Agilent(Keysight)	Approved
28	**Vibration Anlyzer Balancer Instrument**	1	SKF	Approved
		2	Mechanylsis Vb series	Not Approved
		3	B&K Vibro Germany	Approved
		4	GE Bentley Neveda	Approved
		5	Rockwell	Approved
		6	Prufftecknic germany	Not Approved
		7	Spm instruments	Approved
		8	Masibus Automation	Not Approved
		9	tinsley	Not Approved
29	**Portable Meter Calibrator**	1	Fluke	Approved

Chief Engineer
Thermal Projects Construct
TSGENCO, Vidyut Soud
Khairatabad, Hyd-500 0

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		2	Agilent(Keysight)	Approved
		3	Yokogowa	Approved
		4	Tektronix	Approved
		5	wika/scandura	Approved
		6	Keithly	Not Approved
		7	Meco	Approved
30	**Digital Cable Identification System**	1	Ideal	Not Approved
		2	KingFisher	Not Approved
		3	Fluke	Approved
		4	RS Components	Approved
		5	Extech	Approved
31	**Dual Beam Portable Digital Storage Oscilloscope**	1	Tektronix	Approved
		2	Agilent (Keysight)	Approved
		3	Yokogawa	Approved
		4	Rigol	Not Approved
32	**Hand Held Thermocouple and PT-100 OHM Simulator and Indicator**	1	Agilent(Keysight)	Approved
		2	Fluke	Approved
		3	Yokogowa	Approved
		4	Nagman	Not Approved
		5	Aoip France	Approved
		6	Time Electronics	Approved
		7	GE Druck	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		8	Scandura/wika	Approved
		9	Beamex	Approved
33	**Insertion And Extraction Tools For Various Pin Numbers 14,16 And 48**	1	RS Components	Approved
34	**Rheostats**	1	Toshniwal	Not Approved
		2	Time Electronics	Approved
		3	Tinsley	Approved
		4	IET Labs	Approved
35	**Desktop Digital Multimeter**	1	Fluke	Approved
		2	Agilent(keysight)	Approved
		3	Yokogowa	Approved
		4	Nagman	Approved
		5	Tektronix	Approved
		6	Time Electronics	Approved
		7	Extech	Approved
		8	Keithly	Not Approved
36	**Phase Sequence Meter**	1	Fluke-Amprobe	Approved
		2	Agilent(Keysight)	Approved
		3	Yokogowa	Approved
		4	Extech	Approved
		5	RS Components	Approved
37	**Frequency Meter**	1	Fluke	Approved

Chief Engineer
Thermal Projects Constructio
TSGENCO, Vidyut Soudha.
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		2	Agilent(Keysight)	Approved
		3	Yokogowa	Approved
		4	Tektronix	Approved
		5	Aplab	Not Approved
38	**Mini scope Meter**	1	Agilent(Keysight)	Approved
		2	Yokogowa	Approved
		3	Fluke	Approved
39	**Vibration / Sound Level Monitor**	1	Fluke-Amprobe	Approved
		2	HT Italia	Not Approved
		3	RS Components	Approved
		4	Extech	Approved
40	**Portable PH Calibrator**	1	Oakton	Approved
		2	Orion	Approved
		3	Hanna	Approved
		4	Extech	Approved
41	**Module Tester**	1	Qmax	Approved
		2	Estech	Approved
42	**Dc Regulated power Source**	1	Aplab	Approved
		2	Agilent(Keysight)	Approved
43	**Auto Transformer**	1	AE	Approved
44	**Nickel Cadmium Cell**	1	Eveready	Not Approved
		2	Sony	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
45	**Scanner**	1	HP	Approved
		2	Cannon	Approved
		3	Epson	Not Approved
46	**Torximitor**	1	Sper Scientific	Approved
47	**Laptop**	1	HP	Approved
		2	DELL	Approved
		3	IBM	Not Approved
		4	Compaq	Not Approved
		5	Lenovo	Approved
48	**Portable mA Calibrator**	1	Fluke	Approved
		2	Agilent(Keysight)	Approved
		3	GE Druck	Approved
		4	Scandura/wika	Approved
		5	Nagman	Not Approved
		6	Yokogowa	Approved
		7	Time Electronics	Approved
		8	Beamex	Approved
		9	Eurotron	Approved
		10	Tinsley	Approved
		11	Aoip France	Approved
		12	Extech	Approved
49	**Table Mounted mA Calibrator**	1	Fluke	Approved

Chief Engineer
Thermal Projects Construct
TSGENCO, Vidyut Sa
Khairatabad, Hy

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		2	Agilent (Keysight)	Approved
		3	GE Druck	Approved
		4	Scandura/wika	Approved
		5	Nagman	Not Approved
		6	Yokogowa	Approved
		7	Time Electronics	Approved
		8	Beamex	Approved
		9	Eurotron	Approved
		10	Tinsley	Approved
		11	Aoip France	Approved
		12	Extech	Approved
50	**Portable mV Calibrator**	1	Fluke	Approved
		2	Agilent(Keysight)	Approved
		3	GE Druck	Approved
		4	Scandura/wika	Approved
		5	Nagman	Not Approved
		6	Yokogowa	Approved
		7	Time Electronics	Approved
		8	Beamex	Approved
		9	Eurotron	Approved
		10	Tinsley	Approved
		11	Aoip France	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		12	Extech	Approved
51	**Test RTD**	1	Fluke	Approved
		2	Wika	Approved
		3	ASP Sensors	Approved
		4	Isotech	Approved
52	**Frequency Counter/Timer**	1	Agilent(Keysight)	Approved
		2	Tektronix	Approved
		3	Yokogowa	Approved
		4	Fluke	Approved
		5	Aplab	Not Approved
53	**LVS**	1	DELTA ELECTRONICS INDIA PVT. LTD. GURGAON	Approved
		2	PLANER-USA /PYROTECH-UDAIPUR	Approved
		3	BARCO ELECTRONIC SYSTEMS PVT. LTD. NOIDA	Approved
		4	CHRISTIE-USA	Approved
		5	EYEVIS GERMANY	Not Approved
		6	MITSUBISHI ELECTRIC INDIA PVT. LTD. NEW DELHI	Not Approved
		7	PYROTECH ELECTRONICS (P) LTD, UDAIPUR	Not Approved
54	**LCD Projector**		Technical Qalification:Accepted, Provided the Projector shall have 4 K LCD and shall have SMART features.	
		1	HCL infosystem	Approved
		2	Binary Systems	Approved
		3	Orbit peripherals	Approved
		4	AA Enterprises	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 0[illegible]

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		5	Shiba comp	Approved
		6	Msquare innotech	Approved
		7	Title display	Approved
55	**MODULAR DESK/SERVER & PC RACK**	1	ADARSHA CONTROLS SYSTEMS PVT LTD ,BANGALORE	Approved
		2	CHEMIN CONTROLS AND INSTRUMENTATION , PONDICHERRY	Approved
		3	COSMOS MEDIA PRODUCTS PVT LTD ,NOIDA	Approved
		4	HARMONY SYSTEMS ,NEWDELHI	Not Approved
		5	PYROTECH WORKSPACE SOLUTIONS PVT LTD , UDAIPUR	Approved
56	**COMPUTER FURNITURE.**	1	COSMOS MEDIA PRODUCTS PVT LTD ,NOIDA	Approved
		2	HARMONY SYSTEMS ,NEWDELHI	Not Approved
		3	ADARSHA CONTROLS SYSTEMS PVT LTD ,BANGALORE	Approved
		4	GODREJ AND BOYCE MANUFACTURING CO LTD, BANGALORE	Approved
		5	OTS ,BANGALORE	Approved
		6	PYROTECH WORKSPACE SOLUTIONS PVT LTD , UDAIPUR	Approved
57	**WORKSTATIONS , SERVER, PC'S**	1	HP	Approved
		2	FUJITSU	Not Approved
		3	IBM-LENOVO	Approved
		4	DELL	Approved
58	**PRINTERS (Laser/Inkjet)**	1	EPSON(Inkjet only)	Approved
		2	HP	Approved
		3	IBM	Approved
		4	CANON	Approved

Chief Engineer
Thermal Projects Construct
TSGENCO, Vidyut Soud
Khairatabad, Hyd-500

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		5	XEROX	Approved
		6	LEXMARK	Approved
59	**TFT MONITOR**	1	HP	Approved
		2	DELL	Approved
		3	IBM-LENOVO	Approved
		4	NEC	Not Approved
		5	SAMSUNG	Approved
		6	FUJITSU	Not Approved
60	**MINI UPS FOR HMI**	1	HITACHI HI-REL POWER ELECTRINICS,BANGALORE	Approved
		2	VERTIV ENERGY	Not Approved
		3	SCHNEIDER ELECTRIC,BANGALORE	Approved
		4	EMERSON NETWORK INDIA,BANGALORE	Approved
		5	APLAB LIMITED ,THANE	Approved
		6	EMERSON NETWORK ,PUNE	Approved
		7	APC	Not Approved
		8	DELTA	Not Approved
61	**STATION LAN / MIS EQUIPMENT**	1	NETSOFT SYSTEMS & NETWORKS , BANGALORE	Approved
		2	IBM INDIA PVT LTD.	Approved
		3	TEXONIC INSTRUMENTS , BANGALORE	Approved
		4	PRISHA SYSTEMS &NETWORKS PVT LTD.	Not Approved
		5	BINARY SYSTEMS PVT LTD	Not Approved
		6	ORVA NETWORKS PVT LTD	Not Approved

Chief Engineer
Thermal Projects Constructi
TSGENCO, Vidyut Soudha.
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		7	WIPRO INFOTECH ,BANGALORE	Approved
		8	THETHA CONTROLS PUNE	Approved
		9	ORANGE BUSINESS SERVICES	Approved
62	**OFC**	1	AKSH FIBRE, BHIWADI	Approved
		2	HFCL-GOA	Approved
		3	R&M	Not Approved
		4	FINOLEX , PUNE/GOA	Approved
		5	D-LINK	Approved
		6	BIRLA ERICSSON,REWA	Approved
		7	STERLITE	Approved
		8	SCHINEDER - DIGILINK	Not Approved
		10	TERRACOM	Approved
63	**EPABX System (IP Based)**	1	HCL INFOSYSTEMS LTD, NOIDA (Make: ERICSSON - AASTRA)	Approved
		2	BPL TELECOM PVT LTD, BANGALORE (Make: TADIRAN / ALCATEL)	Approved
		3	PROGILITY TECHNOLOGIES PVT. LTD, NEW DELHI (Make:UNIFY-SIEMENS)	Approved
		4	ABS INDIA PVT LTD, BANGALORE (Make:ALCATEL)	Approved
		5	ITI LIMITED, BANGALORE (Make: ITI)	Approved
		6	Vijaya Enterprises, Hyderabad (Make:TADIRAN)	Approved
		7	V Link Systems (P) Ltd., Chennai (Make:TADIRAN)	Approved
		8	CLIXXO BROADBAND PVT LTD, DELHI (Make: CLIXXO)	Approved
		9	AISHAN TECHNOLOGIES PVT LTD, BANGALORE (Make: NEC)	Approved

Chief Engineer
Thermal Projects Constructio
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		10	INTELLICON PVT LTD (Make: KAREL)	Approved
		11	MVD TECHNOLOGIES PVT LTD, BANGALORE (Make: ERICSSON - AASTRA)	Approved
		12	SILK MEDIA PVT LTD, BANGALORE (Make: KAREL, MATRIX)	Approved
64	**UPS System with ACDB (3 Phase Input, 1 Phase Output)**	1	M/s VERTIV ENERGY, AMBERNATH (formerly M/s EMERSON NETWORK POWER, AMBERNATH)	Approved
		2	M/s HITACHI-HIREL POWER ELECTRONICS, GANDHINAGAR	Approved
		3	M/s KELTRON POWER ELECTRONICS,TRIVENDRUM	Approved
		4	M/s VERTIV ENERGY, PUNE (formerly M/s EMERSON NETWORK POWER, PUNE)	Not Approved
		5	M/s CONSUL NEOWATT POWER SOLUTIONS, PUNE	Not Approved
65	**Junction Box (Metal)**	1	M/s PYROTECH, UDAIPUR	Approved
		2	M/s CHEMIN CONTROLS, PONIDCHERRY	Approved
		3	M/s ELECTRO MECHANICAL (INDIA),KOLKATA	Approved
		4	M/s K.S. INSTRUMENTS, BANGALORE.	Approved
		5	M/s KHODAY CONTROL SYSTEMS, BANGALORE	Approved
		6	M/s MANISHA ENTERPRISES, PUNE	Approved
		7	M/S Gee Dee Packages, Mysore	Not Approved
		8	M/S Sajas Electricals, Tiruchirapalli	Approved
		9	M/s PRAMMEN INDUSTRIES, PUDDOKOTTAI	Approved
		10	M/S RMG Electromech Pvt Ltd, Bangalore	Not Approved
		11	M/S Hulasi metals Pvt Ltd, Jaipur	Not Approved
66	**Electronic Transmitter - Pr. / Diff. Pr.**	1	M/s ABB, GERMANY/ BANGALORE	Approved
		2	M/s EMERSON PROCESS , USA / NAVI MUMBAI (formerly FISHER ROSEMOUNT- USA)	Approved

Chief Engineer
Thermal Projects Constructi
TSGENCO, Vidyut Soud
Khairatabad, Hy

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		3	M/s FUJI, JAPAN/FRANCE	Approved
		4	M/s HONEYWELL,USA/PUNE	Approved
		5	M/s YOKOGAWA, JAPAN / BANGALORE	Approved
		6	M/s ENDRESS + HAUSER(I) AUTOMATION,INDIA	Approved
		7	M/s BALDOTA CONTROL & EQUIPMENTS PVT LTD,INDIA (SMAR MAKE)	Approved
		8	M/s SIEMENS LTD,INDIA	Approved
67	**Level Transmitter (Ultrasonic type)**	1	M/s P&F,INDIA	Approved
		2	M/s VEGA,GERMANY	Approved
		3	M/s FORBES MARSHALL	Approved
		4	M/s KROHNE MARSHALL	Approved
		5	M/s ABB	Approved
		6	M/s Emerson Process Management	Approved
		7	M/s SIEMENS MILLTRONICS,CANADA	Approved
		8	M/s ENDRESS+HAUSER, GERMANY/INDIA	Approved
68	**Level Transmitter (RADAR type)**	1	M/s EMERSON PROCESS , USA / NAVI MUMBAI (formerly FISHER ROSEMOUNT- USA)	Approved
		2	M/s ENDRESS+HAUSER, GERMANY / INDIA	Approved
		3	M/s ABB, GERMANY/FARIDABAD	Approved
		4	M/s KROHNE MARSHALL	Approved
		5	M/s VEGA,GERMANY	Approved
		6	M/s K-TEK,USA	Approved
		7	M/s HONEYWELL,USA/INDIA	Approved
		8	M/s P&F,INDIA	Approved

Chief Engineer
Thermal Projects Constructic
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		9	M/s MAGNETROL,BELGIUM	Approved
69	**HART Communicator**	1	M/s MERIAM, USA	Approved
		2	M/s ABB, GERMANY / INDIA	Approved
		3	M/s EMERSON PROCESS , USA / NAVI MUMBAI (formerly FISHER ROSEMOUNT- USA)	Approved
		4	M/s FUJI, JAPAN	Approved
		5	M/s HONEYWELL,USA/PUNE	Approved
		6	M/s GE INDIA INDUSTRIAL PVT. LTD./INDIA	Approved
		7	M/s FLUKE CORPORATION / USA	Approved
		8	M/s YOKOGAWA, JAPAN (YOKOGAWA-BANGALORE)	Approved
		9	M/s GLOBAL INSTRUMENTS	Not Approved
70	**HART Management System**	1	M/s EMERSON PROCESS , USA / NAVI MUMBAI (formerly FISHER ROSEMOUNT- USA)	Approved
		2	M/s MTL, UK / INDIA	Approved
		3	M/s R.STAHL (P) LTD, CHENNAI	Not Approved
		4	M/s PEPPERL + FUCHS, GERMANY / INDIA	Approved
71	**CAMERA OEM FOR CCTV SYSTEM (IP BASED)**	1	PELCO-USA	Approved
		2	BOSCH	Approved
		3	HONEYWELL AUTOMATION ,BANGALORE	Approved
		4	AXIS-SWEDEN	Approved
72	**System Integrators (CCTV + Patrol guard)**	Technical Qualification: CCTV system integrators should have supplied and completely commissioned an IP based CCTV system having minimum 150 cameras in a Power Plant or Oil/Gas		
		1	M/s BINARY SYSTEM PVT LTD, BANGALORE	Approved
		2	M/s CMS,MUMBAI	Approved
		3	M/s HARITASA, BANGALORE	Approved

P V Seshu 3/11/17
Chief Engineer
Thermal Projects Constructio
TSGENCO, Vidyut Soudha
Khairatabad, Hyd-500 00

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		4	M/s HONEYWELL AUTOMATION INDIA LTD	Approved
		5	M/s NETWARE COMPUTERS, DELHI	Approved
		6	M/s NEURAL NETWORKS, MUMBAI	Approved
		7	M/s POLIXEL SECURITY SYSTEMS PVT LTD, GURGAON	Approved
		8	M/s TEXONIC INSTRUMENTS, BANGALORE	Approved
		9	M/s TOSHNIWAL INDUSTRIES PVT LTD, AJMER	Approved
		10	M/s SCORE TECHNOLOGIES, KOLKATA	Not Approved
		11	M/s SIEMENS LTD, BANGALORE	Not Approved
		12	M/s DELCOM TELESYSTEM, NEW DELHI	Not Approved
		13	M/s HEXXA GEO SYSTEM, SURAT	Not Approved
		14	M/s TECHNOCRATS SECURITY SYSTEM PVT LTD,	Not Approved
73	**Cable trays**	1	M/s GEE DEE PACKAGES PVT LTD, MYSORE	Approved
		2	M/s PRAMMEN INDUSTRIES, PUDUKKOTTAI	Approved
		3	M/s PATNY SYSTEMS PVT. LTD, SECUNDARABAD	Approved
		4	M/s M.J.ENGINEERING WORKS PVT. LTD, NEW DELHI	Approved
		5	M/s JAMNA METAL COMPANY, NEW DELHI	Approved
		6	M/s INNOSPACER ENGINEERING TECHNOLOGIES, BANGALORE	Approved
		7	M/s INDIA ELECTRICALS SYNDICATE, KOLKATA	Approved
		8	M/s APT ENGINEERING WORKS, NEW DELHI	Approved
		9	M/s RUKMANI ELECTRICAL & COMPONENTS PVT, KOLKATA	Approved
		10	M/s VATCO, KHAIRHNE, NAVI MUMBAI	Approved
		11	M/s KANADE ANAND UDYOG PVT. LTD, ANDHERI	Approved

Chief Engineer
Thermal Projects Construct
TSGENCO, Vidyut Soud
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		12	M/s CHEMIN CONTROLS AND INSTRUMENTATION, PONDICHERRY	Approved
		13	M/s Silverline Power Infrastructure Pvt Ltd.	Approved
		14	M/S Indiana Gratings - Pune/Mumbai	Approved
		15	M/S Industrial Perforation, Kolkata	Approved
		16	M/S Ratan Engineerong and Projects, Kolkata	Approved
		17	M/S Steelite Engg, Mumbai	Approved
		18	M/S Amtech, Pune	Approved
		19	M/S Unitech fabricators & Engg Pvt ltd, Kolkata	Not Approved
		20	M/S Rabi Engg, Kolkata	Not Approved
		21	M/S Premium Power Products (Cal) Pvt ltd, Kolkata	Not Approved
		22	M/S TRG, Chennai	Not Approved
		23	M/S Passive Infra Projects Pvt Ltd, Rohtak	Not Approved
74	**Pressure and Differential Pressure Gauges**	1	M/s A.N.INSTRUMENTS PVT LTD CHENNAI	Approved
		2	M/s GOA STATIC INSTRUMENTS GOA	Approved
		3	M/s H.GURU INSTRUMENTS(SOUTH INDIA)PVT. BANGALORE	Approved
		4	M/s MANOMETER (INDIA) PVT. LTD., MUMBAI	Approved
		5	M/s WALCHANDNAGAR INDUSTRIES LTD. OPP. A.C MARKET, TARDEO ROAD, BAUMER	Approved
		6	Precision Mass Products Private Limited (Earlier Aschcroft)	Approved
		7	WIKA INSTRUMENTS INDIA PVT. LTD. VILLAGE - KESNAND, PUNE	Approved
		8	GIC(Gauges Bourdon), Panvel	Approved
		9	BAUMER INDIA PRIVATE LIMITED (Formerly Waaree, Mumbai)	Approved
		10	Precisemeasure Controls Pvt. Ltd	Not Approved

PV Sastry 3/11/18
Chief Engineer
Thermal Projects Constructi
TSGENCO, Vidyut Soudh
Khairatabad, Hy

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		11	THERMAL INSTRUMENT INDIA PVT. LTD.	Not Approved
		12	M/s FORBES MARSHALL(HYD) LTD. HYDERABAD	Approved
75	**Level Switch Capacitance Type**	1	M/s LEVCON INSTRUMENTS P LTD KOLKATA	Approved
		2	M/s SBEM PRIVATE LIMITED PUNE	Approved
		3	M/sV.AUTOMAT & INSTRUMENTS PVT. LTD. NEW DELHI	Approved
		4	NIVO CONTROLS PVT LTD	Approved
		5	M/s D.K.INSTRUMENTS PVT. LTD. DHAKURIA, KOLKATA	Approved
		6	PUNE TECHTROL PVT LTD,PUNE	Not Approved
		7	IGEMA GMBH,MUNSTER,GERMANY.	Not Approved
76	**Level Switch Conductivity Type**	1	M/s HI-TECH SYSTEMS & SERVICES LTD CALCUTTA (M/s LEVELSTATE SYSTEMS LTD Make probe and electronics)	Approved
		2	SOLARTRON TRANSDUCER U.K	Not Approved
		3	M/s RAMAN INSTRUMENTS PVT. LTD. 29TH ROAD,BANDRA(WEST),MUMBAI,	Approved
		4	PUNE TECHTROL PVT LTD,PUNE(SYSTEM INTEGRATOR OF FOSSIL POWER SYSTEM)	Not Approved
		5	IGEMA GMBH,MUNSTER,GERMANY.	Not Approved
77	**Level Switch Float Type**	1	M/s LEVCON INSTRUMENTS P LTD KOLKATA.	Approved
		2	M/s SBEM PRIVATE LIMITED PUNE	Approved
		3	M/s V.AUTOMAT & INSTRUMENTS PVT. LTD. NEW DELHI	Approved
		4	M/s D.K.INSTRUMENTS PVT. LTD. DHAKURIA, KOLKATA,	Approved
		5	M/s SIGMA INSTRUMENTS COMPANY BHANDUP(WEST)	Approved
		6	M/s CHEMTROLS SAMIL (INDIA) PVT. LTD. POWAI , MUMBAI	Approved
		7	PUNE TECHTROL PVT LTD,PUNE	Not Approved

Chief Engineer
Thermal Projects Constructio
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		8	IGEMA GMBH,MUNSTER,GERMANY.	Not Approved
78	**Temperature Elements**	1	M/s DETRIV INSTRUMENTATION AND ELETRI MUMBAI	Approved
		2	M/s PYRO ELECTRIC INSTRUMENTS GOA PVT.L MAPUSA, GOA	Approved
		3	M/s TEMPSENS INSTRUMENTS (I) PVT LTD UDAIPUR	Approved
		4	M/s INDUSTRIAL INSTRUMENTATION CHIRANTANI PARK,BANSDRONI,KOLKATA	Approved
		5	EXOTHERM INSTRUMENTS ,THANE	Approved
		6	OKAZAKI,JAPAN	Approved
		7	GOA INSTRUMENTS INDUSTRIES PRIVATE LTD	Approved
		8	THERMAL INSTRUMENT INDIA PVT. LTD.	Approved
		9	Toshniwal Industries Pvt Ltd, Ajmer	Approved
		10	M/s TECHNO INSTRUMENTS SANTEJ, KALOL, GANDHINAGAR, GOA IN	Approved
		11	GAUGES BOURDON INDIA PVT LTD	Approved
		12	Wika Instruments, Pune	Not Approved
		13	Nesstech Instruments Pvt Ltd, Vapi	Not Approved
		14	BAUMER INDIA PRIVATE LIMITED (Formerly Waaree, Mumbai)	Approved
79	**Temperature Gauges**	1	M/s A.N.INSTRUMENTS PVT LTD CHENNAI	Approved
		2	GAUGES BOURDON (INDIA) PVT. LTD.	Approved
		3	M/s GOA THERMOSTATIC INSTRUMENTS GOA	Approved
		4	M/s FORBES MARSHALL(HYD) LTD. HYDERABAD	Approved
		5	WIKA INSTRUMENTS INDIA PVT. LTD. VILLAGE - KESNAND, PUNE	Approved
		6	GOA INSTRUMENTS INDUSTRIES PRIVATE LTD	Approved
		7	BAUMER TECHNOLOGIES (I) PRIVATE LIMITED (Formerly Waaree, Mumbai)	Approved

Chief Engineer
Thermal Projects Constructic
TSGENCO, Vidyut Soudha
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		8	M/s H.GURU INSTRUMENTS(SOUTH INDIA)PVT. BANGALORE	Approved
		9	THERMAL INSTRUMENT INDIA PVT. LTD.	Not Approved
		10	Precision Mass Products Private Limited (Earlier Aschcroft)	Approved
80	**Level Gauge**	1	D.K.INSTRUMENTS PVT. LTD. DHAKURIA, KOLKATA,	Approved
		2	LEVCON INSTRUMENTS P LTD KOLKATA	Approved
		3	SBEM PRIVATE LIMITED PUNE	Approved
		4	SIGMA INSTRUMENTS COMPANY BHANDUP(WEST	Approved
		5	V.AUTOMAT & INSTRUMENTS PVT. LTD. NEW DELHI,	Approved
		6	CHEMTROLS SAMIL (INDIA) PVT. LTD. POWAI , MUMBAI	Approved
		7	PUNE TECHTROL PVT LTD,PUNE	Approved
81	**Air Filter Regulator**	1	PLACKA INSTRUMENTS INDIA PVT LTD CHENNAI	Approved
		2	SMC Pneumatics	Approved
		3	PARKER HANNIFIN INDIA PVT. LTD.	Approved
		4	Divya Control Elements Pvt. Ltd.	Not Approved
		5	SHAVO NORGREN(INDIA)PVT LTD BANGALORE	Approved
82	**CO Analyser Insitu Type**	1	MARVEL ENGG COMPANY CHENNAI	Approved
		2	CHEMTROLS INDUSTRIES LIMITED POWAI, MUMBAI	Approved
		3	FORBES MARSHALL CODEL PVT. LTD. PIMPRI, PUNE	Approved
		4	LAND INSTRUMENTS INTERNATIONAL ENGLAND (UK)	Approved
		5	CODEL INTERNATIONAL LTD	Approved
		6	Protea UK	Not Approved
		7	ICE ASIA, Mumbai	Not Approved

Chief Engineer
Thermal Projects Constructic
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 00

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		8	SICK India	Not Approved
		9	SICK MAIHAK GMBH	Approved
83	**Oxygen Analyser (LT)**	1	M/s ABB INSTRUMENTATION LTD GLOUCESTERSHIR ,UK (M/s ABB LTD PEENYA, BANGALORE is System integrator)	Approved
		2	EMERSON PROCESS MANAGEMENT INDIA PVT LTD, MUMBAI	Approved
		3	AMETEK PROCESS & ANALYTICAL INSTRUMENTS,USA.(M/s CHEMTROLS SAMIL (INDIA) PVT. LTD. POWAI , MUMBAI is System integrator)	Approved
		4	ENOTEC GMBH ,GERMANY.(M/s FORBES MARSHALL PVT LTD PIMPRI, PUNE is System integrator)	Approved
		5	YOKOGAWA ELECTRIC CORPORATION,TOKYO,JAPAN (M/s YOKOGAWA INDIA LIMITED BANGALORE is System integrator)	Approved
		6	TELEDYNE ELECTRONIC TECHNOLOGIES,CALIFORNIA,USA.(M/s STEAM EQUIPMENTS PVT. LTD. KONDHWA BUDURK, PUNE is System integrator)	Approved
84	**Oxygen Analyser (HT)**	1	SECO CONTROLS PVT LTD,CHENNAI	Approved
85	**Steam and Water analysis System (SWAS)**	1	Endress+Hauser, Yokogawa Japan	Approved
		2	ABB INDUSTRIES AG SWITZERLAND	Approved
		3	ROSEMOUNT ANALYTICAL INC IRVINE	Approved
		4	HACH LANGE S.A.R.L CH-1222, VESENAZ	Approved
		5	SWAN Analytical Instruments, Switzerland	Not Approved
		6	Teledyne USA	Approved
		7	METTLER TOLEDO INDIA PVT LTD, MUMBAI	Not Approved
		8	DKK TOA Japan	Not Approved
		9	THERMO ORION INC BEVERLY MA 01915-6199,POLYMETRON,FRANCE	Approved
86	**Steam and Water analysis**	1	EMERSON PROCESS MANAGEMENT KUMARAPARK(WEST), BANGALORE	Approved

Chief Engineer
Thermal Projects Constructic
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
	System (SWAS) - Sampling System(Shelter Type Sampling system shall be provided. Shelter for both Dry & Wet Sampling shall be provided)	2	ABB LTD PEENYA, BANGALORE	Approved
		3	FORBES MARSHALL PVT LTD PIMPRI, PUNE	Approved
		4	ENDRESS + HAUSER INDIA PVT. LTD. MUMBAI	Approved
		5	YOKOGAWA INDIA LIMITED BANGALORE	Approved
		6	FLOW LINE INSTRUMENTATION PVT. LTD.	Not Approved
		7	CHEMIN CONTROLS AND INSTRUMENTATION PONDICHERRY	Approved
		8	STEAM EQUIPMENTS PVT. LTD. KONDHWA BUDURK, PUNE	Approved
87	**Impulse and Sample Pipes (Carbon Steel)**	1	INDIAN SEAMLESS METAL TUBES LTD,PUNE.	Approved
		2	BHARAT HEAVY ELECTRICALS LTD TIRUCHIRAPALLI	Approved
		3	SUMITOMO CORPORATION,JAPAN.	Approved
		4	TPS TECHNITUBE ROHREN WERKE GMBH GERMANY	Approved
		5	HEAVY METAL AND TUBES LTD,AHMEDABAD/MUMBAI	Approved
		6	JINDAL SAW LTD,CHENNAI	Approved
88	**Socket Weld Fittings**	1	PANAM ENGINEERS LTD	Approved
		2	PRECISION ENGG INDUSTRIES GOREGAON(W), MUMBAI	Approved
		3	V.K.INDUSTRIES BANGALORE, VIKAS INDUSTRIAL PRODUCTS NOIDA	Approved
		4	EXCEL HYDRO-PNEUMATICS PVT LTD MUMBAI	Approved
		5	METPRESS ENGINEERING WORKS KOLKATA, BALDOTA VALVE AND MUMBAI	Approved
		6	VIKAS INDUSTRIAL PRODUCTS NOIDA	Approved
		7	BALDOTA VALVE AND MUMBAI	Approved
		8	AURA INC. PHASE - 2, NEW DELHI	Approved
		9	HP VALVES & FITTINGS (INDIA) PVT. L MOGAPPAIR WEST, CHENNAI	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500082

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		10	ARYA CRAFTS & ENGINEERING PVT. LTD.	Approved
		11	PMT ENGINEERS,AHMEDABAD	Approved
		12	PRIME ENGINEERS	Approved
		13	FLOWTECH. KOLKATA	Approved
		14	ARCELLOR	Not Approved
		15	PAUL INDUSTRIES	Not Approved
		16	NAV DURGA FORGING AND FITTINGS, Mumbai	Not Approved
		17	DynaFluid Valves and Flow Controls, Belgaum	Not Approved
89	**Valve Manifolds**	1	PRECISION ENGG INDUSTRIES, MUMBAI	Approved
		2	EXCEL HYDRO-PNEUMATICS PVT LTD,MUMBAI	Approved
		3	METPRESS ENGINEERING WORKS,KOLKATA	Approved
		4	ASTEC VALVE & FITTINGS PVT. LTD,MUMBAI	Approved
		5	BALDOTA VALVE AND MUMBAI	Approved
		6	HP VALVES & FITTINGS (INDIA) PVT. LTD,CHENNAI	Approved
		7	MICRO PRECISION PRODUCTS PVT LTD,FARIDABAD,HARYANA.	Approved
		8	FLUID CONTROLS LIMITED ,PUNE	Approved
		9	PRIME ENGINEERS,MUMBAI	Not Approved
		10	ARYA CRAFTS & ENGINEERING PVT. LTD,MUMBAI	Not Approved
		11	PMT ENGINEERS,AHMEDABAD	Approved
		12	FLOWTECH,KOLKATA.	Approved
		13	ARCELLOR CONTROLS,AHMEDABAD.	Not Approved
		14	Parker HANNIFIN INDIA PVT. LTD,LEBANON (D407131-Super techical dealer for Parker)	Not Approved

Chief Engineer
Thermal Projects Construc
TSGENCO, Vidyu
Khairatabad, Hyd-

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		15	VIPAL ENTEPRISES PVT LTD,MUMBAI.	Not Approved
		16	DYNA FLUID VALVES AND FLOW CONTROLS,UDYAMBAG, BELGAUM	Not Approved
		17	AURA INC,NEW DELHI	Approved
90	**Condensate Pots**	1	INSTRUMENTATION LIMITED PALGHAT	Approved
		2	PRECISION ENGG INDUSTRIES GOREGAON(W), MUMBAI	Approved
		3	EXCEL HYDRO-PNEUMATICS PVT LTD MUMBAI	Approved
		4	METPRESS ENGINEERING WORKS KOLKATA, BALDOTA VALVE AND MUMBAI	Approved
		5	BALDOTA VALVE AND MUMBAI	Not Approved
		6	PMT ENGINEERS,AHMEDABAD	Approved
		7	HP VALVES & FITTINGS (INDIA) PVT. L CHENNAI	Approved
		8	FLOWTECH. KOLKATA	Approved
		9	MICRO PRECISION PRODUCTS PVT LTD FARIDABAD,	Approved
		10	ARCELLOR CONTROLS (INDIA), AHMEDABAD	Not Approved
		11	NAV DURGA FORGING AND FITTINGS, Mumbai	Not Approved
		12	DynaFluid Valves and Flow Controls, Belgaum	Not Approved
91	**Vibration Monitoring Systems Sensors, Analysis System etc.**	1	BHEL EDN (VALMET DNA)	Not Approved
		2	SENSONICS LTD. U.K.	Not Approved
		3	ROCKWELL AUTOMATION U.S.A	Approved
		4	BENTLY NEVADA INC MINDEN	Approved
		5	SKF CONDITION MONITORING CA 92123-1841	Approved
		6	SHINKAWA ELECTRTIC CO., LTD TOKYO	Approved
		7	MEGGITT SA PO BOX 1616 FRIBOURG	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		8	IRD MECHANALYSIS LIMITED, MUMBAI	Approved
		9	BRUEL & KJAER VIBRO, GMBH & U.S.A.	Not Approved
		10	EMERSON PROCESS MANAGEMENT, INDIA	Not Approved
92	**Vibration Monitoring Systems Panel and Accessories**	1	BHEL EDN (VALMET DNA)	Not Approved
		2	SENSONICS TECHNOLOGIES INDIA PVT. LTD., GURGAON	Not Approved
		3	Rockwell Automation India Limited Sahibabad dist. Ghaziabad	Approved
		4	GE INDIA INDUSTRIAL PVT. LTD. BANGALORE	Approved
		5	SKF INDIA LTD	Approved
		6	FORBES MARSHALL PVT LTD PIMPRI, PUNE	Approved
		7	MEGGITT INDIA PRIVATE LTD.	Approved
		8	IRD MECHANALYSIS LIMITED, MUMBAI	Approved
		9	Toshniwal Industries Pvt Ltd, Ajmer	Not Approved
		10	EMERSON PROCESS MANAGEMENT, INDIA	Not Approved
93	**Pressure and Differential Pressure Switch**	1	Precision Mass Products Private Limited (Earlier Aschcroft)	Approved
		2	SWITZER INSTRUMENT LTD AMBATTUR, CHENNAI	Approved
		3	GAUGES BOURDON (INDIA) PVT.LTD	Approved
		4	BAUMER TECHNOLOGIES (I) PVT LTD	Approved
		5	TRAFAG CONTROLS INDIA PVT. LTD	Approved
94	**Compression Fittings**	1	FLUID CONTROLS PVT. LTD,PUNE	Approved
		2	PRECISION ENGG INDUSTRIES, MUMBAI	Approved
		3	EXCEL HYDRO-PNEUMATICS PVT LTD, MUMBAI	Approved
		4	METPRESS ENGINEERING WORKS, KOLKATA	Approved

Chief Engineer
Thermal Projects Constructic
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		5	ASTEC VALVE & FITTINGS PVT. LTD., MUMBAI	Approved
		6	AURA INC, NEW DELHI	Approved
		7	HP VALVES & FITTINGS (INDIA) PVT. LTD, CHENNAI	Approved
		8	PRIME ENGINEERS,MUMBAI	Not Approved
		9	ARYA CRAFTS & ENGINEERING PVT. LTD,MUMBAI	Not Approved
		10	SWAGELOCK,USA	Approved
		11	PARKER HANNIFIN INDIA PVT. LTD.,CHENGAL PATTU,TAMILANADU	Approved
		12	PMT ENGINEERS,AHMEDABAD	Approved
		13	FLOWTECH. KOLKATA.	Not Approved
		14	ARCELLOR CONTROLS ,AHMEDABAD	Not Approved
		15	DYNA FLUID VALVES AND FLOW CONTROLS,UDYAMBAG, BELGAUM	Not Approved
		16	PANAM ENGINEERS LTD,MUMBAI	Approved
95	**Dust Density (Opacity) Monitor**	1	CODEL INTERNATIONAL LTD	Approved
		2	LAND INSTRUMENTS INTERNATIONAL ENGLAND (UK)	Approved
		3	FORBES MARSHALL CODEL PVT. LTD. PIMPRI, PUNE	Approved
		4	SICK MAIHAK GMBH	Approved
		5	DURAG GMBH AND CO KG HUMBURG	Approved
		6	MARVEL ENGG COMPANY CHENNAI	Approved
		7	CHEMTROLS INDUSTRIES LIMITED POWAI, MUMBAI	Approved
		8	DURAG INDIA INSTRUMENTATION PRIVATE	Approved
96	**E/P Convertor Fail Freeze Type**	1	IMI NORGREN HERION PRIVATE LIMITED	Approved
		2	FAIRCHILD INDIA PRIVATE LIMITED NOIDA	Approved

Chief Engineer
Thermal Projects Constructic
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		3	WATSON SMITH LTD ENGLAND	Approved
97	**Instrument Valve**	1	BHARAT HEAVY ELECTRICALS LIMITED VALVES DIVISION,TIRUCHIRAPALLI, TAMILANADU.	Approved
		2	PRECISION ENGG INDUSTRIES, MUMBAI	Approved
		3	EXCEL HYDRO-PNEUMATICS PVT LTD,MUMBAI	Approved
		4	METPRESS ENGINEERING WORKS,KOLKATA	Approved
		5	AURA INC,PHASE-2, NEW DELHI	Approved
		6	FLUID CONTROLS PVT LTD,PUNE	Approved
		7	INSTRUMENTATION LIMITED,PALGHAT	Approved
		8	PMT ENGINEERS,AHMEDABAD	Approved
		9	BALDOTA VALVE AND FITTINGS PVT LTD,MUMBAI	Approved
		10	FLOWTECH,KOLKATA.	Not Approved
		11	HP VALVES & FITTINGS (INDIA) PVT. LTD,CHENNAI	Approved
98	**LIE/LIR**	1	PYROTECH ELECTRONICS (P) LTD,UDAIPUR,RAJASTHAN.	Approved
		2	CHEMIN CONTROLS AND INSTRUMENTATION PVT LTD,PONDICHERRY	Approved
		3	PRAMMEN INDUSTRIES,PUDUKKOTTAI, TAMILANADU.	Not Approved
		4	PROCON INSTRUMENTATION (P) LTD,CHENNAI	Approved
		5	SAJAS ELECTRICALS,TIRUCHARAPALLI/PUDUKKOTAI,TAMILAN	Not Approved
99	**Impulse and Sample Pipes (Alloy Steel)**	1	BHARAT HEAVY ELECTRICALS LTD, TIRUCHIRAPALLI,TAMILANADU.	Approved
		2	SUMITOMO CORPORATION,JAPAN.	Approved
		3	TPS TECHNITUBE ROHREN WERKE GMBH,DAUN,GERMANY	Approved
		4	JINDAL SAW LTD,CHENNAI	Approved
		5	INDIAN SEAMLESS METAL TUBES LTD,PUNE.	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha
Khairatabad, Hyd-500 082

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
		6	HEAVY METAL AND TUBES LTD,AHMEDABAD/MUMBAI	Approved
100	**Impulse and Sample Pipes Stainless Steel**	1	SUMITOMO CORPORATION,JAPAN.	Approved
		2	MBM TUBES PVT LTD,CHATTRAL,GUJARAT	Not Approved
		3	TUBACEX PRAKASH INDIA PVT LTD,UMBERGAON ,GUJARAT	Not Approved
		4	TPS TECHNITUBE ROHREN WERKE GMBH,DAUN,GERMANY	Approved
		5	RATNAMANI METALS & TUBES LTD,AHMEDABAD	Approved
		6	MAXIM TUBES COMPANY PVT LTD,AHMEDABAD	Approved
		7	SURAJ STAINLESS LIMITED,AHMEDABAD	Approved
		8	HEAVY METAL AND TUBES LTD,AHMEDABAD/MUMBAI	Approved
		9	SHUBHLAXMI METALS AND TUBES PVT. LTD, MUMBAI	Approved
101	**Impact Head Type Element**	1	EMERSON PROCESS MANAGEMENT INDIA PVT LTD,PAWANE,NAVI MUMBAI	Approved
		2	SWITZER PROCESS INSTRUMENTS PVT LTD,CHENNAI.	Approved
		3	STAR-MECH CONTROLS (I) PVT.LTD,PUNE.	Approved
		4	VERIS INC,NIWOT COLRADO,USA.(M/s CHANDAK INSTRUMENTS PVT LTD(VENDOR CODE:D447222.) is SYSTEM INTEGRATOR OF M/S VERIS	Not Approved
102	**Level Switch Top mounted**	1	LEVCON INSTRUMENTS P LTD KOLKATA	Approved
		2	SBEM PRIVATE LIMITED PUNE	Approved
		3	SIGMA INSTRUMENTS COMPANY BHANDUP(WEST)	Approved
		4	V.AUTOMAT & INSTRUMENTS PVT. LTD. NEW DELHI	Approved
		5	D.K.INSTRUMENTS PVT. LTD. DHAKURIA, KOLKATA	Approved
		6	PUNE TECHTROL PVT LTD,PUNE	Approved
		7	IGEMA GMBH,MUNSTER,GERMANY.	Not Approved
		8	CHEMTROLS SAMIL (INDIA) PVT. LTD. POWAI , MUMBAI	Approved

Chief Engineer
Thermal Projects Construct
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S.No	Name of System/Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks for YTPS (5x800MW)
103	**Mercury analyser**	1	THERMOFISHER USA/ THERMOFISHER, Mumbai.	Approved
		2	SICK, Germany/ SICK, India.	Approved
		3	Mercury Instruments. Germany/ ENVIRONNEMENT SA INDIA PVT LTD	Approved
		4	PS ANALYTICAL, UK/ AICPL , KOTA	Approved
		5	DURAG, Germany / DURAG, Bangalore, INDIA.	Approved
104	**3D BUNKER LEVEL MONITORING SYSTEM**	1	EIP TECHNOLOGIES (APM MAKE)	Approved
105	**Flue Gas Analyser- DILUTION TYPE**	1	M/s Environnement SA US /M/s. Environnement SA india pvt ltd.	Approved
		2	M/s Chemtrols industries ltd / M/s. Teledyne USA	Approved
		3	M/s. Nevco Engineers Pvt Ltd (OPSIS , SWEDEN)	Approved
		4	M/s Analyser instruments Co. Pvt ltd. (ECOTECH, AUSTRALIA)	Approved

NOTE: All Panel mounted items will be from BHEL Approved Sources.

3/11/18
Chief Engineer
Thermal Projects Construct
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
Maintenance and Calibration Equipment(Lab Items) Mechanical Package			Item Wise Makes	
1	**Dead Weight Tester**	1	DH-Budenberg,. (Wika)	Approved
		2	Dott. Ing. Scandura & FEM S.r.l.(Wika)	Approved
		3	PRESSUREMENT LTD,/ Fluke	Approved
		4	AMETEK	Approved
		5	Yantrika Instruments Pvt. Ltd.,	Approved
		6	DRUCK (GE)	Not Approved
		7	Budenberg	Not Approved
		8	Nagman Instruments & Electronics (P) Ltd.,	Not Approved
2	**Laboratory Test Pressure Gauges**	1	DH-Budenberg,. (Wika)	Approved
		2	ASHCROFT INC,	Approved
		3	Dott. Ing. Scandura & FEM S.r.l.(Wika)	Approved
		4	Yantrika Instruments Pvt. Ltd.	Approved
		5	Yantrika Instruments Pvt. Ltd.	Approved
		6	AFRISO-EURO-INDEX GMBH	Not Approved
		7	JVG Enginners,	Not Approved
		8	Budenberg	Not Approved
3	**Manometers**	1	Fitzer Instruments (I) Pvt. Ltd.,	Approved
		2	Dwyer Instruments INC.,	Approved
		3	DRUCK (GE)	Not Approved
		4	Kamrans	Not Approved
		5	Sharp	Not Approved
4	**Pressure & Vacuum Air Pump**	1	KNF Neuberger,	Approved
		2	Bharath Vacuum Pumps	Approved

Chief Engineer
Thermal Projects Constructio
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 0

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
		3	Toshniwal Brothers (Hyd) Pvt. Ltd.	Not Approved
		4	Elgi	Not Approved
		5	Vacnik	Not Approved
5	Pressure Comparator/ Pressure Comparator (Portable Type)/ Field Pressure Comparator (Portable Type)	1	AMETEK	Approved
		2	FLUKE / PRESSUREMENT LTD	Approved
		3	Beamex	Approved
		4	Dott. Ing. Scandura & FEM S.r.l.(Wika)	Approved
		5	GE (Druck)	Approved
		6	Yokogawa Electric Corporation	Approved
		7	TRANSCAT	Approved
		8	R&D Instruments	Not Approved
		9	Time Electronics	Not Approved
		10	Eurotron Instruments (UK) Ltd.,(EIUK)	Not Approved
		11	AOIP	Not Approved
		12	Wika Instruments	Not Approved
		13	Budenberg	Not Approved
		14	Yantrika Instruments Pvt. Ltd.	Approved
		15	Nagman	Not Approved
6	Temperature Calibration Bath	1	Isothermal Technology Ltd	Approved
		2	Dott. Ing. Scandura & FEM S.r.l., / Wika	Approved
		3	Fluke (Hart Scientific)	Approved
		4	AMETEK	Approved
		5	Eurotron Instruments (UK) Ltd.,(EIUK)	Not Approved
		6	TRANSCAT	Not Approved
		7	DRUCK (GE)	Not Approved
		8	R&D Instruments	Not Approved

Chief Engineer
Thermal Projects Construct
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
		9	Wika Instruments	Not Approved
		10	Nagman	Not Approved
7	Temperature Calibrators / Temperature Calibrator (Table Mounted)	1	AMETEK	Approved
		2	Druck (GE)	Approved
		3	Dott. Ing. Scandura & FEM S.r.l., / Wika	Approved
		4	Isothermal Technology Ltd	Approved
		5	Hart Scientific / FLUKE	Approved
		6	Thermo Scientific (HEREAUS)	Not Approved
		7	AOIP	Approved
		8	YOKOGAWA	Not Approved
		9	TRANSCAT	Not Approved
		10	TINSLEY	Not Approved
		11	Eurotron Instruments (UK) Ltd., (EIUK)	Approved
		12	WIKA INSTRUMENT	Not Approved
8	Hot Air Blower	1	BOSCH	Approved
		2	SKIL	Approved
9	Barometer / Aneroid Barometer	1	Wallace & Tiernan INC	Approved
		2	DRUCK (GE)	Approved
		3	Control Companey (Traceable)	Approved
		4	Extech Instruments Corporation	Approved
		5	WIKA INSTRUMENT	Approved
		6	Meriam Process Technologies	Not Approved
		7	COLE PARMER (Oakton)	Not Approved
		8	TINSLEY	Not Approved
		9	TRANSCAT	Not Approved

Chief Engineer
Thermal Projects Constructic
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
10	Surface Pyrometer / Infrared Pyrometer	1	LAND INSTRUMENTS	Approved
		2	FLUKE	Approved
		3	Raytek	Approved
		4	Acurate Sensor Technologies (Tempsens)	Approved
		5	Wika Instruments	Approved
		6	Heitronics GmbH	Approved
		7	TRANSCAT	Approved
		8	WIKA INSTRUMENT	Approved
		9	Testo	Not Approved
		10	Extech Instruments Corporation	Approved
		11	COLE-PARMER	Approved
		12	DRUCK	Approved
		13	TINSLEY	Approved
11	Pneumatic Test Bench	1	Yantrika Instruments Pvt. Ltd.	Approved
		2	Yokogawa India Ltd.	Approved
		3	Fluke	Approved
		4	The Tinsley Group Ltd.	Approved
		5	WIKA INSTRUMENT (Scandura)	Approved
		6	GE Sensing & Inspection Technologies	Not Approved
		7	R&D Instruments	Not Approved
		8	Nagman Instruments & Electronics (P) Ltd.	Not Approved
12	Portable Vacuum tester	1	AMETEK	Approved
		2	PRESSUREMENT LTD	Approved
		3	ASHCROFT INC	Approved
		4	Beamex	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
		5	Dott. Ing. Scandura & FEM S.r.l.(Wika)	Approved
		6	WIKA INSTRUMENT	Approved
		7	Yokogawa Electric Corporation	Approved
		8	TRANSCAT	Approved
		9	GE Sensing & Inspection Technologies,	Not Approved
		10	Eurotron Instruments (UK) Ltd.	Not Approved
		11	AOIP	Not Approved
		12	Time Electronics	Not Approved
		13	R&D Instruments	Not Approved
		14	Nagman	Not Approved
13	Portable Gas Analyzer	1	LAND INSTRUMENTS	Approved
		2	TESTO	Approved
		3	AFRISO-EURO-INDEX GMBH	Approved
		4	ENDEE ENGINEERS PVT LTD	Approved
		5	BACHARACH	Approved
		6	TINSLEY	Not Approved
		7	Eurotron Instruments (UK) Ltd., (EIUK)	Not Approved
14	Furnace	1	Isothermal Technology Ltd	Approved
		2	Fluke (Hart Scientific)	Approved
		3	Eurotron Instruments (UK) Ltd., (EIUK)	Approved
15	Suppressed Range Mercury In Glass Thermometer	1	Dott. Ing. Scandura & FEM S.r.l.(Wika)	Approved
		2	Swastik	Approved
		3	AMARELL GmbH & Co. KG	Approved
		4	TINSLEY	Not Approved
16	Oil Condition Monitor	1	Parker / Kittiwake	Approved
		2	Pamas	Approved

Chief Engineer
Thermal Projects Constructic
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
17	Portable Ultrasonic Flowmeter	1	GE Sensing & Inspection Technologies	Approved
		2	Flexim GMBH (Chemtrols)	Approved
		3	Micronics	Approved
		4	Fuji	Approved
		5	Tesco Compuflow	Approved
		6	ENDRESS HAUSER	Approved
		7	EUREKA	Approved
		8	TINSLEY	Approved
		9	FORBES MARSHALL	Approved
		10	TRANSCAT	Approved
		11	Adept Fluidyne Pvt. Ltd.	Not Approved
18	Wet & Dry Bulb Hygrometer	1	Yaska Control Technologies	Approved
		2	Extech Instruments Corporation	Approved
		3	GE Sensing & Inspection Technologies	Approved
		4	Polltech Instruments Pvt. Ltd.	Approved
		5	TINSLEY	Approved
		6	Transcat	Approved
		7	Amprobe	Not Approved
19	Flow meter Calibrator	1	GE (Druck)	Approved
		2	Yokogawa Electric Corporation	Approved
		3	ASHCROFT INC	Approved
		4	AMETEK	Approved
		5	Dott. Ing. Scandura & FEM S.r.l.(Wika)	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha
Khairatabad, Hyd-500 082

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
		6	TRANSCAT	Approved
		7	Tinsley	Not Approved
		8	Dwyer Instruments INC.	Approved
		9	Fluke	Approved
		10	R&D Instruments	Not Approved
20	Air Set	1	ABB	Approved
		2	SHAVO NORGEN (I) PVT. LTD.	Approved
		3	PLACKA INSTRUMENTS INDIA PVT. LTD.	Approved
21	Jewellers Lathe	1	Gee Dee Weiler	Approved
		2	HMT Machine Tools Ltd.,	Approved
		3	Batliboi	Approved
		4	PMT Machines Ltd.	Approved
		5	Godrej	Approved
		6	VENUS	Approved
		7	Sherline	Approved
22	Welding Machine	1	BOC India Limited	Approved
23	Grinding Wheel/Grinding Machine	1	BOSCH	Approved
24	Feeler Gauge	1	RS Components	Approved
		2	Sysco Tech Systems (India) Pvt. Ltd.	Approved
		3	Goodwill	Approved
		4	Small Tools Centre	Approved
		5	Mehta Tools Corporation	Approved
		6	Sri Varu Power Tools Co.	Approved
		7	JAIRAMDAS GROUP	Approved
		8	Stanley	Approved

Chief Engineer
Thermal Projects Constructio
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
25	Radial Drilling Machine	1	Eifco	Approved
		2	Ammar Tools	Approved
		3	New Master	Approved
		4	Bhavya Machine Tools	Approved
		5	Micro Engineering Works	Approved
		6	Premier	Approved
26	Portable Drilling Machine	1	BOSCH	Approved
27	Universal Digital Thermometer	1	Yaska Control Technologies	Approved
		2	Extech Instruments Corporation	Approved
		3	TRANSCAT	Approved
		4	GE Sensing & Inspection Technologies	Approved
		5	COLE PARMER	Approved
		6	AOIP	Approved
		7	Eurotron Instruments (UK) Ltd., (EIUK)	Approved
		8	Yudian Automation Technology Co. Ltd.	Approved
		9	Wika Instruments	Approved
		10	Fluke	Approved
		11	Amprobe	Approved
28	LOW AND MEDIUM PRESSURE CONTROLLER	1	ASHCROFT INC	Approved
		2	FLUKE - DH Instruments	Approved
		3	Yokogawa Electric Corporation	Approved
		4	Druck Limited	Approved
		5	Dott. Ing. Scandura & FEM S.r.l.(Wika)	Approved
		6	Beamex	Approved
		7	AMETEK	Approved
		8	DH-Budenberg,. (Wika)	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
		9	TRANSCAT	Approved
		10	WIKA	Not Approved
		11	Time Electronics	Not Approved
		12	AOIP	Not Approved
		13	R&D Instruments	Not Approved
		14	Nagman	Not Approved
		15	Eurotron Instruments (UK) Ltd,	Not Approved
29	PORTABLE PNEUMATIC/ HYDRAULIC CALIBRATOR	1	Beamex	Approved
		2	AMETEK	Approved
		3	FLUKE CORPORATION	Approved
		4	Yokogawa Electric Corporation	Approved
		5	Druck Limited	Approved
		6	Dott. Ing. Scandura & FEM S.r.l.(Wika)	Approved
		7	ASHCROFT INC	Approved
		8	DH-Budenberg,. (Wika)	Approved
		9	TRANSCAT	Approved
		10	WIKA INSTRUMENT	Not Approved
		11	Time Electronics	Not Approved
		12	Eurotron Instruments (UK) Ltd.	Not Approved
		13	R&D Instruments	Not Approved
		14	Nagman	Not Approved
		15	AOIP	Not Approved
30	Bench Vise & Hand Vise	1	Sysco Tech Systems (India) Pvt. Ltd.	Approved
		2	Small Tools Centre	Approved
		3	RS Components	Approved
		4	Goodwill	Not Approved
		5	Stanley	Not Approved

Chief Engineer
Thermal Projects Constructic
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
31	Vacuum Cleaner	1	EUREKA FORBES	Approved
		2	BOSCH	Approved
		3	LG	Approved
32	Anemometer (Portable)	1	Cole-Parmer	Approved
		2	TESTO, INC	Approved
		3	Extech Instruments Corporation	Approved
33	Screw Gauge	1	R. S. Components & Controls	Approved
		2	Sysco Tech Systems (India) Pvt. Ltd.	Approved
		3	Goodwill Enterprises	Approved
		4	Small Tools Centre	Approved
		5	Mehta Tools Corporation	Approved
		6	Sri Varu Power Tools Co.	Approved
		7	JAIRAMDAS GROUP	Approved
		8	Mitutoyo	Approved
		9	Baker	Approved
34	Pitot Tube	1	Dwyer Instruments INC.	Approved
		2	Switzer Instrument Ltd.	Approved
		3	Kamrans	Approved
		4	Amprobe	Approved
		5	Veris Instrument	Approved
35	Test Thermocouple	1	WIKA INSTRUMENT	Approved
		2	AMETEK	Approved
		3	Thermo Scientific (HEREAUS)	Approved
		4	Dott. Ing. Scandura & FEM S.r.l.(Wika)	Approved
		5	Isothermal Technology Ltd, U.K.	Approved
		6	FLUKE CORPORATION	Approved
		7	Druck Limited	Approved

Chief Engineer
Thermal Projects Construc
TSGENCO, Vi
Khairatabad, Hyd

S. No	Name of System/ Package	S. No (Vendors)	Name of Vendors	TSGENCO Remarks
		8	Eurotron Instruments (UK) Ltd.,(EIUK)	Approved
36	Vibration Calibrator (Portable Shaker Table)	1	Meggitt India Pvt Ltd.	Approved
		2	Forbes Marshall Pvt Ltd.(SINKAWA)	Approved

Chief Engineer
Thermal Projects Construction
TSGENCO, Vidyut Soudha,
Khairatabad, Hyd-500 082.

TELANGANA POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499321 Fax: 040 – 23499323.

From:
The Chief Engineer,
Thermal Projects Construction,
TSGENCO, 3rd Floor, A-Block,
Vidyut Soudha, Khiarathabad
Hyderabad-500 082.

To:
M/s Bharat Heavy Electricals Limited,
Industrial Systems Group,
P.B.No.1249, Prof.C N R Rao Circle,
IISc Post, Malleswaram,
Bangalore-560090

Attention:Sri Amit Kumar, Sr.Manager/Project Management & Commercial

Lr.No.CE/TPC/SE-3/EME-11/YTPS(5X800MW)/F.Vendors/D.No.49/18,Dt: 11-09-2018

Sir,

Sub: TSGENCO –YTPS (5X800MW) –Vendors for Ash Handling Package (AHP-Mechanical) being supplied M/s BHEL/ISG, Bangalore – Approval - Reg.

Ref: M/s BHEL letter ref: IS-1-15-2001/AHP Sub-Vendor Approval/02, Dt.29-05-2018.

******

Please refer to the letter cited above, wherein M/s BHEL/ISG, Bangalore has requested for approval of vendors for Ash Handling Package (AHP-Mechanical) for Yadadri Thermal Power Station (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the following vendors for Ash Handling Package (AHP-Mechanical) for Yadadri Thermal Power Station (5X800MW).

Ash Handling Package (AHP-Mechanical) :

Sl.No.	Item Description	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
1	**ASH HANDLING PACKAGE**	MACAWBER BEEKAY PVT.LTD, NOIDA	Not Approved
		THE INDURE PVT., LTD., NEW DELHI	Approved
		MCNALLY BHARAT ENGINEERING COMPANY LTD KOLKATA	Approved
		MECGALE PNEUMATICS PVT. LTD. NAGPUR	Approved
		LARSEN & TOUBRO KOLKATA ALONG WITH UNITED CONVEYOR CORPORATION (UCC-USA) - ALL SUPPLIES FROM INDIA	Approved

P.V-Seenj 11/9/18

Chief Engineer/TPC

Sl.No.	Item Description	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		OSM PROJECTS PRIVATE LIMITED WITH FUJIAN LONGKING COMPANY LIMITED,CHINA - ALL SUPPLIES FROM INDIA	Not Approved
		BHEL ISG, BANGALORE	Approved
2	**MS Pipes - SW/ERW (Black and Galavanized)**	SAIL ROURKELA	Approved
		WELSPUN CORP LIMITED, ANJAR, GUJARAT	Approved
		ASIAN MILLS PRIVATE LIMITED, AHMEDABAD, GUJARAT	Approved
		RATNAMANI METALS & TUBES, AHMEDABAD , GUJARATH	Approved
		SURYA ROSHNI LIMITED, BENGALURU, KARNATAKA	Approved
		JCO GAS PIPE LIMITED, CHINDWARA	Approved
		JOTINDRA STEEL & TUBES LTD. FARIDABAD, HARYANA	Approved
3	**Conveying Air Compressor**	ATLAS COPCO (INDIA) LTD. PUNE	Approved
		AERZEN MACHINES (INDIA) PVT LTD, VADODARA	Approved
		ELGI EQUIPMENT LTD, COIMBATORE	Approved
		INGERSOLL RAND, AHMEDABAD	Approved
4	**Instrument Air Compressor**	ATLAS COPCO (INDIA) LTD. PUNE	Approved
		AERZEN MACHINES (INDIA) PVT LTD, VADODARA	Approved
		ELGI EQUIPMENT LTD, COIMBATORE	Approved
		INGERSOLL RAND, AHMEDABAD	Approved
5	**Water Pumps/Misc Pumps (Horizontal)**	KIRLOSKAR BROTHERS LIMITED, KIRLOSKARWADI	Approved
		M/S SAM TURBO INDUSTRY PVT LTD, COIMBATORE	Approved
		KUBOTA CORPN. OSAKA JAPAN	Approved
		KISHOR PUMPS PVT. LTD., CHENNAI	Approved
		BEACON WEIR LTD, CHENNAI	Approved

P.V. Seeg 11/9/18

Chief Engineer/TPC

Sl.No.	Item Description	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		FLOWMORE LTD, GHAZIABAD	Approved
		BEST & CROMPTON ENGINEERING LIMITED, CHENNAI	Approved
		FLOWSERVES INDIA CONTROLS PVT LTD, COIMBATORE	Approved
		JYOTI LTD, VADODARA	Approved
		MATHER & PLATT PUMPS LIMITED, PUNE/KOLHAPUR	Approved
		WPIL LIMITED, GHAZIABAD	Approved
		VARAT PUMPS, KOLKATA	Approved
6	**Water Pumps/Misc Pumps (Vertical)**	KIRLOSKAR BROTHERS LIMITED, KIRLOSKARWADI	Approved
		M/S SAM TURBO INDUSTRY PVT LTD, COIMBATORE	Approved
		KUBOTA CORPN. OSAKA JAPAN	Approved
		KISHOR PUMPS PVT. LTD., CHENNAI	Approved
		BEACON WEIR LTD, CHENNAI	Approved
		FLOWMORE LIMITED, GHAZIABAD	Approved
		FLOWSERVES INDIA CONTROLS PVT LTD, COIMBATORE	Approved
		JYOTI LTD, VADODARA	Approved
		MATHER & PLATT PUMPS LIMITED, PUNE/KOLHAPUR	Approved
		SULZER PUMPS INDIA LTD., 9 M.I.D.C. THANE-BELAPUR ROAD, NAVI MUMBAI, MAHARASHTRA 400708	Approved
7	**Drain Sump Pumps/Submersible Pump**	MCNALLY SAYAJI ENGINEERING LIMITED, GHAZIABAD	Approved
		WPIL LIMITED, GHAZIABAD	Approved
		VARAT PUMPS & MACHINERY PVT LTD, KOLKATA	Approved
		FLOWMORE LIMITED, GHAZIABAD	Approved
		KIRLOSKAR BROTHERS LIMITED, KIRLOSKARWADI	Approved

11/9/18

Chief Engineer/TPC

Sl.No.	Item Description	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		M/S SAM TURBO INDUSTRY PVT LTD, COIMBATORE	Approved
		METSO INDIA PVT. LTD., NAVI MUMBAI, MAHARASHTRA, INDIA	Approved
		KSB, PUNE	Approved
		MODY INDUSTRY PRIVATE LTD (M/S WPIL LTD., GROUPS COMPANY) KOLKATA	Approved
8	**Ash Slurry pumps**	MCNALLY SAYAJI, BANGALORE	Approved
		WEIR MINERALS (INDIA) PVT. LTD. BANGALORE	Approved
		M/S SAM TURBO INDUSTRY PVT LTD, COIMBATORE	Approved
9	**Mono Rail Hoist / Chain pulley Block**	TRACTEL TIRFOR INDIA, PALWAL	Approved
		TRANSPADE ENGINEERING PVT LTD, BANGALORE	Approved
		ARMSEL , BENGALURU	Approved
		CENTURY CRANE ENGINEERS PVT LTD, BALLABGADH	Approved
		TUOBRO FURGUSON (INDIA) KOLKATA	Approved
		CONSOLIDATED HOIST, SATARA/PUNE	Approved
		HERCULES HOISTS LTD, RAIGAD	Approved
		LIFTING EQUIPMENTS AND ACCESSORIES, SHAHDARA, DELHI	Approved
		MORRIS HOISTS,JAIPUR, RAJASTHAN 302002	Approved
		SOUTHERN PLANTAID, SECUNDERABAD, TELANGANA 500003	Approved
10	**Electric Hoists**	MELTECH CRANES, THANE	Approved
		CENTURY CRANE ENGINEERS PVT LTD, BALLABGADH	Approved
		EDDY CRANES PVT LTD., MUMBAI	Approved
		GRIP ENGINEERS PVT LTD. FARIDABAD, HARYANA	Approved
		HERCULES HOISTS LTD, RAIGAD	Approved

Chief Engineer/TPC

Sl.No.	Item Description	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		LIFTING EQUIPMENTS AND ACCESSORIES,SHAHDARA, DELHI	Approved
		REVA INDUSTRIES LIMITED, FARIDABAD	Approved
		TRANSPADE ENGINEERING PVT LTD, BANGALORE	Approved
11	**Single Grider EOT Crane**	CONSOLIDATED HOIST, SATARA/PUNE	Approved
		TUOBRO FURGUSON, KOLKATA	Approved
		TRANSPADE ENGINEERING PVT LTD, BANGALORE	Approved
		TRACTEL TIRFOR INDIA, PALWAL	Approved
		CENTURY CRANE ENGINEERS PVT LTD, BALLABGADH	Approved
		HERCULES HOISTS LTD, RAIGAD	Approved
		ARMSEL MHE, BANGALORE	Approved
		REVA INDUSTRIES LTD, FARIDABAD	Approved
12	**Cast Basalt lined Pipes and Pipe Fittings**	DEMECH, PUNE	Approved
		THE INDURE PVT., LTD., NEW DELHI	Approved
		GOYENKA CAST ENGGNERING INDIA PVT LTD, RAIPUR	Approved
		BMW STEEL LIMITED, DEHRADUN	Approved
13	**Ball Valves**	SURYA VALVES & INSTRUMENTS MFG CO., TIRUCHIRAPPALLI, TAMIL NADU	Approved
		HAWA ENGINEERS LTD., AHMEDABAD	Approved
		A.V. VALVES LTD, AGRA	Approved
		MICON VALVES (INDIA), MUMBAI	Approved
		AKAY INDUSTRIES PVT LTD., DHARWAD, KARNATAKA	Approved
		INTERVALVE(INDIA) LIMITED, BENGALURU, KARNATAKA	Approved
		LEADER VALVES LTD, JALANDHAR	Approved
		MICROFINISH VALVES PRIVATE LIMITED, HUBLI	Approved
		WEIR BDK VALVES-A UNIT OF WEIR INDIA	Approved

PV 8/9/19

Chief Engineer/TPC

Sl.No.	Item Description	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		PVTL LTD, HUBLI	
14	**Butterfly Valves**	ATAM VALVES PVT LTD., JALANDHAR	Approved
		HAWA ENGINEERS LTD, AHMEDABAD	Approved
		MICON VALVES (INDIA), MUMBAI	Approved
		SURYA VALVES & INSTRUMENTS MFG CO., CHENNAI	Approved
		DEMBLA VALVES LTD, THANE	Approved
		FLOWSERVE, CHENNAI	Approved
15	**Knife Gate Valves**	ORBINOX INDIA PVT LTD, COIMBATORE	Approved
		SURYA VALVES & INSTRUMENTS MFG CO., CHENNAI	Approved
		ASHWATHI CONTROLS PVT. LTD., AHMEDABAD	Approved
		GENERAL ENGINEERING CONSORTIUM, BANGALORE	Approved
		M/S. BRAY CONTROLS INDIA PRIVATE LIMITED, CHENNAI	Approved
		BACHMANN INDUSTRIES INDIA LTD, FARIDABAD, HARYANA	Approved
		FOURESS ENGINEERING (I) LTD, BANGALORE	Approved
16	**Cast Steel, GATE, GLOBE, CHECK Valves**	AV VALVES, AGRA	Approved
		ATAM VALVES PVT LTD., JALANDHAR	Approved
		FLUIDLINE VALVES COMPANY PVT. LTD, WORLI, MUMBAI	Approved
		INTERVALVE(INDIA) LIMITED, BENGALURU, KARNATAKA	Approved
		LEADER VALVES LTD. JALANDHAR	Approved
		NITON VALVE INDUSTRIES PVT LTD, NAVI MUMBAI/AHMEDABAD	Approved
		STEEL STRONG VALVES (I) PVT.LTD., NAVI MUMBAI/AHMEDABAD	Approved
		WEIR BDK VALVES- A UNIT OF WEIR INDIA PVT. LTD. HUBLI	Approved

11/9

Chief Engineer/TPC

Sl.No.	Item Description	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		M/S MICON VALVES (INDIA) LTD, MUMBAI	Approved
17	**Cast Iron. GATE, GLOBE, CHECK Valves**	AV VALVES, AGRA	Approved
		H SARKAR, HOWRAH	Approved
18	**WEIGH BRIDGE**	RICE LAKE, TAMILNADU	Approved
		TECHNO SCALE, AHMEDABAD	Approved
		ABB LIMITED, BANGALORE	Approved
		AVERY (I) LTD., BALLABHGARH	Approved
		SCHENCK JENSON & NICHOLSON, KOLKATA	Approved
		SCHENCK PROCESS INDIA LIMITED, BENGALURU, KARNATAKA	Approved
		ESSAE DIGITRONICS PRIVATE LIMITED, BANGALORE	Approved
		IPA, PVT. LTD,BENGALURU, KARNATAKA	Approved
19	**Water Treatment Plant**	EUREKA FORBES LTD, MUMBAI	Approved
		GEO MILLER & COMPANY PRIVATE LIMITED, OKHLA, NEW DELHI	Approved
		ION EXCHANGE INDIA LTD., MUMBAI	Approved
		THERMAX LTD., PUNE	Approved
		TRIVENI ENGINEERING & INDUSTRIES LTD. NOIDA	Approved
		VA TECH WABAG LTD., CHENNAI	Approved
		POLLUCON ENGINEERING SERVICE, FARIDABAD, HARYANA	Approved
20	**Cast Iron Pipes**	ELECTROSTEEL, CHENNAI	Approved
		KAPILASH DHATU, NAGPUR	Approved
21	**Vacuum Pump**	GARUDA ENGINEERING, AHMEDABAD	Approved
22	**MSERW Pipe as per IS 1239 Upto 150 NB**	DADU PIPES, SECUNDRABAD	Approved
23	**Castable Refractory**	TRL KROSAKI, BANGALORE	Approved

Chief Engineer/TPC

Sl.No.	Item Description	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		ABS REFRACTORIES PVT.LTD., KATNI	Approved
		BHASKAR REFRACTORIES&SW PIPES P LTD, FARIDABAD	Approved
		CALDERYS INDIA REFRACTORIES LTD., KATNI	Approved
		CASTWEL INDUSTRIES, NAGPUR	Approved
		DALMIA REFRACTORIES LIMITED, TIRUCHIRAPALLI, TAMIL NADU	Approved
		INDUSTRIAL ASSOCIATES, KOLKATA	Approved
		MAHAKOSHAL REFRACTORIES PVT. LTD, KATNI	Approved
		SHARADAA CERAMICS PVT.LTD. CHENNAI	Approved
		SOUVENIOR CERAMICS, FARIDABAD	Approved
		VISHVA VISHAL ENGINEERING LTD., MUMBAI	Approved
		VISHWAKARMA REFRACTORIS PRIVATE, BENGALURU	Approved
24	**Gratings**	INDIANA GRATINGS, PUNE	Approved
25	**Blower**	KAY INTERNATIONAL LTD, SONEPAT	Approved
26	**Air Dryer**	DELAIR INDIA PRIVATE LIMITED, GURGAON	Approved
		SUMMIT HYGRONICS PRIVATE LIMITED, COIMBATORE	Approved
27	**Gear Box**	PREMIUM TRANSMISSION, PUNE/FALTA/AURANGABAD	Approved
		FLENDER LIMITED, CHENNAI	Approved
		ELECON ENGINEERING CO . LTD. V V NAGAR	Approved
		NEW ALLENBARRY WORKS, KOLKATA	Approved
		SHANTHI, COIMBATORE	Approved
28	**Fluid Coupling**	PREMIUM TRANSMISSION, AURANGABAD	Approved
		FLUIDOMAT, DEWAS	Approved
		ELECON ENGINEERING CO. LTD. V V NAGAR	Approved
		VOITH, HYDERABAD	Approved

P V Seeg 11/9

Chief Engineer/TPC

Please note that this approval of vendors for Supply of items listed in Ash Handling Package (AHP-Mechanical) does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Yours faithfully

11/9/18

Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
VIDYUT SOUDHA::HYDERABAD - 500082.
CIN:U40102TG2014SGC094070 Phone:040-23499261,Fax:040-23499263.
Web site: www.tsgenco.co.in email id: cetpctgenco@gmail.com

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiaratabad Hyderabad-500 082.	M/s Bharat Heavy Electricals Limited, Component Fabrication Plant, Rudrapur (U S Nagar)-263153, Uttarakhand. T : 05944-257250 Email:rupesh@bhel.in

Attention: Sri Rupesh Kumar, Dy. Mgr/Engineering

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. Rud Vendors Approval/D.No.49/19,Dt: 20.06.19

Sir,

Sub: TSGENCO – YTPS (5X800MW) – M/s BHEL request for additional Vendor approval of M/s Epothane Civilec Engineers Pvt. Ltd., Ghaziabad for supplying Epoxy Insulator – Reg.

Ref: 1) Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. Rud Vendors Approval/D.No.70/18, Dt:18.12.2018
2) M/s BHEL letter ref: BHEL/RUD/ENGG./YADADRI/16-095-A-2/903/008, Dt:16.05.2019.

******

Please refer to the letter (2) cited above, wherein M/s BHEL/Rudrapur has requested for approval of M/s Epothane Civilec Engineers Pvt. Ltd., Ghaziabad as additional vendor for supplying Epoxy Insulator and also requested to accord approval of the vendors which were not approved earlier vide ref (1) cited above for YTPS (5X800MW). In this regard, it is to inform that the vendors approval accorded vide this office letter (1) cited holds good.

However, the credentials of M/s Epothane Civilec Engineers Pvt. Ltd., Ghaziabad were reviewed and TSGENCO remarks against the vendor pertaining to YTPS (5X800MW) are furnished below.

Sl. No.	Component/Item	Name of Vendor	TSGENCO Remarks
1	Epoxy Insulator	M/s Epothane Civilec Engineers Pvt. Ltd., Ghaziabad	Not Approved

Please note that this approval of vendor does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Yours faithfully

20/6/19

CHIEF ENGINEER/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s Bharat Heavy Electricals Limited, PS-PEM, PPEI Building, Plot No 25, Sector 16A, Noida-201301 Email: nainasingh@bhel.in

Kind Attention:Smt.Naina Singh, Mgr./ PG-II/PEM, Noida

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No. 51 /18,Dt:23 .10.2018

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of Vendors furnished by M/s BHEL/PEM unit - Reg.

Ref: 1. M/s BHEL/PS-PEM/PG-II/TSGENCO/YAD/07, dated: 04.05.2018.
2. M/s BHEL/PEM, Email:Dt.05-07-2018
3. M/s BHEL/PEM, Email:Dt.23-07-2018
4. M/s BHEL/PEM, Email:Dt.09-08-2018
5. M/s BHEL/PEM, Email:Dt.20-09-2018
6. M/s BHEL /PEM, Email:Dt.22-09-2018

******

Please refer to the letter 1st cited above, wherein M/s BHEL/PEM has requested for approval of vendors for Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of following list of items does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: List of TSGENCO Approved Vendors of M/s BHEL/PEM Unit.

Yours faithfully,

23/10/18

Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.

3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
I	**PACKAGE CATEGORY = MECH. SYSTEM ENGG.**			
1	**MISC. PUMPS (HORIZONTAL)**	1	BEACON WEIR LTD., CHENNAI	Approved
		2	BEST AND CROMPTON ENGG LTD.,CHENNAI	Approved
		3	FLOWMORE LTD., HARYANA	Approved
		4	FLOWSERVE INDIA CONTROLS PVT. LTD., KOLKATA	Approved
		5	JYOTI LTD.,GUJARAT	Approved
		6	KIRLOSKAR BROTHERS LTD., PUNE	Approved
		7	KISHORE PUMPS CHENNAI	Approved
		8	KUBOTA CORPN, JAPAN	Approved
		9	MAX FLOW PUMPS INDIA PVT. LTD., GURGAON	Approved
		10	SAM PUMP,TAMILNADU	Approved
		11	WPIL LIMITED, KOLKATA	Approved
		12	WILO MATHER & PLATT PUMPS LTD., MUMBAI	Approved
		13	VARAT PUMP AND MACHINERY PVT. LTD., kOLKATA	Not Approved
		14	BHARAT PUMPS & COMPRESSORS LTD, ALLAHABAD (UP)	Not Approved
		15	SINTECH PRECISION PRODUCT LTD., GHAZIABAD(UP)	Not Approved
		16	V-FLO PUMPS & SYSTEMS CO. LTD., CHINA	Not Approved
2	**MISC. PUMPS (VERTICAL)**	1	BEACON WEIR LTD., CHENNAI	Approved
		2	FLOWMORE LTD., HARYANA	Approved
		3	FLOWSERVE INDIA CONTROLS PVT. LTD., KOLKATA	Approved
		4	JYOTI LTD.,GUJARAT	Approved

PV Seeniy 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		5	KIRLOSKAR BROTHERS LTD., PUNE	Approved
		6	KUBOTA CORPN, JAPAN	Approved
		7	KISHORE PUMPS CHENNAI	Approved
		8	SAM PUMP,TAMILNADU	Approved
		9	SULZER PUMPS INDIA LTD.,MAHARASTRA	Approved
		10	WILO MATHER & PLATT PUMPS LTD., MUMBAI	Approved
		11	WPIL LIMITED, KOLKATA	Approved
		12	BHARAT PUMPS & COMPRESSORS LTD, ALLAHABAD (UP)	Not Approved
		13	SINTECH PRECISION PRODUCT LTD. GHAZIABAD (UP)	Not Approved
		14	VARAT PUMP AND MACHINERY PVT. LTD., KOLKATA	Not Approved
3	**SUMP PUMPS/ SUBMERSIBLE PUMPS**	1	DARLING PUMPS PVT. LTD., INDORE	Approved
		2	FLOWMORE LTD., HARYANA	Approved
		3	MCNALLY SAYAJI ENGINEERING LIMITED, GUJARAT	Approved
		4	SU MOTORS PVT. LTD., MUMBAI	Approved
		5	VARAT PUMP AND MACHINERY PVT. LTD., KOLKATA	Approved
		6	WPIL LIMITED, KOLKATA	Approved
		7	AQUA MACHINERIES (P) LTD., GUJARAT	Approved
		8	JEE PUMPS (GUJ) PVT LTD, GUJARAT	Approved
		9	JASCO PUMP PVT. LTD., GUJARAT	Approved
4	**SELF CLEANING STRAINERS**	1	AMIAD FILTRATION SYSTEMS LTD, MUMBAI	Approved
		2	FILTERATION ENGINEERS (I) PVT. LTD., MUMBAI	Approved
		3	GEA BGR ENERGY SYSTEM INDIA LTD., CHENNAI	Approved

PV Sastry 23/10

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		4	MULTITEX FILTRATION ENGINEERS LIMITED, NEW DELHI	Approved
		5	TAPROGGE GMBH, GERMANY	Approved
		6	OTOKLIN GLOBAL BUSINESS LIMITED, MUMBAI	Approved
5	**HEAT EXCHANGERS (PLATE TYPE)**	1	ALFA LAVAL (INDIA) LTD. NEW DELHI	Approved
		2	GEA ECOFLEX INDIA PVT LTD *(NAME CHANGED TO KELVION INDIA PVT. LTD., MUMBAI)*	Approved
		3	IDMC LIMITED, GUJARAT	Approved
		4	SONDEX HEAT EXCHANGERS INDIA LTD, GUJARAT	Approved
		5	TRANTER INDIA PRIVATE LIMITED, PUNE	Approved
		6	HISAKA WORKS LTD., JAPAN	Approved
6	**COLTCS**	1	C.Q.M. LTD, ISRAEL	Approved
		2	GEA BGR ENERGY SYSTEM INDIA LTD., CHENNAI	Approved
		3	MULTITEX FILTRATION ENGINEERS LIMITED, NEW DELHI	Approved
		4	TAPROGGE GMBH, GERMANY	Approved
		5	NORTHERN HEAVY INDUSTRIES GROUP CO. LTD., CHINA	Not Approved
		6	BEIJING CEP GREEN WAVE SCI-TECH CO. LTD., CHINA	Not Approved
7	**APRDS**	1	CONTROL COMPONENT INDIA PVT. LTD., NOIDA	Approved
		2	DAUME REGELARMATUREN GMBH, GERMANY	Approved
		3	HOLTER REGELARMATUREN GMBH & CO., GERMANY	Approved
		4	INSTRUMENTATION LTD., KERALA	Approved
		5	SPX CORPORATION, USA	Approved
		6	KOSO INDIA PRIVATE LIMITED, MAHARASHTRA	Not Approved

23/10

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		7	WALDEMAR PRUSS ARMATURENFABRIK GMBH, GERMANY	Not Approved
		8	KSB MIL CONTROLS LTD., KERALA	Not Approved
		9	PARCOL S.P.A, ITALY	Not Approved
8	**CONICAL STRAINERS**	1	ACME FLUID SYSTEMS, GUJARAT	Approved
		2	JAYPEE INDUSTRIES PVT. LTD., NEW DELHI	Approved
		3	MULTITEX FILTRATION ENGINEERS LIMITED, NEW DELHI	Approved
		4	NISSAN SCIENTIFIC PROCESS EQUIPMENT PVT.LTD., MAHARASHTRA	Approved
		5	OTOKLIN GLOBAL BUSINESS LIMITED, MUMBAI	Approved
		6	FILTERATION ENGINEERS (I) PVT. LTD., MUMBAI	Approved
		7	BHATIA ENGINEERING CO., NEW DELHI	Approved
		8	BOMBAY CHEMICAL EQUIPMENTS, MUMBAI	Not Approved
		9	FILTER CONCEPT PRIVATE LIMITED, GUJARAT	Not Approved
		10	GUJARAT OTOFILT, GUJARAT	Not Approved
		11	SUNGOV ENGINEERING PVT. LTD., CHENNAI	Not Approved
		12	GRAND PRIX ENGINEERING PVT. LTD., FARIDABAD, HARYANA	Not Approved
		13	RAK DIN ENGINEERS, HARYANA	Not Approved
9	**DEBRIS FILTER**	1	GEA BGR ENERGY SYSTEM INDIA LTD., CHENNAI	Approved
		2	TAPROGGE GMBH, GERMANY	Approved
		3	MULTITEX FILTRATION ENGINEERS LIMITED, NEW DELHI	Approved
		4	BEIJING CEP GREEN WAVE SCI-TECH CO. LTD., CHINA	Not Approved
		5	QINGDAO HUATAI ELECTRIC EQUIPMENT CO. LTD, CHINA	Not Approved
II	**PACKAGE CATEGORY = MECH. PIPING & LAYOUT**			
1	**THERMAL INSULATION(R-**	1	EFFICIENT ENTERPRISES HYDERABAD	Approved

P. V. Seeniy 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
	MATTRESSES/P-SECN)	2	GOENKA ROCKWOOL (INDIA) PVT.LTD., CHHATISGARH	Approved
		3	JAMSHEDPUR MINERAL WOOL MFG CO, JHARKHAND	Approved
		4	LLOYD INSULATIONS (INDIA) LTD., NEW DELHI	Approved
		5	LLOYD ROCKFIBRES LTD., NEW DELHI	Approved
		6	LAPINUS ROCKWOOL P LTD, NEW DELHI	Approved
		7	POLYBOND INSULATION PRIVATE LIMITED, CHATTISGARH	Approved
		8	PUNJSTAR INSULATIONFIBRE, NEW DELHI	Approved
		9	ROCKWOOL INDUSTRIES, NEW DELHI	Approved
		10	ROCKWOOL INDIA PVT. LTD., HYDERABAD	Approved
		11	ROXUL-ROCWOOL INSULATION, GUJARAT	Approved
		12	SHREERAM EQUITECH PRIVATE LIMITED, CHATTISGARH	Approved
		13	THERMOCARE ROCKWOOL INDIA PRIVATE LTD., CHATTISGARH	Approved
		14	DHANBAD ROCKWOOL INSULATION (P) LTD., JHARKHAND	Approved
		15	HI-TEC ROCKFIBRE PVT. LTD., CHATTISGARH	Approved
		16	MINSULATE MANUFACTURING COMPANY, JHARKHAND	Approved
2	**BALL VALVES**	1	A.V. VALVES LTD, AGRA (UP)	Approved
		2	AKAY INDUSTRIES PVT.LTD., KARNATAKA	Approved
		3	CHEMTECH INDUSTRIAL VALVES, MAHARASTRA	Approved
		4	DEMBLA VALVES, MAHARASTRA	Approved
		5	HITECH VALVES, CHENNAI	Approved
		6	HAWA VALVES, MUMBAI	Approved

P.V. Seniv 25/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		7	INTERVALVE (INDIA) LTD., PUNE	Approved
		8	JOSHI JAMPALA ENGG PVT LTD, MAHARASTRA	Approved
		9	LEADER VALVES LTD., PUNJAB	Approved
		10	MICROFINISH VALVES PVT LTD., KARNATAKA	Approved
		11	MICON VALVES INDIA, MUMBAI	Approved
		12	SURYA VALVES AND INSTRUMENTS MFG CO., TAMILNADU	Approved
		13	VALTECH INDUSTRIES, MUMBAI	Approved
		14	WEIR BDK VALVES- A UNIT OF WEIR INDIA PVT. LTD.- NEW DELHI	Approved
		15	HAWA ENGINEERS LTD., GUJARAT	Approved
		16	ATAM VALVES PVT. LTD., PUNJAB	Approved
		17	BELGAUM AQUA VALVES PVT. LTD., KARNATAKA	Not Approved
		18	CANLE VALVES PRIVATE LIMITED, TAMIL NADU	Not Approved
		19	CRESCENT VALVES MFG CO. PVT. LTD, MUMBAI	Not Approved
		20	DELVAL FLOW CONTROLS PVT. LTD., NOIDA (UP)	Not Approved
		21	MEVADA ENGINEERING WORKS PVT LTD., MUMBAI	Not Approved
		22	UNIFLOW, CHENNAI	Not Approved
3	**BUTTERFLY VALVES (STEAM SERVICE)**	1	FOURESS ENGG. INDIA LTD., MUMBAI	Approved
		2	INSTRUMENTATION LTD., KERALA	Approved
		3	NENGFA WEIYE TIELING VALVE JOINT-STOCK CO. LTD., CHINA	Not Approved
4	**AIR RELEASE VALVES**	1	A.V. VALVES LTD, AGRA (UP)	Approved
		2	G.M. DALUI AND SONS PVT.LTD., WEST BENGAL	Approved
		3	LEADER VALVES LTD., PUNJAB	Approved

PV Sastry 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		4	UPADHAYA VALVES MANUFACTURERS PRIVATE LIMITED, KOLKATA	Approved
		5	VENUS PUMPS AND ENGG. WORKS, KOLKATA	Approved
		6	R AND D MULTIPLES (METAL CAST) PVT LTD, MUMBAI	Approved
		7	K P MONDAL & SONS, KOLKATA	Not Approved
5	**AIR TRAPS**	1	ARMSTRONG INTRNL PVT LTD, CHENNAI	Approved
		2	ASIAN INDUSTRIAL VALVES & INSTRUMENTS, TAMILNADU	Approved
		3	FORBES MARSHALL PVT.LTD., PUNE	Approved
		4	PENNANT ENGINEERING PVT. LTD., PUNE	Approved
		5	ESCO STEAMCON PVT. LTD., GUJARAT	Not Approved
		6	UNI KLINGER LIMITED, MUMBAI	Not Approved
6	**STEAM TRAPS**	1	ARMSTRONG INTRNL PVT LTD, CHENNAI	Approved
		2	ASIAN INDUSTRIAL VALVES & INSTRUMENTS, TAMILNADU	Approved
		3	FORBES MARSHALL PVT.LTD., PUNE	Approved
		4	LEADER VALVES LTD., PUNJAB	Approved
		5	PENNANT ENGINEERING PVT. LTD., PUNE	Approved
		6	ESCO STEAMCON PVT. LTD., GUJARAT	Not Approved
7	**METAL EXPANSION BELLOWS**	1	FLEXICAN BELLOWS AND HOSES PVT. LTD., GUJARAT	Approved
		2	FLEXATHERM EXPANLLOW PVT. LTD., GUJARAT	Approved
		3	LONESTAR INDUSTRIES, CHENNAI	Approved
		4	MB METALLIC BELLOWS PVT. LTD., CHENNAI	Approved
		5	METALLIC BELOWS INDIA PVT. LTD., CHENNAI	Approved
		6	TEDDINGTON ENGINEERED SOLUTIONS LTD. UK	Approved
		7	B D ENGINEERS, GUJARAT	Not Approved

PV 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
8	**THERMAL INSULATION-ANCILLARY MATERIAL**	1	ALLIED INSULATIONS (INDIA), GHAZIABAD (UP)	Approved
		2	ENERGY SAVING AND ALLIED PRODUCTS, HARYANA	Approved
		3	HKI ENTERPRISES MUMBAI	Approved
		4	INDUSTRIAL ASSOCIATES, KOLKATA.	Approved
		5	LLOYD INSULATIONS (INDIA) LIMITED, NEW DELHI	Approved
		6	SUDHIR TRADING COMPANY, NEW DELHI	Approved
		7	SURESH INDUSTRIAL CORPORATION, CHANDIGARH	Approved
		8	SURESH FASTENERS, CHANDIGARH	Approved
		9	SHREE ENGINEERS, INDORE (MP)	Not Approved
9	**ALUMINIUM SHEETS/COILS**	1	BHARAT ALUMINIUM COMPANY LTD, CHHATTISGARH	Approved
		2	HINDALCO INDUSTRIES LTD, MUMBAI	Approved
		3	JINDAL ALUMINIUM LTD, KARNATAKA	Approved
		4	NATIONAL ALUMINIUM COMPANY LTD., ODISHA	Approved
		5	CHONGQING LANREN ALUMINIUM CO. LTD., CHINA	Not Approved
10	**STEEL GATE/GLOBE/NR VALVES (WATER SYSTEM)**	1	A.V. VALVES LTD, AGRA (UP)	Approved
		2	ATAM VALVES PVT. LTD., PUNJAB	Approved
		3	FLUIDLINE VALVES COMPANY PVT.LTD., GHAZIABAD (UP)	Approved
		4	INTERVALVE (INDIA) LTD., PUNE	Approved
		5	LEADER VALVES LTD., PUNJAB	Approved
		6	NITON VALVE INDUSTRIES PVT LTD, MUMBAI	Approved
		7	STEEL STRONG VALVES (I) PVT.LTD., MUMBAI	Approved

PV Seetha 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		8	WEIR BDK VALVES- A UNIT OF WEIR INDIA PVT. LTD., NEW DELHI	Approved
		9	FOURESS ENGG. INDIA LTD., MUMBAI	Approved
		10	HAWA ENGINEERS LTD., GUJARAT	Approved
		11	MICON VALVES (INDIA) PVT. LTD., MAHARASTRA	Approved
		12	VALTECH INDUSTRIES, MUMBAI	Approved
		13	HAWA VALVES (INDIA) PVT. LTD., MUMBAI	Approved
		14	CANLE VALVES PRIVATE LIMITED, TAMIL NADU	Not Approved
		15	OSWAL INDUSTRIES LTD, MUMBAI	Not Approved
		16	NSSL PRIVATE LIMITED, NAGPUR, MAHARASHTRA	Not Approved
		17	V.K. VALVES PVT. LTD., PUNJAB	Not Approved
III	**PACKAGE CATEGORY = MECHANICAL AUXILIARY**			
1	**FIRE TENDER**	1	AGNI INDUSTRIAL FIRE SERVICES FARIDABAD	Approved
		2	RELIANCE FIRE & SAFETY HYDERABAD	Approved
		3	SEAARA UNIVERSAL PVT LTD,HYDERABAD	Approved
		4	VIJAY FIRE VEHICLES AND PUMPS LTD, MUMBAI	Approved
		5	BRIJBASI HI-TECH UDYOG LTD, UP	Approved
		6	AMBALA COACH BUILDERS, HARYANA	Approved
		7	AAREL INDUSTRIES, MADHYA PRADESH	Approved
		8	UNITED MANUFACTURING CO., NEW DELHI	Not Approved
2	**COMPRESSED AIR SYSTEM**	1	ATLAS COPCO (INDIA) LTD., GURGAON	Approved
		2	AERZEN MACHINES PVT LTD,	Approved
		3	CHICAGO PNEUMATIC SALES,NEW DELHI	Approved
		4	ELGI EQUIPMENTS LTD, NEW DELHI	Approved
		5	INGERSOLL- RAND (INDIA) LTD., HARYANA	Approved

PV Sonis 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		6	KIRLOSKAR PNEUMATIC CO. LTD., NEW DELHI	Approved
3	**AIR CONDITIONING SYSTEM**	1	ADVANCE VENTILATION PVT.LTD., NEW DELHI	Approved
		2	BLUE STAR LTD., MUMBAI	Approved
		3	CARRIER AIRCON PVT LTD,HARYANA	Approved
		4	DRAFT-AIR (INDIA) PVT. LTD., NEW DELHI	Approved
		5	GODREJ & BOYCE MFG CO LTD, NEW DELHI	Approved
		6	MW HIGH TECH PROJECTS (I) PVT. LTD., HARYANA	Approved
		7	STERLING AND WILSON LIMITED, KOLKATA	Approved
		8	VOLTAS LTD., MUMBAI	Approved
		9	GEMINI SHREEWAS (ENGINEERS) PVT. LTD., CHENNAI	Not Approved
		10	INDUSTRIAL PROJECT & PRODUCTS CO., GURGAON	Not Approved
		11	ROOTS COOLING SYSTEMS PVT. LTD., NOIDA (UP)	Not Approved
4	**VENTILATION SYSTEM**	1	AIR LINK ENGINEERS PVT. LTD., NEW DELHI	Approved
		2	ADVANCE VENTILATION PVT.LTD., NEW DELHI	Approved
		3	APC SYSTEMS & PRODUCTS PVT LTD, KOLKATA	Approved
		4	BLUE STAR LTD., MUMBAI	Approved
		5	C.DOCTOR AND CO. PVT.LTD, KOLKATA	Approved
		6	DRAFT-AIR (INDIA) PVT. LTD., NEW DELHI	Approved
		7	DUSTVEN PVT LTD, , KARNATAKA	Approved
		8	MESINA , MUMBAI	Approved
		9	ROOTS COOLING SYSTEMS PVT.LTD., NOIDA (UP)	Approved
		10	S.K.SYSTEMS PRIVATE LTD., HARYANA	Approved

P V Sonia 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		11	STERLING AND WILSON LIMITED, KOLKATA	Approved
		12	VOLTAS LTD., MUMBAI	Approved
		13	TAP ENGINEERING, CHENNAI	Approved
		14	INDUSTRIAL PROJECT & PRODUCTS CO., GURGAON	Not Approved
		15	PACK PLAST INDUSTRIES, RAJASTHAN	Not Approved
5	**FUEL OIL HANDLING & STORAGE SYSTEM**	1	TECHNO ELECTRIC AND ENGG. CO. LTD., KOLKATA	Approved
		2	TECHNOFAB ENGG. LTD., NEW DELHI	Approved
		3	THERMOSYSTEMS PVT. LTD., HYDERABAD	Approved
		4	UNITECH MACHINES LTD., GURGAON (UP)	Approved
		5	GENERAL MECHANICAL WORKS PVT. LTD., GUJARAT	Approved
		6	RAUNAQ INTERNATIONAL LIMITED, HARYANA	Approved
		7	UNITED SYSTEMS & PROJECTS (INDIA) PVT. LTD., TELANGANA	Approved
		8	NEW FIRE ENGINEERS PVT LTD, MUMBAI	Not Approved
		9	SHALKOOT MECHANIQUE PVT. LTD., NOIDA (UP)	Not Approved
		10	XICON INTERNATIONAL LIMITED, MUMBAI	Not Approved
6	**CHEMICAL DOSING SYSTEM**	1	ENPRO INDUSTRIES PVT.LTD., PUNE	Approved
		2	MR SYSTEMS, WESTBENGAL	Approved
		3	POWER PIPING COMPANY, TAMIL NADU	Approved
		4	PSI ENGINEERING SYSTEMS (P) LTD., CHENNAI	Approved
		5	POSITIVE METERING PUMPS (I) PVT. LTD., MAHARASHTRA	Approved
		6	TECHNO CONSULTANTS, MUMBAI	Approved
		7	TECHNOSTRENGTH PVT. LTD., HYDERABAD	Approved

23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		8	V.K PUMP INDUSTRIES PVT LTD, PUNE	Approved
		9	N.M. ENTERPRISES, NEW DELHI	Not Approved
		10	ROCKWIN FLOWMETER INDIA PVT. LTD., GHAZIABAD (UP)	Not Approved
		11	SWELORE ENGG. PVT. LTD, GUJARAT	Not Approved
7	**D/G EOT CRANE ABOVE 100T**	1	ANUPAM INDUSTRIES LTD., GHAZIABAD (UP)	Approved
		2	FURNACE & FONDRY EQUIPMENT CO., MUMBAI	Approved
		3	HEAVY ENGG. CORPORATION LTD., JHARKHAND	Approved
		4	MUKAND LIMITED, MAHARASHTRA	Approved
		5	TRANSPADE ENGG PVT LTD, KARNATAKA	Approved
		6	WMI KONECRANES INDIA LTD., NEW DELHI	Approved
		7	KONECRANES PVT. LTD., MUMBAI	Approved
		8	HENAN WEIHUA HEAVY MACHINERY CO. LTD., CHINA	Not Approved
		9	ALPHA SERVICES, RAJASTHAN	Not Approved
		10	ELECTROMECH MATERIAL HANDLING SYSTEMS (INDIA) PVT. LTD., PUNE	Not Approved
		11	REVA INDUSTRIES LTD., HARYANA	Not Approved
		12	TEREX INDIA PVT. LTD., PUNE	Not Approved
		13	UNIQUE INDUSTRIAL HANDLERS PVT. LTD., MUMBAI	Not Approved
8	**D/G EOT CRANE UPTO 100T**	1	ANUPAM INDUSTRIES LTD., GHAZIABAD (UP)	Approved
		2	CRANEX LIMITED, NEW DELHI	Approved
		3	CENTURY CRANE ENGINEERS PVT. LTD., HARYANA	Approved
		4	FURNACE & FOUNDRY EQUIPMENTS CO., MUMBAI	Approved
		5	GRIP ENGINEERS PVT. LTD., HARYANA	Approved

23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		6	HEAVY ENGG. CORPORATION LTD., JHARKHAND	Approved
		7	REVA INDUSTRIES LTD., HARYANA	Approved
		8	MUKAND LIMITED, MAHARASHTRA	Approved
		9	KONECRANES PVT. LTD., MUMBAI	Approved
		10	ALPHA SERVICES, RAJASTHAN	Not Approved
		11	BRADY & MORRIS ENGINEERING CO. LTD., GUJARAT	Not Approved
		12	ELECTROMECH MATERIAL HANDLING SYSTEMS (INDIA) PVT. LTD, PUNE	Not Approved
		13	GMW PRIVATE LIMITED, GUJARAT	Not Approved
		14	HENAN WEIHUA HEAVY MACHINERY CO. LTD., CHINA	Not Approved
		15	MEEKA MACHINERY PVT. LTD., GUJARAT	Not Approved
		16	MANGLA HOISTS PVT LTD, NEW DELHI	Not Approved
		17	ROCKWELL HOISTO CRANES PVT. LTD., HARYANA	Not Approved
		18	S CRANE ENGINEERING WORKS, MUMBAI	Not Approved
		19	SAFEX ENERGY PVT. LTD., GUJARAT	Not Approved
		20	TEREX INDIA PVT. LTD., PUNE	Not Approved
		21	TUOBRO FURGUSON (INDIA) PVT LTD., KOLKATA	Not Approved
		22	TECHNO INDUSTRIES, AHMEDABAD	Not Approved
		23	UNIQUE INDUSTRIAL HANDLERS PVT LTD., MUMBAI	Not Approved
		24	UNICON TECHNOLOGY INTERNATIONAL PVT. LTD, UP	Not Approved
9	**SINGLE GIRDER EOT/HOT MISC. CRANES**	1	ALE MACHINARIES, USA	Approved
		2	ARMSEL MHE PVT. LTD, KARNATAKA	Approved
		3	BRADY & MORRIS ENGG CO LTD, GUJARAT	Approved

PV 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		4	CONSOLIDATED HOISTS PVT LTD, PUNE	Approved
		5	CENTURY CRANE ENGINEERS PVT. LTD., HARYANA	Approved
		6	HERCULES HOISTS LTD., MAHARASTRA	Approved
		7	INTRICATE ENGG PVT LTD, KOLKATA	Approved
		8	PIONEER CRANES & ELEVATORS, PUNJAB	Approved
		9	REVA INDUSTRIES LTD., HARYANA	Approved
		10	SHIVA FERROUS PVT LTD, WEST BENGAL	Approved
		11	TRANSPADE ENGG PVT LTD, KARNATAKA	Approved
		12	TRACTEL TIRFOR INDIA PVT. LTD., HARYANA	Approved
		13	TUOBRO FURGUSON (INDIA) PVT LTD., KOLKATA	Approved
		14	UNITTEK ENGINEERS PVT LTD, KARNATAKA	Approved
		15	ALPHA SERVICES, RAJASTHAN	Not Approved
		16	MANGLA HOISTS PVT LTD, NEW DELHI	Not Approved
		17	UNIVERSAL HOIST-O-FABRIK, MAHARASHTRA	Not Approved
10	**ELECTRIC HOIST**	1	ALPHA SERVICES, RAJASTHAN	Approved
		2	BRADY & MORRIS ENGG CO LTD, GUJARAT	Approved
		3	CONSOLIDATED HOISTS PVT LTD, PUNE	Approved
		4	CENTURY CRANE ENGINEERS PVT. LTD., HARYANA	Approved
		5	EDDY CRANES PVT. LTD., MUMBAI	Approved
		6	GRIP ENGINEERS PVT. LTD., HARYANA	Approved
		7	HERCULES HOISTS LTD,MAHARASTRA	Approved
		8	LIFTING EQUIPMENTS AND ACCESSORIES, NEW DELHI	Approved
		9	MELTECH CRANES, THANE	Approved

PV Seenaiah 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		10	ROCKWELL HOIST CRANES PVT LTD, NEW DELHI	Approved
		11	REVA INDUSTRIES LTD., HARYANA	Approved
		12	TRANSPADE ENGG PVT LTD, KARNATAKA	Approved
		13	TRACTEL TIRFOR INDIA PVT. LTD., HARYANA	Approved
		14	UNIVERSAL HOIST-O-FABRIK, MAHARASHTRA	Approved
		15	MANGLA HOISTS PVT LTD, NEW DELHI	Not Approved
		16	TECHNO INDUSTRIES, AHMEDABAD	Not Approved
11	**CHAIN PULLEY BLOCK**	1	ARMSEL MHE PVT. LTD, KARNATAKA	Approved
		2	BRADY & MORRIS ENGG CO LTD, GUJARAT	Approved
		3	CENTURY CRANE ENGINEERS PVT LTD, HARYANA	Approved
		4	CONSOLIDATED HOISTS PVT LTD, PUNE	Approved
		5	HERCULES HOISTS LTD., MAHARASTRA	Approved
		6	LIFTING EQUIPMENTS AND ACCESSORIES, NEW DELHI	Approved
		7	SOUTHERN PLANTAID, TELANGANA	Approved
		8	TRACTEL TIRFOR INDIA PVT. LTD., HARYANA	Approved
		9	TRANSPADE ENGG PVT LTD,KARNATAKA	Approved
		10	TUOBRO FURGUSON (INDIA) PVT LTD., KOLKATA	Approved
		11	UNIVERSAL HOIST-O-FABRIK, MAHARASHTRA	Approved
		12	BAKELITE ELECTRICAL MFG. CO. PVT. LTD., MUMBAI	Not Approved
		13	TECHNO INDUSTRIES, AHMEDABAD	Not Approved
12	**MISC. TANKS (SITE FABRICATED)**	1	SAKTHI HI-TECH CONSTRUCTIONS PVT. LTD., CHENNAI	Approved
		2	TECHNO ELECTRIC AND ENGG. CO. LTD., KOLKATA	Approved

P V Seeiy 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		3	THERMOSYSTEMS PVT. LTD., HYDERABAD	Approved
		4	UNITECH MACHINES LTD., GURGAON (UP)	Approved
		5	GMW PRIVATE LIMITED, GUJARAT	Approved
		6	UNITED SYSTEMS & PROJECTS (INDIA) PVT. LTD., TELANGANA	Approved
		7	MAHATHI INFRA SERVICES PVT. LTD., HYDERABAD	Not Approved
		8	SAMAY PROJECT SERVICES PVT. LTD., CHENNAI	Not Approved
		9	SHALKOOT MECHANIQUE PVT. LTD., NOIDA (UP)	Not Approved
		10	XICON INTERNATIONAL LIMITED, MUMBAI	Not Approved
13	**ELEVATORS**	1	JOHNSON & JOHNSON, NEW DELHI	Approved
		2	KONE ELEVATOR INDIA LTD., CHENNAI	Approved
		3	MITSUBUSHI, NEW DELHI	Approved
		4	SCHINDLER INDIA PVT LTD, NEW DELHI	Approved
		5	TECHNO INDUSTRIES, AHMEDABAD	Approved
		6	THYSSENKRUP ELEVATORS, NEW DELHI	Approved
		7	COOPER ELEVATORS INDIA PVT. LTD. CHENNAI	Not Approved
14	**MILL REJECTS SYSTEM (PNEUMATIC TYPE)**	1	H. V. EQUIPMENTS PVT. LTD., NOIDA (UP)	Approved
		2	MELCO INDIA FARIDABAD	Approved
		3	MECAWBER BEEKAY PVT LTD., NEW DELHI	Not Approved
		4	XIAMEN LONGKING BULK MATERIALS SCIENCE & ENGINEERING CO LTD., CHINA	Not Approved
15	**LUBE OIL TRANSFER PUMPS**	1	MATZ PUMPS PVT. LTD., GUJARAT	Approved
		2	TUSHACO PUMPS PVT.LTD. NEW DELHI	Approved
		3	UT PUMPS & SYSTEMS LTD,HARYANA	Approved
		4	ALLWEILER INDIA PRIVATE LIMITED, DAMAN &	Approved

PV 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
			DIU	
		5	DELTA PD PUMPS PVT. LTD., MUMBAI	Approved
		6	DEL PD PUMPS & GEARS PVT LTD, GUJARAT	Not Approved
16	**WEIGH BRIDGE**	1	ACME AUTOMATION, CHATTISHARGH	Approved
		2	AVERY LTD, BALLABGARH, HARYANA	Approved
		3	ABB LTD,HARYANA	Approved
		4	ESSAE DIGITRONICS PVT LTD, HARYANA	Approved
		5	IPA PRIVATE LTD., KARNATAKA	Approved
		6	MET WEIGH INDIA HYDERABAD	Approved
		7	SCHENCK & JENSON & NICOLSON	Approved
		8	SCHENCEK PROCESS INDIA LTD,HARYANA	Approved
		9	STATWEIGH INDIA (P) LTD., KARNATAKA	Approved
		10	TECHNO SCALE INDUSTRIES, GUJARAT	Approved
17	**H2 GEN. PLANT**	1	TELEDYNE ENERGY SYSTEMS INC,USA	Approved
		2	TIANJIN MAINLAND HYDROGEN EQUIPMENT CO. LTD., CHINA	Not Approved
		3	EASTERN ELECTROLYSER LIMITED, NEW DELHI	Approved
		4	HYDROGENICS EUROPE N.V., BELGIUM	Approved
		5	NUBERG ENGINEERING LTD., NOIDA (UP)	Not Approved
		6	SUKAN ENGINEERING PVT. LTD., MUMBAI	Not Approved
		7	SPIRARE ENERGY PVT. LTD., NOIDA (UP)	Not Approved
18	**CONDENSATE POLISHING UNIT**	1	BGR ENERGY SYSTEMS LIMITED., ANDHRA PRADESH	Approved
		2	DRIPLEX WATER ENGINEERING INTERNATIONAL PRIVALTE LIMITED, NEW DELHI	Approved

PV Ramesh 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		3	ION EXCHANGE (INDIA) LTD,HARYANA	Approved
		4	SIEMENS LIMITED,HARYANA	Approved
		5	THERMAX LTD., PUNE	Approved
		6	VA TECH WABAG LTD, NEW DELHI	Approved
19	**OXYGEN DOSING SYSTEM**	1	ENPRO INDUSTRIES PVT.LTD., PUNE	Approved
		2	MR SYSTEMS, KOLKATA	Approved
		3	MPT GMBH, GERMANY	Approved
		4	POWER PIPING COMPANY, TAMIL NADU	Approved
		5	PSI ENGINEERING SYSTEMS (P) LTD., CHENNAI	Approved
		6	ROCKWIN FLOWMETER INDIA PVT. LTD.UP	Approved
		7	TECHNO CONSULTANTS, MUMBAI	Approved
		8	V.K PUMP INDUSTRIES PVT LTD., PUNE	Approved
		9	POSITIVE METERING PUMPS (I) PVT. LTD., MAHARASHTRA	Not Approved
20	**WORKSHOP EQUIPMENT**	1	AVERY WEIGHTRINOX, HARYANA	Approved
		2	BATLIBOI LTD., NEW DELHI	Approved
		3	HMT MACHINE TOOLS LTD (100% SUBSIDAIRY OF M/S HMT LTD.), NEW DELHI	Approved
		4	HYDERABAD TULAMAN LTD., HYDERABAD	Approved
		5	ABRO TECHNOLOGIES PVT. LTD, NEW DELHI	Not Approved
		6	JAGDEEP FOUNDRY (REGD.), PUNJAB	Not Approved
		7	KHALSA ENGINEERING WORKS, NEW DELHI	Not Approved
		8	SAGAR HEAVY ENGINEERINGS PVT. LTD., PUNJAB	Not Approved
IV	**PACKAGE CATEGORY = ELECTRICAL**			
1	**NEUTRAL GROUNDING**	1	BHARTIA CULTER HAMMER FARIDABAD	Approved

PV Seeniy 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
	RESISTOR	2	RSI SWITCHGEAR PVT. LTD., RAJASTHAN	Approved
		3	S.R.NARKHEDE ENGG.PVT.LTD., PUNE	Approved
		4	LACHHMAN ELECTRONICS, NEW DELHI	Approved
		5	AMPCONTROL EQUIPMENTS PVT. LTD., MAHARASHTRA	Approved
		6	RESITECH ELECTRICALS PVT. LTD., KOLKATA	Approved
		7	NATIONAL RESISTORS, MAHARASHTRA	Not Approved
2	**DC LEAD ACID BATTERIES**	1	EXIDE INDUSTRIES LTD, NEW DELHI	Approved
		2	HOPPECKE BATTERIEN GMBH & CO.KG, GERMANY	Approved
3	**DC BATTERY CHARGER**	1	AMARA RAJA POWER SYSTEMS LIMITED,	Approved
		2	CHHABI ELECTRICALS PVT.LTD., MAHARASHTRA	Not Approved
		3	EMERSON NETWORK POWER PVT LTD PUNE	Approved
		4	HBL POWER SYSTEMS LTD., TELANGANA	Approved
		5	STATCON POWER CONTROLS LTD.	Approved
		6	CHLORIDE POWER SYSTEMS & SOLUTIONS LIMITED, KOLKATA	Approved
		7	DUBAS ENGG PVT LTD., KARNATAKA	Not Approved
		8	MASS-TECH CONTROLS PVT.LTD., MUMBAI	Not Approved
		9	STATCON ENERGIAA PRIVATE LIMITED, NOIDA (UP)	Not Approved
		10	VERTIV ENERGY PRIVATE LIMITED, MAHARASHTRA	Not Approved
4	**HT XLPE CABLES**	1	APAR INDUSTRIES LIMITED, GUJARAT	Approved
		2	CABLE CORPORATION OF INDIA LTD., MUMBAI	Approved
		3	GEMSCAB INDUSTRIES LTD., NEW DELHI	Approved
		4	HAVELLS INDIA LIMITED, NOIDA (UP)	Approved

P V Seenu 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		5	KEI INDUSTRIES LTD., NEW DELHI	Approved
		6	KEC INTERNATIONAL LIMITED, MUMBAI	Approved
		7	PARAMOUNT COMMUNICATIONS LTD., NEW DELHI	Approved
		8	POLYCAB WIRES PVT. LTD., MUMBAI	Approved
		9	TORRENT CABLES LTD.GUJARAT	Approved
		10	TIRUPATI PLASTOMATICS PVT LTD., RAJASTHAN	Approved
		11	UNIVERSAL CABLES LTD., MADHYA PRADESH	Approved
		12	TORRENT POWER LTD., GUJARAT	Approved
		13	CMI LTD., NEW DELHI	Not Approved
		14	CRYSTAL CABLE INDUSTRIES LTD., KOLKATA	Not Approved
		15	DYNAMIC CABLES LIMITED, RAJASTHAN	Not Approved
		16	FINOLEX CABLES LIMITED, PUNE	Not Approved
		17	GUPTA POWER INFRASTRUCTURE LIMITED, GHAZIABAD (UP)	Not Approved
		18	RAVIN CABLES LIMITED, MUMBAI	Not Approved
		19	SRIRAM CABLES PVT. LTD., NEW DELHI	Not Approved
		20	STERLITE POWER TRANSMISSION LTD., NEW DELHI	Not Approved
5	**LT XLPE POWER CABLES**	1	CORDS CABLE INDUSTRIES LTD., NEW DELHI	Approved
		2	DIAMOND POWER INFRASTRUCTURE LTD. NEW DELHI	Approved
		3	DELTON CABLES LTD. HARYANA	Approved
		4	GEMSCAB INDUSTRIES LTD., NEW DELHI	Approved
		5	HAVELLS INDIA LTD., NOIDA (UP)	Approved
		6	KEI INDUSTRIES LTD., NEW DELHI	Approved

P V Sooraj 25/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		7	PARAMOUNT COMMUNICATIONS LTD., NEW DELHI	Approved
		8	POLYCAB WIRES PVT. LTD., MUMBAI	Approved
		9	TORRENT CABLES LTD., GUJARAT	Approved
		10	THERMO CABLES LTD., HYDERABAD	Approved
		11	CRYSTAL CABLE INDUSTRIES LTD., KOLKATA	Approved
		12	SUYOG ELECTRICALS LTD., GUJARAT	Approved
		13	CMI LTD., NEW DELHI	Not Approved
		14	APAR INDUSTRIES LTD., MUMBAI	Not Approved
		15	KEC INTERNATIONAL LIMITED, MUMBAI	Not Approved
		16	TIRUPATI PLASTOMATICS PVT. LTD., RAJASTHAN	Not Approved
		17	DYNAMIC CABLES LIMITED, RAJASTHAN	Not Approved
		18	GUPTA POWER INFRASTRUCTURE LIMITED, GHAZIABAD (UP)	Not Approved
		19	GOVIND CABLE INDUSTRIES, GHAZIABAD (UP)	Not Approved
		20	RAVIN CABLES LIMITED, MUMBAI	Not Approved
		21	SRIRAM CABLES PVT. LTD., NEW DELHI	Not Approved
		22	SPECIAL CABLES PVT. LTD., NEW DELHI	Not Approved
6	**CABLE TRAYS & ACC.**	1	INDIANA GRATINGS PVT. LTD., MUMBAI	Approved
		2	INDUSTRIAL PERFORATION (I) PVT.LTD., KOLKATA	Approved
		3	PREMIER POWER PRODUCTS (CAL) PVT. LTD., KOLKATA	Approved
		4	RUKMANI ELECTRICAL & COMPONENTS PVT LTD., KOLKATA	Approved
		5	RABI ENGINEERING WORKS PVT. LTD., KOLKATA	Approved
		6	UNITECH FABRICATORS AND ENGINEERS PVT	Approved

P V Sanjeev 25/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
			LTD., KOLKATA	
		7	INDIA ELECTRICALS SYNDICATE, KOLKATA	Approved
		8	PATNY SYSTEMS PVT. LTD., TELANGANA	Approved
		9	RATAN PROJECTS & ENGINEERING CO. PVT. LTD., KOLKATA	Approved
		10	VINFAB ENGINEERS INDIA PVT. LTD., MUMBAI	Approved
		11	ADVANCE POWER PRODUCTS, KOLKATA	Not Approved
		12	EROS METAL WORKS (P) LTD., MAHARASHTRA	Not Approved
		13	INDMARK FORMTECH PVT. LTD., MAHARASHTRA	Not Approved
		14	MAHESHWARI ELECTRICAL MFRS. PVT. LTD., UP	Not Approved
		15	NAMDHARI INDUSTRIAL TRADERS PVT. LTD, PUNJAB	Not Approved
		16	PARMAR METALS PVT.LTD., RAJKOT	Not Approved
		17	PENTAX FERRO INCORPORATE, MUMBAI	Not Approved
		18	SARAL INDUSTRIES, UP	Not Approved
		19	VATCO ELEC-POWER PVT. LTD., MUMBAI	Not Approved
7	**CABLE TRAY SUPPORT SYSTEM (WELDED TYPE)**	1	ASSOCIATED POWER STRUCTURES PVT. LTD.,	Approved
		2	PATNY SYSTEMS (P) LTD., TELANGANA	Approved
		3	INDUSTRIAL PERFORATION (I) PVT.LTD., KOLKATA	Approved
		4	RATAN PROJECTS & ENGINEERING CO. PVT.LTD., KOLKATA	Approved
		5	TJSV STEEL FABRICATION & GALVANIZING (INDIA) LIMITED, TAMIL NADU	Approved
		6	VINFAB ENGINEERS INDIA PVT. LTD., MUMBAI	Approved
		7	EROS INFRASTRUCTURES PVT. LTD., MAHARASHTRA	Not Approved

23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		8	INDMARK FORMTECH PVT. LTD., MAHARASHTRA	Not Approved
		9	JAGANNATHAN ENGINEERING WORKS, TAMIL NADU	Not Approved
		10	NAMDHARI INDUSTRIAL TRADERS PVT. LTD., PUNJAB	Not Approved
		11	PENTAX FERRO INCORPORATE, MUMBAI	Not Approved
		12	PREMIER POWER PRODUCTS (CAL) PVT. LTD., KOLKATA	Not Approved
		13	PARMAR METALS PVT.LTD., RAJKOT	Not Approved
		14	RABI ENGINEERING WORKS PVT. LTD., KOLKATA	Not Approved
		15	RUKMANI ELECTRICAL & COMPONENTS PVT LTD., KOLKATA	Not Approved
		16	SARAL INDUSTRIES, UP	Not Approved
		17	UNITECH FABRICATORS AND ENGINEERS PVT LTD., KOLKATA	Not Approved
8	**ABOVE GROUND EARTHING MATERIAL**	1	ASSOCIATED POWER STRUCTURES PVT. LTD.GUJARAT	Approved
		2	INDUSTRIAL PERFORATION (I) PVT.LTD., KOLKATA	Approved
		3	PREMIER POWER PRODUCTS (CAL) PVT. LTD., KOLKATA	Approved
		4	PATNY SYSTEMS (P) LTD, TELANGANA	Approved
		5	RUKMANI ELECTRICAL & COMPONENTS PVT LTD., KOLKATA	Approved
		6	UNITECH FABRICATORS AND ENGINEERS PVT LTD., KOLKATA	Approved
		7	INDIA ELECTRICALS SYNDICATE, KOLKATA	Approved
		8	RATAN PROJECTS & ENGINEERING CO. PVT.LTD., KOLKATA	Approved
		9	INDMARK FORMTECH PVT. LTD., MAHARASHTRA	Not Approved
		10	JAGANNATHAN ENGINEERING WORKS, TAMIL NADU	Not Approved
		11	PASSIVE INFRA PROJECTS PVT. LTD., NEW DELHI	Not Approved
		12	EROS INFRASTRUCTURES PVT. LTD., MAHARASHTRA	Not Approved

PV Sastry 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		13	RAJASTHAN METAL SMELTING CO. RAJASTHAN	Not Approved
		14	RABI ENGINEERING WORKS PVT. LTD., KOLKATA	Not Approved
		15	SARAL INDUSTRIES, UP	Not Approved
9	**TREFOIL CLAMPS**	1	AJMERA INDUSTRIAL & ENGINEERING WORKS, MUMBAI	Approved
		2	ELECTROMAC INDUSTRIES, MUMBAI	Approved
		3	MOULDED FIBREGLASS PRODUCTS, KOLKATA	Approved
		4	SUMIP COMPOSITES PVT.LTD., GUJARAT	Approved
		5	AERON COMPOSITE PVT. LTD., GUJARAT	Not Approved
10	**CABLE TERMINATION & JOINTING KITS**	1	ABB LIMITED FARIDABAD	Approved
		2	3M ELECTRO AND COMMUNICATION INDIA P.LTD., NEW DELHI	Approved
		3	RAYCHEM RPG PRIVATE LIMITED, NEW DELHI	Approved
		4	YAMUNA CABLE ACCESSORIES PVT. LTD., HARYANA	Approved
		5	HARI CONSOLIDATED PVT. LTD., NEW DELHI	Approved
		6	CLASSIC ENTERPRISES, MUMBAI	Not Approved
11	**LIGHTING FIXTURES,LAMPS & MISC. ITEMS**	1	AVAIDS TECHNOVATORS PVT. LTD., NEW DELHI	Approved
		2	BAJAJ ELECTRICALS LTD., MUMBAI	Approved
		3	CGL, NEW DELHI	Approved
		4	HAVELLS, NEW DELHI	Approved
		5	MIKA ENGINEERS THANE, MAHARASHTRA	Approved
		6	PHILIPS ELECTRONICS INDIA LTD	Approved
		7	HPL ELECTRIC & POWER LTD, NEW DELHI	Not Approved
		8	HALONIX TECHNOLOGIES (P) LTD., NOIDA (UP)	Not Approved
12	**RIGID STEEL CONDUITS**	REPUTED BIS MAKES SHALL BE ENSURED		

23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
13	**PVC WIRES**	REPUTED BIS MAKES SHALL BE ENSURED		
14	**DISTRIBUTION BOARDS**	1	AMARA RAJA POWER SYSTEMS LIMITED, NEW DELHI	Approved
		2	CHHABI ELECTRICALS PVT.LTD., MAHARASHTRA	Approved
		3	C&S ELECTRIC LIMITED, NEW DELHI	Approved
		4	EMERSON NETWORK POWER, THANE	Approved
		5	HITACHI-HIREL POWER ELECTRONICS, GANDHINAGAR	Approved
		6	HBL POWER SYSTEMS LTD., TELANGANA	Approved
		7	JASPER ENGINEERS PVT. LTD., NOIDA, UP	Approved
		8	JACKSON ENGINEERS LIMITED, NOIDA, UP	Approved
		9	LARSON & TOUBRO LTD., MUMBAI	Approved
		10	NITYA ELECTROCONTROLS PVT. LTD., UP	Approved
		11	RSI SWITCHGEAR PVT. LTD.,RAJASTHAN	Approved
		12	SIEMENS LIMITED,HARYANA	Approved
		13	AVAIDS TECHNOVATORS PVT. LTD., NEW DELHI	Not Approved
		14	BCH ELECTRIC LTD., FARIDABAD	Not Approved
		15	RYB SWITCHGEARS PVT. LTD., NEW DELHI	Not Approved
15	**OIL FILLED SERVICE TRANSFORMERS**	1	ABB,HARYANA	Approved
		2	CGL, NEW DELHI	Approved
		3	DANISH PRIVATE LIMITED, RAJASTHAN	Approved
		4	EMCO LIMITED, NEW DELHI	Approved
		5	ESENNAR TRANSFORMERS (P) LTD., TELANGANA	Approved
		6	KECL,HARYANA	Approved
		7	KRYFS POWER COMPONENTS LTD. , MUMBAI	Not Approved

PV Seenu 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		8	SOUTHERN POWER EQUIPMENT COMPANY PVT. LTD.	Approved
		9	TOSHIBA, NEW DELHI	Approved
		10	VOLTAMP TRANSFORMERS LTD., GUJARAT	Approved
		11	KANOHAR ELECTRICALS LTD., UP	Not Approved
		12	TESLA TRANSFORMERS LTD., MADHYA PRADESH	Not Approved
16	**FIRE SEALING SYSTEM**	1	HILTI INDIA PRIVATE LIMITED, NEW DELHI	Approved
		2	LLOYD INSULATIONS (INDIA) LIMITED, NEW DELHI	Approved
		3	VIJAY SYSTEMS ENGINEERS PVT LTD., GUJARAT	Approved
		4	ASHARAM ENGINEERING AND FIRESTOP SYSTEM PRIVATE LIMITED, CHHATTISGARH	Not Approved
		5	MULTI KILFIRE PVT LTD., GUJARAT	Not Approved
		6	MURUGAPPA MORGAN THERMAL CERAMICS LTD., TAMIL NADU	Not Approved
		7	SIGNUM FIRE PROTECTION (INDIA) PVT LTD., MAHARASHTRA	Not Approved
		8	UNIFRAX INDIA PRIVATE LIMITED, GUJARAT	Not Approved
17	**GCB**	1	ABB SWITZERLAND LTD.,	Approved
		2	GRID SOLUTIONS SAS, FRANCE (Old Name:ALSTOM GRID SAS)	Approved
18	**LT HR PVC CONTROL CABLE**	1	CORDS CABLE INDUSTRIES LTD., NEW DELHI	Approved
		2	DELTON CABLES LTD., HARYANA	Approved
		3	DIAMOND POWER INFRASTRUCTURE LTD.	Approved
		4	GEMSCAB INDUSTRIES LTD., NEW DELHI	Approved
		5	HAVELLS INDIA LIMITED, NOIDA (UP)	Approved
		6	KEI INDUSTRIES LTD., NEW DELHI	Approved
		7	POLYCAB WIRES PVT. LTD., MUMBAI	Approved
		8	TORRENT CABLES LTD., GUJARAT	Approved

PV Seenaiah 23/10/18

Chief Engineer/TPC

Annexure

YADADRI TPS(5X800MW) Approved Vendors List-M/s BHEL/PS-PEM

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. PEM Vendors Approval/D.No.51/18,Dt:23.10.2018

Sl. No	Package Name	Sl. No	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
		9	THERMO CABLES LTD., HYDERABAD	Approved
		10	UNIVERSAL CABLES LTD., MADHYA PRADESH	Approved
		11	SUYOG ELECTRICALS LTD., GUJARAT	Approved
		12	TORRENT POWER LTD., GUJARAT	Approved
		13	KEC INTERNATIONAL LIMITED, MUMBAI	Approved
		14	PARAMOUNT COMMUNICATIONS LTD., NEW DELHI	Approved
		15	ADVANCE CABLE TECHNOLOGIES (P) LTD., KARNATAKA	Approved
		16	CMI LTD., NEW DELHI	Not Approved
		17	ELKAY TELELINKS, NEW DELHI	Not Approved
		18	TEMPSENS INSTRUMENT (I) PVT LTD., RAJASTHAN	Not Approved
		19	TIRUPATI PLASTOMATICS PVT. LTD., RAJASTHAN	Not Approved
		20	SPECIAL CABLES PVT. LTD., NEW DELHI	Not Approved
		21	APAR INDUSTRIES LTD., MUMBAI	Approved
		22	CABLE CORPORATION OF INDIA LTD., MUMBAI	Approved
		23	GOYOLENE FIBRES (INDIA) PVT.LTD., MUMBAI	Not Approved
		24	RAVIN CABLES LIMITED, MUMBAI	Not Approved
		25	RADIANT CORPORATION PRIVATE LIMITED, TELANGANA	Not Approved
		26	SRIRAM CABLES PVT. LTD., NEW DELHI	Not Approved
		27	SERVEL INDIA PVT. LTD., NEW DELHI	Not Approved
19	**EPR INSULATED FIRE SURVIVAL CABLE**	1	APAR INDUSTRIES LIMITED, GUJARAT	Approved
		2	KEI INDUSTRIES, NEW DELHI	Approved
		3	SUYOG ELECTRICALS LTD., GUJARAT	Approved
		4	CMI LTD., NEW DELHI	Not Approved

P V Seshagiri 23/10/18

Chief Engineer/TPC

TELANGANA POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263.

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s BHEL, Industrial Systems Group, P.B.No. 1249, Prof. C N R Rao Circle, IISc Post, Malleswaram, Bengaluru-560012 (P): 080-22184294 Email: amit_kumar@bhel.in

Kind Attention:Sri Amit Kumar, Sr. Manager (PMC)

Lr.No.ED/TPC/SE-3/EME-11/YTPS(5X800MW)/F.AHPVENDORS/D.No.53/18,Dt:24.10.18

Sir,

Sub: TSGENCO –YTPS (5X800MW) – AHP Sub-Vendor Approval-Reg.

Ref: 1) BHEL Letter Ref No: IS-1-15-2001/AHP Sub-Vendor Approval/08, Dt: 24.10.2018.
2) Lr.No.CE/TPC/SE-3/EME-11/YTPS(5X800MW)/F.VENDORS/D.No.49/18,Dt:11.09.18.

******

This is with reference to the letter (1) cited, wherein M/s BHEL requested to approve additional vendors for Ash Slurry Disposal Pipes package.

In this regard, it is to inform that Seven (7) Nos. of Vendors were already approved vide letter (2) cited for MSERW Pipes. Hence, approval of additional vendors cannot be considered now and M/s BHEL/ISG is requested to proceed with ordering of the Ash Slurry Disposal Pipes with the already approved Vendors.

Yours faithfully

P V Seshu 24/10/18

CHIEF ENGINEER/TPC

Copy communicated to:

1. DE/T to the Director(Projects)/TSGENCO, Vidyut Soudha, Hyderabad
2. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.
3. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad

	TELANGANA POWER GENERATION CORPORATION LIMITED (A Govt. Of Telangana Undertaking) Vidyut Soudha, Hyderabad - 500082. Phone: 040 – 23499261 Fax: 040 – 23499263.

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082.	M/s Bharat Heavy Electricals Limited, Industrial Systems Group, P.B.No.1249, Prof.C N R Rao Circle, IISc Post, Malleswaram, Bangalore-560012

Attention:Sri Amit Kumar, Sr.Manager/Project Management & Commercial

Lr.No.CE/TPC/SE-3/EME-11/YTPS(5X800MW)/F.Vendors/D.No.54/18,Dt:29.10.2018

Sir,

Sub: TSGENCO –YTPS (5X800MW)– Additional Vendor for Ash Handling Package being supplied M/s BHEL/ISG, Bangalore – Approval - Reg.

Ref: 1. Lr.No.CE/TPC/SE-3/EME-11/YTPS(5X800MW)/F.Vendors/D.No.49/18,Dt:11.09.2018
2. M/s BHEL letter ref: IS-1-15-2001/AHP Sub-Vendor Approval/06, Dt.23.10.2018.

******

Please refer to the letter cited (2) above, wherein M/s BHEL/ISG, Bangalore has requested for approval of M/s Macawber Beekay Pvt. Ltd, Noida as additional vendor for Ash Handling Package for Yadadri Thermal Power Station (5X800MW). The same was reviewed and TSGENCO hereby accords approval for M/s Macawber Beekay Pvt. Ltd, Noida as additional vendor for Ash Handling Package for Yadadri Thermal Power Station (5X800MW).

Sl.No.	Item Description	Vendor proposed for approval	TSGENCO Remarks for YTPS (5x800MW)
1	**ASH HANDLING PACKAGE**	MACAWBER BEEKAY PVT.LTD, NOIDA	Approved

Please note that this approval of vendors for Supply of items for Ash Handling Package does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Yours faithfully

29/10/18

CHIEF ENGINEER/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay&Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

O/C

भारत हेवी इलेक्ट्रिकल्स लिमिटेड
(भारत सरकार का उपक्रम)
Bharat Heavy Electricals Limited
(A Government of India Undertaking)
इण्डस्ट्रियल सिस्टम्स ग्रुप
INDUSTRIAL SYSTEMS GROUP

फोन/Phone : +91 80 2218 4072
फैक्स/Fax : +91 80 22184074
ई-मेल/E-mail : rtr@bhel.in
पी. बी. नं 1249, प्रो सी एन आर राव सर्कल
आईआईएससी पोस्ट मल्लेश्वरम
बेंगलूरु - 560 012
P.B. No.1249, Prof. C N R Rao Circle
IISc Post Malleswaram
Bengaluru-560 012

BHEL Ref No: IS-1-15-2001/Additional Vendors-machines_01 Date: 31.10.2018

To,
The Chief Engineer,
Thermal Projects Construction,
TSGENCO, 3rd Floor, A-Block,
Vidyut Soudha, Khairatabad, Hyderabad-500082.

Dear Sir,

Sub: 5x800MW Yadadri, Approval of Additional Vendor for machines-reg
Ref: BHEL Letter No: IS-1-15-2001/Additional Vendors-machines dtd: 25.10.2018

In continuation to the BHEL letter Dtd: 25.10.2018 for vendor approval for YADADRI 5X800MW machines supply, we have received credentials of an additional vendor as below.

The following additional vendor given their offer for supplying machines for the said package. We were waiting for the attested credential documents from embassy of India in Russia which we have received on 29.10.2018. We have evaluated the credentials and sending these documents for your kind review and approval as per Annexure-A01 with this letter.

- M/s. Furnace Fabrica India Ltd, Kolkota (in collaboration with M/s JSC Heavy Engineering Ormeto-Yumz , Russia for Wagon Tippler/ Side arm charger & Stacker reclaimer Machines)

M/s. Furnace Fabrica India Ltd, Kolkota:
M/s. Furnace Fabrica India Ltd, Kolkota is a new vendor submitted offer for all the equipment of Machine package as listed in Annexure-A01, in collaboration with M/s JSC Heavy Engineering Ormeto-Yumz , Russia for Wagon Tippler/ Side arm charger & Stacker reclaimer Machines. Respective credentials are attached for your kind reference. The other machines like crusher, screens and paddle feeder, the proposed vendor M/s. Furnace Fabrica India Ltd, Kolkota will procure from TSGENCO approved sources.

Based on the above, kindly accord your approval for the above vendor, to enable us to finalize the offers at the earliest and proceed with ordering.

Thanking you and assuring our best services all the time.

Yours faithfully,
For BHARAT HEAVY ELECTRICALS LTD.

R. Tirupati Rao

(R Tirupati Rao)
Addl. General Manager /Head Engg (Mech.)

Telangana State Power Generation Ltd

ANNEXURE-A01

List of Proposed Vendors for approval of TSGENCO for 5X800MW YADADRI TPS				
Coal Handling Plant (CHP) MACHINES- PROPOSED VENDOR LIST -002				
BHEL Unit: BHEL-ISG				Date: 31.10.18
Sl.No.	Item Description	Proposed Vendors for Yadadri 5X800MW	The following Approved vendors status as per TSGENCO letter for KTPS (1X800MW) Ref: 1) Lr. No.CEE/111/KTPS-VII(1X800MW)/Vendors/D.No.86/15, Dt. 25.05.2015 2) Lr. No.CEE/111/KTPS-VII(1X800MW)/Vendors/D.No.15/15, Dt. 09.04.2015	Remarks
1	STACKER & RECLAIMER	Larsen & Toubro, CHENNAI	Approved	All details given with the Letter Ref. IS-1-15-2001/Additional Vendors-machines Dtd. 25.10.2018
		ELECON EPC PROJECTS LIMITED (Formerly Elecon Engineering Co., Ltd), VALLABH VIDYANAGAR-		
		ThyssenKrupp Limited, PIMPRI PUNE		
		Mcnally Bharat Engineering Ltd, KOLKATA		
		Tenova India Pvt. Ltd. Chennai	Additional Vendor	
		Hunan Changzhong Machinery Co. Ltd., China	Additional Vendor	
		M/s JSC Heavy Engineering Ormeto-Yumz , Russia	**Additional Vendor**	**Seeking for approval.** Credentials given in Annexure
2	WAGON TIPPLER & SIDE ARM CHARGER	Larsen & Toubro, CHENNAI	Approved	All details given with the Letter Ref. IS-1-15-2001/Additional Vendors-machines Dtd. 25.10.2018
		ELECON EPC PROJECTS LIMITED (Formerly Elecon Engineering Co., Ltd), VALLABH VIDYANAGAR-		
		ThyssenKrupp Limited, PIMPRI PUNE		
		Mcnally Bharat Engineering Ltd, KOLKATA		
		Tennova India Pvt. Ltd. Chennai	Additional Vendor	
		Wuhan Power Equipment factory, China (Collaborator of M/s. Hunan Changzhong Machinery Co. ltd, China)	Additional Vendor	
		M/s JSC Heavy Engineering Ormeto-Yumz , Russia	**Additional Vendor**	**Seeking for approval.** Credentials given in Annexure
3	SCREEN	Larsen & Toubro, CHENNAI	Approved	All details given with the Letter Ref. IS-1-15-2001/Additional Vendors-machines Dtd. 25.10.2018
		ELECON EPC PROJECTS LIMITED (Formerly Elecon Engineering Co., Ltd), VALLABH VIDYANAGAR-		
		Mcnally Bharat Engineering Ltd, KOLKATA		
		ThyssenKrupp Limited, PIMPRI PUNE	Additional Vendor	
		M/s Shandong Shankung Machinery Co. Ltd. China (Collaborator of M/s. Hunan Changzhong Machinery Col ltd, China)	Additional Vendor	
4	CRUSHERS	Larsen & Toubro, CHENNAI	Approved	All details given with the Letter Ref. IS 1-15-2001/Additional Vendors-machines Dtd. 25.10.2018
		ELECON EPC PROJECTS LIMITED (Formerly Elecon Engineering Co., Ltd), VALLABH VIDYANAGAR-		
		ThyssenKrupp Limited, PIMPRI PUNE		
		Mcnally Bharat Engineering Ltd, KOLKATA		
		M/s Shandong Shankung Machinery Co. Ltd. China (Collaborator of M/s. Hunan Changzhong Machinery Co. ltd, China)	Additional Vendor	
5	PADDLE FEEDER	Larsen & Toubro, CHENNAI	Approved	All details given with the Letter Ref. IS-1-15-2001/Additional Vendors-machines Dtd. 25.10.2018
		ELECON EPC PROJECTS LIMITED (Formerly Elecon Engineering Co., Ltd), VALLABH VIDYANAGAR-		
		ThyssenKrupp Limited, PIMPRI PUNE		
		Mcnally Bharat Engineering Ltd, KOLKATA	Additional Vendor	
		M/s Shandong Shankung Machinery Co. Ltd. China (Collaborator of M/s. Hunan Changzhong Machinery Co. ltd, China)	Additional Vendor	

O/C

भारत हेवी इलेक्ट्रिकल्स लिमिटेड
(भारत सरकार का उपक्रम)
Bharat Heavy Electricals Limited
(A Government of India Undertaking)
इण्डस्ट्रियल सिस्टम्स ग्रुप
INDUSTRIAL SYSTEMS GROUP

फोन/Phone : +91 80 2218 4072
फैक्स/Fax : +91 80 22184074
ई-मेल/E-mail : rtr@bhel.in
पी.बी.नं 1249, प्रो सी एन आर राव सर्कल
आईआईएससी पोस्ट मल्लेश्वरम
बेंगलूरू - 560 012
P.B. No.1249, Prof. C N R Rao Circle
IISc Post Malleswaram
Bengaluru-560 012

BHEL Ref No: IS-1-15-2001/Additional Vendors-machines Date: 25.10.2018

To,
The Chief Engineer,
Thermal Projects Construction,
TSGENCO, 3rd Floor, A-Block,
Vidyut Soudha, Khairatabad, Hyderabad-500082.

30/10/2018

Dear Sir,

Sub: 5x800MW Yadadri, Approval of Additional Vendors for machines-reg.

We have floated enquiry on open tender basis for Machines package (i.e Wagon Tippler, Side Arm Charger, Apron feeder, Stacker/ Reclaimer, Paddle feeder, Crusher & Screen) for Yadadri 5X800MW TPS project. Offers of following vendors have been technically reviewed by us and found in order and these vendors are meeting the BHEL's technical PQ criteria stipulated for this package.

1. M/s L&T, Kolkata
2. M/s Elecon, Anand
3. M/s McNally Bharat Engineering Ltd, Kolkata
4. M/s Thyssen Krup Limited, Pimpri Pune
5. M/s Tenova India Pvt. Ltd., Chennai
6. M/s Hunan Changzhong Machinery Co. Ltd., China (in collaboration with M/s Wuhan Power Equipment factory, China & M/s Shandong Shankung Machinery Co. Ltd., China)

Vendors under Sl. 1 & 2, i.e, M/s L&T and M/s Elecon have been approved for all the machines of this package for KTPS project as per attached list (Annexure-A).

Vendors under Sl no 3 to 6, approval is required as mentioned below. (Details enclosed in attached Annexure-A)

3) M/s Mc Nally Bharat Engineering Ltd, Kolkata:
As per the KTPS approved vendor list this vendor is approved for the above machines except Paddle Feeder. Credentials of Paddle Feeder are attached for your review and approval.
4) M/s Thyssen Krup Limited, Pimpri Pune:
As per the KTPS approved vendor list, this vendor is approved for the above machines except Screen. Credentials of Screen are attached for your review and approval.
5) M/s Tenova India Pvt. Ltd. Chennai:
M/s Tenova India Pvt Ltd is a new vendor proposed for approval of Wagon Tippler, Stacker Reclaimer. Credentials of the same are attached for your review and approval. Other machines like Crusher, Screen and Paddle feeders will be sourced by them from approved vendors of TSGENCO. Currently M/s Tenova is executing and supplying Portal Reclaimer for Maitree Bangladesh Project (2X660MW) for BHEL-ISG.

6) M/s Hunan Changzhong Machinery Co. Ltd., China:
M/s Hunan Changzhong Machinery Co. Ltd., China is a new vendor submitted offer for all the equipments of Machine package as listed in Annexure-A, in collaboration with M/s Wuhan Power Equipment factory, China for supplying Wagon Tippler, Side arm charger and M/s Shandong Shankung Machinery Co. Ltd. China for supplying Crushers, Screens & Paddle Feeders. Respective credentials are attached for your kind review and approval. Currently M/s
Hunan is executing Stacker reclaimer package for NTPC, North Karanpura ((3X660MW) and BIFPCL Maitree, Bangladesh (2x660MW) projects for BHEL ISG.

Based on the above, kindly accord your approval for the above vendors, to enable us to finalize the offers at the earliest and proceed with ordering.

Thanking you and assuring our best services all the time.

Yours faithfully,
For BHARAT HEAVY ELECTRICALS LTD.

R. Tirupati Rao

(R Tirupati Rao)
Addl. General Manager /Head Engg (Mech.)

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263.

From:	To:
Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082.	M/s Bharat Heavy Electricals Limited, Industrial Systems Group, P.B.No.1249, Prof.C N R Rao Circle, IISc Post, Malleswaram, Bangalore-560090

Attention:Sri Amit Kumar, Sr.Manager/Project Management & Commercial

Lr.No.CE/TPC/SE-3/EME-11/YTPS(5X800MW)/F.AHP Vendors/D.No.63/18,Dt:14.11.2018

Sir,

Sub: TSGENCO –YTPS (5X800MW) – AHP Sub-vendor Approval -Reg

Ref:1. Lr.No.CE/TPC/ SE-3/EME-11/YTPS (5x800MW)/F.AHP Vendors/D.No.49/18, Dt:11-09-2018
2. M/s BHEL letter ref: IS-1-15-2001/AHP Sub-Vendor Approval/08, Dt.24-10-2018
3. Lr.No.CE/TPC/ SE-3/EME-11/YTPS (5x800MW)/F.AHP Vendors/D.No.53/18, Dt:24-10-2018
4. M/s BHEL letter ref: IS-1-15-2001/AHP Sub-Vendor Approval/09, Dt.25-10-2018

******

This has the reference to the letter (4) cited, wherein M/s BHEL/ISG, Bangalore requested for approval of additional sub-vendors for Ash Slurry Disposal MSERW Pipes.

In this connection it is to inform that the letters issued from this office vide ref (1) and (3) holds good and M/s BHEL/ISG is requested to proceed with ordering of the Ash Slurry Disposal MSERW Pipes with the already approved vendors.

Yours faithfully

14/11/18

CHIEF ENGINEER/TPC

Copy communicated to:

1. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
2. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
3. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.

TELANGANA STATE POWER GENERATION CORPORATION LIMITED
(A Govt. Of Telangana Undertaking)
Vidyut Soudha, Hyderabad - 500082.
Phone: 040 – 23499261 Fax: 040 – 23499263

From:	To:
The Chief Engineer, Thermal Projects Construction, TSGENCO, 3rd Floor, A-Block, Vidyut Soudha, Khiarathabad Hyderabad-500 082. cetpctgenco@gmail.com	M/s Bharat Heavy Electricals Limited, Component Fabrication Plant, Rudrapur (U S Nagar)-263153, Uttarakhand. T : 05944 - 257250 Email: rupesh@bhel.in

Kind Attention:Sri Rupesh Kumar, Dy Mgr.

Lr.No.CE/TPC/SE-3/EME-11/YTPS/F. Rud Vendors Approval/D.No. 70 /18,Dt:18.12.2018

Sir,

Sub: TSGENCO – Yadadri TPS (5X800MW) – Approval of Vendors furnished by M/s BHEL/ Rudrapur unit - Reg.

Ref: BHEL/RUD/ENGG./YADADRI/16-095-A-2/903/005,Dt:13/07/2018.

******

Please refer to the letter cited above, wherein M/s BHEL/ Rudrapur has requested for approval of vendors for Yadadri TPS (5X800MW). The same was reviewed and TSGENCO hereby accords approval for the vendors. The list of approved vendors is enclosed as Annexure.

Please note that this approval of vendors for Supply of following list of items does not absolve M/s BHEL of its responsibility of supplying and conforming to the relevant specifications and standards as per the terms and conditions of the contract.

Encl: List of TSGENCO Approved Vendors of M/s BHEL/Rudrapur Unit.

Yours faithfully,

Chief Engineer/TPC

Copy communicated to:

1. The Chief Engineer/Construction/YTPS Site/Dameracherla/Nalgonda.
2. FA&CCA (Res.)&CFO/TSGENCO/Vidyut Soudha/Hyderabad.
3. SE/Tech to The Chairman & Managing Director/TSGENCO/Vidyut Soudha/Hyderabad.
4. Superintending Engineer/Civil/YTPS Site/Dameracherla/Nalgonda(Dist.).
5. Dy CCA, YTPS-II/Co-ordination/Dameracherla/Nalgonda(Dist.).
6. DE/Tech to Director (Projects)/TSGENCO/Vidyut Soudha/Hyderabad.
7. SAO/Pay & Accounts/TSGENCO/Vidyut Soudha/Hyderabad.
8. M/s Tata Consulting Engineers Limited,73/1,Sheriff Centre, St. Marks road, Bangalore-560 001.
9. TCE, Site office, Room No.323, Vidyut Soudha, Hyderabad
10. Sri Y.A.Srinivas Rao, BHEL/PMG Camp Office, Vidyut Soudha, Hyderabad.