

BILL OF QUANTITY

Name of Project : 220/33kV SUBSTATION AT MASJID MOTH.
Name of Work : YARD TREATMENT AND FENCING.

S.No.	Item Description	Quantity	Unit	Unit Rate (Rs)	Amount (Rs)
1	Providing treatment for prevention of growth of weeds/grass in switchyard areas as per Customer's specification vide clause No. 7.02.02 of General technical requirements complete in all respect including supply of labour and materials. The scope of work also includes levelling ,dressing ,loading ,unloading , etc required for completing the works as per above specification but excluding the laying of earthing network.	11700	SQM		
2	Providing and fixing 3.0 meter high chainlink fencing including all allied works as per approved drawing No. TB-3-222-607-626.The work shall include all civil works ,materials ,angles ,barbed wire and fence etc as per above drawing.	150	RM		
Total amount (Rs.)					