



SCHEDULE OF WINDOWS, VENTS, DOORS

TYPE	SIZE OF WALL OPENING	DESCRIPTION	REQ. NOS.	REMARKS
W1	3000 X 1800	ALUMINIUM GLAZED WINDOW SLIDING	21	
W2	1800 X 1800	ALUMINIUM GLAZED WINDOW SLIDING / FIXED	7	
W3	750 X 750	ALUMINIUM GLAZED VENT TOP HUNG	9	
D1	1800 X 2400	T.W. PANDOOOR DOUB. SH.T.	2	
D2	2000 X 2800	T.W. PANDOOOR DOUB. SH.T.	1	
D3	2000 X 2800	STEEL DOOR DOUB. SH.T.	1	
D4	1800 X 2400	ALUMINIUM GLAZED DOOR DOUB. SH.T.	1	
D5	900 X 2400	ALUMINIUM GLAZED DOOR	11	
D6	750 X 2100	F.R.P. DOOR	9	

SCHEDULE OF FLOORING

AREA	DESCRIPTION	SKIRTING /DADO
CONTROL ROOM	POLISHED KOTA	150 HT POLISHED KOTA
BATTERY ROOM	ACID RESISTANT TILES (CERAMIC TILES)	2750 HT ACID RESISTANT TILES
AG /DC ROOM	MARBLE MOSAIC TILES (MANDANA STONE)	150 HT. M.M. TILES
TOILET	POLISHED KOTA	1500 HT CERAMIC TILES
WC.	CERAMIC TILES	1500 HT CERAMIC TILES
SHEFT INCHARGE ROOM	CERAMIC ANTISKID TILES WITH SCOURING OF SAME TILES	
CONFERENCE HALL	CERAMIC ANTISKID TILES WITH SCOURING OF SAME TILES	
LOUNGE	MARBLE WITH GRANITE SCOURING 6"	
REST ROOM	WHITE POLISH KOTA	
OFFICE	WHITE POLISH KOTA	
STAIRCASE	MARBLE WITH GRANITE SCOURING 6"	
PASSAGE	MARBLE WITH GRANITE SCOURING 6"	

NOTES/REFERENCES

REVISION

TYPE	DATE	DESCRIPTION	DRN.	CHGRD.	SUBMTD.	APPD.

MAHARASHTRA STATE ELECTRICITY TRANS CO. LTD

PROPOSED CONTROL ROOM FOR 400KV SUB-STN

DRWN: SASHAD	TRANS. PROJECTS	DRG.No.
CHECKED:	DEPARTMENT	TRP-400KV CROOM/016.1048
SUBMITTED:	DATE	15-10-2007
APPROVED:	SCALE: 1:100	REV.