

Summary of Un-Price Bid Format

Project Name: IOCL Paradip-Standby SRU (525TPD) Train project, Odisha

Works & Services Name: “MECHANICAL TIE-IN AND CONTRO TRACE” WORKS for IOCL Paradip-Standby SRU (525TPD) Train project, Odisha.

Enquiry no.T0AUX00047, dated:16.07.2021

abstract of sheet							
Sl No	Description	UOM	Qty	Unit Rate	Amount	Weightage %	Remark
A	B	C	D	E	F	G	H
1	Mechanical Tie-In Works	Set	1	no need to quote here	no need to quote here	83.4061358%	Refer Section-1
2	Contro Trace Works	Set	1			16.5938642%	Refer Section-2
	Grand Total (Excluding Taxes)					100.00%	
Note.1	Bidders should quote only the Total Amount in the specified place. They should not fill/quote/write anything in col. (E) & (F) of Abstract sheet as well as section - 1 to 2 . These rates & amount will be derived from the Total amount quoted and weightage factor assigned against respective items indicated in col. G. (Bidder to quote the total price in BHEL NIC portal https://eprocurebhel.co.in)						
2	Evaluation Shall be based on total amount quoted by bidder.						

Section 1: Mechanical Tie-In Works, enquiry no.T0AUX00047						
SI No	Description	UOM	Qty	Unit Rate	Amount	Weightage %
1	Receipt from BHEL store, transportation to site, Fabrication, erection, welding, radiography, painting of the following piping including pipe fittings and structures as per BHEL site engineer's instructions and technical specifications:					
1.1	CS Non IBR	MT	16.00			9.0215566%
1.2	CS IBR	MT	12.00			8.5223678%
1.3	CS- NACE	MT	23.00			13.7359907%
1.4	CS-NACE+HIC	MT	4.00			2.5308867%
1.5	SS	MT	1.50			2.0331811%
1.6	Valves	MT	40.00			22.5538914%
1.7	Structures	MT	6.00			1.7612713%

SI No	Description	UOM	Qty	Unit Rate	Amount	Weightage %
2	Installation, testing and commissioning of Insulation and dismantling of existing insulation, steam tracing pipelines.					
2.1	Removal, disposal of existing piping insulation as per BHEL/ IOCL instructions (This is inclusive of the existing mineral wool , Cladding ,insulation auxiliaries)	MT	40			14.7639280%
2.2	Removal, disposal of existing steam tracing piping as per BHEL/ IOCL instructions	MT	25			7.0480911%
2.3	Installation of insulation (This is inclusive of the mineral wool, , insulation auxiliaries and consumables)	MT	15			4.5124628%
2.4	Installation of Aluminium cladding including all hardware	MT	25			10.9341387%
3	Supply, erection, testing and commissioning of the following gate valves:					
3.1	Size: 2" , VMS : 513 FE	Nos	2			0.4792719%
3.2	Size: 3" , VMS : 513 FE	Nos	3			1.3787385%
3.3	Size: 4" , VMS : 513 FE	Nos	1			0.7242233%
	Total weightage % (Excl. taxes)					100.00%

Section 2-Contro Trace Works, enquiry no.T0AUX00047						
SI No	Description	UOM	Qty	Unit Rate	Amount	Weightage%
1	Installation, testing, and commissioning of contro trace bolt on heating system as per BHEL approved drawings, instructions of BHEL site engineer and under supervision of contro trace material supplier	Inch Meter	35000			100%
	Total weightage (Excl. taxes)					100%