

TENDER SPECIFICATION

Sl No	Tender Specification Number	Unit Number & Project
1	BHE/PW/PUR/ DHJOI-BLR (BLOCK-I)/966	UTILITY BOILER 1, HRSG 2 AND 4 (Block I)
2	BHE/PW/PUR/ DHJOI-BLR (BLOCK-II)/967	UTILITY BOILER 2, HRSG 1 AND 3 (Block II)

RECEIPT/COLLECTION/LOADING/UNLOADING/TRANSPORTATION OF MATERIALS FROM BHEL/CLIENT'S STORES/STORAGE YARD TO SITE OF WORK, ERECTION, TESTING, COMMISSIONING, SUPPLY OF PAINTS/PRIMER AND APPLICATION OF PAINTS FOR FINAL PAINTING AND HANDING OVER OF 220 TPH UTILITY BOILER (UB) + 110 TPH HEAT RECOVERY STEAM GENERATORS (HRSG) ALONG WITH ITS AUXILIARIES, STEEL STACK WITH COMPLETE PLATFORMS ETC INCLUDING ELECTRICAL WORK OF STACK, PIPING (POWER CYCLE PIPING, INTEGRAL PIPING, CONDENSATE & FEED WATER PIPING, DM WATER, HSD & NAPHTHA PIPING, NATURAL GAS, COOLING WATER, REGENERATIVE CYCLE PIPING, INCLUDING PLANT AIR, INSTRUMENT AIR & SERVICE AIR PIPING ETC.) WITH ASSOCIATED FITTINGS, VALVES, HANGERS & SUPPORTS, APPLICATION OF THERMAL INSULATION OF UB AND HRSG WITH AUXILIARIES, STEEL STACK, PIPING WITH VALVES & FITTINGS INCLUDING GAS TURBINE AND STEAM TURBINE SET EQUIPMENTS – HEATERS, DE-AERATOR, TANKS, VESSELS & PIPING ETC FOR OPAL (ONGC PETRO ADDITIONS LIMITED) STEAM AND POWER GENERATION SYSTEM PACKAGE FOR DAHEJ PETROCHEMICAL COMPLEX, SPLIT AS (Block I) UTILITY BOILER 1, HRSG 2 AND 4, (Block II) UTILITY BOILER 2, HRSG 1 AND 3.

AT

2X30MW STG + 2X220 TPH UB + 4XFr6 B GT + 4X110 TPH HRSG AT
OPaL, DAHEJ- BHARUCH, GUJARAT

TECHNICAL BID - VOLUME- I

TENDER SPECIFICATIONS CONSISTS OF:

- Notice Inviting Tender
- Volume 1 A - Technical Conditions of Contract,
- Volume 1 B - Special conditions of Contract,
- Volume 1 C - General conditions of Contract
- Volume 1 D - Forms & Procedures



Bharat Heavy Electricals Limited
(A Government of India Undertaking)
Power Sector - Western Region

345-Kingsway, Nagpur-440001

CONTENTS			
Volume No	Description	Hosted in website bhel.com as files titled	No. of pages
NIL	Tender Specification Issue Details	(Part of <u>Vol-IA-966,967</u>)	1
NIL	Notice Inviting Tender	(Part of <u>Vol-IA-966,967</u>)	20
I-A	Technical Conditions of Contract	Vol-IA-966,967	113
I-B	Special Conditions of Contract	Vol-IBCD-966,967	47
I-C	General Conditions of Contract	(Part of <u>Vol-IBCD-966,967</u>)	29
I-D	Forms & Procedures	(Part of <u>Vol-IBCD-966,967</u>)	54
II	Price Bid Specification	Vol-II-966,967	5

TENDER SPECIFICATION

SI No	Tender Specification Number	Unit Number & Project
1	BHE/PW/PUR/ DHJOI-BLR (BLOCK-I)/966	UTILITY BOILER 1, HRSG 2 AND 4 (Block I)
2	BHE/PW/PUR/ DHJOI-BLR (BLOCK-II)/967	UTILITY BOILER 2, HRSG 1 AND 3 (Block II)

RECEIPT/COLLECTION/LOADING/UNLOADING/TRANSPORTATION OF MATERIALS FROM BHEL/CLIENT'S STORES/STORAGE YARD TO SITE OF WORK, ERECTION, TESTING, COMMISSIONING, SUPPLY OF PAINTS/PRIMER AND APPLICATION OF PAINTS FOR FINAL PAINTING AND HANDING OVER OF 220 TPH UTILITY BOILER (UB) + 110 TPH HEAT RECOVERY STEAM GENERATORS (HRSG) ALONG WITH ITS AUXILIARIES, STEEL STACK WITH COMPLETE PLATFORMS ETC INCLUDING ELECTRICAL WORK OF STACK, PIPING (POWER CYCLE PIPING, INTEGRAL PIPING, CONDENSATE & FEED WATER PIPING, DM WATER, HSD & NAPHTHA PIPING, NATURAL GAS, COOLING WATER, REGENERATIVE CYCLE PIPING, INCLUDING PLANT AIR, INSTRUMENT AIR & SERVICE AIR PIPING ETC.) WITH ASSOCIATED FITTINGS, VALVES, HANGERS & SUPPORTS, APPLICATION OF THERMAL INSULATION OF UB AND HRSG WITH AUXILIARIES, STEEL STACK, PIPING WITH VALVES & FITTINGS INCLUDING GAS TURBINE AND STEAM TURBINE SET EQUIPMENTS – HEATERS, DE-AERATOR, TANKS, VESSELS & PIPING ETC FOR OPAL (ONGC PETRO ADDITIONS LIMITED) STEAM AND POWER GENERATION SYSTEM PACKAGE FOR DAHEJ PETROCHEMICAL COMPLEX, SPLIT AS (Block I) UTILITY BOILER 1, HRSG 2 AND 4, (Block II) UTILITY BOILER 2, HRSG 1 AND 3.

AT

**2X30MW STG + 2X220 TPH UB + 4XFr6 B GT + 4X110 TPH HRSG AT OPAL,
DAHEJ- BHARUCH, GUJARAT**

EARNEST MONEY DEPOSIT: Refer Notice Inviting Tender
LAST DATE FOR Refer Notice Inviting Tender
TENDER SUBMISSION .

THESE TENDER SPECIFICATION DOCUMENTS CONTAINING VOLUME-I AND VOLUME- II ARE ISSUED TO:

M/s.
.....

PLEASE NOTE:
THESE TENDER SPECS DOCUMENTS ARE NOT TRANSFERABLE.

For Bharat Heavy Electricals Limited


ADDITIONAL GENERAL MANAGER (Purchase)
Place: Nagpur

Date :

966
&
967

NOTICE INVITING TENDER

Bharat Heavy Electricals Limited



Ref: NO: BHE/PW/PUR/DHJOI-Block I & II /966,967
Dt: 09/02/2011

NOTICE INVITING TENDER (NIT)
**NOTE: BIDDER MAY DOWNLOAD FROM WEB
SITES
OR
PURCHASE TENDERS FROM THIS OFFICE ALSO**

=====

To

Dear Sir/Madam

Sub : NOTICE INVITING TENDER

Sealed offers in two part bid system are invited from reputed & experienced bidders (meeting [PRE QUALIFICATION CRITERIA](#) as mentioned in Annexure-I) for the subject job by the undersigned on the behalf of BHARAT HEAVY ELECTRICALS LIMITED as per the tender document. Following points relevant to the tender may please be noted and complied with.

1.0 Salient Features of NIT

SL NO	ISSUE	DESCRIPTION
i	TENDER NUMBER	BHE/PW/PUR/ DHJOI-BLR (BLOCK I)/966 BHE/PW/PUR/ DHJOI-BLR (BLOCK II)/967
ii	Broad Scope of job	RECEIPT/COLLECTION/LOADING/UNLOADING/TRANSPORTATION OF MATERIALS FROM BHEL/CLIENT'S STORES/STORAGE YARD TO SITE OF WORK, ERECTION, TESTING, COMMISSIONING, SUPPLY OF PAINTS/PRIMER AND APPLICATION OF PAINTS FOR FINAL PAINTING AND HANDING OVER OF 220 TPH UTILITY BOILER (UB) + 110 TPH HEAT RECOVERY STEAM GENERATORS (HRSG) ALONG WITH ITS AUXILIARIES, STEEL STACK WITH COMPLETE PLATFORMS ETC INCLUDING ELECTRICAL WORK OF STACK, PIPING (POWER CYCLE PIPING, INTEGRAL PIPING, CONDENSATE & FEED WATER PIPING, DM WATER, HSD & NAPTHA PIPING, NATURAL GAS, COOLING WATER, REGENERATIVE CYCLE PIPING, INCLUDING PLANT AIR, INSTRUMENT AIR & SERVICE AIR PIPING ETC.) WITH ASSOCIATED FITTINGS, VALVES, HANGERS & SUPPORTS, APPLICATION OF THERMAL INSULATION OF UB AND HRSG WITH AUXILIARIES, STEEL STACK, PIPING WITH VALVES & FITTINGS INCLUDING GAS TURBINE AND STEAM TURBINE SET EQUIPMENTS – HEATERS, DE-AERATOR, TANKS, VESSELS & PIPING ETC FOR OPAL

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 8 of 146

		(ONGC PETRO ADDITIONS LIMITED) STEAM AND POWER GENERATION SYSTEM PACKAGE FOR DAHEJ PETROCHEMICAL COMPLEX, SPLIT AS (Block I) UTILITY BOILER 1, HRSG 2 AND 4, (Block II) UTILITY BOILER 2, HRSG 1 AND 3. BLOCK I AND BLOCK II SHALL BE AWARDED TO SEPARATE AGENCIES	
iii	DETAILS OF TENDER DOCUMENT		
a	Volume-IA	Technical Conditions of Contract (TCC) consisting of Scope of work, Technical Specification, Drawings, Procedures, Bill of Quantities, Terms of payment, etc	Applicable
b	Volume-IB	Special Conditions of Contract (SCC)	Applicable
c	Volume-IC	General Conditions of Contract (GCC)	Applicable
d	Volume-ID	Forms and Procedures	Applicable
e	Volume- I E	Technical Specifications	Applicable
e	Volume-II	Price Schedule (Absolute value).	Applicable
iv	Issue of Tender Documents	1. <u>Sale from BHEL PS Regional office at : Start : 09/02 / 2012 Closes: 03/03/2012 , Time :16.00 Hrs</u> 2. From BHEL website (www.bhel.com) Tender documents can however be downloaded from website till due date of submission	Applicable
v	DUE DATE & TIME OF OFFER SUBMISSION	Date :05/03 / 2012 , Time :15.00Hrs Place : BHEL OFFICE AT NAGPUR Tenders being submitted through representative shall be handed over to any of the following BHEL officials after making entry/registration at the reception: RK Ranade/ Sr Manager (Purchase) Pratish Gee Varghese/Engineer(Purchase)	Applicable
vi	OPENING OF TENDER	1 hours after the latest due date and time of Offer submission Notes: (1) In case the due date of opening of tender becomes a non-working day, tenders shall be opened on next working day at the same time. (2) Bidder may depute representative to witness the opening of tender	Applicable
vii	EMD AMOUNT	Rs 2,00,000/- (Rupees Two Lakhs Only)	Applicable
viii	COST OF TENDER	Rs 2000/-.	Applicable
ix	LAST DATE FOR SEEKING CLARIFICATION	Date: (Atleast 5 days before the due date of offer submission) Along with soft version also, addressing to undersigned & to others as per contact address given below	Applicable
x	SCHEDULE OF Pre Bid Discussion (PBD)	Date : Not applicable.	Not applicable.
xi	INTEGRITY PACT	Applicable.	Applicable

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 9 of 146

	& DETAILS OF INDEPENDENT EXTERNAL MONITOR (IEM)	NAME OF IEM – Shri Kanwarjit Singh , IRS (Retd.) D-6/12, Ground Floor, Vasant Vihar, New Delhi - 110 057 kanwarfeb@gmail.com	
xii	Latest updates	Latest updates on the important dates, Amendments, Correspondences, Corrigenda, Clarifications, Changes, Errata, Modifications, Revisions, etc to Tender Specifications will be hosted in BHEL webpage (www.bhel.com -->Tender Notifications →View Corrigendums) <u>and not in the newspapers</u> . Bidders to keep themselves updated with all such information	

- 2.0 The offer shall be submitted as per the instructions of tender document and as detailed in this NIT. Bidders to note specifically that all pages of tender document, including these NIT pages of this particular tender together with subsequent correspondences shall be submitted by them, duly signed & stamped on each page, as part of offer. **Rates/Price including discounts/rebates, if any, mentioned anywhere/in any form in the techno-commercial offer other than the Price Bid, shall not be entertained.**
- 3.0 Unless specifically stated otherwise, bidder shall remit cost of tender and courier charges if applicable, in the form of Demand Draft drawn in favour of Bharat Heavy Electricals Ltd, payable at Power Sector Regional HQ at Nagpur issuing the Tender, along with techno-commercial offer. Bidder may also choose to deposit the Tender document cost by cash at the Cash Office as stated above against sl no iv of 1, on any working day; and in such case copy of Cash receipt is to be enclosed with the Techno Commercial offer. Sale of tender Documents shall not take place on National Holidays, holidays declared by Central or State Governments and BHEL PS HQ at Nagpur, Sundays and second/ last Saturdays
- 4.0 Unless specifically stated otherwise, bidder shall deposit EMD through Demand Draft/Pay Order in favour of Bharat Heavy Electricals Ltd, payable at Nagpur. For other details and for 'One Time EMD' please refer General Conditions of Contract.
- 5.0 **Procedure for Submission of Tenders:** The Tenderers must submit their Tenders to Officer inviting Tender, as detailed below:
- PART-I consisting of 'PART-I A (Techno Commercial Bid)' & 'PART-I B (EMD/COST of TENDER)' in two separate sealed and superscribed envelopes (ENVELOPE-I & ENVELOPE-II)
 - PART-II (Price Bid) – in sealed and superscribed envelope (ENVELOPE-III)
- 6.0 The contents for ENVELOPES and the superscription for each sealed cover/Envelope are as given below. **(All pages to be signed and stamped)**

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 10 of 146

Sl no	Description	Remarks
	Part-I A	
	<u>ENVELOPE – I superscribed as :</u> PART-I (TECHNO COMMERCIAL BID) TENDER NO : NAME OF WORK : PROJECT: DUE DATE OF SUBMISSION:	
	CONTAINING THE FOLLOWING:-	
i.	Covering letter/Offer forwarding letter of Tenderer.	
ii.	Duly filled-in 'No Deviation Certificate' as per prescribed format to be placed after document under sl no (i) above. <u>Note:</u> a. In case of any deviation, the same should be submitted separately for technical & commercial parts, indicating respective clauses of tender against which deviation is taken by bidder. The list of such deviation shall be placed after document under sl no (i) above. It shall be specifically noted that deviation recorded elsewhere shall not be entertained. b. BHEL reserves the right to accept/reject the deviations without assigning any reasons, and BHEL decision is final and binding. - i). In case of acceptance of the deviations, appropriate loading shall be done by BHEL - ii). In case of unacceptable deviations, BHEL reserves the right to reject the tender	
iii.	Supporting documents/ annexure/ schedules/ drawing etc as required in line with Pre-Qualification criteria. It shall be specifically noted that all documents as per above shall be indexed properly and credential certificates issued by clients shall distinctly bear the name of organization, contact ph no, FAX no, etc.	
iv.	All Amendments/Correspondences/Corrigenda/Clarifications /Changes/ Errata etc pertinent to this NIT.	
v.	Integrity Pact Agreement (Duly signed by the authorized signatory)	If applicable
vi.	Duly filled-in annexures, formats etc as required under this Tender Specification/NIT	
vii.	Notice inviting Tender (NIT)	
viii.	Volume – I A : <u>Technical</u> Conditions of Contract (TCC) consisting of Scope of work, Technical Specification, Drawings, Procedures, Bill of Quantities, Terms of payment,	

**Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967**

	etc	
ix.	Volume – I B : Special Conditions of Contract (SCC)	
x.	Volume – I C : General Conditions of Contract (GCC)	
xi.	Volume – I D : Forms & Procedures	
xii.	Volume- I E : Technical Specifications	
xiii.	Volume – II (UNPRICED – without disclosing rates/price, but mentioning only 'QUOTED' or 'UNQUOTED' against each item	
xiv.	Any other details preferred by bidder with proper indexing.	

	PART-II	
	PRICE BID consisting of the following shall be enclosed	
	<u>ENVELOPE-III</u> superscribed as: PART-II (PRICE BID) TENDER NO : NAME OF WORK : PROJECT: DUE DATE OF SUBMISSION:	
	CONTAINING THE FOLLOWING	
i	Covering letter/Offer forwarding letter of Tenderer enclosed in Part-I	
ii	Volume II – PRICE BID (Duly Filled in Schedule of Rates – rate/price to be entered in words as well as figures)	

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 12 of 146

OUTER COVER		
	ENVELOPE-IV (MAIN ENVELOPE / OUTER ENVELOPE) superscribed as: TECHNO-COMMERCIAL BID, PRICE BID & EMD TENDER NO: NAME OF WORK: PROJECT: DUE DATE OF SUBMISSION:	
	CONTAINING THE FOLLOWING:	
i	- o Envelopes I - o Envelopes II - o Envelopes III	

SPECIAL NOTE : All documents/ annexures submitted with the offer shall be properly annexed and placed in respective places of the offer as per enclosure list mentioned in the covering letter. BHEL shall not be responsible for any missing documents.

- 7.0 No Deviation with respect to tender clauses and no additional clauses/ suggestions/ in Techno-commercial bid/ Price bid shall normally be considered by BHEL. Bidders are requested to positively comply with the same.
- 8.0 BHEL reserves the right to accept or reject any or all Offers without assigning any reasons thereof. BHEL also reserves the right to cancel the Tender wholly or partly without assigning any reason thereof. Also BHEL shall not entertain any correspondence from bidders in this matter (except for the refund of EMD).

9.0 Assessment of Capacity of Bidders:

Bidders capacity for executing the job under tender shall be assessed as per the following:

- i. **Assigning Weightages (A) for Similar Jobs Under-Execution:** Weightages shall be worked out and assigned based on the average number of Similar Works under execution including works yet to be commenced by the agency, in the following manner:
 - i). Number of Similar Jobs
 - a) No. of jobs in BHEL, PSER : Say 'J'
 - b) No. of jobs in BHEL, PSSR : Say 'K'
 - c) No. of jobs in BHEL, PSWR : Say 'L'
 - d) No. of jobs in BHEL, PSNR : Say 'M'
 - e) No. of jobs with other customers* : Say 'N' (*: Other than BHEL PSER, PSSR, PSWR & PSNR)
 - f) Average No. of Jobs is 'P' = (J+K+L+M+N) divided by 5
 - ii) Weightage "A" assigned to bidders based on Average Number of jobs "P":

-
- a) If 'P' = 0-1, "A" will be equal to '3'
 - b) If 'P' = 2-3, "A" will be equal to '2'
 - c) If 'P' = 4-5, "A" will be equal to '1'
 - d) If 'P' is Above 5, "A" will be equal to '0'

- II. **Weightage "B" for Quarterly Performance Reports of Vendors:** This shall be based on the averages of the net weighted score obtained by the bidder for the jobs under execution (excluding works not commenced) for the quarter previous to the last quarter reckoned from the date of latest due date of submission, in all four Regions i.e BHEL PSER, PSSR, PSWR & PSNR, in the following manner.

- i). Ratings by Power Sector Region:

- a) PS ER's Rating '**R_{er}**' = $(X_1 + X_2 + \dots + X_n)$ divided by n
- b) PS WR's Rating '**R_{wr}**' = $(X_1 + X_2 + \dots + X_n)$ divided by n
- c) PS SR's Rating '**R_{sr}**' = $(X_1 + X_2 + \dots + X_n)$ divided by n
- d) PS NR's Rating '**R_{nr}**' = $(X_1 + X_2 + \dots + X_n)$ divided by n
- e) **Over all Power Sector Region Rating '**R_{BHEL}**'** = $(R_{er} + R_{wr} + R_{sr} + R_{nr})$ divided by 4

(where " $X_1, X_2, X_3, \dots, X_n$ " is the net weighted score obtained by the bidder as per the "Evaluation of Contractor Performance (Quarterly)" against the various contracts 'n' under execution in the respective Region).

- ii) Weightage "B" assigned to bidders based on Overall Power Sector Rating (**R_{BHEL}**):

- a) If **R_{BHEL}** is 80% and above, "B" will be equal to '6'
- b) If **R_{BHEL}** is $> 70\% < 80\%$, "B" will be equal to '5'
- c) If **R_{BHEL}** is $> 60\% < 70\%$, "B" will be equal to '4'
- d) If **R_{BHEL}** is $\leq 60\%$, "B" will be equal to '0'

- III. **Evaluation of Bidders capacity to execute the job under tender:** shall be based on the sum of scores obtained in 'A' and 'B', as below:

- a) **6 or above : Considered 'Qualified' for the job under tender**
- b) **Less than 6: Considered 'NOT Qualified' for the job under tender**

- IV. **Explanatory note:**

- a) Similar work means GTG,GTG,BOILER or Turbine or Civil or Electrical or CI, etc irrespective of rating of Plant
- b) Quarter shall be as per the quarter defined in the "Evaluation of Contractor performance (Quarterly)". For contracts where annexed Quarterly Evaluation performance was not part of the contract, 'Quarterly Performance Reports' previous to the last quarter reckoned

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 14 of 146

.....
from the date of latest due date of submission, given by the respective project site against the contract will be the basis for evaluation.

- c) Vendors who are not executing any jobs presently in the Region and first timers to the Region, may be considered subject to satisfying all other tender conditions
 - d) 'Under execution' shall mean works in progress upto GTG,GTG,BOILER Steam Blowing (for GTG,GTG,BOILER and Auxilliaries) or Synchronisation (for all other jobs including Civil) shall be considered.
- 10.0 Since the job shall be executed at site, bidders must visit site/ work area and study the job content, facilities available, availability of materials, prevailing site conditions including law & order situation etc before quoting for this tender. They may also consult this office before submitting their offers, for any clarifications regarding scope of work, facilities available at sites or on terms and conditions. No additional claim shall be entertained by BHEL in future, on account of non-acquaintance of above.
- 11.0 For any clarification on the tender document, the bidder may seek the same in writing or through e-mail, as per specified format, within the scheduled date for seeking clarification, from the office of the undersigned. BHEL shall not be responsible for receipt of queries after due date of seeking clarification due to postal delay or any other delays. Any clarification / query received after last date for seeking clarification may not be normally entertained by BHEL and no time extension will be given.
- 12.0 BHEL may decide holding pre-bid discussion [PBD] with all intending bidders as per date indicated in the NIT. The bidder shall ensure participation for the same at the appointed time, date and place as may be decided by BHEL. Bidders shall plan their visit accordingly. The outcome of pre-bid discussion (PBD) shall also form part of tender.
- 13.0 In the event of any conflict between requirement of any clause of this specification/ documents/drawings/data sheets etc or requirements of different codes/standards specified, the same to be brought to the knowledge of BHEL in writing for clarification before due date of seeking clarification (whichever is applicable), otherwise, interpretation by BHEL shall prevail. Any typing error/missing pages/ other clerical errors in the tender documents, noticed must be pointed out before pre-bid meeting/submission of offer, else BHEL's interpretation shall prevail.
- 14.0 Unless specifically mentioned otherwise, bidder's quoted price shall deemed to be in compliance with tender including PBD.
- 15.0 Bidders shall submit Integrity Pact Agreement (Duly signed by authorized signatory who signs in the offer), **if applicable**, along with techno-commercial bid. This pact shall be considered as a preliminary qualification for further participation. **The names and other details of Independent External Monitor (IEM) for the subject**

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 15 of 146

.....
tender is as given at point (xi) of 1 above.

- 16.0 The Bidder has to satisfy the Pre Qualifying Requirements stipulated for this Tender in order to be qualified. The Price Bids of only those bidders will be opened who will be qualified for the subject job on the basis of pre-qualification evaluation/ techno-commercial bids, approval/ acceptance of customer (as applicable), etc. and date of opening of price bids shall be intimated to only such bidders.
- 17.0 In case BHEL decides on a 'Public Opening', the date & time of opening of the sealed PRICE BID shall be intimated to the qualified bidders and in such a case, bidder may depute one authorised representative to witness the price bid opening. BHEL reserves the right to open 'in-camera' the 'PRICE BID' of any or all Unsuccessful/Disqualified bidders under intimation to the respective bidders.
- 18.0 Validity of the offer shall be for **six months** from the latest due date of offer submission (including extension, if any) or specified otherwise in SCC of tender.
- 19.0 BHEL reserves the right to decide the successful bidder on the basis of Reverse Auction process. In such case all qualified bidders will be intimated regarding procedure/ modality for Reverse Auction process prior to Reverse Auction and price will be decided as per the rules for Reverse Auction. .
- However, if reverse auction process is unsuccessful as defined in the RA rules/procedures, or for whatsoever reason, then the sealed 'PRICE BIDs' will be opened for deciding the successful bidder. BHEL's decision in this regard will be final and binding on bidder.
- 20.0 On submission of offer, further consideration will be subject to compliance to tender & qualifying requirement and customer's acceptance, as applicable.
- 21.0 In case the bidder is an "Indian Agent of Foreign Principals", 'Agency agreement has to be submitted along with Bid, detailing the role of the agent along with the terms of payment for agency commission in INR, along with supporting documents.
- 22.0 The bidders shall not enter into any undisclosed M.O.U. or any understanding amongst themselves with respect to tender.
- 23.0 In case Consortium Bidding is allowed as per Pre Qualifying Requirement, then Prime Bidder and Consortium Partner shall enter into Consortium Agreement. Validity period of Consortium Agreement shall be 6 months after which the same can be re validated.

'Stand alone' bidder cannot become a '**prime bidder' or a 'consortium bidder' in a consortium bidding.** Prime bidder shall neither be a consortium partner to other prime bidder nor take any other consortium partners. However, consortium partner may enter into consortium agreement with other prime bidders. In case of non compliance, consortium bids of such Prime bidders will be rejected. .

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 16 of 146

-
- 24.0 The bidder shall submit documents in support of possession of 'Qualifying Requirements" duly self certified and stamped by the authorized signatory, indexed and properly linked in the format for PQR. In case BHEL requires any other documents/proofs, these shall be submitted immediately.
- 25.0 The bidder may have to produce original document for verification if so decided by BHEL.
- 26.0 Order of Precedence
In the event of any ambiguity or conflict between the Tender Documents, the order of precedence shall be in the order below:
- a. Amendments/Clarifications/Corrigenda/Errata etc issued in respect of the tender documents by BHEL
 - b. Notice Inviting Tender (NIT)
 - c. Price Bid
 - d. Technical Conditions of Contract (TCC)—Volume-1A
 - e. Special Conditions of Contract (SCC) —Volume-1B
 - f. General Conditions of Contract (GCC) —Volume-1C
 - g. Forms and Procedures —Volume-1D

for BHARAT HEAVY ELECTRICALS LTD

AGM

(Purchase)

Enclosure

- 01. Annexure-1: Pre Qualifying criteria.
 - 02. Annexure-2: Check List .
 - 03. Annexure – 3- Integrity Pact
- Other Tender documents as per this NIT.

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 17 of 146

ANNEXURE - 1

PRE QUALIFYING CRITERIA

JOB	RECEIPT/COLLECTION/LOADING/UNLOADING/TRANSPORTATION OF MATERIALS FROM BHEL/CLIENT'S STORES/STORAGE YARD TO SITE OF WORK, ERECTION, TESTING, COMMISSIONING, SUPPLY OF PAINTS/PRIMER AND APPLICATION OF PAINTS FOR FINAL PAINTING AND HANDING OVER OF 220 TPH UTILITY BOILER (UB) + 110 TPH HEAT RECOVERY STEAM GENERATORS (HRSG) ALONG WITH ITS AUXILIARIES, STEEL STACK WITH COMPLETE PLATFORMS ETC INCLUDING ELECTRICAL WORK OF STACK, PIPING (POWER CYCLE PIPING, INTEGRAL PIPING, CONDENSATE & FEED WATER PIPING, DM WATER, HSD & NAPHTHA PIPING, NATURAL GAS, COOLING WATER, REGENERATIVE CYCLE PIPING, INCLUDING PLANT AIR, INSTRUMENT AIR & SERVICE AIR PIPING ETC.) WITH ASSOCIATED FITTINGS, VALVES, HANGERS & SUPPORTS, APPLICATION OF THERMAL INSULATION OF UB AND HRSG WITH AUXILIARIES, STEEL STACK, PIPING WITH VALVES & FITTINGS INCLUDING GAS TURBINE AND STEAM TURBINE SET EQUIPMENTS – HEATERS, DE-AERATOR, TANKS, VESSELS & PIPING ETC FOR OPAL (ONGC PETRO ADDITIONS LIMITED) STEAM AND POWER GENERATION SYSTEM PACKAGE FOR DAHEJ PETROCHEMICAL COMPLEX, SPLIT AS (Block I) UTILITY BOILER 1, HRSG 2 AND 4, (Block II) UTILITY BOILER 2, HRSG 1 AND 3. BLOCK I AND BLOCK II SHALL BE AWARDED TO SEPARATE AGENCIES		
TENDER NO	BHE/PW/PUR/ DHJOI-BLR (BLOCK I)/966 BHE/PW/PUR/ DHJOI-BLR (BLOCK II)/967		
SL NO	PRE QUALIFICATION CRITERIA	Bidders claim in respect of fulfilling the PQR Criteria	
		Name and Description of qualifying criteria	Page no of supporting document
A	Submission of Integrity Pact duly signed (if applicable)	APPLICABLE	
B	Assessment of Capacity of Bidder to execute the work as per sl no 9 of NIT (if applicable)	Applicable	
	C) <u>Bidder must have, achieved any one of the following in last seven years as on the latest date of offer Submission.</u> C.1) Executed One Boiler (Consisting of Pressure Parts, Structures/ESP and IBR/Power Cycle Piping of the same Unit as a stand alone bidder) of a Unit of rating 100 TPH or above OR C.2) Executed One job of Steam Generator of rating 100 TPH or above comprising of Pressure Parts (200 MT)/Power Cycle Piping (IBR) of 200 MT, and Structures of 400 MT with his own T&Ps and consumables. OR C.3) Executed Two jobs of Renovation and modernization or Capital Overhaul of a Boiler of Rating 200 TPH or higher, each of value 150 Lakhs or above under direct order of BHEL		

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 18 of 146

	OR		
	C.4) Executed One STG of 100 MW or higher under direct order of BHEL		
D 1	<u>Financial TURNOVER</u> Bidders must have achieved an average annual financial turnover (Audited) of Rs. 360 Lakhs or more over last three Financial Years (FY) i.e, 2008-2009, 2009-2010, 2010-11.		
2	<u>NETWORTH</u> Net worth of bidder based on latest Audited Accounts as furnished for 'D.1' above should be positive		
3	<u>PROFIT</u> Bidder must have earned cash profit in any one of the three Financial Years as applicable in the last three years defined in 'D1' above based on latest Audited Accounts.		
E	<u>Approval of Customer</u> Note: Names of bidders who stand qualified after compliance of criteria A to D shall be forwarded to customer for their approval. Price bid of only those bidders shall be opened who are approved by customer.	APPLICABLE	
F	<u>Consortium Criteria</u>	NOT APPLICABLE	
<u>Explanatory Notes for 'PQR'</u> <u>A) Explanatory Notes for PQR 'C'- 'Technical'</u> 'Executed' means the vendor should have achieved the criteria specified in the Common QRs even if the Contract has not been completed or closed. - Unless otherwise specified, for the purpose of PQR, the word 'EXECUTED' means: "Boiler light Up" in respect of Boiler & Aux and ESP "Synchronisation" in respect of STG/GTG/HTG "Steam Blowing Completing" in respect of Power Cycle Piping "Hydraulic Test" of the system in respect of Structures, Pressure Parts/IBR Piping - Boiler means HRSG or WHRB or any other types of Steam Generator - Critical/power cycle piping means Main Steam, Hot Reheat, Cold Reheat, HP Bypass, LP Bypass Lines. - For the purpose of PQR, 3.5 TPH shall be considered equivalent to one MW where ever rating of BOILER is mentioned in TPH. ~~Similarly where ever rating of Gas Turbine is mentioned in terms of frame Size, ISO rating of the same in terms of MW shall be considered for evaluation.~~ <u>B) Explanatory Notes for PQR 'D'- 'Financial'</u> - Net Worth = Paid up share capital + Reserves (Share Capital OR Partnership Capital OR Proprietor Capital as the case may be) - Profit shall be NET Profit (PAT + Non Cash Expenditure viz depreciation). - In case audited financial statement have not been submitted for all the three years as indicated in 'D1' above, then applicable audited statement submitted by the bidder against the requisite three year, will be averaged for three years.			

BIDDER SHALL SUBMIT ABOVE PRE-QUALIFICATION CRITERIA FORMAT, DULY FILLED-IN, SPECIFYING RESPECTIVE ANNEXURE NUMBER AGAINST EACH CRITERIA AND FURNISH RELEVANT DOCUMENT IN THE RESPECTIVE ANNEXURES IN THEIR OFFER along with copies of

**BHEL PSWR
Notice Inviting Tender**

**Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967**

Page 19 of 146

.....
Work Orders, Work Completion certificates, Audited profit and Loss Account for the last three years and other related documents as per PQR & tender specification..

ANNEXURE - 2

CHECK LIST

NOTE:- Tenderers are required to fill in the following details and no column should be left blank

1	Name and Address of the Tenderer		
2	Details about type of the Firm/Company		
3	Details of Contact person for this Tender	Name : Mr/Ms Designation: Telephone No: Mobile No: Fax No:	
4	EMD DETAILS	DD No: Date : Bank : Amount: <u>Please tick (√) whichever applicable:-</u> ONE TIME EMD / ONLY FOR THIS TENDER	
		APPLICABILITY	BIDDER REPLY
5	Whether the format for compliance with PRE QUALIFICATION CRITERIA (ANNEXURE-I) is understood and filled with proper supporting documents referenced in the specified format	Applicable	YES / NO
6	Whether Audited profit and Loss Account for the last three years submitted	Applicable	YES/NO
7	Whether Copy of PAN Card submitted	Applicable	YES/NO
8	Whether all pages of the Tender documents including annexures, appendices etc are read understood and signed	Applicable	YES/NO
9	Integrity Pact	Applicable	Applicable
10	Declaration by Authorized Signatory	Applicable	YES/NO
11	Whether No Deviation Certificate submitted	Applicable	YES/NO
12	Whether Declaration confirming knowledge about Site Conditions submitted	Applicable	YES/NO
13	Whether Declaration for relation in BHEL submitted	Applicable	YES/NO
14	Whether Non Disclosure Certificate submitted	Applicable	YES/NO
15	Whether Bank Account Details for E-Payment submitted	Applicable	YES/NO
16	Capacity Evaluation of Bidder for current Tender	Applicable	YES/NO
17	Tie Ups/Consortium Agreement are submitted ~~as per format~~	Not Applicable	YES/NO
18	Whether Power of Attorney for Submission of Tender/Signing Contract Agreement submitted	Applicable	YES/NO
19	Whether Analysis of Unit rates submitted	Applicable	YES/NO

NOTE : STRIKE OFF 'YES' OR 'NO', AS APPLICABLE

DATE :

AUTHORISED SIGNATORY
(With Name, Designation and Company seal)

ANNEXURE - 3

INTEGRITY PACT

Between

Bharat Heavy Electricals Ltd. (BHEL), a company registered under the Companies Act 1956 and having its registered office at “BHEL House” Siri Fort, New Delhi – 110049 (India) hereinafter referred to as “The Principal”, which expression unless repugnant to the context of meaning hereof shall include its successors or assigns of the ONE PART

And

_____, (description of the party along with address), hereinafter referred to as “The Bidder/ Contractor” which expression unless repugnant to the context or meaning hereof shall include its successors or assigns of the OTHER PART

Preamble

The Principal intends to award, under laid-down organizational procedures, contract/s for

_____. The Principal values full compliance with all relevant laws of the land, rules and regulations and the principles of economic use of resources, and of fairness and transparency in its relations with its Bidder(s)/ Contractor(s).

In order to achieve these goals, the Principal will appoint Independent External Monitor(s), who will monitor the tender process and the execution of the contract for compliance with the principles mentioned above.

Section 1 - Commitments of the Principal

1.1 The Principal commits itself to take all measures necessary to prevent corruption and to observe the following principles:-

1.1.1 No employee of the Principal, personally or through family members, will in connection with the tender for, or the execution of a contract, demand, take a promise for or

accept, for itself or third person, any material or immaterial benefit which the person is not legally entitled to.

- 1.1.2 The Principal will, during the tender process treat all Bidder(s) with equity and reason. The Principal will in particular, before and during the tender process, provide to all Bidder(s) the same information and will not provide to any Bidder(s) confidential / additional information through which the Bidder(s) could obtain an advantage in relation to the tender process or the contract execution.
- 1.1.3 The Principal will exclude from the process all known prejudiced persons.
- 1.2 If the Principal obtains information on the conduct of any of its employees which is a penal offence under the Indian Penal Code 1860 and Prevention of Corruption Act 1988 or any other statutory penal enactment, or if there be a substantive suspicion in this regard, the Principal will inform its Vigilance Office and in addition can initiate disciplinary actions.

Section 2 – Commitments of the Bidder(s)/ Contractor(s)

- 2.1 The Bidder(s)/ Contractor(s) commit himself to take all measures necessary to prevent corruption. He commits himself to observe the following principles during his participation in the tender process and during the contract execution.
- 2.1.1 the Bidder(s)/ Contractor(s) will not, directly or through any other person or firm, offer, promise or give to the Principal or to any of the Principal's employees involved in the tender process or the execution of the contract or to any third person any material, immaterial or any other benefit which he / she is not legally entitled to, in order to obtain in exchange any advantage of any kind whatsoever during the tender process or during the execution of the contract.
- 2.1.2 The bidder(s)/ Contractors(s) will not enter with other Bidder(s) into any illegal or undisclosed agreement or understanding, whether formal or informal. This applies in particular to prices, specifications, certifications, subsidiary contracts, submission or non-submission of bids or any other actions to restrict competitiveness or to introduce cartelization in the bidding process.
- 2.1.3 The Bidder(s)/ Contractor(s) will not commit any penal offence under the relevant IPC/PC Act; further the Bidder(s)/ Contractor(s) will not use improperly, for purposes of competition or personal gain, or pass on to others, any information or document provided by the Principal as part of the business relationship, regarding plans, technical proposals and business details, including information contained or transmitted electronically.

-
- 2.1.4 The Bidders (s)/ Contractor(s) will, when presenting his bid, disclose any and all payments he has made, and is committed to or intends to make to agents, brokers or any other intermediaries in connection with the award of the contract.
- 2.2 The Bidder(s)/ Contractor(s) will not instigate third persons to commit offences outlined above or be an accessory to such offences.

Section 3 – Disqualification from tender process and execution from future contracts

If the Bidder(s)/Contractor(s), before award or during execution has committed a transgression through a violation of Section 2 above, or acts in any other manner such as to put his reliability or credibility in question, the Principal is entitled to disqualify the Bidder(s)/ Contractor(s) from the tender process or take action as per separate “Guidelines on for Suspension of Business Dealings with Suppliers/ Contractors” framed by the Principal.

Section 4 – Compensation for Damages

- 4.1 If the Principal has disqualified the Bidder from the tender process prior to the award according to Section 3, the Principal is entitled to demand and recover the damages equivalent to Earnest Money Deposit/ Bid Security.
- 4.2 If the Principal has terminated the contract according to Section 3, or if the Principal is entitled to terminate the contract according to Section 3, the Principal shall be entitled to demand and recover from the Contractor liquidated damages equivalent to 5% of the contract value or the amount equivalent to Security Deposit/ Performance Bank Guarantee, whichever is higher.

Section 5 – Previous Transgression

- 5.1 The Bidder declares that no previous transgressions occurred in the last 3 years with any other company in any country conforming to the anti-corruption approach or with any other Public Sector Enterprise in India that could justify his exclusion from the tender process.
- 5.2 If the Bidder makes incorrect statement on his subject, he can be disqualified from the tender process or the contract, if already awarded, can be terminated for such reason.

Section 6 – Equal treatment of all Bidders/ Contractors/ Sub-Contractors

- 6.1 The Bidder(s)/ Contractor(s) undertake(s) to obtain from his sub-contractors a commitment consistent with this Integrity Pact and report Compliance to the Principal. This commitment shall be taken only from those sub-contractors whose contract value

.....
is more than 20% of Bidder's/ Contractor's contract value with the Principal. The Bidder(s)/Contractor(s) shall continue to remain responsible for any default by his Sub-contractor(s).

- 6.2 The Principal will enter into agreements with identical conditions as this one with all Bidders and Contractors.
- 6.3 The Principal will disqualify from the tender process all bidders who do not sign this pact or violate its provisions.

Section -7 Criminal Charges against violating Bidders/ Contractors/ Sub-contractors

If the Principal obtains knowledge of conduct of a Bidder, Contractor or Sub-contractor, or of an employee or a representative or an associate of a Bidder, Contractor or Subcontractor which constitutes corruption, or if the Principal has substantive suspicion in this regard, the Principal will inform the Vigilance Office.

Section – 8 Independent External Monitor(s)

- 8.1 The Principal appoints competent and credible Independent External Monitor for this Pact. The task of the Monitor is to review independently and objectively, whether and to what extent the parties comply with the obligations under this agreement.
- 8.2 The Monitor is not subject to instructions by the representatives of the parties and performs his functions neutrally and independently. He reports to the CMD, BHEL.
- 8.3 The Bidder(s)/ Contractors(s) accepts that the Monitor has the right to access without restriction to all contract documentation of the Principal including that provided by the Bidder(s)/ Contractor(s). The Bidder(s)/Contractor(s) will grant the monitor, upon his request and demonstration of a valid interest, unrestricted and unconditional access to his contract documentation. The same is applicable to Sub-contractor(s). The Monitor is under contractual obligation to treat the information and documents of the Bidder(s)/ Contractor(s)/ Sib-contractor(s) with confidentiality.
- 8.4 The Principal will provide to the Monitor sufficient information about all meetings among the parties related to the contract provided such meeting could have an impact on the contractual relations between the Principal and the Contractor. The parties offer to the Monitor the option to participate in such meetings.
- 8.5 As soon as the Monitor notices, or believes to notice, a violation of this agreement, he will so inform the Management of the Principal and request the Management to

discontinue or take corrective action, or heal the situation, or to take other relevant action. The Monitor can in this regard submit non-binding recommendations. Beyond this, the Monitor has no right to demand from the parties that they act in a specific manner, refrain from action or tolerate action.

- 8.6 The Monitor will submit a written report to the CMD, BHEL within 8 to 10 weeks from the date of reference or intimation to him by the Principal and, should the occasion arise, submit proposals for correcting problematic situations.
- 8.7 The CMD, BHEL shall decide the compensation to be paid to the Monitor and its terms and conditions.
- 8.8 If the Monitor has reported to the CMD, BHEL, a substantiated suspicion of an offence under relevant IPC/PC Act, and the CMD, BHEL has not, within reasonable time, taken visible action to proceed against such offence or reported it to the Vigilance Office, the Monitor may also transmit this information directly to the Central Vigilance Commissioner, Government of India.
- 8.9 The number of Independent External Monitor(s) shall be decided by the CMD, BHEL
- 8.10 The word 'Monitor' would include both singular and plural.

Section 9 – Pact Duration

- 9.1 This Pact begins and shall be binding on and from the submission of bid(s) by bidder(s). It expires for the Contractor 12 months after the last payment under the respective contract and for all other Bidders 6 months after the contract has been awarded.
- 9.2 If any claim is made/ lodged during this time, the same shall be binding and continue to be valid despite the lapse of this pact as specified as above, unless it is discharged/ determined by the CMD, BHEL.

Section 10 – Other Provisions

- 10.1 This agreement is subject to Indian Laws and jurisdiction shall be registered office of the Principal, i.e. New Delhi.
- 10.2 Changes and supplements as well as termination notices need to be made in writing. Side agreements have not been made.

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 26 of 146

-
- 10.3 If the contractor is a partnership or a consortium, this agreement must be signed by all partners or consortium members.
- 10.4 Should one or several provisions of this agreement turn out to be invalid, the reminder of this agreement remains valid. In this case, the parties will strive to come to an agreement to their original intentions.
- 10.5 Only those Bidders/ Contractors who have entered into this agreement with the Principal would be competent to participate in the bidding. In other words, entering into this agreement would be a preliminary qualification.

For & On Behalf of the Principal
(Office Seal)

For & On Behalf of the Bidder/ Contractor
(Office Seal)

IMPORTANT INFORMATION

1. PRICE VARIATION COMPENSATION

Refer Clause 2.17 of Volume I C 'General Conditions of Contract' (Price Variation Compensation): For the purpose of calculating PVC, following 'Commodities shall be reckoned for the respective categories:

Category	Commodity to be Used for PVC Calculation
Electrode	Welding Rod (Individual Commodity)
High Speed Diesel	High Speed Diesel (Individual Commodity)
Cement	Grey cement (Individual Commodity)
Structural & Reinforcement Steel	a1. Iron & semis (Group Item)
Materials (Other than Cement & Steel)	All Commodities (Group Item)

2. INTEREST BEARING RECOVERABLE ADVANCE

Refer Clause 2.13 of Volume I C 'General Conditions of Contract' (Interest Bearing Recoverable Advance): Following additional points shall be noted:

- Bank Guarantee towards 'Interest Bearing Advance' shall be atleast 110% of the advance so as to enable recovery of not only principle amount but also the interest portion, if so required.
 - 'Interest Bearing Recoverable Advance' shall not be paid in less than two installments. Contractor shall establish the utilization of advance drawn before the release of next installment.
3. The offers of the bidders who are on the banned list as also the offer of the bidders, who engage the services of the banned firms, shall be rejected. The list of banned firms is available on BHEL web site (www.bhel.com ---> Tender Notification -> List of Banned Firms)
4. This tender is for 6 Units of Steam Generators (2 Units of 220 TPH Utility Boiler and 4 Units of 110 TPH HRSG), which is divided into 2 Blocks. Block – I comprises of (UB # 1, HRSG 2 & 4) and Block – II comprises of (UB # 2, HRSG 1 & 3).

1. Tender specification (Volume I) is common for both the Blocks.
2. Both the BLOCKS shall be awarded to separate agencies.
3. Rates for E & C of Steam Generators in ONE BLOCK has been invited in Volume II price bid specification.
4. Bidders are required to submit their rates/price for Steam Generators in ONE BLOCK only in Volume II Price bid
5. L-1 bidder shall be considered for award of BLOCK 1 (**UB # 1, HRSG 2 & 4**).
6. For award of BLOCK 2 (**UB # 2, HRSG 1 & 3**), next bidder in the order of their price competitiveness (i.e L-2, then L-3 and hence forth) shall be given an option to match their Per unit rate/price, with the Awarded per unit rate/price of BLOCK I.

BHEL PSWR
Notice Inviting Tender

Tender Specification No: BHE/PW/PUR/ DHJOI-BLR(BLOCK-I)/966
BHE/PW/PUR/ DHJOI-BLR(BLOCK-II)/967

Page 28 of 146


.....
In case none of the bidders agree to match the Awarded per unit rate of BLOCK I, then BHEL may consider awarding the BLOCK 2 (**UB # 2, HRSG 1 & 3**) to L-1 bidder or opt any other suitable method to finalize BLOCK 2 (**UB # 2, HRSG 1 & 3**).

7. In case after award of job, the agency fails to display satisfactory performance in execution of job and BHEL feels it is necessary to make alternate arrangement to execute balance work or any portion of work on risk purchase basis or otherwise, then BHEL reserves the right to exercise the method mentioned in SI No 6 to finalize another/additional agency.

966
&
967

TECHNICAL CONDITIONS OF CONTRACT (TCC)

BHARAT HEAVY ELECTRICALS
LIMITED



TECHNICAL CONDITIONS OF CONTRACT (TCC)

CONTENTS

SI No	DESCRIPTION	Chapter	No. OF PAGES
Volume-IA	Part-I: Contract specific details		
1	Project Information	Chapter-I	2
2	Scope of Works and Technical Specifications	Chapter-II	10
3	Facilities in the scope of Contractor/BHEL (Scope Matrix)	Chapter-III	8
4	T&Ps and MMEs to be deployed by Contractor	Chapter-IV	3
5	T&Ps and MMEs to be deployed by BHEL on sharing basis	Chapter-V	1
6	Time Schedule	Chapter-VI	1
7	Terms of Payment	Chapter-VII	2
8	Taxes and other Duties	Chapter-VIII	2
9	Tender Drawings	Chapter-IX	2
10	Appendix	Chapter-X	1

TECHNICAL CONDITIONS OF CONTRACT (TCC)

CONTENTS

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter - I : Project Information

1.0	Project Information
1.1	INTROUCTION ONGC Petro Additions Limited (OPaL) is setting up a Petrochemical Complex at Dahej in the state of Gujarat, India. The complex consist of dual feed Ethylene Cracker of 1100 KTPA capacity. The scope of the present project is to set up a steam and power generation system to primarily meet the process steam requirement and incidentally generate power to partly meet the power requirement for the Petrochemical Complex. The project shall consist of 2X220 TPH Utility Boilers, 2X30 MW STG, 4XFr6B GTG and 4X110 TPH HRSG with associated auxiliary systems and accessories. BHEL has been awarded the EPC package comprising of system design, detailed engineering, manufacturing, procurement, civil works, supply, fabrication, inspection, transportation, storage, installation, insurance, testing, mechanical completion, pre-commissioning, commissioning and performance guarantee test runs of the complete system. The project is to be completed within 30 months from zero date i.e. 15/04/2011. Site information a) Location : Dahej SEZ near Village Ambhetha at Dahej, District-Bharuch, Gujarat b) Longitude : 21°40'47"N to 21°41'48"N c) Latitude : 72°35'24"E to 72°36'44"E d) Nearest Railway Station : Bharuch – 45 km e) Nearest Town : Bharuch - 45 Km, Vadodara - 140 Km f) Nearest Port : Dahej - 10 Km g) Nearest Air Port : Vadodara - 140 km h) Access Road : Bharuch-Dahej State Highway - SH6 - 1.2 Km i) Height above mean sea level : Mean Sea Level (MSL) = 5.1M w.r.t. Chart datum Finished Grade Level (FGL)=6.6M/ 7.1M/ 7.6M above MSL
1.2	<u>CLIMATIC CONDITIONS</u> 1. <u>Seismic data</u> a. Zone : III 2. Air Temperature

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter - I : Project Information

	a. Air Temperature Max/Min	: 40° C / 13° C
	b. Design dry bulb Temp Max/Min	: 42° C / 29° C
	3. Relative Humidity	: 90%@ 42 °C
	4. Rainfall	
	Annual Rainfall	: 1000 mm
	5. Wind velocity/ direction	
	a. March- October	: 44 km/h/ South west
	b. November- February	: 15KM/Hr/ North west/North/ North East
	6. Climatic Conditions	: Tropical

The bidder is advised to visit and examine the site of works and its surroundings and obtain for himself on his own responsibility all information that may be necessary for preparing the bid and entering into the contract. All costs for and associated with site visits shall be borne by the bidder.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – II : Scope of Works and technical Specification

2.0 SCOPE OF WORK:

The work to be carried out under the scope of these specifications is broadly as under:

2.1 UTILITY BOILER

The scope of work shall include the receipt / collection / loading of materials from BHEL/client's stores / storage yard / pre-identified location, shifting / transportation/ unloading / dragging of materials to site of work / designated location; pre-erection checks, pre-assembly if necessary, erection, testing, assistances for commissioning & trial operation, handing over, completion of PG test related works and assistance for performance guarantee test of Utility Boiler of 1x220TPH capacity (fired on NAPHTHA, Natural Gas, Complex Gas, & HSD) with all its auxiliaries and accessories, Rotating equipments, support & supporting structures, ducts & dampers, fuel piping, Deaerator with Feed Storage Tanks, Utility Boiler piping including integral piping, Power Cycle Piping, application of thermal insulation and cladding work of equipments / piping / vessels / & tanks etc, surface preparation, supply of Paints/Primer and application of paints for final painting of Block I (UB 1, HRSG 2 & 4) and Block II (UB 2, HRSG 1 & 3) with all its auxiliaries at 2X30 MW STG+2X220 TPH UB + 4XFr6 B GT+4X110 TPH HRSG, OPaL Dahej, Bharuch- Gujarat.

2.1.1

Following named systems are broadly in the scope for Utility Boiler (for each Block) in the present contract:

- Utility Boiler supporting structures.
- Stairs, Platforms, Hand Rails, Toe Guards etc.
- Utility Boiler pressure parts.
- Utility Boiler trim & integral piping and mountings
- Fuel oil Pumps & pipeline
- Feed Water System piping for UB
- Complex Gas system piping for UB
- HSD system piping for UB
- Natural Gas System piping for UB
- Naphtha system piping for UB
- HP steam system piping
- Utility Boiler Non-pressure parts

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – II : Scope of Works and technical Specification

- Rotating machines with their drives (Naphtha pump for UB-1 one pump driven by Steam Turbines and other one pumps is electric motor driven, FD fan & GR fan for UB are dual drive (Motor + Turbine).
- Handling arrangements for rotating machines & other equipment.
- Power Cycle Pipeline.
- Low Pressure (Instrument Air, Service Air, Cooling water & Service water, Fire water etc.) Pipeline
- De-aerating Heater & Feed Water Storage Tank with associated structures and approach platforms
- Roof & Side Cladding (metapoly sheet) of Boiler & Elevator.
- Insulation and Cladding.
- Temporary piping with tanks, valves, supports & fittings for EDTA cleaning/Chemical cleaning/flushing, Steam Blowing, Hydraulic test etc.
- Surface preparation and supply of Paints/Primer and application of paints for final painting on non-insulated surfaces.

2.2 HEAT RECOVERY STEAM GENERATORS (HRSG)

Collection of materials from BHEL/Client's stores/storage yard; transportation to site, Erection, Testing & Assistance for commissioning, Trial Operation and handing over of complete HRSG & its auxiliaries and steel stack including its electrical works, power cycle piping including P-91 materials, regenerative system piping with associated fittings, valves, supports including tanks & vessels, application of thermal insulation of HRSG with auxiliaries, steel stack, piping's with valves & fittings including gas turbine and steam turbine set equipments, heaters, tanks, vessels & pipings, supply of Paints/Primer and application of paints for final painting etc. of Block I (UB 1, HRSG 2 & 4) and Block II (UB 2, HRSG 1 & 3) with all its auxiliaries at 2X30 MW STG + 2X220 TPH UB + 4XFr6 B GT+4X110 TPH HRSG, OPaL Dahej, Bharuch- Gujarat.

The work is mainly categorized as follows:

- Erection, testing and commissioning of 110 TPH HRSG (for Block I & II) and its auxiliaries.
- Assembly, erection including welding & NDE etc. of steel stack / chimney of 40 meter height with associated electrical works of aviation lights, earthing & lightening arrestors etc.
- Erection, welding, testing and commissioning with radiography, NDE & heat treatment etc. of power cycle piping's with associated valves, hangers & supports and fittings etc.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – II : Scope of Works and technical Specification

- Erection, welding, testing and commissioning with radiography, NDE & heat treatment etc. of regenerative piping with associated valves, hangers & supports, fittings etc.
- Preparation & chipping of civil foundations and grouting of foundations / packers / foundation bolts / frames etc.
- Application of thermal insulation & lining on HRSG with associated auxiliaries / equipments, steel stack, tanks / vessels, piping's with valves & fittings including gas turbine and steam turbine set equipments, heaters, tanks, vessels & pipings etc.
- Chemical cleaning/ flushing including EDTA cleaning, flushing with air / water / oil etc., Hydro testing, steam blowing including lube oil flushing etc. of equipments, pipings and other associated systems covered under the scope.
- supply of Paints/Primer and application of paints for final painting including surface preparation, cleaning, marking of identification marks, colour bands, direction of rotation / flow marks, legends etc. as per OPal/EIL/ site requirement.

2.3 Construction Power & Water:

2.3.1 CONSTRUCTION POWER: Shall be provided on chargeable basis.

Tariff & other details shall be as follows:

1. BHEL is lining up construction power from M/s Torrent and it is expected to be made available by end of Jan'12 at 415 V at a single point.

Construction power will be provided on chargeable basis. The charges will comprise of per unit charges as charged by M/s Torrent plus 56% additional charges towards fixed cost. Hence the monthly charges to be paid by bidder will be as below:

Monthly Charge = 1.56 X (per unit rate charged by M/s Torrent) X (Units consumed for that month)

Per unit rate charged by M/s Torrent may vary in future and same shall be applicable to contractor. At present, the rate charged by M/s Torrent is Rs 6.30 per unit as energy charges.

There will be number of contractors using construction power at LT side. In case there is a difference in energy consumption in HT & LT side, i.e the sum of LT side energy meter readings with individual agency are less than the total energy consumption recorded in HT side energy meter of

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – II : Scope of Works and technical Specification

respective month, the differential consumption shall be proportionately distributed among all users in line with their energy consumption

2. Construction power (three phase, 415 V/ 440 V) will be provided at one point near the site at a distance of approx. 500M. **The electricity shall be provided on chargeable basis including all taxes, duties, levies etc as applicable.** Further distribution shall be arranged by the contractor at his own cost and services. Contractor shall be responsible for fulfillment of all requirements including statutory requirements in this regard. Contractor shall deploy and install required energy meter, cables, fuses, distribution boards, switchboards, bus bars, earthing arrangements, protection devices and any other installation as specified by statutory authority/act. Contractor shall also obtain approvals of appropriate authority and pay necessary fees, levies etc towards the clearance of such installations, prior to use. Sufficient power factor compensation equipments like capacitor shall be provided by contractor for reactive loads like welding machines etc. In case of any fine/penalty on account of low power factor, same shall be shared by contractor proportionately according to power consumption.
3. Contractor shall make necessary arrangements for onward distribution of construction power taking due care of surrounding construction activities like movement of cranes & vehicles, civil work, fabrication/construction/assembly/ erection etc and safety of personnel. It may become necessary to relocate some of the installations to facilitate work by other agencies or by him.
4. It shall be the responsibility of the Contractor to provide, maintain the complete installation on the load side of the supply with due regard to the safety requirements at site. All cabling and installations shall comply in all respects with the appropriate statutory requirements. The installation and maintenance of this shall be done by licensed and experienced electrician.
5. While reasonable efforts will be made to ensure continuous electric power supply, interruptions cannot be ruled out and no claim from the Contractor shall be entertained on this account such as idle labor, extension of time etc. The Contractor shall adjust his working shift accordingly and deploy additional manpower, if necessary, so as to achieve the target.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – II : Scope of Works and technical Specification

6. Contractor shall be well equipped with back-up power supply arrangement like DG set and diesel operated welding machine etc to tackle situations arising due to failure of supplied power, so as to ensure continuity and completion of critical processes that are underway at the time of power failure or important activities planned in immediate future.
7. BHEL is not responsible for any loss or damage to the Contractor's equipment as a result of variations in voltage or frequency or interruptions in power supply.
8. **Contractor to note that till construction power is made available by BHEL, contractor shall make his own arrangement like DG set etc. The contractor shall also take the approval/ permission of Gujarat State statutory authorities for his DG set installation.**
9. Contractor is requested to maintain the power factor above 0.95. On account of lapses by contractor on such account, the penalty as charged by M/s Torrent Power on account of drop in power factor below 0.9 shall be charged proportionately by sub-contractors working in the respective calendar month.
10. Contractor is advised to maintain the calibrated energy measuring instruments and use their system as efficiently as possible to maintain the HT side input energy meter reading and LT side outgoing energy meter reading to sub-contractors as equal.

In case there is any difference between the sum of the LT side meter readings of all sub-contractors and the HT side meter reading of M/s Torrent, same shall be distributed proportionately among all sub-contractors working during the respective calendar month.

- 1) Any taxes, duties, levies, cess etc as being charged/ levied by M/s Torrent/ state statutory authority shall be passed on to the sub-contractors proportionately in the respective calendar month bill.

2.3.2 Construction and Potable water shall be arranged by Contractor within the quoted rate. No additional payment shall be made on account of this.

Since the project site is under the SEZ's Area (Special Economic Zone), benefit of Exemption in Excise Duty, Service Tax, VAT etc may be availed by the contractor. For this necessary document shall be provided by BHEL to Contractor for obtaining Exception Certificate from the concerned Authority.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – II : Scope of Works and technical Specification

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Chapter – III : Facilities in the scope of Contractor/BHEL (scope Matrix)

Sl.No	Description PART I	Scope / to be taken care by		Remarks
		BHEL	Bidder	
3.1	ESTABLISHMENT			
3.1.1	FOR CONSTRUCTION PURPOSE:			
a	Open space for office (as per availability)	Yes		Location will be finalized after joint survey with owner
b	Open space for storage (as per availability)	Yes		Location will be finalized after joint survey with owner
c	Construction of bidder's office, canteen and storage building including supply of materials and other services		Yes	
d	Bidder's all office equipments, office / store / canteen consumables		Yes	
e	Canteen facilities for the bidder's staff, supervisors and engineers etc		Yes	
f	Fire fighting equipments like buckets, extinguishers etc		Yes	
g	Fencing of storage area, office, canteen etc of the bidder		Yes	
3.1.2	FOR LIVING PURPOSES OF THE BIDDER			
a	Open space for labour colony (as per availability)		Yes	Contractor has to make his own arrangements for space, shelter and transportation of labours as per their requirement.
b	Labour Colony with internal roads, sanitation, complying with statutory requirements		Yes	
3.2.0	ELECTRICITY			
3.2.1	Electricity for construction purposes 3 Phase 415/440 V (To be specified whether chargeable or free)			

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Chapter – III : Facilities in the scope of Contractor/BHEL (scope Matrix)

Sl.No	Description PART I	Scope / to be taken care by		Remarks
		BHEL	Bidder	
a	Single point source	Yes		Shall be provided by BHEL on chargeable basis. Pl. refer clause no. 2.3.1 in this regard.
b	Further distribution including all materials, Energy Meter, Protection devices and its service		Yes	
c	Duties and deposits including statutory clearances if applicable		Yes	
3.2.2	Electricity for the office, stores, canteen etc of the bidder.			Contractor has to make his own arrangement.
a	Single point source		Yes	
b	Further distribution including all materials, Energy Meter, Protection devices and its service		Yes	
c	Duties and deposits including statutory clearances if applicable		Yes	
3.2.3	Electricity for living accommodation of the bidder's staff, engineers, supervisors etc		Yes	Contractor has to make his own arrangement.
a	Single point source		Yes	
b	Further distribution including all materials, Energy Meter, Protection devices and its service		Yes	
c	Duties and deposits including statutory clearances if applicable		Yes	
3.3.0	WATER SUPPLY			
3.3.1	For construction purposes: (to be specified whether chargeable or free)			

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Chapter – III : Facilities in the scope of Contractor/BHEL (scope Matrix)

Sl.No	Description PART I	Scope / to be taken care by		Remarks
		BHEL	Bidder	
a	Making the water available at single point		yes	Contractor has to make his own arrangement.
b	Further distribution as per the requirement of work including supply of materials and execution		Yes	
3.3.2	Water supply for bidder's office, stores, canteen etc			
a	Making the water available at single point			Contractor has to make his own arrangement.
b	Further distribution as per the requirement of work including supply of materials and execution		Yes	
3.3.3	Water supply for Living Purpose			Contractor has to make his own arrangement.
a	Making the water available at single point		Yes	
b	Further distribution as per the requirement of work including supply of materials and execution		Yes	
3.4.0	LIGHTING			
a	For construction work (supply of all the necessary materials) 1. At office/storage area 2. At the preassembly area 3. At the construction site /area		Yes	

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Chapter – III : Facilities in the scope of Contractor/BHEL (scope Matrix)

Sl.No	Description PART I	Scope / to be taken care by		Remarks
		BHEL	Bidder	
b	For construction work (execution of the lighting work/ arrangements) 1. At office/storage area 2. At the preassembly area 3 At the construction site /area		Yes	
c	Providing the necessary consumables like bulbs, switches, etc during the course of project work		Yes	
d	Lighting for the living purposes of the bidder at the colony / quarters		Yes	
3.5.0	COMMUNICATION FACILITIES FOR SITE OPERATIONS OF THE BIDDER			
a	Téléphone, fax, internet, intranet, e-mail etc		Yes	
3.6.0	COMPRESSED AIR wherever required for the work		Yes	
3.7.0	Demobilization of all the above facilities		YES	
3.8.0	TRANSPORTATION			
a	For site personnel of the bidder		Yes	
b	For bidder's equipments and consumables (T&P, Consumables etc)		Yes	

Sl.No	Description PART II	Scope / to be taken care by		Remarks
		BHEL	Bidder	
	3.9.0 ERECTION FACILITIES			

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Chapter – III : Facilities in the scope of Contractor/BHEL (scope Matrix)

Sl.No	Description PART II 3.9.0 ERECTION FACILITIES	Scope / to be taken care by		Remarks
		BHEL	Bidder	
3.9.1	Engineering works for construction:			
a	Providing the erection/constructions drawings for all the equipments covered under this scope	Yes		
b	Drawings for construction methods	Yes	Yes	In consultation with BHEL
c	As-built drawings – where ever deviations observed and executed and also based on the decisions taken at site- example – routing of small bore pipes		Yes	Changes are to be marked in drawing & handover to BHEL on completion of work.
d	Shipping lists etc for reference and planning the activities	Yes		
e	Preparation of site erection schedules and other input requirements		Yes	In consultation with BHEL
f	Review of performance and revision of site erection schedules in order to achieve the end dates and other commitments	Yes	Yes	In consultation with BHEL
g	Weekly erection schedules based on Sl No. e		Yes	In consultation with BHEL
h	Daily erection / work plan based on Sl No. g		Yes	In consultation with BHEL

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Chapter – III : Facilities in the scope of Contractor/BHEL (scope Matrix)

Sl.No	Description PART II 3.9.0 ERECTION FACILITIES	Scope / to be taken care by		Remarks
		BHEL	Bidder	
i	Periodic visit of the senior official of the bidder to site to review the progress so that works are completed as per schedule. It is suggested this review by the senior official of the bidder should be done once in every two months.		Yes	
j	Preparation of preassembly bay		Yes	NOT APPLICABLE
k	Laying of racks for gantry crane if provided by BHEL or brought by the contractor/bidder himself		Yes	NOT APPLICABLE
L	Arranging the materials required for preassembly		Yes	NOT APPLICABLE

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Chapter – IV : T&Ps AND MME TO BE DEPLOYED BY
CONTRACTOR

A: TOOLS AND PLANTS TO BE DEPLOYED BY CONTRACTOR FOR EACH BLOCK

SN	DESCRIPTION	CAPACITY (MINIMUM)	MINIMUM QUANTITY	REMARKS
1	CRAWLER CRANE	75 MT	1	From the first month of start of Erection work
2	MOBILE CRANE	18 MT	1	TO BE DEPLOYED FROM THE START OF ERECTION
3	PICK & CARRY CRANE	12 MT	1	TO BE DEPLOYED FROM THE START OF ERECTION
4	PICK & CARRY CRANE	10 MT	1	TO BE DEPLOYED FROM THE START OF ERECTION
5	TRAILER WITH PRIME MOVER	15/20 MT	1	1 NO. FROM START AND 1 MORE FROM START+2 MONTHS BOTH TILL TRIAL RUN
6	AIR COMPRESSOR (ELECTRIC/DIESEL OPERATED)	140 CFM, 7 KG/CM2	1	
7	TIG WELDING SET	AS REQUIRED	8 NOS. AND FURTHER AS PER REQUIREMENT	
8	PLASMA CUTTING M/C	FOR CUTTING UP TO 10 MM THICK STAINLESS STEEL	AS REQUIRED	
9	3-PHASE DISTRIBUTION BOARD WITH COMPLETE SET UP FOR DRAWL OF CONSTRUCTION POWER & FITTED WITH ENERGY METER	600 Amp	AS PER REQUIREMET	
10	POWER CABLE FOR DRAWL OF CONSTRUCTION POWER	AS REQUIRED	AS REQUIRED	
11	PRE HEATING / STRESS RELIEVING SET (HEATING	AS REQUIRED	AS REQUIRED	

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 46

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Chapter – IV : T&Ps AND MME TO BE DEPLOYED BY
CONTRACTOR

SN	DESCRIPTION	CAPACITY (MINIMUM)	MINIMUM QUANTITY	REMARKS
	CONTROL PANEL, CABLES, HEATING ELEMENTS, THERMOMETERS ETC.)			
12	RADIOGRAPHY ARRANGEMENT WITH RADIOACTIVE ISOTOPE SOURCE	IRIDIUM-192	AS PER REQUIREMENT	
13	THEODOLITE OF REQUIRED ACCURACY	TO ENSURE VERICALITY OF STRUCTURAL COLUMNS	AS REQUIRED	
14	SELF DRILLING CUM TAPPING MACHINE FOR FIXING OF SHEETING WORK SCREWS	AS REQUIRED	AS REQUIRED	
15	RADIOGRAPHY ARRANGEMENT WITH RADIOACTIVE ISOTOPE SOURCE	COBALT-60	1 SET	
16	CHEMICAL CIRCULATION PUMPS TO HANDLE ACID SOLUTION, OPR TEMP 80 DEG CEL, WITH DRIVE MOTORS, STARTER PANEL, CABLE, SWITCH FUSE UNIT ETC.	SUGGESTED RATING: 150 M3, 120-150 M WC, WITH 90KW, 3000 RPM, 150 Amps MOTOR. HOWEVER, CONTRACTOR SHALL DEPLOY THE RQUIRED CAPACITY PUMP WITH ACCESSORIES AFTER OBTAINING WRITTEN APPROVAL OF BHEL.	AS REQUIRED	
17	WELDING GENERATOR (ELECTRICAL)	300 AMPERE RATING	AS REQUIRED	
18	WELDING GENERATOR (DIESEL OPERATED)	300 AMPERE RATING	AS REQUIRED	
19	RADIOGRAPHY FILM VIEWER	AS REQUIRED	AS REQUIRED	
20	ELECTRIC WINCH	3/2 TON CAPACITY	AS REQUIRED	
21	PIPE BENDING MACHINE- HAND OPERATED	UP TO 2" NB PIPES	AS REQUIRED	

BHEL-PSWR

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Chapter – IV : T&Ps AND MME TO BE DEPLOYED BY
CONTRACTOR

SN	DESCRIPTION	CAPACITY (MINIMUM)	MINIMUM QUANTITY	REMARKS
22	HAND WINCH	0.5 TON	AS REQUIRED	
23	BAKING OVEN AND HOLDING OVEN WITH THERMOSTAT AND TEMPERATURE GAUGE FOR WELDING ELECTRODES	AS PER REQUIREMENT	AS REQUIRED	
24	PORTABLE OVEN FOR COATED WELDING ELECTRODES	AS PER REQUIREMENT	AS REQUIRED	
25	ELECTRIC MOTOR DRIVEN HYDRAULIC TEST PUMP WITH DRIVE AND STARTER ETC.	400 Kg/Cm2 250 Kg/Cm2	1 NO. 1 NO.	FURTHER AS REQUIRED
26	SCAFFOLDING MATERIALS (SCAFFOLDING PIPES WITH CLAMPS ETC.)	ADEQUATE TO SUIT THE REQUIREMENT	800 SETS AND FURTHER AS PER REQUIREMENT	
27	ALU. SHEET CLAD PROFILE MAKING MACHINE	AS PER REQUIREMENT	AS REQUIRED	
28	HAND TOOLS, CUTTING TOOLS GRINDING MACHINES ETC	AS PER REQUIREMENT	AS REQUIRED	
29	NIBBLING MACHINE	AS PER REQUIREMENT	AS REQUIRED	
30	SHEARING MACHINE	AS PER REQUIREMENT	AS REQUIRED	
31	WATER PUMP TO LIFT WATER TO TOP OF BOILER	AS PER REQUIREMENT	AS REQUIRED	
32	PORTABLE GRINDING M/C	AS PER REQUIREMENT	AS REQUIRED	
33	PORTABLE DRILLING M/C	AS PER REQUIREMENT	AS REQUIRED	
34	CHAIN PULLEY BLOCKS	Assorted capacities	AS REQUIRED	
35	FIRE RETARDANT TARPAULINS	AS PER REQUIREMENT	AS REQUIRED	

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 48

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Chapter – IV : T&Ps AND MME TO BE DEPLOYED BY
CONTRACTOR

SN	DESCRIPTION	CAPACITY (MINIMUM)	MINIMUM QUANTITY	REMARKS
36	FIRE EXTINGUISHER	AS PER REQUIREMENT	AS REQUIRED	

A: MEASURING AND MONITORING DEVICES (MMD) TO BE DEPLOYED BY CONTRACTOR

AS PER REQUIREMENT TO BE FINALIZED AT SITE.

NOTE:

- 1) ALL THE TOOLS AND PLANTS REQUIRED FOR THIS SCOPE OF WORK, EXCEPT THE TOOLS & PLANTS PROVIDED BY BHEL ARE TO BE ARRANGED BY CONTRACTOR WITHIN THE QUOTED RATES. THE LIST IS SUGGESTIVE IN NATURE. ANY ADDITIONAL T&P REQUIRED TO BE ARRANGED BY THE CONTRACTOR.
- 2) IF ABOVE MENTIONED T & P ARE NOT DEPLOYED IN SPECIFIED TIME BHEL WILL CHARGE TO CONTRACTOR CURRENT MARKET RATE + 30 % OVERHEADS FOR NON AVAILABILITY T&P OR LEVY A DAY WISE PENALTY FOR NON DEPLOYMENT OR DELAYED DEPLOYMENT.
- 3) IF THE WORKS GET DELAYED DUE TO NON-AVAILABILITY OF T&P, BHEL RESERVES THE RIGHT TO GET THE WORK DONE AT THE RISK AND COST OF CONTRACTOR WITHIN PREJUDICE TO RIGHTS OF BHEL AS IN GCC.
- 4) THE MANUFACTURING YEAR OF ALL MAJOR T&PS DEPLOYED BY THE CONTRACTOR (75 MT, CRAWLER CRANE, 18 MT MOBILE CRANE AND 12/10 MT PICK & CARRY CRANE) SHOULD NOT BE MORE THAN 10 YEARS AS ON THE DATE OF DEPLOYMENT. IF AT ANY MOMENT OF TIME DURING THE EXECUTION OF WORK, ANY CRANE IS FOUND TO BE NOT IN A GOOD WORKING CONDITION AND NON-PERFORMING AT DESIRED MINIMUM CAPACITY, AS CERTIFIED BY BHEL ENGINEER, THE CONTRACTOR SHALL DEPLOY ANOTHER CRANE IN GOOD WORKING CONDITION WITH MINIMUM DESIRED CAPACITY. IF CONTRACTOR FAILS TO DEPLOY THE SAME WITH IN 10 DAYS, BHEL WILL RECOVER NON-REFUNDABLE PENALTY PER DAY OF DELAY IN THE FOLLOWING MANNER -

1. IN RESPECT OF 75 MT CRANE: @ RS. 5,000 / -

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – IV : T&Ps AND MME TO BE DEPLOYED BY CONTRACTOR

- 2. IN RESPECT OF 18 MT CRANE: @ RS. 3,000 / -
- 3. IN RESPECT OF 12 MT CRANE: @ RS. 1,000 / -
- 4. IN RESPECT OF 10 MT CRANE: @ RS. 1,000 / -

BES = BOILER ERECTION START, CF = COAL FIRING, BLU = BOILER LIGHT UP, FL = FULL LOAD,

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – V: T&Ps and MMEs to be deployed by BHEL on sharing basis

LIST OF T&P TO BE PROVIDED BY BHEL FREE OF HIRE CHARGES ON SHARING BASIS: FOR EACH BLOCK

SN	DESCRIPTION	QUANTITY	REMARKS
1	Cranes	-	All cranes (except Contractor scope) required for the mentioned work will be arranged by BHEL as per requirement.
2	Multi Sheave Pulley	-	For DL
3	Single Sheave Pulley	-	"
4	Electric Winch with wire rope	-	"

Note:

- 1) CRANES DEPLOYED BY BHEL SHALL BE OWNED OR HIRED BY BHEL.
- 2) OPERATOR AND O&M FOR BHEL OWNED CRANE WILL BE ARRANGED BY BHEL (FREE OF CHARGES).
- 3) OPERATORS AND O&M FOR HIRED CRANE WILL BE PROVIDED BY THE HIRING AGENCY (FREE OF CHARGES).
- 4) CONTRACTOR SHALL PROVIDE THE FUEL FOR BHEL PROVIDED CRANES (HIRED/OWNED) FOR THEIR USE.
- 5) CONTRACTOR SHALL MAKE NECESSARY ARRANGEMENTS LIKE LAYING OF SPECIAL SLEEPER BEDS AND STEEL PLATES (ALL ARRANGED BY CONTRACTOR), ASSEMBLY AND DISMANTLING OF HEAVY LIFT ATTACHMENT, BOOM, JIB ETC FOR MOVEMENT AND OPERATION OF THE CRANE.
- 6) CRANES PROVIDED BY BHEL WILL BE ON SHARING BASIS WITH OTHER AGENCIES / CONTRACTORS OF BHEL. THE ALLOCATION OF CRANES SHALL BE THE DISCRETION OF BHEL ENGINEER, WHICH SHALL BE BINDING ON THE CONTRACTOR. CRANES WILL BE DEPLOYED AT APPROPRIATE TIME AS DECIDED BY BHEL FOR SUITABLE DURATION AND INTENDED PURPOSE.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – VI: Time Schedule

6.1 TIME SCHEDULE & MOBILIZATION

6.1.1 INITIAL MOBILIZATION

After receipt of fax **Letter of Intent (LOI)**, Contractor shall discuss with Project Manager / Construction Manager regarding initial mobilization. Contractor shall mobilize necessary resources within 2 weeks of issue of fax letter of intent or as per the directive of Project Manager / Construction Manager. Such resources shall be progressively augmented to match the schedule of milestones and commissioning.

6.1.2 MOBILIZATION FOR ERECTION, TESTING, ASSISTANCE FOR COMMISSIONING ETC.

The activities for Erection, Testing etc. shall be started as per directions of Construction Manager of BHEL. Contractor shall mobilise further resources (in addition to those required for activities under clause no. 6.1.1) as per requirement to commence the work of erection, testing etc. of boiler and auxiliaries and progressively augment the resources to match schedule of the project.

6.1.3 COMMENCEMENT OF CONTRACT PERIOD AND TENTATIVE SCHEDULE

Erection/placement on its designated foundation / location, of the first major permanent equipment / component / column covered in the scope of these specifications shall be recognized as “**Start of Contract Period**”. Smaller items like packer plates, shims, anchors, inserts etc. will not be considered as start of contract period.

The Contractor has to subsequently augment his resources in such a manner that following major milestones of erection & commission are achieved on specified schedules:

According to the contract between BHEL and Owner the schedule of important milestones is as follows:

For Block I (UB1, HRSG 2 & 4) :

Major Milestone for UB 1 and HRSG 2 & 4 of OPaL Dahej Project

SL No.	Milestones	Date of completion Assuming DOS: 01/03/12
	UTILITY BOILER # 1	
1	Erection Start	1 st week of Mar'12
2	Drum Lifting	2 nd week of May'12
3	Hydro Test	2 nd week of Aug'12
4	Boiler Light Up (BLU)	2 nd week of Oct'12
5	Safety Valve Floating	3 rd week of Nov'12
6	Synchronization	1 st week of Dec'12
7	Completion of Trail run	Jan'2013

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 52

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – VI: Time Schedule

8	Completion of all Facilities	Jan'2013
---	------------------------------	----------

SL No.	Milestones	Tentative completion Schedule
	HRSG # 2	
1	HRSG Erection Start	3 rd week of Apr'12
2	HRSG Drum Lifting	3 rd week of Aug'12
3	Hydraulic Test	2 nd week of Dec'12
4	Gas In and Alkali boil Out	3 rd week of Feb'13
5	Safety Valve Floating & Steam Blowing	3 rd week of Mar'13
6	Co-Gen Commissioning (GTG 1 + HRSG 1)	3 rd week of Apr'13
7	Reliability Run Completion	Apr'2013
8	Completion of all Facilities	Apr'2013
	HRSG # 4	
1	HRSG Erection Start	3 rd week of Aug'12
2	HRSG Drum Lifting	3 rd week of Dec'12
3	Hydraulic Test	2 nd week of Apr'13
4	Gas In and Alkali boil Out	3 rd week of Jun'13
5	Safety Valve Floating & Steam Blowing	3 rd week of Jul'13
6	Co-Gen Commissioning (GTG 3 + HRSG 3)	3 rd week of Aug'13
7	Reliability Run Completion	Sep'2013
8	Completion of all Facilities	Sep'2013

For Block II (UB2, HRSG 1 & 3) :

Major Milestone for UB 2 and HRSG 1 & 3 of OPaL Dahej Project

SL No.	Milestones	Date of completion Assuming DOS: 01/04/12
	HRSG # 1	
1	HRSG Erection Start	1 st week of Apr'12
2	HRSG Drum Lifting	3 rd week of Jun'12
3	Hydraulic Test	2 nd week of Oct'12
4	Gas In and Alkali boil Out	3 rd week of Dec'12
5	Safety Valve Floating & Steam Blowing	2 nd week of Jan'13
6	Co-Gen Commissioning (GTG 1 +	3 rd week of Feb'13

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – VI: Time Schedule

	HRSG 1)	
7	Reliability Run Completion	Mar'2013
8	Completion of all Facilities	Mar'2013
SL No.	Milestones	Tentative completion Schedule
	HRSG # 3	
1	HRSG Erection Start	1 st week of Jun'12
2	HRSG Drum Lifting	3 rd week of Aug'12
3	Hydraulic Test	2 nd week of Dec'12
4	Gas In and Alkali boil Out	3 rd week of Feb'13
5	Safety Valve Floating & Steam Blowing	2 nd week of Mar'13
6	Co-Gen Commissioning (GTG 3 + HRSG 3)	3 rd week of Apr'13
7	Reliability Run Completion	May'2013
8	Completion of all Facilities	May'2013
	UTILITY BOILER # 2	
1	Erection Start	1 st week of Jul'12
2	Drum Lifting	3 rd week of sep'12
3	Hydro Test	2 nd week of Jan'13
4	Boiler Light Up (BLU)	2 nd week of Mar'13
5	Safety Valve Floating	3 rd week of Apr'13
6	Synchronization	3 rd week of May'13
7	Completion of Trail run	Jun'2013
8	Completion of all Facilities	Jul'2013

In order to meet above schedule in general, and any other intermediate targets set, to meet customer/ project schedule requirements, Contractor shall arrange & augment all necessary resources from time to time on the instructions of BHEL.

6.1.4 CONTRACT PERIOD

The contract period for completion of entire work under scope shall be **19 (Nineteen)** months for **Block I** (UB 1, HRSG 2 & 4) and **16 (sixteen)** months for **Block II** (UB 2, HRSG 1 & 3) from the “start of contract period” as specified earlier.

The period from the commencement of preparatory work for erection till the actual “start of contract period” shall not be reckoned for the above purpose.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – VI: Time Schedule

Note:

- Agency should note that the construction works for both the stream viz UBs and HRSGs along with its auxiliaries shall have to go parallelly to match with the commissioning schedule of the plant. For this it will necessary to deploy “Dedicated Resources” like Manpower, Machineries and Materials Area wise to execute the works simultaneously.
- Bidders are requested to submit Resource deployment plan Area wise with detail program in line with above schedule in the form of Bar Chart / MS project planer along with their offer.

6.1.5

IN ORDER TO MEET ABOVE SCHEDULE AND OTHER INTERMEDIATE TARGETS/ACTIVITIES AS SET **BY BHEL ENGINEER IN CHARGE** AT SITE & TO MEET CUSTOMER REQUIREMENTS/PROJECT SCHEDULE, CONTRACTOR SHALL ARRANGE ALL NECESSARY RESOURCES AND WORK FORCE IN CONSULTATION WITH BHEL ENGINEER AT SITE TO UNDERTAKE WORKS CONCURRENTLY IN ALL POSSIBLE FRONTS AS MADE AVAILABLE TO CONTRACTOR.

CONTRACTOR SHALL NOTE THAT INDIVIDUAL MILESTONES AS ABOVE SHALL BE ACHIEVED AS PER SCHEDULE FURNISHED ABOVE. **THE DATE OF START OF FIRST MAJOR PERMANENT EQUIPMENT / COMPONENT / COLUMN COVERED IN THE SCOPE SHALL BE RECKONED AS THE START OF CONTRACT PERIOD FOR THIS PURPOSE.**

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – VII: Terms of Payment

The progressive payment for erection, testing and commissioning on accepted price of contract value will be released as per the break up given hereinafter:

TERMS OF PAYMENT FOR STEAM GENERATOR (UTILITY BOILER AND HRSG)												
SL NO	Contract (Main Package) Identification ---->	Boiler				Rotating Machine	Steel Stack	PIPING			De- aerator	INSULATION
	Rate schedule Identification ----->	Struct ure	Pressure Parts	Non Pressure Parts	Air Pre Heaters	1) RM 2) Handling Eqpts	HRSG Chimney/Ste el stack	1)P-91 2) AS 3) CS (HP) 4) CS (LP) 5) SS	Hangers & Supports	Temporar y Piping 1) Steam Blowing 2) Chemical Cleaning	De-aerator, feed storage Tank and associate approach platform with ladders	1) Castable & Pourable 2) Iron Components 3) Wool mattresses 4) Aluminium sheeting
I	PRO RATA PAYMENTS (85%)											
1.1	ON PRE-ASSEMBLY WHEREVER APPLICABLE (IF NOT APPLICABLE, THIS PORTION SHALL BE CLUBBED WITH PLACEMENT IN POSITION)	20	20	25		15	15	20	15			--
1.2	PLACEMENT IN POSITION	15	10	10		20	20	20	25		25	50
1.3	ALIGNMENT	15	15	10		20	15	10	15		20	15
1.4	WELDING/BOLTING/FIXING	15	20	15		20	20	15	30		30	20
1.5	COMPLETION OF NON DESTRUCTIVE EXAMINATION & STRESS RELIEVING/ HEAT TREATMENT (if not applicable, then this portion to be paid along with welding)	5	10	--		--	--	5				--
1.6	On Drum Lifting	0										
1.7	COMPLETION OF ATTACHMENT WELDING, FIN WELDING, SUPPORTS		5									

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 56

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – VII: Terms of Payment

1.8	COMPLETION OF ROOF SKIN CASING		5									
1.9	INSTALLATION OF TEMPORARY PIPING									60		
1.10	DISMANTLING OF TEMPORARY PIPING, EDGE PREPARATION AND RETURN TO BHEL STORES, AREA CLEANING									25		
1.11	HANGERS & SUPPORTS ETC WHEREVER NECESSARY AS PER DRG		--	25		--	15	10				--
1.12	COMPLETION OF FURNACE ALIGNMENT AND FIRE BALL CHECKING	5										
1.13	COMPLETION OF BACK PASS ALIGNMENT	5										
1.14	COMPLETION OF VIBRATION SNUBBERS, MECHANICAL SPACERS, CASSETTE BAFFLES, STEAM COOLED SPACERS	5										
1.15	COMPLETION OF HOPPERS ALONG WITH ALL DOORS, HEATING ELEMENTS, POKING DOORS, ETC		--	0		--	0	--				--
1.16	COMPLETION OF INNER, OUTER ROOF INSULATOR HOUSING, RECTIFIER TRANSFORMERS, PENT HOUSE MONO RAILS, HOISTS ETC		--	--		--	--	--				--
1.17	ERECTION OF EMITTING AND COLLECTING RAPPING SYSTEM WITH ALL DRIVES		--	--		--	--	--				--
1.18	EQUIPMENT TRIAL OPERATION					10						
1.19	HYDRAULIC TEST OR PNEUMATIC TEST							3				

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 57

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – VII: Terms of Payment

1.20	FLOATING OF LINES, FINAL ADJUSTMENT OF SUPPORTS FOR COLD AND HOT VALUES (if not applicable, this portion to be clubbed along with hydraulic test/pneumatic test)							2				
1.21	AIR PRE HEATERS (PG 52) From the total amount payable for the PGMA weight at tonnage rates, payment will be regulated as under:											
1.21.1	Completion of Support steel squareness and levelling, Expansion arrangement, Housing panel erection and alignment, Erection, alignment and welding of pedestals				11							
1.21.2	Completion of Erection, alignment and welding of Support Bearing, Guide Bearing, Rotor post, Bottom and Top centre sections, Hot and cold end connecting plates				14							
1.21.3	Completion of erection and alignment of modules				15							
1.21.4	Completion of erection, alignment and welding of Pin Rack assembly and Drive assembly				12							
1.21.5	Completion of seals setting				17							
1.21.6	Erection, alignment and welding of Lube oil systems, Cleaning Device, Fire sensing device, Deluge and water wash lines, Observation port and lighting assemblies and other accessories				13							
1.21.7	Completion of PGMA				1							
1.21.8	Air preheater Trial Run				2							

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 58

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – VII: Terms of Payment

1.21.8	Erection, Testing & commissioning of De-aerator, feed storage tank and associated approach platform with ladders etc.										10	
	TOTAL FOR PRO RATA PAYMENTS (TOTAL 85%)	85	85	85	85	85	85	85	85	85	85	85
II	STAGE/MILESTONE PAYMENTS (15%)											
2.1	AIR & GAS TIGHTNESS TEST		--	5		--	5	--				--
2.2	GAS DISTRIBUTION TEST		--	--		--		--				--
2.3	CHARGING OF ESP FIELDS		--	--		--		--				--
2.4	COMPLETION OF AIR & GAS TIGHTNESS TEST FOR FURNACE		2									
2.5	BOILER HYDRAULIC TEST (DRAINABLE)	0	2									
2.6	BOILER HYDRAULIC TEST (NON DRAINABLE)		1									
2.7	Reheater Coils Hydraulic Test		2									
2.8	Clean Air Flow test					1						
2.9	Boiler Light Up/Gas In	0	1		2	1		1	1			1
2.10	ABO		1	1	2	1	1	1	1			1

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 59

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – VII: Terms of Payment

2.11	Steam Blowing	0		2	1	1	2	1	1			1
2.12.	SVF		2		2			1	1			1
2.13	Oil Flushing (TG/GT)											
2.14	Barring Gear (TG)/ Cranking (GT)											
2.15	Rolling/FSNL and Synchronisation	0							1			
2.16	Fuel Firing			2	2	2	2		1			1
2.17	Full Load					1		1	1			1
2.18	Trial Operation of Unit					2		2	2			2
2.19	Completion of sheet covering for Boiler roof, burner roof, lift shaft cladding, completion of gutters	3										
2.20	Completion of all drains and vents to respective locations and placement of instrument sensors after steam blowing							2				
2.21	Painting	6	0	1	1	2	1	2	1			0
2.22	Area cleaning, temporary structures cutting/removal and return of scrap	1	1	1	1	1	1	1	2			3
2.23	Punch List points/pending points liquidation	2	1	1	2	1	1	1	1			1
2.24	Submission of 'As Built Drawings'											

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 60

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter – VII: Terms of Payment

2.25	Material Reconciliation	2	1	1	1	1	1	1	1	15		2
2.26	Completion of Contractual Obligation	1	1	1	1	1	1	1	1			1
	TOTAL FOR STAGE/MILESTONE PAYMENTS (15%)	15	15	15	15	15	15	15	15	15		15
	TOTAL I + II	100	100	100	100	100	100	100	100	100		100
	*INCLUDING NDE AND SR/HT WHERE EVER APPLICABLE (IF APPLICABLE, WEIGHTAGE OF 10%)											

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VIII: Taxes and Other Duties

8.1 TAXES, DUTIES, LEVIES

8.1.1

The contractor shall pay all (save the specific exclusions as enumerated in this contract) taxes, fees, license charges, deposits, duties, tools, royalty, commissions or other charges which may be levied on the input goods & services consumed and output goods & services delivered in course of his operations in executing the contract. In case BHEL is forced to pay any of such taxes, BHEL shall have the right to recover the same from his bills or otherwise as deemed fit.

However, provisions regarding Service Tax and Value Added Tax (VAT) on output services and goods shall be as per following clauses.

8.1.2 Service Tax & Cess on Service Tax

OPAL DAHEZ Project falls under SEZ “Special Economic Zone” as such Service Tax is exempted for this project.

Contractor should ensure as flows.

- a) Invoices raised by contractor should state the wording that “ Services provided Within the SEZ”
- b) Invoices should also bear the name of customer i.e. “OPAL Dahej”

8.1.3 VAT (Sales Tax /WCT)

As regards Value Added Tax (VAT) on transfer of property in goods involved in Works Contract (previously known as Works Contract Tax) applicable as per local laws, the price quoted by the contractor shall be **exclusive** of the same. Where such taxes are required to be paid by the contractor, this will be reimbursed on production of proof of payment made to the authorities by the Contractor. In any case the Contractor shall register himself with the respective Sales Tax authorities of the state and submit proof of such registration to BHEL along with the first RA bill. The contractor has to take all necessary steps to **minimize tax on input goods** by purchasing the materials from any registered dealer of the concerned state only. In case contractor opts for composition, it will be with the prior express consent of BHEL. Deduction of tax at source shall be made as per the provisions of law unless otherwise found exempted. In case tax is deducted at source as per the provisions of law, this is to be construed as an advance tax paid by the contractor and no reimbursement thereof will be made unless specifically agreed to.

8.1.4 Modalities of Tax Incidence on BHEL

Wherever the relevant tax laws permit more than one option or methodology for discharging the liability of tax/levy/duty, BHEL will have the right to adopt the appropriate one considering the amount of tax liability on BHEL/Client as well as procedural simplicity with regard to assessment of the liability. The option chosen by BHEL shall be binding on the Contractor for discharging the obligation of BHEL in respect of the tax liability to the Contractor.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VIII: Taxes and Other Duties

8.1.5 New Taxes/Levies

In case the Government imposes any new levy/tax on the output service/ goods/work after award of the contract, the same shall be reimbursed by BHEL at actual.

In case any new tax/levy/duty etc. becomes applicable after the date of Bidder's offer, the Bidder/Contractor must convey its impact on his price duly substantiated by documentary evidence in support of the same **before opening of Price Bid**. Claim for any such impact after opening the Price Bid will not be considered by BHEL for reimbursement of tax or reassessment of offer.

No reimbursement/recovery on account of increase/reduction in the rate of taxes, levies, duties etc. on input goods/services/work shall be made. Such impact shall be taken care of by the Price Variation/Adjustment Clause (PVC) if any. In case PVC is not applicable for the contract, Bidder has to make his own assessment of the impact of future variation if any, in rates of taxes/duties/ levies etc. in his price bid.

8.1.6 Submission of Periodical Reports

Contractor shall submit periodical reports in respect of following aspects of operation:

- 1) Consumption of welding electrodes and gases
- 2) Consumption of construction power
- 3) Manpower reports
- 4) Daily and Monthly Progress reports
- 5) Field calibration reports

BHEL at site will inform formats for these reports.

8.1.7 It is the responsibility of the contractor to arrange gate pass for all his employees, T&P etc. Necessary coordination with customer officials is the responsibility of the contractor. Contractor to follow all the procedures laid down by the customer for making gate passes. Where permitted, by customer/ BHEL, to work beyond normal working hours, the contractor shall arrange necessary work permit for working beyond normal working hours

8.2 BUILDING & OTHER CONSTRUCTION WORKERS (REGULATION OF EMPLOYMENT AND CONDITIONS OF SERVICE) ACT, 1996 (BOCW Act) AND RULES OF 1998 READ WITH BUILDING & OTHER CONSTRUCTION WORKERS CESS Act, 1996 & CESS RULES, 1998.

In case any portion of work involves execution through building or construction workers, then compliance to the above titled Acts shall be ensured by the contractor and contractor shall obtain license and deposit the cess under the Act. In the circumstances it may be ensured as under:-

- i. It shall be the sole responsibility of the contractor in the capacity of employer to forthwith (within a period of 15 days from the award of work) apply for a licence to the Competent Authority under the BOCW Act and obtain proper certificate thereof by specifying the scope of its work. It shall also be responsibility of the contractor to furnish a copy of

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VIII: Taxes and Other Duties

such certificate of licence / permission to BHEL within a period of one month from the date of award of contract.

- ii. It shall be the sole responsibility of the contractor as employer to ensure compliance of all the statutory obligations under these act and rules including that of payment / deposit of 1% cess on the extant of work involving building or construction workers engaged by the contractor within a period of one month from the receipt of payment.
- iii. It shall be the responsibility of the sub-contractor to furnish the receipts / challans towards deposit of the cess together with the number, name and other details of beneficiaries (building workers) engaged by the sub-contractor during the preceding month.
- iv. It shall be the absolute responsibility of the sub-contractor to make payment of all statutory payments & compensations to its workers including that is provided under the Workmen's Compensation Act, 1923.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VIII: Taxes and Other Duties

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-IX : SPECIFIC INCLUSIONS

SPECIFIC INCLUSIONS

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-X : SPECIFIC EXCLUSIONS

10.0 EXCLUSIONS

The following works are specific exclusions from the scope of work under erection, testing & commissioning of tender specification-

- Sub-delivery items and electrical components such as push-buttons, junction boxes etc.
- E&C work of cable trays, cables and earthing etc
- Control panels, EPMS, MCC etc.
- Electrical & C&I items of handling system.
- All electrical and control & instrumentation items except those specified elsewhere in these specifications.
- Civil works except to the extent specifically indicated elsewhere in this tender.
- Supply of primer and paints for final painting.
- Pneumatic copper tubing and fittings thereof.
- Testing and commissioning of heating elements, thermostats, HV rectifier transformers.
- Electrical and C&I items of Variable Frequency Drives as provided elsewhere in these specifications.

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

ESTIMATED WEIGHT OF VARIOUS SYSTEM IN SCOPE OF WORK

LIST OF APPLICABLE PGMA'S FOR UTILITY BOILER (Applicable for UB 1 & 2)

S.N.	PG	MA	PGMA Description	Est Wt in Kg	Wt in MT	PKG	PG Wt MT
[1]	From Trichy (Cust. No.-6011)						
A	STRUCTURES (Trichy Supply)						
1	08	101	FURNACE BUCKSTAY-UPPER	30000.00	30.00	STR	
2	08	104	FURNACE BUCKSTAY-MIDDLE	30000.00	30.00	STR	
3	08	107	FURNACE BUCKSTAY-LOWER	20000.00	20.00	STR	
4	08	900	FURNACE KEY BUCKSTAY	6000.00	6.00	STR	
			PG Weight				86.00
5	09	001	Seal Boxes For Furnace Opening	2800.00	2.80	STR	
6	09	002	Seal Boxes For Instrument Inserts	1400.00	1.40	STR	
7	09	003	Light Up Supplies	300.00	0.30	STR	
			PG Weight				4.50
8	35	010	FOUNDATION MATERIAL	10000.00	10.00	STR	
9	35	110	MAIN COLUMN-LEFT	115000.00	115.00	STR	
10	35	120	MAIN COLUMN-RIGHT	115000.00	115.00	STR	
11	35	210	CEILING STRUCTURE FABRICATED BEAMS	80000.00	80.00	STR	
12	35	220	CEILING STRUCTURE ROLLED BEAMS	20000.00	20.00	STR	
13	35	230	HORIZONTAL BRACING FOR CEILING STRUCT	5000.00	5.00	STR	
14	35	310	AIR HEATER SUPPORT FRAME	15000.00	15.00	STR	
15	35	351	HORIZONTAL BRACING LEVEL-1	12000.00	12.00	STR	
16	35	352	HORIZONTAL BRACING LEVEL-2	12000.00	12.00	STR	
17	35	353	HORIZONTAL BRACING LEVEL-3	12000.00	12.00	STR	
18	35	380	LANDINGS FOR DRUM LIFTING	30000.00	30.00	STR	
19	35	390	PLATFORM FOR DRUM ERECTION	20000.00	20.00	STR	
20	35	510	COLUMN FRONT BRACING	55000.00	55.00	STR	
21	35	520	COMLUMN SIDE BRACING	95000.00	95.00	STR	
22	35	530	COLUMN REAR BRACING	65000.00	65.00	STR	
23	35	811	FLOOR GRILLS	20000.00	20.00	STR	
24	35	820	STAIRS AND LADDERS	9000.00	9.00	STR	
25	35	850	HAND RAILS AND POSTS	15000.00	15.00	STR	
			PG Weight				705.00

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 68

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

26	36	110	COLUMNS NEAR APH	25000.00	25.00	STR	
27	36	150	COLUMN BRACINGS	45000.00	45.00	STR	
28	36	210	MAIN FLOOR-1ST LEVEL	30000.00	30.00	STR	
29	36	230	MAIN FLOOR-3RD LEVEL	20000.00	20.00	STR	
30	36	240	MAIN FLOOR-4TH LEVEL	20000.00	20.00	STR	
31	36	250	MAIN FLOOR-5TH LEVEL	25000.00	25.00	STR	
32	36	380	LANDINGS FOR COMMISSIONING	20000.00	20.00	STR	
33	36	390	MISCELLANEOUS FLOOR	20000.00	20.00	STR	
34	36	440	HORIZONTAL BEAMS	30000.00	30.00	STR	
35	36	441	DUCT SUPPORTS	35000.00	35.00	STR	
36	36	442	PIPING SUPPORTS	25000.00	25.00	STR	
37	36	446	EXTWRNAL PIPING SUPPORTS	25000.00	25.00	STR	
38	36	610	ROOF STRUCTURE	45000.00	45.00	STR	
39	36	611	ROOF SHEETING	20000.00	20.00	STR	
40	36	612	RAINWATER PIPES-PVC	5000.00	5.00	STR	
41	36	820	STAIRS AND LADDERS	15000.00	15.00	STR	
42	36	850	HAND RAILS AND POSTS	35000.00	35.00	STR	
			PG Weight				440.00
43	38	010	FOUNDATION MATERIAL INTER CONN COLUMNS	5000.00	5.00	STR	
44	38	110	COLUMNS-INT. CONNECTION	20000.00	20.00	STR	
45	38	150	COLUMN BRACINGS	20000.00	20.00	STR	
46	38	210	PLATFORMS AND FLOORS	20000.00	20.00	STR	
47	38	810	FLOOR GRILLS	15000.00	15.00	STR	
			PG Weight				80.00
48	39	010	FOUNDATION MATERIAL ID & FD	10000.00	10.00	STR	
49	39	101	COLUMN-ID SYSTEM	40000.00	40.00	STR	
50	39	121	COLUMN -PA&FD SYSTEM	40000.00	40.00	STR	
51	39	150	COL.BRACING BET.ID & CHIMNEY	10000.00	10.00	STR	
52	39	200	PA&FD DUCT SUPPORT BEAMS	25000.00	25.00	STR	
53	39	210	COLUMN BRACING PA&FD SYSTEM	25000.00	25.00	STR	
54	39	300	ID SYSEM FLOOR	10000.00	10.00	STR	
55	39	301	PLATFORM FOR FANS	3000.00	3.00	STR	
56	39	302	STRUCTURE FOR MOTOR HOOD	12000.00	12.00	STR	
57	39	303	FD FAN HANDLING STRUCTURE	15000.00	15.00	STR	
58	39	311	ID DUCT SUPPORT BEAMS	25000.00	25.00	STR	
			PG Weight				215.00
59	41	200	GAS SPUDS	1000.00	1.00	STR	

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

			PG Weight				1.00
			SUB TOTAL A (Structure)	1531500.00	1531.50		
B	PRESSURE PARTS (Trichy Supply)						
1	04	114	Upper Drum + Intl Id 49-60	60000.00	60.00	PP	
2	04	144	Upper Drum Sspn Id 49-60	4850.00	4.85	PP	
3	04	194	Upper Drum Trans Strr Id 49-60	5150.00	5.15	PP	
			PG Weight				70.00
4	05	137	Inlet Front Lower Ww Header	5000.00	5.00	PP	
5	05	147	Inlet Rear Lower Ww Header	6100.00	6.10	PP	
6	05	155	Inlet Side Lower Ww Header	12000.00	12.00	PP	
7	05	228	Ww Outlet Header Screen Tube	3000.00	3.00	PP	
8	05	231	Outlet Front Upper Ww Header	1900.00	1.90	PP	
9	05	251	Outlet Side Upper Ww Header	4500.00	4.50	PP	
			PG Weight				32.50
10	06	400	Unclassified Burner Panel	12000.00	12.00	PP	
11	06	631	Front Upper Ww Pnl	22000.00	22.00	PP	
12	06	634	Front Intermediate Ww Pnl	15000.00	15.00	PP	
13	06	637	Waterwall Lower Front Panel	9000.00	9.00	PP	
14	06	641	Rear Upper Ww Pnl	7000.00	7.00	PP	
15	06	644	Rear Intermediate Ww Pnl	19000.00	19.00	PP	
16	06	647	Rear Lower Ww Pnl	9000.00	9.00	PP	
17	06	651	Side Upper Ww Pnl	48000.00	48.00	PP	
18	06	653	Side Intermediate Ww Pnl	20000.00	20.00	PP	
19	06	655	Side Lower Ww Pnl	29000.00	29.00	PP	
			PG Weight				190.00
20	07	101	Downcomer Piping-Natural Circulation	46000.00	46.00	PP	
21	07	201	Riser Tubes	18000.00	18.00	PP	
21	07	223	Furnace Screen Tubes	2500.00	2.50	PP	
22	07	231	Lower Corner Transition Tubes	2500.00	2.50	PP	
23	07	232	Upper Corner Transition Tubes	900.00	0.90	PP	
24	07	401	Waterwall Suspension	7500.00	7.50	PP	
25	07	410	Downcomer Suspension	2500.00	2.50	PP	
26	07	420	Downcomer Guides	1500.00	1.50	PP	
27	07	431	Riser Tube Support	2000.00	2.00	PP	
28	07	601	Pressure Seals	500.00	0.50	PP	
29	07	992	Welding Consumables	100.00	0.10	PP	
			PG Weight				84.00

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 70

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

30	10	135	LTSH Inlet Header	2000.00	2.00	PP	
31	10	137	Final SH Inlet Header	2000.00	2.00	PP	
32	10	184	Rear steam cooled wall outlet header	2000.00	2.00	PP	
33	10	191	SH Radiant Roof Inlet Header	2000.00	2.00	PP	
34	10	235	LTSH Outlet Header	3000.00	3.00	PP	
35	10	237	Final SH Outlet Header	3000.00	3.00	PP	
36	10	240	Platen SH O/L Header	3000.00	3.00	PP	
37	10	258	Platen SH Outlet Header	3000.00	3.00	PP	
38	10	655	Hanger Platen SH Inlet Header	3000.00	3.00	PP	
			PG Weight				23.00
39	11	235	Loose Tubes for Platen SH	2000.00	2.00	PP	
40	11	236	Loose Tubes for Platen SH	10000.00	10.00	PP	
41	11	248	LTSH Coil Assembly	40000.00	40.00	PP	
42	11	249	LTSH loose tubes (Inlet & Outlet)	5000.00	5.00	PP	
43	11	250	Final SH Coil Assembly (Upper)	22000.00	22.00	PP	
44	11	251	Final SH Coil Assembly (Lower)	35000.00	35.00	PP	
45	11	252	Platen SH Loose tubes (Inlet & Outlet)	4000.00	4.00	PP	
46	11	255	SH Hanger Platen Coil Assembly	15000.00	15.00	PP	
47	11	271	Final SH Loose tubes (Inlet & Outlet)	4000.00	4.00	PP	
48	11	615	SH Rear Panel	3000.00	3.00	PP	
49	11	691	SH Radiant Wall Roof Panels	7000.00	7.00	PP	
			PG Weight				147.00
50	12	136	SH linkfrom SCW to LTSH	1200.00	1.20	PP	
51	12	147	Link from LTSH to Hanger Platen SH I/L H	2700.00	2.70	PP	
52	12	551	SH Horizontal Platen Hanger tubes	5500.00	5.50	PP	
53	12	803	SH Steam Cooled Spacer tubes	1000.00	1.00	PP	
54	12	850	Sat Links	4000.00	4.00	PP	
55	12	852	DESH Links	4000.00	4.00	PP	
56	12	900	SH DESH	1500.00	1.50	PP	
57	12	901	SH Hangers and supports (Headers)	4000.00	4.00	PP	
58	12	902	SH Hangers and supports (Links)	4000.00	4.00	PP	
59	12	903	SH Misc components	4000.00	4.00	PP	
60	12	992	Welding consumables	100.00	0.10	PP	
61	12	993	Erection materials	200.00	0.20	PP	
			PG Weight				32.20
62	18	001	Furnace roof skin casing	2000.00	2.00	PP	
63	18	010	PP Attachments in Furnace Roof Skin	1800.00	1.80	PP	

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

			Casi				
			PG Weight				3.80
64	19	105	Economiser coils	16000.00	16.00	PP	
65	19	115	Eco - III	26000.00	26.00	PP	
66	19	125	Eco - II	28000.00	28.00	PP	
67	19	194	Eco loose tubes (Inlet & Intermediate st	2000.00	2.00	PP	
68	19	701	Eco Inlet Header	2000.00	2.00	PP	
69	19	702	Eco Outlet Header	1400.00	1.40	PP	
70	19	753	Eco intermediate header (Rear)	2500.00	2.50	PP	
71	19	763	Eco intermediate header (Front)	2500.00	2.50	PP	
72	19	802	Eco Hanger Tubes	1500.00	1.50	PP	
73	19	850	Eco Feed pipe	1000.00	1.00	PP	
74	19	851	Eco Link to Drum	4000.00	4.00	PP	
75	19	901	Eco supports and suspensions (Headers)	3000.00	3.00	PP	
76	19	902	Eco supports and suspensions (Links)	3500.00	3.50	PP	
77	19	903	Eco Misc components	2000.00	2.00	PP	
			PG Weight				95.40
78	20	002	Long Retractable Soot Blower T30 Mk 1e	9372.00	9.37	PP	
79	20	004	Wall Box Non-Pressurised For Lrsb Mk-1	400.00	0.40	PP	
80	20	511	Da Head Valve Assy	85.00	0.09	PP	
81	20	988	Sdot Blower Commissioning Spare	7.00	0.01	PP	
82	20	998	Special Tools For Soot Blowers	8.00	0.01	PP	
			PG Weight				9.87
83	21	600	Soot Blower Piping And Fittings	5600.00	5.60	PP	
84	21	601	Sootblower Piping Supports	3800.00	3.80	PP	
85	21	700	Bulked Bps Components For Sb Piping	600.00	0.60	PP	
86	21	800	Sb Valves (Bhel)	250.00	0.25	PP	
87	21	825	Sb Valves (Sub Delivery)	200.00	0.20	PP	
88	21	850	Soot Blower Safety Valve (Bhel)	23.00	0.02	PP	
89	21	875	Silencer For Sb Safety Valve (Bhel)	400.00	0.40	PP	
90	21	987	Commg Spares For Sb Safety Valve	1.00	0.00	PP	
91	21	988	Commg Spares For Sub Deliveries	1.00	0.00	PP	
92	21	992	Welding Consumables	40.00	0.04	PP	
			PG Weight				10.92

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 72

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

93	24	200	Boiler Trim Piping And Fittings	23400.00	23.40	PP	
94	24	201	Supports For Trim Piping	5800.00	5.80	PP	
95	24	220	Safety Valve Esc Pipe&Drain - Rh Uty B	8500.00	8.50	PP	
96	24	225	Silencer Support-Safety Valves	14300.00	14.30	PP	
97	24	235	Slncr&Suprt-Starting Vent - Rh Uty Blr	1900.00	1.90	PP	
98	24	240	Sample Cooler And Supports	700.00	0.70	PP	
99	24	260	Valves (Bhel) Rh Uty Blr	6600.00	6.60	PP	
100	24	265	Valves & Fittings (Sd) Rh Uty Blr	1600.00	1.60	PP	
101	24	273	Direct Water Level Gauge - Bhel	280.00	0.28	PP	
102	24	275	Headers For Trim Piping	810.00	0.81	PP	
103	24	280	Erv And Safety Valves(Bhel)	2000.00	2.00	PP	
104	24	285	Safety Valve/Erv Silencers(Bhel)	27000.00	27.00	PP	
105	24	290	Startup vent Silencer	1000.00	1.00	PP	
106	24	350	Boiler Filling Piping	500.00	0.50	PP	
107	24	351	Hangers And Supports Of Blr Filling Pipe	250.00	0.25	PP	
108	24	700	Bulked Bps Components For Trim Pipes	300.00	0.30	PP	
109	24	955	Lapping Tools For Sv&Erv	85.00	0.09	PP	
110	24	960	Lapping Tools For Conventional Valves(	35.00	0.04	PP	
111	24	987	Commg Spares For Safety Valves/Erv	2.00	0.00	PP	
112	24	988	Commg Spares For Sub-Dely Valves	25.00	0.03	PP	
113	24	989	Commg Spares For Conventional Valves	6.00	0.01	PP	
			PG Weight				95.09
114	42	010	FF SKID - LO PUMPING	10000.00	10.00	PP	
115	42	045	FF SKID - DO PUMPING	500.00	0.50	PP	
116	42	065	FF SKID - DO TANK	500.00	0.50	PP	
117	42	072	FF SKID - LO_AIR CONTROL STATION	3000.00	3.00	PP	
118	42	076	FF SKID - FG_PG CONTROL STATION	4000.00	4.00	PP	
119	42	122	PIPING, PH - LO	2000.00	2.00	PP	
120	42	152	PIPING, OPRG FLOOR - LO	2000.00	2.00	PP	
121	42	154	PIPING, OPRG FLOOR - DO	500.00	0.50	PP	
122	42	155	PIPING, OPRG FLOOR - IGNITOR GAS	600.00	0.60	PP	
123	42	156	PIPING, OPRG FLOOR - FUEL GAS	18000.00	18.00	PP	

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 73

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

124	42	157	PIPING, OPRG FLOOR - ATM AIR	1500.00	1.50	PP	
125	42	270	SD - BURNER FLOOR SKIDS	3000.00	3.00	PP	
126			PG Weight				45.60
127	43	002	PIPING - SCANNER COOLING AIR SYSTEM	12000.00	12.00	PP	
			PG Weight				12.00
128	xx	xxx	Spry Cum Tray Dearator (Commn for UB 1 & UB 2)				
129			Heater (L 7850 x W 2550 x H 2850)	11800.00	11.80	PP	
130			Feed storage tank (Sec-I) (L 8750 x W 3700 x H 4300)	15800.00	15.80	PP	
131			Feed storage tank (Sec-II) (L 10000 x W 3700 x H 4300)	17200.00	17.20	PP	
132			Feed storage tank (Sec-III) (L 8750 x W 3700 x H 4300)	15800.00	15.80	PP	
133			Loose items (for Stand pipes, Platform etc)	5000.00	5.00	PP	
			PG Weight				65.60
134	81	003	CONTINUOUS BLOW DOWN EXPANDER-D1500 MM	2200.00	2.20	PP	
135	81	008	INTERMITTENT BLOW DOWN EXPANDER-D2000 MM	5000.00	5.00	PP	
136	81	128	HIGH PRESSURE DOSING SYSTEM	850.00	0.85	PP	
			PG Weight				8.05
			SUB TOTAL B (Pressure Parts)	925030.00	925.03		
C	Non Pressure Parts (Trichy Supply)				0.00		
1	07	993	Consumables & Erection Materials	1200.00	1.20	NPP	
			PG Weight				1.20
2	18	020	Vibration Snubbers	500.00	0.50	NPP	
			PG Weight				0.50
3	19	992	Welding consumables	100.00	0.10	NPP	
4	19	993	Erection materials	200.00	0.20	NPP	
			PG Weight				0.30
5	24	992	Welding Consumables	20.00	0.02	NPP	
6	24	993	Consumables & Erection Materials	7.00	0.01	NPP	
7	24	994	Name Plates	160.00	0.16	NPP	
			PG Weight				0.19
8	28	220	Doors	2500.00	2.50	NPP	
9	28	700	Fasteners	500.00	0.50	NPP	
			PG Weight				3.00

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 74

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

10	30	103	Seal Plate Assy	3000.00	3.00	NPP	
11	30	105	Furnace Bottom Enclosure Framing	2300.00	2.30	NPP	
12	30	215	Main Boiler	4200.00	4.20	NPP	
13	30	219	Vertical Roof Enclosure Framing	21000.00	21.00	NPP	
14	30	220	Deck Support And Seals	6200.00	6.20	NPP	
			PG Weight				36.70
15	31	010	Skin Casing Comps Welded To Pressure P	400.00	0.40	NPP	
16	31	301	Miscellaneous Casing	1000.00	1.00	NPP	
			PG Weight				1.40
17	32	993	Erection Materials	1500.00	1.50	NPP	
			PG Weight				1.50
18	41	350	AIR COOLED OIL GUN ASSY.	3150.00	3.15	NPP	
19	41	390	OIL GUN VICE AND RACK ASSY	300.00	0.30	NPP	
20	41	450	GAS IGNITORS	600.00	0.60	NPP	
21	41	998	COMM SPARES - BURNERS	50.00	0.05	NPP	
			PG Weight				4.10
22	42	700	BPS FASTENERS	300.00	0.30	NPP	
23	42	988	COMM SPARES - FF SKIDS	300.00	0.30	NPP	
			PG Weight				0.60
24	43	202	SD - SCANNER COOLING AIR SYSTEM	1000.00	1.00	NPP	
25	45	180	WIND BOX ASSY - 18 IN	5000.00	5.00	NPP	
26	45	181	WIND BOX ASSY - 18 IN	5000.00	5.00	NPP	
			PG Weight				11.00
27	48	012	DUCT FD FAN TO AH	29000.00	29.00	NPP	
28	48	013	DAMPER FD FAN TO AH	2100.00	2.10	NPP	
29	48	014	EXPJ JT FD FAN TO AH	500.00	0.50	NPP	
30	48	015	SUPPORT FD FAN TO AH	1450.00	1.45	NPP	
31	48	042	COMBUSTOR BOTTOM WIND BOX	6000.00	6.00	NPP	
32	48	202	DUCT AH TO COMBUSTOR	10700.00	10.70	NPP	
33	48	203	DAMPER AH TO COMBUSTOR	2500.00	2.50	NPP	
34	48	204	EXPJ JT AH TO COMBUSTOR	500.00	0.50	NPP	
35	48	205	SUPPORT AH TO COMBUSTOR	5350.00	5.35	NPP	
36	48	432	DUCT COMBUSTOR TO AH	25000.00	25.00	NPP	
37	48	433	DAMPER COMBUSTOR TO AH	2500.00	2.50	NPP	
38	48	434	EXPJ JT COMBUSTOR TO AH	500.00	0.50	NPP	
39	48	435	SUPPORT COMBUSTOR TO AH	1250.00	1.25	NPP	

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

40	48	442	DUCT AH TO CHIMNEY	34000.00	34.00	NPP	
41	48	443	DAMPER AH TO CHIMNEY	2500.00	2.50	NPP	
42	48	444	EXPJ JT AH TO CHIMNEY	500.00	0.50	NPP	
43	48	445	SUPPORT AH TO CHIMNEY	1700.00	1.70	NPP	
44	48	452	DUCT COMBUSTOR TO GR FAN	13000.00	13.00	NPP	
45	48	453	DAMPER COMBUSTOR TO GR FAN	1500.00	1.50	NPP	
46	48	454	EXPJ JT COMBUSTOR TO GR FAN	500.00	0.50	NPP	
47	48	455	SUPPORT COMBUSTOR TO GR FAN	650.00	0.65	NPP	
48	48	462	DUCT GR FAN TO COMBUSTOR	3000.00	3.00	NPP	
49	48	463	DAMPER GR FAN TO COMBUSTOR	1500.00	1.50	NPP	
50	48	464	EXPJ JT GR FAN TO COMBUSTOR	500.00	0.50	NPP	
51	48	465	SUPPORT GR FAN TO COMBUSTOR	300.00	0.30	NPP	
			PG Weight				147.00
			Gate & Dampers (Ranipet supply)				
52	57	013	DAMPERS BET FD FAN & APH	2000.00	2.00	NPP	
53	57	023	DAMPERS SEC. AIR INT	1750.00	1.75	NPP	
54	57	033	SA SCAPH INLET DAMPE	2000.00	2.00	NPP	
55	57	053	DAMPER GAS RECIRCLN	500.00	0.50	NPP	
56	57	063	SA SCAPH OUTLET DAMP	2000.00	2.00	NPP	
57	57	083	DAMPER COLD AIR FD F	2000.00	2.00	NPP	
58	57	293	DAMPER HOT SA FOR GA	600.00	0.60	NPP	
59	57	303	DAMPERS GR FAN SUCTI	1000.00	1.00	NPP	
60	57	313	DAMPERS GR SYSTEM OU	800.00	0.80	NPP	
61	57	323	DAMPERS FLOWGAS ECO	800.00	0.80	NPP	
62	57	577	ELECT ACTUATOR FOR G	3000.00	3.00	NPP	
63	57	988	DUCTS COMMISSIONING	50.00	0.05	NPP	
			PG Weight				16.50
64	81	415	TEST THERMOWELLS	50.00	0.05	NPP	
65	81	421	SENSING ELEMENTS FOR STEAM LINES	800.00	0.80	NPP	
			PG Weight				0.85
			SUB TOTAL C (Non Pressure Parts)	224837.00	224.84		
			Insulation				
1	32	010	Fixing Comp For Blr Pr Parts Insul	2800.00	2.80	INSU	
2	32	110	Fixing Comp For Blr Mountings Insul	1200.00	1.20	INSU	
3	32	120	Fixing Comp For Sb Pipes Insul	5000.00	5.00	INSU	

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

4	32	310	Fixing Comp For Air Ducts Insul	5500.00	5.50	INSU	
5	32	410	Fixing Comp For Ah And Gas Ducts Insul	5000.00	5.00	INSU	
6	32	510	Fixing Comp For Id Ducts Insul	6500.00	6.50	INSU	
7	32	710	Fixing Comp For Oil System Insul	1000.00	1.00	INSU	
			PG Weight				27.00
8	33	021	Blr Pr Parts Mineral Wool	3000.00	3.00	INSU	
9	33	121	Blr Mountings Mineral Wool	2500.00	2.50	INSU	
10	33	126	Sb Pipes Mineral Wool	1000.00	1.00	INSU	
11	33	201	Main Blr Formed Refractory Is8	1000.00	1.00	INSU	
12	33	212	Main Blr Castable Refractory Gr C	31000.00	31.00	INSU	
12	33	230	Main Blr Pourable Insulation	30000.00	30.00	INSU	
13	33	241	Main Blr Calcium Silicate	3500.00	3.50	INSU	
14	33	321	Air Ducts Mineral Wool	15000.00	15.00	INSU	
15	33	421	Air Heater And Gas Ducts Mineral Wool	15000.00	15.00	INSU	
16	33	521	Id Ducts Mineral Wool	5500.00	5.50	INSU	
17	33	721	Oil System Mineral Wool	2100.00	2.10	INSU	
18	33	924	Misc Eqpts Asbestos Materials	150.00	0.15	INSU	
19	33	970	Misc Eqpts Expanded Metal	1000.00	1.00	INSU	
20	33	975	Misc Eqpts Sealing Compound	100.00	0.10	INSU	
			PG Weight				110.85
21	37	010	Blr Outer Casing Components	3000.00	3.00	INSU	
22	37	810	Blr Outer Casing Aluminium-Ribbed	6000.00	6.00	INSU	
23	37	910	Blr Outer Casing Aluminium-Plain	9000.00	9.00	INSU	
			PG Weight				18.00
24	81	318	FIX COM FOR MISCELLANEOUS PPG INSULATION	800.00	0.80	INSU	
25	81	325	MINERAL WOOL MATTRESS	5000.00	5.00	INSU	
26	81	341	SEALING COMPOUND FOR INSL	80.00	0.08	INSU	
27	81	350	ALUMINIUM CLADDING FOR INSULATION	4000.00	4.00	INSU	
			PG Weight				9.88
	xx	xxx	CLADDING SHEET, INSULATION MATERIALS (HYDERABAD SUPPLY)- THIS SHOULD BE INCLUDING OF TG SIDE EQUIPMENTS, PIPING, and VALVE etc. TURBINE DRAIN PIPING, GLAND /SEAL STEAM PIPING & COMMON SYSTEM	6000.00	6.00	INSU	

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 77

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

			ETC WHICH WILL BE ERECTED BY OTHER TG ERECTION AGENCY OF RESPECTIVE UNITS.				
			SUB TOTAL D (Insulation)	171730.00	171.73		
E	Rotating Machines						
1	99	100	FAN HANDLING EQUIPMENTS	2000.00	2.00	R/M	
			PG Weight				2.00
	Air Pre Heater (Ranipet Supply)						
2	50	510	STEAM COIL A P H	4000.00	4.00	R/M	
			PG Weight				4.00
3	53	000	SPECIAL TOOLS/CONT	301.63	0.30	R/M	
4	53	010	RTYP AH-ROTOR ASSY	11250.00	11.25	R/M	
5	53	013	RTYP AH-ROTORSEALS	1059.61	1.06	R/M	
6	53	024	RTYP AH-BAS&ELE ASSY	12240.00	12.24	R/M	
7	53	025	RTYP AH-BAS&ELE ASSY	24805.00	24.81	R/M	
8	53	061	RTYP AH-CENTRE SECTN	7350.00	7.35	R/M	
9	53	062	RTYP AH-CENTRE SECTN	3863.56	3.86	R/M	
10	53	070	RTYP AH-HOUSINGSHELL	6612.17	6.61	R/M	
11	53	071	RTYP AH-PEDASTAL	423.18	0.42	R/M	
12	53	072	RTYP AH-PEDASTAL	447.80	0.45	R/M	
13	53	100	RTYP AH-ROTOR DRIVE	850.00	0.85	R/M	
14	53	211	RTYP AH-AIRSEAL PIPE	107.94	0.11	R/M	
15	53	220	RTYP AH-GENL DETAILS	6091.58	6.09	R/M	
16	53	261	RTYP AH-GUIDE BEARNG	437.15	0.44	R/M	
17	53	262	RTYP AH-SUPRT BEARNG	1090.36	1.09	R/M	
18	53	271	RTYP AH-OIL PIPING	304.36	0.30	R/M	
19	53	274	OIL CIRCULATION UNIT	137.79	0.14	R/M	
20	53	301	RTYP AH-WASH.MANIFLD	125.00	0.13	R/M	
21	53	302	RTYP AH-WASH.MANIFLD	110.00	0.11	R/M	
22	53	316	RTYP AH-CLEANG EQPT	610.00	0.61	R/M	
23	53	988	RTYP AH COMMG SPARE	100.00	0.10	R/M	
			PG Weight				78.32
	FAN (Ranipet Supply)						
24	56	000	TOOLS & FIXTURE/CONT	300.00	0.30	R/M	
25	56	011	FD FAN FOUNDATION MA	1000.00	1.00	R/M	
26	56	051	GR FDN MATERIAL	1150.00	1.15	R/M	
27	56	091	RAD FAN-FIRST FILL L	6000.00	6.00	R/M	

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

28	56	115	FDFAN BC1S2000-2500	13000.00	13.00	R/M	
29	56	154	BAC 1 SUC GR FAN	11000.00	11.00	R/M	
30	56	650	GR FAN MOTOR	3500.00	3.50	R/M	
31	56	710	STM TURBINE - FD FAN	3000.00	3.00	R/M	
32	56	750	STM TURBINE - GR FAN	2500.00	2.50	R/M	
33	56	810	RADL FDFAN COUPLING	500.00	0.50	R/M	
34	56	850	GR FAN RADL-COUPLING	300.00	0.30	R/M	
35	56	910	RAD FDFAN ACCESSORY	1500.00	1.50	R/M	
36	56	911	FD FAN SILENCER	23000.00	23.00	R/M	
37	56	915	FD/SA FAN CLUTCH/STM	2500.00	2.50	R/M	
38	56	950	GR FAN ACCESSORIES	1500.00	1.50	R/M	
39	56	955	GR FAN SLOW TURN MEC	2500.00	2.50	R/M	
							73.25
			IS-MOTOR SUPPLY				
40			FD Fan Motor	8500	8.5	R/M	
			SUB TOTAL E (Rotating Machines)	166067	166.07		
F	Piping (PC Chennai Supply)						
1	80	300	MS FROM SUPERHEATER TO BOILER STOP VALVE	4000	4.00	PPG	
2	80	342	AUX STEAM TO SCAPH	1500	1.50	PPG	
3	80	351	AUX STEAM TO UNLISTED USERS - SG SCOPE	10000	10.00	PPG	
4	80	364	CBD TANK VENT TO SYSTEM	200	0.20	PPG	
5	80	365	CBD TANK VENT/SV EXHAUST TO ATMOSPHERE	50	0.05	PPG	
6	80	366	IBD TANK VENT TO ATMOSPHERE	2000	2.00	PPG	
7	80	450	CBD AND EMERGENCY DRUM DRAIN	200	0.20	PPG	
8	80	451	BOILER INTEGRAL PIPING DRAINS	650	0.65	PPG	
9	80	453	LP PIPING DRAINS - SG SCOPE	1500	1.50	PPG	
10	80	454	SCAPH DRAINS	250	0.25	PPG	
11	80	460	SG AUX COOLING WATER UNIT SYSTEM	5000	5.00	PPG	
12	80	471	BOILER WATER WASH TO & FROM UNIT	2500	2.50	PPG	
13	80	600	HIGH PRESSURE DOSING PIPING	350	0.35	PPG	
14	80	612	SERVICE AIR FOR INDIVIDUAL UNITS	1800	1.80	PPG	
15	80	616	INSTRUMENT AIR FOR INDIVIDUAL	2200	2.20	PPG	

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 79

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

			UNIT				
16	80	901	SUB DELIVERY VALVES FOR LIGHT UP	1800	1.80	PPG	
17	80	920	H&S FOR HYDRO TEST	1500	1.50	PPG	
18	80	922	H&S FOR LIGHT UP - NON STEAM LINES	4000	4.00	PPG	
			SUB TOTAL F (Piping)	39500.00	39.50		
			GRAND TOTAL (A+B+C+D+E+F)	3058,664.00	3058.66	MT	

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

ESTIMATED WEIGHT OF VARIOUS PRODUCT GROUPS OF HRSG, CHIMNEY, POWER CYCLE & RE-GENERATIVE PIPING INSULATION WITH CLADDING MATERIALS FOR OPaL DAHEJ

SI No	PGMA	Description	Desn Wt, Kgs	Wt in MT	PKG
1) STRUCTURES					
1	35-010	BLR FNDN MATERIALS	16,330.711	16.331	STR
2	35-110	MAIN COLUMNS LEFT	42,000.792	42.001	STR
3	35-120	MAIN COLUMNS RIGHT	42,000.792	42.001	STR
4	35-131	INLET DUCT SUPPORTS	40,739.576	40.740	STR
5	35-140	AUXILIARY COLUMNS	5,261.612	5.262	STR
6	35-591	BOTTOM BRACING BEAM	7,675.760	7.676	STR
7	35-592	TOP BRACING BEAM	7,104.048	7.104	STR
8	35-593	BASE BEAMS	2,056.416	2.056	STR
9	35-594	STIFFENER BEAMS	14,558.700	14.559	STR
10	35-595	LATERAL SUPP BEAM FR	4,470.257	4.470	STR
11	35-596	LATERAL SUPP BEAM RR	5,760.449	5.760	STR
12	35-597	MODULE AND DRUM SUPPORT STRUCTURE	4,388.240	4.388	STR
13	35-220	PIPING SUPPORT - STRUCTURE	3,000.000	3.000	STR
14	35-540	COLUMN BRACINGS	6,000.000	6.000	STR
15	36-240	MAIN FLOOR 4TH LEVEL	4,000.000	4.000	STR
16	36-390	MISCELLANEOUS PLATFORMS	2,000.000	2.000	STR
17	36-820	STAIRS AND LADDERS	7,500.000	7.500	STR
18	37-810	OUTER CASING SHEET	2,900.000	2.900	STR
19	35-610	BOILER ROOF STRUCTUR	22,000.000	22.000	STR
20	35-611	BOILER ROOF SHEETING	3,000.000	3.000	STR
21	36-210	MAIN FLOOR 1ST LEVEL	8,000.000	8.000	STR
22	36-220	MAIN FLOOR 2 LEVEL	10,000.000	10.000	STR
23	36-230	MAIN FLOOR 3RD LEVEL	4,000.000	4.000	STR
24	36-250	MAIN FLOOR 5TH LEVEL	7,000.000	7.000	STR
25	36-810	FLOORGRILLS AND GUAGES	25,000.000	25.000	STR
26	36-850	HANDRAILS AND POSTS	12,000.000	12.000	STR
27	97-457	ANGLES AND CHANNELS	4,800.000	4.800	STR
		SUB TOTAL - 1 (STRUCTURE)	313,547.353	313.547	
2) PRESSURE PARTS INCL. HEAT TRANSFER MODULES					
01	04-116	BOILER DRUM WITH INTERNALS	50,528.282	50.528	PP
02	04-148	DRUM SLIDE BEARING PLATES	128.000	0.128	PP

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 81

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

03	04-158	FASTENERS FOR DRUM SADDLE	23.280	0.023	PP
4	HL-102	EVAPORATOR MODULE ASSY.- MIDDLE	37,536.985	37.537	PP
5	HL-103	EVAPORATOR MODULE ASSY.- REAR	18,711.344	18.711	PP
6	HL-201	LINKS FOR EVAP. MODULES- FRONT	928.720	0.929	PP
7	HL-203	LINKS FOR EVAP. MODULES- REAR	145.680	0.146	PP
8	07-504	DISC SPRING FOR MODULES SUPPORT	171.134	0.171	PP
9	07-505	EVAP. MODULE SUPPORTS-FRONT	316.748	0.317	PP
10	07-506	EVAP. MODULE SUPPORTS-MIDDLE	593.790	0.594	PP
11	07-507	EVAP. MODULE SUPPORTS-REAR	297.430	0.297	PP
12	07-993	ERECTION MATERIALS	296.464	0.296	PP
13	12-900	DESUPERHEATER	457.196	0.457	PP
14	19-852	ECO-I TO II INTERCONNECTING LINKS	242.225	0.242	PP
15	19-912	ECO MODULES SUPPORTS	292.312	0.292	PP
16	19-913	ECO MODULES SUPPORTS	511.512	0.512	PP
17	19-914	ECO MODULES SUPPORTS	216.873	0.217	PP
18	HL-151	ECONOMISER MODULES	15,020.736	15.021	PP
19	33-975	SEALING COMPONENTS	150.000	0.150	PP
20	HL-098	COLUMN-CASING BRIDGING COMPONENTS	10,850.000	10.850	PP
21	HL-101	EVAPORATOR MODULE ASSY.- FRONT	15,000.000	15.000	PP
22	HL-202	LINKS FOR EVAP. MODULES- MIDDLE	8,500.000	8.500	PP
23	HL-302	EVAPORATOR BAFFLES & SPACERS-MIDDLE	1,400.000	1.400	PP
24	HL-331	SUPERHEATER BAFFLES & SPACERS	1,300.000	1.300	PP
25	HL-351	ECO BAFFLES & SPACERS	1,500.000	1.500	PP
26	07-206	RISER PIPES	3,500.000	3.500	PP
27	07-210	RISER HEADERS & LINKS	2,000.000	2.000	PP
28	07-411	DOWNCOMER SUSPENSIONS	500.000	0.500	PP
29	07-992	IMPORTED ELECTRODES	25.000	0.025	PP
30	08-910	EXPANSION MOVEMENT MEASURING COMPONENT	100.000	0.100	PP
31	10-135	DESH INLET HEADER	500.000	0.500	PP
32	10-221	SH OUTLET HEADER	500.000	0.500	PP
33	10-235	DESH OUTLET HEADER	500.000	0.500	PP
34	12-850	SAT. STEAM CONNECTION LINKS	1,100.000	1.100	PP
35	12-852	DESH INLET AND OUTLET LINKS	3,300.000	3.300	PP
36	12-901	SUPPORTS FOR SAT. LINKS	750.000	0.750	PP
37	12-902	SUPPORTS FOR MS LINE	400.000	0.400	PP
38	12-912	SH MODULES SUPPORTS	1,100.000	1.100	PP
39	12-992	ELECTRODES	10.000	0.010	PP

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 82

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

40	12-993	ERECTION MATERIALS	400.000	0.400	PP
41	19-702	ECO. OUTLET HEADER	250.000	0.250	PP
42	19-850	ECONOMISER FEED PIPE	300.000	0.300	PP
43	19-851	ECONOMISER LINK TO DRUM	850.000	0.850	PP
44	19-901	SUPPORTS FOR ECO. INLET LINE	250.000	0.250	PP
45	19-902	ECO TO DRUM LINK SUPPORTS	250.000	0.250	PP
46	19-908	SUPPORTS FOR CPH LINKS	150.000	0.150	PP
47	19-911	WPH MODULE SUPPORTS	500.000	0.500	PP
48	19-992	ELECTRODES	5.000	0.005	PP
49	19-993	ERECTION MATERIALS	250.000	0.250	PP
50	24-400	HP Drains, vents & Fittings	10,000.000	10.000	PP
51	24-401	BLR Trim piping supports	2,400.000	2.400	PP
52	24-460	BHEL Valves	8,400.000	8.400	PP
53	24-465	SUB Delivery valves	3,000.000	3.000	PP
54	24-473	HP DWLG	420.000	0.420	PP
55	24-475	HP Drain headers	1,000.000	1.000	PP
56	24-480	HP Saafety valves	700.000	0.700	PP
57	24-485	HP Safety valve silencer supp	5,000.000	5.000	PP
58	24-490	HP Startup vent silencer	1,150.000	1.150	PP
59	24-955	Lapping tools for safety valves	42.000	0.042	PP
60	24-960	Lapping tools-Conv.valves	300.000	0.300	PP
61	24-992	Welding Consumables	50.000	0.050	PP
62	24-993	Erection materials	250.000	0.250	PP
63	97-401	LOCAL GAUGES	100.000	0.100	PP
64	HL-131	SUPERHEATER-II MODULES	14,900.000	14.900	PP
65	HL-132	SUPERHEATER-I MODULES	14,900.000	14.900	PP
66	HL-152	ECONOMISER MODULES	26,000.000	26.000	PP
67	HL-153	ECONOMISER MODULES	11,200.000	11.200	PP
68	HL-171	WPH MODULE ASSY.	11,200.000	11.200	PP
69	HL-231	SH-II MODULE CROSS OVER & LINKS	750.000	0.750	PP
70	HL-232	SH-I MODULE CROSS OVER & LINKS	950.000	0.950	PP
71	HL-251	LINKS FOR ECO MODULES	500.000	0.500	PP
72	HL-252	LINKS FOR ECO MODULES	500.000	0.500	PP
73	HL-253	LINKS FOR ECO MODULES	450.000	0.450	PP
74	HL-271	LINKS FOR WPH MODULES	350.000	0.350	PP
75	HL-303	EVAPORATOR BAFFLES & SPACERS-REAR	1,500.000	1.500	PP
76	HL-371	WPH BAFFLES & SPACERS	1,500.000	1.500	PP
77	HL-606	TOP & BOTTOM CASING S6 - S7	2,300.000	2.300	PP
		SUB TOTAL - 2 (PRESSURE PARTS)	302,420.711	302.421	

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 83

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

3) NON PRESSURE PARTS					
1	HL-501	SIDE CASING S1 - S2	4,300.000	4.300	NPP
2	HL-502	SIDE CASING S2-S3	3,850.000	3.850	NPP
3	HL-503	SIDE CASING S3 - S4	3,750.000	3.750	NPP
4	HL-504	SIDE CASING S4 - S5	3,450.000	3.450	NPP
5	HL-505	SIDE CASING S5 - S6	3,450.000	3.450	NPP
6	HL-506	SIDE CASING S6 - S7	3,450.000	3.450	NPP
7	HL-601	TOP & BOTTOM CASING S1 - S2	3,150.000	3.150	NPP
8	HL-602	TOP & BOTTOM CASING S2- S3	2,000.000	2.000	NPP
9	HL-603	TOP & BOTTOM CASING S3 - S4	2,050.000	2.050	NPP
10	HL-604	TOP & BOTTOM CASING S4 - S5	1,900.000	1.900	NPP
11	HL-605	TOP & BOTTOM CASING S5 - S6	2,300.000	2.300	NPP
12	24-420	HP Safety valve escape piping	6,900.000	6.900	NPP
13	24-425	HP Safety valve silencer supp	8,600.000	8.600	NPP
14	24-994	NAME PLATES	100.000	0.100	NPP
15	41-130	Duct Burner Assy	14,000.000	14.000	NPP
16	41-390	Oil gun vice & rack	200.000	0.200	NPP
17	41-450	Pipe type Gas Ignitor	750.000	0.750	NPP
18	41-988	Commissioning Spares	25.000	0.025	NPP
19	41-997	Mandatory Spares	300.000	0.300	NPP
20	42-001	Pneumatic fittings	100.000	0.100	NPP
21	42-002	Steam Blow materials	150.000	0.150	NPP
22	42-005	Instrument Fittings	200.000	0.200	NPP
23	42-072	Skid Assy - Burner Valves (LO_AIR)	1,000.000	1.000	NPP
24	42-076	Skid Assy - Burner Valves (FG_PG)	3,500.000	3.500	NPP
25	42-152	Operating Floor – LO	1,000.000	1.000	NPP
26	42-155	Operating Floor - FUEL GAS	3,000.000	3.000	NPP
27	42-156	Operating Floor - PILOT GAS	500.000	0.500	NPP
28	42-157	Operating Floor - Atm. Air	1,000.000	1.000	NPP
29	42-270	SD - FF SKIDS	1,000.000	1.000	NPP
30	42-988	Commissioning Spares	100.000	0.100	NPP
31	42-997	Mandatory Spares	200.000	0.200	NPP
32	43-002	Scanner Cooling Air Piping	1,200.000	1.200	NPP
33	43-003	Augmenting air piping	6,500.000	6.500	NPP
34	43-008	Seal Air Piping	3,000.000	3.000	NPP
35	43-202	SD - Scanner Air system	1,500.000	1.500	NPP
36	43-203	SD - Augmenting Air system	2,000.000	2.000	NPP
37	43-208	SD - Seal Air system	750.000	0.750	NPP
38	48-200	INSTRUMENT TAPPINGS	2,100.000	2.100	NPP
39	48-422	HRSG INLET DUCT	37,400.000	37.400	NPP

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 84

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

40	48-424	EXP. JOINT – INLET	500.000	0.500	NPP
41	48-452	DUCT BOILER OUTLET	4,000.000	4.000	NPP
42	48-454	EXP.PIECES – OUTLET	1,000.000	1.000	NPP
43	48-482	DISTRIBUTION GRID	1,400.000	1.400	NPP
44	48-700	BULKED BPS COMPONENTS	100.000	0.100	NPP
45	80-992	Welding Consumables	3.000	0.003	NPP
		SUB TOTAL - 3 (NON-PRESSURE PARTS)	137,728.000	137.728	
4) POWER CYCLE PIPING, REGENERATIVE CYCLE PIPING, TANKS AND VESSELS ETC					
1	12-851	MAIN STEAM LINE	3,000.000	3.000	PCP
2	19-101	WPH INLET LINE	350.000	0.350	PCP
3	19-102	WPH OUTLET LINE	300.000	0.300	PCP
4	80-145	BD tank exhausts & vents	3,600.000	3.600	PCP
5	80-219	HP Dosing system	4,000.000	4.000	PCP
6	80-273	BLOW DOWN SYSTEM VALVES	300.000	0.300	PCP
7	80-274	CBD tank safety valve	30.000	0.030	PCP
8	80-600	HP Dosing piping	300.000	0.300	PCP
9	81-005	IBD tank	3,000.000	3.000	PCP
10	81-411	BDT tubular level gauge	120.000	0.120	PCP
11	81-413	BDT control valve (SD)	240.000	0.240	PCP
12	81-011	CBD tank	2,000.000	2.000	PCP
		SUB TOTAL-4 (PCP, REGENERATIVE PPG, TANKS AND VESSELS)	17,240.000	17.240	
5) LINING & INSULATION					
1	32-010	CLADDING SHEET INLET DUCT	5,375.536	5.376	INSU
2	28-700	CLADDING SHEET FIXING PINS, NUTS& WASHER	5,900.000	5.900	INSU
3	32-020	CLADDING SHEET BURNER OUTLET DUCT	6,500.000	6.500	INSU
4	32-055	EXTERNAL INSULATION -PIPING	2,300.000	2.300	INSU
5	32-110	CLADDING SHEET - MODULE AREA	9,800.000	9.800	INSU
6	32-810	CLADDING SHEET - OUTLET DUCT	1,000.000	1.000	INSU
7	32-993	ERECTION MATERIALS	400.000	0.400	INSU
8	33-021	CERAMIC WOOL	33,500.000	33.500	INSU
9	33-621	MINERAL WOOL FOR PIPING	8,500.000	8.500	INSU
10	33-970	WIRE MESH	320.000	0.320	INSU
	xx-xxx	CLADDING SHEET, INSULATION MATERIALS (HYDERABAD SUPPLY)- THIS SHOULD BE INCLUDING OF TG SIDE EQUIPMENTS, PIPING, and VALVE etc. TURBINE DRAIN PIPING, GLAND /SEAL	6000.00	6.00	INSU

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 85

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

		STEAM PIPING & COMMON SYSTEM ETC WHICH WILL BE ERECTED BY OTHER TG ERECTION AGENCY OF RESPECTIVE UNITS.			
		SUB TOTAL - 5 (LINING & INSULATION)	79,595.536	79.596	
		GRAND TOTAL HRSG (Each Unit)		850.53	

ESTIMATED WEIGHT OF HRSG CHIMNEY FOR EACH UNIT (Ranipet Supply)

S. No.	PGMA	Description	Design Wt (MT)
1	87010	CHIMNEY FDN MATERIAL	6.0
2	87100	CHIMNEY SHELL	71.5
3	87150	CHIMNEY STRAKES	13.0
4	87200	PAINTER TROLLEY	1.0
5	87300	PLATFORMS & LADDERS	8.0
6	87930	AVIATION LAMPS	0.5
7	87950	CHIMNEY INSULATION	6.5
8	87960	CHIMN INS FIX COMP	3.0
		CHIMNEY TOTAL WEIGHT FOR EACH	109.5

Note: The OPAL-Dahej, HRSG chimney (ID-3.5m, Ht-40.0m) details are as follows for each HRSG Stack:

- Total no. of shell involved in one steel stack - 16nos, each 2.5m high.
- ID, OD & weight of bottom most shell and confirm whether it is supplied in single piece or two half - 3.5m, 3.556m, ~7.0MT. All the shells will be supplied in two halves.
- ID, OD & weight of Top most shell - 3.5m, 3.52m, ~3.0MT.
- Heaviest weight shell - bottom most shell ~ 7.0MT
- Chimney height/Elevation of top most shell - 40.0m

ESTIMATED WEIGHT OF IBR PIPING IN SCOPE OF WORK (PC CHENNAI SUPPLY) for Each Block:

SL NO	PGMA	DESCRIPTION	WT In (kgs)	Wt In (MT)	IBR	ACTIVITY
-------	------	-------------	-------------	------------	-----	----------

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

1	80130	VHP STEAM SYSTEM	225,000.00	225.00	I	LU
2	80131	HP STEAM SYSTEM	35,000.00	35.00	I	LU
3	80132	MP STEAM SYSTEM	12,500.00	12.50	I	LU
4	80133	LP STEAM SYSTEM	55,000.00	55.00	I	LU
5	80134	EXTRACTION STEAM SYSTEM	15,000.00	15.00	I	LU
6	80135	BFP DISCHARGE - UB SYSTEM	42,500.00	42.50	I	LU
7	80136	BFP DISCHARGE - HRSG SYSTEM	60,000.00	60.00	I	LU
8	80137	SPRAY WATER SYSTEM	1,250.00	1.25	I	LU
9	80149	MISC.EXHAUSTS & VENTS	1,250.00	1.25	I	LU
10	80452	HP PIPING DRAINS - SG SCOPE	2,500.00	2.50	I	LU
11	80453	LP PIPING DRAINS - SG SCOPE	1,250.00	1.25	I	LU
12	80992	IMPORTED ELECTRODES	250.00	0.25	N	HT
TOTAL IBR PIPING (MT)				452		
TOTAL IBR PIPING (MT) (considering margin) for Each block				485		

FOR ABOVE MENTION IBR PIPING- LINE SIZE, LENGTH PIPE OD/TH DETAILS OF CARBON STEEL AND ALLOY STEEL:

S.NO.	LINE SIZE	LENGTH in m	Sch/Thk	PIPE ODxTHK IN mm	WEIGHT (kg)
A . IBR PIPING - CARBON STEEL					
A1. PIPES					
1	1"	900	XS	33.4x4.5	1458
2	1.5"	240	XS	48.3x5.08	649
3	2"	100	XS	60.3x5.54	374
4	6"	250	XS	168.3x14.27	6775
5	8"	190	XS	219.1x12.7	6141
6	10"	60	STD	273x9.30	1809
7	12"	175	STD	323.8x9.53	6464
8	14"	300	STD	355.6x9.53	12199
9	3"	765	STD	88.9x5.49	4319
10	4"	190	STD	114.3x6.02	1527

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 87

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

11	3/4"	300	S160	26.7X5.56	435
12	6"	275	STD	168.3x7.11	3886
13	8"	400	STD	219.1x8.18	8509
14	12"	50	25	323.9x25	2725
15	14"	40	S60	355.6x12.7	2148
16	1.5"	100	S160	48.3X5.08	271
17	2"	75	S160	60.3X11.07	504
18	4"	135	S160	114.3X13.49	2261
19	6"	470	21.95	168.3x21.95	18615
20	10"	390	9.27	273X9.27	11755
21	14"	250	36	355.6X36	35465
22	3/4"	100	S160	26.7X5.6	144
23	16"	25	XS	406.4x12.7	1537
24	20"	105	XS	508x12.7	8137
26	16"	55	STD	406.4x9.53	2566
27	18"	50	STD	457.2x12.7	3480
29	24"	115	STD	610x14.27	12053
30	28"	80	STD	711.2x9.53	6595
33	16"	20	17	406.4x17	1632
34	10"	30	12.7	273X12.7	1223
35	12"	50	10.31	323.9X10.31	1993
36	20"	35	25	508X25	5211
37	20"	15	9.53	508X9.53	878
SUB TOTAL A1- CS PIPING					173738
A2. WEIGHT OF VALVES, FLANGES WITH FITTINGS					45000
TOTAL CARBON STEEL PIPING (A1+A2)					218738
B . IBR PIPING - ALLOY STEEL					
B1. PIPES					
1	1"	150	XXS	33.4X9.09	408
2	3/4"	160	XXS	26.7X7.82	291
3	1.5"	120	XXS	48.3X10.15	573
4	12"	650	35.08	323.9X35.08	81201
5	8"	140	32	219.1X32	10335
6	4"	55	22	114.3X22	1650
7	6"	55	27.5	168.3X27.5	2625
8	24"	35	73.7	610X73.7	14875
9	3"	30	20	88.9X20	435
10	2"	50	12.5	60.3X12.5	368
11	12"	25	14.27	323.8X14.27	1361
12	16"	375	55	406.4X55	89362
13	12"	30	9.53	323.9X9.53	1108
14	4"	20	6.02	114.3X6.02	160
15	8"	25	36	219.1X36	2032

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 88

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

SUB TOTAL B2- AS PIPING	206784
B2. WEIGHT OF VALVES, FLANGES, WITH FITTINGS AND STEAM TRAPS	60000
TOTAL ALLOY STEEL PIPING (B1+B2)	266784
TOTAL IBR PIPING (KG)	485522
TOTAL IBR PIPING (MT) for each Block	485.522

Note:

All Pipes, Flanges & Fittings are supplied by Piping Centre, Chennai
Valves are supplied by BHEL-Tiruchy or Other manufacturers.

ESTIMATED WEIGHT OF NON- IBR PIPING IN SCOPE OF WORK (EMRP SUPPLY) for Each Block

NON-IBR PIPING LINE WT AND DIMENSION DETAILS

S.NO	LINE SIZE	LENGT H in m	Sch/Th k	PIPE ODxTHK IN mm	WEIGHT (kg)	SYSTEM
A . NON-IBR PIPING - CARBON STEEL						
A1 PIPES						
A1.1 CARBON STEEL PIPES (SEAMLESS)						
1	1/2"	204	SCH 160	21.3X4.8	66.3	CONDENSATE & FEED WATER PIPING
2	3/4"	414	SCH 160	26.7X5.6	199.41	CONDENSATE & FEED WATER PIPING
3	1"	3438	SCH XS	33.4X4.5	1850.79	CONDENSATE & FEED WATER PIPING
4	1 1/2"	402	SCH XS	48.3X5.1	361.8	CONDENSATE & FEED WATER PIPING
5	2"	8130	SCH XS	60.3X5.5	10121.85	CONDENSATE & FEED WATER PIPING
6	3"	11358	STD	88.9X5.5	21390.9	CONDENSATE & FEED WATER PIPING
7	4"	7332	STD	114.3X6.0	19674.2	CONDENSATE & FEED WATER PIPING
8	6"	3096	STD	168.3X7.1	14551.2	CONDENSATE & FEED WATER PIPING
9	8"	1836	STD	219.1X8.2	13005	CONDENSATE & FEED WATER PIPING
10	10"	714	STD	273.0X9.3	7163.8	CONDENSATE & FEED WATER PIPING
11	12"	960	STD	323.8X9.5	11808	CONDENSATE & FEED

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 89

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

						WATER PIPING
12	14"	288	STD	355.6X9.5	3897.6	CONDENSATE & FEED WATER PIPING
A1.2 CARBON STEEL PIPES (WELDED)						
1	16"	394	STD	406.4X9.5	6126.7	CONDENSATE & FEED WATER PIPING
2	18"	546	STD	457.2X9.5	9555	CONDENSATE & FEED WATER PIPING
3	24"	102	STD	609.6X9.5	2397	CONDENSATE & FEED WATER PIPING
A1.3 CARBON STEEL PIPES (IS1239- BLACK)						
1	3/4"	102	HEAVY	26.7X3.25	32.3	COOLING WATER
2	1"	3096	HEAVY	33.4X4.05	1532.52	COOLING WATER
3	2"	3072	HEAVY	60.3X4.47	3159.04	COOLING WATER
4	3"	1194	HEAVY	88.9X4.85	2009.9	COOLING WATER
5	4"	1254	HEAVY	114.3X5.40	3009.6	COOLING WATER
6	6"	1176	HEAVY	168.3X5.40	4155.2	COOLING WATER
A1.4 CARBON STEEL PIPES (IS 3589)						
1	8"	1128	6.0 MM	219.1X6.0	5927.64	COOLING WATER
2	10"	1134	6.0 MM	273.1X6.0	7465.5	COOLING WATER
3	12"	732	6.0 MM	323.9X6.0	5736.44	COOLING WATER
4	16"	402	8.0 MM	406.4X8.0	5220.64	COOLING WATER
5	20"	112	10.0 MM	508.0X10.0	2184	COOLING WATER
6	20"	200	10.0 MM	508.0X10.0	3900	COOLING WATER
7	24"	606	10.0 MM	609.6X10.0	14251.1	COOLING WATER
8	30"	420	12 MM	762.0X12	9429	COOLING WATER
9	54"	96	14 MM	1372X14	7499.2	COOLING WATER
10	70"	114	18 MM	1778X18	14842.8	COOLING WATER
A1.5 GALVANIZED IRON PIPES (IS 1239 GALV)						
1	1"	4056	HEAVY	33.4X4.05	2007.72	PLANT AIR & INSTRUMENT AIR
2	1 1/2"	36	HEAVY	48.3X4.05	26.58	PLANT AIR & INSTRUMENT AIR
3	4"	480	HEAVY	114.3X5.40	1152	PLANT AIR & INSTRUMENT AIR
Sub Total (A-1.1+1.2+1.3+1.4+1.5)					215710.73	
A2. MITRE BENDS AND REDUCERS TO BE MADE AT SITE BY ERECTION AGENCY, WEIGHT OF VALVES, FLANGES WITH FITTINGS					50000	PLANT AIR & INSTRUMENT AIR, COOLING WATER
TOTAL CARBON STEEL PIPING					265710.73	

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 90

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

B. NON-IBR PIPING - STAINLESS STEEL						
B1 PIPES						
B1.1 STAINLESS STEEL PIPES (SEAMLESS)						
1	1"	984	SCH 40S	33.4X3.38	410	HSD&NAPTHA
2	2"	492	SCH 40S	60.3X3.9	442.8	DM WATER
3	3"	630	SCH 10S	88.9X3.05	677.25	HSD&NAPTHA
4	6"	456	SCH 10S	168.3X3.40	1051.84	NATURAL GAS
5	8"	480	SCH 10S	219.1X3.76	1596.8	CONDENSATE & FEED WATER SUCTION PIPING
B1.2 STAINLESS STEEL PIPES (WELDED)						
1	16"	114	SCH 10S	406.4X4.78	898.51	DM WATER
Sub Total (B1.1+B1.2)					5077.2	
B2. WEIGHT OF VALVES, FLANGES WITH FITTINGS					1250	
TOTAL STAINLESS STEEL PIPING (B1+B2)					6327.2	
Pipe Hanger Assemblies					2,500	
Structural Steel for Pipe Supports					20,833	
TOTAL NON-IBR PIPING (Kg)					295370.93	
TOTAL NON-IBR PIPING (MT) (considering margin) For each Block					300.00	

Note:

- 1) All Pipes are supplied in Single commercial lengths, with edge preparation by EMRP.
- 2) Cutting into required spool lengths, edge preparation of spools, welding of Stubs & support attachments are to be done at Site by Erection Agency.
- 3) Miter Bends, Reducers in Cooling Water Piping are to be fabricated at Site by Erection Agency using the pipe supplied by EMRP.
- 4) Buried Piping in CW system; Coal tar tape to be arranged by Erection Agency & wrapped on pipe before burying as per Customer requirement.
- 5) Cathodic protection as per OPaL/EIL's specification is required for all underground piping; PE&SD will supply the material required, Erection Agency to provide lugs on pipe.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

- 6) Supports to be fabricated at Site from structural steel supplied by PE&SD
- 7) All dummy flange/plates for Hydro test for the piping system included in this Tender specification are to be arranged by Contractor as part of scope of work.

Thermal Insulation Material for B.O.P. Piping: For each Block

S. No.	Item Description	Weight (Kg)	Remark
1	Thermal Insulation Material for B.O.P. Piping		
a	Mineralwool Mattress	11,200	
b	Cladding Material - Aluminium sheet	20,000	
c	Ancilliary Material	15,000	
	Total(a+b+c)	46200	
	Total considering margin	50000	
	Total (MT)	50	MT
Note:	Thermal Insulation Material for B.O.P. Piping is supplied by PE&SD; Application to be done by Erection Agency		

SUMMARY OF TENTATIVE WEIGHT OF SYSTEMS/EQUIPMENTS INVOLVED IN ERECTION, TESTING & COMMISSIONING SCOPE FOR Block I :

S.N.	Package/Equipments	Weight (Kg)	Approx. WT.(MT)
A	Utility Boiler Unit # 1 with associated Equipment & Aux. :		
1	Structure	1,531,500.00	1,531.50
2	Pressure Part	925,030.00	925.03
3	Non Pressure Part	224,837.00	224.84
4	Insulation	171,730.00	171.73
5	Rotating Machines (Inc. FD Fan motor IS supply)	166,067.00	166.07
6	UB Piping (PC Chennai Supply)	39,500.00	39.50
	Sub Total A	3,058,664.00	3,058.66
B	HRSG Unit # 2 with associated Equipments & Aux. :		
1	Structure	313,547.35	313.55
2	Pressure Parts including Heat Transfer Modules	302,420.71	302.42
3	Non Pressure Part	137,728.00	137.73
4	Power Cycle Piping, Regenerative Cycle piping, Tanks and Vassels etc.	17,240.00	17.24

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 92

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

5	Lining & Insulation	79,595.54	79.60
	Sub Total B	850,531.60	850.53
C	HRSB Unit # 4 with associated Equipments & Aux. :		
1	Structure	315,000.00	315.00
2	Pressure Parts including Heat Transfer Modules	305,000.00	305.00
3	Non Pressure Part	138,000.00	138.00
4	Power Cycle Piping, Regenerative Cycle piping, Tanks and Vassels etc.	17,000.00	17.00
5	Lining & Insulation	81,000.00	81.00
	Sub Total C	856,000.00	856.00
D	HRSB Chimney/Steel Stack for Unit 2 & 4	219,000.00	219.00
	Sub Total D	219,000.00	219.00
F	IBR Piping (PC Chennai supply)		
1	Carbon Steel Piping with fittings	218,738.00	218.74
2	Alloy Steel Piping with fittings	266,784.00	266.78
	Sub Total F	485,522.00	485.52
G	Non-IBR Piping (EMRP Mumbai supply)		
1	Carbon Steel Piping with fittings	265,710.33	265.71
2	stainless Steel Piping with fittings	6,327.20	6.33
3	Pipe Hanger Assemblies	2,500.00	2.50
4	Structural Steel for Pipe Supports	20,833.00	20.83
	Sub Total G	295,370.53	295.37
	Sub Total G (With Margin)	300,000.00	300.00
H	Thermal Insulation Material for B.O.P. Piping		
1	Mineralwool Mattress	11,200.00	11.20
2	Cladding Material - Aluminium sheet	20,000.00	20.00
3	Ancilliary Material	15,000.00	15.00
	SubTotal H (considering margin)	50,000.00	50.00
	Grand Total (A+B+D+E+F+G+H)	5,819,717.60	5,819.72

SUMMARY OF TENTATIVE WEIGHT OF SYSTEMS/EQUIPMENTS INVOLVED IN

ERECTION, TESTING & COMMISSIONING SCOPE FOR Block II :

S.N.	Package/Equipments	Weight (Kg)	Approx. WT.(MT)
A	Utility Boiler Unit # 2 with associated Equipment & Aux. :		

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 93

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

1	Structure	1,531,500.00	1,531.50
2	Pressure Part	925,030.00	925.03
3	Non Pressure Part	224,837.00	224.84
4	Insulation	171,730.00	171.73
5	Rotating Machines (Inc. FD Fan motor IS supply)	166,067.00	166.07
6	UB Piping (PC Chennai Supply)	39,500.00	39.50
	Sub Total A	3,058,664.00	3,058.66
B	HRSG Unit # 1 with associated Equipments & Aux. :		
1	Structure	313,547.35	313.55
2	Pressure Parts including Heat Transfer Modules	302,420.71	302.42
3	Non Pressure Part	137,728.00	137.73
4	Power Cycle Piping, Regenerative Cycle piping, Tanks and Vassels etc.	17,240.00	17.24
5	Lining & Insulation	79,595.54	79.60
	Sub Total B	850,531.60	850.53
C	HRSG Unit # 3 with associated Equipments & Aux. :		
1	Structure	315,000.00	315.00
2	Pressure Parts including Heat Transfer Modules	305,000.00	305.00
3	Non Pressure Part	138,000.00	138.00
4	Power Cycle Piping, Regenerative Cycle piping, Tanks and Vassels etc.	17,000.00	17.00
5	Lining & Insulation	81,000.00	81.00
	Sub Total C	856,000.00	856.00
D	HRSG Chimney/Steel Stack for Unit 1 & 3	219,000.00	219.00
	Sub Total D	219,000.00	219.00
F	IBR Piping (PC Chennai supply)		
1	Carbon Steel Piping with fittings	218,738.00	218.74
2	Alloy Steel Piping with fittings	266,784.00	266.78
	Sub Total F	485,522.00	485.52
G	Non-IBR Piping (EMRP Mumbai supply)		
1	Carbon Steel Piping with fittings	265,710.33	265.71
2	stainless Steel Piping with fittings	6,327.20	6.33
3	Pipe Hanger Assemblies	2,500.00	2.50
4	Structural Steel for Pipe Supports	20,833.00	20.83
	Sub Total G	295,370.53	295.37
	Sub Total G (With Margin)	300,000.00	300.00
H	Thermal Insulation Material for B.O.P. Piping		
1	Mineralwool Mattress	11,200.00	11.20

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Annexure-I ESTIMATED WEIGHT FOR VARIOUS SYSTEMS IN SCOPE OF WORK

2	Cladding Material - Aluminium sheet	20,000.00	20.00
3	Ancilliary Material	15,000.00	15.00
	SubTotal H (considering margin)	50,000.00	50.00
	Grand Total (A+B+D+E+F+G+H)	5,819,717.60	5,819.72

NOTES:

1. Besides product groups indicated herein, there is likelihood of addition of new product groups by BHEL' s unit for release of some items, integral to this work. Tenderers' quoted unit rates shall be applicable for such product groups also.
2. The weights given against PGMA's listed above are tentative. It may change after detailed engineering is done. Rate quoted by the Contractor shall not change due to variation in weight.
3. Rate Schedule Identified for PGMA's of Piping and Insulation are Indicative only and based on envisaged material specification. Payment shall be made on the basis of material specification of actual material received and erected at site.
4. BHEL's decision with regard to classification of a particular product group for applicable rate category shall be final & binding on the Contractor.
5. Besides the above, weight of all temporary piping, valves, pumps, tanks and other miscellaneous equipments etc for carrying out hydraulic test, chemical cleaning, steam blowing and other tests, as stated elsewhere will get added.
6. Electrical & C&I items of handling system is excluded from the scope of work.

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-II LIST OF IBR WELD JOINTS

Shall be issued during Execution

TECHNICAL CONDITIONS OF CONTRACT (TCC)
Annexure-III PAINTING SCHEME

PAINTING SCHEME: Applicable for each Block

PAINTING SCHEME AS PER OPaL/EIL SPECIFICATION FOR SHOP & FIELD
PAINTING **SECTION C: 4.9, SPECIFICATION No. 6987-0642-PT-F09 Rev 0**
(Uploaded as File titled Painting Scheme – 966-967)

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-I GENERAL

GENERAL REQUIREMENTS – COMMON TO ALL WORK

11.1

The intent of specification is to provide services according to the most modern and proven techniques and codes. The omission of specific reference to any method, equipment or material necessary for proper and efficient execution of this work shall not relieve the Contractor of the responsibility of providing such facilities to complete the work without any extra compensation.

11.2

The terminal points decided by BHEL shall be final and binding on the Contractor for deciding the scope of work and effecting payment for the work done.

11.3

The work shall be executed under the usual conditions affecting major power plant construction and in conjunction with numerous other operations at site. The Contractor and his personnel shall cooperate with personnel of BHEL, BHEL'S Customer, Customer's consultants and other Contractors, coordinating his work with others and proceed in a manner that shall not delay or hinder the progress of work of the project as a whole.

11.4

The work covered under this specification is of highly sophisticated nature, requiring the best quality workmanship, supervision, engineering and construction management. The Contractor should ensure proper planning and successful & timely completion of the work to meet the overall project schedule. The Contractor must deploy adequate quantity of tools & plants, modern / latest construction aids etc. He must also deploy adequate trained, qualified and experienced supervisory staff and skilled personnel.

11.5

Contractor shall erect and commission all the equipments and auxiliaries as per the sequence & methodology prescribed by BHEL depending upon the technical requirements. Availability of materials and fronts will decide this. BHEL Engineer's decision regarding correctness of the work and method of working shall be final and binding on the Contractor. No claims for extra payment from the Contractor will be entertained on the ground of deviation from the methods / sequence adopted in erection of similar sets elsewhere.

11.6

All necessary certificates and licenses, permits & clearances required to carry out this work from the respective statutory/ local authorities are to be arranged by the Contractor at his cost in time to ensure smooth progress of work.

11.7

The boiler shall be erected as per relevant provisions of latest Indian Boiler Regulations (IBR) and amendments/addendums thereof, if any.

11.8

The work shall conform to dimensions and tolerances specified in the various drawings / documents that will be provided during various stages of erection. If any portion of work is found to be defective in workmanship, not conforming to drawings or other stipulations due to Contractor's

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-I GENERAL

fault, the Contractor shall dismantle and re-do the work duly replacing the defective materials at his cost, failing which the work will be got done by BHEL and recoveries will be effected from the Contractor's bills towards expenditure incurred including cost of materials and departmental overheads of BHEL.

11.9

The Contractor shall perform any services, tests etc, which may not be specified but nevertheless, required for the completion of work within quoted rates.

11.10

All necessary certificates and licenses required for carrying out this work are to be arranged by the Contractor expeditiously.

11.11

The Contractor shall execute the work in the most substantial and workman like manner. The stores shall be handled with care and diligence.

11.12

BHEL reserves right to recover from the Contractor any loss which arises out of undue delay / discrepancy / shortage / damage or any other causes due to Contractor's lapse during any stage of work. Any loss to BHEL due to Contractor's lapse shall have to be made good by the Contractor.

11.13

All cranes, transport equipment, handling equipment, tools, tackles, fixtures, equipment, manpower, supervisors/engineers, consumables etc, except otherwise specified as BHEL scope of free issue, required for this scope of work shall be provided by the Contractor. All expenditure including taxes and incidentals in this connection will have to be borne by Contractor unless otherwise specified in the relevant clauses. The Contractor's quoted rates should be inclusive of all such contingencies.

11.14

During the course of erection, testing and commissioning certain rework / modification / rectification / repair / fabrication etc may become necessary on account of feed back / revision of drawing etc. This will also include modifications / re-works suggested by BHEL / customer / other inspection group. Contractor shall carry out such rework / modification / rectification / fabrication / repair etc promptly and expeditiously. Daily log sheets signed by BHEL engineer and indicating the details of work carried out, man-hours etc shall be maintained by the Contractor for such reworks. Claim of Contractor if any, for such works will be governed by relevant clauses of 'General Conditions of Contract'.

11.15

All works such as cleaning, leveling, aligning, trial assembly, dismantling of certain equipments / components for checking and cleaning, surface preparation, fabrication of structures, tubes and pipes as per general engineering practice and as per BHEL Engineer's instructions at site, cutting, gouging, weld depositing, grinding, straightening, chamfering, filing, chipping, drilling, reaming, scrapping, lapping, fitting up etc as may be applicable in such erection works and which are

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-I GENERAL

treated incidental to the erection works and necessary to complete the work satisfactorily, shall be carried out by the Contractor as part of the work within the quoted rates.

11.16

The Contractor shall make all fixtures, temporary supports, steel structures required for jigs & fixtures, anchors for load and guide pulleys required for the work. Contractor shall arrange necessary steel for such usage. Only the steel for making temporary structure (cat head) for drum lifting will be provided by BHEL in random sizes materials available at site.

11.17

The Contractor shall take delivery of the components, equipments, chemicals, and lubricants etc from the BHEL stores/ storage area after getting the approval of BHEL Engineer on standard indent forms of BHEL. Complete and detailed account of the materials and equipments after usage shall be submitted to the BHEL and reconciled periodically.

11.18

Contractor shall plan and transport equipments, components from storage to erection site and erect them in such a manner and sequence that material accumulation at site does not lead to congestion at site of work. Materials shall be stacked neatly, preserved and stored in the Contractor's shed and at work areas in an orderly manner. In case it is necessary to shift and re-stack the materials kept at work areas/ site to enable other agencies to carry out their work or for any other reason, same shall be done by Contractor most expeditiously as incidental to work.

11.19

Plant materials should not be used for any temporary supports / scaffolding/ preparing pre-assembly bed etc.

11.20

The details of equipments to be erected under this contract are generally as per the schedule given in relevant appendices. These details are approximate and meant only to give a general idea to the tenderer about the magnitude of the work involved. Actual quantum and type of equipments will be based on the relevant erection documents which will be furnished to the Contractor in due course of erection and the weight and quantity as per the relevant engineering documents will only be admissible for the billing purpose.

11.21

Hangers & suspensions, supports etc for tubes, piping, & ducts etc will be supplied in running / random lengths / sizes which shall be cut to suitable sizes and adjusted as required.

11.22

Spring suspension / constant load hangers may have to be pre-assembled for required load and erection carried out as per instructions of BHEL. Adjustments, removal of temporary arrests/locks, cutting of excess thread length of hanger tie-rod etc have to be carried out as and when required. Load setting of spring hangers, as per BHEL's documents/instructions, during various stages of erection & testing and after floating of piping/ducting during cold and hot condition will have to be done as part of work. This exercise may have to be repeated till satisfactory results are achieved.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-I GENERAL

11.23

Contractor shall lay/install the field-routed/small-bore pipelines to suit site condition/requirement. Before laying/installing such pipelines, the contractor shall prepare necessary sketch for routing these pipe lines and get the same approved by BHEL. Contractor must take care of the location/layout of other systems and equipment before preparing such sketch to avoid interference. There is a possibility of minor change in routing such pipelines even after completion of erection; contractor shall carry out the same without any extra cost to BHEL.

11.24

Welding of necessary instrumentation tapping points, thermowell, thermocouple pad, metal temp pad and clamps, root valve including reducer (to suit Control & Instrumentation Impulse Piping requirements), condensing vessel, flow metering & measurement devices, and control valves to be provided on boiler & its auxiliaries and piping are covered within the scope of this specification. The installation of all the above items will be Contractor's responsibility even if:

- a) Items are not specifically indicated under the respective product groups as given in the technical specifications.
- b) Items are supplied by an agency other than BHEL.

Pre-heating, NDE, and Post weld heat treatment for above shall be done as per the specifications as part of work.

11.25

Certain instrumentation like pressure switches, air sets, filters, regulators, pressure gauges, junction boxes, power cylinders, dial thermometers, flow meters, valve actuators, flow indicators, centrifugal/speed switches of motors, accumulators etc are received in assembled condition as integral part of equipments. Contractor shall dismount such instruments for calibration and hand over the same to BHEL. C & I erection agency will do storage / re-erection calibration etc.

11.26

Fixing and seal welding of thermowells & plugs before Hydro test/ steam blowing of equipment or other piping system is within the scope of work. Contractor shall also remove the seal welded plugs by process of grinding and fix and seal weld thermowells after hydro test/steam blowing of lines as part of work.

11.27

Actuators/drives of valves, dampers, gates, powered vanes etc may have to be serviced, lubricated, before erection, during pre-commissioning & commissioning, including carrying out minor adjustments required as incidental to the work.

11.28

All electrical motors have to be tested for IR & PI values prior to the trial run. Where required, dry out may have to be carried out by using external heating source. Contractor shall make all arrangements in this regard and complete the work as instructed. BHEL will provide the motorized insulation testers.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-I GENERAL

11.29

In installation of various equipments it may become necessary to install these on temporary supports/ hanger due to various reasons including non-availability of suspension materials. Contractor shall install such temporary suspensions/hangers and later on shift the relevant equipments to their respective permanent hangers/ suspensions/ supports as incidental to work. Requisite materials for such temporary arrangements will be provided by BHEL on free -returnable basis which shall be returned to BHEL after the use.

11.30

The work shall be carried out strictly in accordance to the "Field Quality Plan" approved by BHEL/client. Contractor, jointly with BHEL, shall prepare all necessary records of measurements/readings/ protocols etc.

11.31

All works such as cleaning, levelling, aligning, trial assembly, dismantling of certain equipments / components for checking and cleaning, surface preparation, fabrication of sheets, tubes and pipes as per the general engineering practice and as per BHEL engineers instructions at site, cutting, weld desposing, grinding, straightening, chamfering, filing, chipping, drilling, reaming, scraping, lapping, fitting up etc as may be applicable in such erection works and which are treated incidental to the erection work and necessary to complete the work satisfactorily shall be carried out by the Contractor as part of the work.

11.32

Interconnection/ hookup, if any, with the existing system shall form part of work. Such interconnections, hookups may require shut down of running plant and the relevant work have to be completed within such planned shutdowns. This may call for working with enhanced resources and on extended hours. Contractor's offer shall cover all such contingencies.

11.33

Contractor shall regulate flow of material to and from site in such a manner and sequence that material accumulation at site does not lead to congestion at site. In case it is necessary to shift and restack the materials kept at work areas / site to enable other agencies to carry out their work or further any other reason, it shall be done by the Contractor most expeditiously. No claim for extra payment for such work will be entertained.

11.34

It may so happen that certain components like manhole doors, hanger etc may be supplied in loose items. They need to be assembled as per relevent drawings or as per advice of BHEL engineer prior to erection. This forms the part of the scope of work.

11.35

The Contractor shall have total responsibility for all equipment and materials in his custody at Contractor's stores, loose, semi-assembled, assembled or erected by him at site. He shall effectively protect the finished works from action of weather and from damages or defacement and shall also cover the finished parts immediately on completion of work as per BHEL engineer's instructions. The machine surfaces/finished surfaces should be greased and covered.

11.36

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-I GENERAL

BHEL is operating web based computerized site operation management system (SOMS) that includes, inter-alia, issue of materials, daily progress reporting, Contractor's running monthly billing and material reconciliation through a computerized data management system. Contractor shall install necessary hardware to hook-up with the BHEL's system and use the same for his scope of work.

11.37

In the event the computerized SOMS is inoperative for any reasons, the Contractor shall take delivery of materials from the storage area/sheds of BHEL/customer after getting the approval of the engineer/customer on standard indent forms to be specified by BHEL/customer. All these records however shall be updated in the SOMS as and when the SOMS is reactivated/normalized.

11.38

All lubricants and chemicals required for testing, preservation, chemical cleaning / acid cleaning, oil flushing, and the lubricants for trial runs of the equipments and trial operation of the unit will be supplied by BHEL free of charges.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-I GENERAL

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

2 DETAILS OF SCOPE OF WORK FOR UTILITY BOILER, AUXILIARIES & PIPING

The scope of work is further detailed in the specifications hereinafter.

2.1 PRESSURE PARTS

- A) Fabrication and installation of **temporary structure** for erection of Boiler Drum is in the scope of the contractor's work. BHEL will issue the required Structural Steel for this purpose free of charges. Contractor shall have to fabricate Built Up Beams and other structural members that are required for supporting the drum lifting equipment. Contractor shall erect, fasten, weld these structures and carry out NDE as per relevant codes and practices as part of work. After completion of drum erection activity, contractor shall dismantle these structures and return to BHEL stores. Contractor shall repair the areas of permanent equipment/ structures as well as Built-Up Structural Beams affected due to installation of temporary structures and finish as per relevant codes of practice or as instructed by BHEL. Payment for installation of temporary structures as aforesaid will be made at the rate accepted for Structures; no separate payment will be made for fabrication, dismantling and finishing work and return of materials.
- B) Pressure parts components like headers, panels, coils, loose tubes etc have to be flushed/blown with compressed air, checked for dimensional accuracy and configuration and minor rectifications, if necessary will have to be done before erection. This will involve making appropriate bed of steel structures over the concrete blocks/ steel pedestals. Necessary steel, concrete blocks shall be arranged by the Contractor. bed shall be fabricated as per BHEL requirement.
- C) Normally the high pressure valves will have prepared edges for welding. But, if it becomes necessary, the Contractor shall prepare new edges or recondition the edges by grinding or chamfering to match the corresponding tubes and pipes. No gas cutting will be permitted. All fittings like "T" pieces, weld neck flanges, reducers, etc shall be suitably matched with pipes for welding (This is applicable to piping work also).
- D) Welding of all attachments on pressure parts including those required for insulation work is in the scope of work.
- E) Surfaces inside seal box and other areas that are to be applied with castable refractory lining shall be painted with black bitumen paint before boxing up and application of refractory. Seal boxes need to be partially cut open in order to pour refractory. Contractor shall carry out necessary cutting and seal welding of such cutouts. Contractor shall provide the black bitumen paint of required specification for such applications.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

- F) Furnace area and heat recovery area of flue gas passage has to be made leak proof by seal welding. Air leak test by pressurization has to be conducted to prove effectiveness of the seal weld and soap bubble or any other similar test will have to be carried out for the entire seal welds to ascertain the effective sealing is achieved. The tests may have to be repeated till satisfactory result is achieved.
- G) If required, the pressure parts, after initial erection and tests, will have to be preserved by either dry or wet preservation procedure. Contractor shall erect the piping & valves and provide necessary assistance for the same. Required piping, valves and preservative (gas / chemicals) will be provided by BHEL as free issue.
- H) The drum internals, if already installed, may have to be removed to facilitate inspection by statutory authorities and chemical cleaning. The drum internals are to be preserved properly and re-fitted at appropriate stage as part of work.
- I) Superheater and/or re-heater system will have HP butt weld joints. Welding of these HP joints shall involve pre-heating and post heating by resistance heating, argon purging of joints during welding process and full TIG weld. Contractor should follow required procedure welding NDT, etc.

J) BOILER DRUM:

- All the required T & Ps and arrangements required for Drum lifting is in the contractor scope. The entire activities of drum lifting are to be carried out as per instructions of BHEL / Customer Engineers.
- Contractor shall collect, load, transport / shift the Boiler Drum from the storage yard / identified location to the cavity of boiler, upload & handle further as required for its erection. Contractor shall make all necessary arrangements like arranging and laying of sleeper bed, steel structures, steel plates & rails etc for transport of Boiler Drum.

Boiler Drum is to be erected by using Winch method. Contractor may engage specialized agency to erect the Boiler Drum by this method. Contractor shall deploy the agency and other resources well in time to suit the milestone schedule.

- BHEL shall arrange to unload boiler drum in a convenient location nearer to Boiler Foundation. Transportation of the same to erection site for erection shall be within the scope of work of the contractor.
- Drum lifting structures shall be fabricated by the contractor at site according of BHEL drawing. Necessary steel for the same shall be arranged by BHEL. Fabrication, erection and complete installation of drum lifting arrangements,

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

including supply of consumables and anchoring for diversion pulleys shall be carried out by the contractor at no extra cost.

- HSFG bolts of boiler supporting structure are to be tightened, by turn of nut method / Torque Wrench, as per the instructions of BHEL Engineer. The bolted Joints should be jointly checked by the BHEL/customer and contractor's personnel for the required tightness and retightened wherever necessary. The tightened bolts should be identified by colour paints. Facility for random checking with calibrated torque wrenches shall also be provided by contractor.

After completion of drum lifting, erection and alignment, the drum lifting arrangements shall be dismantled by the contractor and returned to BHEL stores in good condition and to the satisfaction of BHEL Engineer.

- Corrections in the profiles of scalloped plates/bars, skin casing, seal plates etc. for proper matching with mating parts, wherever required, shall be done as incidental to the work.

2.2 TRIM & INTEGRAL PIPING OF BOILER AND POWER CYCLE PIPING

2.2.1

The work on various piping systems will include cutting to required length, edge preparation, laying, fixing & welding of the pipes / elbows / fittings/ valves etc. in the pipeline, fixing & adjustment of supports / anchors / shock absorbers and carrying out all other activities / work to complete the erection and also carrying out all pre-commissioning / commissioning operations mentioned in the specification as per BHEL Engineers instructions and / or as per approved drawings / documents.

2.2.2

Tubes or pipes wherever deemed convenient, will be sent in random lengths. These shall be cut and edge prepared to suit the site conditions and the layouts. Fittings like bends tees, elbows, reducers, flanges etc will be supplied as loose items. However, bends of tube size up to NB. 65 mm will have to be formed at site as incidental to work.

2.2.3

All drains / vents / relief/ escape / safety valve exhaust piping etc to various tanks / sewage / drain canal / flash box / sump / atmosphere etc from the stubs on the piping and equipments are covered in the scope of work.

2.2.4

Connection (either flanged, bolted or welded) of piping to the terminal points/equipments etc is in the scope of work even though such terminal point/equipment may not form part of this work. All NDE including radiography of joints so made, post-weld-heat-treatment if any, are also within the scope of work/specification. The terminal points work is inclusive

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

of cutting of existing lines, if required, edge preparation, welding/blanking and hook up work.

2.2.5

It should be ensured that all the terminal point connections are done without transferring any undue load or strain to the other equipments. Necessary protocols have to be prepared for such fit-up along with BHEL/customer representative before connecting. All NDE including radiography of joints so made, post weld heat treatment if any, is also within the scope of work/ specification.

2.2.6

Mechanical freeness of valves has to be ensured prior to erection.

2.2.7

The above provisions shall be applicable, mutatis - mutandis, to other piping systems e.g. Boiler front Naphtha piping, Fuel Gas piping from boiler front and up-to burner wind box including control valves, trip valves and conventional valves (as shown in the scheme of fuel gas system), HP auxiliary steam piping from boiler front row column to drive turbine of (i) FD fan (II) GR fan and (iii) Fuel oil pump, Fuel oil piping, Lub oil piping of rotating M/c etc.

2.2.8

Main Steam pipeline up to turbine including the strainer and terminal joint with turbine is included in the scope of work. Bidder shall follow BHEL approved procedure for welding, pre-heating. Detailed procedure will be issued to the contractor. The main steam pipeline between strainer and turbine does not undergo steam blowing, therefore this pipeline must be thoroughly cleaned of dust, scale, burr, any foreign materials and deposits by manual and mechanical cleaning method. Contractor shall take at most care in the cleaning activity so as to ensure that no undesirable particle enters inside the turbine. Contractor shall obtain specific written clearance from BHEL before and after the cleaning activity.

Contractor shall take utmost care and work in co-ordination with BHEL's turbine erection agency to ensure that no undesirable stress/force/load gets transferred to turbine or any other rotating machine that is connected to the pipelines in scope of this contract.

2.2.9 Following items of work shall also form part of piping erection:

- a. Installation & removal of isolating devices/ NRVS and removal & re-fixing of internals required for hydraulic testing, pre-commissioning and commissioning activities. Required gaskets will be supplied by BHEL free of cost.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

- b. Matching of flanges for achieving parallelism and alignment resorting to heat correction or other suitable methods as per instructions of BHEL Engineers.
- c. To locate the cause of vibrations in pumps or other auxiliaries and to carry out necessary corrections in piping and its supports. This may involve cutting, fresh edge preparation, welding, radiography, stress relieving, etc., of suction, discharge, re-circulating and other connected piping and its supports at a number of places.
- d. Fabrication and erection of racks and steel supports for all the piping including critical piping. Steel for this purpose will be supplied by BHEL.
- e. Erection, welding, NDE and stress relieving of certain equipments, e.g. flow nozzles, control valves etc, after completion of certain activities e.g. chemical cleaning, steam blowing etc is part of work. This may involve removal of portions from the already erected pipelines in order to introduce these equipments and resultant edge preparation etc shall be incidental to work. No separate/ additional payment is envisaged for cutting, welding and edge preparation in this regard. The removed pieces of pipes shall be returned to BHEL stores with proper cleaning, dressing and identification marking.
- f. Welding of root valves including reducer (to suit Control & Instrumentation Impulse Piping requirements) with small length of piping to the pressure, flow and level tapping points on piping or flow nozzles / orifices / metering elements fixed on piping.
- g. Opening of valve actuators, dismantling of actuators from the valves, refitting and rendering assistance connected with the electrical and mechanical problems.
- h. Fixing and welding including due NDE & PWHT etc of carrier plates on to the pipes.

2.2.10

As far as possible pre-assy of piping on ground is to be done. The erection of various piping may have to be started from any random reference instead of the terminal points in order to meet certain completion commitments.

2.2.11

The location of drain headers, valves, stations, steam traps of piping as indicated in the BHEL drawings are suggestive only. The final location and routings shall be decided to suit the site conditions. While routing such lines and fixing the stations, it has to be erected so as to provide easy accessibility and free path for the purpose of easy operation

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

and maintenance. These locations shall be acceptable to the client. Sometimes, the locations of stations and routing of lines may have to be changed as per the site conditions. All such works shall be carried out expeditiously as per the instructions of BHEL Engineer. The decision of BHEL Engineer is final and binding on the Contractor.

2.2.12

The rate quoted in rate schedule is also inclusive of pre-heating, welding, post heating, post weld heat treatment/ stress relieving and NDE of piping.

2.2.13

Erection of piping systems shall involve co-ordination with the erection of the turbine, turbo-generator, condenser, boiler, boiler feed pumps and other major equipments. Wherever required, approval of concerned BHEL Engineer/other erection agency must be obtained prior to making piping interface connections to such equipments. Sequence of work shall be carefully planned to minimize interference with other groups working in the same area. Actual sequence to be followed shall be subject to the approval of BHEL Engineer and BHEL Engineer may direct the Contractor to reschedule his work to suit the status of the site work.

2.2.14

While erecting the field run pipes, the Contractor shall check the accessibility of valves, instruments tapping points and maintain minimum head room requirement and other necessary clearance from the adjoining work areas to avoid interferences.

Steam Turbines and all Steam line drain headers will be operate from common steam header; Contractor under this Tender specification shall carried out the main steam piping works as per instruction of BHEL Site in charge.

2.2.15

All pipelines shall be given proper slope towards the drain points during erection. For maintaining the slopes as given in the drawings for larger thickness and larger dia pipelines, edge preparation for welding may have to be altered suitably to achieve the slope.

2.2.16

All pipelines shall be provided, as per the instructions of BHEL Engineer, with suitable Vent and the drain points with valve (s) on the highest and lower points of the pipe run although may not be specifically mentioned in the drawing.

2.2.17

It may become necessary to make & install temporary spool pieces for certain process requirements. Contractor's scope shall include preparation, erection, fit-up, welding, NDE etc and dismantling of such spool pieces at appropriate stage without any additional payment.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

2.2.18

Normally, setting of hangers in cold condition is done by simulation adding additional temporary weight, which will be roughly equal to the weight of the insulation. Attachment of temporary weights and floating of the joints in the simulation test is to be treated as part of contractual work. Hanger settings may have to be repeated till free-floating joints are achieving. Hanger adjustments to be repeated for steam blowing by resetting hot and cold values if required. This may have to be repeated several times after steam blowing and synchronization. The weights will be supplied by BHEL. Contractor has to transport from BHEL stores and return the same after completion of work. No extra claim on this account will be entertained.

2.2.18

The complete of scope Instrument air, Service air piping with valves, fittings, traps, supports etc. for Boiler with Aux. and TG system with Aux. is covered under these specifications. Contractor shall plan his resources and carry out the work in consultation with BHEL Engineer at site to achieve the individual milestone schedules and overall project milestone schedules. Contractor shall carry out the complete works of threading, tapping, fitting of joints with sealing compound, leak test etc. as drawing requirement and instruction of BHEL Engineer at site. The required sealing compound shall be provided by Contractor as part of scope of work.

2.3 ROTATING MACHINERY

- a Specifications covered under the following para and also other relevant specifications contained in other paras elsewhere in this tender document will be applicable for rotating machines like **FD-Radial Forced draft fan** (with silencer and dual drives) / **GR - Radial Gas Recirculation fan** with dual drives, Bi-sector regenerative air heater, Seal air fans, Blowers, HP & LP dosing pump skids and other similar auxiliaries.
- b All lubricants for testing, preservation and lubricants for Trial runs of the equipments shall be supplied by BHEL as free issue. All services including labour shall be provided by the Contractor for drawing these from BHEL / customer's stores, transporting, handling, filling, emptying, re-filling, accounting and return of surplus lubricants / empty containers / old & used lubricants after draining etc. Contractor should clean the spilled / leaking lubricants thoroughly, consumables for such cleaning will be in Contractor's scope.
- c All rotating machinery and equipments shall be cleaned, lubricated, checked for their smooth rotation, if necessary, by dismantling and re-fitting before erection. Also, the equipments may have to be checked for clearances, tolerances at any stage of the

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

work including during testing, commissioning etc. shaft of the rotating machines shall be rotated periodically to avoid damages. All these shall be part of work.

- d Trial run of the drives in un-coupled state and then coupled with equipment has to be done after necessary alignment & coupling. Forced lube oil systems including lube oil piping of drives, rotating equipments etc form part of the work under these specifications. Hydraulic test of oil coolers, oil piping etc is in the scope of work. Where required cooler may have to be dismantled for hydraulic test and re-erected thereafter as part of work.
- e Certain rotating machinery, after testing, pre-commissioning may have to be re-aligned/hot aligned and vital clearances re-set. This may necessitate disconnection of cabling, removal of certain instruments etc and restoration thereafter.
- f Protective lubricant coats / fill provided on / in the critical area of equipments have to be removed at appropriate stage and regular lubricants, after removal / cleaning of protective coat / fill, as per specifications should be filled / applied. Cleaning / flushing agents / oils will be provided by BHEL.
- g Chemical cleaning, steam blowing and air drying of the connecting pipes for the lube oil system has to be carried out wherever required as per instruction manuals / drawings. Chemicals, suiting BHEL specification, for such chemical cleaning is in the scope of Contractor.
- h Even though rotating machines may be grouted to foundation using non-shrink grout mix, blue matching of packer plates / shims with foundation / between packers / equipment base should be done as incidental to work wherever instructed by BHEL Engineer.
- i) Skid mounted equipments may need checking, re-setting due to various reasons as incidental to work.

2.4 MAIN SUPPORTING STRUCTURES, EXTERNAL STRUCTURES, ELEVATOR STRUCTURES, STAIRWAYS, GALLERIES & PLATFORMS & HANDLING ARRANGEMENT

2.4.1

Contractor shall supply and erect one number passenger cum goods elevator of 1.5 MT capacity to reach up-to the boiler drum level to facilitate erection, movement of person and goods etc. the arrangement shall conform to applicable safety norms. Contractor shall dismantle and take the elevator back after completion of work. The elevator shall be made ready at the time of drum lifting.

2.4.2

Boiler main supporting structures have to be erected in a sequential manner.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

2.4.3

Quality norms with regard to verticality of column, inter-alia, have to be adhered to strictly, at various stages of erection.

2.4.4

Stiffening / strengthening of main supporting structure, if any, due to deviation in verticality of columns post drum lifting, shall be carried out, including fabrication, if any. Necessary steel for this will be provided in random sizes by BHEL as free issue. Payment for such stiffening/ strengthening shall be made for weight certified by BHEL engineer at the item rate applicable to structures, provided the deviation has occurred for the reasons not attributable to the Contractor.

If the deviations are attributable to Contractor, the materials required for Rectification / Stiffening / Strengthening, fabrication, erection of the same shall be to the Contractors account.

2.4.5

Each ceiling girder will be supplied in pieces and ceiling girders are to be pre-assembled at site and welding & ndt tests are to be carried out, including 100% radiography for the welded joints in ceiling girders on ground prior to their erection in position.

2.4.6

It is likely that, in deviation from prescribed sequence, erection of certain elements of structure may be deferred for later stage, to facilitate, say crane boom reach to higher elevation, passage of drum during drum lifting etc. this may necessitate temporary installation of some structural steels at appropriate locations to keep the stability of structure intact. such temporary installations shall be removed subsequently and returned to BHEL stores/ storage yard. Finishing work in the related permanent structures shall be done as per the instruction of BHEL engineer. BHEL will provide necessary steels on free issue basis in random sizes for such installations, which shall be fabricated by the Contractor to suit the requirement.

Payment for such installations shall be made on the accepted tonnage rate of structures. No separate payment will be made for fabrication, removal & return of the materials to BHEL stores.

2.4.7

In some cases, the structural material will be supplied in random lengths, which have to be fabricated to suit the requirement as incidental to work. Also, it may sometimes be necessary to remove some of the erected members to facilitate erection of bigger/ pre-assembled equipments. In such cases, the removal and re-erection of such members as agreed by the BHEL Engineer will have to be done by the Contractor as incidental to work.

2.4.8

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

Contractor shall arrange materials required for temporary cat ladders & working platforms during erection of columns, platforms and other structural components. Such arrangements shall, as far as possible, be only of clamping & bolting type, as welding on columns etc will not be permitted. After the completion of work these shall be removed.

2.4.9

All the hand rails and toe guards shall be provided as per drawings and site requirement. hand rails supplied in running lengths shall be suitably cut, edge prepared and welded. Also, hand rails/ guards may have to be provided from the safety point of view in certain places though not indicated in the erection drawings. The weld joints of hand rails shall be ground smooth to flush finish.

2.4.10

Electro forged floor grills will be supplied for this project. These may have to be cut to suit requirement. Cutting shall be done only by mechanical cutters **and not by gas cutting**. Cold galvanizing compound is to be applied on the cut surface/edge. Supply of Cold galvanizing paint in contractor's scope.

Fixing of floor grills shall be done by self-tapping screws **and not by weldable studs**. Special purpose electrically operated hand tools are available in the market for this, which drills, taps and fixes the screws in a single operation. BHEL will supply the necessary self-drilling-cum-tapping screws and fixing clips. Contractor shall deploy the **drilling cum fixing machine** required for this purpose as a regular scope of work.

2.4.11

The Contractor shall also install additional platforms of permanent nature for approaching different equipment as per the site requirement and to meet O&M requirements, though these may not indicated in the erection drawings. Materials required for such platforms will be supplied by BHEL in random sizes on free issue basis. These have to be fabricated to suit the requirement. Payment only for erected weight as certified by BHEL engineer shall be made at the rate applicable for structures. No payment is envisaged for fabrication of structures.

2.4.12

All relevant provisions as above shall apply, mutatis-mutandis, to the work of external structures, interconnecting structures, elevator structures, ESP stairways and galleries & equipment handling system etc.

2.5 OTHER PRODUCTS AND SYSTEMS AND COMMON REQUIREMENTS

- C) Certain structural items like silencer supports, roof cladding structure, platform etc will be supplied in running lengths which shall be cut to required suitable sizes and adjusted/trimmed as part of work.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

- D) Contractor has to make canopies for motors, actuators, lube oil units, control valves, etc. Material for this will be supplied in random lengths / sizes. No separate payment for fabrication is envisaged. Only the erection tonnage rate applicable for structure will be paid for this work.
- E) BHEL will supply **Metapoly Sheets** for roof and side cladding of Boiler and elevator structure. These sheets are to be fixed with self tapping screws (supplied by BHEL) in similar manner as in case of Galvanized floor grills. Contractor shall deploy the **drilling cum fixing machine** required for this purpose as a regular scope of work.
- F) In case the fans (FD/GR) are provided with variable frequency drive, Contractor has to erect & commission the mechanical components of the fan. Electrical/ Electronic Panels, transformers, cabling etc are not in this work specification. However in case of Hydraulic Coupling, the coupling shall be in scope of this contractor.
- G) Actuators / drives of dampers, gates etc may have to be serviced, lubricated before erection, during pre-commissioning and commissioning, including carrying out adjustments required as incidental of the work.
- H) All welded joints should be painted with anticorrosive paint/primer immediately after completion of all work. Necessary paints and other consumables for the above work are in the scope of the contractor.
- I) Spring suspension / constant load hangers may have to be preassembled for required load and erection carried out as per instruction of BHEL. Adjustments, removal of temporary arrests / locks, cutting of excess thread length of hanger, tie rod etc, have to be carried out as and when required. Load setting of spring hangers, as per BHEL's documents / instructions, during various stages of erection and testing and after floating of piping / ducting during cold and hot condition will have to be done. This exercise may have to be repeated till satisfactory results are achieved.
- J) Hangers and suspensions, support steels for ducts and other equipments, piping etc will be supplied in running/random lengths/ sizes, which shall be cut to suitable sizes and adjusted as required.
- K) Air leak test is to be conducted for the cold & hot secondary air ducts, primary air ducts. Also gas tightness test is to be done for the flue gas ducts. In addition to this, leak tests are to be done for the furnace, skin casing works carried out in the boiler roof, furnace bottom etc to the satisfaction of BHEL/Customer.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

- L) Touch up and preservative painting of all components issued to and/or erected by contractor shall form part of scope of work. The contractor shall arrange all paints, primer and consumables, T&P and facilities.
- M) Feed Storage Tank of Deaerator will be shipped in three sections apart from heater, loose parts and structural steel for approach platform. The complete FST Sections and heater will be required to be lifted and place at its designed platform. Contractor shall carry out all the works of lifting, placement, assembly, welding, Post & Pre-heat treatment, NDE / NDT, Radiography, Hydraulic testing, flushing etc. as scope of work as per drawings & documents requirement and instructions of BHEL Engineer at site.

There may be access / approach limitations to place & erect the FST sections & Heater of Deaerator and it may be necessary to make temporary platform / approach to access the desired location / foundation and erect the equipments. Contractor shall make such temporary approach platform & ladders etc. as scope of work including providing structural steel, rails and other members etc.

3 DETAILS OF SCOPE OF WORK FOR HRSG, AUXILIARIES & PIPING

The scope of work is further detailed in the specifications hereinafter.

ERECTION OF HRSG, ITS AUXILIARIES

3.1 HRSG RECEIPT, UNLOADING, STACKING AND ERECTION OF MODULES:

3.1.1 ERECTION OF HEAT TRANSFER MODULES:

The heat transfer modules will be sent loose, 2-3 Nos. with intermediate wooden packing, in light crating-cum-arrestor arrangement welded to the trailer bed. The crate-arrestor has to be cut at site for unloading the modules one-by-one. For unloading the modules special unloading frames have to be used as the modules being flexible have propensity to bending. Utmost care is, therefore, essential while unloading the modules and a special frame will have to be used for unloading supplied by BHEL, manufacturing unit.

These modules will be unloaded directly at site and only 2-3 modules, with wooden packing between them at appropriate locations, shall be kept in each stack.

For erection of these modules yet another frame, for making the module vertical, will be required. Frame will have to be fabricated at site by the contractor.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

Required materials for fabrication of special frames for unloading as-well-as vertical frame shall be issued in random sizes by BHEL on free-returnable basis. No separate payment is envisaged for this fabrication.

In all these handling of modules polyester flat webbing sling shall be used. These slings shall be arranged by Contractor.

There are 44 modules per HRSG total 88 modules for both the units, dimension of each module is 3715mm x 127mm x 11400mm, and each module weighs 3.7 MT approx.

3.1.2 ERECTION OF HRSG DRUM:

The tentative weight and dimensions respectively are as under:

HRSG Drum: 1 no- weight – 55.4 MT, Dia.-1900 mm (Approx), length- 9600 mm (approx), ID 1676 mm. The elevation of Centre Line of HRSG Drum is 19550 mm.

These have to be erected with the help of adequate capacity crane from the side of HRSG after the erection of casing and heat transfer modules of respective circuits.

3.1.3

It shall be the responsibility of the contractor to provide temporary ladders on columns, chimney etc in a manner prescribed by BHEL using their own material till such time as permanent stairways are completed.

3.1.4

Pressure Parts components like Headers, Modules, loose tubes / links etc. have to be checked for dimensional accuracy and configuration and minor rectifications, if necessary will have to be done before erection. This will involve making appropriate bed of steel structures over the concrete blocks. Steel, in random sizes, for this purpose will be provided by BHEL from the packing materials / scraps etc., where as necessary concrete blocks shall be arranged by the contractor. Bed shall be fabricated as per requirement. These shall be dismantled & returned to BHEL at appropriate stage. No separate payment for making / dismantling such bed is envisaged.

3.1.5

Normally the high pressure valves will have prepared edges for welding. But, if it becomes necessary, the contractor shall prepare new edges or recondition the edges by grinding or chamfering to match the corresponding tubes and pipes. All fittings like “T” pieces, weld neck flanges, reducers, etc., shall be suitably matched with pipes for welding (this is applicable to piping work also).

3.1.6

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

Tubes or pipes wherever deemed convenient, will be sent in random lengths. Tubes / pipes sent in standard/ random length shall be cut and edge prepared to suit the site conditions and the layouts. Bends of tubes up to OD 65 mm will have to be formed at site as incidental to the work. This is applicable to piping work also.

3.1.7

Welding of all attachments, including those of stainless steel hooks/ pins on casing & inlet duct, non-pressure parts, pressure parts/ piping including those required for insulation work of HRSG with aux, steel stack and equipments, tanks / vessels, heaters, deaerator etc. of Gas Turbine set, piping's is in the scope of work.

3.1.8

Furnace area and Heat recovery area of flue gas passage has to be made leak proof by seal welding. Air leak test by pressurization has to be conducted to prove effectiveness of the seal weld and bubble / soap test will have to be carried out for the entire seal welds to ascertain the effective sealing is achieved. The tests may have to be repeated till satisfactory result achieved.

3.1.9

If required, the pressure parts, after initial erection and tests, will have to be preserved by either dry or wet preservation procedure. Contractor shall render all assistance for this and erect temporary piping with valves wherever necessary. Required material will be provided by BHEL.

3.1.10

Any fixtures, concrete block supports, steel structures, required for temporary supporting for pre-assembly or checking and welding for lifting and handling during pre-assembly and erection shall be arranged by the contractor.

3.1.11

The drum internals, if already installed, may have to be removed to facilitate tube expansion, inspection by statutory authorities and chemical cleaning. The drum internals are to be preserved properly and refitted afterwards as part of work.

3.1.2

PIPING (POWER CYCLE PIPING, INTEGRAL PIPING, REGENERATIVE PIPING INCLUDING INSTRUMENT AIR & SERVICE AIR PIPING ETC.)

3.1.2.1

The work on various piping systems will include cutting to required length, edge preparation, laying, fixing & welding of the pipes / elbows / fittings/ valves etc. in the pipeline, fixing & adjustment of supports / anchors / shock absorbers and carrying out all other activities / work to complete the erection and also carrying out all pre-commissioning

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

/ commissioning operations mentioned in the specification as per BHEL Engineers instructions and / or as per approved drawings / documents.

3.1.2.2

Laying of pipelines as per the specifications, between equipments constituting terminal point, whether the terminal equipments fall within the scope of the work / specification or not, is within the scope of the work / specification. The contractor shall complete terminal joints at both ends for all the piping schemes covered in the specification.

3.1.2.3

Aligning, matching and welding of piping to the terminal points (such as stubs, on terminal equipments, stubs on headers, battery limits etc), even if these terminal equipment/point do not form part of this scope of work / specification, and stress relieving and NDE of joints so made is also within the scope of work / specification. Also, where the piping connection to the terminal points involves flanged joints, mounting and welding of flanges on piping as well as terminal equipment matching of flanges as specified elsewhere herein, fixing of gaskets, bolting and tightening as per BHEL engineer's instruction is also in this scope of work / specifications. required fasteners and gaskets will be supplied by BHEL free of cost.

3.1.2.4

Following items of work shall also form part of piping erection:

- 1) Installation & removal, as applicable, of isolating devices/ NRVS and removal & re-fixing of internals required for hydraulic testing, pre-commissioning and commissioning activities. Required gaskets will be supplied by BHEL free of cost.
- 2) Matching of flanges for achieving parallelism and alignment resorting to heat correction or other suitable methods as per instructions of BHEL Engineers.
- 3) To locate the cause of vibrations in pumps or other auxiliaries and to carry out necessary corrections in piping and its supports. This may involve cutting, fresh edge preparation, welding, radiography, stress relieving, etc., of suction, discharge, re-circulating and other connected piping and its supports at number of places.
- 4) Increase or decrease in length of piping including change in layout to suit site conditions.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

- 5) Fabrication and erection of racks and steel supports for all the piping including of system piping. Steel for this purpose will be supplied by BHEL in random sizes.
- 6) Erection, welding, NDE and stress relieving of certain equipments, e.g. flow nozzles, control valves etc, after completion of certain activities e.g. chemical cleaning, steam blowing etc is part of work. This may involve removal of portions from the already erected pipelines in order to introduce these equipments and resultant edge preparation etc shall be incidental to work. no separate/ additional payment is envisaged for cutting, welding and edge preparation in this regard. the removed pieces of pipes shall be returned to BHEL stores with proper cleaning, dressing and identification marking.
- 7) Matching of all fittings like tees, bends, flanges, reducers, valves, socket fittings, etc with pipes for welding. This may involve weld build up, edge preparation, etc.
- 8) Cleaning of all pipes as prescribed, flushing by compressed air etc.
- 9) Welding of root valves including reducer (to suit Control & Instrumentation Impulse Piping requirements) with small length of piping to the pressure, flow and level tapping points on piping or flow nozzles / orifices / metering elements fixed on piping.
- 10) Welding of weld blanks with due NDE & PWHT, if required, on a temporary basis.
- 11) Opening of valve actuators, dismantling of actuators from the valves, refitting and rendering assistance connected with the electrical and mechanical problems.
- 12) Fixing and welding including due NDE & PWHT etc of carrier plates on to the pipes.

3.1.2.5

On all steam piping, water piping, oil piping, air piping, etc, where butt welding is involved, root TIG welding and subsequent arc welding shall be adopted as instructed by BHEL engineer. The decision of BHEL engineer regarding welding procedure for welding of above lines will be binding on the contractor.

3.1.2.6

Pipes / tubes / structural materials, which are issued in running meters, may not be sent in standard lengths. These have to be cut to suit site conditions.

3.1.2.7

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

certain pipe lines of oil, air, steam and water will be field routed as per schemes approved at site or as per the instructions of BHEL engineer, and will be supplied in random lengths / running lengths. The contractor shall lay the piping according to instructions at sites, after carrying out the necessary fabrication, edge preparation, routing, supporting etc, in best professional manner and as per instructions. The supports for field-routed piping shall be fabricated and erected as per the requirement of the work. The steel required for the supports will be provided by BHEL free of cost at their stores.

3.1.2.9

All weld joints on piping shall be ground or filed on completion of welding and before radiography as per instructions BHEL engineer so as to achieve smooth surface free of notches, ripples, undulations, etc. and to limit the reinforcement as per the codes.

3.1.2.10

Contractor shall erect the piping by doing pre-assemble on ground if possible at the first instance. The pipe laying shall be carried out from the available terminal point / points or any other area between the terminal points. The erection can be carried out on temporary supports to obtain proper alignment and welding. After fixing the permanent supports, all the temporary supports shall be removed. The alignment, distances and loading of the supports shall be checked and the required spring compression achieved in the case of spring hangers.

3.1.2.11

Contractor shall carryout edge preparations for welds joints in accordance with BHEL drawings / BHEL standards / BHEL engineer's instruction.

3.1.2.12

The location of drain headers, valves, stations, steam traps of piping as indicated in the BHEL drawings are suggestive only. The final location and routings shall be decided to suit the site conditions. While routing such lines and fixing the stations, it has to be erected so as to provide easy accessibility and free path for the purpose of easy operation and maintenance. These locations shall be acceptable to the client. Sometimes, the locations of stations and routing of lines may have to be changed as per the site conditions. All such works shall be carried out expeditiously as per the instructions of BHEL engineer. The decision of BHEL engineer is final and binding on the contractor.

3.1.2.13

The rate quoted in rate schedule is also inclusive of pre-heating, welding, radiography, post heating, post weld heat treatment/ stress relieving and NDE.

3.1.2.14

Hanger rods shown in the piping arrangement drawing may have to cut and welded to suit site condition. The contractor shall do cutting and welding of these hanger rods. The NDE & stress relieving required on welded hanger rods shall be carried out. The hanger for piping will be tested for even distribution of load with the help of torque wrench.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

3.1.2.15

The piping may be provided with hand holes. The hand holes will be opened up for inspection and seal welded prior to operation.

3.1.2.16

Structural materials required for the supporting / operating platforms required for the valves/equipments at various levels for the safe operation will be issued in random sizes to the contractor free of cost. however, the contractor's quoted rate shall include fabrication and erection of all such of platforms at site and no extra payments shall be allowed for this and only tonnage rate applicable for structures only will be payable.

3.1.2.17

Erection of piping systems shall be coordinated by the contractor as required, with the erection of the Gas Turbine, Steam Turbine, GT & STG generators, condenser, Boiler feed pumps and other major equipments, approval must be obtained from the concerned BHEL engineer and other agencies concerned prior to making piping interface connections to the aforementioned equipments. Sequence of work shall be carefully planned to minimize interference with other groups working in the same area. Actual sequence to be followed shall be subject to the approval of engineer and engineers may, at time, direct the contractor to reschedule his work as per status of the site work.

3.1.2.18

While erecting the field run pipes, the contractor shall check the accessibility of valves, instruments tapping points and maintain minimum head room requirement and other necessary clearance from the adjoining work areas to avoid interferences.

3.1.2.19

All pipelines shall be given proper slope towards the drain points during erection.

3.1.2.20

All pipe lines shall be provided with suitable vent and the drain points with valve (s) on the highest and lower points of the pipe run although may not be specifically mentioned in the drawing as per the instructions of BHEL engineer.

3.1.2.21

For instrument connections, pipe stubs including the instrument tubing up to the root valves including reducer (to suit Control & Instrumentation Impulse Piping requirements) shall be installed by the contractor. Root valves including reducer (to suit Control & Instrumentation Impulse Piping requirements) shall be located in the convenient location / place as required by the customer to facilitate easy operation as per the decision / instruction of BHEL engineer.

3.1.2.22

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

The contractor shall be responsible for correct orientation of all valves so that flow direction, seats, stem and hand wheel are in desired locations. Information regarding orientation of valves, not fully located on drawings, may be obtained from the BHEL engineers.

3.1.2.23

The piping systems, which come under the purview of IBR, should meet the requirement of IBR. The contractor shall be well versed with all the latest amendments of Indian boiler regulations.

3.1.2.24

All piping shall be grouped wherever practicable and shall be routed to present a neat appearance.

3.1.2.25

For field run piping, contractor shall fabricate and erect all hangers and supports as required with due regard to general arrangement layout of other pipes, hangers, cable trays, ducting, structural members, etc.

3.1.2.26

For maintaining the slopes as given in the drawings for larger thickness and larger dia pipelines, edge preparation for welding may have to be altered suitably to achieve the slope.

3.1.2.27

it may become necessary to make & install temporary spool pieces for certain process requirements. Contractor's scope shall include preparation, erection, fit-up, welding, NDE etc and dismantling of such spool pieces at appropriate stage without any additional payment.

3.1.2.28

In pipelines like re-heater lines, CRH lines, extraction lines, HP/IP & LP bypass lines etc., the NRVS and valves will also be erected by contractor under this tender specifications. though these NRVS & valves may be supplied from different units / different sources, the erection, alignment, welding, NDE test, heat treatment, radiography, supporting etc. along with their control/ governing oil system piping with tanks, pumps, power cylinders etc. including the oil flushing & commissioning of these valves shall be carried out by contractor as per instruction of BHEL engineer and drawings / documents requirement. Similarly erection / fixing, welding etc. of strainers, dummy devices in various lines, valves and their subsequent removal & re-fixing during pre-commissioning / commissioning stages of steam blowing, flushing etc. shall be carried out by contractor under these tender specifications.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

3.1.2.29

All temporary lines required for chemical cleaning, hydraulic testing, steam blowing, etc., shall be supplied in 'as is where is' condition. The contractor shall arrange to carry out the required fabrication, dressing, grinding, cleaning, cutting, edge preparation etc., while carrying out erection. No extra claim on this account will be entertained. For human protection, temporary insulation over piping to be applied at no extra cost.

3.1.2.30

Before laying the piping on supports, the coordinates and elevations of all supports shall be checked by the contractor for correctness. Discrepancies from the execution drawings, if any, shall be promptly brought to the notice of BHEL engineer in writing and correction shall be carried out as per his instructions.

3.1.2.31

Normally, hangers setting in cold condition are done by simulation adding additional temporary weight, which will be roughly equal to the weight of the insulation. Attachment of temporary weights and floating of the joints in the simulation test to be treated as part of job. Hanger settings have to be repeated for achieving free-floating joints. Hanger adjustments to be repeated for steam blowing by resetting hot and cold values if required. This may have to be repeated several times after steam blowing and synchronization. The weights will be supplied by BHEL. Contractor has to transport from BHEL stores and return the same after completion of work. No extra claim on this account will be entertained.

3.1.2.32

All the instrumentation tap-off points like thermo-wells, root valves including reducer (to suit Control & Instrumentation Impulse Piping requirements), impulse lines, nipples etc., shall also be erected and welded by the contractor irrespective of whether such materials are supplied by BHEL or any other agency.

3.1.2.33

The weld grooves of MS line, HRH line, CRH line, BFD lines and other pipes will be as per BHEL standard specifications. Further, the edge preparation shall be done as per instruction of BHEL site engineer and same shall be binding on the contractor.

3.1.2.34

All equipments / works shall be preserved and protected properly during and after erection. Instructions / directions given by BHEL in this connection will have to be observed by the contractor.

3.1.2.35

The location of tanks, vessels, valves, stations etc in the pipelines indicated in the BHEL drawings may be indicative only. The final location and routings shall be decided to suit the site conditions. While routing such lines and fixing the stations, they have to be erected so as to provide easy accessibility and free path for the purpose of easy operation

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

and maintenance. These locations shall be acceptable to the client. Sometimes, the locations of stations and routing of lines may have to be modified as per the site conditions. All such work shall be carried out expeditiously as per the instructions of BHEL engineer. The decision of BHEL engineer is final and binding on the contractor.

3.1.2.36

All G.I. pipelines shall be joined by threaded (screwed) joints. Pipes and fittings will be supplied by BHEL as commercially available. Contractor shall arrange to check and clean and ream the existing threads if necessary, by running thread cleaning die/tap or by machining. Fresh threading shall be done in case existing thread is found damaged beyond repair after cutting off the damaged portion within the quoted rates. Fresh threading shall also be done in G.I. pipe ends cut to suit site layout.

3.1.2.37

Both male and female threads shall be cleaned of oil, grease etc, with appropriate solvent etc. prior to jointing. Joints shall be sealed by applying teflon tape on male thread. All joints shall be tightened adequately so as to achieve leak-proof joint. Exposed portion of the external threads shall be coated with zinc silicate paint. Contractor shall arrange all consumables for cleaning, sealing and painting.

3.1.2.38

Pressure testing with compressed air and external application of soap solution or flame or any other BHEL-approved method shall be done on all joints. Such tests may have to be repeated several times to ensure a leak proof system. Leakages if any shall be repaired by the contractor promptly according to the BHEL-approved procedure/method. Any additional expenses for repair attributable to contractor shall be borne by the contractor.

3.2 OTHER PRODUCTS AND SYSTEMS

3.2.1

Ducts / expansion bellows are normally supplied in loose wall plates / segments and these are to be assembled and welded at site before erection. All joints connecting ducts, expansion pieces and dampers shall be seal welded. These welds have to be tested by LPI and made leak proof as per technical instruction / requirement.

3.2.2

Certain structural items like silencer supports, roof cladding structure, platform etc., will be supplied in running lengths which shall be cut to required suitable sizes and adjusted/trimmed as part of work.

3.2.3

Additional platforms of permanent nature for approaching different equipments like actuators, valves, instruments etc. as per site / BHEL client's requirements, which may not be indicated in drawings, but essential for safe access, shall be made by the contractor

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

from structural steel / materials supplied in random lengths / sizes. The contractor will be paid for this work on accepted erection tonnage rate for structures.

3.3 HRSG STEEL STACK/ CHIMNEY ERECTION

3.3.1 THE DETAILS OF CHIMNEY IS AS FOLLOWS:

- Chimney Inner Diameter : 3.5 M
- Chimney Total Height : 40.0 M
- Total Chimney Estimated PGMA Weight : 110 MT each Stack
- Total no. of shell involved in one steel stack - 16nos, each 2.5m high.
- ID, OD & weight of bottom most shell and confirm whether it is supplied in single piece or two half - 3.5m, 3.556m, and ~7.0MT. All the shells will be supplied in two halves.
- ID, OD & weight of Top most shell - 3.5m, 3.52m, ~3.0MT
- Heaviest weight shell - bottom most shell~ 7.0MT
- Chimney height/Elevation of top most shell - 40.0 mtr.

All shells are to be welded as per erection detail. Flange holes are given for locating/ erection/ alignment purpose only.

3.4.2

Welding of chimney joints shall be carried out by certified welder. Wherever necessary, radiography have to be taken to meet the BHEL/statutory requirements.

3.4.3

Chimney has to be insulated up to full height and approximate. Insulation thickness: is 80mm LRB wool mattress, however actual insulation thickness shall be as per drawings which will be provided during execution of work at site.

3.4.4

Helical strakes as indicated in the erection drawings are to be welded onto the chimney.

3.4.5

Chimney base will be supplied in two halves, which will have to be assembled at site.

3.4.6

Painter's trolley will be supplied in parts and will have to be assembled.

3.4.7

All electrical works such as lightening arrestors, earthing and aviation lights etc. are in the scope of work.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-II BOILER, AUXILIARIES & PIPING

3.4.8

Stack/ chimney have to be painted as per the requirement of aviation / Relevant BIS standards.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-III FOUNDATIONS & GROUTINGS

13 PREPARATION OF FOUNDATIONS, AND GROUTING OF EQUIPMENT OF UTILITY BOILER & AUXILIARIES

13.1

Building foundations and other necessary civil works for supporting structures, equipments etc will be provided by BHEL / Customer. The checking of dimensional accuracy, axes, elevation, levels etc, with reference to bench marks of foundations and anchor bolt pits have to be checked and logged by the Contractor. The permanent benchmark / reference marks will have to be transferred to new locations with sufficient care to maintain the accuracy and protected / preserved with adequate care (to enable rechecking at later dates) as per BHEL instruction.

Minor adjustment of foundation level, dressing and chipping of foundation surfaces and blue-matching (wherever required) for of all equipments as per BHEL Engineers instructions, should be done by the Contractor as part of the work. Contractor/BHEL shall prepare protocols before taking over the foundations. Dressing and chipping of foundations upto 35mm for achieving proper levels will be within the scope of work/specification.

13.2

All temporary foundations and anchor points required for installing erection Equipments and winches, foundations for pumps, tanks etc are in the scope of Contractor. All building materials like cement, steel including re-inforcement bars, grits cements etc for such temporary foundations shall have to be arranged by the Contractor within the quoted rates. All such foundations shall be demolished and normal ground conditions restored after the usage.

Neutralisation pit for EDTA cleaning is to be made by the Contractor. After completion of job pit has to be dismantled and area is to be levelled before handing over of area to owner.

Effluent to be disposed off safely from neutralising pit to a safe area as per instruction of BHEL Engineer.

13.3

Contractor shall carry out scrapping and blue matching of embedded plates/ packers of rotating equipments. Chipping and the leveling of concrete surfaces, fine dressing up to the extent required to obtain contact between packer and concrete, is also covered in the scope of this work. Scrapping, chipping and matching shall be done so as to achieve prescribed percentage of contact between the two surfaces.

13.4

BHEL will provide free of cost only the shims and packer plates (either machined or plain) which go as permanent part of the equipment. Certain packer plates and shims over and above the quantity received as a part of supplies from manufacturing units of BHEL, will have to be cut out from steel plates / steel sheets at site to meet site requirement. Contractor shall cut and prepare packers and shims by gas cutting / chiseling / grinding and de-burr the same. However, machining of the packers wherever necessary, shall be arranged by contractor.

13.5

Complete grouting of structures equipments, including anchor/ foundation bolts, beneath base, base hollows etc, as may be applicable, is included in the scope of Contractor. Arranging all

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-III FOUNDATIONS & GROUTINGS

labour, building materials including cement, ordinary portland as well as quick setting – free flow - non-shrink grout mix (e.g. conbextra gp1/gp2), form work, shuttering, and any other requirements is in the Contractor's scope. Contractor shall obtain approval of BHEL for cement (ordinary portland as-well-as quick setting – free flow- non-shrink grout mix) prior to use. Cleaning of foundation surfaces, pocket holes and anchor bolt pits and de-watering and making them free of oil, grease, sand and other foreign materials by soda washing, water washing, compressed air and other approved methods are within the scope of this specification/ work.

13.6

After the grouting has finally set and cured, alignment of equipments involved shall be checked again to verify for any disturbance or any other reason. If required, de-coupling of equipments has to be done for conducting the verification. In case any disturbance is noticed the cause, if any, shall be removed and re-alignment done as part of work.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-IV WELDING, RADIOGRAPHY, NDT, PWHT

14 WELDING, RADIOGRAPHY AND OTHER NON-DESTRUCTIVE TESTING, POST WELD HEAT TREATMENT

14.1 WELDING

14.1.1

Installation of equipment involves good quality welding, NDE checks, post weld heat treatment etc. Contractor's personnel engaged should have adequate qualification on the above works.

14.1.2

The method of welding (viz) arc, TIG or other method will be indicated in the detailed drawing/documents. BHEL Engineer will have the option of changing the method of welding as per site requirement.

14.1.3

Welding of high pressure joints shall be done by IBR certified high pressure welders who have been permitted by CIB of state concerned for deployment at the site of work.

14.1.4

Welding of all attachments to pressure parts, piping shall be done only by the qualified and approved welders.

14.1.5

Before any welder is engaged on work, he shall be tested and qualified by BHEL/ customer, though they may possess the IBR/other certificate. BHEL reserves the right to reject any welder without assigning any reason. All the expenditure in testing/qualification of the Contractor's welder shall be borne by Contractor.

14.1.6

Unsatisfactory and continuous poor performance may result in discontinuation of concerned welder.

14.1.7

The welded surface shall be cleaned of slag and painted with primer paint to prevent rusting, corrosion. For this consumables like paint /primer etc will be in the Contractor's scope.

14.1.8

HP joint fit-up, should be protected, where required, by use of tapes/protective paint as may be prescribed by BHEL. The Contractor shall arrange consumables like protective paints/tapes etc.

14.1.9

The Contractor shall maintain welding records in the form as prescribed by BHEL containing all necessary details, and submit the same to the BHEL Engineer as required. Interpretation of the BHEL Engineer regarding acceptability of the welds shall be final.

14.1.10

In the case of P-91 pipe welding, Contractor shall deploy welders having experience in welding of P-91 material. The welders engaged by Contractor if not qualified for P-91 welding will be trained by BHEL at BHEL welding research institute (WRI) Trichy and allowed to work only after passing the

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-IV WELDING, RADIOGRAPHY, NDT, PWHT

required test arranged by BHEL. All the expenditure towards such qualification including cost of training, traveling expenses, stay etc., shall be borne by the Contractor.

14.1.11

Joint fit up will be a stage of inspection. Where required, joints shall be offered for visual inspection after root run. Subsequent welding should be made only after the approval of root run.

14.1.12 SOCKET WELDING:

In execution of this work, considerable number of socket weld joints is involved. The exact quantity of such socket welds or probable variation in the quantum cannot be furnished. The tenderer shall take notice of this while quoting as no extra claim on this account will be entertained. The socket welding on HP parts/ HP piping shall be done by the IBR qualified welders. Contractor has to adhere to the procedures/specification as indicated in the drawing for socket welding.

14.1.13

Welding electrodes have to be stored in enclosures having temperature and humidity control arrangements. This enclosure shall meet BHEL specifications.

14.1.14

Welding electrodes, prior to their use, call for baking for specified period and will have to be held at specified temperature for specified period. Also, during execution, the welding electrodes have to be carried in portable ovens.

14.2 HEAT TREATMENT:

14.2.1

For the purpose of temperature recording of stress relieving process, thermocouples have to be attached to the weld joint. The number of temperature measuring points and locations shall be as per the standards of BHEL. Thermocouples have to be attached using capacitor discharge type portable thermocouple attachment unit. Contractor shall arrange sufficient number of thermocouple attachment units.

14.2.2

Contractor should provide temperature indicator / temperature recorder for measuring temperature during pre-heating for welding or for controlling temperature of metal for hot correction etc. The temperature recorders should be preferably of solid state type.

14.2.3

Heat treatment may be required to be carried out at any time (day or night) to ensure the continuity of the process. The Contractor shall make all necessary arrangements including labourer required for the same as per directions of BHEL.

14.2.4

In certain cases only the pre-heating of weld joints may be called for.

14.2.5

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-IV WELDING, RADIOGRAPHY, NDT, PWHT

For weld joints of heavy structural sections, if heat treatment is required, the same shall be carried out as part of the work.

14.2.6

Checking effectiveness of stress relieving by hardness tests (by digital hardness tester or other approved test methods as per BHEL Engineer's instruction) including necessary testing equipments is within the scope of the work / specification.

14.2.7

Preheating, inter-pass heating, post weld heating and stress relieving after welding are part of erection work and shall be performed by the Contractor in accordance with BHEL engineer's instructions. Where the electric resistance heating method is adopted Contractor shall make all arrangement including heating equipment with automatic recording devices, all heating elements, thermocouples and attachment units, graph sheets, thermal chucks, & insulating materials like mineral wool, asbestos cloth, ceramic beads, asbestos ropes etc, required for all heating and stress relieving works.

BHEL will provide the induction heating equipment set for SA 335 P-91 materials piping only. The set will comprise of following:

- (i) Main panel
- (ii) Capacitor panel
- (iii) Interconnection power & control cables between above panels
- (iv) 185 sq mm special connecting cable from capacitor panel output – 5m length.

Contractor shall provide the input electrical power connection including arrangements such as DB, cables etc, thermocouple pads, thermocouples and compensating cables, induction heating annealing cables (from the capacitor panel to joint and for wrapping around the weld joint) (spec: single core 240 sq mm, 1200a, 3khz), ceramic wool and other consumables etc as may be required. Quantum of annealing cable requirement will depend on many parameters e.g. weld joint size, heat input, type of connection i.e. series or parallel etc.

Likely supplier: Mansfield Cable Co. Noida (UP).

14.2.8

All the recorded graphs for heat treatment shall be handed over to BHEL/ IBR authorities and due clearances obtained.

14.2.9

During welding & post weld heat treatment of main steam piping (P-91 material), the induction heating process shall continue un-interrupted. Therefore, contractor shall arrange back-up DG set to take care of power interruptions during the process.

14.2.10

Results of these processes shall be verified/ validated as per requirements of BHEL/client.

14.3 NON DESTRUCTIVE EXAMINATION:

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-IV WELDING, RADIOGRAPHY, NDT, PWHT

14.3.1

Contractor shall provide all resources and make all arrangements for the radiographic examination of welds for this work. for reasons of safety, invariably the radiography work will be carried out after the normal working hours and close of other site activities only. in this regard, the Contractor has to adhere to the safety rules / regulations laid by barc authorities from time to time.

14.3.2

Radiography inspection of welds shall be performed in accordance with requirements and recommendation of BHEL Engineer. The minimum quantum of radiographic inspection shall be as per provision of IBR/BHEL's erection documents. They may, however be increased depending upon the performance of the individual welder at the discretion of BHEL Engineer/Boiler inspecting authority. Bidder shall also arrange the UT equipment with recording facility at his own cost. Usage of UT equipment shall be as per direction of BHEL engineer. Records of UT shall be produced as per site requirement.

14.3.3

All X-Ray / Gamma Ray films of weld joints shall be preserved properly and be handed over to BHEL/ IBR authorities and requisite clearances shall be obtained by the Contractor.

14.3.4

The field welded joints shall be subject to Dye-penetrant/MPT/RT/ other non-destructive examination as specified in the respective engineering documents/ as instructed by BHEL.

14.3.5

Wherever required, surface preparation, like smooth grinding of welded area, prior to Radiography shall be done. It may also become necessary to adopt inter-layer radiography/MPT/UT depending upon the site/ technical requirement necessitating interruptions in continuity of the work and making necessary arrangements for carrying out the above work. The Contractor shall take all this into account in his offer. The required NDT method/procedure will be decided by BHEL engineer at site.

14.3.6

Tenderer shall note that 100% radiography shall be taken on all high pressure welding till such time the welders' performance is found by BHEL Engineers to be satisfactory. Subsequently, subject to consistency in welder's performance, the percentage of radiography will be based on BHEL's standard practice/code requirement. the defects shall be rectified immediately and to the satisfaction of BHEL engineer. The decision of BHEL engineer regarding acceptance / rejecting the joints will be final and binding on the Contractor.

14.3.7

100% radiograph of certain sizes in piping have to be taken as per BHEL standards/ drawings.

14.3.8

For carrying out ultrasonic testing of welding joints of large size tubes and pipes, it will be necessary to prepare surface by grinding and buffing a smooth finish and contour as necessary. The Contractor's scope of work includes such preparation as incidental to work.

14.3.9

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-IV WELDING, RADIOGRAPHY, NDT, PWHT

After stress relieving 5% of UT for all critical lines and 2% of UT for other alloy steel lines to be taken to ensure soundness of joints particularly stress relieving cracks. No separate payment will be made.

14.3.10

Contractor may have to undertake radiography with cobalt-60 isotope camera in certain cases. However, for any reason if use of Cobalt-60 is not possible then these joints shall be checked by radiography after completion of welding up to suitable part of thickness with IR-192 other suitable source subsequently after completing the joint UT to be done. For this Contractor has to deploy level-II operator certified by BARC.

14.3.11

In the case of P-91 piping wherever radiography is not possible, alternatively ultrasonic test has to be carried out apart from other nde checks.

14.3.12

For piping of thickness less than 25 mm no radiography plugs will be provided radiography shots to be taken by double wall technique or any other method to be adopted in consultation with BHEL engineer at site.

14.3.13

No separate payment for any NDE activities (including radiography) will be made.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-V LINING & INSULATION

15 LINING AND INSULATION

Application of insulation, finishing, cladding and outer casing etc of the following:

1. Utility Boiler
2. Boiler auxiliaries including, but not limited to, ducts, fuel oil Equipments, fans etc
3. Boiler integral piping and tanks & vessels
4. Power cycle piping and critical piping including vessels and tanks & other equipments
5. LP piping and other equipments
6. Other equipments including BOIs, though not listed above but required for completion

15.1

The work shall conform to dimension and tolerances specified in the various drawing and documents that will be provided during the execution. if any portion of the work is found to be defective in workmanship or not conforming to drawings or other specifications, the Contractor shall dismantle and re-do the work duly replacing the defective materials at his cost, failing which the work will be got done by engaging other agencies or departmentally and recoveries will be deducted from Contractor's bills towards expenditure incurred including 30% departmental charges.

15.2

The terminal points as decided by BHEL shall be final and binding on the Contractor.

15.3

All insulation and refractory materials including iron components and outer sheet casing materials, cladding sheets etc required will be supplied by BHEL and the same have to be erected/ applied as per the drawings and specifications of BHEL by the Contractor.

15.4

The Contractor shall provide all the necessary scaffolding materials, temporary structures and necessary safety devices etc, during all stages of work. Scaffolding materials (poles, gratings etc) shall be of light weight construction. Contractor shall arrange steel pipes & clamps with accessories like base plate attachment, fixing pins, struts etc for scaffolding required for this work. However, BHEL's decision in this regard shall be final and binding. Contractor shall arrange the scaffolding materials in sufficient quantity.

The Contractor shall provide the required quantity of wire, nails, and planks for formwork and other materials for shuttering and curing works.

15.5

Contractor shall observe all precaution for laying, curing etc of pourable insulation. the Contractor at his own cost shall redo any defective works found.

15.6

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-V LINING & INSULATION

Wool insulation is received at site as loose bonded mattresses in standard sizes. These are to be dressed/cut to suite the equipments. Multiple layers of wool have to be applied as directed and as per drawings and specifications for all equipments/ systems covered under the scope of work.

15.6

Cutting & dressing of insulation bricks to suit the site area of application is incidental to work.

15.7

Removable type of insulation has to be provided for valves fittings, expansion joints etc as per drawing or as directed by BHEL Engineer.

15.8

The cladding and outer casing are aluminium sheets. All relevant specifications and procedures with regards to beading, sealing etc for aluminium sheets have to be adhered to.

15.9

Cladding/outer casing shall be fixed expeditiously, so as to avoid damage to the insulation from the weather.

15.10

The overlapping surface of outer casing/cladding sheet shall be coated with sealing compound, which will be supplied by BHEL free of cost.

15.11

To take care of bimetal corrosion due to variety of metals in contact of each other viz retainer to support, support to outer casing/cladding, cladding-to-cladding etc, suitable paints specified by BHEL, to be applied and/or neoprene rubber packing/strips or any other insert may have to be fixed as required.

15.12

The Contractor shall leave certain gaps and openings while doing the work as per the instructions of BHEL Engineer to facilitate inspection by boiler inspector or during commissioning to fix gauges, fittings, instruments etc. these gaps will have to be finished as per drawings at later date by the Contractor at his cost.

Contractor shall cut open works in needed as per BHEL Engineer's instructions during commissioning for inspection, checking and make good the works after inspection is over without any extra payment.

15.13

A log book shall be maintained by the Contractor for the clearance of the area for application of refractory and insulation. Where the Contractor does the work on his own accord without prior permission, the work should be re-done, at his own cost, where necessitated.

15.14

Wastage allowances for the material issued are envisaged as follows:

➤ a	Pourable & castable insulation	-	2%
-----	--------------------------------	---	----

BHEL-PSWR

Tender Specification No: BHE/PW/PUR/DHJOI-BLR/966, 967

Technical Conditions of Contract –Volume I A (Part I : Contract Specific Details)

Page 136

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-V LINING & INSULATION

➤ b	Insulation bricks and motor	-	2%
➤ c	Wool mattresses	-	2%
➤ d	Cladding sheets	-	2%

The wastage allowance will be applicable on the net issued quantity i.e. total quantity issued reduced by the quantity returned to stores as unused/fresh item. Contractor shall reconcile the material issues periodically as prescribed by BHEL site

15.15

The following works are also included in the scope of this contract.

Cutting of cladding sheets as per the profile of the equipment and painting on inner surface two coats of bituminous paint. Paint will be supplied by Contractor.

Cutting of the wool mattresses to the required shape and application of finishing cement of required thickness wherever required.

15.16

Insulation work of temporary piping for alkali boil out, steam blowing and chemical cleaning has to be carried out at site. The same have to be removed and returned to the BHEL stores after the completion of activity. Rates quoted for application of wool for boiler and auxiliaries will be applicable for this work also. No separate payment will be made for removal of temporary insulation and return of the same to BHEL stores/yard.

15.17

In certain instances, co-ordinated/phased application of castable refractory/ insulation on pressure parts etc may be necessitated in consideration of sequence of activities of other erection agencies. Contractor shall do such phased work as may be directed by BHEL.

15.18

Prior to application of refractory bituminous painting on the pressure parts and other area is under Contractor scope. The bituminous paint will be supplied by Contractor. No separate payment will be made for application of paint.

15.19

HRSG casing, inlet and outlet ducts have to be fully insulated at site with ceramic wool and SS cladding on gas flow path side.

15.20

application of wool insulation, sheet metal cladding, welding of hooks/supports to hold insulation covered under this contract, shall include, but are not limited to, the following :-

- a) Where indicated, removable type of insulation to be provided for valves, expansion joints, etc. as per the drawings or as directed by BHEL engineer.
- b) Wool insulations are received at site as bonded and unbounded mattresses in standard sizes. These are to be dressed / cut to suit work by the contractor.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-V LINING & INSULATION

- c) Application of insulation and refractory works and sheet metal covering as given in various drawings/ specifications of BHEL, supplied to the contractor.
- d) Outer sheet cladding by fabrication of aluminum sheets to the sizes and shapes specified in drawings, beading, swaging, beveling of sheets, crowning the sheets, if necessary, fixing the same to supports, over wool insulation with screws/retainers as specified in BHEL drawings or as instructed by BHEL engineer.
- e) Welding of hooks/supports on equipment including on pr. parts and piping to support wool insulation, as per the drawings or as instructed by BHEL engineers.
- f) Painting the inner side of aluminum/GI/steel cladding, with anticorrosive paint as specified. The required paint and thinner is in the contractor's scope. Also, all other accessories consumables for painting, cleaning the surfaces etc shall also be arranged by the contractor.
- g) The contractor shall leave certain gaps and openings while doing the work as per the instructions of BHEL engineer to facilitate inspection by boiler inspector or cut open during commissioning to fix gauges, fittings, and instruments. These gaps will have to be finished as per drawings at a later date by the contractor at no extra cost to BHEL.
- h) The skin casing plate's scalloped bars and other materials that are to be matched with the erected components have to be cut and re-welded from the fabricated pieces as incidental to work.
- i) wastage allowance for the materials issued shall be as under :-
 - Refractory 2%
 - Wool insulation 2%
 - Cladding sheets 2%
- j) The cladding inside the inlet duct, casings etc are of stainless steel material. Some trimming/ finishing required at site during fixing shall also be done as part of work.

15.21

Application of lining and insulation on all piping covered under this Specification is also the part of this work. Similarly, it is applicable for Lining and insulation of TG side auxiliaries such as heaters, de-aerators Etc. However, application of spray insulation on turbine is not in the scope of work.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VI PAINTING

16 PAINTING

OPaL/EIL Specification for Shop & Field Painting **SECTION C: 4.9, SPECIFICATION No. 6987-0642-PT-F09 Rev 0** with regard to surface preparation and final painting with colour codes / scheme for surface preparation and finish paints coating including primer coating for shop and field painting is attached separately along with this tender specification for ready reference. Contractor shall carry out surface preparation and final painting works as per customer specification and instruction of BHEL engineer at site.

16.1

All the primer, thinner & paints for final painting and all other consumables like brush, cleaning agents etc and all T&P including scaffolding materials, manpower, supervision is in contractor's scope.

16.2

Components of the boiler & auxiliaries will in general be supplied painted by BHEL manufacturing units as per their standard applicable painting schemes. Contractor shall carry out primer and finish painting coats and DFT requirement with colour codes & specifications as per requirement of customer.

All exposed metal parts of the equipment including piping, structures, railings etc. wherever applicable, after installation unless otherwise surface protected, shall be first painted with at least one coat of suitable primer which matches the shop primer paint used, after thoroughly cleaning all such parts of all dirt, rust, scales, greases, oils and other foreign materials by wire brushing, scraping or sand blasting, and the same being inspected and approved by BHEL engineer for painting. Afterwards, the above parts shall be finished with two coats of alloyed resin machinery enamel paints.

16.3

Painting of welded areas / painting of areas exposed after removal of temporary supports / touch-up painting on damaged areas of employer's structures, where inter-connection, welding / modification etc. has been carried out by the bidder.

- (a.) clean the surface to remove flux spatters and loose rust, loose coatings in the adjoining areas of weld seams by wire brush and emery paper.
- (b.) painting procedure to be followed as mentioned above for touch-up painting on damaged areas.

16.4

The scope of work includes painting of colour bands, lettering, marking and signs for direction of flow/rotation, names etc of approved colours as per the standard colour codes and specifications specified in tender specification or as advised by BHEL/customer engineer at site for the equipments/ components covered in these specifications. Applicable paints and primer shall be supplied by BHEL.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VI PAINTING

16.5

All exposed metal parts of the equipment including piping, structures, hand railing, grating etc shall be thoroughly cleaned off dust, rust, scales and other foreign materials by manual or mechanized wire brushing, scrapping, sand blasting etc and the same being inspected and approved by BHEL/customer engineer before application of primer. Afterwards, the above parts shall be finish painted with specified number of coats as per specification.

16.6

In certain isolated instances where it is not possible to clean the equipments as explained above, cleaning by grinding might have to be resorted to. No damage to the equipment/components should be caused.

16.7

Surface to be painted should be free of oil and grease. It should be removed by using suitable cleaning agents including permitted solvents. Surface cleaned by chemical agent, if required, shall be treated further as prescribed in use of such cleaning agents. The Contractor at his own cost shall provide all the consumables and application implements.

16.8

During the preparation of surface, if the shop coat is damage by chemical cleaning or by mechanical means, Contractor shall repair the same free of cost to BHEL.

16.9

Specified drying time shall be permitted from one to another coat.

16.10

This work requires working at higher altitudes from ground level to as high as 90 m and more. The work spread is also substantial involving substantial run of structures and piping. Contractor shall take sufficient precautions to avoid any accident and hazard in all respects. The ropes, ladders, scaffolding materials, clamps etc and climber used should be of standard quality for safe and smooth execution of work.

16.11

Contractor shall carry out the work in such a way that other erected equipment, structure, civil foundations and other property are not damaged. For damages in any of such cases due to lapses by Contractor, BHEL shall have the right to recover the cost of such damages from the Contractor.

16.12

Contractor shall take due care to cover/protect the equipment which are already painted while carrying out the painting of other adjacent equipment. If so happens, it shall be cleaned and repainted by the Contractor without any extra charges.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VI PAINTING

16.13

In general, painting of structural parts and colour bands, lettering, marking of direction of flow/rotation etc will be carried out by brush painting. However, areas/equipments inaccessible for manual painting have to be painted by spray painting. The decision of BHEL engineer, in this regard, shall be final and binding on the Contractor. For the purpose of spray painting, air at one point will be made available by BHEL free. Laying of air hose pipe and any other line required shall be done by Contractor at his cost. The Contractor shall provide spray equipment set.

16.14

The Contractor shall provide all the necessary scaffolding materials, temporary structures and necessary safety devices etc, during execution of the work.

16.15

Final painting work shall be started after obtaining clearance from BHEL engineers and as per his instructions.

16.16 PRIMER AND PAINTS FOR FINAL PAINTING

Supply of Paints/Primer/Thinner and application of paints for final painting and all other consumables like brush, cleaning agents etc and all T&P including scaffolding materials, manpower, and supervision is in contractor's scope.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VII TESTING, PRE-COMMISSIONING, COMMISSIONING

17.1

Testing, pre-commissioning, & commissioning will involve, though not limited to these, various testing e.g. hydro-static pressure, pressure decay tests, leak test, trial runs of equipments; flushing by air, water, oil, steam as applicable; checking/setting various clearances/ parameters, ensuring operation of various equipments free of undue restrictions, chemical (**EDTA**) cleaning & alkali boil out of boiler, steam blowing of the boiler and the critical piping, floating of safety valves, coal firing, trial operation and loading etc are some of these activities. All the activities for commissioning of the set, as informed by BHEL from time to time shall be completed.

17.2

All these tests should be repeated till all the equipments satisfy the requirement / obligations of BHEL to their client and also the relevant statutory authority.

17.3

Contractor shall lay / install necessary temporary piping, pumps, valves, blanks, gauges, cables, switches etc for conduct of hydraulic / pressure test, chemical cleaning, steam / air blowing etc. this may involve cutting of some portion of existing piping / valves, placing of rubber wedges / blanks in the valves and other openings, fabrication and installation of temporary tanks for chemical mixing, temporary access platforms to mixing tanks etc. Where required, bends have to be fabricated / formed at site from random length / size of pipes / structural steel. Temporary installation itself has to be tested, tried, and subject to non-destructive examinations as per the instructions of BHEL as part of work.

No payment will be made for temporary installations made for hydraulic testing of various systems & piping. Similarly no payment will be made for electrical installations made for any temporary system.

17.4

All materials, equipments necessary for installation of temporary system as above will be supplied by BHEL as free returnable issue in random sizes / lengths. However, servicing, fabrication, erection, dismantling of the same after completion of the process, and handing over back to BHEL stores will be the responsibility of the Contractor.

In accounting of materials following wastage allowances are provided:

1. Structural items	:	5%
2. Pipes	:	3%

No wastage allowance for valves & other equipments.

17.5

Fabrication, fit-up, pre-heating, welding, post-weld heating and post-weld-heat treatment if any, of requisite blanks for conduct of hydraulic test / leakage test is part of work. Similarly, removal of blanks, restoration and normalization of the concerned system / line is to be done as part of work. BHEL will provide the material for blanks free of charge. No separate payment is envisaged for these activities.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VII TESTING, PRE-COMMISSIONING, COMMISSIONING

17.6

Overhauling, cleaning, servicing of tanks, pumps, equipments, valves, during erection and commissioning stages are in the scope of work. Gaskets, packing & spares for replacement will be provided free of charges by BHEL.

17.7

After chemical cleaning / pickling of lubricating system (including oil piping, oil tank and other fittings) of rotating machines, oil flushing for lubricating systems as per instructions of BHEL engineer shall be carried out. Cleaning of oil tank of lubricating oil system of rotating machinery before and after oil flushing is in the scope of work.

17.8

Transportation of oil drums from customer's / BHEL's stores, filling of oil for flushing, first fill of lubricants and subsequent topping up during trials, tests and commissioning is included in the scope of this contract. The Contractor shall have to return all the empty drums to the customer / BHEL stores. Similarly, for various pre-commissioning / commissioning activities / processes mentioned in various clauses, transport of chemicals from BHEL / customer's stores, charging of chemicals into the system and returning of remaining chemicals and the empty containers of the chemicals to customer / BHEL stores is the responsibility of the Contractor.

17.9

During trial runs/ tests, pre-commissioning / commissioning, replacing / changing mechanical / other seals of equipments like pumps, removal and cleaning / replacing of filters etc is within the scope of work. Replacement spares for this purpose will be provided by BHEL.

17.10

In case any defect is noticed during tests, trial runs of all equipments and their auxiliaries, such as interferences, rubbing, loose components, abnormal noise or vibration, strain on connected equipment etc the Contractor shall immediately attend to these defects and take necessary corrective measures. Readjustment and/or realignment, if necessary, shall be done as per BHEL engineer's instructions. Claim, if any, for these works shall be governed by relevant clauses of 'General Conditions of Contract provided the cause of such work is not attributable to the Contractor.

17.11

- ✓ Contractor shall cut / open / dismantle work, if needed, as per BHEL Engineer's instructions during commissioning for inspection, checking and make good the works after inspection is over.
- ✓ Similarly, during the course of erection, if certain portion of equipments erected by the Contractor has to be undone for enabling other Contractors / agencies of BHEL / customer to carry out their work, Contractor shall carry out such jobs expeditiously and promptly and make good the job after completion of work by other Contractors / agencies of BHEL / customer as per BHEL engineer's / agencies of BHEL / customers instructions. Claims, if any, in this regard shall be governed relevant clauses of 'General Conditions of Contract

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VII TESTING, PRE-COMMISSIONING, COMMISSIONING

17.12

During this period, though BHEL/ client's staff will also be associated in the work, the Contractor's responsibility will be to arrange for complete requirement of men and required tools and plants, consumables, scaffolding and approaches etc till such time the commissioned unit undergoes trial operations.

17.13

Commissioning activities will continue till the completion of trial operation. During this period Contractor shall make available the services of separate dedicated workforce comprising of suitable skilled and semi-skilled / un-skilled workmen and supervisory staff alongwith necessary tools and plants, consumables etc.

17.14

It shall be specifically noted that the Contractor may have to work round the clock during the pre-commissioning and commissioning period alongwith BHEL Engineers and hence considerable overtime payment is involved. The Contractor's quoted rates shall be inclusive of all these factors.

17.15

The Contractor shall carry out any other tests as desired by BHEL engineer on erected equipment covered under the scope of this contract during testing, pre-commissioning and commissioning, to demonstrate the completion of any part or whole of work performed by the Contractor.

17.16

At various stages of completion boiler has to be preserved against corrosion either by wet preservation or by dry preservation as per the requirement of BHEL Engineer. Contractor shall carry out the entire incidental jobs like filling up of water, dozing of chemicals and pressurizing the system to the required pressure, change of gas refills etc. The boilers have a permanent N₂ blanketing arrangement.

During this period, though BHEL/ client's staff will also be associated in the work, the Contractor's responsibility will be to arrange for complete requirement of men and required tools and plants, consumables, scaffolding and approaches etc., till such time the commissioned unit is taken over.

17.17

Commissioning activities will continue till the completion of trial run, trial operation. During this period Contractor shall make available the services of separate dedicated labor force comprising of suitable skilled and semi/un-skilled hands along with necessary tools and plants, consumables etc.

17.18

It shall be specifically noted that the Contractor may have to work round the clock during the pre-commissioning and commissioning period along with BHEL engineers and hence considerable overtime payment is involved. The Contractor's quoted rates shall be inclusive of all these factors.

17.19

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VII TESTING, PRE-COMMISSIONING, COMMISSIONING

Conducting of performance guarantee test is in the scope of work. Contractor shall install all necessary tapping points, instruments etc and provide necessary assistance in this regard.

In case PG test is getting delayed beyond the contract period (normal plus extension if any) due to reasons not attributable to the Contractor, PG test issue will be mutually discussed and decided. However installation of necessary tapping points, impulse pipes, approaches etc are to be completed by the Contractor.

17.20

The Contractor shall carry out any other tests as desired by BHEL engineer on erected equipment covered under the scope of this contract during testing, pre-commissioning and commissioning, to demonstrate the completion of any part or whole of work performed by the Contractor.

TECHNICAL CONDITIONS OF CONTRACT (TCC)

Chapter-VIII PRESERVATION & PROTECTION OF COMPONENTS

18.2 PRESERVATION & PROTECTION OF COMPONENTS

At all stages of work, equipments/materials in the custody of Contractor, including those erected, will have to be preserved as per the instructions of BHEL. Necessary preservation agents including the primer & paint, for the above work shall be provided by the Contractor.

18.3

The Contractor shall make suitable security arrangements including employment of security personnel and ensure protection of all materials/ equipment in their custody and installed equipments from theft/fire/pilferage and any other damages and losses.

18.4

Contractor shall collect all scrap materials periodically from various area of work site, deposit the same at one place earmarked at site or shift the same to a place earmarked in BHEL/ client's stores. In case of failure of Contractor in compliance of this requirement, BHEL will make suitable arrangement at Contractor's risk and cost.

18.5

The entire surplus, damaged, unused materials, packaging materials / containers, special transporting frames, gunny bags, etc shall be returned to BHEL stores by the Contractor.

18.6

The Contractor shall not waste any materials issued to him. In case it is observed at any stage that the wastage/excess utilization of materials is not within the permissible limits, recovery for the excess quantity used or wasted will be effected with departmental charges from the Contractor. Decision of BHEL on this will be final and binding on the Contractor.

18.7

For any class of work for which no specifications have been laid down in these specifications, work shall be executed as per the instructions of BHEL.