

Additional Requirements for BHEL TENDER with Ref: EN-BSK-191

1. The enquiry items (Barstocks- IBR Attested) of Grade SA182F22CL3 shall be supplied as per the below indicated 'Length Requirement'.

Item	Material	MATL SPECN	TDC	Process	Qty	Unit	BHEL Length Requirement
10	153393080000	DIA 50.0 MM - SA182F22CL3	TDC:0:309/12	Rolled Route	6,000	Kg	06 Meter Fixed Length
20	153391730000	DIA 63.0 MM - SA182F22CL3	TDC:0:309/12	Rolled Route	14,000	Kg	Between 04 to 06 Meter
30	153393790000	DIA 75 - SA182F22CL3	TDC:0:309/12	Rolled Route	12,000	Kg	Between 04 to 06 Meter
40	153391940000	DIA 80.0 MM - SA182F22CL3	TDC:0:309/12	Rolled Route	25,000	Kg	06 Meter Fixed Length
50	153391950000	DIA 100.0 MM - SA182F22CL3	TDC:0:309/12	Rolled Route	16,000	Kg	06 Meter Fixed Length
60	153393700000	DIA 125 MM SA182F22CL3	TDC:0:404/19	Forged Route	5,000	Kg	Between 02 to 03 Meter
70	153393710000	DIA 140 SA182F22CL3	TDC:0:404/19	Forged Route	9,000	Kg	Between 02 to 03 Meter
80	153392380000	DIA 150 -SA182F22CL3	TDC:0:404/19	Forged Route	4,000	Kg	Between 02 to 03 Meter
90	153393350000	DIA 165 SA182F22CL3 (ATTEST)	TDC:0:404/19	Forged Route	10,000	Kg	Between 02 to 03 Meter
100	153392390000	DIA 200 SA182F22CL3	TDC:0:404/19	Forged Route	14,000	Kg	Between 02 to 03 Meter
110	153393520000	DIA 210 SA182F22CL3 (ATTEST)	TDC:0:404/19	Forged Route	6,500	Kg	Between 02 to 03 Meter
120	153393180000	DIA 250 - SA182F22CL3(ATTEST)	TDC:0:404/19	Forged Route	5,000	Kg	Between 02 to 03 Meter
				Total	126,500		

The Acceptance/Rejection of Offers for any deviation from the above condition shall be done post-tender opening at the time of 'Techno-Commercial Evaluation'.

2. Delivery Schedule shall be within 12 Weeks from the Date of Purchase Order.