

SECTION - 1

SCOPE, SPECIFIC TECHNICAL REQUIREMENTS & QUANTITIES

1.1.0 SCOPE

1.1.1 The scope of work under this specification is civil works for Boundary wall and other allied works for Earth Electrode Station at Village Serav, Tahasil Bah, District Agra associated with +-800kV NE-Agra HVDC Project at Agra in Uttar Pradesh, being executed by BHEL on turnkey basis. The Customer is Power Grid Corporation of India Ltd.

1.1.2 The Civil Works shall generally include, *but not limited to*, following:

- (i) Boundary wall
- (ii) Main Gate
- (iii) Any other work felt necessary for the project in Earth Electrode Station area.

1.1.3 The works to be performed in the above constructions include preparation of bar bending schedules, based on the drawings released for construction and getting the same approved by the Engineer-in-charge plus the execution of the work including providing of all labour, supervision, materials, scaffolding, power, fuel, construction equipments, tools and plants, supplies, transportation, all incidental items necessary for successful completion of the work including contractor's supervision and in strict accordance with the drawings and specifications and with inspection and testing standards. The nature of work shall generally involve excavation in all type of soil including dewatering, shoring, strutting, backfilling with available excavated earth around completed structures, disposal of surplus soil, concreting including reinforcement and formwork, providing necessary steel embedments and other inserts, barbed wire, gates, gratings, drains, brick work, plaster, painting etc., all complete as per detailed specification, drawings and directions of Engineer-in-charge.

1.2.0 SPECIFIC TECHNICAL REQUIREMENT

1.2.1 The specific technical requirements for the execution of civil works shall be as per PGCIL Technical Specification (Refer SECTION 3) and latest CPWD Specifications. **In case of any difference between PGCIL Technical Specification & latest CPWD Specifications, the provisions of PGCIL Specification shall be considered.**

1.3.0 BILL OF QUANTITIES

- 1.3.1 The Bill of Quantity-cum-Price Schedule shall be as per page 1.3 to page 1.5.
- 1.3.2 The quantities indicated in the 'Bill of Quantity-cum-Price Schedule' are indicative and can vary to any extent. Contractor shall not be entitled for any claim for any such variation in the quantities.
- 1.3.3 The provision of Bill of Quantity-cum-Price Schedule, specification and drawings shall be read in conjunction with each other and in case of conflict amongst them, the clarification shall be obtained from the Engineer-in-charge whose decision shall be final and binding.
- 1.3.4 Method of measurement:
 - 1.3.4.1 Excavation shall be measured in cubic meters. The lateral dimensions to be considered for working out excavation quantity shall be the PCC dimension below the footing as per approved drawing. Nothing extra shall be paid for slope cutting, etc. Backfilling & disposal qtys shall be worked out based on the above dimensions only.
 - 1.3.4.2 For other items, unless otherwise described the method of measurement as described in 'Method of Measurement of Building and Civil Engineering Works'-IS 1200(Part I to XXV) latest edition of BIS shall be followed.