

Scope of Work and Payment

S. No.	Scope	Confirmation by Calibration Agency
1	Calibration of the following equipment: As enclosed annexure – 3 Vendor must have capability of testing all instruments as per annexure – 3.	Complied/ Not Complied
2	The calibration work will have to be completed within 30 days from date of P.O. placement at BHEL Bhopal works. Delay in execution of work may cause penalty of 0.5% of contract value per week upto maximum of 10%.	Complied/ Not Complied
3	All the ranges shall be covered during calibration. Please refer the Calibration range enclosed in Annexure-3. Should there be any comments or range which are technically not feasible; the same may please be brought out.	Complied/ Not Complied
4	The instrument may be calibrated at the works of TEM, block 2, BHEL Bhopal . All items required to calibrate items shall be brought by the Calibration Agency. Any facility or necessary arrangement required for calibration of Items shall be clearly written in submitted offer.	Complied/ Not Complied
5	The Standard Equipment/ Instruments used for calibration shall have capability (class/accuracy/stability) to maintain proper accuracy ratio during calibration and traceability to National/ International Standards. Calibration agency to specify in their offer. Documents for traceability of standard and instrument used for calibration shall be submitted with offer.	Complied/ Not Complied
6	Calibration stickers bearing equipment details, calibration date, calibration status put on the Instruments.	Complied/ Not Complied
7	Detail calibration certificate of the instrument shall be prepared in line with ISO 17025:2005/as per applicable standard and should be submitted within 7 days from date of completion of calibration.	Complied/ Not Complied
8	The payment shall be made after completion of work and submission of Final Invoice/ Bill.	Agreed/ Not Agreed
9	Deviation, if any, shall be clearly brought out.	Complied/ Not Complied
10	The Party shall confirm all the above points failing which their offer may not be considered.	Complied/ Not Complied
11	CT/PT's may be tested as per standard IS 2705/IS 3156 respectively.	Complied/ Not Complied

