

TENDER

(NIT NO. TA/TCL/45/19-20)

FOR

**MISCELLANEOUS ALUMINIUM WORKS
IN KASTURBA HOSPITAL, HABIBGANJ
N'HOOD IN BHEL BHOPAL TOWNSHIP.**

PRICE BID

SECTION - VI



**TOWNSHIP CIVIL MAINTENANCE
BHARAT HEAVY ELECTRICALS LIMITED**

**(A Government of India Undertaking)
BHOPAL - 462 022 (M.P)**

PREAMBLE OF PRICE BID

1.0. This Price Bid consists of three Schedules:

1.1 Schedule A

Schedule A consists of single Annexure :

1) Annexure-I includes items based on GST Compliant DSR-2012, Rate analysis and Budgetary offer.

Bidders are requested to quote their rates in Percentage above/below/at Par for Annexure-I.

1.2 Schedule B

Schedule B gives the details of free issue materials given by BHEL.

1.3 Schedule C

Schedule C gives the details of Tools & Tackles provided by BHEL on Chargeable Basis.

2.0 The work to be carried out under the contract shall, except as otherwise provided in tender conditions, include all labour, materials, tools, plant, equipment, and transport which may be required in preparation of and for full & entire execution and completion of the Works. The descriptions given in the Schedule of Quantities shall, unless otherwise stated, be held to include waste on materials, carriage and cartage, carrying in return of empties, hoisting, setting, fitting and fixing in position and all other labours necessary in and for the full and entire execution and completion as aforesaid in accordance with good practice and recognized principles as laid down in Technical Specification & elsewhere in Tender Specification.

3.0 The price bid should not contain any condition. Conditional price Bids shall be summarily rejected.

4.0 The bidder should not leave any column blank in Price Schedules.

5.0 Price Quoted shall include all taxes, & duties except GST.

6.0 **Unless otherwise specified in the items involving cement or reinforcement steel, these items shall be issued free of cost by BHEL.**



TOWNSHIP CIVIL MAINT. & CONST. DIVISION

SCHEDULE 'A'

Annexure: I

Name of work : Miscellaneous aluminium works in Kasturba Hospital, Habibganj N'Hood in BHEL Bhopal Township.

S.No	It. Code	Description of items	Qty.	Unit	Rate	Amount
1		Dismantling doors, windows and clerestory windows (steel or wood) shutter including chokhats, architrave, holdfasts, etc. complete and stacking within 50 metres lead:				
	15.12.1	Of area 3 sqm and below.	17.00	each	101.70	1,728.90
2		Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
i		For fixed portion				
	21.1.1.1 RA	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	425.00	kg	294.19	1,25,030.75
ii		For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)				
	21.1.2.1 RA	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	120.00	kg	338.31	40,597.20

[illegible]

SCHEDULE – “B”								
Name of work : Miscellaneous aluminium works in Kasturba Hospital, Habibganj N'Hood in BHEL Bhopal Township.								
----- NIL-----								
SCHEDULE – “C”								
----- NIL-----								
Signature of Contractor								