

ANNEXURE- HV/BHAVINI/001		
1	Machine Type	AC Type High Voltage Tester
2	Output Voltage	0 to 100kV AC
3	Capacity	Leakage current 100mA Max on H.V. Side
4	Operating Voltage	415V, Single Phase, 50Hz
5	Duty Cycle	5min ON/ 15min OFF
6	Indications	Indication required for Mains On, HV On with Buzzer, HV off
7	Indication Meter	All indication meter input/output should be Digital Meter.
8	Transformer cooling	Oil cooled (First time oil to be filled by supplier)
9	Variable Reactor	With Motorized control
12	Mobility	Portable/Suitable for transportation with lifting arrangement
	Buzzer	Buzzer to be ON while carrying out HV Test on job.
	Power Cable	Input Power Cable to be provided
		HT Cable for testing purposes to be provided
		Earthing cable for testing purposes to be provided
		Suitable Cover for Bushing stand, motorized panel stand and control unit to be provided for avoiding dust ingress
		Arrangement to be provided
13	Warranty	Two Years from date of dispatch
14	Test Certificate	To be provided
16	Operation & Maintenance Manual	To be provided
17	Mandatory Spares (if any)	To be provided
18	Delivery	FOR Rudrapur
Any other item not specified above but need for successful functioning of equipment to be provided by vendor		

Mr. S. S. S.
10/11/17