

Procurement and installation of split Air Conditioner (SAC) at BHEL-ASSCP, Gwalpahari, Gurgaon

S.No	Items	Qty	Unit	Remark
A	Supply, installation, testing and commissioning of 2TR,220-240 volt., three star rated (minimum), non-invertor split air – conditioning units with stabilizer with rotary compressor complete with indoor and outdoor units comprising of blowers, motors. <u>COPPER cooling (tube) coil, COPPER condenser (tube) coil,</u> condenser fan and copper pipes (3 Mtr/10 feet per AC), PVC drain pipe (3 Mtr/10 feet per AC), control cable (suitable size) from indoor to outdoor units, Suitable size of heavy duty MS stand for outdoor unit. Pressure/leak testing with gas and other accessories as required. AC Make: - Blue star, Hitachi, O General, Voltas, Panasonic Stabilizer make: -Blue bird, Legrand, V guard Note- The Units of the BEE star rating should be ≥ 3 star 2018 rating. Warranty-1 year on complete AC and 4 years on compressor	8	Set	Rate to be quoted as per annexure -1

Procurement and installation of window Air Conditioner (WAC) at ASSCP, Gurgaon

S.No	Items	Qty	Unit	Remark
B	Supply, installation, testing and commissioning of 1.5 TR,220-240 volt., three star rated (minimum), non-invertor window air –conditioning units with Stabilizer with rotary compressor having <u>copper cooling (tube) coil</u> AC Make: - Blue star, Hitachi, O General, Voltas, Panasonic Stabilizer make: -Blue bird, Legrand, V guard Note -The Units of the BEE star rating should be ≥ 3 star 2018 rating Warranty-1 year on complete AC and 4 years on compressor	2	Set	Rate to be quoted as per annexure -1

Note- Vendor is required to deliver and install the AC's at BHEL-ASSCP, Gwalpahari, Gurgaon.

Ankur

Bharat Heavy Electricals Limited
Amorphous Silicon Solar Cell Plant

Annexure -1

Reference for 2 Ton Split AC quotation

Sl.No.	Specifications/Parameters	Rate per unit	Quantity	GST rate	Amount
1	Type -Split AC, Tonnage -2 ton Condenser tubing- Copper make BEE Star rating ≥ 3 star rating 2018 AC Make - Blue star, Hitachi, O General, Voltas, , Panasonic Drain pipe, Copper Pipe- 3 Mtr/10 Feet per AC to be included in offer Warranty-1 year on complete AC and 4 years on compressor				
2	Accessories: a) Stabilizer per AC Stabilizer make: -Blue bird, Legrand, V guard				
	b) Wall Floor/outdoor Stand per AC				
3	Installation charges				
4	Freight charges				

Reference for 1.5 Ton Window AC quotation

Sl.No.	Specifications/Parameters	Rate per unit	Quantity	GST rate	Amount
1	Type-Window AC, Tonnage -1.5 ton Condenser tubing - Copper make BEE Star rating ≥ 3 star rating 2018 Make - Blue star, Hitachi, O General, Voltas, Panasonic Warranty-1 year on complete AC and 4 years on compressor				
2	Accessories: Stabilizer per AC Stabilizer make: -Blue bird, Legrand, V guard				
3	Installation charges				
4	Freight charges				

Note- Vendor is required to deliver and install the AC's at BHEL-ASSCP, Gwalpahari, Gurgaon.

