

L-1, bidder shall be considered for award of BOS-1 i.e 40 MW site on 'total cost to BHEL' as per BOQ-A as below.

BOQ - A for BOS-1(i.e 40 MW Site)			
Name of work : Supply, E&C of BOS and O&M (for Five years) of BOS" for 1x65MW of Solar PV plant of NLC at Neyveli, Cuddalore District, Tamilnadu.			
Item. NO	DESCRIPTION OF ITEM	UNIT	QTY
SUPPLY ITEMS			
1.00	Supply of HDPE conduits,cable ties, PVC pipes,hardware,tray supports etc		
1.01	Supply of 200MM cable ties (1 PAC=100 Pcs)	PAC	1250
1.02	Supply of 63MM Dia HDPE Pipe (double walled corrugated (DWC) pipe)	Meter	12000
1.03	Supply of PVC pipes (200mm Dia)	Meter	500
1.04	Supply of Aluminium Trefoil clamps for 33 KV (UE) 1Cx 300 Sq mm HT Cable	NO	5400
1.05	Supply of Aluminium Trefoil clamps for 1.1 KV 1CX630 Sq mm Cable	NO	2500
2.00	Supply of 33KV Metering Yard Equipments		
2.01	Supply of ACSR conductor for carrying 800A current at 33kV voltage level	Meter	350
2.03	Supply of Clamps & Connectors & bolts & nuts for interconnection of 33kV cables,CTs,PTs,GOS isolator,LA etc. with ACSR conductor as per attached metering yard layout (PY-LE-1-M088-2019-01) & TCC Cl. No 4.1(2).	SET	2
2.04	Supply of Surge Supressor for metering yard (1 phase)	NO	6
2.05	Supply of 800A, 25KA for 1sec GOS Isolator with Earth Switch	NO	2
2.07	Supply of 800A/5A Current Transformer (2Core),CL-0.2s (1 phase)	NO	18
2.09	Supply of Voltage Transformer 50VA with Jumper (1 phase) (33kV/110/ $\sqrt{3}$ V)	NO	18
2.10	Supply of GI Structural Steel for 33 KV metering yard for mounting of CTs,PTs,GOS isolator,LAs, supporting ACSR conductor, 33kV cable support etc.	KG	12000
3	Supply items of module cleaning system:		
3.01	Supply of Pipes & Fittings for Bore well	NO	7
3.02	Supply of 3Hp or higher submeesible pump with Motor shall meet required flow nad pressure	NO	7
3.03	Supply of Single phase starter	NO	7
3.04	Supply of Storage Tank 1500L (Syntex or equavllent PVC storage tank)	NO	7
3.05	Supply of HDPE Pipe for Module Cleaning System,size shall be suitable require flow and pressure.	Meter	6000

L-1, bidder shall be considered for award of BOS-1 i.e 40 MW site on 'total cost to BHEL' as per BOQ-A as below.

BOQ - A for BOS-1(i.e 40 MW Site)			
Name of work : Supply, E&C of BOS and O&M (for Five years) of BOS" for 1x65MW of Solar PV plant of NLC at Neyveli, Cuddalore District, Tamilnadu.			
Item. NO	DESCRIPTION OF ITEM	UNIT	QTY
3.06	Supply of 1/2 inch Nipple	NO	200
3.07	Supply of Hose 1/2 inch with gun	Meter	2500
3.08	Supply of Valves for Module Cleaning System as per the BOQ indicated in TCC (Cl.4.5) Sl.no-4.	LOT	1
3.09	Supply of Reducer 2inch to 1/2 inch	NO	120
3.10	Supply of 3HP or Higher Booster pump with motor with starter arragnment shall meet required flow nad pressure	NO	7
3.11	Supply of Flow meter	NO	7
3.12	Supply of Level indicater(Analog)	NO	7
3.13	Supply of Accessories for pipe fitting as per the BOQ indicated in TCC (Cl.4.5).	SET	7
3.14	Supply of 3C X 6 SQMM Cu flexible cable suitable for submerged in water.	Meter	1000
4	Supply fo Miscellanious items		
4.01	Furniture items as per the BOQ indicated in TCC (Cl.4.11)	SET	1
4.02	Supply of Board for electric shock	NO	9
4.03	Supply of Board for artificial respiration	NO	9
4.04	Supply of Board displaying dos and donts.	NO	9
4.05	Supply of Board displaying fire extinguishers data	NO	9
4.06	Supply of No smoking board	NO	10
4.07	Supply of Board showing list of O&M staff with names	NO	1
4.08	Supply of Board showing list of contact details	NO	2
4.09	Supply of Danger boards with details such as value	NO	48
4.10	Supply of Identification boards, of suitable sizes	NO	16
4.11	Supply of Checkered plate 6mm thick width-1000mm	KG	1200
4.12	Supply of DCP type 9kG capacity Fire Extinguishers with SBC powder cartridge operated (200GM, IS 4947) with controllable discharge mechanism class B rating 34B as per IS 15683. including all necessary statutory certificates	NO	16
4.13	Two fire bucket with suitable MS Stand sets	NO	9

L-1, bidder shall be considered for award of BOS-1 i.e 40 MW site on 'total cost to BHEL' as per BOQ-A as below.

BOQ - A for BOS-1(i.e 40 MW Site)			
Name of work : Supply, E&C of BOS and O&M (for Five years) of BOS" for 1x65MW of Solar PV plant of NLC at Neyveli, Cuddalore District, Tamilnadu.			
Item. NO	DESCRIPTION OF ITEM	UNIT	QTY
4.14	Supply of safety gadgets as per BOQ indicated TCC (Cl.4.17)	SET	1
4.15	Supply of Hume pipe 200 mm dia (Light duty non pressure NP3 class RCC pipes with collars jointed	RM	400
4.16	Insulating mat Class A 2mm thick upto 3.3kV class, 10x1m as per IS-15652	NO	30
4.17	Insulating mat Class C 3mm thick upto 33kV class, 10x1m as per IS-15652	NO	10
Erection & Commissioning of Items			
5	E&C of Interconnection modules ,SMB's		
5.01	Excavation ,laying,glanding etc of 6 sq.mm DC cables (Layin inside HDPE duct from PV modules to SMB)	^Meter	4800
5.02	Erection of SMB Mounting Structure frame	NO	333
5.03	Installation of SMB Box	NO	333
5.04	Interconnection of MC4 Connector for 6sq.mm cable	NO	8124
5.05	6sq.mm 'DC Cable Termination between string and SMB	NO	333
6	Erection & Testing of Cables		
6.01	Excavation for burying of 33kV cables,1.1KV grade cables , DC cables, OFC cables, Signal cables etc as per the list given Annexure-2 of TCC. (Burying of cable shall be strictly done as per IS: 1255)	Meter	4800
6.02	'1Cx300 SQMM Al Armour,33kV (UE) grade HT cable.These cables shall be laid in trefoil formation by using trfoil clamps.	Meter	15000
6.03	1C X 240 sq.mm DC cable Copper conductor, EBXL XLPE insulated, Armored including glanding & termination	Meter	150000
6.04	1Cx 630 sqmm, LT power cable: Al conductor including glanding & termination	Meter	6000
6.05	4Cx70 sqmm, 'LT power cable: Al conductor including glanding & termination	Meter	600
6.06	4Cx35 sqmm, 'LT power cable,Al conductor including glanding & termination	Meter	1200
6.07	4Cx25 sqmm, LT power cable Al conductor including glanding & termination	Meter	4800
6.08	4Cx16 sqmm,LT power cable Al conductor including glanding & termination	Meter	9600
6.09	4Cx10 sqmm, ,LT power cableAl conductor including glanding & termination	Meter	1200
6.10	4Cx6 sqmm,LT power cable, Al conductor including glanding & termination	Meter	2400
6.11	:4Cx4 sqmm,,'LT power cable Al conductor including glanding & termination	Meter	3000
6.12	3Cx4 sqmm, 'LT power cableAl conductor including glanding & termination	Meter	3000
6.13	10Cx 2.5 sqmm,Control cable Copper conductor including glanding & termination	Meter	900

L-1, bidder shall be considered for award of BOS-1 i.e 40 MW site on 'total cost to BHEL'
as per BOQ-A as below.

BOQ - A for BOS-1(i.e 40 MW Site)			
Name of work : Supply, E&C of BOS and O&M (for Five years) of BOS" for 1x65MW of Solar PV plant of NLC at Neyveli, Cuddalore District, Tamilnadu.			
Item. NO	DESCRIPTION OF ITEM	UNIT	QTY
6.14	5Cx 2.5 sqmm,Control cable, Copper conductor including glanding & termination	Meter	1500
6.15	2Cx 1.5 sqmm, ,Control cable,Copper conductor including glanding & termination	Meter	5500
6.16	2Px0.5 sq.mm signal cable including glanding & termination	Meter	1500
6.17	5Px0.5 sq.mm signal cable including glanding & termination	Meter	2400
6.18	12Cx1.5 sq.mm signal cable laying glanding	Meter	600
6.19	CAT 5 ethernet cable including glanding & termination	Meter	1800
6.20	RS 485 communication cable including glanding & termination	Meter	21000
6.21	OFC cable for scada	Meter	10200
6.22	OFC cable for telephone system	Meter	9000
6.23	33KV,1Cx300Sq.mm (UE) Al cable Termination	Nos	180
6.24	Commissioning for the cables listed above SI.No.6.02 to 6.22	Lot	1
7	Erection and Testing Elec Panel in PCSS:		
7.01	Power Conditioning Unit including base channel erection (1AU= 4 no. PCU, EACH PCU DIM:3800MM x1000MMx3000MM)	AU	7
7.02	33kV VCB Panel including base channel erection (1AU=2 I/C + 1 O/G=3 PNLs, 3900MMx2725MMx2600MM)	AU	7
7.03	415V ACDB including base channel erection (1AU= 1No ACDB, 3500MMx600MMx2400MM)	AU	7
7.04	110V DC VRLA Battery including base channel erection (1AU=55AH capacity having 54 cells, 750MMx450MM)	AU	7
7.05	110V DC 15A Battery charger including base channel erection (750MMx750MMx1500MM)	AU	7
7.06	SCADA RTU Panel including base channel erection (800MMx800MMx1600MM)	AU	7
7.07	230V 5KVA UPS including base channel erection (1320MMx750MMx1600MM)	AU	7

L-1, bidder shall be considered for award of BOS-1 i.e 40 MW site on 'total cost to BHEL'
as per BOQ-A as below.

BOQ - A for BOS-1(i.e 40 MW Site)			
Name of work : Supply, E&C of BOS and O&M (for Five years) of BOS" for 1x65MW of Solar PV plant of NLC at Neyveli, Cuddalore District, Tamilnadu.			
Item. NO	DESCRIPTION OF ITEM	UNIT	QTY
7.08	230V 5KVA UPS Battery including base channel erection (2550MMx800MM)	AU	7
7.09	2.5MVA.33KV/350V Inverter Transformer (1AU=2 nos,2.5MVA Trans.Each dimension:3200MMx3100MMx3500MM)	AU	7
7.10	25kVA,350V/433V aux transformer (1 AU= 2 nos. 25KVA Auxiliary Trafo.)	AU	7
7.11	Commissioning equipment from Sl.7.01 to 7.08	AU	7
7.12	commissioning of 2.5MVA and 25KVA Inverter Transformers (1 AU= 2 nos. 2.5MVA Trafos andf 2 nos. 25KVA Auxiliary Trafo.)	AU	7
7.13	Commissioning support for Fire alarm panel (Commissioning supervision by OEM)	AU	7
7.14	Oil filtrion of 2.5MVA Transformers (1AU=2 nos.2.5MVA transformers,oil capacity of each trafo around 1900 ltrs & 2 nos. 25kVA)	AU	7
8	E&C Elec Panel Installation in PESS		
8.01	Power Conditioning Unit including base channel erection (1AU= 4 no. PCU, EACH PCU DIM:3800MM x1000MMx3000MM)	AU	1
8.02	33kV VCB Panel including base channel erection (1AU=9 I/C+1 B/C+2BPT+2 O/G+1 Spare=15 PNLs 19500MMX2725MMx2600MM)	AU	1
8.04	415V ACDB including base channel erection (1AU= 1No ACDB, 3500MMx600MMx2400MM)	AU	1
8.05	SCADA at PESS including base channel erection associated HMI & Printers (1AU=1500MMx800MMx1600MM (Includes all the panel & assciated cabling & Inegration as per Cl.4.37 of TCC)	AU	1
8.06	10kVA, 230V parallel redundant UPS including base channel erection ((1320MMx750MMx1600MM))	AU	1
8.07	10kVA, 230V parallel redundant UPS Batteries including base channel erection (2550MMx800MM)	AU	1
8.08	110V DC VRLA Battery (1AU=165AH capacity having 54 cells, 750MMx450MM)	AU	1
8.10	110V DC 50A Battery charger including base channel erection (750MMx750MMx1500MM)	AU	1
8.12	2.5MVA.33KV/350V Inverter Transformer (1AU=2 nos,2.5MVA Trans.Each dimension:3200MMx3100MMx3500MM)	AU	1

L-1, bidder shall be considered for award of BOS-1 i.e 40 MW site on 'total cost to BHEL'
as per BOQ-A as below.

BOQ - A for BOS-1(i.e 40 MW Site)			
Name of work : Supply, E&C of BOS and O&M (for Five years) of BOS" for 1x65MW of Solar PV plant of NLC at Neyveli, Cuddalore District, Tamilnadu.			
Item. NO	DESCRIPTION OF ITEM	UNIT	QTY
8.13	Aux transformer 75KVA,350V/433V erection at PESS (1AU=2 nos,75KVA AUX Trafos.)	AU	1
8.14	IP based Tele phone exchange including base channel erection (800MMx800MMx2000MM)	AU	1
8.15	Weather Monitoring system. (Includes Pyranometer for solar irradiation, thermometer for ambient temperature, anemometer for wind velocity associated cabling works)	AU	1
8.16	'Clean agent gas extinguishing system such as IG 541 / IG 55 which includes I&C of cylinders, pipes & fittings, manifolds, supply of mounting structures, Pressure relieve devices, Nozzles, ball valves, Release panels, associated batteries, associated cabling, manifolds etc as per TCC	AU	1
8.17	Commissioning of equipment from Sl.no.8.01 to 8.16	AU	1
8.18	commissioning of 2.5MVA and 75KVA Inverter Transformers (1 AU= 2 nos. 2.5MVA Trafos andf 2 nos. 25KVA Auxiliary Trafo.)	AU	1
8.19	Commissioning of Fire alarm panel	AU	1
8.20	Oil filtration of transformers at PESS. (1 AU= 2 nos. 2.5MVA Trafos andf 2 nos. 25KVA Auxiliary Trafo.)	AU	1
9	E&C: Erection & Testing of 33kV metering yard:for 40MW (Refer Meetring yard layout:(PY-LE-1-M088-2019-01)		
9.01	Erection of structure for metering yard (1AU=Activity Equivalent to 1 Nos of O/G Fdr)	AU	2
9.02	Erection of ACSR conductor erection and stringing of ACSR conductor upto gantry as per attched metering yard layout (PY-LE-1-M088-2019-01) (1AU=Activity Equivalent to 1 Nos of O/G Fdr)	AU	2
9.03	Erection of ' CTs, PTs, LAs, GOS Isolator etc. (1AU=Activity Equivalent to 1 Nos of O/G Fdr)	AU	2
9.04	Erection of ABT meter panel including calibration of meters in approved calibration centers of respective RLDC/State power utilities/CTU. It is the responsibility of the vendor to get ABT meters sealed by RLDC/ state power utilities/CTU.	Nos	6
9.05	Testing & commissioning of metering yard Equipment (1AU=Completed Metering yard)	AU	2
10	E&C: Earthing & lightning system system: PCSS building ,PESS building,Metering yard,DC arrayard etc		

L-1, bidder shall be considered for award of BOS-1 i.e 40 MW site on 'total cost to BHEL'
as per BOQ-A as below.

BOQ - A for BOS-1(i.e 40 MW Site)			
Name of work : Supply, E&C of BOS and O&M (for Five years) of BOS" for 1x65MW of Solar PV plant of NLC at Neyveli, Cuddalore District, Tamilnadu.			
Item. NO	DESCRIPTION OF ITEM	UNIT	QTY
10.01	75x10mm earth stripLaying of earth strip below ground -	Mtrs	3600
10.02	75x10mm Earth strip-Laying of earth strip above ground with equipment connections	Mtrs	1500
10.03	50x6 mm earth strip-Laying of earth strip above ground with equipment connections	Mtrs	1440
10.04	25x3mm earth strip-Laying of earth strip below ground	Mtrs	9000
10.05	25x3mm earth strip-Laying of earth strip above ground with equipment connections	Mtrs	16000
10.06	8swg-Laying of earth wire above ground with equipment connections	Mtrs	3000
10.07	35x6 mm earth strip-Laying of earth strip above ground for lightnin gprotection system	Mtrs	800
10.08	65mm GI Pipe electrode-Installation of Earth Pit including filling with charcoal and salt	Mtrs	95
10.09	40mm GI Rod electrode-Installation of Earth Pit including filling with charcoal and salt	Mtrs	65
10.10	Installation of vertical air termination rods	Nos	18
10.11	Installation Lightning Protection(ESE)	NO	32
11	E&C of cable Trays		
11.01	600W Ladder type GI cable tray including support erection	Mtrs	900
11.02	300W Peforated cable tray including support erection	Mtrs	480
12	Erection&Commissioning: Outdoor area Lighting system (refer attached outdoor area illumination layout)		
12.01	120W LED Flood Light Fixture	NO	2
12.02	40 W LED Batton Fixture	NO	10
12.03	30 W LED street Fixture	NO	550
12.04	Poles 2.2 Mtrs & 4.2 Mtr Poles	NO	550

L-1, bidder shall be considered for award of BOS-1 i.e 40 MW site on 'total cost to BHEL' as per BOQ-A as below.

BOQ - A for BOS-1(i.e 40 MW Site)			
Name of work : Supply, E&C of BOS and O&M (for Five years) of BOS" for 1x65MW of Solar PV plant of NLC at Neyveli, Cuddalore District, Tamilnadu.			
Item. NO	DESCRIPTION OF ITEM	UNIT	QTY
12.05	Poles 11 Mtrs Poles	NO	2
12.06	JBs/Welding receptacles/TPN Socket/Surface mounted board/	NO	20
12.07	Commissioning of Illumination system	LOT	1
13	E&C:Module Cleaning system: '1 AU = Activity equivalent to 1 out of 13 No 5 MW Site.	AU	8
14	E&C: Construction of bore wells: '1 AU = Activity equivalent to 1 out of 11 No bore well.	AU	7
15	E&C: Commissioning , state clearance '1 AU = Activity equivalent to 1 out of 2 Sites.	AU	1
16	Operation & Maintenance		
16.01	Operations and Maintenance per Month (five years) (1 AU = Activity equivalent to 1 Months out of 60 Months)	AU	60 months
	Notes:		
1	The successful bidder will be required to provide Operation & Maintenance services for the entire 40 MW site under this contract.		
2	The unit rate for item no. 6.24,8.17,12.07 & 16.01 derived from the weightage % indicated in price bid format will be reduced to 61.54% for arriving at unit rate for contract for 40 MW site(Ref. BOQ-A)		