

2 X 660 MW ENNORE STPP
ANNEXURE - A
BOQ-CUM-PRICE SCHEDULE FOR SCREENED CONTROL CABLE
ENQUIRY NO: PE/PG/EN1/E-6237/2019 dated 18.06.2019

A.0) MAIN SUPPLY

1) Individual & Overall Screened Cable (Type-F)-Armoured cable

Multi pair (twisted) individual & overall shielded instrumentation cables. (Type-F)								INDIAN BIDDERS								FOREIGN BIDDERS			
S.No.	Item Code	Item Description	UOM	HSN CODE	TOTAL QUANTITY	LOT-1 QTY	Drum Length	Unit Price (Ex-Works) INR	Total Price (Ex-Works) INR	FREIGHT CHARGES		TOTAL PRICES (ex works + freight) (INR)	APPLICABLE GST ON (TOTAL EX WORKS + FREIGHT) BOTH			TOTAL PRICE F.O.R Prices with taxes (INR)	CURRENCY	UNIT C&F PRICE ON CHENNAI /INDIAN SEA PORT	TOTAL C&F PRICE ON CHENNAI /INDIAN SEA PORT
										@ % OF TOTAL EX WORKS	AMOUNT (INR)		TYPE OF GST (IGST/SGST ETC.)	GST RATE ON(TOTAL EX WORKS + FREIGHT)	TOTAL AMOUNT IN (INR)				
(i)	507-31116-A	1.1kV TYPE F(IO) 2P - 0.5 ARMoured	MTR	8544	97,000	44000	1000												
(ii)	507-31009-A	1.1kV TYPE F(IO) 4P - 0.5 ARMoured	MTR	8544	1,16,000	82000	1000												
(iii)	507-31013-A	1.1kV TYPE F(IO) 8P - 0.5 ARMoured	MTR	8544	24,000	8000	1000												
(iv)	507-31001-A	1.1kV TYPE F(IO) 12P - 0.5 ARMoured	MTR	8544	34,000	23000	1000												
(v)	507-31121-A	1.1kV TYPE F(IO) 24P - 0.5 ARMoured	MTR	8544	2,000	0	500												

2) Overall Screened Cable (Type-G)-Armoured cable

Multi pair (twisted) overall shielded instrumentation cables. (Type-G)																			
(i)	507-31025-A	1.1kV TYPE G(O) 2P - 0.5 ARMoured	MTR	8544	1,000	0	1000												
(ii)	507-31029-A	1.1kV TYPE G(O) 4P - 0.5 ARMoured	MTR	8544	54,000	23000	1000												
(iii)	507-31033-A	1.1kV TYPE G(O) 8P - 0.5 ARMoured	MTR	8544	62,000	0	1000												
(iv)	507-31017-A	1.1kV TYPE G(O) 12P - 0.5 ARMoured	MTR	8544	50,000	17000	1000												

Notes :

- Indented Quantities indicated above at **S. No. 1 & 2** shall be known as Order Quantities. The variation in quantities of all sizes for **Main supply (S. No. 1 & 2)** put together shall be limited to (-) 30% to (+) 30% of the total contract value derived on the basis of the Ordered quantities for this very project.
- The quantities will be released for manufacture in more than one lot.
- The LOT-1 quantities, which are indicated above, shall be released for manufacture along with LOI. However, manufacturing of LOT-1 quantities shall be done after the approval of technical and quality documentation. Subsequent lots shall be cleared for manufacture based on progress of engineering and site requirements.
- Delivery schedule of LOT-1 and subsequent lots shall be as per NIT.
- The bidder shall indicate the unit price of each type and size of cables listed as per the BOQ in the Price Schedule. The unit price shall apply for adjustment of variation in quantity as stipulated above.
- Overall tolerance on total dispatched quantity of each size shall be (-) 2% and (+) 0% except where the total ordered quantity is one single drum length of 1000m, in which case it shall be -5%/0%. Cables consumed for testing and inspection shall be to bidder's account.
- Standard drum length shall be 1000 metres upto 12P & Standard drum length shall be 500 metres above 12P. The tolerance of drum length shall be +/- 5%.
- For each individual cable size, one short length of not less than 200m may be accepted only in the final drum length to complete the supply (except where the total ordered quantity is one single drum length of 1000m). The overall tolerance limits stipulated above shall continue to apply (in case short lengths are accepted).
- In case of the quantities of any one lot cleared by BHEL for manufacturing are manufactured and offered for inspection by successful bidder in more than one batch, BHEL reserves the right to witness type testing on all batches without any price implications.
- Test charges are deemed to be included in price of cables. No separate, Test charges to be quoted by bidder.No separate charges shall be payable for tests.