

1 X 250 MW ROURKELA TPS
ENQUIRY NO.: PEIPGINSPIE-5589/2017 dtd 10.04.2017
BOQ-CUM-PRICE SCHEDULE FOR ANUBAR (REV 00)

FOR INDIAN BIDDERS									
COMPLETE ANUBAR ASSEMBLY including Purge Air System. Charges as per specification & GA Drawing. All wetted parts shall be of SS316 as indicated in datasheets.									
S.No.	Item Description	Qty for 1 Unit	UNIT PRICE (EX-WORKS) DULY PACKED Rs	TOTAL PRICE (EX-WORKS) DULY PACKED Rs	ED Including cess @....% Rs	CST @...% against 'C' form & E1/E2 forms Rs	Freight Including service tax @...% of Total Ex-works Rs	TOTAL FOR SITE PRICE Rs	
1	Anubar assembly along with accessories (i.e. Flanges, Spool piece, gaskets, fasteners, nuts, bolts, etc)	1 no.							
2	Connector (Swage lock Double Compression Type), Stainless Steel 316, 1/2" NPT (M) x to suit 15 Nb size impulse pipe at other end.	2 Nos.							
3	1/2" Stainless Steel 316 impulse pipe	2 meter							
4	TEE, Stainless Steel 316, straight end socket weld x 90 Deg. end socket weld x 90 Deg. end 1/4" NPT (F)	2 nos.							
5	Globe isolation valve, 1/2" size, Stainless Steel 316, Socket weld along with suitable connectors.	2 nos.							
6	Connector (Swage lock Double Compression Type), Stainless Steel 316, 1/4" NPT (M) x to suit 1/4" size Stainless Steel tube at other end.	9 nos.							
7	Globe isolation valve, 1/4" size, Stainless Steel 316, screwed end.	2 nos.							
8	1/4" OD Annealed Stainless Steel Tube 316	20 meter							
9	Stainless Steel 316 TEE, 1/4" NPT (F)	1 nos.							
10	Connectors (Swage lock double compression type), stainless steel 316 to suit 2" isolation valve female thread as per IS 554 x to suit 1/4" OD Stainless steel tube 316 at other end.	1 nos.							
B) START-UP/COMMISSIONING SPARES									
1	(2 SETS OF GASKET FOR EACH TAG)	2 Sets							
TOTAL (A+B)									
C) RECOMMENDED SPARES (OPTIONAL)									
1	FOR THREE YEARS OF OPERATION (ITEM WISE BREAK-UP TO BE ATTACHED BY THE BIDDER)								
TOTAL (C)									

NOTES

1 Only Total (A+B) shall be considered for evaluation.

2 Recommended spares (S.No. C) are under optional category and charges for the same shall not be considered for evaluation.

Signature
10/11/17

1 X 250 MW ROURKELA TPS
ENQUIRY NO.: PE/PG/NSP/E-5569/2017 dtd 10.04.2017
BOQ-CUM-PRICE SCHEDULE FOR ANUBAR (REV 00)

FOR FOREIGN BIDDERS				
A) COMPLETE ANUBAR ASSEMBLY including Purge Air System. Charges as per specification & GA Drawing. All wetted parts shall be of SS316 as indicated in datasheets.				
			Applicable for Foreign Bidders (Bidder to indicate their Currency)	
S.No.	Item Description	Qty for 1 Unit	Unit C&F Mumbai Sea Port Price (Currency)	Total C&F Mumbai Sea Port Price (Currency)
1	Anubar assembly along with accessories (i.e. Flanges, Spool piece, gaskets, fasteners, nuts, bolts, etc)	1 no.		
2	Connector (Swage lock Double Compression Type), Stainless Steel 316, 1/2" NPT (M) x to suit 15 Nb size impulse pipe at other end.	2 Nos.		
3	1/2" Stainless Steel 316 impulse pipe	2 meter		
4	TEE, Stainless Steel 316, straight end socket weld x 90 Deg. end socket weld x 90 Deg. end 1/4" NPT (F)	2 nos.		
5	Globe isolation valve, 1/2" size, Stainless Steel 316, Socket weld along with suitable connectors.	2 nos.		
6	Connector (Swage lock Double Compression Type), Stainless Steel 316, 1/4" NPT (M) x to suit 1/4" size Stainless Steel tube at other end.	9 nos.		
7	Globe isolation valve, 1/4" size, Stainless Steel 316, screwed end.	2 nos.		
8	1/4" OD Annealed Stainless Steel Tube 316	20 meter		
9	Stainless Steel 316 TEE, 1/4" NPT (F)	1 nos.		
10	Connectors (Swage lock double compression type), stainless steel 316 to suit 2" isolation valve female thread as per IS 554 x to suit 1/4" OD Stainless steel tube 316 at other end.	1 nos.		
B) START-UP/COMMISSIONING SPARES				
1	(2 SETS OF GASKET FOR EACH TAG)	2 Sets		
TOTAL (A+B)				
C) RECOMMENDED SPARES (OPTIONAL)				
1	FOR THREE YEARS OF OPERATION (ITEM WISE BREAK-UP TO BE ATTACHED BY THE BIDDER)			
TOTAL (C)				

NOTES

- Only Total (A+B) shall be considered for evaluation.
- Recommended spares (S.No. - C) are under optional category and charges for the same shall not be considered for evaluation.

Saini
10/04/17