



PROJECT:- 1 x 800 MW WANAKBORI TPP
BOQ CUM PRICE SCHEDULE FOR EPR INSULATED FIRE SURVIVAL CABLE
ENQUIRY No.-PE/PG/WAN/E-5362/2016 Dtd. 27.09.2016

ANNEXURE-I

COPPER CONDUCTOR, EPR INSULATED, HOFR SHEATH ARMoured FIRE SURVIVAL CABLE TO TECHNICAL SPECIFICATION No. PE-TS-408-507-E005.										APPLICABLE
S. NO.	Cable Size (No. of cores x Cross section Area (sq.mm))	Order Quantity (meters)	LOT-1 QUANTITY (meters)	Drum length (meters)	Unit price (Ex-works) Rs.	Total price (Ex-works) Rs.	ED@.....%(Rs.)	CST@.....% against form C/E1 or VAT@.....% (Rs.)	Freight Incl. service tax@.....% of Ex-works (Rs.)	Total FOR Site Price. (Rs.)
1	2	3	4	5	6	7=3*6	8	9	10	11=7+8+9+10
A	3C-2.5 (GS ARMoured)	1000	1000	500						
B	5C-2.5 (GS ARMoured)	3000	2000	500						
C	2C-95 (GS ARMoured)	5500	3500	500						
D	1C-400 (GS ARMoured)	1000	1000	500						
E	1C-400 (CU ARMoured)	1000	1000	500						
F	1C-630 (CU ARMoured)	4000	3000	500						
	TOTAL PRICE (RS.)									

Notes :

1. The variation in quantities of all sizes for Main items put together shall be limited to (-)30% to (+) 30% of the total contract value derived on the basis of the Ordered quantities for this very project.
2. The bidder shall indicate the unit price of each type and size of cables listed as per the BOQ-Cum-Price Schedule enclosed with this specification. The unit prices shall apply for adjustment of variation in quantity as stipulated above.
3. Lot-1 Quantity indicated above shall be cleared for manufacturing along with LOI/PO. However, manufacturing of the cables shall be taken up by the successful bidder only after approval of technical and quality documentation. Subsequent lots shall be cleared for manufacture based on progress of engineering and site requirements.
4. Delivery schedule of LOT-1 and subsequent lots shall be as per NIT.
5. Standard drum length shall be 500 metres.Tolerance on individual drum length shall be $\pm 5\%$.
6. Overall tolerance on total dispatched quantity of each size shall be (-) 2% and (+) 0%. Cables consumed for testing and inspection shall be to bidder's account.
7. For each individual cable size, one short length of not less than 200m may be accepted only in the final drum length to complete the supply. The overall tolerance limits stipulated above shall continue to apply (in case short lengths are accepted).
8. Bidder shall indicate unit price of cables inclusive of type test charges . No separate Type Test charges are to be quoted by bidder.
9. The charges of Hydrolytic Stability test, if asked to perform shall be reimbursed extra at actual against original money receipt of Govt. lab (CPRI/ERDA).
10. In case the quantities cleared by BHEL for manufacturing (in a lot) are manufactured and offered for inspection by successful bidder in more than one batch, BHEL reserves the right to witness type testing on all batches.