

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

ESTIMATE Part - I Page 1 of 13

ESTIMATE REF NO : CF/MC/09/50

NAME OF WORK : PROVIDING CIVIL WORKS FOR 100 TONE WEIGH BRIDGE AND CONTROL ROOM IN EXTENDED FACTORY .

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RS RATE P	RS AMOUNT P
2.8.1	01	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. For All kinds of soil.	210.000	CUM	103.40	21714.00
2.6.1	02	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. For All kinds of soil.	90.000	CUM	101.85	9166.50
2.7	03	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5 m, disposed earth to be levelled and neatly dressed.				
2.7.1	03A	For Ordinary rock.	10.000	CUM	152.60	1526.00
2.7.3	03B	For Hard rock (blasting prohibited).	10.000	CUM	325.25	3252.50
2.1.1	04	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m, disposed soil to be levelled and neatly dressed :ForAll kinds of soil.	1800.000	SQM	20.74	37332.00
2.9	05	*Excavation work by mechanical means excavator)/manual means in foundation trenches or drains not exceeding 1.5 m in width or 10 sqm on				.00

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

Page 2 of 13**ESTIMATE**

ESTIMATE REF NO : CF/MC/09/50

NAME OF WORK : PROVIDING CIVIL WORKS FOR 100 TONE WEIGH BRIDGE AND CONTROL ROOM IN EXTENDED FACTORY .

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT
					RS	P	RS
		plan including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50m."					
2.9.1	06A	For Ordinary rock.	10.000	CUM	162.65		1626.50
2.9.2	06B	For hard rock (requiring blasting)	5.000	CUM	272.95		1364.75
2.9.3	06C	Hard rock (blasting prohibited)	2.000	CUM	332.45		664.90
4.1.10	07	"Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 Cement : 5 coarse sand :10 graded stone aggregate 40 mm nominal size)."	27.000	CUM	1564.35		42237.45
5.9.1	08A	"Centering and shuttering including strutting, propping etc. and removal of form for:For Foundations, footings, bases of columns, etc. For mass concrete."	55.000	SQM	119.25		6558.75
5.9.2	08B	Walls (any thickness) including attached pilasters,butteresses, plinth and string courses etc.	140.000	SQM	180.40		25256.00
5.9.5	08C	Lintels, beams, plinth beams, girders, bressumers and cantilevers.	35.000	SQM	162.65		5692.75
I	09	Providing pockets or holes in foundations for holding down bolts using G.I pipes or 12 mm thick shuttering plywood including fixing the pipes or and plywood work of required sizes in position to correct alignment level and removal of the form work. Rate all inclusive.	1.000	SQM	718.75		718.75
13.47.1	10	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade New work (Two or more coats applied @ 1.43 Itr/	50.000	SQM	60.10		3005.00

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

Page 3 of 13**ESTIMATE**

ESTIMATE REF NO : CF/MC/09/50

NAME OF WORK : PROVIDING CIVIL WORKS FOR 100 TONE WEIGH BRIDGE AND CONTROL ROOM IN EXTENDED FACTORY .

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE RS P	AMOUNT RS P
		10 sqm. over and including base coat of water proofing cement paint applied @ 2.20 kg/10 sqm).				
5.33	10	"Providing and laying in position machine batched, machine mixed and machine vibrated design mix cement concrete of specified grade for reinforced cement concrete work including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including Admixtures in recommended proportions as per IS 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. M-25 grade reinforced cement concrete by using 410kg. of cement per cum of concrete. All work up to floor V level."	45.000	CUM	2023.60	91062.00
5.37	11	"Providing and laying in position ready mixed concrete manufactured in fully automatic batching plant and transported to site of work in transit mixer for a lead up to 10kms having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work including pumping of R.M.C. from transit mixer to site of laying, excluding the cost of centering, shuttering finishing and reinforcement including cost of admixtures in recommended proportions as per IS : 9103 to accelerate/retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer - in - charge. M-25 grade Reinforced cement concrete by using 410kg of cement per cum of concrete. All works up to floor V level."	5.000	CUM	4356.50	21782.50

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED
BOILER AUXILIARIES PLANT
RANIPET - 632406

Page 4 of 13**ESTIMATE**

ESTIMATE REF NO : CF/MC/09/50

NAME OF WORK : PROVIDING CIVIL WORKS FOR 100 TONE WEIGH BRIDGE AND CONTROL ROOM IN EXTENDED FACTORY .

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE RS P	AMOUNT RS P
5.39	12	Extra for carriage of R.M.C. beyond the initial lead of 10km.	5.000	CUM	20.90	104.50
5.22.3	13	"Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. For Cold twisted bars."	4250.000	KG	6.19	26307.50
5.1.2	14	"Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)"	10.000	CUM	1660.00	16600.00
2.27	15	" Supplying and filling in plinth with good sand under floors including, watering, ramming consolidating and dressing complete."	22.000	CUM	301.50	6633.00
1.1.2/4	16A	Conveyance of earth, sand, gravel etc by contractor's own lorry for loading ,leading ,unloading,stacking or spreading asper the instruction of Engineer in charge.From 0 KM to 1 KM.	260.000	CUM	49.42	12849.20
10.1	17	Structural steel work in single section fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	500.000	KG	6.50	3250.00
16.1	18	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm. depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth lead upto 50 metres.	350.000	SQM	33.90	11865.00

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

Page **5** of **13****ESTIMATE**

ESTIMATE REF NO : CF/MC/09/50

NAME OF WORK : PROVIDING CIVIL WORKS FOR 100 TONE WEIGH BRIDGE AND CONTROL ROOM IN EXTENDED FACTORY .

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	P
16.3.9	19	supply and stacking of red gravel at site.	80.000	CUM	144.05		11524.00	
16.72	20	Supplying and stacking of hard stone (for stone pitching) 22.5 cm thick at site.	20.000	CUM	458.35		9167.00	
16.3.2	21	Supplying and stacking at site.For 63 mm to 45 mm size stone aggregate.	70.000	CUM	768.45		53791.50	
16.3.7	22	Supplying and stacking at site for Stone screening 11.2 mm nominal size (Type B).	15.000	CUM	979.40		14691.00	
1	23	Laying spreading and compacting stone aggregate of specified sizes to WBM specifications including spreading in uniform thickness, hand picking , rolling with 3 wheeled road / vibratory roller 8-10 tonne in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate watering and compacting to the required density .	50.000	CUM	192.55		9627.50	
2.25	24	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	65.000	CUM	45.70		2970.50	
17.2/2002	25	Consolidation of subgrade with power Road roller of 8 to 12 Tone capacity including making good the undulations etc.,with earth or quarry spoils etc.,and rerolling the subgrade.	1800.000	SQM	1.02		1836.00	
5.12	26	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement : 3 fine	5.000	CUM	2913.85		14569.25	

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

Page 6 of 13**ESTIMATE**

ESTIMATE REF NO : CF/MC/09/50

NAME OF WORK : PROVIDING CIVIL WORKS FOR 100 TONE WEIGH BRIDGE AND CONTROL ROOM IN EXTENDED FACTORY .

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	P
		sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20mm nominal size).						
CF26/08-09 :	27	Grouting the holding bolts and underneath the base plates etc., after alignment with non-shrink free flow grout mix of SHRINKOM 30 (ACC'S MAKE) or equivalent as per standard specifications and instructions of Engineer-in-charge. Rate to include charges for cleaning the sleeves or pockets and other incidental charge, tools and plants etc., Complete.	0.200	CUM	40422.55		8084.51	
CF27/08-09 :	28	Pressure grouting of cement slurry admixed with an expensive plasticizing agent, packing with quick setting cement and providing at floor and wall joints etc. with cement mortar after applying one coat of water based dispersion of acrylic polymer mixed with the cement.	10.000	POINT	275.00		2750.00	
10.19	29	Providing and fixing bolts M.S round holding down bolts with nuts and washer plates complete.	100.000	KG	52.05		5205.00	
7.1.1	30	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) at plinth level with : For Cement mortar 1:6 (1 cement: 6 coarse sand)	95.000	CUM	1411.55		134097.25	
6.1.2	31	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: For Cement mortar 1:6 (1 cement: 6 coarse sand) .	10.000	CUM	1798.00		17980.00	
11.41.2	32	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with	6.000	SQM	967.51		5805.09	

CONTRACTOR/TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

Page **7** of **13****ESTIMATE**

ESTIMATE REF NO : CF/MC/09/50

NAME OF WORK : PROVIDING CIVIL WORKS FOR 100 TONE WEIGH BRIDGE AND CONTROL ROOM IN EXTENDED FACTORY .

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	F
		water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete. For Size of Tile 60x60 cm.						
13.1.2	33	12 mm cement plaster of mix :1:6 (1 cement: 6 coarse sand)	50.000	SQM	49.00		2450.10	
13.2.2	34	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement: 6 fine sand).	35.000	SQM	56.28		1969.66	
13.16.1	35	6 mm cement plaster of mix : 1:3 (1 cement: 3 fine sand).	15.000	SQM	43.14		647.09	
21.1.1.2	36	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and paneling to be paid for separately) :					.00	

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

Page **8** of **13****ESTIMATE**

ESTIMATE REF NO : CF/MC/09/50

NAME OF WORK : PROVIDING CIVIL WORKS FOR 100 TONE WEIGH BRIDGE AND CONTROL ROOM IN EXTENDED FACTORY .

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	P
21.1.1.2	36A	For fixed portion. Powder coated aluminium (minimum thickness of powder coating 50 micron).	30.000	KG	306.30		9189.00	
21.1.2.2	36B	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of PVC / neoprene gasket required (Fittings shall be paid for separately). Powder coated aluminium (minimum thickness of powder coating 50 micron).	30.000	KG	326.60		9798.00	
21.2.2	37	Providing and fixing 12mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides.	2.000	SQM	812.60		1625.20	
21.3	38	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):					.00	
21.3.1	38A	With float glass panes of 4.0 mm thickness.	10.000	SQM	554.95		5549.50	
21.3.2	38B	With float glass panes of 5.50 mm thickness.	2.000	SQM	673.55		1347.10	
13.37	39	White washing with lime to give an even shade: New work (three or more coats)	20.000	SQM	6.75		135.00	

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

Page 9 of 13**ESTIMATE**

ESTIMATE REF NO : CF/MC/09/50

NAME OF WORK : PROVIDING CIVIL WORKS FOR 100 TONE WEIGH BRIDGE AND CONTROL ROOM IN EXTENDED FACTORY .

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	P
13.41.1	40	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade. New work (two or more coats) over and including priming coat with cement primer.	30.000	SQM	41.55		1246.50	
12.34/2002	41	Lime concrete terracing on roofs average thickness 10 cm laid to fall with 25mm nominal size bricks agregate and 50% lime mortar 1:2 (1 lime putty : 2 surkhi) rammed and finished with gur and belbiri treatment complete including rounding of junction with parapet wall complete.	2.000	CUM	272.80		545.60	
12.20	42	Providing and laying pressed clay tiles (as per approved pattern 20 mm nominal thickness and of approved size) on roofs jointed with cement mortar 1:4 (1 cement : 4 coarse sand) mixed with 2% integral water proofing compound laid over a bed of 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) and finished neat complete.	15.000	SQM	288.24		4323.65	
CF11/09-10	43	Providing & fixing of heavy duty Aluminium Grill 3" hole & 6mm thick of approved design & pattern as approved by the Engineer in charge to the windows. The rate to include cost of all material, for fixing of aluminium Grill with necessary fixing arrangements using required heavy duty Aluminium sections used for paneling & fixing arrangements etc,Complete.	8.000	SQM	2070.00		16560.00	

Sub total for Part - I 698054.55

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

ESTIMATE**Part - II**Page 10 of 13

ESTIMATE REF NO : CF/MC/09/55

NAME OF WORK : PROVIDING D.S.L FOUNDATION FOR GANTRY CRANE IN EXTENDED FACTORY.

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RS RATE P	RS AMOUNT P
2.8.1	01	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. For All kinds of soil.	450.000	CUM	103.40	46530.00
2.9	02	"Excavation work by mechanical means excavator)/manual means in foundation trenches or drains not exceeding 1.5 m in width or 10 sqm on plan including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50m."				.00
2.9.1	02A	For Ordinary rock.	100.000	CUM	162.65	16265.00
2.9.2	02B	Hard rock (requiring blasting)	5.000	CUM	272.95	1364.75
2.9.3	02C	For Hard rock (Blasting prohibited).	5.000	CUM	332.45	1662.25
4.1.10	03	"Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 Cement : 5 coarse sand :10 graded stone aggregate 40 mm nominal size)."	25.000	CUM	1564.35	39108.75
5.9.1	04	"Centering and shuttering including strutting, propping etc. and and removal of form for:For Foundations, footings, bases of columns, etc. For mass concrete."	500.000	SQM	119.25	59625.00
DATA	05	Providing pockets or holes in foundations for holding down bolts using G.I pipes or 12 mm including fixing the pipes or and plywood work	5.000	SQM	718.75	3593.75

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

ESTIMATE

Page 11 of 13

ESTIMATE REF NO : CF/MC/09/55

NAME OF WORK : PROVIDING D.S.L FOUNDATION FOR GANTRY CRANE IN EXTENDED FACTORY.

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	P
		of required sizes in position to correct alignment level and removal of the form work. Rate all inclusive.						
5.33	06	"Providing and laying in position machine batched, machine mixed and machine vibrated design mix cement concrete of specified grade for reinforced cement concrete work including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including Admixtures in recommended proportions as per IS 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. M-25 grade reinforced cement concrete by using 410kg. of cement per cum of concrete. All work up to floor V level."	115.000	CUM	2023.60		232714.00	
5.37	07	"Providing and laying in position ready mixed concrete manufactured in fully automatic batching plant and transported to site of work in transit mixer for a lead up to 10kms having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work including pumping of R.M.C. from transit mixer to site of laying, excluding the cost of centering, shuttering finishing and reinforcement including cost of admixtures in recommended proportions as per IS : 9103 to accelerate/retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer - in - charge. M-25 grade Reinforced cement concrete by using 410kg of cement per cum of concrete. All works up to floor V level."	10.000	CUM	4356.50		43565.00	

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED

BOILER AUXILIARIES PLANT

RANIPET - 632406

Page 12 of 13**ESTIMATE**

ESTIMATE REF NO : CF/MC/09/55

NAME OF WORK : PROVIDING D.S.L FOUNDATION FOR GANTRY CRANE IN EXTENDED FACTORY.

CPWD 2007 REF	SLNO	DESCRIPTION	QTY	UNIT	RATE		AMOUNT	
					RS	P	RS	P
5.39	08	Extra for carriage of R.M.C. beyond the initial lead of 10km.	10.000	CUM	20.90		209.00	
5.22.3	09	"Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. For Cold twisted bars."	10000.000	KG	6.19		61900.00	
2.27	10	"Supplying and filling in plinth with good sand under floors including, watering, ramming consolidating and dressing complete."	5.000	CUM	301.50		1507.50	
1.1.2/5	11	Conveyance of earth, sand, gravel etc by contractor's own lorry for loading, leading, unloading, stacking or spreading as per the instruction of Engineer in charge. From 1KM to 2 KM.	150.000	CUM	56.41		8461.50	
10.1	12	Structural steel work in single section fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	50.000	KG	6.50		325.00	
2.25	13	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	370.000	CUM	45.70		16909.00	
10.19	14	Providing and fixing M.S. round holding down bolts with nuts and washer plates complete.	1000.000	KG	52.05		52050.00	

Sub total for Part - II 585790.50

0
—
0

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED
 BOILER AUXILIARIES PLANT
 RANIPET - 632406

ANNEXURE		
Providing Civil works for 100 Tone weigh bridge and control room in extended factory (PART - I)	Rs	6,98,054.55
Providing DSL foundation for gantry crane in extended factory (PART - II)	Rs	5,85,790.50
Total Estimated value..... (A)	Rs	12,83,845.05
Contractor Tender Percentage @ ABOVE / BELOW / AT PAR % (Percentage in words.....) (B)		
Sub total.....(A+B)	Rs	
Service Tax @..... %..... (C)	Rs	
Service head :.....	Rs	
Total value of work : (A + B + C)	Rs	

CONTRACTOR/ TENDERER

ACCEPTING OFFICER

BHARAT HEAVY ELECTRICALS LIMITED , BOILER AUXILIARIES PLANT, RANIPET - 632 406				
Civil Projects & Services Dept.				
SPECIAL CONDITIONS OF CONTRACT				
1	The tenderer shall quote a percentage above or below or at par, the rates shown in the Bill of Quantities based on CPWD DSR 2007. The percentage quoted shall be clearly written both in words and figures. The contractor should accustom with CPWD DSR & Specifications before quoting.			
2	The quoted percentage will apply to the individual items uniformly .			
3	The above rates does not include PF & ESI remittance .The tenderer shall quote inclusive of PF & ESI contribution to their workers.			
4	Items of work other than those mentioned in Bill of Quantities will have to be carried out at the rates to be fixed by this organisation .The same offered percentage will be applicable with reference to CPWD DSR 2007.			
5	Safety precautions should be taken while doing the work. You will have to follow all safety requirements to carry out the work inside the factory premises.			
6	CONTRACT CONDITIONS ON TAXES & DUTIES			
	a. The Tenderer shall have been Registered under Excise, Sales Tax, VAT, Service Tax regulations if applicable and provide a copy of such registration to BHEL as part of the tender document. In case of fresh registration/amendment thereon, the same shall be carried out before start of the work. PAN no shall be submitted as part the tender document. (copy to be enclosed)			
	b. Service Tax shall be paid by the service provider namely the Tenderer.			
	c. Required Tax Invoice as per the existing provisions to be issued in required parts duly signed by the Competent/Authorized Official of the Contractor to BHEL			
	d. If due to deficiency in the document submitted, BHEL could not avail CENVAT, VAT Credit, the credit amount will be recovered from the amount due to the Tenderer .			
	e. If payment of statutory dues are not made in accordance with the applicable provisions of the relevant Act within the time specified and Penalty, Interest etc paid/payable by the Contractor, the same shall not be reimbursed by BHEL and the entire implication is only to be born by the Contractor. The Tenderer shall clearly indicate the rate of applicable taxes and duties for the work to be executed.			
	f. The Tenderer shall indicate all exemptions on account of thrushold limits or special notification under any stature. Any modification theron shall also be intimated immediately on changes.			
	g. The quote submitted shall include all taxes and duties of whatsoever in nature but exclusive of Service Tax which shall be quoted separately if applicable. The existing rate shall be quoted clearly. If reduced rates are applicable on account of material, labour if any the same shall be indicated clearly. After tender opening addition of any tax & duty is not admissible.			
	h. f any composition scheme is to be availed by the Tenderer, the all relevant terms and conditions shall be indicated clearly in the offer. The required compliance under relevant statue shall be carried out.			
	i. Any statutory variation will be to the account of BHEL. But if the variation is effective during the delayed/extended period of execution for reasons attributable to the vendor, the same shall be borne by the vendor only.			
	J1. Whether Servicable Turnover has crossed the Service Tax Threshold Limit as per Service Tax Rules for the tenderer.	YES	NO	Remarks
	J2.Registered with Service Tax authorities	YES	NO	
	J3.If yes copy of Service Tax Regn. Is enclosed	YES	NO	

CONTRACTOR/TENDERER

ACCEPTING OFFICER

	J4.Service Tax Registration No.			
	J5.Under which Service Head(s):			
	J6.Service Tax @ % is applicable as extra for this tender.			
	J7.Whether Input credit for the Materials is availed by the tenderer.	YES	NO	
	J8.Whether Input credit for the service portion is availed by the tenderer.	YES	NO	
	J9.The Toal Value of Work (A+B+C) quoted is in the Tender is Inclusive of Service Tax . (Must be quoted both in figures and words)			
	J10.Tenderer has their own PF registration	YES	NO	
	J11.Tenderer has their own ESI registration	YES	NO	
	J12.PAN No. of the Tenderer			
7	<p>7a) Power and water for all civil & road construction works will be provided by BHEL from the nearest tapping point at the recovery rates specifed below. The contractor should make necessary arrangement for tapping the same at his own cost.</p> <p>7b) The Contractor should quote the tender considering the above. The recovery rates towards the cost for these facilities will be @ 1% for water charges & 0.5% for Power charges will be effected from the bills on the executed value as certified by the Engineer-in-charge based on the usage of Power & water .</p> <p>7c) In case the above facilities are not provided by BHEL, the tenderer has to arrange these facilities at his own cost and the recovery rates of 1% for water charges & 0.5% for Power charges will not be effected on the executed value as certified by the Engineer-in-charge.</p>			
8	All materials shall confirm to the latest IS/IRC specifications			
9	Once the work is completed the contractor should remove all the unwanted materials from the site time to time and it should be disposed off as per the instructions of Engineer-in-charge without any further delay.			
10	All works shall be carried out as per standard specifications and instructions of Engineer-in-charge.			
11	All materials, colour, shade,brand, etc. shall be got approved from the Engineer-in-charge before the start of the work and shall confirm to the latest IS/IRC specifications..			
12	The current minimum wages per day for USW is Rs.165.00/-			
13	The contractor have to follow all statutory requirements like PF ,ESI etc.,through out the contract period.			
14	The General conditions of contract in force shall apply to this contract.			
15	The contractor is required to engage a Diploma holder Engineer through out the contract period.			
16	Time is essence of the contract. Any delay beyond the delivery date will be subjected to LD.			
17	Tenderers are requested to visit the site and verify themselves about the actual site conditions to know about the site facilities, distances and assess the site condition before quoting for the job. No compensation for not acquainting themselves with the actual site conditions will be entertained at the later stage.			
18	All materials shall confirm to the latest IS/IRC/MORTH specifications			

CONTRACTOR/TENDERER

ACCEPTING OFFICER