

194

PRE-QUALIFICATION REQUIREMENT**(Rev-02)**

1	Submission of EMD as specified in NIT (Receipt copy to enclosed)
2	Bidder should have successfully executed (running / completed) similar works for any of the following during the last seven years: (i). For serial No. 12 of Indent No. 20190062 (Rev-03) - Three Similar work costing not less than the amount to Rs. 0.50 Lakh each or - Two Similar works costing not less than the amount to Rs, 0.60 Lakhs each or - One Similar work costing not less than the amount to Rs. 1.00 Lakhs each (ii). For serial No. 5 & 6 of Indent No. 20190062 (Rev-03) - Three Similar work costing not less than the amount to Rs. 0.60 Lakh each or - Two Similar works costing not less than the amount to Rs, 0.70 Lakhs each or - One Similar work costing not less than the amount to Rs. 1.10 Lakhs each (iii). For serial No. 7, 8, 9, 10 & 11 of Indent No. 20190062 (Rev-03) - Three Similar work costing not less than the amount to Rs. 1.45 Lakh each or - Two Similar works costing not less than the amount to Rs, 1.80 Lakhs each or - One Similar work costing not less than the amount to Rs. 2.90 Lakhs each Actual executed value shall be considered based on work completion certificate from work contracting organization. Bidders to submit work execution certificate from the work contracting organization bearing its complete address, name of contact person and valid contact phone no(s) in support of this criteria.
3	(a). Average Financials turnover during the last three years, ending 31st March 2018 should be at least 0.35 Lakhs for serial no. 12, 0.40 Lakhs for serial no. 5 & 6 and 1.10 Lakhs for serial no. 7,8,9,10 & 11 of Indent No. 20190062 (Rev-03). (b). Bidder must have earned profit in any of the three financial years as applicable in the last three financial years as furnished for (a) above. Note: PROFIT shall be PBT earned during any one year of last three financial years as in (a) above. The following documents should be submitted by the bidder: (i). Balance sheet and Profit & Loss Account (audited/issued by Chartered Accountant) of last three years ending on 31st March 2018 in support of the above. (ii). If financial statements are not required to be audited statutorily, then instead of audited financial statements, financial statements are required to be certified by Chartered Accountant.
4	Bidder to submit signed & stamped (on each page) copy of terms & conditions and scope of work unequivocal acceptance of all terms & conditions and scope of work of contract.
5	Note (i): The party should submit EMD as per Sl. 1, documents mentioned in Sl. NO. 2 & 3 and acceptance as per Sl. 4. These are mandatory qualifying criteria & non fulfillment of any one or more criteria shall render the offer as technically rejected. Note (ii): Time period for achievement of the Qualification Requirements is in the last 7 years ending on the 'latest date of Bid Submission' of tender. Note (iii). Definition of similar work: Bidder should have experience of, Painting work for item no. 12 (if vendor is quoting for item 12), Civil work for item no. 05 & 06 and MS Fabrication work experience for rest of the items.

Authorized Sign. With seal



Name of the Party

Address:

Contact of details

E-Mail Address:

SPECIAL TERMS & CONDITIONS

- 1). In old surface painting, all loose pieces and scales shall be removed by sand papering. the surface shall be cleaned of all grease, dirt, etc. after removal of scrap will be removed by contractor at a suitable place directed by engineer-in-charge.
- 2). Paint should be placed in 2 coats. The finished surface shall be even and uniform and shall be free from brush marks.
- 3). Paint drops cleaning will be done by contractor.
- 4). Cement should be received from civil store on day to basis for execution of works.
- 5). Shuttering & scaffolding materials is to be arranged by contractor.
- 6). Disposal of scrap materials by contractor up to lead 200 meters.
- 7). Crane, ladder etc. whatever required to remove the MS structure/ tower from the top of main gate, is to be arranged by contractor.
- 8). Tile wastage etc. should be dumped at a suitable place as per direction given by engineer-in-charge.
- 9). Rectification of cable trenches is based as per site requirement.
- 10). Cable trench covers length & breadth varies as per site requirement.
- 11). All type of tools & tackles required for the works will be arranged by the contractor.
- 12). Power & water supply point will be provided by M/s BHEL.
- 13). The quantity/area of items may be decrease at the time of work.
- 14). All direction in respect of execution of work given by engineer-in-charge will be final and no-objectionable by the contractor.
- 15). The vitrified floor tiles, MS Structure, Galvalume Sheets, MS sheets, Cement, Sand, Aggregate and self-drilling screw will be provided by BHEL. The labour, welding machine, welding rods, sun film for glasses and other required tools & tackles etc. will be borne & brought by the contractor.
- 16). **Work Completion schedule:** The work will be completed within 60days from the date of order.
- 17). **LD Clause:** LD clause having penalty on late delivery @0.5% per week, which will be applicable if works not get completed within delivery schedule.
- 18). **Risk Purchase:** In case, contractor does not carry out the services/repair as per work completion schedule, in order to safeguard its interest under the contract, BHEL, at its own discretion, may get the services/repair/replacement of spares done through suitable alternative source(s) at risk & cost of the contractor. In such cases, any cost incurred to BHEL over and above contracted rates shall be recovered from dues payable to the contractor and no claim of compensation of loss, whatsoever, incurred by the contractor due to such recovery, shall be entertained by BHEL.

Signature
27/9/19

Signature

19. Contractor have to provide the following documents and acceptance:

1	Name & Address of Party	
2	EPF Registration No.(Enclose a Copy)	
3	ESI Registration No.(Enclose a Copy)	
4	Pan Card No.(Enclose a copy)	
5	GST Registration no.(Enclose a Copy)	
6	Bank Account Details IFSC Code Account No. Bank Name Branch Name	Accepted & Documented submission
7	Acceptance to provide trained /qualified staff	Accepted & Documented submission
8	Acceptance of E-Payment	Accepted & Documented submission



Addl. Engineer (Civil)



Dy. Manager (Mnt/Civil/DTG)

BOQ & FORMAT OF PRICE BID FOR MISCELLANEOUS CIVIL WORKS AT BHEL-CFP RUDRAPUR

ANNEXURE-III (Rev-01)

S.NO.	Description of work	Qty	Unit	Rate	Amount
1	Painting Works As per Annexure- V on Internal & External surfaces at BHEL-CFP Rudrapur	1.00	set		
2	Floor tiling work (Main gate reception, old PPC room adjacent to OAB, Production office, OAB, Electrical office, Server Room). The tiles, Cement, sand and water point will be provided by BHEL.	5850.00	Sq. ft		
3	Rectification of cable trenches including resizing of trench & fixing of support for covers. The required materials will be provided by BHEL.	100.00	RM		
4	Fabrication and fixing of MS Structure as Shed post, truss, Purlins, Cable Trench Covers, Drain grating and Ladder for OPS crane. Structural steel will be provided by BHEL. The welding machine, welding rods and other required tools & tackles will be arranged by the contractor.	16302.00	Kg		
5	Fixing of galvalume sheets at shed. The Galvalume sheets & self drilling screw will be provided by BHEL. The tools will be arranged by the contractor.	3800.00	Sq-ft		
6	Fabrication of File Racks. The materials will be provided by BHEL. The welding machine, welding rod and other tools are in contractor's scope.	1675.00	Kg		
7	Supply and pasting of sunfilm on glasses of Admin buliding. The materials and tools are in contractor's scope.	768.00	Sq. ft		
8	Removal of Tower from roof top of Main Gate. Required tools and machines will be bought & borne by the contractor.	1.00	No.		
	TOTAL AMOUNT OF PART (A)+ PART (B)				
	GST				
	GRAND TOTAL				

Note: - L1 will be decide on individual item basis.



ANNEXURE-V

S.NO.	Description of work	Qty	Unit	Price distribution in % of total	Rate	Amount
	Painting Work					
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	2282.97	Sqm	15		
2	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer (Only cement primer will be supplied by BHEL). It will include the painting of the new surface appeared during repairing work.	1699.22	Sqm	30		
3	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats)(Only oil bound distemper will be supplied by BHEL). It will include the painting of the new surface appeared during repairing work.	1155.79	Sqm	25		
4	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface (acrylic paint & its carriage will be supplied by BHEL). It will include the painting of the new surface appeared during repairing work.	1127.18	Sqm	30		
	Total Amount					
	Gst@18%					
	Grand Total					

Signature
8/8/19