



भारत हेवी इलेक्ट्रिकल्स लिमिटेड
(भारत सरकार का उपक्रम)
सेंट्रलाइज्ड स्टेपिंग इकाई एवं फेब्रिकेशन प्लांट
औद्योगिक क्षेत्र जगदीशपुर, जिला- अमेठी (उ०प्र०)-227817
दूरभाष: 05361-224128, फैक्स: 05361-224166

SECTION – III

TENDER FOR CLEANING AND RECTIFICATION OF DRAINS AT CSU& FP PLANTS AT BHEL JAGDISHPUR

Tender Enquiry No: BHE/FP/CVL/17-18/02

BOQ & Price Schedule

BHARAT HEAVY ELECTRICALS LIMITED
(A GOVERNMENT OF INDIA UNDERTAKING)
CSU & FP Industrial Area, Jagdishpur (UP) 227817



भारत हेवी इलेक्ट्रिकल्स लिमिटेड
(भारत सरकार का उपक्रम)
सीएसयू एवं एफ़पी जगदीशपुर, जनपद- अमेठी

SECTION-III

TE. No. BHE/CSU/CVL/17-18/02

BOQ & PRICE SHEDULE OF TENDER FOR CLEANING AND RECTIFICATION OF DRAINS AT CSU& FP Plants at BHEL Jagdishpur

S. No.	DESCRIPTION OF WORK	UNIT	QTY.	Quoted Rate (Rs.)		Amount (Rs.)
				In Figures	In words	
1	Cleaning of Drain and disposal of sludge/ malba / debris within 1.5 Km. lead as per direction of Engineer-in- charge.	Rm	2175			
2	Demolishing R.B. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in- charge.	Cum	3.5			
3	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. All kinds of soil.	Cum	27.0			
4	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Cum	5.0			
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8(1 Cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	Cum	1.0			



भारत हेवी इलेक्ट्रिकल्स लिमिटेड
(भारत सरकार का उपक्रम)
सीएसयू एवं एफ़पी जगदीशपुर, जनपद- अमेठी

SECTION-III

TE. No. BHE/CSU/CVL/17-18/02

BOQ & PRICE SHEDULE OF TENDER FOR CLEANING AND RECTIFICATION OF DRAINS AT CSU& FP Plants at BHEL Jagdishpur

S. No.	DESCRIPTION OF WORK	UNIT	QTY.	Quoted Rate (Rs.)		Amount (Rs.)
				In Figures	In words	
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	14.0			
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level with 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	Cum	1.5			
8	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand)	Sqm	36.0			
9	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete with 300 mm dia. R.C.C. pipe	Rm	60.0			
10	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete with 250 mm dia. R.C.C. pipe	Rm	50.0			
Total Amount (Exclusive of Service Tax)=						
Total Amount in Figures						

Note: Service tax shall be paid extra as applicable.

(Sign Seal of BHEL)

(Sign Seal of the contractor)