



BHARAT HEAVY ELECTRICALS LIMITED
PROJECT ENGINEERING MANAGEMENT, NOIDA

Date-23-Oct-21

CORRIGENDUM- 01

PROJECT	:	1X660 MW WBPDCS SAGARDIGHI project
PACKAGE	:	ELEVATORS
ENQUIRY NO	:	PE/PG/SGI/E-6788/2021 dtd 13/10/2021
SUBJECT	:	PRE-BID CLARIFICATION + DUE DATE EXTENSION

Type of Corrigendum			
Technical Corrigendum -	<input checked="" type="checkbox"/>	Commercial Corrigendum -	<input checked="" type="checkbox"/>

In reference to the above mentioned tender enquiry for **ELEVATORS** package.

Please note the following:

1. Bidders are requested to go through the attached pre-bid clarification with this corrigendum and quote accordingly.
2. Due date for offer submission has been extended from 23/10/2021 to 29/10/2021 (11:00 AM and P1 shall be opened at 4:00 pm on 29/10/2021).

All the other terms and conditions of the tender enquiry shall remain unchanged. All the bidders are requested to quote accordingly.

Yours faithfully,

For and on behalf of BHEL

Guru Das
Manager



**1X660MW SAGARDIGHI TPP EXTENSION (UNIT-5)
PACKAGE: ELEVATORS**

SPECIFICATION No: PE-TS-445-502-A001

VOLUME: III

SECTION-III

SUB-SECTION-III C

REV 00

DATE 23.10.2021

SUB SECTION-III E

PRE BID CLARIFICATIONS



**1X660MW SAGARDIGHI TPP EXTENSION (UNIT-5)
PACKAGE: ELEVATORS**

SPECIFICATION No: PE-TS-445-502-A001

VOLUME: III

SECTION-III

SUB-SECTION-IIIIC

REV 00

DATE 23.10.2021

PRE-BID CLARIFICATIONS

S. No.	Section/Clause/Page No.	Statement of the referred clause / Clarification Required	BHEL's clarification
1.	-	Payment Terms is not mentioned in the document.	Shall be as per GCC rev-07 (https://pem.bhel.com/Documents/GCC/GCCR ev07.pdf)
2.	-	Details of Security Deposit / Bank Guarantee required is not available in the document.	Shall be as per GCC rev-07 (https://pem.bhel.com/Documents/GCC/GCCR ev07.pdf)
3.	-	Warranty / Guarantee & LD details are not available in the document.	Shall be as per GCC rev-07 (https://pem.bhel.com/Documents/GCC/GCCR ev07.pdf)
4	SPEC. NO. PE-TS-445-502-A001 / TECHNICAL SPECIFICATION FOR ELEVATOR	Flooring for Lift Car is mentioned as Vitrified Ceramic Tiles in one place and other place it is mentioned as MS Chequered flooring. Please confirm.	Please refer Datasheet-A (Section-IC), page 267 of 286 of Technical Specification. MS Chequered flooring shall be provided. Requirement mentioned in Datasheet shall prevail.
5	SPEC. NO. PE-TS-445-502-A001 / TECHNICAL SPECIFICATION FOR ELEVATOR	Handrail asked in 3 side of Car. Please confirm as this is not required in Goods elevator i.e. Capacity of 2000 Kg and 1000Kg	Specification shall be followed.
6	SPEC. NO. PE-TS-445-502-A001 / TECHNICAL SPECIFICATION FOR ELEVATOR	Emergency Exit is asked in the specification. Please note that this is an outdated requirement. Further Emergency Exit can be provided in Goods Elevator i.e. Capacity of 2000 Kg and 1000Kg only. Also wherever Emergency Exit has been asked, False Ceiling in Car can not be provided.	Noted. However, this may be reviewed during detail engineering stage and acceptance of same is not binding on the customer hereby and will be solely as per discretion of the customer after reviewing failsafe operation.
7	SPEC. NO. PE-TS-445-502-A001 / TECHNICAL SPECIFICATION FOR ELEVATOR	Mirror in Lift Car has been asked in the specification. Please note that for Goods Lift, it is not advisable as the same will be prone to damage due to material handling.	Specification shall be followed.
8	SPEC. NO. PE-TS-445-502-A001 /	Trailing cables - FRLS type/as per manufacture	The same may be read as:



**1X660MW SAGARDIGHI TPP EXTENSION (UNIT-5)
PACKAGE: ELEVATORS**

SPECIFICATION No: PE-TS-445-502-A001

VOLUME: III

SECTION-III

SUB-SECTION-III C

REV 00

DATE 23.10.2021

TECHNICAL SPECIFICATION FOR
ELEVATOR

standard

Trailing cables – FRLS VLH (Fire Retardant
Low Smoke Very Low Halogen) ~~as per~~
~~manufacture standard~~