



निविदा सूचना TENDER ENQUIRY

भारत हेवी इलेक्ट्रिकल्स लिमिटेड, हीप, हरिद्वार - 249 403 भारत

Bharat Heavy Electricals Ltd. HEEP, HARIDWAR-249 403 INDIA
B/ 4011/0/2194V1

19-11-2020

AZ 17001(B)

Phone: (0091)(01334) 227350-227356 (7 Lines) & 228350-51(2 Lines) • Telefax (0091) (01334) 226462 & 223948

TIN No. : 0500175727/30-09-05
C.S.T.No. : HR-5000030/16-03-65

निविदा सूचना नं. ENQUIRY NO. ★

DUPLICATE

12-12-2020

BHEL

कृपया निम्नलिखित के लिए निविदा दें। PLEASE QUOTE FOR THE FOLLOWING :

Vendor Code

00001

HARIDWAR249403

INDIA

SL	MATERIAL CODE ITEM DESCRIPTION	QUANTITY	UNIT	LOTNO	LOT DELIVERY QTY SCHEDULE
1	W90313240400 DRG: 21324030000 REV: 01 LEAK OFF STEAM VALVE WITH PNEUMATIC ACTUATOR	2	NO	1 2	1 30/07/22 1 30/01/23
2	W99313240530 DRG: 41324030004 REV: SPARES:LEAK OFF STEAM VALVE	1	ST	1	1 31/12/22

** IMPORTANT: This enquiry is 2 part tender. Techno-Commercial bid (Part-1) & Price Bids (Part-2) should be submitted in separate envelopes. These two envelopes should be submitted in a common sealed envelope. Techno-Commercial Bid shall contain detailed Technical Specification, Drawings Technical documents, Catalogues, taxes & duties, payment terms, delivery period, Validity of offer, Replica of Price Bid (Copy of price bid without price part) etc. The confirmation to the special terms & conditions must be submitted alongwith Techno-Commercial bid.

Special Instructions:

Items is required for Khurja Project.
The Offers is to be submitted as per NIT documents.

General Instructions:

Please visit our site www.bhelhwr.co.in for latest version of General Instructions and Standard Terms & Conditions (GISTC) for Tender Enquiries. All the bidders/vendors must ensure compliance of latest GISTC. Terms & Conditions printed overleaf of this Standard Tender enquiry format are null & void.

For this procurement, Public Procurement (Preference to Make in India), Order 2017 dated 15.06.2017 & 28.05.2018 and subsequent Orders issued by the respective Nodal Ministry shall be applicable even if issued after issue of this NIT but before finalization of contract / PO / WP against this NIT.

In the event of any Nodal Ministry prescribing higher or lower percentage of purchase preference and/ or local content in respect of this procurement, same shall be applicable.

Default purchase preference under Make in India order shall be 20% to suppliers

Page No

1

★ महत्वपूर्ण: कृपया कोटेशन देने से पूर्व पीछे दिए गये अनुदेशों को ध्यानपूर्वक पढ़िये।

PLEASE CAREFULLY THE INSTRUCTIONS GIVEN ON REVERSE BEFORE QUOTING



निविदा सूचना

भारत हेवी इलेक्ट्रिकल्स लिमिटेड, हीप, हरिद्वार - 249 403 भारत

TENDER ENQUIRY**Bharat Heavy Electricals Ltd. HEPP, HARIDWAR-249 403 INDIA****19-11-2020**

AA-17001(B)

B/ 4011/0/2194V1

Phone : (0091)(01334) 227350-227356 (7 Lines) & 228350-51(2 Lines) • Telefax (0091) (01334) 226462 & 223948

TIN No. : 05001757277/30-09-05
C.S.T.No. : HR-5000030/16-03-65

MATERIAL CODE	ENQUIRY NO	QUANTITY	UNIT	LOTNO	दिनांक Date
ITEM DESCRIPTION	कृपया निम्नलिखित के लिए निविदा दें। PLEASE QUOTE FOR THE FOLLOWING:				

with default minimum local content of 50% for all items / works / services.
For further details, please refer latest version of GISTC.
Procurements where the Estimated value to be procured is less than Rs. 5 lakhs
shall be exempted from Public Procurement (Preference to Make in India),
Order 2017 dated 15.06.2017 & 28.05.2018

for Sanath
19/11/20

RAHUL SHARMA
DY. MANAGER (PPX-BOI)

AGM (PPX-BOI)
BHARAT HEAVY ELECTRICALS LIMITED,
Heavy Electrical Equipment Plant
Ranipur, Haridwar – 249 403
(UK), India



Tender Enquiry No. B/4011/2020/2194V/1 for Leak Steam Valve for Khurja project.

ENQUIRY DUE DATE/ TENDER OPENING DATE:12/12/2020

INDEX

The technical specifications/Drawings uploaded along with this Open Tender are as mentioned below. In case of non-receipt or non-clarity of any of these documents, you may contact undersigned. No Financial Implication on account of non-availability of documents would be entertained after opening of Techno-Commercial Offers.

LIST OF ENCLOSURES

<u>Commercial Documents</u>			
Sl. No.	<u>Document No.</u>	<u>Number of pages</u>	Page No. of PDF file
1.	TENDER DETAILS (INDEX)	01	Pg. 1 to 1
2.	TENDER DETAILS AND INSTRUCTION TO BIDDERS (ANNEXURE-1)	07	Pg. 2 to 8
3.	SPECIAL TERMS AND CONDITIONS INDIAN SUPPLIER (ANNEXURE-1A)	07	Pg. 9 to 15
4.	GENERAL INSTRUCTIONS & STANDARD TERMS & CONDITIONS (GISTC VERSION APRIL-2019, REV.:04) FOR INDIGINOUS SUPPLIER	12	Pg. 16 to 27
5.	Certificate by Chartered Accountant on Letter Head (MSME)	01	Pg. 28 to 28
6.	Make in India Certificate.	01	Pg. 29 to 29
7.	List of BHEL consortium Bank	01	Pg. No 30 to 30
	TOTAL PAGES	30	

<u>Technical Documents</u>			
	<u>Document No.</u>	<u>Number of pages</u>	Page No. of PDF file
1.	PRE-QUALIFICATION REQUIREMENT (ANNEXURE-A)	2	Pg. 1 to 2
2.	Technical Documents	9	Pg. 3 to 11
3.	Standard Quality Plan	3	Pg. 12 to 14
	TOTAL PAGES	14	
	<u>Commercial Documents and Technical Documents</u>	44	

RAHUL SHARMA (DY. MANAGER/PPX-BOI)
Email: rahuls@bhel.in
Ph. 01334-281753
Mobile No.-9758539500

Ashish Gupta (SDGM/ PPX-BOI)
Email: gupta.a@bhel.in
Ph. 01334- 285834
Mobile No.-9410395860



PPX-BOI DEPARTMENT
BHARAT HEAVY ELECTRICALS LIMITED
HEEP: HARDWAR-249 403 (Uttarakhand)
FAX: +91 1334 226084/226462
TEL: +91 1334 28 1753 / 5834/1690

ENQUIRY NO. B/4011//2020/2194V1
ITEM: LEAK OFF STEAM VALVE
PROJECT: KHURJA PROJECT

NIT: TENDER DETAILS AND INSTRUCTION TO BIDDERS (ANNEXURE-1)

1. SCOPE OF ENQUIRY

Sealed Bids are invited from bidders for the supply of Leak Steam Control Valve along with spares for Khurja Project as per requirement mentioned below:

Please note that Procurement of all items covered as following details (sl. Item No. -1 to 3) would be made from the same vendor.

Sl. No.	Material Code	Item Description	Qty.	Scheduled Delivery
1.	W90313240400	Leak off Steam Control Valve	1 No.	30/07/2022
		Leak off Steam Control Valve	1 No.	30/01/2023
2.	W99313240530	Spares: Leak off Steam Valve	1 Set	31/12/2022

Note: Bidders are requested to quote their best possible minimum delivery in numbers of weeks' / months from the date of purchase order / document approval.

2. PROJECT INFORMATION:

Project Name	2x660MW Khurja Unit-1 & 2
Consignee Address	GENERAL MANAGER(PROJECTS) KHURJA STPP, THDC INDIA LIMITED DIST- BULANDSAHAR UTTAR PRADESH, PIN-203131
Custom Duty	CD- Project Import
GST	Extra as applicable

3. PRE-QUALIFICATION REQUIREMENT (PQR)

The Pre-Qualification Requirements have been compiled and placed at **ANNEXURE-A**. All the bidders should ensure submission of complete details and documents as called for in these requirements. The Offers submitted by the bidders would be scrutinized with respect to Pre-Qualification Requirements first. Techno-Commercial offer of only those bidders shall be evaluated who meet the Pre-Qualification Requirements.

Important Note: Bidders should ensure completeness and correctness of all supporting documents of PQR along with their offer. Not more than 30 days (After Opening of Techno-commercial offers) will be allowed to bidders for completing PQR documents. PQR review will be closed within 30 days of opening of techno-commercial Bids. Offers of Bidder / Bidders, who do not meet PQR i.e. do not complete the PQR documentation within 30 days of opening of techno-commercial bid, may be ignored and no-further correspondence may be entertained thereafter.

4. SUBMISSION OF OFFER

4.1 Only English version of all documents would be valid & binding.

4.2 Bidders are advised to study all the tender documents carefully. Submission of offer by the bidder shall be deemed to have been done after careful study and examination of the tender documents and with full understanding of the implications thereof. The specifications and terms & conditions shall be deemed to have been accepted unless otherwise specifically commented upon in 'Deviation' sheets by the bidder in his offer. Non-compliance with any of the requirements and instructions in the Tender Enquiry may result in rejection of the offer.



PPX-BOI DEPARTMENT
BHARAT HEAVY ELECTRICALS LIMITED
HEEP: HARDWAR-249 403 (Uttarakhand)
FAX: +91 1334 226084/226462
TEL: +91 1334 28 1753 / 5834/1690

ENQUIRY NO. B/4011//2020/2194V1
ITEM: LEAK OFF STEAM VALVE
PROJECT: KHURJA PROJECT

NIT: TENDER DETAILS AND INSTRUCTION TO BIDDERS (ANNEXURE-1)

4.3 Name of dealing person of vendor with Contact No(s), Email ID and Address of correspondence shall be provided in the bid. (02 Person's or more details may be provided by bidder).

4.4 Tenders are to be submitted in **Two Parts (Pre-Qualification Requirement(PQR) & Techno-commercial Bid – Part 1 and Price Bid – Part 2).**

Part-1 (Pre-Qualification Requirement(PQR) & Techno-commercial Bid – Part 1) will be opened first. And price bids of only those successful bidders would be opened who are qualified in all means and meeting all tender requirements.

The offers are to be submitted on or before the Due Date and time, as per details below:

[A] PART-I: PRE-QUALIFICATION REQUIREMENT (PQR) & TECHNO-COMMERCIAL BID

Comprising of following documents:

- a. Earnest Money Deposit (EMD)/details of EMD in case of e-payment (or Notarized copy of required Certificate for exemption of EMD)
- b. Vendors are required to furnish requisite details in the formats specified in bidding documents for meeting the stipulated **Pre-Qualification Requirements (PQR)** along with all supporting documents to fulfill the PQR requirement. The Pre-Qualification requirements are as per enclosed **ANNEXURE-A**.
- c. Complete Technical offer with relevant drawings/ documents etc.
- d. **"TENDER DETAILS AND INSTRUCTION TO BIDDERS (ANNEXURE-1)", Special Terms & Conditions of the Tender enquiry (Annexure-1A) and "GISTC [General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (Version April-2019, Rev:04)]"** are an integral part of this enquiry and endorsed copies of these documents (duly signed and stamped on each page, as a token of acceptance) are to be necessarily submitted along with the offer.
- e. Commercial Terms & Conditions.
- f. Replica of price-bid without prices.
- g. **Quality Requirement: -**
 1. Please confirm for compliance of enclosed standard quality plan no. QA/BI/QP/135.
 2. Inspection shall be done by BHEL nominated inspection agency BVIL as per BHEL standard quality plan no. QA/BI/QP/135. Please confirm.
 3. The Charges for Pre-Inspection would be borne by BHEL. However at least 15 days' notice is to be provided for arranging Pre-Inspection.
- h. Any Deviation with reference to technical requirements/specification to be laid down on separate sheet along with the cost of Withdrawal of such technical deviations (if any). Acceptance of such technical deviations would be at the discretion of BHEL.
- i. Supplier Registration Form: Online Registration Portal is operational in BHEL. Bidders not registered at BHEL, Hardwar for this item; have to apply through Online Registration portal, <https://supplier.bhel.in/>. All credentials and/or documents duly signed and stamped related to registration has to be uploaded on the website and the application submitted for registration. Application registration No. (for applying online form) should be mentioned in the techno-commercial offer.
- j. Any other documents required to be submitted as per your offer.

[B] PART-II: PRICE-BID

- a. Price bid
- b. Cost of withdrawal of deviation (if any) shall be submitted in this part.

4.5 Following shall be super scribed on the envelopes which shall be addressed by name and designation to the official inviting tender:



PPX-BOI DEPARTMENT
BHARAT HEAVY ELECTRICALS LIMITED
HEEP: HARDWAR-249 403 (Uttarakhand)
FAX: +91 1334 226084/226462
TEL: +91 1334 28 1753 / 5834/1690

ENQUIRY NO. B/4011//2020/2194V1
ITEM: LEAK OFF STEAM VALVE
PROJECT: KHURJA PROJECT

NIT: TENDER DETAILS AND INSTRUCTION TO BIDDERS (ANNEXURE-1)

PART-I BID: 1. TENDER ENQUIRY NO. AND ITEM DESCRIPTION

2. DUE DATE FOR OPENING

3. TECHNO-COMMERCIAL BID WITH PQR.

PART-II BID: Price bid envelopes to be prepared by participant bidders and envelope to be super scribed in BOLD Letters "Part- II Bid- Price Bid – Tender Enq. No..... , NAME OF PROJECT". As mentioned below

1. TENDER ENQUIRY NO AND ITEM DESCRIPTION

2. DUE DATE FOR OPENING

3. PRICE BID with Project NAME

4.6 Parts –I Bid & Part- II Bid shall be submitted in separate sealed covers duly super scribed as indicated above and shall be enclosed further in a main cover envelope duly sealed and super scribed as:

1. TENDER ENQUIRY NO AND ITEM DESCRIPTION (As per page 1 of this document)

2. DUE DATE FOR OPENING

3. PART-I BID & PART-II BID

4.7 (a) Quotation must be enclosed in sealed cover on which tender enquiry number and the due date MUST BE written and be invariably sent under REGISTERED POST / SPEED POST / COURIER/Dropped in the Tender Box of HEEP BHEL Haridwar, addressed as follows:

To,
THE HEAD OF MATERIAL MANAGEMENT,
Heavy Electrical Equipment Plant,
Bharat Heavy Electricals Limited,
HARIDWAR-249403 (Uttarakhand), INDIA.

4.7 (b) Bidders can submit their offer through email at tendercell.heep@bhel.in on or before due date and time as per tender enquiry. Bidders submitting their bids through e-mail shall have to mention following in subject line.

1. Tender Enquiry Reference No. _____

2. Bid Opening Date (Part 1, Techno- commercial) _____

Vendor to submit their bids as attachment (pdf format) with password protection and share the password through mail (tendercell.heep@bhel.in) after 1:45 PM (IST) on the day of bid opening, however if no password is received up to 04:00 PM (IST) bids will not be opened and will be ignored. Submission of bids through email shall be considered as consent to open the bid without physically witnessing the event.

4.8 Tender opening is scheduled to start in the Tender Room at 2:00 PM, on the due date. Therefore, bid/quotations must reach tender Box latest by 1:45 PM on due date. Only participating bidders are allowed to attend tender opening. TENDERS RECEIVED AFTER THE SPECIFIED DATE & TIME OF THEIR 'SUBMISSION' WILL BE TREATED AS LATE TENDERS AND SHALL NOT BE CONSIDERED UNDER ANY CIRCUMSTANCES.

The bid/quotation must be posted before due date, keeping allowance for postal transit time. Alternatively, the tenders duly sealed and super-scribed as above may be deposited in the Tender Box. Quotations sent by any mode but not received in time will be ignored by BHEL. Tender received through authorized E-mail is also acceptable. **However, in time submission of tender in tender box shall be the responsibility of the bidder, sent through any mode.** Documents submitted with the offer/bid shall be



PPX-BOI DEPARTMENT
BHARAT HEAVY ELECTRICALS LIMITED
HEEP: HARDWAR-249 403 (Uttarakhand)
FAX: +91 1334 226084/226462
TEL: +91 1334 28 1753 / 5834/1690

ENQUIRY NO. B/4011//2020/2194V1
ITEM: LEAK OFF STEAM VALVE
PROJECT: KHURJA PROJECT

NIT: TENDER DETAILS AND INSTRUCTION TO BIDDERS (ANNEXURE-1)

signed and stamped in each page by authorized representative of the bidder.

4.9 PART-I Bid (Techno-Commercial bid with PQR) will be opened on Due Date and time specified in the Enquiry, or extension thereof, in presence of tenderers who may like to attend. Incomplete offers are liable to be rejected.

4.10 Only those vendors would be considered for Price Bid Opening/Reverse Auction who are accepted in all respect i.e. Pre-qualification Requirement, techno-commercial acceptance, "BHEL" etc. on or before the date of Price Bid Opening/Reverse Auction.

4.11 All correspondence thereof, shall be addressed to the following persons:

Mr. Rahul Sharma
Designation: Dy. Manager (PPX-BOI)
4th Floor, Main Admin. Building
HEEP, BHEL, Hardwar- 249403
Uttarakhand, India
Email ID: rahuls@bhel.in
Tel: +91 1334 28 1753
Mobile No.: 9758539500

Mr. Ashish Gupta
Designation: SDGM (PPX-BOI)
4th Floor, Main Admin. Building
HEEP, BHEL, Hardwar- 249403
Uttarakhand, India
Email ID: gupta.a@bhel.in
Tel: +91 1334 28 5834
Mobil No.:9410395860

4.12 Bidders or their authorized representatives shall be allowed in the tender room in area identified for bidders and only one authorized representative from each bidder shall be allowed. The authorized representative should bring enquiry specific authority letter from their principal for attending the bid opening on that particular day. General authorization letter is not acceptable.

4.13 Bidder shall not be allowed to carry camera/laptop/any kind of recording device in the tender room. The use of Mobile Phone is also restricted in the Tender Room. Any kind of photography / videography by bidders is not allowed in tender room.

4.14 Details of offers shall be read out to bidders and in no case the offers shall be handed over to any of the bidder's /bidder's representative for noting down.

4.15 As per directives of CENTRAL VIGILANCE COMMISSION, GOVERNMENT OF INDIA, one agent cannot represent two or more suppliers or quote on their behalf in a particular tender. If so found at any stage, BHEL Hardwar is likely to cancel Enquiries / POs to such suppliers. Further, such agent is likely to be de-listed (Black listed for business from BHEL).

Moreover, either the agent could bid on behalf of the manufacturer/ supplier or the manufacturer/ supplier could bid directly but not both. In case bids are received from both the manufacturer/ supplier and the agent, bid received from the agent shall be ignored.

Vendors operating from BHEL quarters, unauthorized colonies on BHEL Land and Dharamshalas / Hotels shall not be considered, hence such vendors need not apply.

4.16 The offer of vendors who are banned/deleted/under hold by BHEL, shall be rejected. The list of banned firms is available on BHEL website www.bhel.com. (Supplier Registration link).

4.17 Please ensure that each page of the offer/bid is signed & stamped by authorized representative of bidder.

4.18 Envelope not marked with tender Enquiry no. is liable to be ignored and may not be opened.

k. EARNEST MONEY DEPOSIT (EMD)



PPX-BOI DEPARTMENT
BHARAT HEAVY ELECTRICALS LIMITED
HEEP: HARDWAR-249 403 (Uttarakhand)
FAX: +91 1334 226084/226462
TEL: +91 1334 28 1753 / 5834/1690

ENQUIRY NO. B/4011//2020/2194V1
ITEM: LEAK OFF STEAM VALVE
PROJECT: KHURJA PROJECT

NIT: TENDER DETAILS AND INSTRUCTION TO BIDDERS (ANNEXURE-1)

5.1 Interested bidders must submit their offer along with the following Earnest Money Deposit (EMD) in a separate sealed envelope:

Details	Amount In INR	Amount in Foreign Currency	Type
EMD	INR 1,00,000/- (INR One Lakh)	Foreign currency equivalent to INR 1,00,000/-	Refundable

5.2 The EMD should be submitted in the form of demand draft / Pay Order/ cash (as permissible under income tax act). The Drafts shall be drawn in favor of "**BHEL Hardwar**". In case of foreign bidders, e-payment is also acceptable. For e-payment, RTGS details are as mentioned below:

Bank Details	SWIFT Details of bank	Contact Details of Banker
STATE BANK OF INDIA RANIPUR BRANCH, OPP: BHEL MAIN GATE, SECTOR-5, RANIPUR, HARIDWAR, UTTRAKHAND INDIA; PIN CODE : 249403	SWIFT NO: SBININBB225 CC ACCOUNT NO: 10667995458 IFSC CODE: SBIN0000586	Name: Sh. Sudhir Sharma Design: Chief Manager (IBD) Contact No. +91 1334 224201 +91 1334 226125 Fax: +91 1334 226512

5.3 The suppliers who are already registered in PMD (product Material Directory) of BHEL, HEEP Haridwar for supply of this item are exempted from submission of EMD.

5.4 MSE Suppliers/Central / State – PSUs / Government departments are exempted from submission of the EMD. "MSE Suppliers can avail the intended benefits only if they submit along with the offer Udyog Adhaar Memorandum (UAM), attested copies of either EM II certificate having deemed validity (05 years from the date of issue of acknowledgement in EM II) or valid NSIC certificate or EM II certificate along with attested copy of a CA certificate (format enclosed where deemed validity of EM II certificate of five years has expired) applicable for the relevant financial year (latest audited). Date to be reckoned for determining the deemed validity will be the date of bid opening (part-1 bid in case of two part bid). Non-submission of such documents will lead to consideration of their bid at par with other bidders. No benefit shall be applicable for this enquiry if any deficiency in the above required documents is found or the requisite documents are not submitted before price-bid opening. If the tender is to be submitted through e-procurement portal, then the above require document are to be uploaded on the portal. Documents should be notarized or attested by a Gazette Officer."

5.5 The bidder whose bid is technically not accepted will be informed & EMD wherever submitted shall be returned after the finalization of the contract.

5.6 EMD by the Tenderer will be forfeited as per Tender Documents if, the successful bidder/vendor refuses to honor the Order after award of the same on him and/or withdraws his bid and /or unilaterally changes the offer and/or any of its terms & conditions within the validity period.

6. TECHNICAL REQUIREMENT

Please ensure completeness of your offer along with all the relevant documents as per **technical specifications/documents/addendum etc.**

7. PRE BID CLARIFICATION/ PRE BID MEETING

- Please note that as per BHEL's Policy, we cannot allow Price impact for the requirement / scope of supply, which is a part of specification/documents of our tender enquiry. Hence please read all specification / documents thoroughly and submit your offer accordingly.



PPX-BOI DEPARTMENT
BHARAT HEAVY ELECTRICALS LIMITED
HEEP: HARDWAR-249 403 (Uttarakhand)
FAX: +91 1334 226084/226462
TEL: +91 1334 28 1753 / 5834/1690

ENQUIRY NO. B/4011//2020/2194V1
ITEM: LEAK OFF STEAM VALVE
PROJECT: KHURJA PROJECT

NIT: TENDER DETAILS AND INSTRUCTION TO BIDDERS (ANNEXURE-1)

- In case of any confusion / non-clarity on any of the clause / requirement of specification, please clarify the same from BHEL before submission of offer. Pre-bid meeting can also be arranged on bidder's request for clarification of techno-commercial scope.
- Deviation & request regarding non-clarity / contradictory conditions / ambiguity of specifications would not be entertained after opening of techno-commercial offers. Further no price impact would be allowed for the requirement which is already part of the specifications of the tender enquiry, after opening of techno-commercial offers.

8. Evaluation will be done as follows:

All the items covered in the enquiry will be procured from single source. Evaluation shall be done on total landed cost to BHEL up to Project site, considering all items/material codes and quantity of the project taken together.

9. IMPORTANT NOTE

Deviations (if any) are to be listed separately in deviation sheet. Please note that in case, deviation sheet is not received along with the offer, it will be considered that all terms and conditions mentioned in above documents are acceptable to the bidder and your offer will be processed accordingly.

10. LIST OF ENCLOSURES

Commercial Documents:

- TENDER DETAILS AND INSTRUCTION TO BIDDERS (ANNEXURE-1)**
- Special Terms & Conditions of the tender enquiry (Annexure-1A) for Indigenous vendor.
- GISTC; Version April -2019, Rev:04 (for Indigenous Bidders)
- MSME format
- Make in India Certificate.
- List of BHEL consortium Bank

Technical Documents:

- Pre-Qualification Requirements (Annexure-A)
- Technical drawings
- Annexure-B
- Annexure-C
- Standard quality plan no. QA/BI/QP/135

12. PUBLIC PROCUREMENT (PREFERENCE TO MAKE IN INDIA)

- For the procurement the local content to categories a supplier as a class1 local supplier/class II local supplier/non local supplier & purchase preference to class I local supplier, is a defined in public procurement (preference to make in India), order 2017 dated 4.6.20 issued by DPIIT. In case of subsequent order issued by the nodal ministry, changing the definition of local content for the item of the NIT, the same shall be applicable even if issued after issue of this NIT, but before open of Part-ii bids against this NIT. Please confirm.



PPX-BOI DEPARTMENT
BHARAT HEAVY ELECTRICALS LIMITED
HEEP: HARDWAR-249 403 (Uttarakhand)
FAX: +91 1334 226084/226462
TEL: +91 1334 28 1753 / 5834/1690

ENQUIRY NO. B/4011//2020/2194V1
ITEM: LEAK OFF STEAM VALVE
PROJECT: KHURJA PROJECT

NIT: TENDER DETAILS AND INSTRUCTION TO BIDDERS (ANNEXURE-1)

b) **Bidders to take note that this is not a Global Tender.** As per extant Make In India Order no. P-45021/2/2017-PP (BE-II) Dt: 04.06.2020, following may please be considered:

- 'Class-I local supplier' means a supplier or service provider, whose goods, services or works offered for procurement, has local content equal to or more than 50%, as defined under this under.
- 'Class-II local supplier' means a supplier or service provider, whose goods, services or works offered for procurement, has local content more than 20% but less than 50%, as defined under this under.
- Non-Local supplier' means a supplier or service provider, whose goods, services or works offered for procurement, has local content less than or equal to 20%, as defined under this under.

Eligibility of 'Class-I local supplier' / 'Class-II local supplier' / 'Non-Local suppliers' for this procurement shall be in accordance/ compliance, as defined under this order.

For and on behalf of BHEL, Hardwar

(Ashish Gupta)
SDGM / PPX-BOI

SPECIAL TERMS & CONDITIONS OF THE TENDER ENQUIRY
Enquiry No. B/4011/2020/2194V1 for Leak Steam Control Valve of Khurja Project.
ANNEXURE-1A [Indian Supplier]

Sl. No	Terms	Description	Your confirm ation																											
1.	Submission of Offer	The offer/bid shall be signed and stamped on each page by authorized representative of the bidder.																												
2.	Special Term	Techno-commercial terms as confirmed above in Annexure-1A shall supersede the similar terms & conditions found contradictory written elsewhere in the offer. Kindly confirm the same.																												
3.	Documents Checklist:	Kindly confirm that the following documents have been submitted along with your offer: 1. Requisite EMD 2. Signed & Stamped Copy of Material Details and ITB- Annex-1 3. Pre-Qualification Requirements (as defined in Annexure-A). 4. Complete Technical offer with relevant drawings/ documents /QP etc. (as per special instructions mentioned in Annexure-1A). 5. Experience Details. 6. Any other document as specified in “Instructions to Bidders and/or Special conditions of Enquiry”. Please note that all details required in supplier registration form to be filled and submitted on online supplier registration portal on www.bhel.com along with complete documents.																												
4.	Evaluation criteria	All the items covered in the enquiry will be procured from single source. Evaluation shall be done on total landed cost to BHEL up to Project sites, considering all items/material codes and quantity of project taken together.																												
5.	Special Instructions along with Details of requirement	<table><tr><td colspan="6">The requirement covered in the enquiry is as per details given below:</td></tr><tr><td>Sl. No.</td><td>Material Code</td><td>Item Description</td><td>Project</td><td>Qty.</td><td>Scheduled Delivery</td></tr><tr><td rowspan="2">1.</td><td rowspan="2">W90313240400</td><td rowspan="2">Leak off Steam Control Valve</td><td>Khurja Unit-1</td><td>1 No.</td><td>30/07/2022</td></tr><tr><td>Khurja Unit-2</td><td>1 No.</td><td>30/01/2023</td></tr><tr><td>2.</td><td>W99313240530</td><td>Spares: Leak off Steam Valve</td><td>Khurja Unit-1</td><td>1 Set</td><td>31/12/2022</td></tr></table>	The requirement covered in the enquiry is as per details given below:						Sl. No.	Material Code	Item Description	Project	Qty.	Scheduled Delivery	1.	W90313240400	Leak off Steam Control Valve	Khurja Unit-1	1 No.	30/07/2022	Khurja Unit-2	1 No.	30/01/2023	2.	W99313240530	Spares: Leak off Steam Valve	Khurja Unit-1	1 Set	31/12/2022	
The requirement covered in the enquiry is as per details given below:																														
Sl. No.	Material Code	Item Description	Project	Qty.	Scheduled Delivery																									
1.	W90313240400	Leak off Steam Control Valve	Khurja Unit-1	1 No.	30/07/2022																									
			Khurja Unit-2	1 No.	30/01/2023																									
2.	W99313240530	Spares: Leak off Steam Valve	Khurja Unit-1	1 Set	31/12/2022																									
6.	Special Instruction of Technical requirement	1. Please ensure to submit price offer against each item mentioned in the BHEL drawing No. 31324000001 for our future reference and ordering (if required). Please also confirm that your prices of these items shall be valid till entire guarantee period.																												
		2. Please ensure to furnish duly filled check list for Leak steam valve (As per annexure-B) to confirm BHEL’s specifications requirements.																												
		3. Please ensure to furnish duly filled ANNEXURE-C along with your offer and submit all the documents accordingly.																												
		4. Vendor has to submit Packing list of items for BHEL review after placement of Purchase Order and before dispatch. Please confirm.																												

SPECIAL TERMS & CONDITIONS OF THE TENDER ENQUIRY
Enquiry No. B/4011/2020/2194V1 for Leak Steam Control Valve of Khurja Project.
ANNEXURE-1A [Indian Supplier]

		5. Item no. 2 of enquiry is for mandatory spares. Please confirm that mandatory spares shall be packed in a separate box painted green with "Mandatory Spares for Leak off Steam Valve" clearly labeled on it.	
7.	Engineering Document/ Document approval	Drawings/Data sheets/Documents/Type Test/ Quality Plan etc. as called for in the specifications shall be submitted for approval to BHEL for BHEL/customer approval within 30 days of purchase order. Any delay in delivery on account of late submission of drawings shall be to vendors account. BHEL will arrange the approval of the drawings/data sheets/ documents within 30 days of their receipt provided those are complete in all respect. Delays in approval shall be dealt on merit basis.	
8.	O&M Manuals	Kindly confirm that in the event of ordering, 25 Sets (Paper based) and 3 Set (in CD ROM) of O & M manual shall be furnished containing all drawings and datasheet, catalogues of all instruments and instructions for storage, erection & commissioning, operation and maintenance after approval. Please submit same to BHEL Haridwar after despatch of material. Kindly confirm that in the event of ordering, 02 Sets of O&M Manuals would be kept inside the dispatch box of Leak Steam Control Valve & the same shall also be mentioned in your Shipping/Packing List.	
9.	Quality Requirements	Please confirm for compliance of enclosed standard quality plan no. "QA/BI/QP/135". Inspection shall be done by BHEL nominated inspection agency BVIL as per BHEL standard quality plan no. "QA/BI/QP/135". Please confirm. The Charges for Pre-Inspection would be borne by BHEL. However at least 15 days' notice is to be provided for arranging Pre-Inspection.	
10.	Confirmation to General Instructions and Standard Terms & Conditions (GISTC), Revision -4	Please submit signed and stamped copy of General Instructions and Standard Terms & Conditions (enclosed) as your acceptance to these terms and conditions. Deviation to "General Instructions and Standard Terms & Conditions, Revision 4", if any, shall be submitted along with offer in separate documents. Please note that in case no- deviation sheet of "General Instructions and Standard Terms & Conditions, Revision 4", is received along with offer, it will be presumed that all terms and conditions mentioned in "General Instructions and Standard Terms & Conditions, Revision 4", shall be acceptable to you and your offer will be processed accordingly.	
11.	Validity	Confirm that validity of the offer shall be 180 days from the due date of opening of Techno-Comm. Offers. BHEL reserves the right to reject any or all quotations, quoting validity less than 180 days.	
12.	Special Instruction	Please note that as per BHEL's Policy, we cannot allow Price impact for the requirement / scope of supply, which is a part of specifications of our tender enquiry. Hence please read all specification / documents thoroughly and submit your offer as per specifications of tender enquiry. In case of any confusion / un-clarity on any of the clause / requirement of specification, please clarify the same from BHEL before submission of offer. No deviation & request regarding un-clarity / contradictory conditions / ambiguity of specifications would be entertained after opening of techno-commercial offers. Further no price impact would be allowed for the	

SPECIAL TERMS & CONDITIONS OF THE TENDER ENQUIRY
Enquiry No. B/4011/2020/2194V1 for Leak Steam Control Valve of Khurja Project.
ANNEXURE-1A [Indian Supplier]

		requirement which is already part of the specifications of the tender enquiry, after opening of techno-commercial offers. Please note and confirm.	
13.	Statutory Variation and Taxes & Duties	Details of applicable Taxes & Duties are to be mentioned as per clause 11 of General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC), Revision 4. In this regard, following information is to be specifically mentioned in the offer: - Name of the vendor - GST Registration Number. - Address of Principal place of Business - Type of Business - HSN Code, its description and rate of applicable GST for the offered material. - Whether registered under Composite scheme of GST (Y/N) - During despatch of item Vendor will quote vendor's & BHEL's GST no. on GST portal. - Confirmation regarding online entry of vendor's sale at the time of despatch quoting BHEL's GST no. on GST portal. In case on line entry does not appear to BHEL at the time of vendor's payment, GST will not be paid and shall be deducted from bill.	
14.	Basis of quotation	Confirm that Prices have been quoted on <u>Ex-Works with Freight pre-paid</u> basis up to Khurja project site. Please Mention; -Ex-works price and freight price Separately. The goods must be dispatched through any BHEL approved transporters which are posted at our website https://hwr.bhel.com . Please note that if you dispatch the material by any BHEL un-approved transporter then you will be required to furnish the MRC (Material Receipt Certificate) / Receipted GR from "BHEL Site"/ "BHEL Authorized Agency" (confirming receipt of item at delivery address as mentioned above). No demurrage charges would be borne by BHEL. Please mention separately Packing and Forwarding charges in terms of % of basic prices (if any) and mention specifically that it is inclusive or not inclusive in the quoted price. In case the offer is silent regarding these charges, the same would be considered to be inclusive in the offer. Kindly confirm. Please mention separately Freight charges in terms of % of basic prices (if any) and mention specifically that it is inclusive or not inclusive in the quoted price. In case the offer is silent regarding these charges, the same would be considered to be inclusive in the offer. Kindly confirm. Kindly confirm that the prices have been quoted on firm basis. The offer of the vendors not quoting firm prices is likely to be rejected by BHEL. Transit insurance would be arranged by BHEL. Please send your offer keeping this in view. Applicable GST should be indicated separately and clearly in the quotation, else it will be concluded that the offer is inclusive of these Taxes & Duties. The price comparison will be on the basis of total cost involved for delivery up to Project Sites. Offers shall be loaded (if required) for applicable duties/taxes and other charges involved for delivery up to Site as per BHEL practice/ statutory rates. The evaluation currency for this Tender shall be "INR".	
15.	Delivery :	You are requested to offer your best possible delivery in number of weeks/ months from the date of Purchase Order/documents approval.	

SPECIAL TERMS & CONDITIONS OF THE TENDER ENQUIRY
Enquiry No. B/4011/2020/2194V1 for Leak Steam Control Valve of Khurja Project.
ANNEXURE-1A [Indian Supplier]

		Project name	Possible delivery in number of weeks/months from the date of Purchase Order/documents approval/BOM approval.		
		Khurja Unit-1 & 2			
		Material shall be required as per delivery schedule of BHEL. However, you are requested to offer your best possible delivery in number of weeks/months from the date of Purchase Order/documents approval.			
16.	Penalty for Late Delivery	Penalty for Late Delivery would be applicable @0.5% of the “lot wise order value” per week of delay or part thereof subject to a maximum of @10% of the “lot wise order value”. The date of GR would be treated as the date of delivery for penalty purposes. Date of GR shall be treated as delivery date for all purposes.			
		Loading for deviation in penalty for LD clause: - Please note that, in case of deviation in penalty clause, BHEL will evaluate your offer after loading on account of deviation in penalty as per BHEL rules/policy. Loading will be done to the extent by which penalty clause is not agreed.			
17.	Payment Terms	Payment terms: 100% payment shall be made after receipt of material at Khurja Project Site. Receipted LR certificate from BHEL will be part of negotiation document for claiming payment.			
		Mode of Payment: The payment may be claimed by submitting receipted GR along with bill thru bank or directly to BHEL by submitting receipted GR & billing documents. In case of payment through bank, all bank charges shall be on either side i.e. your bank's charges shall be to your account and our bank's charges shall be to our account. In case documents are presented directly to our nominated Banks, bank charges shall be to your account.			
		Loading for Deviation in Payment terms: In case of deviation in above mentioned payment term, your offer would be evaluated with loading as per BHEL rules/policy.			
		Inspection shall be done by BHEL nominated inspection agency BVIL as per BHEL standard quality plan no. QA/BI/QP/135 REV.01. Please confirm.			
		The Charges for Pre-Inspection would be borne by BHEL. However at least 15 days' notice is to be provided for arranging Pre-Inspection.			
18.	MDCC clause	Material shall be dispatched only after issue of material dispatch clearance certificate (MDCC) by BHEL. All test certificates and relevant documents are to be sent to BHEL before dispatch of material for issue of MDCC, which will be issued after review of test certificates etc. MDCC will be issued within 07 days of receipt of these documents once found complete in all respects. In case of any delay on account of BHEL in issuing MDCC, delivery shall be extended by no. of days in excess of 7 days taken by BHEL in issuing MDCC and delays shall be dealt on merit basis. Material is to despatched within 07 days of receipt of MDCC from BHEL without waiting for PO amendment.			
19.	Guarantee	Kindly confirm that Guarantee shall be provided for a period of “ 24 months from the date of dispatch ”. In case of any failure or trouble reported from site, the supplier should depute their representative immediately to attend the problem and replace the defective component/part if required, without any additional cost to BHEL.			
		Please note that vendors quoting guarantee less than 24 months from the date of dispatch, may result in non-consideration of bids.			

SPECIAL TERMS & CONDITIONS OF THE TENDER ENQUIRY
Enquiry No. B/4011/2020/2194V1 for Leak Steam Control Valve of Khurja Project.
ANNEXURE-1A [Indian Supplier]

		In case of deviation in Guarantee Period, offer shall be evaluated with loading @4% per-annum (on pro-rata basis) of quoted material value, for the deviated guarantee period.	
		Within guarantee period Supplier shall be responsible for free replacement of defective equipment / material at our site	
20.	Arbitration, Risk Purchase & FORCE AJEURE	Kindly confirm Arbitration, Risk Purchase & Force Majeure shall be applicable as per GISTC (copy enclosed).	
21.	Deviation: (if any)	Kindly confirm that there is no deviation with respect to BHEL Specifications. However, if there is any deviation with respect to the tender documents then the same should be brought out specifically in separate annexure marked "Deviations" (Technical/Commercial). The additional price, if any, for withdrawal of these deviations must be provided.	
22.	Deficiencies and Defective Supplies	Should, any deficiencies be established / suppliers be proved (found) defective, the same shall have to be made good / replaced by the suppliers under "Free of Charge" invoice, at suppliers cost, risk and responsibility.	
23.	General terms	Pl. Confirm that the prices will remain firm during the entire validity and execution of the Project.	
		Confirm that there is no deviation with respect to BHEL Specifications. However, deviations, if any, are to be listed as a separate attachment. The additional price, if any, for withdrawal of these deviations must be provided. The offers that do not meet the substantial requirements of our enquiry are liable to be ignored. The bidders shall be deemed to comply with all the requirements of bidding documents except for listed deviations without any extra cost irrespective of any mention to the contrary anywhere else in the bid.	
		Please note no revision in the prices or submission of supplementary price bid will be allowed during the validity of the offer. However if there is any change by BHEL w.r.t. original specifications/ requirement/ scope/terms and conditions, the bidders may be asked by BHEL to submit only the price impact bid for such changes only.	
		Confirm that Approx. Weight and Volume of the packages has been mentioned in the Techno-Commercial Offer (Part – 1).	
		All envelopes to be marked with whether "Priced Bid" (Part – 2) or "Un-Priced Bid Cum Techno-Commercial Bid" (Part – 1). The replica of Priced Bid (without prices) would be necessarily submitted along with Part-1 of the offer.	
		BHEL also reserves the right to Increase or decrease the tendered quantities. Vendor should be prepared to accept order for reduced Quantity without any extra charges. Vendor should also be prepared for giving discount in case of Increase in Quantity	
		Please note that in unlikely event of delay in dispatches (for reasons attributed to either side) your invoices would be processed after suitable deduction as per PO clause. Any issue/ dispute regarding deduction of penalty for LD can be settled later on. This would help in earlier processing of invoice.	
		Kindly confirm that the prices for list of Recommended Spares and commissioning spares along with price breakup of individual spares have been quoted separately in your offer and the prices for these spares would remain valid for entire guarantee period.	

SPECIAL TERMS & CONDITIONS OF THE TENDER ENQUIRY
Enquiry No. B/4011/2020/2194V1 for Leak Steam Control Valve of Khurja Project.
ANNEXURE-1A [Indian Supplier]

		Kindly confirm that in the event of ordering, 02 Sets of O&M Manuals would be kept inside the dispatch box of Leak Steam Control Valve & the same shall also be mentioned in your Shipping/Packing List.	
24.	Order Acceptance:	In case of ordering, Ink signed order acceptance shall be furnished within 15 days of receipt of purchase order. In case, order acceptance is not received within 15 days of order placement, PO will be assumed to be deemed accepted by vendor.	
25.	PUBLIC PROCUREMENT (PREFERENCE TO MAKE IN INDIA)	For the procurement the local content to categorize a supplier as a class1 local supplier/class II local supplier/non local supplier & purchase preference to class I local supplier, is a defined in public procurement (preference to make in India), order 2017 dated 4.6.20 issued by DPIIT. In case of subsequent order issued by the nodal ministry, changing the definition of local content for the item of the NIT, the same shall be applicable even if issued after issue of this NIT, but before open of Part-ii bids against this NIT. Please confirm. Bidders to take note that this is not a Global Tender. As per extant Make In India Order no. P-45021/2/2017-PP (BE-II) Dt: 04.06.2020, following may please be considered: • ‘Class-I local supplier’ means a supplier or service provider, whose goods, services or works offered for procurement, has local content equal to or more than 50%, as defined under this under. • ‘Class-II local supplier’ means a supplier or service provider, whose goods, services or works offered for procurement, has local content more than 20% but less than 50%, as defined under this under. • Non-Local supplier’ means a supplier or service provider, whose goods, services or works offered for procurement, has local content less than or equal to 20%, as defined under this under. Eligibility of ‘Class-I local supplier’ / ‘Class-II local supplier’ / ‘Non-Local suppliers’ for this procurement shall be in accordance/ compliance, as defined under this order. Participant bidders to submit signed & stamped copy of Make in India deceleration certificate along with offer (refer enclosed).	
26.	Right of Acceptance:	BHEL reserves the right to reject any or all the quotations without assigning any reasons thereof. BHEL also reserves the right to Increase or decrease the tendered quantities. Vendors should be prepared to accept order for reduced Quantity without any extra charges. Vendor should also be prepared for giving discount in case of Increase in Quantity.	
27.	Reverse Auction	Please confirm your participation in Reverse Auction as per guidelines as available on BHEL portol for this tender. “BHEL shall be resorting to Reverse Auction (RA) (Guidelines as available on www.bhel.com) for this tender.” RA shall be conducted among all the techno-commercially qualified bidders. Price bids of all techno-commercially qualified bidders shall be opened and same shall be considered as initial bids of bidders in RA. In case any bidder does not participate in online Reverse Auction, their sealed envelope price bid along with applicable loading, if any, shall be considered for ranking. The detailed guidelines and process of RA are available on our website linked as - http://www.bhel.com/index.php/vender	

SPECIAL TERMS & CONDITIONS OF THE TENDER ENQUIRY
Enquiry No. B/4011/2020/2194V1 for Leak Steam Control Valve of Khurja Project.
ANNEXURE-1A [Indian Supplier]

28.	BHEL Registration	Online Registration Portal is operational in BHEL. Bidders not registered at BHEL, Hardwar for this item; have to apply through Online Registration portal, https://supplier.bhel.in/ . All credentials and/or documents duly signed and stamped related to registration has to be uploaded on the website and the application submitted for registration. Application registration No (for applying online form) should be mentioned in the techno commercial offer.	
29.	Details of Contact Person	Details of Contact person Name, Designation, Department complete postal, E-mail address & Fax no, phone, Mobile no. to be mentioned.	

Kindly ensure to submit below listed Enclosures along with 'Techno-Commercial Bid':

1. **Copy / Replica of Price Bid (without prices).**
2. **Signed & Stamped copy (each page) of duly filled 'Annexure-1A' i.e. Special terms & Conditions of Tender Enquiry.**
3. **Signed & Stamped copy (each page) of GISTC (Version April 2019, Rev. 04).**
4. **Signed & Stamped copy (each page) of Standard Quality Plan from bidder.**
5. **Any other document required to be submitted as per your offer.**
6. **Catalog / Leaflet of the Equipment / Instrument.**

Note:

Bidders can submit their offer through email at tendercell.heep@bhel.in on or before due date and time as per tender enquiry. Bidders submitting their bids through e-mail shall have to mention following in subject line.

1. Tender Enquiry Reference No. _____
2. Bid Opening Date (Part 1, Techno- commercial) _____

Vendor to submit their bids(Part-1, Part-2 both) as attachment (pdf format) with password protection and share the password through mail (tendercell.heep@bhel.in) after 1:45 PM (IST) on the day of bid opening, however if no password is received up to 04:00 PM (IST) bids will not be opened and will be ignored. Submission of bids through email shall be considered as consent to open the bid without physically witnessing the event.

(Signature of the Vendor with Seal)
--



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

Table of Contents

1. GENERAL	1
2. ORIGIN OF QUOTATION	1
3. SUBMISSION OF TENDER	1
4. TENDER OPENING	2
5. SPECIFICATION, DRAWINGS & STANDARD	2
6. PRICE SCHEDULE	3
7. REVERSE AUCTION	3
8. DELIVERY TERMS.....	4
9. PENALTY FOR LATE DELIVERY	4
10. PAYMENT TERMS	4
11. TAXES & DUTIES	5
12. BANK GUARANTEE	6
13. GUARANTEE / WARRANTY AND CORRESPONDING REPAIRS / REPLACEMENT OF GOODS	6
14. QUALITY REQUIREMENT	6
15. VALIDITY.....	6
16. RIGHT OF ACCEPTANCE.....	6
17. TRANSIT INSURANCE.....	7
18. RISK PURCHASE	7
19. FORCE MAJEURE CLAUSE.....	7
20. NON-DISCLOSURE AGREEMENT.....	8
21. SETTLEMENT OF DISPUTES / ARBITRATION	8
22. WHARFAGE / DEMURRAGE RESPONSIBILITY.....	8
23. CONDITIONS FOR AVAILING MICRO & SMALL ENTERPRISES (MSE'S) BENEFITS.....	8
24. INFORMATION TO THE BIDDERS.....	10
25. MAKE IN INDIA (GOVT-NOTIFICATION).....	10
26. NOTE	11

1. GENERAL.

These general terms & conditions shall apply to all the Tender Enquiries, notice inviting tenders, request for quotations concerning the supply of goods and / or rendering of services to Bharat Heavy Electricals Ltd., HEEP, Haridwar (hereinafter referred to as BHEL or the Purchaser). In case of placement of order these conditions will become part of Purchase Order (P.O) until unless the deviations are specifically agreed by BHEL.

2. ORIGIN OF QUOTATION.

- The quotation should preferably be from the principal bidder. However tender specific authorized registered dealer/agent can also submit the bid on their behalf, failing which the quotation is liable to be ignored. BHEL prefers to deal directly with the principal manufacturers.
- An agent cannot quote on behalf of more than one principal in the same Tender Enquiry.

3. SUBMISSION OF TENDER.

- Bid / Quotation must be enclosed in sealed cover on which tender enquiry number and the due date MUST BE written and be invariably sent under REGISTERED POST / SPEED POST / COURIER / Dropped in the Tender Box: addressed as follows:
-

Quotation against Enquiry No. _____

Dated: _____

Due on: _____

To,

**THE HEAD OF MATERIALS MANAGEMENT,
Heavy Electrical Equipment Plant,
Bharat Heavy Electricals Limited,
HARIDWAR-249403 (Uttarakhand), INDIA.**

- TENDER ROOM is located at: Room No. - 415, 4th Floor, Main Admin. Building, BHEL-HEEP, Haridwar.



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

- c) In case of Three / Two Part Bid, technical bid containing technical offer, duly signed and un-priced copy of the Price Bid should be kept in one envelope. Price Bid containing only the price should be kept in a separate envelope. All envelopes indicating Part-1 or Part-2 or Part-3 as the case may be to be put in a bigger envelope. Please note that un-priced bid should be the exact replica of price bid but without prices.
- d) The bid / quotation must be posted before due date, keeping allowance for postal transit time. Quotations sent by any mode but not received in time will be ignored. Tender received through authorized E-mail is also acceptable. However, in time submission of tender in tender box shall be the responsibility of the bidder, sent through any mode. Documents submitted with the offer / bid shall be signed and stamped in each page by authorized representative of the bidder.
- e) Any additional documents submitted by supplier / bidder, during processing of registration application / tender or after placement of order shall not be accepted unless it is submitted with forwarding letter and duly signed and stamped.
- f) The bids of the bidders who are on the banned list and also the bids of the bidders, who engage the services of the banned firms, shall be rejected. The cutting / overwriting in the bid / offer must be duly attested by the signatories to the bid. The list of firms banned by BHEL is available on BHEL web site www.bhel.com.
- g) Being PMD vendor, if you are not quoting against this tender enquiry, please send your regret letter positively for our reference with valid reasons for not participating in the tender enquiry. Repeated lack of response on the part of bidder may lead to deletion such PMD vendor from BHEL's approved vendor list.
- h) The bidders will submit Integrity Pact, duly signed by its authorized signatory, along with their bids wherever estimated tender value is Rs. 5 Crore or more.
- i) In case of open tender, the unregistered bidder shall submit inter alia duly filled-in Supplier Registration Form (SRF) along with the bid. Bidders can download the SRF from www.bhel.com
- j) BHEL reserves the right to award tendered quantities among more than one bidder (after acceptance of L1 price by the other bidders). BHEL can also consider awarding of part of the tendered quantity to other than L-1 bidder at **L1 counter offered rates**, if the quantity offered by the L-1 bidder is less than the quantity tendered for.
- k) In case of e-Tendering (Online bidding through e-portal), offline bid submitted in hard copy or in any other form by the vendor / supplier will not be accepted and will be rejected outrightly. Only e-portal bid will be accepted.

4. TENDER OPENING.

Tender opening is scheduled to start in the Tender Room at 2:00 PM, on the due date. Therefore, bid / quotations must reach this office / tender Box latest by 1:45 PM on due date. Only participating bidders are allowed to attend tender opening. **TENDERS RECEIVED AFTER THE SPECIFIED TIME OF THEIR 'SUBMISSION' WILL BE TREATED AS LATE TENDERS AND SHALL NOT BE CONSIDERED UNDER ANY CIRCUMSTANCES.** The bidders or their authorized representatives may be allowed to attend tender opening if duly authorized by their principals, through a tender specific letter on that particular day. General authorization letter is not acceptable.

Note: - Foreign bidders willing to attend the bid opening has to provide the requisite documents to the concerned Purchase executives for arranging gate pass for them.

5. SPECIFICATION, DRAWINGS & STANDARD.

- a) Bidders must give their detailed specification in the quotation along with relevant technical literature / catalogue etc. against the tender enquiry.



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

- b) The Bid should be accompanied with relevant copies of catalogues, drawings or specification as per tender enquiry. If these documents are not furnished, the offer is liable to be rejected.
- c) Wherever national / international (N/IN) standards are referred, the latest N/IN standards are to be followed. Mention year & date of standard revision that shall be followed for the supply.
- d) All Drawings and Standards are proprietary of BHEL. It must not be used in anyway detrimental to the interest of the company.

6. PRICE SCHEDULE.

- a) Kindly quote your prices in figures and words both. In case of any discrepancy in value, the prices quoted in words shall be considered for evaluation and establishing L1 status.
- b) Prices quoted should not be more than the prices quoted to any other BHEL units / offices / divisions. Vendor to submit copy of latest Purchase Order placed by any unit of BHEL for similar items in the technical bid. In case no order has been placed on such items, specific confirmation that no order has been placed on such items should be provided.
- c) Prices should be quoted on F.O.R. Destination basis. Transit insurance shall be arranged by BHEL and not to be included in the prices. The offers quoted on other than F.O.R destination basis may result in non-consideration of such bids.
- d) In case BHEL accepts the EX-Works prices, such offers will be loaded by 1.5% of EX-Works value towards freight or with actual freight charges as per BHEL freight rate contract whichever is higher.
- e) In case of Indigenous items covered by DGS & D Rate Contract, the bidders should submit latest valid copy of the rate contract along with bid / quotation
- f) Applicable **IGST / CGST / SGST** and any other statutory levy should be indicated separately and clearly in the bid / quotation.

- g) Bidders can dispatch goods through any Indian Bank Association approved transporters having their branch at HARIDWAR / destination. If material is dispatched through other than Indian Bank Association approved transporter, material to be delivered on door delivery BHEL Stores basis.
- h) In case of dispatch of material through any other unapproved transporter, payment shall be made only after receipt of material and any additional charges payable to the transporter shall be to the bidder's account.
- i) Any demurrage / godown rent payable to the transporter / or to godown's owner due to any delay attributed by the supplier shall be recovered from supplier's account.

NB: Financial evaluation of L1, L2Status will be on the basis of Landed Cost to BHEL.

7. REVERSE AUCTION.

- a) BHEL reserves the right to go for Reverse Auction (RA) instead of opening the sealed envelope price bid, submitted by the bidder. This will be decided after Techno-Commercial Evaluation. All bidders to give their acceptance for participation in RA. Non-acceptance to participate in RA may result in non-consideration of their bids, in case BHEL decides for RA. Detailed guidelines available at our site www.bhel.com
- b) In case BHEL decides to go for Reverse Auction, only those bidders who have given their acceptance to participate in RA will be allowed to participate in the Reverse Auction. Those bidders who have given their acceptance to participate in Reverse Auction will have to necessarily submit 'online sealed bid' in the Reverse Auction. Non-Submission of 'online sealed bid' by the bidder will be considered as tampering of the tender process and will invite action by BHEL as per extant guidelines in vogue.

Quotations / Bids not in accordance with General Instructions and Standard Terms & Conditions are likely to be ignored.



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

8. DELIVERY TERMS.

- a) Goods shall be delivered on 'FOR Destination' basis to the named destination unless otherwise called for in the tender enquiry.
- b) Loading on account of 3rd party inspection charges in case of Indian bidders shall be 0.20%.

9. PENALTY FOR LATE DELIVERY.

a) Where items of Purchase Order are independently usable.

Penalty for Late Deliveries shall be applicable @0.5% per week or part thereof on the value of respective delayed supplies subject to a maximum of 10% of the value of respective delayed supplies. Value of delayed supplies will mean the Gross Value payable to the vendor (Before LD) against such supplies excluding taxes and duties.

b) Where the total items are required for a main equipment and items are interdependent.

Penalty for Late Deliveries shall be applicable @0.5% per week or part thereof on total value of Purchase Order subject to maximum of 10% of the total value of Purchase Order. Purchase Order value for this purpose shall be the Total Gross Value payable to the vendor (Before LD) excluding taxes and duties.

- c) Bidders are requested to quote the best delivery meeting the delivery requirements. BHEL reserves the right to reject the offers not meeting BHEL's delivery requirement.
- d) Commencement of delivery period shall be reckoned from the date of PO / LOI or any other agreed milestone.
- e) Bidder shall deliver the goods in the manner and schedule agreed under the terms and conditions of Purchase order.
- f) **DELIVERY IN CASE OF REJECTION:** In case the material is rejected, then date of replacement will be considered as the actual date of delivery.

g) **DELIVERY AGAINST BANK DOCUMENTS:** In case payment terms quoted by bidder are documents through bank, and the delivery terms being "FOR Haridwar / FOR Transporter Go-down" then date of delivery will be date of intimation by transporter / bidder of delivery of material at Haridwar for the penalty purpose.

g) Where the payments are through bank, the documents may be presented for negotiation to BHEL authorized / nominated bank.

10. PAYMENT TERMS.

- a) BHEL's standard payment term is Payment after receipt and acceptance of materials / items at HEEP, BHEL-Store or at desired destination unless otherwise specified in Special Terms attached to the tender enquiry.
- b) BHEL reserves the right to accept or reject the offer of the bidder who quotes the payment term other than BHEL's standard payment term.
- c) Loading on account of deviation in payment terms shall be done as per extant rules of BHEL-Haridwar.
- d) 100% payment along with taxes, freight & insurance will be made after receipt and acceptance of material and within 75 days from the date of invoice subject to submission of non-discrepant documents within 15 days of supply as per terms and conditions of Purchase Order. In case any discrepancy found in the documents, BHEL will notify the same to vendor within 7 days of receipt. Vendor has to clear all the discrepancies in one go within 7 days thereafter else the payment of vendor may get delayed.
- e) For MSEs (covered under MSME Act) which are registered and periodically renewed with BHEL, the payment will be made within 45 days or as prescribed in the relevant act.
- f) Adherence to the above time schedule of payment is contingent upon Vendor complying with GST Rules w.r.t availment of Input Tax Credit by BHEL.
- g) In case GST credit is delayed / denied to BHEL, due to non / delayed receipt of goods and / or tax invoice or expiry of the timeline prescribed in GST Law for availing such ITC, or any other reason not attributable to BHEL, GST amount shall be

**BHARAT HEAVY ELECTRICALS LIMITED**

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)**For Indian Bidders (Version April-2019, Rev: 04)**

recoverable from Vendor along with interest levied / leviable on BHEL.

- h) The taxes and duties that are reimbursed would be the ones applicable as on the contractual Purchase order delivery date or the amount actually paid whichever is less.

i) The loading criteria for the different payment terms shall be as under;

Payment Terms	Days of Loading
After Receipt & Acceptance of material within 75 days of supply.	No Loading
Against Delivery at BHEL-Stores Haridwar.	45
Against documents through bank (CAD):	45
Letter of Credit (LC)	120
Usance LC	No Loading if usance period is > 120 Days.
	Loading of days' difference i.e. difference between 120 days and usance period if the usance period is < 75 days.
Advance	Delivery Period + 120 Days - Advance Payment Days.

11. TAXES & DUTIES.

- a) The bidder to specify in their offer (part 1 bid) the category of their registration under GST like Registered, Unregistered and composite dealer.
- b) The provisional GST registration number of Bharat Heavy Electrical Ltd, Heavy Electricals Equipment Plant, Ranipur, Haridwar is "05AAACB4146P1ZL" with state Code as "05" and State Name as "Uttarakhand".
- c) Please quote our provisional GST registration number in all invoices raised for supply of goods and services under GST regime and also ensure filing of timely return and payment of tax and compliance of other applicable provisions on supplier under GST regime.
- d) No GST will be reimbursed to unregistered or composite dealer. In the event, any GST is quoted by composite dealer,

the same shall be added to the cost of supply in evaluating the bid.

- e) Since, input credit of GST will be available to BHEL-Haridwar only after correct filing of return and payment of applicable GST by supplier, reimbursement of GST shall be made by BHEL-Haridwar on matching of vendor inputs at GST portal, ensuring availability of input credit to BHEL Haridwar. Payment of GST will be made to vendor after matching of input credit and vendor to ensure submission of their invoices along with consent to accept payment of tax after such matching in all cases where bills are submitted directly to BHEL-Haridwar or through bank or under LC or through any other mode.
- f) In the event of any disallowance of input credit or applicability of interest or any other financial liability arises on BHEL-Haridwar due to any default of supplier under GST, such implication shall be to supplier's account.
- g) In the event of any change in the status of the vendor after the submission of the bid but before the supply, GST applicable at the time of supply or in the bid, based on the registration status of the vendor, whichever is lower shall be payable.
- h) Where ever applicable If PAN (Permanent Account Number) of the recipient is not available, income tax is deductible either at the normal rate or at the rate of 20 percent, whichever is higher as per Section 206AA of Indian Income Tax Act 1961.
- i) The bidder shall clearly indicate HSN (*Harmonised System Nomenclature*) / SAC (*Service Accounting Code*), its description and applicable rate of GST for each item in his techno-commercial bid.
- j) Statutory Variation in Taxes & duties as applicable at the time of supply shall be payable. However, in the event of no change in law but bidder quoting certain tax structure in bid document which is lower than the applicable one, such amount shall be the maximum amount of tax that can be claimed by bidder.



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

k) **IMPORTED GOODS OFFERED BY INDIAN BIDDERS AGAINST DEALER INVOICE:** Wherever the material being offered is imported, the bidder must quote the prices inclusive of IGST. The rate and value of IGST as included in the price must be indicated separately. In case quantum of IGST is not mentioned by the bidder the same will not be considered for evaluation. However, bidder will have to pass on the benefit of IGST to BHEL at the time supply.

l) In case of directly dispatchable items to Customer's Site, BHEL-Haridwar will inform the GST registration number of the respective customer which must be mentioned on the vendor's invoice. Vendor to ensure availability of such information from BHEL-Haridwar before dispatch of any material. However, while filing GSTN-1, BHEL Haridwar GSTN number to be quoted.

Note: - Vendors must ensure compliance of all the applicable rules and procedure as envisaged in the GST Regime. Any loss to BHEL-Haridwar due to fault / non-compliance by the vendor will be to the vendor's account.

12. BANK GUARANTEE.

In case the bank guarantees are required to be deposited towards security deposit/performance guarantee or for any other purpose as per the terms of this tender enquiry, such bank guarantees of the requisite value in the denominated currency of the purchase order should be from one of the Indian branch of BHEL consortium banks and the bank guarantee should be in the proforma as prescribed by BHEL. The proforma of bank guarantee and the list of consortium banks are displayed at BHEL website www.bhelhwr.co.in. However, in case the bank guarantee is not from BHEL consortium banks, then the bidder has to get the bank guarantee confirmed from one of the Indian branch of BHEL consortium banks and the bank charges for such confirmation will be borne by the bidder.

13. GUARANTEE / WARRANTY AND CORRESPONDING REPAIRS / REPLACEMENT OF GOODS.

Goods shall comply with the specifications for material, workmanship and performance. Unless otherwise specified, the warranty shall be for a period of 18 months from the date of receipt. If the delivery is found non-compliant during the warranty period, leading to rejection, the Seller shall arrange free replacement / repair of goods, within one month from the date of intimation or any mutually agreed period. The rejected goods shall be taken away by the Seller at his cost and replaced on Delivered Duty Paid (DDP) (FOR - BHEL Stores / designated destination basis) within such period. In the event of the Seller's failure to comply, Purchaser may take action as appropriate, including Repair / Replenish rejected goods & disposal of rejections, at the risk & cost of the Seller. In case the defects attributable to Seller are detected during processing of the goods at BHEL or at our subcontractor's works, the Seller shall be responsible for free replacement / repair of the goods as required by BHEL.

b) **RETURN OF REJECTED MATERIAL FOR REPLACEMENT:** The bidder shall have to pay 5% incidental charges while taking back supplied material if it is found rejected on receipt. The rejected material shall be sent back only after receipt of replacement / submission of BG / refund of amount paid.

14. QUALITY REQUIREMENT.

Your bid / quotation should have specific confirmation regarding meeting all our quality requirements such as. (i) Test Certificate (TC), (ii) Guarantee Certificate (GC) / Warranty Certificate (WC), (iii) Quality Plan (QP) (if applicable); and (iv) Pre-Dispatch Inspection at your works (if applicable).

15. VALIDITY.

The quotation should be valid for a minimum period of 90 days effective from the date of opening of tender, unless otherwise specified in the tender enquiry.

16. RIGHT OF ACCEPTANCE.

a) **BHARAT HEAVY ELECTRICALS LIMITED HARIDWAR** reserves the right to reject any or all the bids / quotations without assigning any reason thereof. BHEL also reserves the right to increase or decrease the tendered quantities. Bidders should be prepared to accept order for reduced quantity without any extra charges.



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

b) Any discount / revised offer / bids submitted by a bidder on its own shall be considered, provided it is received on or before the due date and time of offer / bid submission (Part-1). Conditional discounts shall not be considered for evaluation of tenders.

c) Unsolicited discounts / revised offers / bids given after Part-1 bid opening shall not be accepted. No change in price will be permitted within the validity period asked for in the tender enquiry.

d) In case of changes in scope and / or technical specification and / or commercial terms & conditions having price implication, techno-commercially acceptable bidders shall be asked by BHEL to submit the impact of such changes on their price bids. In case a bidder opts to submit revised price bid instead of impact called for then the latest price bid shall prevail. However, in both situations, original price bid will be necessarily opened.

e) The bidder whose bid is technically not accepted will be informed & EMD wherever submitted shall be returned after finalization of contract. EMD shall be forfeited in the event of bidder opting out after tender opening.

f) BHEL reserves the right to short close the existing Purchase Order / Rate Contract / Work Order or any extension thereof at any stage.

17. TRANSIT INSURANCE.

a) Transit Insurance will be covered by BHEL under its open Insurance Policy. Seller shall inform dispatch particulars (Purchase Order, RR /GR, Invoice value etc.) to "Finance department (Store bill Section), BHEL Ranipur, Haridwar (Uttarakhand-India) with value of consignment to the Purchaser within 07 days of dispatch for BHEL to arrange insurance coverage in its policy. Failure on the part of seller to inform dispatch particulars will make him liable to pay for any transit damages / losses suffered by the Purchaser.

b) If Quoted Prices are inclusive of transit insurance, no weightage shall be given while evaluating the bids for Cost of Insurance, being in BHEL Scope.

18. RISK PURCHASE.

In case of abnormal delays (beyond the maximum late delivery period as per Penalty clause) in supplies / defective supplies or non-fulfillment of any other terms and conditions given in Purchase Order, BHEL may cancel the Purchase Order in full or part thereof, and may also make the purchase of such material from elsewhere / alternative source at the risk and cost of the supplier. BHEL will take all reasonable steps to get the material from alternate source at optimum cost. If bidder does not agree to the above Risk Purchase Clause, BHEL reserves the right to reject the offer. In case for compelling reasons BHEL accepts the offer without acceptance of this clause by the bidder and in the eventuality of Risk Purchase, appropriate action will be taken as per BHEL extant rules. This will be without prejudice to any other right of BHEL under the contract.

19. FORCE MAJEURE CLAUSE.

Notwithstanding any other thing contained anywhere else in the contract or PO (Purchase Order), In case the discharge of obligation under the contract by either party is impeded or made unreasonably onerous, neither party shall be considered in breach of the contract to the extent that performance of their respective obligation is prevented by an event of Force Majeure that arises after the effective date (PO date).

In the above clause, Force Majeure means an event beyond the control of the parties to the contract which prevents a party from complying with any obligation of the contract including but not limited to:

- a) Act of God (Such as but not limited to earthquake, drought, tidal waves, floods etc.).
- b) War (whether war be declared or not), Hostilities Invasion, Act of foreign enemy etc.
- c) Rebellion, revolution, insurrection, civil war etc.



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

- d) Contamination of Radio Activity from any nuclear fuel or from any other nuclear waste or any other hazardous materials.
- e) Riots, commotions, strike unless restricted to the employees of supplier.
- f) Acts of terrorism.
- g) Other unforeseeable circumstances beyond the control of the parties and which the affected party cannot avoid even by using its best efforts.
- h) Cancellation of contract by customer.
- i) Change in law / government. Regulation making the performance impossible.

The party claiming to be affected by force majeure shall notify the other party in writing immediately without delay on the intervention and on the cessation of such circumstances.

Irrespective of any extension of time, if an event of force majeure occurs and its effect continues for more than 180 days the affected party shall have right to cancel the contract.

As soon as reasonably practicable following the date of commencement of a Force Majeure Event, and within a reasonable time following the date of termination of a Force Majeure Event, either Party invoking it shall submit to the other Party reasonable proof of the nature of the Force Majeure Event and of its effect upon the performance of the Party's obligations under this Agreement.

The party shall, and shall ensure that its Subcontractors shall, at all times take all reasonable steps within their respective powers and consistent with Good Operating Practices (but without incurring unreasonable additional costs) to:

- a) Prevent Force Majeure Events affecting the performance of the party's obligations under this Agreement.
- b) mitigate the effect of any Force Majeure Event and
- c) Comply with its obligations under this Agreement.

If the war like situation has developed in a country where a seller's works is located in this P.O. or there is political instability and Indian Embassy located in that country forbids or advises for not having any business dealing with the sellers located in such zone / region/ country, then BHEL reserves the right to cancel the order.

20. NON-DISCLOSURE AGREEMENT.

All Drawing and Technical Documents relating to the product or it's manufacture submitted by one party to the other, prior or subsequent to the formation of contract, shall remain property of the submitting party. Drawing, technical documents or other technical information received by one party, shall not without the consent of the other party, be used for any other purpose than that, for which they were provided. Such technical information shall not without the consent of the submitting party, otherwise be used or copied, reproduced, transmitted or communicated to a third party. Patterns supplied by BHEL will remain BHEL's property which shall be returned by the bidder on demand to BHEL. Bidder shall in no way share or use such intellectual property of BHEL to promote his own business with others. BHEL reserves the right to claim damages from the bidder, or take appropriate penal action as deemed fit against the bidder, for any infringement of the provisions contained herein.

21. SETTLEMENT OF DISPUTES / ARBITRATION.

In all cases of dispute, the matter shall be referred for ARBITRATION by sole arbitrator to be appointed by the Unit Head of Bharat Heavy Electricals Ltd., at HARIDWAR. The award of the Arbitrator shall be final and binding on both the parties. The place of Arbitration shall be Haridwar.

JURIDICTION: The courts of Haridwar, India, shall have exclusive jurisdiction.

22. WHARFAGE / DEMURRAGE RESPONSIBILITY.

In the event of delay in receipt of documents by Manager (Stores-Shipping) BHEL-Haridwar and in case where dispatches are made through Unapproved Transporter the sole responsibility for wharfage / demurrage for such delay shall be that of supplier.

23. CONDITIONS FOR AVAILING MICRO & SMALL ENTERPRISES (MSE'S) BENEFITS.

- a) "MSE Suppliers can avail the intended benefits only if they submit along with the offer, attested copies of either EM II certificate having deemed validity (five years from the date of



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

issue of acknowledgement in EM II) or valid NSIC certificate or EM II certificate along with attested copy of a CA certificate (Format enclosed at annexure-1 where deemed validity of EM II certificate of five years has expired) applicable for the relevant financial year (latest audited). Date to be reckoned for determining the deemed validity will be the date of bid opening (Part 1 in case of two-part bid) or vendor has to give Udyog Adhar Memorandum (UAM). Non submission of such documents will lead to consideration of their bid at par with other bidders. No benefit shall be applicable for this enquiry if any deficiency in the above required documents is found or the requisite documents are not submitted before price bid opening. If the tender is to be submitted through e-procurement portal, then the above require document are to be uploaded on the portal. Documents should be notarized or attested by a Gazetted officer. **UAM need not required to be notarized or attested.**

b) Any new supplier will be eligible for registration with BHEL as MSE supplier provided at least any one of the following documents are submitted along with application for registration: -

1. Udyog Adhar Memorandum (UAM).
2. Valid National Small Industries Commission (NSIC) Certificate.
3. Entrepreneurs Memorandum part II (EM II) certificate (valid based on deemed validity of 5 years) or
4. EM II certificate along with attested copy of CA Certificate (as per prescribed format at annexure-A) applicable for the relevant financial year (latest audited), where the deemed validity of EM II is over.
5. However, credentials of all MSE suppliers will be verified before advancing the intended benefits.
6. MSE bidders claiming SC/ST status will have to submit SC/ST certificate of the Proprietor from competent authority. Attested (notarized or attested by Gazetted officer) copy to be submitted along with the offer.
7. In case techno-commercial accepted bidders include MSE source and their prices (based on landed cost – considering quoted prices) are within the price band of 15% w.r.t. L-1 bidder, then BHEL can offer **25%** of quantity of respective item (rounded off to nearest number) to MSE bidders at L-1 price and in case, more than one MSE bidder is in 15 % band and the same is accepted by more than one MSE bidders then **25%**

quantities of respective items will be considered for ordering on proportionate basis amongst MSE bidders.

8. There will be minimum of **3%** reservation for women owned MSEs within the above mentioned 25% reservation.
9. The reservation for MSEs owned by SC/ST will be **6.25%** { 25% out of target of 25% - refer para 4 of Public Procurement Policy for the Micro and Small Enterprises(MSEs)}.
10. The definition of MSEs owned by Women Entrepreneurs is clarified as under:
 - a) In case of proprietary MSE, proprietor shall be Woman.
 - b) In case of partnership MSE, the Woman partners shall be holding at least 51% of share in the unit.
 - c) In case of Private Limited companies, at least 51% share shall be held by Women promoters.
11. The definition of MSEs owned by SC/ST is clarified as under:
 - a) In case of proprietary MSE, proprietor(s) shall be SC/ST.
 - b) In case of partnership MSE, the SC/ST partners shall be holding at least 51% of shares in the unit.
 - c) In case of Private Limited companies, at least 51% share shall be held by SC/ST promoters.
12. While distributing the **25%** quantity amongst MSE bidders the decimal points in quantity shall be ignored for all the bidders except the L-1 amongst MSE bidders. Balance quantity after allocating the quantity to other MSE bidders ignoring the quantities in decimal, shall be given to L-1 (amongst MSE) bidder. However, if there are more than one MSE bidder at the same price level than preference for additional quantities due to ignoring off the decimal (as mentioned above) shall be given to the bidder offering favorable terms to BHEL and if the conditions offered are also same then preference will be given to the bidder having high SPR rating.
13. In case there are more than one MSE bidders (with different landed cost to BHEL) within 15% price band of lowest bidder and quantity to be offered is 1 no. only, then preference shall be given to the MSE bidder with lowest landed cost.
14. In case there are more than one MSE bidders (with same landed cost to BHEL) within 15% price band of lowest bidder and quantity to be offered is 1 no. only, then preference shall be given first, based on the favorable terms in the bid and in case terms are also same, the bidder with high SPR rating shall be given preference.



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

15. If L1 bidder is MSE bidder, entire quantity will be given to such MSE bidder only.
16. Note: It may however be noted that MSE guidelines as on date (Date of Technical Bid Opening Part-1) shall prevail.
17. "As per the OM No. F.No. 1(2)(1)/2016-MA dtd. 09.02.2017 issued from the Office of Development Commissioner (Micro, Small & Medium Enterprises), "Traders and agents should not be allowed to avail the benefits extended under the PP Policy."

In view of this, it is clarified that benefits of MSE (such as EMD Waiver, Tender fee exemption, Price preference, Payment preference etc.) will be given only to those MSE Vendors who are manufacturers of offered items against the NIT. No MSE benefits shall be provided to Agents / Stockists / Dealers / Traders etc. for the items offered but not manufactured by themselves."

24. INFORMATION TO THE BIDDERS.

- a) Purchase related information is available at our Business-to-Business (B2B) Portal available on our website www.bhelhwr.co.in The user ID & password can be obtained by sending a request to concerned purchase executives.
- b) Intimate your change in mail address or communication address or changes, if any, by email to AGM (SDX/MM) giving your bidder Code.
- c) Please resolve your rejections and unexecuted overdue purchase order immediately which are posted at our B2B Portal, which can be visited through our site www.bhelhwr.co.in
- d) Copy of this Tender Enquiry is being sent through the post.

25. MAKE IN INDIA (GOVT-NOTIFICATION).

- A. This tender enquiry shall be governed by notification no. P-45021/2/2017-PP (BE-II) dated 28.05.2018 of government of INDIA. Accordingly, the minimum local content, the margin of purchase preference and the procedure for preference to make in INDIA shall be adhered.
- B. Default purchase preference shall be 20% to local suppliers with default minimum local content of 50% for all items / works / services unless any of the Nodal Ministry has

prescribed, or prescribe in future lower or higher percentage of purchase preference and/or local content in respect of any items / works / services in which case the purchase preference and/ or local content for that particular items / works / services shall be as prescribed by the Nodal Ministry.

- C. Vendor to specifically confirm if they are local supplier or not as per above mentioned notification. Accordingly, the local supplier at the time of tender, bidding or solicitation shall be required to provide self-certification that the item offered meets the minimum local content and shall give details of the location(s) at which the local value addition is made.

'Local Supplier' means a supplier or service provider whose product or service offered for procurement meets the minimum local content. 'Local Content' means the mount of value added in India, which shall, unless otherwise prescribed, be the total value of the item procured (excluding net domestic indirect taxes) minus the value of imported content in the item (including all custom duties) as a proportion of the total value, in percent.

- D. In cases of Procurement for a Value in Excess of Rs. 10 Crores, the Local Supplier shall be required to provide a Certificate from the Statutory Auditor or Cost Auditor of the Company (in the case of companies) or from a practicing Cost Accountant or practicing Chartered Accountant (in respect of suppliers other than companies) giving the percentage of Local Content.
- E. Requirement of Purchase Preference: Purchase preference shall be given to local suppliers in all procurements undertaken in the manner specified hereunder-
- a. "In Procurement of Goods, Services or Works in respect of which the Nodal Ministry has communicated that there is sufficient local capacity and local competition, and where the estimated value of procurement is Rs. 50 lakhs or less, only local suppliers shall be eligible. If the estimated value of procurement of such goods or services or works is more than Rs. 50 lakhs, the provisions of below sub-paragraph b or c, as the case may be, shall be apply".
- b. "In the procurements of goods or work which are not covered by above paragraph a and which are divisible in nature, the following procedure shall be followed";
- i) Among all qualified bids, the lowest bid will be termed as L1. If L1 is from a local supplier, the contract for full quantity will be awarded to L1.



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

- ii) If L1 bid is not from a local supplier, 50% of the order quantity shall be awarded to L1. Thereafter, the lowest bidder among the local suppliers will be invited to match the L1 price for the remaining 50% quantity subject to the local suppliers quoted price falling within the margin of purchase preference, and contract for that quantity shall be awarded to such local supplier subject to matching the L1 price. In case such lowest eligible local supplier fails to match the L1 price or accepts less than the offered quantity, the next higher local supplier within the margin of purchase preferences shall be invited to match the L1 price for remaining quantity and so on, and contract shall be awarded accordingly. In case some quantity is still left uncovered on local suppliers, then such balance quantity may also be ordered on the L1 bidder.
- c. "In procurements of goods or works not covered by sub-paragraph E.a) and which are not divisible and in procurement of services where the bid is evaluated on price alone, the following procedure shall be followed":-
- i) Among all qualified bids, the lowest bid will be termed as L1. If L1 is from a local supplier, the contract will be awarded to L1
- ii) If L1 is not from a local supplier, the lowest bidder among the local suppliers will be invited to match the L1 price subject to local supplier's quoted price, falling within the margin of purchase preference, and the contract shall be awarded to such local supplier subject to matching the L1 price.
- iii) In case such lowest eligible local supplier fails to match the L1 price, the local supplier with the next higher bid within the margin of purchase preference shall be invited to match the L1 price and so on and contract shall be awarded accordingly. In case none of the local suppliers within the margin of purchase preference matches the L1 price, then the contract may be awarded to the L1 bidder.
- F. "For this procurement, Public Procurement (Preference to Make in India), Order 2017 dated 15.06.2017 & 28.05.2018 and subsequent Orders issued by the respective Nodal Ministry shall be applicable even if issued after issue of this NIT but before finalization of contract / PO / WP against this NIT.

In the event of any Nodal Ministry prescribing higher or lower percentage of purchase preference and/ or local content in respect of this procurement, same shall be applicable."

- G. Procurements where estimated value to be procured is less than Rs. 5 lakhs shall be exempted from GOI order No. P-45021/2/2017-PP (BE-II) dated 28.05.2018
- H. For procurement of Goods & Services which are divisible in nature, following shall be operated for **MSE bidders** under Public procurement (Preference to make in India), Order 2017 (revision) :-
- a. If L1 bid is not from local Supplier and price quoted by MSE bidder falls within the margin of Purchase preference (L1+15% for MSEs), then 25 % of total order quantity of respective item (rounded off to nearest number) shall be awarded to MSE bidder, subject to MSE bidder matching the L1 Price. Out of Remaining 75% quantity, distribution shall be operated as per below sub-clause (2) -
- b. If Local Supplier (Next to L1, other than MSE) quoted price falling within the Margin of Purchase Preference, and local supplier matches the L1 price, then 50% of remaining Quantity (after allocation of 25% to MSE) i.e. 37.5% shall be awarded to local supplier and 37.5% shall be awarded to Foreign bidder.

Note : L1 Price refers to lowest evaluated / landed cost to company.

For Further details, please refer GOI order no. P-45021 / 2 / 2017 - PP (BE-II) dated 28.05.2018.

26. NOTE.

- a) Special conditions of enquiry, if enclosed by BHEL, will supersede the respective standard / general terms of enquiry.
- b) Any other Standard terms and Conditions of the bidder attached / referred against the tender enquiry will be treated as null and void ab initio.
- c) In order to protect the commercial interests of BHEL, it becomes necessary to take action against suppliers / contractors by way of supervision of business dealings, who either fail to perform or are in default without any reasonable cause, cause loss of business / money / reputation, indulged in malpractices, cheating, bribery, fraud or any other



BHARAT HEAVY ELECTRICALS LIMITED

HEEP-HARIDWAR, UTTARAKHAND (249403)

General Instructions and Standard Terms & Conditions for bidding against Tender Enquiry (GISTC)

For Indian Bidders (Version April-2019, Rev: 04)

misconducts or formation of cartel so as to influence the bidding process or influence the price etc. Guide- lines for Suspension of Business Dealings with Suppliers / Contractors shall prevail over which is available at BHEL website <http://www.bhel.com>

d) The bidder along with its associate / collaborators / sub-contractors / sub-vendors / consultants / service providers shall strictly adhere to BHEL Fraud Prevention Policy displayed on BHEL website <http://www.bhel.com> and shall immediately bring to the notice of BHEL-Management about any fraud or suspected fraud as soon as it comes to their notice.

e) "BHEL shall recover the amount of compensation paid to victim(s) by BHEL towards loss of life / permanent disability due to an accident which is attributable to the negligence of contractor, agency or firm or any of its employees as detailed below;

1. **Victim:** Any person who suffers permanent disablement or dies in an accident as defined below.

2. **Accident:** Any death or permanent disability resulting solely and directly from any unintended and unforeseen injurious occurrence caused during the manufacturing / operation and works incidental thereto at BHEL factories/ **offices and precincts** thereof , project execution , erection and commissioning, services, repairs and maintenance, trouble shooting, serving , overhaul, renovation and retrofitting , trial operation, performance guarantee testing undertaken by the company or during any works / during working at BHEL Units/ Offices/ townships and premises/ project sites.

3. **Compensation in respect of each of the victims:**

(i) In the event of death or **permanent disability** resulting from **Loss of both limbs:** Rs. 10,00,000/- (Rs. Ten Lakh).

(ii) In the event of **other permanent disability:** Rs. 7,00,000/- (Rs. Seven Lakh).

4. **Permanent Disablement:** A disablement that is classified as a permanent total disablement under the proviso to Section 2(l) of the Employees Compensation Act, 1923."

Certificate by Chartered Accountant on letter head

This is to Certify that M/s,

(hereinafter referred to as 'company') having its registered office at.....is

registered under MSMED Act 2006, (Entrepreneur Memorandum No (Part- II)

.....dtd:.....,

Category :.....(Micro/Small). (Copy enclosed).

Further verified form the Books of Accounts that the investment of the company as

on dateas per MSMED Act 2006 is as follows:

1. **For Manufacturing Enterprises:** Investment in plant and machinery (i.e. original cost excluding land and building and the items specified by the Ministry of Small Scale Industries vide its notification No.

S.O.1722 (E) dated October 5, 2006:

Rs.....Lacs

2. **For Service Enterprises:** Investment in equipment (original cost excluding land and building and furniture, fittings and other items not directly related to the service rendered or as may be notified under the MSMED act, 2006:

Rs.....Lacs

(Strike off whichever is not applicable)

The above investment of RsLacs is within permissible limit of Rs..... Lacs for

.....micro / small (Strike off which is not applicable) Category under MSMED Act 2006.

Or

The company has been graduated from its original category (Micro / Small) **(Strike off whichever is not applicable)** and the date of graduation of such enterprises from its original category is

(dd/mm/yyyy) which is within the period of 3 years from the date of graduation of such enterprises from

its original category as notified vide S.O. No. 3322(E) dated 01.11.2013 published in the gazette notification

dated 04.11.2013 by Ministry of MSME.

Date:

(Signature)

Name-

Membership Number-

Seal of Chartered Accountant

Format for Self Certification under preference to Make in India order

Certificate

In line with Government Public Procurement Order No. P-45021/2/2017-BE-II dt. 15.06.2017 & P-45021/2/2017-PP (BE-II) dated 28.05.2018, we hereby certify that we M/s _____ (supplier name) are local supplier meeting the requirement of minimum local content _____ **%(Percentage)** as defined in above orders, for the items _____ covered against Enquiry No. - _____

Details of location at which local value addition will be made is as follows:

We also understand, false declarations will be in breach of the Code of Integrity under Rule 175(1)(i)(h) of the General Financial Rules for which a bidder or its successors can be debarred for up to two years as per Rule 151 (iii) of the General Financial Rules along with such other actions as may be permissible under law.

Seal and Signature of Supplier

List of Consortium Banks * (wef 22.03.2016)

	Nationalised Banks		Nationalised Banks
1	Allahabad bank	19	Vijaya Bank
2	Andhra bank		Public Sector Banks
3	Bank of Baroda	20	IDBI
4	Canara Bank		Foreign banks
5	Corporation bank	21	CITI Bank N.A
6	Central bank	22	Deutsche Bank AG
7	Indian Bank	23	The Hongkong and Shanghai Banking Corporation Limited
8	Indian Oversea Bank	24	Standard Chartered Bank
9	Oriental bank of Commerce	25	J P Morgan
10	Punjab National Bank		
11	Punjab & Sindh Bank		Private banks
12	State Bank of India	26	Axis Bank
13	State Bank of Hyderabad	27	The Federal Bank Limited
14	Syndicate Bank	28	HDFC
15	State Bank of Travancore	29	Kotak Mahindra Bank
16	UCO Bank	30	ICICI
17	Union Bank of India	31	Indusind Bank
18	United Bank of India	32	Yes Bank



PPX-BOI DEPARTMENT
BHARAT HEAVY ELECTRICALS LIMITED
HEEP: HARDWAR-249 403 (Uttarakhand)
FAX: +91 1334 226084/226462
TEL: +91 1334 28 1753/1690
PRE-QUALIFICATION REQUIREMENT

Enquiry No.:
B/4011/2020/2194V1
Item-Leak Steam control
valve
Project: Khurja Unit-1 & 2

Sl. No.	PQR FOR LEAK OFF STEAM VALVE FOR 2X660 MW KHURJA PROJECT	Vendor's Response
1.	The Vendor should have experience of designing, manufacturing, & supply of control valve that has been used in steam applications of Steam Turbines of rating 500MW or above as per following details:	
1.1	Design pressure :16 bar or above	
1.2	Design temperature :360 deg C or above	
1.3	Valve size :10" or above	
1.4	Working Medium: Steam	
1.5	ANSI class of supplied valves shall be ANSI 300 or higher	
1.6	Operating time for full control stroke shall be less than or equal to 3 Seconds	
1.7	Valve Leakage class : Class IV as per ANSI FCI 70-2	
1.8	Actuators of the valve shall be pneumatically operated	
1.9	The vendor should have experience of SMART type positioner. An Electro-Pneumatic controller SIPART PS2 by Siemens company or ARCAPRO 827A BY ARCA company is not recommended.	
2.	The vendor should have experience of supplying the valve satisfying all the conditions referred at the point no. 1 above for at least one steam Turbine power plant of rating 500MW or above, which has been commissioned at least one year before as on date of bid opening. The vendor to submit experience details as per Annexure-A along with relevant documents of supplied valve & its actuator along with accessories like datasheets & drawings etc. to support their claim.	

Note: -

1. Against vendor's replies, BHEL reserves the right to ask for more information/documents/clarifications. Vendor's offer shall not be considered if vendor fails to furnish the document/information/clarifications as mentioned above or vendor doesn't meet the above acceptance criteria.

Signature of authorized signatory.....



PPX-BOI DEPARTMENT
BHARAT HEAVY ELECTRICALS LIMITED
HEEP: HARDWAR-249 403 (Uttarakhand)
FAX: +91 1334 226084/226462
TEL: +91 1334 28 1753/1690
PRE-QUALIFICATION REQUIREMENT

Enquiry No.:
B/4011/2020/2194V1
Item-Leak Steam control
valve
Project: Khurja Unit-1 & 2

Experience Details for Leak off Steam Valve:

Annexure-A

Sl. No.		Applicable Data	
		As per BHEL requirement	As per Vendor's experience
1.	Name of power station and its location		
2.	Client name and its address, Fax no. & contact no.		
3.	Name and designation of the responsible person in client's organization / Power plant		
4.	Capacity in MW of unit		
5.	P.O. no. and date		
6.	Date of commissioning of above project		
7.	Manufactured by		
8.	Evidence of supply the valve for above mentioned project viz. PO copy/end user certificate (shall not be more than 7 years old as on date of bid opening)		
9.	Design Parameters		
	Design pressure	16 bar (a) or above	
	Design temperature	360 deg C or above	
10.	Size of the valve	>10"	
11.	Operating time of actuators (open/close)	<3 sec	
12.	Leakage class	Class IV as per ANSI FCI 70-2	
13.	Type of actuator	Pneumatically actuated	
14.	Working medium	Steam	
15.	Valve type	Control Valve	
16.	Positioner Type	SMART type	

Signature of authorized signatory.....

Dated- 08.06.17		
ANNEXURE- B		
Check –List for Seal steam valve (Material code: W90313240400), Drawing. No. 21324030000, Rev. 01:		
SL No.	BHEL SPECIFICATION REQUIREMENT	Vendor's confirmation/ Remark
1	Valve body material: ASTM A217 GR. C12A	
2	Design pressure: 16 bar (a) Design Temperature: 590 deg C	
3	Valve Characteristics: Equal %	
4	Counter Flange/Expander/Reducer material: ASTM A182 F91	
5	Overall dimensions: (a) Vertical span including dismantling space < 3500 mm (b) Flange to flange Horizontal span including expander/reducer (if any) < 2000 mm	
6	Counter flange End connection details: i. Inlet : 457.2X9.53, Butt welded as per fig.4 of ASME B16.25 ii. Outlet : 457.2X9.53, Butt welded as per fig.4 of ASME B16.25	
7	Valve shall be capable of handling at least 120% of required maximum flow at full open condition	
8	Controllable range of Cv	
9	Hand wheel for manual operation shall be provided.	
10	Manual vent valve shall be provided for manual release of entrapped air in actuator.	
11	Following commissioning spares shall be provided: i. Packing & gaskets 1 set. ii. Lock Washer for flange: 1 set for each flange connection	
12	Noise level: 85 db at a distance of 1 meter	
13	Valve shall be IBR approved.	
14	End connection for air supply: pipe connector (CS, weldable) with 3/4" butt welded connection, to be provided by the vendor	
15	Failure mode: (a) On air supply failure: stay put (b) On control signal failure: Closed	
16	Cv test report submission after placement of P.O.	
17	Operating time < 3 sec	
18	Weight of complete assembly of valve along with actuator < 2000 Kg	
19	Valve leakage class-IV as per ANSI FCI 70-2	
20	Function of Actuator: Air to open spring to close	
21	Type of drive of actuator: spring diaphragm	
22	Recommended quality and quantity of air	
23	Required supply air pressure,	
24	Documents submission for BHEL approval within 4 weeks after placement of P.O. as per Annexure-C	
25	O & M Manual: Submission of 25 Hard copies (3 copies along with equipment to the site & remaining 22 to BHEL, Hardwar within 12 weeks of placement of P.O.)	

Dated - 30.09.16			
ANNEXURE-C			
Leak off steam control valve - Check List for Documents/Information to be furnished along with the offer			
SL. No.	Document/Information details	Enclosed with the offer	
		Yes	No
1	Data sheet of valve and actuator		
2	Sizing calculation of valve and actuator		
3	General arrangement drawing of valve along with actuator indicating: i. overall dimensions, ii. required maintenance space, iii. details of weld ends, iv. overall assembly weight v. direction of flow		
4	Hook up diagram along with its functional write up		
6	Detailed catalogue mentioning type of position transmitter position controller, volume booster, air lock relay, air filter and regulator		
7	Priced list of recommended spare parts as perBHEL Drg. 31324000001 for future ordering.		
Leak off steam control valve - Check List for Documents (in addition to above mentioned documents) to be furnished after placement of PO			
SL. No.	Document/Information details	Vendor's confirmation	
1	Cross sectional drawing of valve and actuator with items to be supplied as spares clearly correlated with the item no. of corss sectional drawings		
2	BOM of valve and actuator		
3	Valve charateristic curve		
4	Recommended quality and quanti and supply pressure of actuator air		

PROJECT : 250 /500/660/700/800 MW PROJECT

Date:11.04.2017 , REV03

ITEM : GLAND & SEAL STEAM CONTROL VALVE

ADDENDUM TO DRAWING NO:

APPLICATION : STEAM TURBINE

ADDITIONAL SPECIFICATION :

1.0 SCOPE: This specification is intended to cover the requirements of Smart positioner for Pneumatic actuator of control valve.

2.0 ELECTRICAL:

- 2.1 Input signal shall be 4-20 mA from control system with Hart signal super- imposed.
- 2.2 Power supply: loop powered .
- 2.3 Valve position sensing to be provided, non contact type, 4-20 mA for control system.

3.0 ENVIRONEMENT:

- 3.1 Operating temp shall be 0 to 70 degree C.
- 3.2 Humidity: 0-95%
- 3.3 Protection class shall be IP-65 minimum.

4.0. SOFTWARE CONFIGURATION DIAGNOSTIC:

- 4.1 Windows 2000/NT based software. Software shall meet the requirement for configuration, diagnostics, calibration and testing of the actuator. However, Software package for advanced diagnostic features is not required.
- 4.2 It shall have advanced diagnostic features like Travel Counter on line partial closure test, valve signature analysis, step response test, valve friction/jamming detection. The Positioner shall be advanced diagnostic compatible.
- 4.3 Factory valve signature tests reports (PR vs valve travel and Travel vs IP signal shall be provided.

5.0 CONFIGURATION/OPERATING MODES:

- 5.1 Calibration: Remote calibration, auto & manual calibration shall be possible.
- 5.2 Operating range : Full range & split range signal range.
- 5.3 Valve action : Direct & reverse valve action.
- 5.4 Flow characterization possible to fit valve linear,, equal percentage.

6.0 FAIL SAFE

- 6.1 In case control signal 4 – 20 Ma DC fails, (Pneumatic supply in OK condition, the valve will move to the default Fail safe position (Fail Close --- for Leak as well as seal steam valves).
In case Pneumatic signal fails, control signal (4 – 20 ma DC) in OK condition, then Air inside the Actuator will be Locked by Air Lock Relay, thus Fail Lock condition will be achieved i.e Last Position hold prior to Failure of Air supply.

7.0 PERFORMANCE:

- 7.1 Characteristic deviation shall be $\leq 0.5\%$ of SPAN.
- 7.2 Ambient temp. effect shall be $\leq 0.01\%$ Deg. C or better.

8.0 ACCESSORIES:

- 8.1 In built operator panel display with push buttons for configuration and display on the positioner itself (password/hardware Lock).
- 8.2 Air filter regulator to be provided.
- 8.3 Press Gauge Block for supply & output pressure, filter regulator other accessories shall be provided as on required basis for making system complete.

- 8.4 Junction Box to be provided. Junction Box Specification -18 Ways, ½” NPT 3 Nos. Cable entry. Weather Proof IP 65 Min.
- 8.5 Cable glands to be provided. Cable gland specification-Double Compression SS 304(Weather Proof IP 65)
- 8.6 Position transmitter whether integral part of positioner or not :- To be specified by vendor.

9.0 DOCUMENTS TO BE PROVIDED:

- 9.1 Datasheet including positioner model and make, Hook –up diagram to be complete input/output signals duly terminated onto JB.

10.0 PACKING:

- 10.1 The positioner shall be loosely supplied in the main package with proper identification along with all fittings for mounting on the main valve and cables for termination to the Junction Box.
- 10.2 The Packing should be seaworthy (with silica gel) to avoid ingress of Moisture.
- 10.3 The positioner shall be packed in separate wooden box/compartment to avoid breakage.
- 10.4 Proper Labeling such as item name “Positioner”, “P.O.” etc. shall be clearly indicated on the wooden Box for identification in case of misplacement.
- 10.5 Two sets of Mounting and Calibration Instruction manual shall be sent along with the positioner.
- 10.6 O&M manual for mounting and calibration of positioner shall be submitted along with the offer.

Prepared:
(Mudit Jain)Sd/-
(CIE)

Checked:
(Saswati) Sd./-
(CIE)

Approved:
(B.S. Rana) Sd./-
(CIE)

OPERATING PARAMETERS	OPERATING CONDITION		
	CASE -1	CASE -2	CASE -3
INLET PRESSURE bar(a)	1.048		
INLET TEMPERATURE	357.5	430.2	459.7
FLOW RATE (Kg/sec.)	1.32	2.16	2.74
OUTLET PRESSURE bar(a)	0.4		
FLUID	STEAM		
DESIGN PRESSURE bar(a)	16 bar		
DESIGN TEMPERATURE (°C)	590		




FIG.1: SCHEMATIC DIAGRAM FOR LEAKAGE
STEAM CONTROL VALVE

TYPE	ELECTRO-PNEUMATIC
INPUT SIGNAL	4 TO 20 mA.
OPERATING TIME FOR FULL CONTROL STROKE	3 sec.
ΔP ACTUATOR	2 bar
TYPE OF DRIVE	DIAPHRAGM
FAILURE MODE	STAYPUT
PRESSURE OF CONTROL AIR SUPPLY AHEAD OF ACTUATOR (MAX/MIN.)	10/5 bar(g)
PNEUMATIC CONNECTION	3/4" WELDABLE
POSITIONER	1/P – POSITIONER (SMART TYPE)
ELECTRONIC POSITION FEEDBACK TRANSMITTER FOR BHEL USE	2 WIRE TYPE 4~20 mA OUTPUT, 24 V DC

ITEM DESCRIPTION
1. CONTROL VALVE FUNCTION: AIR TO OPEN SPRING TO CLOSE.
2. PNEUMATIC ACTUATOR: SPRING-DIAPHRAGM TYPE
3. I/P—POSITIONER
4. AIR VOLUME BOOSTER
5. BLOCKING VALVE
6. FILTER AND REDUCING STATION
7. STOP VALVE
8. 3/4" PIPE CONNECTOR




TABLE-3: END CONNECTION DETAIL(i.e. COUNTER FLANGES, REFER SH.2, T.R. 1.3):-

FIG. 2: PROPOSED ARRANGEMENT OF LEAKEGE

END CONNECTION	NOMINAL DIA.	SIZE		TYPE OF CONNECTION	WELD FIG./ FORM
		OUTER DIA.(mm)	WALL THICKNESS(mm)		
INLET	18"	457.2	9.53	BUTT WELDED	FIG.4 AS PER ASME B16.25
OUTLET	18"	457.2	9.53	BUTT WELDED	FIG.4 AS PER ASME B16.25

MAT. CODE : W9031340400

NOTE:

FOR TECHNICAL REQUIREMENTS REFER SHEET-2

GRADE OF UNTOL.DIM	GMS No. / GBOM No.		STATUS of DRG	
	APPROVED DEPT	NAME		SIGN
	CIE	SASWATI		SD-
				DATE
W/C/G - $\varnothing$ /M/ $\varnothing$ AAO230208			05.06.17	
WELDING - A/B/ $\varnothing$ /D AAO621104				
GAS CUTTING - T3 AAO621101				

 BHARAT HEAVY ELECTRICALS LTD. RANPUR HARIDWAR	TYPE OF PRODUCT		STEAM TURBINE
	OR		
	NAME OF CUSTOMER/PROJECT		
	NAME	SIGN	DATE
DRN	H. SINGH	sd -	03.06.17
CHD	KKS/NIN	sd -	03.06.17
		sd	03.06.17
			var

REV DATE	ALTERED	REV DATE	ALTERED	REV DATE	ALTERED
	CHECKED		CHECKED		CHECKED

REV	DATE	ALTERED	REV	DATE	ALTERED	KJSS	SD/-
		CHECKED			CHECKED		
			01	16.11.17			

CODE 4011		NTS	-	-	75 77
-----------	---	-----	---	---	-------

[illegible]

REV. SHOWN

TECHNICAL REQUIREMENTS:

1. DESIGN AND MANUFACTURING REQUIREMENTS:

- 1.1 SUPPLIER TO OFFER THE VALVE & ACTUATOR SUITING TO THE INPUT PARAMETERS AS SPECIFIED IN THE TABLE-1 & 2.
- 1.2 VALVE SHALL BE ABLE TO MANAGE THE MASS FLOWS FOR ALL CASES AS MENTIONED IN VALVE DATA TABLE-1.
- 1.3(0) VALVE SHALL BE FLANGED ENDED AT INLET/OUTLET AND COUNTER FLANGES RAISED FACE & WELDING NECK TYPE CONNECTIONS AND SEALING. END CONNECTIONS OF OUTER FLANGES SHALL BE PROVIDED AS PER TABLE-2 TO MATCH WITH THE PRES IN BEL SCOPE. EXPANDER/REDUCER, IF REQUIRED, SHALL BE PROVIDED BY THE SUPPLIER OF MATERIAL. GRADE ASTM A182 Gr. F91. ALTERNATIVELY, COUNTER FLANGES & EXPANDER/REDUCER OF MATERIAL GRADE ASTM A217 Gr. C12A IS ALSO ACCEPTABLE PROVIDED RT SHALL BE CARRIED OUT AS PER PROCEDURE MENTIONED IN ASME B16.34 & ACCEPTANCE CRITERIA SHALL BE SEVERITY LEVEL-1 AS PER ASTM E680/ASTM E280 DEPENDING UPON APPLICABLE THICKNESS.
- 1.3(0) HORIZONTAL & VERTICAL DIMENSION LIMITS SHOWN IN THE PROPOSED ARRANGEMENT DRAWING OF VALVE SHALL BE COMPLIED BY THE VENDOR. WEIGHT OF THE COMPLETE ASSEMBLY OF VALVE INCLUDING ACTUATOR SHALL NOT EXCEED 2000 KG.
- 1.4 VALVE BODY MATERIAL SHALL CONFORM TO ASTM A217 Gr. C12A.
- 1.5 VALVE CHARACTERISTICS SHALL BE EQUAL PERCENTAGE.
- 1.6 VALVE LEAKAGE CLASS: CLASS IV AS PER ANSI FC1-70-2.
- 1.7 THE VALVE MUST BE DESIGNED KEEPING IN VIEW OF THE FOLLOWING DATA:
- (i) AMBIENT TEMPERATURE: -4°C TO 50°C.
- (ii) ABSOLUTE HUMIDITY: <= 60g WATERING DRY AIR.
- (iii) MAX. EARTHQUAKE FACTORS HORIZONTAL: 0.3g (Safe operation)/0.4g (Limit of integrity)
- (iv) MAX. EARTHQUAKE FACTORS VERTICAL: 0.2g (Safe operation)/0.25g (Limit of integrity)
- (v) NOISE LEVEL AT 1M DISTANCE: <= 85 db(A)
- 1.8 FUNCTION OF VALVE ACTUATOR SHALL BE: AIR TO OPEN AND SPRING TO CLOSE.
- 1.9 SMART TYPE POSITIONER, AIR VOLUME BOOSTER, AIR LOCKING SYSTEM FOR STAYPUT ACTION, FILTERS, STOP VALVES, ASSOCIATED PIPES AND PIPE CONNECTORS SHALL BE SUPPLIED BY THE VENDOR ALONG WITH THE ACTUATOR.
- 1.10 ADDITIONAL SPECIFICATIONS OF SMART POSITIONER AS PER DOCUMENT NO. 4-18102-50001 SHALL BE COMPLIED BY THE VENDOR.
- 1.11 AN ELECTRO-PNEUMATIC CONTROLLER SPART PS2 BY SIEMENS COMPANY OR ARCAPRO 8274 BY ARCA COMPANY IS NOT ALLOWED TO BE INSTALLED.
- 1.12 MOUNTING POSITION OF THE VALVE SHALL BE HORIZONTAL WITH VERTICAL SPINDLE.
- 1.13 HANDWHEEL SHALL BE PROVIDED IN THE ACTUATOR FOR MANUAL OPERATION. PROVISION SHALL BE MADE BY THE VENDOR FOR MANUAL RELEASE OF AIR WHICH GETS TRAPPED IN THE ACTUATOR IN CASE VALVE IS ON STAYPUT DURING AIR FAILURE.
- 1.14 THE FOLLOWING ITEMS SHALL BE INCLUDED IN THE OFFER AS COMMISSIONING SPARES:
- (i) PACKING AND GASKETS: 1 SET
- (ii) LOCK WASHER FOR FLANGE: 1 COMPLETE SET FOR EACH FLANGE CONNECTION.
- (iii) O-RING MATERIAL MUST BE PROVIDED FREE FROM HARMFUL POLLUTIONS LIKE ASBESTOS AND FERRITE AND SHOULD HAVE AN EXTRAORDINARY TEMPERATURE RESISTANCE.
- 1.16 THE VALVE SHALL BE BIRP APPROVED.
- 1.17 THE VALVE SEALS SHALL BE SUITABLE FOR OBTAINING MAXIMUM OPERATING CONDITIONS WITH VALVE OPENING AT APPROXIMATELY 80% TOTAL TRAVEL. VALVES SHALL BE OPEN NOT LESS THAN 1/3 OF FULL OPENING FOR MINIMUM FLOW AND SHALL BE CAPABLE OF HANDLING AT LEAST 120% OF THE REQUIRED MAXIMUM FLOW AT FULL OPEN CONDITION.
- 1.18 VALVE SHALL HAVE AN ARROW PERMANENTLY FIXED ON THE VALVE BODY TO INDICATE THE CORRECT DIRECTION OF FLOW.
- 1.19 VALVE SHALL HAVE A STAINLESS STEEL NAME PLATE PERMANENTLY FASTENED TO THE YOKE WHICH SHALL BE VISIBLE WHEN THE VALVE IS IN SERVICE. THE NAME PLATE SHALL INCLUDE
- (i). TAG NO. AND VALVE SERIAL NO.
- (ii). BODY MATERIAL, SIZE AND PRESSURE RATING
- (iii). TRIM MATERIAL, SIZE CHARACTERISTICS
- (iv). ACTION ON AIR FAILURE
- (v). SPRING RANGE
- (vi). STEM TRAVEL
- (vii). VALVE ACTION, ETC.

2. TESTING REQUIREMENTS:

- 2.1 CV TEST SHALL BE CARRIED OUT BY THE SUPPLIER FOR THE VALVE & TEST REPORT SHALL BE SUBMITTED FOR BHEL REVIEW. THE CV TEST CAN BE CARRIED OUT PHYSICALLY ON THE VALVE OR THROUGH COMPUTER SIMULATION. IN CASE TEST REPORT IS ALREADY AVAILABLE WHICH IS NOT MORE THAN 5 YEARS OLD, THE SAME SHALL BE ACCEPTABLE. FURTHER, IN CASE THE OFFERED VALVE IS ALREADY IN SUCCESSFUL OPERATION USING THE SAME VALVE BODY, SEAT & TRIM COMBINATION AS OF THE OFFERED VALVE, THE VENDOR MAY FURNISH NAME OF PROJECT, DATA SHEET, CROSS-SECTIONAL DRAWING OF THAT VALVE FOR REVIEW IN LIEU OF THE CV TEST REPORT.
- 2.2 FOLLOWING TESTS SHALL BE PERFORMED ON VALVE & TEST REPORTS SHALL BE SUBMITTED FOR BHEL REVIEW:-
- 2.2.1 SHELL STRENGTH TEST AS PER TEST P10 OF EN12266 PART-1 (LATEST EDITION) OR EQUIVALENT TEST AS PER ANSI / ASME STANDARD.
- 2.2.2 SHELL TIGHTNESS TEST AS PER TEST P11 OF EN12266 PART-1 (LATEST EDITION) OR EQUIVALENT TEST AS PER ANSI / ASME STANDARD.
- 2.2.3 SEAT TIGHTNESS TEST AS PER EN60634.4 (LATEST EDITION) OR ANSI FC1-70-2 (LATEST EDITION).
- 2.2.4 VALVE SHALL BE FUNCTIONALLY TESTED TO CHECK ITS DESIGN CHARACTERISTICS.
- 2.3 RT & UT SHALL BE PERFORMED ON VALVE COMPONENTS AS PER ASME B16.34.

3. DOCUMENTS TO BE SUBMITTED BY THE SUPPLIER:

3.1 DOCUMENTS TO BE SUBMITTED ALONGWITH THE OFFER:

- (i) DATA SHEET OF VALVE & ACTUATOR.
- (ii) SIZING CALCULATIONS OF VALVE & ACTUATOR.
- (iii) CROSS-SECTIONAL DRAWING OF VALVE ALONGWITH BILL OF MATERIAL.
- (iv) VALVE CHARACTERISTIC CURVES.
- (v) GENERAL ARRANGEMENT DRAWING OF VALVE ALONG WITH ACTUATOR INDICATING OVERALL DIMENSIONS, REQUIRED MAINTENANCE SPACE, DETAILS OF WELD ENDS, OVERALL ASSEMBLY WEIGHT & DIRECTION OF FLOW.
- (vi) HOOK-UP DIAGRAM ALONG WITH ITS FUNCTIONAL WRITE-UP.
- (vii) CATALOGUES OF ALL ACCESSORIES eg. POSITIONER, VOLUME BOOSTER, AIR LOCK RELAY, AIR FILTER & REGULATOR.
- (viii) REQUIRED SUPPLY AIR PRESSURE, SPRING RANGE, TUBING/CONNECTION SIZE.
- (ix) RECOMMENDED QUALITY & QUANTITY OF AIR.
- (x) LIST OF COMMISSIONING SPARES.
- (xi) PRICED LIST OF RECOMMENDED SPARES FOR FUTURE ORDERING.

3.2 DOCUMENTS TO BE SUBMITTED IN THE EVENT OF ORDERING:

- (i) IN THE EVENT OF ORDERING THE FOLLOWING DOCUMENTS ARE REQUIRED TO BE SUBMITTED WITHIN 4 WEEKS OF PLACEMENT OF PURCHASE ORDER & GOT APPROVED BY BHEL BEFORE START OF ANY MANUFACTURING ACTION.
- (a) VALVE & ACTUATOR DATASHEET.
- (b) CROSS-SECTIONAL DRAWING OF VALVE ALONGWITH BILL OF MATERIAL.
- (c) GENERAL ARRANGEMENT DRAWING OF VALVE ALONG WITH ACTUATOR INDICATING OVERALL DIMENSIONS, REQUIRED MAINTENANCE SPACE, DETAILS OF WELD ENDS, OVERALL ASSEMBLY WEIGHT & DIRECTION OF FLOW.
- (d) HOOK-UP DIAGRAM OF VALVE WITH ACTUATOR, POSITIONER, FILTERS & GAUGES ETC.

- (ii) 25 HARD COPIES OF O&M MANUAL SHALL BE SUPPLIED BY THE VENDOR. OUT OF THESE 3 COPIES SHALL BE SENT TO SITE ALONGWITH THE EQUIPMENT & REMAINING 22 COPIES SHALL BE SENT TO BHEL, HARDWARE WITHIN 12 WEEKS OF PLACEMENT OF P.O.

4. GENERAL REQUIREMENTS:-

- 4.1 GUARANTEE: GUARANTEE/MAINTENANCE PERIOD SHALL BE 24 MONTHS FROM THE DATE OF SHIPMENT OR 18 MONTHS FROM THE DATE OF COMMISSIONING, WHICHEVER IS EARLIER. IN CASE OF ANY FAILURE OR TROUBLE REPORTED FROM THE SITE, THE SUPPLIER WOULD DEPUTE THEIR REPRESENTATIVE IMMEDIATELY TO ATTEND THE PROBLEM AND REPLACE THE DEFECTIVE COMPONENT/PARTS IF REQUIRED.

- 4.2 PAINTING: THE PAINTING SURFACE SHALL BE PREPARED ACCORDING TO ISO 8503-1 Sa 2 1/2. WELDING END SHALL BE 80mm PAINT FREE. VALVE BODY IS TO BE PAINTED WITH ALUMINUM PAINT AS PER IS:13183 Gr.1 WITH PAINT THICKNESS OF MINIMUM 70 MICRONS.

4.3 PACKING & DESPATCH:

- (i) THE VALVE SHALL BE PACKED AND LOCKED IN SUCH A WAY, THAT IN GENERAL CASE ANY DAMAGE IS PROHIBITED.
- (ii) ALL OPENINGS SHALL BE PLUGGED.
- (iii) AS FAR AS POSSIBLE NECESSARY ACCESSORY DEVICES FOR TRANSPORTATION PURPOSE SHALL BE ATTACHED TO THE VALVE AND/OR TO THE PACKING & LIFTING EYES & LIFTING SIGNS.
- (iv) BEARING AREAS SHALL BE MARKED IF NECESSARY.
- (v) MANDATORY SPARES SHALL BE PACKED IN A SEPARATE GREEN COLOUR BOW WITH MANDATORY SPARES FOR LEAK OFF STEAM VALVE LABELED ON IT.

- 4.4 THE SUPPLIER SHALL BEAR FULL RESPONSIBILITY FOR COMPLIANCE OF ALL THE PARTS & COMPONENTS SUPPLIED IN PURSUENT TO THIS SPECIFICATION WITH THE FULL SCOPE OF SAFETY REGULATIONS OF THE COUNTRY.

MAT. CODE : W90313240400

STEAM TURBINE

NAME OF CUSTOMER/PROJECT

BHARAT HEAVY ELECTRICALS LTD.
RANIPUR, HARDWAR

DEPT. STE



SCALE N.T.S

WEIGHT (KG)

REF. TO ASSY. DRG.

ITEM NO.

NO. OF ITEMS

TITLE LEAK STEAM CONTROL VALVE WITH PNEU. ACT.

CARD NO. 13240-30000

22.03.24

SHEET No. 02

No. OF SHEETS 02

SIZE A2

22.03.24

FIRST ANGLE PROJECTION

(ALL DIMENSIONS ARE IN mm) FORM DG 39(B)

REV	DATE	ALTERED	REV	DATE	ALTERED	GMS No./ C.B.O.M.- NO.			STATUS OF DRG U
		CHECKED			CHECKED				
ZONE			ZONE			AGREED DEPT	NAME	SIGN	DATE
GRADE OF UNTOL.DIM		M/CG. - AA0230208 m		WELDING-CLASS 'B' OF AA0621104		GAS CUTTING-TABLE 3 OF AA0621101			

SPARES APPLICABLE FOR LEAK OFF STEAM VALVE WITH PNEUMATIC ACTUATOR

SL.NO.	CUSTOMER SPECIFICATION CLAUSE NO.	DESCRIPTION	QUANTITY
01.	C.1.XIV	GLAND STEAM LEAK OFF VALVE (COMPLETE ASSEMBLY WITHOUT PNEUMATIC ACTUATOR)	01 NO

NOTES:-

1. ALL THE MANDATORY SPARES SPECIFIED ABOVE SHALL BE MANUFACTURED EXACTLY SAME AS AGAINST MAIN SUPPLY.
2. INTERCHANGEABILITY OF THE MENTIONED ITEMS ARE FOR REPLACEMENT WITH THEIR PARTS FOR WHICH SUPPLY IS TO BE MADE AGAINST MAIN OFFER.
3. ALL THE SPARES MUST BE PACKED IN SEALED TRANSPARENT PLASTIC BAGS AND CLEARLY MARKED OR LABELLED ON THE OUTSIDE OF THE PACKING WITH ITS DESCRIPTION & ASSEMBLY PART NUMBERS.
4. QUALITY CHECKS & TESTING NORMS/REQUIREMENTS AS PER AGREED QUALITY PLAN (QP) SHALL ALSO BE APPLICABLE FOR ALL THE SPARES AS LISTED.
5. IF ANY ITEM IS NOT APPLICABLE THAN EQUIVALENT ITEM TO BE SUPPLIED BY THE VENDOR.
6. ALL MANDATORY SPARES ARE TO BE PACKED IN GREEN COLOUR BOX WITH "MANDATORY SPARES FOR LEAK OFF STEAM VALVE" LABELED ON IT.

Ref. Drawing No>

Sign & Date



BHARAT HEAVY ELECTRICALS LTD.
RANIPUR, HARDWAR

MAT. CODE: W99313240530

NAME	SIGN	DATE	NO. OF VAR
DRN HARENDRA	-sd-	03.09.20	
CHD A.K.S/S.M.	-sd-	03.09.20	
APPD R.RAWAT	-sd-	03.09.20	

Inventory No.

DEPT STE		SCALE	WEIGHT (KG)	REF. TO ASSY. DRG.	ITEM No.	NO. OF ITEMS
CODE 4011		-	-	-	-	-
TITLE : SPARES FOR LEAK OFF STEAM VALVE				CARD CODE	DRAWING NO. 4-13240-30004	
				7	22	23 24
				SHEET No. 01 No. OF SHEETS 01		

A4 SIZE

COPYRIGHT AND CONFIDENTIAL

THE INFORMATION ON THIS DOCUMENT IS THE PROPERTY OF BHARAT HEAVY ELECTRICALS LIMITED. IT MUST NOT BE USED DIRECTLY OR INDIRECTLY IN ANY WAY DETERIMENTAL TO THE INTEREST OF THE COMPANY.


MANUFACTURER'S NAME AND ADDRESS				STANDARD QUALITY PLAN				TO BE FILLED BY BHEL				TO BE FILLED BY BHEL			
BHEL		VENDOR'S NAME		ITEM	LEAK STEAM VALVE		QP NO.	QA-BI QP_135							
		AS PER PO		DRG. NO.	SPEC.	REV	DATED	23.11.2017							
COMPONENT & OPERATIONS		CHARACTERISTICS		CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORDS	AGENCY		REMARKS			
1	2	3	4	5	6	7	8	9	D	M	B	N	11		
Page 1 of 3															

1.	Body / Bonnet	Mechanical Properties	CR	Physical Test	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	V		
		Chemical Analysis	CR	Chemical Testing	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	V		
		Heat Treatment	CR	Time & Temp.	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	V		
		Internal Soundness	CR	Radiography & UT	100%	ASME B 16.34	ASME 16.34 APPDX.1	IR	✓	P	V		
		Hydraulic Test	CR	Hydraulic Test	100%	ANSI B 16.5/ ASME B 16.34	No Leakage	IR	✓	P	V		
2.	Trim (Plug, Seat, Stem)	Mechanical Properties	MA	Physical Test	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	V		
		Chemical Analysis	MA	Chemical Testing	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	V		
3.	Studs and Nuts	Mechanical Properties	CR	Physical Test	One Per Lot	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	COC	✓	P	V		
		Chemical Analysis	CR	Chemical Testing	One Per Lot	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	COC	✓	P	V		

MANUFACTURER/SUBCONTRACTOR		LEGEND: ! RECORDS IDENTIFIED WITH 'TICK' SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION. M: MANUFACTURER / SUBCONTRACTOR B: BHEL / NOM. INSPECTION AGENCY N: CUSTOMER INDICATE 'P' PERFORM 'W' WITNESS AND 'V' VERIFICATION ALL 'W' INDICATED IN COLUMN 'N' SHALL BE 'CHP' OF CUSTOMER		FOR CUSTOMER USE Vibhuti paliwal 19.09.2020 Sr Engr -qax	
				APPROVED BY	

MANUFACTURER'S NAME AND ADDRESS				STANDARD QUALITY PLAN				TO BE FILLED BY BHEL				TO BE FILLED BY BHEL					
BHEL		VENDOR'S NAME		ITEM	LEAK STEAM VALVE		Qp NO.	QA-BI QP_135									
		DRG. NO.		SPEC.	REV	AS PER PO		DATED	23.11.2017								
SL. NO.		COMPONENT & OPERATIONS		CHARACTERISTICS		CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORDS		AGENCY		REMARKS		
1		2		3		4	5	6	7	8	9	D	M	B		N	11

4.	Packing and Other Internal Parts	Material & Functional Tests	MA	As required by relevant Standard	Sample	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	COC	✓	P	V		
	Actuator	Model	MA	Verify	Sample	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	COC	✓	P	V		
		Functional Test	MA	Leakage	Sample	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	COC	✓	P	V		
	Positioner	Model	MA	Verify	Sample	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	COC	✓	P	V		
		Functional Test	MA	Testing With Valve	Sample	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	COC	✓	P	V		
5.	Complete Valve	Hydraulic Test	CR	Hydraulic Test	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	W		
		Seat Leakage Test	CR	Leak test	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	W		
		Packing Tightness / Gasket Leakage	CR	Leak test	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	W		

MANUFACTURER/SUBCONTRACTOR		LEGEND: ! RECORDS IDENTIFIED WITH 'TICK' SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION. M: MANUFACTURER / SUBCONTRACTOR B: BHEL / NOM. INSPECTION AGENCY N: CUSTOMER INDICATE 'P' PERFORM 'W' WITNESS AND 'V' VERIFICATION ALL 'W' INDICATED IN COLUMN 'N' SHALL BE 'CHP' OF CUSTOMER		FOR CUSTOMER USE  APPROVED BY Vibhuti paliwal 19.09.2020 Sr Engr-qax	
----------------------------	--	---	--	---	--

MANUFACTURER'S NAME AND ADDRESS				STANDARD QUALITY PLAN						TO BE FILLED BY BHEL				TO BE FILLED BY BHEL			
BHEL	VENDOR'S NAME		ITEM	LEAK STEAM VALVE		QP NO.	QA BI QP 135		23.11.2017	Page 3 of 3							
			DATED														
			DRG. NO.	AS PER PO													
			SPEC.	AS PER PO													
			REV	00													
SL. NO.	COMPONENT & OPERATIONS	CHARACTERISTICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORDS		AGENCY		REMARKS					
1	2	3	4	5	6	7	8	9	D	M	B	N	11				

	Operating Test (Opening & closing Time)	CR	Performance	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	W								
	Flow Capacity Test	CR	Valve Full Capacity	One Per Type	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	V								

Final Inspection

Painting	Color & Thickness	MA	Coating Thickness	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	V								
Overall Dimensions	Overall Dimensions Inspection	MA	End to End dimensions	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	TC	✓	P	V								
Counter flange and nozzle	Dimensions	MA	Dimensional	100%	BHEL APPROVED DRG	BHEL APPROVED DRG	TC	✓	P	V								
6.	Complete Valve S/A & Packing	MA	Verification	100%	BHEL APPROVED DATA SHEET/DRG	BHEL APPROVED DATA SHEET/DRG	IR	✓	P	V								

*Note: All valves to be witnessed by BHEL nominated agency.

MANUFACTURER/SUBCONTRACTOR	LEGEND: ! RECORDS IDENTIFIED WITH 'TICK' SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION. M: MANUFACTURER / SUBCONTRACTOR B: BHEL / NOM. INSPECTION AGENCY N: CUSTOMER INDICATE 'P' PERFORM 'W' WITNESS AND 'V' VERIFICATION ALL 'W' INDICATED IN COLUMN 'N' SHALL BE 'CHP' OF CUSTOMER				FOR CUSTOMER USE				APPROVED BY			

Vibhuti paliwal
19.09.2020
Sr Engr -qax