BHEL::RC PURAM - HYDERABAD

M&S-P&C DEPARTMENT

TENDER REF.M&S/P&C/2018/36 DT.19/07/2018

PRICE BID

WORK:Strengthening of BHEL feeders at TSTRANSCO substation

S. No	Work Description	Unit	Quantity	Rate/Unit	Amount IN Rs.
1	Shifting and Laying of 1C X 630 sq.mm, 11KV(UE), XLPE cable in the existing RCC/ HUME/ METAL pipe as required. The job includes opening of trench covers wherever required, providing appropriate metal tags for easy identification and closing the trench covers after the completion of laying.	Mts	6,492	44.00	285,648.00
2	Excavation of cable trench(500x1000mm): In soil, excavation of 1000mm deep and 500mm width trench, supply & spreading of sand, supply & laying of bricks & shabad stone as per IS:1255 1983 and back filling after cable laid with marking plates.	Mts	47	405.17	19,042.99
3	Identification, disconnection and removal of existing 1C X 630 sq.mm / 1C X 500 sq.mm cables from the trench and shifting to scrapyard or following the instructions of site engineer	Mts	3,678	15.70	57,744.60
4	Providing RCC trench of size 1.2m (Width) X 1.5m (Height) for the new bay With trays and support.	Mts	20	3,763.20	75,264.00
5	Shifting and execution of end termination kits for 1C X 630 sq.mm and connection of the kit to busbars. The job includes providing mechanical support/suitable clamping to cables to ensure the load of cable is not on the bus bars	Nos	48	1,055.32	50,655.36
6	Providing Twin Moose, Copper Bus Bars, Supporting clamps to cables, Insulator for the Busbar and Twin Moose etc as required for cable termination.	Bulk	1	13,480.00	13,480.00
				Total	**501,835.00**

Note:- The tenderers are required to quote their tender value on percentage(%) basis at excess or less or on par with estimated value.

Tender (%)	in figures	in words
Excess		
Less		
Estimate rate only		

NOTE:L1 will be decided on overall value only.

SIGNATURE/STAMP OF VENDOR